This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

BRANNER
GEOLOGICAL LIBRARY

STANFORD UNIVERSITY LIBRARIES

Water-Supply and Irrigation Paper No. 172 Series P, Hydrographic Progress Reports, 48

DEPARTMENT OF THE INTERIOR
UNITED STATES GEOLOGICAL SURVEY
CHARLES D. WALCOTT, DIRECTOR

REPORT

OF

PROGRESS OF STREAM MEASUREMENTS

FOR

THE CALENDAR YEAR 1905

PREPARED UNDER THE DIRECTION OF F. H. NEWELL

PART VIII.—Missouri River Drainage

BY

CYRUS C. BABB, M. C. HINDERLIDER, and JOHN C. HOYT

WASHINGTON
GOVERNMENT PRINTING OFFICE
1906

659140

CONTENTS.

	Page.
roduction	1
Organization and scope of work	1
Definitions	3
Explanation of tables	4
Convenient equivalents	5
Field methods of measuring stream flow	6
Office methods of computing run-off	10
Cooperation and acknowledgments	11
ieral features of the Missouri River drainage	12
ssouri River	12
Description of basin	12
Jefferson River near Sappington, Mont	13
Madison River (including Cherry Creek) near Norris, Mont	16
Gallatin River at Logan, Mont	18
West Gallatin River near Salesville, Mont	21
Missouri River at Cascade, Mont	24
Missouri River at Great Falls, Mont	26
Missouri River near Williston, N. Dak	28
Missouri River at Washburn, N. Dak	30
Missouri River near Bismarck, N. Dak	30
Missouri River at Kansas City, Mo	32
Miscellaneous measurements	36
iith River drainage basin	36
Smith River at Truly, Mont	36
n River drainage basin	37
Description of basin	37
North Fork of Sun River near Augusta, Mont	38
South Fork of Sun River at Augusta, Mont	40
Sun River at Sun River, Mont	42
Willow Creek near Augusta, Mont	43
Miscellaneous measurements	45
elt Creek drainage basin	45
Belt Creek near Belt, Mont	45
ighwood Creek drainage basin	46
Highwood Creek near Highwood, Mont	46
arias River drainage basin	48
Description of basin	48
Marias River near Shelby, Mont	48
Cutbank Creek at Cutbank, Mont	50
Teton River near Belleview, Mont	52
Teton River near Choteau, Mont	53
lk River drainage basin	54
Description of basin	54
South Fork of Milk River near Browning, Mont	55

Milk River drainage basin—Continued. Page.
Milk River at Havre, Mont ... 57
Milk River at Malta, Mont ... 59
North Fork of Milk River near Chinook, Mont ... 61
Beaver Creek near Ashfield, Mont ... 63
Beaver Creek overflow near Bowdoin, Mont ... 65
Private canals in Milk River Valley ... 67
Description of canals ... 67
Paradise Valley canal near Chinook, Mont ... 67
Cook canal near Chinook, Mont ... 70
Matheson canal near Chinook, Mont ... 72
Harlem canal near Zurich, Mont ... 74
Agency ditch near Harlem, Mont ... 75
Fort Belknap canal near Chinook, Mont ... 77
Reser ditch near Chinook, Mont ... 79
West Fork ditch near Chinook, Mont ... 81
Dowen & Buckley ditch near Chinook, Mont ... 82
Rokita ditch near Chinook, Mont ... 83
Corregan ditch near Chinook, Mont ... 83
Winter-Anderson canal near Chinook, Mont ... 83
Parallel-Creek ditches near Harlem, Mont ... 83
Rock Creek canal near Hinsdale, Mont ... 83
Seepage measurements ... 85
Milk River, Mont ... 85
Cutbank Creek, Mont ... 85
Miscellaneous measurements ... 86
Musselshell River drainage basin ... 87
Musselshell River at Shawmut, Mont ... 87
Little Muddy River drainage basin ... 89
Little Muddy River near Williston, N. Dak ... 89
Yellowstone River drainage basin ... 91
Description of basin ... 91
Yellowstone River near Livingston, Mont ... 92
Yellowstone River near Billings, Mont ... 95
Yellowstone River at Glendive, Mont ... 97
Clark Fork, at Fromberg, Mont ... 100
Pryor Creek at Huntley, Mont ... 103
Bighorn River at Thermopolis, Wyo ... 106
Bighorn River at Fort Custer, Mont ... 108
Little Bighorn River at Crow Agency, Mont ... 111
Shoshone River near Cody, Wyo ... 113
South Fork of Shoshone River at Marquette, Wyo ... 115
Piney Creek at Kearney, Wyo ... 117
Miscellaneous measurement ... 120
Little Missouri River drainage basin ... 120
Description of basin ... 120
Little Missouri River at Alzada, Mont ... 120
Little Missouri River at Camp Crook, S. Dak ... 123
Little Missouri River at Medora, N. Dak ... 125
Knife River drainage basin ... 128
Knife River at Broncho, N. Dak ... 128
Heart River drainage basin ... 130
Heart River near Richardton, N. Dak ... 130
Apple Creek drainage basin ... 133
Apple Creek near Bismarck, N. Dak ... 133

Page.
nnon Ball River drainage basin 134
Cannon Ball River at Stevenson, N. Dak 134
and River drainage basin 135
Grand River at Seim, S. Dak 135
oreau River drainage basin 137
Moreau River at Bixby, S. Dak 137
eyenne River drainage basin 140
Description of basin 140
Cheyenne River at Edgemont, S. Dak 141
Beaver Creek near Edgemont, S. Dak 145
Hat Creek near Edgemont, S. Dak 147
Spring Creek near Rapid, S. Dak 149
Rapid Creek at Rapid, S. Dak 151
Boxelder Creek at Blackhawk, S. Dak 154
Belle Fourche River at Belle Fourche, S. Dak 156
Redwater River at Belle Fourche, S. Dak 159
Spearfish Creek near Spearfish, S. Dak 161
Redwater canal at Minnesela, S. Dak 163
White River drainage basin 166
White River at Interior, S. Dak 166
Niobrara River drainage basin 167
Description of basin 167
Niobrara River near Valentine, Nebr 168
Red Deer Lake near Woodlake, Nebr 172
Miscellaneous measurements 173
Platte River drainage basin 173
General features 173
North Platte River 173
Description of basin 173
Grizzly Creek at Hebron, Colo 174
Little Grizzly Creek at Hebron, Colo 176
Roaring Fork of North Platte River near Hebron, Colo 178
North Fork of North Platte River at Higho, Colo 181
North Platte River near Hebron, Colo 183
North Platte River near Cowdrey, Colo 185
Canadian River at Cowdrey, Colo 187
Michigan Creek near Walden, Colo 190
Michigan Creek near Cowdrey, Colo 192
North Platte River at Saratoga, Wyo 194
North Platte River at Guernsey, Wyo 196
North Platte River at Alcova, Wyo 199
North Platte River near Mitchell, Nebr 202
North Platte River at Bridgeport, Nebr 204
North Platte River at North Platte, Nebr 207
Laramie River at Glendevey, Colo 209
Laramie River near Jelm, Wyo 212
McIntyre Creek at Gleneyre, Colo 214
South Platte River 216
Description of basin 216
South Platte River at South Platte, Colo 217
South Fork of South Platte River at South Platte, Colo 220
South Platte River at Denver, Colo 223
South Platte River near Kersey, Colo 227
South Platte River near Julesburg, Colo 229

Platte River drainage basin—Continued. P
South Platte River—Continued.
Clear Creek at Forkscreek, Colo
Miscellaneous measurements
Platte River
Description of basin
Platte River near Lexington, Nebr
Platte River near Columbus, Nebr
Loup River at Columbus, Nebr
Kansas River drainage basin
General features
Republican River
Description of basin
Republican River near Bostwick, Nebr
Republican River at Benkelman, Nebr
South Fork of Republican River at Benkelman, Nebr
Republican River at Junction, Kans
Miscellaneous measurement
Smoky Hill River
Description of basin
Smoky Hill River at Ellsworth, Kans
Beaver River (Ladder Creek) near Scott City, Kans
Kansas River
Description of basin
Kansas River at Lecompton, Kans
Blue River near Manhattan, Kans
Osage River drainage basin
Osage River at Ottawa, Kans
Gasconade River drainage basin
Gasconade River at Arlington, Mo
Index

ILLUSTRATIONS.

Pa
PLATE I. Map of the United States, showing location of principal river stations maintained during 1905
FIG. 1. Cable station, showing section of river, car, gage, etc
2. Discharge, mean-velocity, and area curves for South Fork of Skykomish River near Index, Wash

PROGRESS REPORT OF STREAM MEASUREMENTS FOR THE CALENDAR YEAR 1905.

PART VIII.

By C. C. Babb, M. C. Hinderlider, and J. C. Hoyt.

INTRODUCTION.

ORGANIZATION AND SCOPE OF WORK.

The hydrographic work of the United States Geological Survey includes the collection of facts concerning and the study of conditions affecting the behavior of water from the time it reaches the earth as rain or snow until it joins the oceans or the great navigable rivers. These investigations became a distinct feature of the work of the Survey in the fall of 1888, when an instruction camp was established at Embudo, N. Mex. The first specific appropriation for gaging streams was made by the act of August 18, 1894, which contained an item of $12,500 "for gauging the streams and determining the water supply of the United States, including the investigation of underground currents and artesian wells in the arid and semiarid sections." (28 Stat L., p. 398.)

Since that time the appropriations have been gradually increased, as shown by the following table:

Annual appropriations for hydrographic surveys, fiscal years ending June 30, 1895-1906.

1895	$12,500	1901	100,000
1896	30,000	1902	100,000
1897	50,000	1903	200,000
1898	50,000	1904	200,000
1899	50,000	1905	200,000
1900	50,000	1906	200,000

As a result of the increased appropriations the work has been greatly extended and at the same time it has been more thoroughly systemized by the adoption of standard methods and by grouping the States into districts, in each of which a district hydrographer and a corps of assistants carry on a comprehensive study of the hydrographic resources.

The chief features of the hydrographic work are the collection of data relating to the flow of the surface waters and the study of the conditions affecting this flow. Information is also collected concerning river profiles, duration and magnitude of floods, water power, etc., which may be of use in hydrographic studies. This work includes the study of the hydrography of every important river basin in the United States and is of direct value in the commercial and agricultural development of the country.

In order to collect the material from which estimates of daily flow are made, gaging stations are established. The selection of a site for a gaging station and the length of time it is maintained depend largely on the physical features and the needs of each locality. If the water is to be used for power, special effort is made to obtain information concerning the minimum flow; if water is to be stored, the maximum flow receives special attention. In all sections of the country permanent gaging stations are maintained for general statistical

purposes, to show the conditions existing through long periods. They are also used as primary stations, and their records in connection with short series of measurements, serve as bases for estimating the flow at other points in the drainage basin.

During the calendar year 1905 the division of hydrography has continued measuring the flow of streams on the same general lines as in previous years. Many new and improved methods have been introduced, by which the accuracy and value of the results have been increased. Approximately 800 regular gaging stations were maintained during the year, and an exceptionally large number of miscellaneous measurements and special investigations were made. The "Report of Progress of Stream Measurements," which contains the results of this work, is published in a series of fourteen Water-Supply and Irrigation Papers, Nos. 165 to 178, as follows:

No. 165. Atlantic coast of New England drainage.
No. 166. Hudson, Passaic, Raritan, and Delaware river drainages.
No. 167. Susquehanna, Gunpowder, Patapsco, Potomac, James, Roanoke, and Yadkin river drainages.
No. 168. Santee, Savannah, Ogeechee, and Altamaha rivers and eastern Gulf of Mexico drainages.
No. 169. Ohio and lower eastern Mississippi river drainages.
No. 170. Great Lakes and St. Lawrence River drainages.
No. 171. Hudson Bay and upper eastern and western Mississippi River drainages.
No. 172. Missouri River drainage.
No. 173. Meramec, Arkansas, Red, and lower western Mississippi river drainages.
No. 174. Western Gulf of Mexico and Rio Grande drainages.
No. 175. Colorado River drainage.
No. 176. The Great Basin drainage.
No. 177. The Great Basin and Pacific Ocean drainages in California.
No. 178. Columbia River and Puget Sound drainages.

These papers embody the data collected at the regular gaging stations, the results of the computations based on the observations, and such other information as may have a direct bearing on the study of the subject, and include, as far as practicable, descriptions of the basins and the streams draining them.

For the purpose of introducing uniformity into the reports for the various years the drainages of the United States have been divided into eleven grand divisions, which have been again divided into secondary divisions, as shown in the following list. The Progress Report has been made to conform to this arrangement, each part containing the data for one or more of the secondary divisions. The secondary divisions have in most cases been redivided, and the facts have been arranged, so far as practicable, geographically.

List of drainage basins in the United States.

NORTHERN ATLANTIC DRAINAGE BASINS.

St. John.
St. Croix.
Penobscot.
Kennebec.
Androscoggin.
Presumpscot.
Saco.
Merrimac.
Connecticut.
Blackstone.
Thames.
Housatonic.
Hudson.
Passaic.
Raritan.
Delaware.
Susquehanna.
Potomac.
Minor Chesapeake Bay.
Minor northern Atlantic.

SOUTHERN ATLANTIC DRAINAGE BASINS.

James.
Chowan.
Roanoke.
Tar.
Neuse.
Cape Fear.
Great Pedee (Yadkin).
Santee.
Savannah.
Ogeechee.
Altamaha.
Minor southern Atlantic.

EASTERN GULF OF MEXICO D

Suwanee.
Apalachicola.
Mobile.
P


L SURVEY
123° 121° 119° 117° 115° 113° 111° 109° 107° 105° 103°
D O M I N I O
W A S H I N G T O N
M O N T A N A
R E G O N I D A H O
W Y O M I N G
N E B
N E V A D A
U T A H
C O L O R A D O
A R I Z O N A
N E W M E X I C O
T E
M E X
L O W E R C A L I F O R N I A
119° 117° 115° 113° 111° 109° 107° 105° 103°

MAP OF THE UNITED STATES, SH



ATION OF PRINCIPAL

MAINTAINED

EASTERN MISSISSIPPI RIVER DRAINAGE BASINS.

ırn Mississippi.	Upper eastern Mississippi.

ST. LAWRENCE RIVER DRAINAGE BASINS.

ior.	Niagara River.
gan.	Lake Ontario.
ı.	Lake Champlain (Richelieu River).
air.	Minor St. Lawrence.

WESTERN MISSISSIPPI RIVER DRAINAGE BASINS.

ern Mississippi.	Lower western Mississippi.
	Arkansas.
	Red.

WESTERN GULF OF MEXICO DRAINAGE BASINS.

	Guadelupe.
	San Antonio.
	Nueces.
	Rio Grande.
(Texas).	Minor western Gulf of Mexico.

COLORADO RIVER DRAINAGE BASIN.

THE GREAT BASIN.

ountains.	Sierra Nevada.
	Minor streams in Great Basin.

PACIFIC COAST DRAINAGE BASINS.

acific.	Columbia.
ico Bay.	Puget Sound.
acific.	

HUDSON BAY DRAINAGE BASINS.

DEFINITIONS.

ıme of water flowing in a stream—the "run-off" or "discharge"—is expressed in rms, each of which has become associated with a certain class of work. These be divided into two groups—(1) those which represent a rate of flow, as second-ns per minute, miner's inch, and run-off in second-feet per square mile; and (2) h represent the actual quantity of water, as run-off in depth in inches and acre-y may be defined as follows:

l-foot" is an abbreviation for cubic foot per second, and is the rate of discharge of ing in a stream 1 foot wide, 1 foot deep, at a rate of 1 foot per second. It is gen-l as a fundamental unit from which others are computed.

s per minute" is generally used in connection with pumping and city water supply. iner's inch" is the rate of discharge of water that passes through an orifice 1 inch der a head which varies locally. It has been commonly used by miners and irri-oughout the West, and is defined by statute in each State in which it is used. In s the California miner's inch is used, which is the fiftieth part of a second-foot.

l-feet per square mile" is applied to the average number of cubic feet of water r second from each square mile of area drained, on the assumption that the run-ibuted uniformly, both as regards time and area.

ff in inches" is the depth to which the drainage area would be covered if all the ing from it in a given period were conserved and uniformly distributed on the It is used for comparing run-off with rainfall, which is usually expressed in depth

oot" is equivalent to 43,560 cubic feet, and is the quantity required to cover an depth of 1 foot. It is commonly used in connection with storage for irrigation ere is a convenient relation between the second-foot and the acre-foot. One t flowing for twenty-four hours will deliver 86,400 cubic feet or approximately

EXPLANATION OF TABLES.

For each regular gaging station are given, as far as available, the following data:

1. Description of station.
2. List of discharge measurements.
3. Gage-height table.
4. Rating table.
5. Table of estimated monthly and yearly discharges and run-off, based on all the facts obtained to date.

The descriptions of stations give such general information about the locality and equipment as would enable the reader to find and use the station. They also give, as far as possible, a complete history of all the changes that have occurred since the establishment of the station that would be factors in using the data collected.

The discharge-measurement table gives the results of the discharge measurements made during the year, including the date, the name of the hydrographer, the gage height, the area of cross section, the mean velocity, and the discharge in second-feet.

The table of daily gage heights gives the daily fluctuations of the surface of the river as found from the mean of the gage readings taken each day. The gage height given in the table represents the elevation of the surface of the water above the zero of the gage. At most stations the gage is read in the morning and in the evening.

The rating table gives discharges in second-feet corresponding to each stage of the river as given by the gage heights.

In the table of estimated monthly discharge, the column headed "Maximum" gives the mean flow for the day when the mean gage height was highest. This is the flow as given in the rating table for that mean gage height. As the gage height is the mean for the day, there might have been short periods when the water was higher and the corresponding discharge larger than given in this column. Likewise in the column of "Minimum" the quantity given is the mean flow for the day when the mean gage height was lowest. The column headed "Mean" is the average flow for each second during the month. On this are based the computations for the three remaining columns, which are defined on page 3.

In the computations for the tables of this report the following general and special rules have been used:

Fundamental rules for computation.

1. The highest degree of precision consistent with the rational use of time and money is imperative.
2. All items of computation should be expressed by at least two and not more than four significant figures.
3. Any measurement in a vertical velocity, mean velocity, or discharge curve whose per cent of error is five times the average per cent of error of all the other measurements should be rejected.
4. In reducing the number of significant figures, or the number of decimal places, by dropping the last figure, the following rules apply:

(*a*) When the figure in the place to be rejected is less than 5, drop it without changing the preceding figure. Example: 1,827.4 becomes 1,827.

(*b*) When the figure in the place to be rejected is greater than 5, drop it and increase the preceding figure by 1. Example: 1,827.6 becomes 1,828.

(*c*) When the figure in the place to be rejected is 5, and it is preceded by an even figure, drop the 5. Example: 1,828.5 becomes 1,828.

(*d*) When the figure in the place to be rejected is 5, and it is preceded by an odd figure, drop the 5 and increase the preceding figure by 1. Example: 1,827.5 becomes 1,828.

Special rules for computation.

1. Rating tables are to be constructed as closely as the data on which they are based will warrant No decimals are to be used when the discharge is over 50 second-feet.
2. Daily discharges shall be applied directly to the gage heights as they are tabulated.
3. Monthly means are to be carried out to one decimal place when the quantities are below 100 second-feet. Between 100 and 10,000 second-feet, the last figure in the monthly mean shall be a significant figure. This also applies to the yearly mean.
4. Second-feet per square mile and depth in inches for the drainage area shall be carried out to at least three significant figures, except in the case of decimals, where the first figure is preceded by one or more naughts (0), when the quantity shall be carried out to two figures. Example: 1.25; .125, .012, .0012. The yearly means for run-off shall be carried out to at least three significant figures and at least two decimals.

EASTERN MISSISSIPPI RIVER DRAINAGE BASINS.

rn Mississippi.	Upper eastern Mississippi.

ST. LAWRENCE RIVER DRAINAGE BASINS.

or.	Niagara River.
an.	Lake Ontario.
.	Lake Champlain (Richelieu River).
ir.	Minor St. Lawrence.

WESTERN MISSISSIPPI RIVER DRAINAGE BASINS.

rn Mississippi.	Lower western Mississippi.
	Arkansas.
	Red.

WESTERN GULF OF MEXICO DRAINAGE BASINS.

	Guadelupe.
	San Antonio.
	Nueces.
	Rio Grande.
Texas).	Minor western Gulf of Mexico.

COLORADO RIVER DRAINAGE BASIN.
THE GREAT BASIN.

untains.	Sierra Nevada.
	Minor streams in Great Basin.

PACIFIC COAST DRAINAGE BASINS.

cific.	Columbia.
co Bay.	Puget Sound.
cific.	

HUDSON BAY DRAINAGE BASINS.

DEFINITIONS.

me of water flowing in a stream—the "run-off" or "discharge"—is expressed in ms, each of which has become associated with a certain class of work. These be divided into two groups—(1) those which represent a rate of flow, as second- s per minute, miner's inch, and run-off in second-feet per square mile; and (2) h represent the actual quantity of water, as run-off in depth in inches and acre- y may be defined as follows:

-foot" is an abbreviation for cubic foot per second, and is the rate of discharge of ing in a stream 1 foot wide, 1 foot deep, at a rate of 1 foot per second. It is gen- as a fundamental unit from which others are computed.

s per minute" is generally used in connection with pumping and city water supply. ner's inch" is the rate of discharge of water that passes through an orifice 1 inch ler a head which varies locally. It has been commonly used by miners and irri- ughout the West, and is defined by statute in each State in which it is used. In s the California miner's inch is used, which is the fiftieth part of a second-foot.

-feet per square mile" is applied to the average number of cubic feet of water second from each square mile of area drained, on the assumption that the run- buted uniformly, both as regards time and area.

f in inches" is the depth to which the drainage area would be covered if all the ing from it in a given period were conserved and uniformly distributed on the t is used for comparing run-off with rainfall, which is usually expressed in depth

ot" is equivalent to 43,560 cubic feet, and is the quantity required to cover an depth of 1 foot. It is commonly used in connection with storage for irrigation ere is a convenient relation between the second-foot and the acre-foot. One t flowing for twenty-four hours will deliver 86,400 cubic feet or approximately

EXPLANATION OF TABLES.

For each regular gaging station are given, as far as available, the following data:

1. Description of station.
2. List of discharge measurements.
3. Gage-height table.
4. Rating table.
5. Table of estimated monthly and yearly discharges and run-off, based on all the facts obtained to date.

The descriptions of stations give such general information about the locality and equipment as would enable the reader to find and use the station. They also give, as far as possible, a complete history of all the changes that have occurred since the establishment of the station that would be factors in using the data collected.

The discharge-measurement table gives the results of the discharge measurements made during the year, including the date, the name of the hydrographer, the gage height, the area of cross section, the mean velocity, and the discharge in second-feet.

The table of daily gage heights gives the daily fluctuations of the surface of the river as found from the mean of the gage readings taken each day. The gage height given in the table represents the elevation of the surface of the water above the zero of the gage. At most stations the gage is read in the morning and in the evening.

The rating table gives discharges in second-feet corresponding to each stage of the river as given by the gage heights.

In the table of estimated monthly discharge, the column headed "Maximum" gives the mean flow for the day when the mean gage height was highest. This is the flow as given in the rating table for that mean gage height. As the gage height is the mean for the day, there might have been short periods when the water was higher and the corresponding discharge larger than given in this column. Likewise in the column of "Minimum" the quantity given is the mean flow for the day when the mean gage height was lowest. The column headed "Mean" is the average flow for each second during the month. On this are based the computations for the three remaining columns, which are defined on page 3.

In the computations for the tables of this report the following general and special rules have been used:

Fundamental rules for computation.

1. The highest degree of precision consistent with the rational use of time and money is imperative.
2. All items of computation should be expressed by at least two and not more than four significant figures.
3. Any measurement in a vertical velocity, mean velocity, or discharge curve whose per cent of error is five times the average per cent of error of all the other measurements should be rejected.
4. In reducing the number of significant figures, or the number of decimal places, by dropping the last figure, the following rules apply:

(*a*) When the figure in the place to be rejected is less than 5, drop it without changing the preceding figure. Example: 1,827.4 becomes 1,827.

(*b*) When the figure in the place to be rejected is greater than 5, drop it and increase the preceding figure by 1. Example: 1,827.6 becomes 1,828.

(*c*) When the figure in the place to be rejected is 5, and it is preceded by an even figure, drop the 5. Example: 1,828.5 becomes 1,828.

(*d*) When the figure in the place to be rejected is 5, and it is preceded by an odd figure, drop the 5 and increase the preceding figure by 1. Example: 1,827.5 becomes 1,828.

Special rules for computation.

1. Rating tables are to be constructed as closely as the data on which they are based will warrant. No decimals are to be used when the discharge is over 50 second-feet.
2. Daily discharges shall be applied directly to the gage heights as they are tabulated.
3. Monthly means are to be carried out to one decimal place when the quantities are below 100 second-feet. Between 100 and 10,000 second-feet, the last figure in the monthly mean shall be a significant figure. This also applies to the yearly mean.
4. Second-feet per square mile and depth in inches for the individual months shall be carried out to at least three significant figures, except in the case of decimals where the first significant figure is preceded by one or more naughts (0), when the quantity shall be carried out to two significant figures. Example: 1.25; .125, .012, .0012. The yearly means for these quantities are always to be expressed in three significant figures and at least two decimals places.

CONVENIENT EQUIVALENTS.

1 second-foot equals 50 California miner's inches.
1 second-foot equals 38.4 Colorado miner's inches.
1 second-foot equals 40 Arizona miner's inches.
1 second-foot equals 7.48 United States gallons per second; equals 448.8 gallons per minute; equals 646,272 gallons for one day.
1 second-foot equals 6.23 British imperial gallons per second.
1 second-foot for one year covers 1 square mile 1.131 feet deep, or 13.572 inches deep.
1 second-foot for one year equals 0.000214 cubic mile; equals 31,536,000 cubic feet.
1 second-foot equals about 1 acre-inch per hour.
1 second-foot falling 10 feet equals 1.136 horsepower.
100 California miner's inches equals 15 United States gallons per second.
100 California miner's inches equal 77 Colorado miner's inches.
100 California miner's inches for one day equal 4 acre-feet.
100 Colorado miner's inches equal 2.60 second-feet.
100 Colorado miner's inches equal 19.5 United States gallons per second.
100 Colorado miner's inches equal 130 California miner's inches.
100 Colorado miner's inches for one day equal 5.2 acre-feet.
100 United States gallons per minute equal 0.223 second-foot.
100 United States gallons per minute for one day equal 0.44 acre-foot.
1,000,000 United States gallons per day equal 1.55 second-feet.
1,000,000 United States gallons equal 3.07 acre-feet.
1,000,000 cubic feet equal 22.95 acre-feet.
1 acre-foot equals 325,850 gallons.
1 inch deep on 1 square mile equals 2,323,200 cubic feet.
1 inch deep on 1 square mile equals 0.0737 second-foot per year.
1 inch equals 2.54 centimeters.
1 foot equals 0.3048 meter.
1 yard equals 0.9144 meter.
1 mile equals 1.60935 kilometers.
1 mile equals 1,760 yards; equals 5,280 feet; equals 63,360 inches.
1 square yard equals 0.836 square meter.
1 acre equals 0.4047 hectare.
1 acre equals 43,560 square feet; equals 4,840 square yards.
1 acre equals 209 feet square, nearly.
1 square mile equals 259 hectares.
1 square mile equals 2.59 square kilometers.
1 cubic foot equals 0.0283 cubic meter.
1 cubic foot equals 7.48 gallons; equals 0.804 bushel.
1 cubic foot of water weighs 62.5 pounds.
1 cubic yard equals 0.7646 cubic meter.
1 cubic mile equals 147,198,000,000 cubic feet.
1 cubic mile equals 4,667 second-feet for one year.
1 gallon equals 3.7854 liters.
1 gallon equals 8.36 pounds of water.
1 gallon equals 231 cubic inches (liquid measure).
1 pound equals 0.4536 kilogram.
1 avoirdupois pound equals 7,000 grains.
1 troy pound equals 5.760 grams.
1 meter equals 39.37 inches. Log. 1.5951654.
1 meter equals 3.280833 feet. Log. 0.5159842.
1 meter equals 1.093611 yards. Log. 0.0388629.
1 kilometer equals 3.281 feet; equals five-eighths mile, nearly.
1 square meter equals 10.764 square feet; equals 1.196 square yards.
1 hectare equals 2.471 acres.
1 cubic meter equals 35.314 cubic feet; equals 1.308 cubic yards.
1 liter equals 1.0567 quarts.
1 gram equals 15.43 grains.
1 kilogram equals 2.2046 pounds.
1 tonneau equals 2,204.6 pounds.
1 foot per second equals 1.097 kilometers per hour.
1 foot per second equals 0.68 mile per hour.
1 cubic meter per minute equals 0.5886 second-foot.
1 atmosphere equals 15 pounds per square inch; equals 1 ton per square foot; equals 1 kilogram per square centimeter.
Acceleration of gravity equals 32.16 feet per second every second.
1 horsepower equals 550 foot-pounds per second.

1 horsepower equals 76 kilogram-meters per second.
1 horsepower equals 746 watts.
1 horsepower equals 1 second-foot falling 8.8 feet.
1¼ horsepowers equal about 1 kilowatt.
To calculate water power quickly: $\frac{\text{Sec.-ft.} \times \text{fall in feet}}{11}$ = Net horsepower on water wheel, realizing 80 per cent of the theoretical power.
Quick formula for computing discharge over weirs: Cubic feet per minute equals $0.4025\, l\sqrt{h^3 l}$ = length of weir in inches; h=head in inches flowing over weir, measured from surface of still water.
To change miles to inches on map:
Scale 1 : 125000, 1 mile=0.50688 inch.
Scale 1 : 90000, 1 mile=0.70400 inch.
Scale 1 : 62500, 1 mile=1.01376 inches.
Scale 1 : 45000, 1 mile=1.40800 inches.

FIELD METHODS OF MEASURING STREAM FLOW.

The methods used in collecting these data and in preparing them for publication are given in detail in Water-Supply Papers No. 94 (Hydrographic Manual, U. S. Geological Survey) and No. 95 (Accuracy of Stream Measurements). In order that those who use this report may readily become acquainted with the general methods employed, the following brief description is given:

Streams may be divided, with respect to their physical conditions, into three classes—(1) those with permanent beds; (2) those with beds which change only during extreme low or high water; (3) those with constantly shifting beds. In estimating the daily flow special methods are necessary for each class. The data on which these estimates are based and the methods of collecting them are, however, in general the same.

There are three distinct methods of determining the flow of open-channel streams—(1) by measurements of slope and cross section and the use of Chezy's and Kutter's formulas; (2) by means of a weir; (3) by measurements of the velocity of the current and of the area of the cross section. The method chosen for any case depends on the local physical conditions, the degree of accuracy desired, the funds available, and the length of time that the record is to be continued.

Slope method.—Much information has been collected relative to the coefficients to be used in the Chezy formula, $v = c\sqrt{rs}$. This has been utilized by Kutter, both in developing his formula for c and in determining the values of the coefficient n which appears therein. The results obtained by the slope method are in general only roughly approximate, owing to the difficulty in obtaining accurate data and the uncertainty of the value for n to be used in Kutter's formula. The most common use of this method is in estimating the flood discharge of a stream when the only data available are the cross section, the slope as shown by marks along the bank, and a knowledge of the general conditions.

Weir method.—When funds are available and the conditions are such that sharp-crested weirs can be erected, these offer the best facilities for determining flow. If dams are suitably situated and constructed they may be utilized for obtaining reliable estimates of flow. The conditions necessary to insure good results may be divided into two classes—(1) those relating to the physical characteristics of the dam itself, and (2) those relating to the diversion and use of water around and through the dam.

The physical requirements are as follows: (*a*) Sufficient height of dam, so that backwater will not interfere with free fall over it; (*b*) absence of leaks of appreciable magnitude; (*c*) topography or abutments which confine the flow over the dam at high stages; (*d*) level crests, which are kept free from obstructions caused by floating logs or ice; (*e*) crests of a type for which the coefficients to be used in $Q = c\, b\, h^{\frac{3}{2}}$, or some similar standard weir formula, are known (see Water-Supply Paper No. 150); (*f*) either no flash boards or exceptional care in reducing leakage through them and in recording their condition.

Preferably there should be no diversion of water through or around the dam. Generally, however, a dam is built for purposes of power or navigation, and part or all of the water flowing past it is diverted for such uses. This water must be measured and added to that passing over the dam. To insure accuracy in such estimates the amount of water diverted

should be reasonably constant. Furthermore, it should be so diverted that it can be measured, either by a weir, by a current meter, or by a simple system of water wheels which are of standard make or which have been rated as meters under working conditions and so installed that the gate openings, the heads under which they work, and their angular velocities may be accurately observed.

The combination of physical conditions and uses of the water should be such that the estimates of flow will not involve, for a critical stage of considerable duration, the use of a head, on a broad-crested dam, of less than 6 inches. Moreover, when all other conditions are good, the cooperation of the owners or operators of the plant is still essential if reliable results are to be obtained.

A gaging station at a weir or dam has the general advantage of continuity of record through the periods of ice and floods, and the disadvantages of uncertainty of coefficient to be used in the weir formula and of complications in the diversion and use of the water.

Velocity method.—The determination of the quantity of water flowing past a certain section of a stream at a given time is termed a discharge measurement. This quantity is the product of two factors—the mean velocity and the area of the cross section. The mean velocity is a function of surface slope, wetted perimeter, roughness of bed, and the channel conditions at, above, and below the gaging section. The area depends on the contour of the bed and the fluctuations of the surface. The two principal ways of measuring the velocity of a stream are by floats and current meters.



FIG. 1.—Cable station, showing section of river, car, gage, etc.

Great care is taken in the selection and equipment of gaging stations for determining discharge by velocity measurements in order that the data may have the required degree of accuracy. Their essential requirements are practically the same, whether the velocity is determined by meters or floats. They are located as far as possible where the channel is straight both above and below the gaging section; where there are no cross currents, backwater, or boils; where the bed of the stream is reasonably free from large projections of a permanent character; and where the banks are high and subject to overflow only at flood stages. The station must be so far removed from the effects of tributary streams and dams or other artificial obstructions that the gage height shall be an index of the discharge.

Certain permanent or semipermanent structures, usually referred to as "equipment," are generally appurtenant to a gaging station. These are a gage for determining the fluctuations of the water surface, bench marks to which the datum of the gage is referred, permanent marks on a bridge or a tagged line indicating the points of measurement, and, where the current is swift, some appliance (generally a secondary cable) to hold the meter in position in the water. As a rule the stations are located at bridges if the channel conditions are satisfactory, as from them observations can more readily be made and the cost of equipment is small.

The floats in common use are the surface, subsurface, and tube or rod floats. A corked bottle with a flag in the top and weighted at the bottom makes one of the most satisfactory

surface floats, as it is affected but little by wind. In case of flood measurements, good results can be obtained by observing the velocity of floating cakes of ice or débris. In all surface float measurements coefficients must be used to reduce the observed velocity to the mean velocity. The subsurface and tube or rod floats are intended to give directly the mean velocity in the vertical. Tubes give excellent results when the channel conditions are good, as in canals.

In measuring velocity by a float, observation is made of the time taken by the float to pass over the "run," a selected stretch of river from 50 to 200 feet long. In each discharge measurement a large number of velocity determinations are made at different points across the stream, and from these observations the mean velocity for the whole section is determined. This may be done by plotting the mean positions of the floats as indicated by the distances from the bank as ordinates and the corresponding times as abscissas. A curve through these points shows the mean time of run at any point across the stream, and the mean time for the whole stream is obtained by dividing the area bounded by this curve and its axis by the width. The length of the run divided by the mean time gives the mean velocity.

The area used in float measurements is the mean of the area at the two ends of the run and at several intermediate sections.

The essential parts of the current meters in use are a wheel of some type, so constructed that the impact of flowing water causes it to revolve, and a device for recording or indicating the number of revolutions. The relation between the velocity of the moving water and the revolutions of the wheel is determined for each meter. This rating is done by drawing the meter through still water for a given distance at different speeds and noting the number of revolutions for each run. From these data a rating table is prepared which gives the velocity per second for any number of revolutions.

Many kinds of current meters have been constructed. They may, however, be classed in two general types—those in which the wheel is made up of a series of cups, as the Price, and those having a screw-propeller wheel, as the Haskell. Each meter has been developed for use under some special condition. In the case of the small Price meter, which has been largely developed and extensively used by the United States Geological Survey, an attempt has been made to get an instrument which could be used under practically all conditions.

Current-meter measurements may be made from a bridge, cable, or boat or by wading, and gaging stations may be classified in accordance with such use. Fig. 1 shows a typical cable station.

In making the measurement an arbitrary number of points are laid off on a line perpendicular to the thread of the stream. The points at which the velocity and depth are observed are known as measuring points, and are usually fixed at regular intervals, varying from 2 to 20 feet, depending on the size and condition of the stream. Perpendiculars dropped from the measuring points divide the gaging section into strips. For each strip or pair of strips the mean velocity, area, and discharge are determined independently, so that conditions existing in one part of the stream may not be extended to parts where they do not apply.

Three classes of methods of measuring velocity with current meters are in general use—multiple-point, single-point, and integration.

The three principal multiple-point methods in general use are the vertical velocity-curve, 0.2 and 0.8 depth, and top, bottom, and mid depth.

In the vertical velocity-curve method a series of velocity determinations are made in each vertical at regular intervals, usually from 0.5 to 1 foot apart. By plotting these velocities as abscissas and their depths as ordinates and drawing a smooth curve among the resulting points the vertical velocity-curve is developed. This curve shows graphically the magnitude and changes in velocity from the surface to the bottom of the stream. The mean velocity in the vertical is then obtained by dividing the area of the velocity-curve and its axis by the depth. On account of the

elocity or at an arbitrary depth for which the coefficient for reducing the mean has been determined.

nsive experiments by vertical velocity-curves show that the thread of mean velocity y occurs at from 0.5 to 0.7 of the total depth. In general practice the thread of mean is considered to be at 0.6 depth, at which point the meter is held in a majority of the ements. A large number of vertical velocity-curve measurements taken on many under varying conditions show that the average coefficient for reducing the velocity d at 0.6 depth to mean velocity is practically unity.

e other principal single-point method the meter is held near the surface, usually 1 low, or low enough to be unaffected by the wind or other disturbing influences. nown as the subsurface method. The coefficient for reducing the velocity taken ubsurface to the mean has been found to be from 0.85 to 0.95, depending on the stage, , and channel conditions. The higher the stage the larger the coefficient. This is specially adapted for flood measurements or when the velocity is so great that the an not be kept at 0.6 depth.

ertical-integration method consists in moving the meter at a slow uniform speed e surface to the bottom and back again to the surface and noting the number of revo- and the time taken in the operation. This method has the advantage that the velocity point of the vertical is measured twice. It is well adapted for measurements under as a check on the point methods.

rea, which is the other factor in the velocity method of determining the discharge of a, depends on the stage of the river, which is observed on the gage, and on the gen- itour of the bed of the stream, which is determined by soundings. The soundings ally taken at each measuring point at the time of the discharge measurement, either g the meter and cable or by a special sounding line or rod. For streams with perma- ds standard cross sections are usually taken during low water. These sections serve k the soundings which are taken at the time of the measurements and from them any which may have taken place in the bed of the stream can be detected. They are also e in obtaining the area for use in computations of high-water measurements, as accu- ndings are hard to obtain at high stages.

mputing the discharge measurements from the observed velocities and depths at points of measurement the measuring section is divided into elementary strips, as in fig. 1, and the mean velocity, area, and discharge are determined separately for

From these data an approximate estimate of the daily flow can be made by constructing a rating curve (really a series of curves) similar to that used for open channels, but considering, in addition to gage heights and discharge, varying thickness of ice. Such data as are available in regard to this subject are published in Water-Supply Paper No. 146, pp. 141-148.

OFFICE METHODS OF COMPUTING RUN-OFF.

There are two principal methods of estimating run-off, depending on whether or not the bed of the stream is permanent.

For stations on streams with permanent beds the first step in computing the run-off is the construction of the rating table, which shows the discharge corresponding to any stage of the stream. This rating table is applied to the record of stage to determine the amount of water flowing. The construction of the rating table depends on the method used in measuring flow.

For a station at a weir or dam, the basis for the rating table is some standard weir formula. The coefficients to be used in its application depend on the type of dam and other conditions near its crest. After inserting in the weir formula the measured length of crest and assumed coefficient, the discharge is computed for various heads, and the rating table considered.


MEAN VELOCITY, AREA AND RATING CURVES FOR SKYKOMISH RIVER (SO. FORK) NEAR INDEX, WASH.
MEASUREMENTS IN 1902 NO. 1 TO 7
" 1903 8 " 12
RATING CURVE
AREA CURVE
MEAN VELOCITY CURVE
GAGE HEIGHT IN FEET
AREA IN SQUARE FEET
VELOCITY IN FEET PER SECOND
DISCHARGE IN SECOND-FEET

FIG. 2.—Discharge, mean-velocity, and area curves for South Fork of Skykomish River near Index, Wash.

The data necessary for the construction of a rating table for a velocity-area station are the results of the discharge measurements, which include the record of stage of the river at the time of measurement, the area of the cross section, the mean velocity of the current, and the quantity of water flowing. A thorough knowledge of the conditions at and in the vicinity of the station is also necessary.

The construction of the rating table depends on the following laws of flow for open permanent channels: (1) The discharge will remain constant so long as the conditions at or near the gaging station remain constant. (2) The discharge will be the same whenever the stream is at a given stage, if the change of slope due to the rise and fall of the stream be neglected. (3) The discharge is a function of and increases gradually with the stage.

The plotting of results of the various discharge measurements using gage heights as ordinates, and discharge, mean velocity, and area as abscissas, will define curves which show the discharge, mean velocity, and area corresponding to any gage height. For the development of these curves there should be therefore a sufficient number of discharge measurements to cover the range of the stage of the stream. Fig. 2 shows a typical rating curve with its corresponding mean velocity and area curves.

measurements. Its principal use is in connection with the area curve in locating discharge measurements and in constructing the rating table.

ischarge curve is defined primarily by the measurements of discharge, which are and weighted in accordance with the local conditions existing at the time of each nent. The curve may, however, best be located between and beyond the measure- r means of curves of area and mean velocity. The discharge curve under normal is is concave toward the horizontal axis and is generally parabolic in form.

preparation of the rating table the discharge for each tenth or half tenth on the ken from the curve. The differences between successive discharges are then taken sted according to the law that they shall either be constant or increasing.

termination of daily discharge of streams with changeable beds is a difficult prob- case there is a weir or dam available, a condition which seldom exists on streams of , estimates can be obtained by its use. In case of velocity-area stations frequent measurements must be made if the estimates are to be other than rough approxi-

For stations with beds which shift slowly or are materially changed only during ating tables can be prepared for periods between such changes and satisfactory btained with a limited number of measurements, provided that some of them are n after the change occurs. For streams with continually shifting beds, such as the and Rio Grande, discharge measurements should be made every two or three days, discharges for intervening days obtained either by interpolation modified by gage r by Professor Stout's method, which has been described in full in the Nineteenth Report, Part IV, page 323, and in Engineering News of April 21, 1904. This method, hic application of it, is also much used in estimating flow at stations where the bed slowly.

COOPERATION AND ACKNOWLEDGMENTS.

f the measurements presented in this paper have been obtained through local phers. Acknowledgment is extended to other persons and corporations who have these hydrographers or have cooperated in any way, either by furnishing records ight of water or by assisting in transportation.

llowing list, arranged geographically by States, gives the names of the hydrog- nd others who have assisted in furnishing and preparing the data contained in this

Kansas.—District hydrographer, M. C. Hinderlider; resident hydrographer, W. G. Russell. Acknowledgments are due the Atchison, Topeka and Santa Fe, Union Pacific, Missouri, Kansas and Texas, Missouri Pacific, and Chicago, Rock Island and Pacific railways for annual passes issued to Mr. Russell.

Missouri. District hydrographer, F. W. Hanna,[a] assisted by M. S. Brennan and S. K. Clapp. Acknowledgment is due the St. Louis and San Francisco Railroad for transportation furnished to Messrs. Hanna and Brennan.

Nebraska.—District hydrographer, M. C. Hinderlider [b] assisted by J. C. Stevens and by H. C. Gardner, and F. S. Dobson, assistants to the State engineer. Valuable assistance was rendered by Prof. O. V. P. Stout, of the University of Nebraska, in the way of free use by J. C. Stevens of office facilities and suggestions in the methods for the collection of field data. Acknowledgments are also due the Chicago, Burlington and Quincy, Chicago and Northwestern, and Fremont, Elkhorn and Missouri Valley railroads for annual passes issued in favor of Messrs. Stevens and Gardner.

Montana. District engineer, C. C. Babb,[c] assisted by C. T. Prall, L. R. Stockman, H. M. Morse, W. B. Freeman, J. H. Sloan, A. P. Porter, and Gordon Edson. Acknowledgments are due the Great Northern and Northern Pacific railways for transportation and to Mr. J. W. Shields, of Choteau, Mont., for voluntary observations of Teton River.

North Dakota.—District hydrographer, F. W. Hanna, assisted by E. F. Chandler, of the engineering department of the University of North Dakota.

South Dakota.—Resident hydrographer, R. F. Walter.[d]

Wyoming.—The hydrographic work in the State has been carried on under the direction of the district hydrographer, M. C. Hinderlider, and by the resident hydrographer, A. J. Parshall. Acknowledgments are due for annual passes over all their lines in Wyoming to the Union Pacific, Chicago, Burington and Quincy, Colorado and Southern, Colorado and Wyoming, and Fremont, Elkhorn and Missouri Valley railroads.

GENERAL FEATURES OF THE MISSOURI RIVER DRAINAGE.

Missouri River and its innumerable tributaries drain an immense area in the northern and western section of the United States. The northern boundary of this area is approximately the fiftieth parallel, the southern the thirty-ninth; its western limit is the Rocky Mountain region, while to the east the divide between this basin and that of the upper Mississippi crosses eastern North and South Dakota, western Iowa, and northeastern Missouri. Its extent east and west is about 900 miles; north and south it is 600 miles; the basin comprises a total of 492,000 square miles.

The topography of the basin is of the most varied character, ranging from the mountainous regions of Montana, Wyoming, and Colorado to the rolling prairies of the Dakotas, Nebraska, and Kansas. The upper tributaries drain a forested region, but the main stream flows through a country almost wholly devoid of forests. The precipitation in the mountainous portion of the basin is mainly in the form of heavy snowfall, but a great part of the area lies within the arid and semiarid regions, and it is probable that the average annual precipitation throughout the entire basin is less than 20 inches.

The tributaries are mostly in the upper course of the river and from the western side of the basin. The most important of these tributaries are Mussellshell, Marias, Milk, Yellowstone, Cheyenne, Platte, and Kansas rivers.

The work of the United States Geological Survey in this drainage area during 1905 is set forth in the following pages:

MISSOURI RIVER.

DESCRIPTION OF BASIN.

Missouri River proper is formed in southwestern Montana by the union of three streams which were discovered by Lewis and Clark in 1806 and named by them Jefferson, Madison, and Gallatin rivers. Jefferson and Madison forks come together first, and within 2 miles they are joined by the Gallatin. The head of the Missouri thus formed lies in about latitude 45° 56′ north and longitude 111° 32′ west. Each of the three headwater rivers is

[a] District hydrographer for Missouri during 1906, A. H
[b] District hydrographer for 1906, Adna Dobson, Stat
[c] District hydrographer for Montana, northweste
ming, 1906, H. M. Morse, Huntley, Mont.
[d] District hydrographer for 1906, J. E. Stewart, I

feet wide, flows with great velocity, and discharges large quantities of water. The Gallatin is the most rapid of the three. The beds of all are formed of smooth pebbles and gravel and the waters are perfectly transparent.

From the junction of the three forks the course of the Missouri lies through mountain valleys and deep canyons, from which it finally issues through a gorge in a range of rocks, called by Lewis and Clark the "gates of the Rocky Mountains." Thirty-five miles above Fort Benton the river pours over Great Falls and from that point onward it is a navigable stream. For miles below the falls the river flows in a deep canyon, with banks ranging from 100 to 160 feet in height. Below the mouth of Marias River, which enters from the north, the banks are less abrupt and rise with gentle slopes to the bluffs. The high-water width of the river, which in the vicinity of Fort Benton is 500 to 1,000 feet, increases to 1,500 feet at the mouth of Milk River and to 2,000 feet near the mouth of the Yellowstone. Below the Yellowstone the width gradually increases from 2,000 to 3,000 feet, and this remains approximately the average width for 600 miles of its course.

From the mouth of the Yellowstone the Missouri follows a winding but on the whole southeasterly course until it is joined by the Kansas; thence it flows more to the east across the State of Missouri, and empties into the Mississippi 16 miles above St. Louis, 189 miles above the mouth of the Ohio, and 2,824 miles below the junction of its three upper forks.

For the first 350 miles below the union of the three forks the Missouri is a comparatively clear stream, but approximately midway between the forks and the mouth of the Yellowstone its character gradually changes and it becomes turbid. Although a large amount of the sediment carried by the Missouri is undoubtedly brought in by the drainage of its tributaries, the greater part is derived from the caving of its banks.

The volume of the Missouri is subject to great variations, the ordinary high-water discharge at the mouth being about 28 times the low-water discharge. The freshets are caused by melting snow and heavy summer rains. The amount of snow falling on the prairies is usually small, but among the Rocky Mountains the snows begin early, continue late, and accumulate to great depths. The regular floods occur in May and June, the June rise being as a rule higher and lasting longer. Thereafter the river steadily decreases in volume, the minimum being reached during the winter months.

Except in the mountain canyons the Missouri flows through an alluvial bottom land of the most fertile character, varying in width from 1½ miles near the mouth to 17 miles in the vicinity of Sioux City. Through this flood plain the river winds back and forth, leaving tongues of land alternately on either side, stretching out from one bluff to within a few thousand feet of the other. In the vicinity of St. Joseph the Missouri is said to make eight complete crossings within a distance of 30 miles, measured in the direction of its general course.

Irrigation is practiced on various tributaries of the stream and agriculture has been extensively developed in several of the valleys. The Missouri itself has not been used for irrigation, owing to its high banks and the consequent difficulty of diversion.

Information in regard to this basin is contained in the following publications of the United States Geological Survey (Ann = Annual Report; WS = Water-Supply Paper):

Description: Ann 11, ii, pp 42–43; 12, ii, pp 236–237; 13, iii, pp 34–35; 22, iv, p 280; WS 84, pp 13–14; 99, pp 34–36; 130, pp 68–69.
Irrigation surveys in, engineering features: Ann 11, ii, pp 114–133; 13, iii, pp 34–63, 53–54.
Rainfall data: Ann 13, iii, pp 39–41; 20, iv, p 235; WS 75, pp 114–116.
Rainfall and run-off relation: Ann 20, iv, pp 232–235; WS 75, pp 117–118.

JEFFERSON RIVER NEAR SAPPINGTON, MONT.

This station was established November 13, 1894, and was discontinued December 31, 1905. It is located 1 mile north of the railroad station at Sappington, Mont., and 7 miles above Willow Creek.

The channel is straight for 500 feet above and below the station. Both banks are composed of clay and are covered with willows and underbrush; the right bank may overflow at extremely high water. The bed is smooth and regular and is covered with gravel. The current is swift and entirely free from eddies. The section is an excellent one.

Until June 15, 1904, discharge measurements were made by means of a cable sit about 300 feet above the old wooden bridge of the Northern Pacific Railway. On that the cable station was destroyed and for a time measurements were made from the lowe of the railroad bridge. The new cable put in November 1, 1904, was placed about 50 above the old one, on account of the building of a new railroad bridge at the former si

During 1905 the gage was read twice daily up to April 1 by John Fraser and from A to November 11 by L. T. Hare, the agent of the Northern Pacific Railway at Sappin after the latter date observations were taken once each day. The original gage was a cal staff fastened to the middle pier of the Northern Pacific Railway bridge. Novem 1897, the gage datum was lowered 0.80 foot. Readings for the subsequent years adjusted to the new datum, but those for the rest of 1897 were corrected to agree wit old datum. Later a chain gage was fastened to the upstream side of the old railroad br the length of the chain was 16.30 feet. June 14, 1905, the gage was moved to the d stream side of the new railroad bridge, 200 feet above; the new chain length is 24.31 The same datum was used for the new gage, and as the water surface is 0.03 foot high this point, there was an increase of 0.03 foot in the gage readings. All readings, how have been referred to the old datum. Bench marks Nos. 1, 2, and 3 are unreliable an additional bench marks have been established, as follows: (4) A cross on top of the c at the northwest corner of a small concrete culvert 800 feet east of the old railroad br elevation, 11.57 feet. (5) A flat notch cut in the sloping surface on the lower wing w the east abutment of the Northern Pacific Railway bridge, about 4 feet from the l corner, marked "U. S. G. S. B. M.;" elevation, 11.62 feet. Elevations are above the of the gage.

Information in regard to this station is contained in the following publications o United States Geological Survey (Ann = Annual Report; Bull = Bulletin; WS = W Supply Paper):

Description: Ann 18, iv, pp 134–135; 19, iv, p 281; Bull 131, p 22; 140, pp 92–93; WS 15, pp 70–7 p 68; 37, pp 206–207; 49, p 264; 66, p 19; 84, pp 47–48; 99, p 133; 130, pp 85–86.

Discharge: Ann 18, iv, p 135; Bull 131, pp 22, 92; 140, p 93; WS 15, p 71; 27, pp 74–75; 37, p 207; 49, 66, p 20; 84, p 48; 99, p 133; 130, p 86.

Discharge, monthly: Ann 18, iv, p 136; 19, iv, p 282; 20, iv, pp 234, 238; 22, iv, p 285; WS 75, pp 11; 84, p 49; 99, p 135; 130, p 88.

Discharge, yearly: Ann 20, iv, p 53.

Gage heights: WS 11, p 49; 15, p 71; 27, p 71; 37, p 207; 49, p 264; 66, p 20; 84, p 48; 99, p 134; 130,

Hydrographs: Ann 19, iv, p 283; 20, iv, p 238; 22, iv, pp 286, 287; WS 75, p 120.

Rainfall and run-off relation: Ann 20, iv, p 235; WS 75, p 118.

Rating tables: Ann 18, iv, p 135; 19, iv, p 282; WS 27, p 75; 52, p 516; 66, p 170; 84, p 48; 99, 130, p 87.

Discharge measurements of Jefferson River near Sappington, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	I ch
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Se*
April 3	L. R. Stockman	250	631	2.01	2.20	
May 4	J. H. Sloan	250	705	2.06	2.32	
May 19	do	250	581	2.11	2.05	
June 14	do	252	1,172	3.52	4.02	
July 8	do	255	887	2.38	2.82	
August 4	do	248	558	1.76	1.92	
September 7	do	237	377	1.56	1.50	
September 21	do	247	363	1.33	1.37	
October 27	H. M. Morse	250	583	1.99	2.15	
November 16	J. H. Sloan	250	646	2.03	2.25	

ly gage height, in feet, of Jefferson River near Sappington, Mont., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
...	6.35	4.35	5.2	2.2	2.4	2.15	3.7	1.95	1.5	1.5	1.95	2.6
...	5.3	4.3	5.2	2.2	2.45	2.35	3.6	1.9	1.5	1.5	2.1	2.6
...	5.4	4.3	5.3	2.1	2.4	2.4	3.6	1.9	1.5	1.5	2.15	2.6
...	5.3	4.3	5.3	2.1	2.35	2.6	3.55	1.85	1.5	1.5	2.15	2.6
...	5.3	4.55	3.35	2.1	2.3	2.8	3.4	1.8	1.5	1.6	2.15	2.6
...	5.15	4.7	2.65	2.1	2.3	3.15	3.2	1.75	1.5	1.6	2.15	2.5
...	5.25	4.8	2.5	2.15	2.2	3.35	3.0	1.7	1.5	1.6	2.15	2.5
...	5.3	4.8	2.3	2.2	2.1	3.4	2.75	1.6	1.5	1.6	2.25	2.5
...	5.3	4.9	2.3	2.45	2.1	3.5	2.65	1.6	1.4	1.6	2.25	2.5
...	5.05	4.9	2.3	2.55	2.2	3.55	2.55	1.6	1.4	1.6	2.25	2.5
...	4.95	4.9	2.3	2.6	2.2	3.6	2.45	1.55	1.4	1.6	2.15	2.6
...	2.95	4.8	2.15	2.5	2.2	3.7	2.35	1.6	1.4	1.6	2.15	2.6
...	2.7	4.8	2.2	2.5	2.15	3.8	2.25	1.5	1.4	1.65	2.15	2.7
...	2.7	4.55	2.2	2.4	2.1	3.9	2.1	1.5	1.4	1.7	2.25	2.8
...	2.85	4.5	2.35	2.4	2.05	3.95	2.1	1.5	1.4	1.7	2.25	3.0
...	3.2	4.6	2.4	2.4	2.0	3.8	2.2	1.5	1.4	1.7	2.25	3.2
...	3.85	4.6	2.45	2.5	1.95	3.6	2.3	1.5	1.4	1.7	2.4	3.3
...	4.75	4.6	2.5	2.5	2.0	3.3	2.3	1.5	1.4	1.8	2.4	3.4
...	5.35	4.85	2.5	2.5	2.1	3.25	2.3	1.5	1.4	1.8	2.4	3.1
...	5.3	4.9	2.5	2.5	2.1	3.2	2.3	1.5	1.3	1.8	2.4	3.0
...	5.2	5.0	2.55	2.55	2.15	3.1	2.25	1.4	1.3	1.85	2.4	2.8
...	5.2	5.15	2.45	2.7	2.25	3.0	2.1	1.4	1.3	1.85	2.4	2.8
...	5.2	5.2	2.4	2.7	2.3	3.0	2.1	1.4	1.3	1.9	2.4	2.7
...	5.25	5.1	2.4	2.7	2.3	3.45	1.95	1.4	1.3	1.95	2.4	2.7
...	5.3	5.15	2.3	2.7	2.2	3.65	1.75	1.3	1.4	2.05	2.4	2.7
...	5.3	5.15	2.3	2.7	2.15	4.15	1.75	1.35	1.4	2.05	2.4	2.8
...	5.35	5.2	2.35	2.7	2.15	4.65	1.75	1.35	1.35	2.1	2.4	3.0
...	5.4	5.2	2.2	2.75	2.05	4.7	1.85	1.55	1.3	2.15	2.4	3.2
...	5.4	.....	2.2	2.6	2.1	4.45	2.0	1.6	1.35	2.05	2.5	3.3
...	5.4	.....	2.2	2.55	2.0	3.95	2.0	1.55	1.5	1.95	2.5	3.2
...	4.8	.....	2.2	.....	2.0	.....	2.0	1.5	.....	1.95	.....	3.0

ver partly gorged January 1 to March 6; probably also gorged somewhat during December.

ng table for Jefferson River near Sappington, Mont., from January 1 to December 31, 1905.

ge ht.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
t.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
20	405	2.40	1,485	3.60	3,425	4.80	5,675
30	465	2.50	1,625	3.70	3,605	4.90	5,865
40	530	2.60	1,775	3.80	3,785	5.00	6,055
50	600	2.70	1,925	3.90	3,965	5.20	6,445
60	675	2.80	2,085	4.00	4,155	5.40	6,845
70	755	2.90	2,245	4.10	4,345	5.60	7,255
80	840	3.00	2,405	4.20	4,535	5.80	7,675
90	930	3.10	2,565	4.30	4,725	6.00	8,095
00	1,025	3.20	2,735	4.40	4,915	6.20	8,535
10	1,125	3.30	2,905	4.50	5,105	6.40	8,975
20	1,235	3.40	3,075	4.60	5,295		
30	1,355	3.50	3,245	4.70	5,485		

table is applicable only for open-channel conditions. It is based on 17 discharge measure- during 1904–5, and is well defined throughout.

Estimated monthly discharge of Jefferson River near Sappington, Mont., for 1905.

[Drainage area, 8,984 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inche
March 7-31	1,700	1,180	1,413	70,070	0.157	
April	2,005	1,125	1,578	93,900	.176	
May	1,555	978	1,214	74,650	.135	
June	5,485	1,180	3,206	190,800	.357	
July	3,605	798	1,665	102,400	.185	
August	978	498	658	40,460	.073	
September	600	465	536	31,890	.060	
October	1,180	600	814	50,050	.091	
November	1,625	978	1,346	80,090	.150	
The period				734,300		

NOTE.—No estimate for ice period.

MADISON RIVER (INCLUDING CHERRY CREEK) NEAR NORRIS, MONT.

This station was established May 2, 1897, when the old station at Three Forks was discontinued. The gage is situated at Black's ranch, 12 miles north of Norris and 25 miles west of Bozeman; the measuring section is located at the point where the river emerges from the canyon, about 4 miles above the gage.

The channel is curved both above and below the measuring section, but the bridge is at a right angle to the current. Both banks are high and rocky and do not overflow. The bed of the stream is rocky and the current is swift.

Discharge measurements are made from the lower side of the steel highway bridge. The initial point for soundings is at the left abutment.

The gage at Black's ranch, which is observed twice daily by Mrs. S. A. Black, is a vertical rod fastened to a post firmly set in the bed of the river at the right bank and braced with cross-pieces from the bank. It is about 125 yards west of the house of the observer. The gage is referred to bench marks as follows: (1) Top of large granite bowlder, marked with a spot of black paint, 20 feet south of the gage rod and 8 feet east of the river bank; elevation, 6.86 feet. (2) Top of white granite bowlder, marked with black paint, on the right bank 250 feet west of the gage; elevation, 8.82 feet. Elevations are above the zero of the gage.

Between the bridge and the gage, about 1½ miles above the latter, Cherry Creek enters the river from the right. In order to determine the total amount of water flowing past the gage measurements of this creek are always made when the river is measured, and the result added to that at the bridge above. The gaging station on Cherry Creek is at the wooden highway bridge 100 yards above its mouth.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Descripton: 99, p 130-131; 130, p 77.
Discharge: 99, p 131; 130, p 77.
Discharge, monthly: 99, p 132; 130, p 79.
Gage heights: 99, pp 131-132; 130, p 78.
Rating table: 99, p 132; 130, p 78.

Discharge measurements of Madison River (including Cherry Creek) near Norris, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.	Discharge (Cherry Creek included).
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*	*Sec.-ft.*
April 1	L. R. Stockman	216	376	3.54	1.32	1,330	1,346
May 2	J. H. Sloan	234	340	3.52	1.30	1,335	1,358
May 17	do	232	371	4.22	1.43	1,576	1,612
June 13	do	246	556	6.00	2.21	3,333	3,488
July 5	do	243	505	5.36	1.88	2,714	2,752
August 3	do	232	349	3.55	1.21	1,239	1,250
September 2	do	231	316	3.55	1.23	1,121	1,135
September 26	do	233	320	3.45	1.22	1,104	1,118
October 22	do	232	327	3.46	1.22	1,131	1,146
November 18	do	232	332	3.45	1.22	1,148	1,157

Daily gage height, in feet, of Madison River (including Cherry Creek) near Norris, Mont., for 1905.

	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1		1.4	1.4	1.85	1.9	1.25	1.2	1.2	1.2
2		1.4	1.4	1.95	1.9	1.25	1.2	1.2	1.2
3		1.4	1.4	2.2	2.0	1.25	1.2	1.2	1.2
4		1.4	1.4	2.2	2.0	1.25	1.2	1.2	1.2
5		1.4	1.4	2.3	2.0	1.25	1.2	1.2	1.2
6		1.4	1.4	2.34	2.0	1.25	1.2	1.2	1.2
7		1.4	1.4	2.3	2.0	1.25	1.2	1.2	1.2
8		1.4	1.4	2.3	2.0	1.28	1.2	1.2	1.2
9		1.4	1.45	2.3	2.0	1.3	1.2	1.2	1.2
10		1.4	1.5	2.3	1.6	1.3	1.2	1.2	1.2
11		1.4	1.5	2.3	1.05	1.3	1.22	1.2	1.2
12	1.3	1.4	1.45	2.3	1.15	1.3	1.25	1.2	1.2
13	1.3	1.4	1.45	2.25	1.35	1.3	1.25	1.2	1.2
14	1.4	1.4	1.45	2.2	1.5	1.3	1.25	1.2	1.2
15	1.4	1.4	1.45	2.2	1.5	1.25	1.25	1.2	1.2
16	1.4	1.4	1.5	2.2	1.4	1.2	1.25	1.2	1.2
17	1.4	1.4	1.55	2.2	1.4	1.2	1.25	1.2	1.2
18	1.4	1.4	1.6	2.1	1.4	1.2	1.25	1.2	1.2
19	1.4	1.4	1.65	2.05	1.4	1.2	1.25	1.2	1.2
20	1.4	1.4	1.65	2.0	1.35	1.2	1.25	1.2	1.2
21	1.4	1.4	1.65	1.9	1.35	1.2	1.25	1.2	1.2
22	1.4	1.4	1.3	1.9	1.35	1.2	1.25	1.2	1.2
23	1.4	1.4	1.25	1.9	1.3	1.2	1.25	1.2	1.2
24	1.4	1.4	1.2	1.9	1.3	1.2	1.25	1.2	1.2
25	1.4	1.4	1.2	1.9	1.3	1.2	1.25	1.2	1.2
26	1.4	1.4	1.2	1.8	1.22	1.2	1.25	1.2	.....
27	1.3	1.4	1.1	1.7	1.28	1.2	1.25	1.2	.....
28	1.3	1.4	1.1	1.6	1.3	1.2	1.25	1.2	.....
29	1.3	1.4	1.2	1.6	1.3	1.2	1.25	1.2	.....
30	1.3	1.4	1.5	1.8	1.25	1.2	1.25	1.2	.....
31	1.3	.....	1.6	.....	1.25	1.2	1.25	1.2	.....

NOTE.—River frozen January 1 to March 11 and November 26 to December 31, inclusive.

Station rating table for Madison River (including Cherry Creek), near Norris, Mont., from March 12 to November 25, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.10	900	1.50	1,770	1.80	2,500	2.10	3,275
1.20	1,100	1.60	2,000	1.90	2,750	2.20	3,550
1.30	1,320	1.70	2,250	2.00	3,000	2.30	3,850
1.40	1,540						

The above table is applicable only for open-channel conditions. It is based on 16 discharge measurements made during 1904–5 and is fairly well defined throughout.

Estimated monthly discharge of Madison River (including Cherry Creek), near Norris, Mont., for 1905.

[Drainage area, 2,085 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 12-31	1,540	1,320	1,463	58,040	0.702	0.822
April	1,540	1,540	1,540	91,640	.739	.824
May	2,125	900	1,570	96,540	.753	.868
June	3,974	2,000	3,195	190,100	1.53	1.71
July	3,000	800	1,844	113,400	.884	1.02
August	1,320	1,100	1,177	72,370	.565	.651
September	1,210	1,100	1,171	69,680	.562	.627
October	1,100	1,100	1,100	67,640	.528	.609
November 1-25	1,100	1,100	1,100	54,540	.528	.491
The period				814,000		

GALLATIN RIVER AT LOGAN, MONT.

Gallatin River is formed by two chief upper branches, known as East and West Gallatin rivers, which rise on the western slopes of the Gallatin Range and unite a few miles east of Logan, whence the main stream flows northward to its point of junction with Jefferson and Madison rivers near Three Forks, Mont.

A gaging station was established at Logan August 24, 1893. The present station is located 200 yards northwest of the Logan railroad depot.

The channel is straight for 200 feet above and below the station. The right bank is high and rocky. The left is comparatively low and might overflow in the highest floods. Both banks are covered with bushes. The bed of the stream is sandy, with a small amount of vegetation. There is but one channel at all stages, and the current is moderate.

Discharge measurements are made by means of a cable, car, tagged wire, and stay wire just below the gage. The initial point for soundings is at the left cable support.

During 1905 gage readings were taken once each day up to October 27 by N. A. Smith. After that date the gage was read by S. M. Kirkbridge. The original gage was a rod fastened to the cribbing at the intake pipe of the pump at the railroad pump house immediately below the old Northern Pacific Railway bridge; but this was washed out, together with the crib, March 10, 1894, before any discharge measurements had been made. [illegible] 1894, a new gage rod was installed under the north[illegible] ments of the river were thereafter made by mean[illegible] was replaced September 16, 1896, by a wire gag[illegible]

bridge in the east span. Bench mark No. 2 of this gage answered to the description of bench mark No. 1 of the previous gage. This gage was destroyed in April, 1901, when the old railroad bridge was being replaced. A temporary gage was established for the summer, and July 26, 1901, the datum of this gage was raised 1.23 feet. October 20, 1901, a new wire gage was established on the site of the present station, 150 yards upstream from the bridge, but the readings on this gage had no relation to those of the previous gages. April 16, 1905, the wire was replaced by a standard chain gage, but owing to unreliable descriptions of old bench marks there was probably a slight change in the gage datum at that time. The length of the chain from the end of the weight to the outside of the handle ring is 21.21 feet. The bench marks in present use are as follows: (1) A railroad spike in the west side of the rear post of the gage frame 3.6 feet from the top of the horizontal bar; elevation above the zero of the gage, 8.02 feet. (2) A point halfway down on the beveled edge at the top of the concrete just below the roller bearing on the northeast abutment of the Northern Pacific Railway bridge; elevation above the zero of the gage, 11.71 feet.

This station was discontinued December 31, 1905.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 18, iv, p 128–129; 19, iv, p 277; Bull 131, pp 16–17; 140, p 89; WS 15, p 68; 27, p 68; 36, pp 197–198; 49, p 262; 66, pp 17–18; 84, pp 38–39; 99, pp 123–124; 130, pp 82–83.

Discharge: Ann 18, iv, p 129; Bull 131, pp 17, 92; 140, p 90; WS 15, p 68; 27, p 74; 36, p 198; 49, p 262; 66, p 18; 84, p 39; 99, p 124; 130, p 84.

Discharge, monthly: Ann 18, iv, p 130; 19, iv, p 278; 20, iv, pp 234, 240; 22, iv, p 282; Bull 140, p 91; WS 75, p 116; 84, p 40; 99, p 126; 130, p 85.

Discharge, yearly: Ann 20, iv, p 53.

Gage heights: Bull 131, p 18; 140, p 90; WS 11, p 48; 15, p 68; 27, p 70; 36, p 198; 49, p 263; 66, p 18; 84, p 39; 99, pp 124–125; 130, p 84.

Hydrographs: Ann 18, iv, p 130; 19, iv, p 278; 20, iv, p 240; 22, iv, p 282.

Rainfall and run-off relation: Ann 20, iv, p 235; WS 75, p 118.

Rating tables: Ann 18, iv, p 129; 19, iv, p 277; Bull 140, p 90; WS 27, p 75; 52, p 516; 84, p 40; 99, p 125; 130, p 85.

Discharge measurements of Gallatin River at Logan, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 3	L. R. Stockman	138	380	1.42	1.20	540
May 4	J. H. Sloan		397	1.55	1.35	614
May 19	do		508	2.21	1.94	1,125
June 14	do	150	670	3.64	2.70	2,438
July 8	do	140	340	1.04	.68	353
August 5	do	130	272	.73	.40	200
September 7	do	130	299	.78	.70	235
September 21	do	130	303	.87	.77	263
October 20	do	142	375	1.47	1.28	552
October 27	H. M. Morse	142	392	1.57	1.41	614
November 16	J. H. Sloan	143	391	1.60	1.42	623

Daily gage height, in feet, of Gallatin River at Logan, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	2.85	1.2	1.45	.....	1.3	2.1	2.5	0.4	0.6	1.1	1.3	
2	2.55	1.15	1.45	.....	1.3	2.4	2.6	.3	.6	1.1	1.4	
3	2.4	1.5	1.4	.....	1.3	2.65	2.45	.4	.6	1.1	1.5	
4	1.85	3.9	1.4	.....	1.3	2.7	[a]2.35	.4	.6	1.1	1.5	
5	1.6	3.9	1.4	1.2	1.3	3.1	2.25	.4	.6	1.1	1.4	
6	1.5	3.9	1.4	1.15	1.3	3.0	1.8	[a]4	.7	1.1	1.4	
7	1.6	3.9	1.4	1.1	1.25	2.9	1.3	.4	.7	1.1	1.4	
8	1.8	3.9	1.4	1.1	1.25	2.85	.8	.4	.7	1.1	1.4	
9	1.8	3.9	1.35	1.2	1.4	3.25	.6	.45	.7	1.1	1.4	
10	1.6	3.9	1.35	1.3	1.7	3.25	.5	.5	.7	1.15	1.4	
11	1.5	3.9	1.35	1.3	1.65	3.0	[a].45	.5	.7	[a]1.18	1.4	
12	1.5	3.8	1.35	1.3	1.6	2.9	.4	.6	.65	1.2	1.4	
13	1.5	3.8	1.35	1.2	1.5	2.8	.4	.6	[a].65	1.2	1.4	
14	1.5	3.85	1.35	1.2	1.35	2.7	.4	.6	.65	1.2	1.4	
15	1.8	3.85	1.35	1.25	1.35	2.6	.45	.6	.65	1.2	1.4	
16	2.0	3.85	1.35	1.25	1.4	2.5	.45	.6	.7	1.2	1.4	
17	2.2	3.85	1.4	1.3	1.35	2.5	.4	.7	.65	1.2	1.4	
18	1.8	3.85	1.4	1.25	1.7	2.6	.4	.7	.7	1.2	1.4	
19	1.8	3.85	1.35	1.25	1.8	2.8	.4	.7	.75	1.25	1.4	
20	1.7	3.9	1.35	1.25	1.85	2.9	.4	.7	.8	1.25	1.4	
21	1.5	3.9	1.35	1.25	1.9	2.0	.35	.7	.8	1.25	1.5	
22	1.5	3.85	1.35	1.2	2.0	2.1	.3	.6	.8	1.3	1.4	
23	1.5	3.8	1.3	1.25	1.9	2.2	.3	.6	.8	1.3	1.4	
24	1.45	3.7	1.3	1.25	1.8	2.3	.4	.7	.8	1.4	1.4	
25	1.45	3.0	1.3	1.3	1.7	2.4	.4	.7	.8	1.4	1.4	
26	1.4	2.0	.....	1.3	1.7	2.55	.4	.7	.85	1.4	1.5	
27	1.4	1.55	.....	1.3	1.75	2.4	.4	.6	.9	1.4	1.5	
28	1.4	1.5	.....	1.3	2.65	2.3	.4	.6	.95	1.4	1.5	
29	1.4	.....	.....	1.3	2.65	2.1	.4	.6	1.0	1.3	1.2	
30	1.3	.....	.....	1.3	2.9	2.25	.4	.6	1.1	1.3	2.1	
31	1.25	.....	.....	.....	2.7	.....	.4	.6	.....	1.2	.....	

[a] Gage heights interpolated.

NOTE.—January 1-10, ice gorge below station; also February 4-26, inclusive. January 30 to Febru 3, inclusive, December 28-31, inclusive; readings to top of ice; drift ice floating in the river. Novem 29 to December 27, inclusive, ice floating in the river and probably gorge below for part of the ti River open January 11-29 and February 27 to November 28, inclusive. Gage destroyed March replaced April 4.

Station rating table for Gallatin River at Logan, Mont., from January 1, 1904, to Decem 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.30	178	1.30	545	2.20	1,210	3.20	2,205
.40	192	1.40	605	2.30	1,300	3.40	2,445
.50	210	1.50	670	2.40	1,390	3.60	2,685
.60	230	1.60	740	2.50	1,480	3.80	2,950
.70	260	1.70	810	2.60	1,570	4.00	3,240
.80	300	1.80	880	2.70	1,670	4.20	3,540
.90	340	1.90	955	2.80	1,770	4.40	3,870
1.00	385	2.00	1,035	2.90	1,870	4.60	4,230
1.10	435	2.10	1,120	3.00	1,980	4.80	4,620
1.20	485						

The above table is applicable only for open-channel conditions. It is based on discharge measurem made during 1904-5, and is not well defined.

Estimated monthly discharge of Gallatin River at Logan, Mont., for 1905.

[Drainage area, 1,805 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January 11-29	1,210	605	741	27,930	0.411	0.290
March 1-25	635	545	586	29,060	.324	.302
April 5-30	545	435	512	26,400	.284	.275
May	1,870	515	836	51,400	.463	.534
June	2,265	1,035	1,592	94,730	.882	.984
July	1,570	178	428	26,320	.237	.273
August	260	178	225	13,840	.125	.144
September	435	230	279	16,600	.155	.173
October	605	435	499	30,680	.276	.318
November 1-28	670	545	617	34,270	.342	.356
The period				351,200		

NOTE.—No estimate for ice period.

WEST GALLATIN RIVER NEAR SALESVILLE, MONT.

West Gallatin River joins the East Gallatin a few miles east of Logan, Mont.

The gaging station was established in July, 1895. It is located at the Williams highway bridge, 16 miles southwest of Bozeman, Mont., from which point it is reached by driving. The nearest post-office is Salesville, 4 miles below the station.

The channel is nearly straight, with slight curves above and below the station. The banks are high and not liable to overflow. The bed of the stream is composed of bowlders and is fairly permanent. At flood stages water flows behind the bridge abutment near the right bank; at other times it is all confined in one channel. The bridge is not quite at a right angle to the direction of the current. During high water discharge measurements are frequently rendered impossible by the logs and ties which are floated down the river from the canyon to the Northern Pacific Railway. On account of the velocity of the current a stay wire is needed for the meter at nearly all stages of the river.

Discharge measurements are made from the lower side of the highway bridge. The initial point for soundings is on the guard rail over the left pier.

The gage was read until June 30, 1905, by Mrs. Alvin DeLong, who lived near the bridge; on that date gage readings were discontinued on account of difficulty in procuring an observer. The gage record was begun August 1, 1895. The gage first installed was a rod firmly spiked to a tree above the bridge, near the right bank. May 31, 1896, the datum was lowered 5 feet, and the rod was regraduated so as to correspond to the new datum. This gage is still in place, and is frequently used at high stages, as it stands in less turbulent water. In September, 1896, a wire gage was placed on the upstream side of the bridge and made to read the same as the rod gage. This was replaced April 20, 1904, by a standard chain gage, approximately the same datum being maintained. The present chain length is 17.43 feet. August 22, 1904, the rod gage was found to read 0.16 foot low as compared with the chain-gage datum. The new gage is referred to bench marks as follows: (1) The head of the westernmost rivet holding the angle irons on the top of the southwest cylindrical pier; elevation, 13.86 feet. (2) A large bowlder firmly set in the ground on the south side of the wagon road near the fence and 123 feet east of the southeast pier; elevation, 13.69 feet. Elevations are above the datum of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 14, ii, p 101; 18, iv, p 124; 19, iv, p 275; Bull 140, pp 86–87; WS 15, p 66; 27, p 68; 36, pp 195–196; 49, pp 260–261; 66, pp 16–17; 84, pp 40–41; 99, pp 126–127; 130, pp 79–80.

Discharge: Ann 18, iv, p 125; Bull 131, p 90; 140, p 86; WS 15, p 66; 27, pp 68, 74; 36, p 196; 49, p 261; 66, p 17; 84, p 41; 99, p 127; 130, p 80.

Discharge, monthly: Ann 14, ii, p 102; 18, iv, p 126; 19, iv, p 276; 20, iv, pp 234, 241; 21, iv, p 184; 22, iv, p 280; Bull 140, p 88; WS 75, pp 117, 118; 84, p 43; 99, p 129; 130, p 82.

Discharge, yearly: Ann 20, iv, p 52.

Gage heights: Bull 140, p 87; WS 11, p 47; 15, p 66; 27, p 69; 36, p 196; 49, p 261; 66, p 17; 84, p 42; 99, pp 127–128; 130, p 81.

Hydrographs: Ann 18, iv, p 126; 19, iv, p 277; 20, iv, p 241; 21, iv, p 185; 22, iv, p 281; WS 75, p 119.

Rainfall and run-off relation: Ann 20, iv, p 235; WS 75, p 118.

Rating tables: Ann 18, iv, p 125; 19, iv, p 276; Bull 140, p 87; WS 27, p 75; 39, p 446; 52, p 516; 66, p 170; 84, p 42; 99, p 128; 130, p 81.

Discharge measurements of West Gallatin River near Salesville, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 31	L. R. Stockman	83	183	1.88	2.90	343
May 1	J. H. Sloan	87	217	2.48	3.30	538
May 17	.....do	90	234	3.06	3.59	716
June 12	.....do	130	416	6.45	5.30	2,681
August 2	.....do	87	201	2.30	3.10	463
September 1	.....do	85	181	2.15	2.95	390
September 25	.....do	83	178	1.92	2.96	343
October 21	.....do	86	196	2.23	3.05	438
November 17	.....do	85	190	2.24	3.04	425

Daily gage height, in feet, of West Gallatin River near Salesville, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	Aug.	Sept.	Oct.	Nov.
	2.8	2.9	2.9	2.8	3.4	4.6	.....	2.95	.....	.....
	2.9	2.9	2.9	2.9	3.2	4.9	3.10	.....	.....	.....
	2.9	2.9	2.9	2.9	3.2	5.1	.....	.....	.....	.....
	2.9	2.9	2.9	2.9	3.1	5.2	.....	.....	.....	.....
	3.0	2.9	2.9	2.9	3.1	5.2	.....	.....	.....	.....
	3.0	3.0	2.9	2.9	3.1	5.1	.....	.....	.....	.....
	3.0	3.0	2.9	2.9	3.1	5.1	.....	.....	.....	.....
	2.9	3.0	2.9	2.9	3.4	5.3	.....	.....	.....	.....
	2.9	3.0	2.9	2.9	3.5	4.9	.....	.....	.....	.....
	3.0	3.0	3.0	2.9	3.3	4.8	.....	.....	.....	.....
	2.8	3.0	3.0	2.9	3.2	5.2	.....	.....	.....	.....
	2.8	3.0	3.0	2.9	3.2	5.3	.....	.....	.....	.....
	2.9	3.0	3.0	3.0	3.2	5.3	.....	.....	.....	.....
4	2.9	3.1	3.0	3.0	3.3	5.3	.....	.....	.....	.....
5	2.9	3.1	2.9	3.0	3.3	5.3	.....	.....	.....	.....
6	2.9	3.2	2.9	3.0	3.3	5.2	.....	.....	.....	.....
7	2.9	3.4	2.9	3.0	3.4	5.2	.....	.....	.....	3.04
8	2.9	3.5	2.9	3.1	3.6	5.0	.....	.....	.....	.....
9	2.9	3.3	2.9	3.1	3.9	4.8	.....	.....	.....	.....
10	2.9	3.3	2.9	3.1	3.7	4.4	.....	.....	.....	.....
11	2.9	3.1	2.8	3.1	3.7	4.5	.....	.....	3.05	.....
12	2.9	3.0	2.8	3.1	3.8	4.8	.....	.....	.....	.....
13	2.9	3.0	2.9	3.1	3.8	4.8	.....	.....	.....	.....
14	2.9	2.9	2.9	3.1	3.8	4.9	.....	.....	.....	.....
15	2.9	2.9	2.9	3.2	3.8	4.7	.....	.....	.....	.....
16	2.9	2.9	2.9	3.4	3.8	4.7	.....	2.96	.....	.....
17	2.9	2.9	2.9	3.4	3.7	4.8	.....	.....	.....	.....
18	2.9	2.9	2.9	3.3	3.7	4.6	.....	.....	.....	.....
19	2.9	.....	2.9	3.2	3.7	4.4	.....	.....	.....	.....
20	2.9	.....	2.8	3.2	3.9	4.4	.....	.....	.....	.....
21	2.9	.....	2.8	.....	4.2	.....	.....	.....	.....	.....

NOTE.—No observer July 1 to December 31, inclusive. Open-channel conditions assumed during winter months. Gage heights interpolated March 1–4, inclusive, and April 8.

Station rating table for West Gallatin River near Salesville, Mont., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.80	310	3.50	670	4.20	1,265	4.90	2,105
2.90	350	3.60	740	4.30	1,370	5.00	2,245
3.00	395	3.70	815	4.40	1,480	5.10	2,390
3.10	440	3.80	895	4.50	1,595	5.20	2,545
3.20	490	3.90	980	4.60	1,715	5.30	2,700
3.30	545	4.00	1,070	4.70	1,840	5.40	2,865
3.40	605	4.10	1,165	4.80	1,970	5.50	3,040

The above table is applicable only for open-channel conditions. It is based on 16 discharge measurements made during 1904–5, and is fairly well defined between gage heights 3 feet and 5 feet.

Estimated monthly discharge of West Gallatin River near Salesville, Mont., for 1905.

[Drainage area, 860 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	395	310	352	21,640	0.409	0.472
February	670	350	415	23,050	.483	.503
March	395	310	352	21,640	.409	.472
April	605	310	415	24,690	.483	.539
May	1,265	440	690	42,430	.802	.925
June	2,700	1,480	2,155	128,200	2.51	2.80
The period				261,600		

MISSOURI RIVER AT CASCADE, MONT.

This station was established July 20, 1902. It is located at the highway bridge at the east end of the town of Cascade, Mont., about one-fourth mile from the railroad.

The channel is straight 600 feet above the station to the island in the center of the stream another island, 200 feet below the bridge, divides the river into two channels and causes a rather sudden change in the direction of the current. A fall of about 1 foot at this island produces rapids in the river below the station. The left bank is high, but the right may overflow at extreme flood stages. The central pier of the bridge is protected by an ice breaker, which extends about 125 feet upstream and has considerable effect on the current to the left, especially in low water.

Discharge measurements are made from the upstream side of the bridge. The initial point for soundings is near the left bank; it is a notch on the guard rail 2 feet to the left of the center of the southwest pier.

A standard chain gage, which is read twice each day by H. W. Ludwig, has replaced the chain gage first installed. It is located on the upstream side of the left span and is fastened to the floor of the bridge. The length of the chain is 31.99 feet. The gage is referred to bench marks as follows: (1) The top of an old iron bolt which secures the bed plate on the southwest iron bridge pier; it is painted in black "U.S.G.S.B.M." and has an elevation of 28.54 feet above gage datum. (2) A standard iron bench mark of the Missouri River Commission, situated 200 feet south of the Great Northern Railway station; elevation above the zero of the gage, 36.58 feet.

Information in regard to this station is contained in the following Water-Supply Paper of the United States Geological Survey:

Description: 84, p 35; 99, p 117; 130, p 72.
Discharge: 84, p 35; 99, p 117; 130, p 73.
Discharge, monthly: 99, p 119; 130, p 74.
Gage heights: 84, p 36; 99, p 118; 130, p 73.
Rating table: 99, p 118; 130, p 74.

Discharge measurements of Missouri River at Cascade, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 5	L. R. Stockman	349	2,537	1.37	4.20	3,484
May 12	H. M. Morse	.....	2,643	1.77	4.59	4,696
June 13	do	371	3,355	2.88	6.44	9,669
July 12	W. B. Freeman	356	2,618	1.53	4.60	4,013
August 8	H. M. Morse	348	2,443	.72	3.74	1,769
September 12	W. B. Freeman	350	2,253	.91	3.58	2,043
November 21	do	354	2,525	1.35	4.31	3,412

Daily gage height, in feet, of Missouri River at Cascade, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	4.6	4.1	4.55	4.4	4.6	4.6	6.55	4.1	3.6	3.3	3.95	5.5
2	4.6	4.1	4.45	4.4	4.6	4.6	6.35	4.05	3.6	3.3	4.0	5.5
3	4.6	4.1	4.35	4.4	4.6	4.65	6.15	3.98	3.6	3.3	4.0	5.5
4	4.6	4.2	4.3	4.38	4.5	4.72	5.9	3.88	3.6	3.3	4.0	5.5
5	4.6	4.2	4.3	4.35	4.5	4.8	5.8	3.85	3.6	3.3	4.0	5.5
6	4.6	4.2	4.4	4.3	4.5	5.15	5.75	3.75	3.6	3.4	4.05	5.5
7	4.6	4.2	4.4	4.3	4.5	5.95	5.45	3.75	3.6	3.4	4.08	5.5
8	4.6	4.2	4.4	4.25	4.5	6.22	5.32	3.75	3.6	3.4	4.1	5.5
9	4.6	4.3	4.5	4.2	4.5	6.45	5.25	3.75	3.6	3.4	4.15	5.5
10	4.7	4.3	4.5	4.2	4.5	6.6	5.2	3.75	3.6	3.4	4.18	5.4
11	4.7	4.3	4.5	4.2	4.5	6.6	4.75	3.75	3.6	3.45	4.2	5.3
12	4.8	4.28	4.5	4.25	4.6	6.58	4.58	3.75	3.6	3.5	4.2	5.2
13	4.8	4.32	4.5	4.28	4.65	6.45	4.5	3.75	3.6	3.6	4.2	4.95
14	4.8	5.25	4.5	4.3	4.55	6.4	4.48	3.75	3.6	3.6	4.2	4.75
15	4.8	5.75	4.5	4.35	4.65	6.65	4.38	3.75	3.6	3.63	4.23	4.65
16	4.8	5.9	4.5	4.4	4.65	6.6	4.3	3.78	3.6	3.7	4.25	4.55
17	4.7	5.92	4.5	4.4	4.7	6.55	4.25	3.65	3.6	3.75	4.25	4.5
18	4.7	5.95	4.5	4.45	4.7	6.35	4.2	3.5	3.55	3.8	4.28	4.6
19	4.6	5.95	4.5	4.45	4.68	6.2	4.12	3.5	3.52	3.85	4.3	4.6
20	4.6	5.95	4.5	4.48	4.65	6.15	4.05	3.5	3.5	3.87	4.3	4.7
21	4.5	5.72	4.5	4.5	4.62	5.98	4.0	3.5	3.45	3.9	4.3	4.7
22	4.5	5.55	4.5	4.5	4.6	5.88	4.0	3.45	3.42	3.9	4.35	4.7
23	4.4	5.3	4.5	4.5	4.58	5.75	3.95	3.45	3.4	3.9	4.35	4.7
24	4.4	5.05	4.5	4.55	4.52	5.5	3.95	3.45	3.4	3.9	4.4	4.7
25	4.3	4.9	4.5	4.6	4.48	5.25	3.95	3.48	3.4	3.9	4.43	4.7
26	4.3	4.85	4.5	4.6	4.42	5.12	4.05	3.52	3.4	3.9	4.48	4.7
27	4.2	4.75	4.5	4.65	4.35	6.28	4.0	3.55	3.3	3.9	4.55	4.7
28	4.2	4.65	4.5	4.7	4.38	6.42	4.0	3.4	3.3	3.95	4.75	4.7
29	4.1	.....	4.45	4.7	4.45	6.55	3.95	3.5	3.3	3.95	5.5	4.7
30	4.1	.....	4.45	4.7	4.5	6.65	4.0	3.5	3.3	3.95	5.5	4.7
31	4.1	.....	4.4	.....	4.55	.....	4.0	3.6	.....	3.95	.....	4.7

NOTE.—River frozen and readings taken to the surface of the ice January 1 to February 28, inclusive, and November 28 to December 19, inclusive.

Station rating table for Missouri River at Cascade, Mont., from January 1 to Decemb 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
3.30	1,720	4.20	3,120	5.10	5,500	6.00	8,260
3.40	1,800	4.30	3,340	5.20	5,800	6.10	8,580
3.50	1,900	4.40	3,560	5.30	6,100	6.20	8,900
3.60	2,020	4.50	3,800	5.40	6,400	6.30	9,220
3.70	2,160	4.60	4,060	5.50	6,700	6.40	9,560
3.80	2,320	4.70	4,320	5.60	7,000	6.50	9,900
3.90	2,500	4.80	4,600	5.70	7,300	6.60	10,240
4.00	2,700	4.90	4,900	5.80	7,620		
4.10	2,900	5.00	5,200	5.90	7,940		

The above table is applicable only for open channel conditions. It is based on 15 discharge me ments made during 1904–5, and is well defined between gage heights 3.5 feet and 6.5 feet.

Estimated monthly discharge of Missouri River at Cascade, Mont., for 1905.

[Drainage area, 18,295 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	De in
March	3,930	3,340	3,721	228,800	0.203	
April	4,320	3,120	3,635	216,300	.199	
May	4,320	3,450	3,944	242,500	.216	
June	10,410	4,060	8,081	480,900	.442	
July	10,070	2,600	4,518	277,800	.247	
August	2,900	1,800	2,147	132,000	.117	
September	2,020	1,720	1,929	114,800	.105	
October	2,600	1,720	2,159	132,800	.118	
November 1–27	3,930	2,600	3,158	169,100	.173	
The period				1,995,000		

MISSOURI RIVER AT GREAT FALLS, MONT.

The flow of Missouri River at Great Falls, Mont., is divided into four parts:

1. Water flowing over Black Eagle Falls dam.
2. Water leaking through the dam.
3. Water used on the north side of the river by the Boston and Montana smelter.
4. Water used on the south side of the river by the electric light and power compan the Royal Milling Company.

Black Eagle Falls dam was begun April 15, 1890, and completed March 15, 1891.[a] total cost of the dam from the inception of the enterprise to November 30, 1891, was $17 Originally the crest of the dam stood 40 feet above the surface of the water below the f the tailrace; but September 1, 1904, additional flashboards were erected, and the cre since been 41 feet above the water in the tailrace. The original elevation of the flashb on the crest was 3,282.05 feet above sea level. The present elevation is 3,282.18 f wooden crest was sharp, but is now slightly worn b[illegible] f[illegible] Th[illegible] is 745 feet. The amount of water flowing over weir.

[a] Parker, M. S., Black Eagle Falls d[illegible]

ın and Montana smelter has a gage above the dam which is read four times daily. ıce between gage readings and the elevation of the crest gives the head on the ɔrds of gage heights have been kept since April 13, 1897. The zero of the gage ı elevation of 3,200 feet above sea level.

ɔ, 1905, the water leaking through the dam was measured and found to be 72 The water was low at the time (gage height, 3,280.80 feet), and it is probable :er head would increase the amount of leakage.

r power is owned by the Great Falls Water Power and Townsite Company and ıarious corporations. A record is kept of the horsepower developed, the compu- ıg based on gate openings and heads, using an efficiency of 80 per cent for the From the monthly average of horsepower and head computation has been made hly average of water used by the Boston and Montana smelter from 1897 to 1905, ılts are shown in the accompanying table.

ıuth side of the river the Royal Milling Company pays for 300 horsepower deliv- top of the bank. No regular record is kept of the amount of water used, but ests are made to determine whether the required horsepower is developed. The t and power company contracts for 1,000 horsepower, and as it is used for light- ction purposes the required amount is constantly changing and hourly records The average total horsepower used on the south side of the river is 1,300. Based ıncy of 80 per cent and a head of 41 feet, the flow required to develop this power ıd-feet.

ɔximate idea of the quantity of water in the Missouri at Great Falls could be r combining the various parts noted above.

Missouri River used by Boston and Montana smelter at Great Falls, Mont., 1897–1905.

nth.	Second-feet.	Acre-feet.	Month.	Second-feet.	Acre-feet.
ɔ97.			1899.		
.....	1,400	83,310	January	1,764	108,500
.....	1,343	82,580	February	1,795	99,690
.....	1,359	83,560	March	1,804	110,900
.....	1,484	88,300	April	1,763	104,900
.....	1,469	90,310	May	1,783	109,600
.....	1,462	87,000	June	1,792	106,600
.....	1,441	88,600	July	1,803	110,900
			August	1,838	113,000
ɔiod.....	.....	603,700	September	1,791	106,600
			October	1,684	103,500
ɔ98.			November	1,839	109,400
.....	1,531	94,140	December	1,831	112,600
.....	1,332	73,980			
.....	953	58,600	The year	1,791	1,296,000
.....	984	58,550			
.....	1,277	78,520	1900.		
.....	1,530	91,040	January	1,760	108,200
.....	1,449	89,100	February	1,839	102,100
.....	1,729	106,300	March	1,881	115,700
.....	1,663	98,960	April	1,884	112,100
.....	1,711	105,200	May	1,722	105,900
.....	1,711	101,800	June	1,832	109,000
.....	1,753	107,800	July	1,844	113,400
			August	1,898	116,700
ır.....	1,469	1,064,000	September	1,786	106,300
			October	1,752	107,700

Water from Missouri River used by Boston and Montana smelter at Great Falls, Mont., 1897–1905—Continued.

Month.	Second feet.	Acre-feet.
1900—Continued.		
November	1,708	101,600
December	1,849	113,700
The year	1,813	1,312,000
1901.		
January	1,375	84,550
February	1,579	87,690
March	1,688	103,800
April	2,028	120,700
May	2,077	127,700
June	2,121	126,200
July	1,983	121,900
August	1,874	115,200
September	1,806	107,500
October 1–24	1,773	84,400
The period	.....	1,080,000
1902.		
January 13–31	1,355	51,070
February	1,780	98,860
March	2,202	135,400
April	2,222	132,200
May	2,226	136,900
June	2,375	141,300
July	2,243	137,900
August	1,980	121,800
September	1,782	106,000
October	2,161	132,900
November	2,020	120,200
December	1,794	110,300
The period	.....	1,425,000
1903.		
January	2,200	135,300
February	1,962	109,000
March	2,087	128,300
April	2,239	133,200
May	2,128	130,800
June	2,196	130,700
July	2,252	138,500
August	2,216	136,300
September	1,707	101,600
October	1,912	117,600
November	1,183	70,390
December	2,036	125,200
The year	2,010	1,457,000
1904.		
January	2,016	124,000
February	1,953	112,300
March	2,216	136,300
April	2,321	138,100
May	2,341	143,900
June	2,114	125,800
July	2,225	136,800
August	2,153	132,400
September	1,737	103,400
October	2,143	131,800
November	2,109	130,800
December	2,027	124,600
The year	2,120	1,540,000
1905.		
January	1,955	120,200
February	1,882	104,500
March	2,304	141,700
April	2,297	136,700
May	2,243	137,900
June	2,300	136,800
July	2,231	137,200
August	1,669	102,600
September	1,214	72,240
October	1,402	86,200
The period	.....	1,176,000

MISSOURI RIVER NEAR WILLISTON, N. DAK.

This station was established April 24, 1905. It is located at Bakers Ferry, 10 miles down the river from Williston, N. Dak., and 13½ miles southeast by the main traveled road on the east side of the river from Williston ferry landing.

The channel is straight for about ,750 feet both above and below the station. The right bank consists of stiff clay and rises to an elevation of 25 feet above gage zero; the left bank is composed of loose sand and slopes upward to an elevation of 22 feet above gage zero; neither bank is subject to overflow The bed of he stream is of sand and is shifting.

Discharge measurements are made from a cable ferry boat. The initial point for soundings is the face of the cut bank on the right shore.

A standard chain gage, which was read during 1905 by George E. Baker, is located on a projecting timber extendi the bank of the river. The length of the chain

e end of the weight to the marker is 37.80 feet. The gage is referred to bench marks rs: (1) An aluminum tablet set in the top of a 6 by 6 inch square post about 20 feet the gage; elevation, 26.92 feet. (2) A cross of staples in the flat top of a large post, gh, about 3 rods southeast of the gage and 2 feet northwest of the supporting pole at end of the ferry cable; elevation, 30.00 feet. Elevations are above the datum of

Discharge measurements of Missouri River near Williston, N. Dak., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	Chandler and Richards.....	507	4,543	2.78	6.58	12,640
.....	E. F. Chandler.....	525	4,480	2.32	5.26	10,390
.....	P. M. Churchill.....	787	13,280	5.24	12 20	69,510
.....	.....do.....	770	11,710	4.95	11.10	58,030
.....	.....do.....	753	5,925	2.51	6.70	14,880
19..	Chandler and Fellows.....	435	2,705	2.51	4.41	6,781

ily gage height, in feet, of Missouri River near Williston, N. Dak., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	.....	9.3	12.1	9.8	4.9	4.9	5.0
.....	.....	9.4	12.6	9.0	4.8	4.8	5.0
.....	.....	10.4	12.3	9.5	4.9	5.1	5.2
.....	.....	11.0	12.0	9.8	4.9	5.6	5.2
.....	.....	11.3	12.6	9.1	4.9	5.3	5.1
.....	.....	11.8	11.9	9.1	4.9	5.0	4.9
.....	.....	13.0	11.6	8.8	4.9	5.5	4.9
.....	.....	13.6	11.5	8.2	4.8	5.2	4.9
.....	.....	13.2	11.2	7.9	4.8	4.9	4.9
.....	.....	13.2	11.1	7.8	4.8	4.5	5.0
.....	.....	12.9	11.2	7.5	4.7	4.5	5.0
.....	.....	13.5	11.2	7.3	4.7	4.4	5.1
.....	.....	13.4	11.1	7.1	4.7	4.3	5.0
.....	.....	12.8	11.1	6.8	4.6	4.3	5.0
.....	.....	12.4	11.0	6.7	4.6	4.2	5.0
.....	.....	12.4	11.1	6.5	4.6	4.2	5.1
.....	.....	12.9	11.0	6.4	4.6	4.4	5.0
.....	.....	12.8	11.0	6.5	4.5	4.4	5.0
.....	.....	12.5	11.2	6.3	4.4	4.5	4.9
.....	.....	12.3	11.0	6.1	4.4	4.7	4.9
.....	.....	12.2	10.6	6.0	4.4	4.8	4.9
.....	.....	12.3	10.2	5.9	4.4	4.9	5.0
.....	6.7	11.8	9.9	5.8	4.3	4.9	5.0
.....	7.6	11.5	9.8	5.7	4.3	4.9	5.0
.....	8.0	11.5	9.4	5.5	4.2	5.0	4.9
.....	7.9	11.8	9.0	5.4	4.1	5.0	5.0
.....	8.4	12.2	8.9	5.3	4.0	5.0	5.1
.....	9.3	12.1	8.9	5.2	4.0	4.9	[a] 2.1
.....	9.5	11.8	9.2	5.1	4.0	4.9	4.6
.....	9.3	11.9	9.5	5.0	4.0	4.9	4.9
.....	9.2	.....	10.9	4.9	.....	4.9	.....

[a] Ice gorge above held water back.

iver frozen over November 30.

MISSOURI RIVER AT WASHBURN, N. DAK.

This station was established June 28, 1905, and was discontinued November 30, 1
A record of river stages only was desired, and no discharge measurements were made. staff gage is attached to the piling foundation of the "Soo" Railroad grain elevator on left bank of the river. During 1905 the gage was read by Charles W. Blunt. Bench m were established as follows: (1) A horizontal line of brass-head nails and spikes driven the pile to which the gage is fastened; elevation, 14.00 feet. (2) A similar line of r driven into the pile at the east end of the retaining wall below the elevator; elevation, 1 feet. Elevations refer to the datum of the gage.

Daily gage height, in feet, of Missouri River near Washburn, N. Dak., for 1905.

Day.	June.	July.	Aug.	Sept.	Oct.	Nov.	Day.	June.	July.	Aug.	Sept.	Oct.
1	.....	8.65	6.35	3.9	3.0	3.3	17	.....	7.8	5.1	3.55	2.9
2	.....	8.9	7.0	3.9	3.0	3.05	18	.....	7.75	5.05	3.5	2.9
3	.....	9.25	7.35	3.8	3.0	3.1	19	.....	7.75	4.9	3.45	2.85
4	.....	9.45	6.85	3.8	3.0	3.0	20	.....	7.45	4.9	3.4	2.8
5	.....	9.05	6.65	3.8	3.0	3.0	21	.....	7.4	4.9	3.35	2.8
6	.....	9.2	6.65	3.8	3.0	3.1	22	.....	7.45	4.9	3.25	2.8
7	.....	9.3	6.7	3.75	3.0	3.15	23	.....	7.3	4.7	3.2	2.9
8	.....	9.1	6.55	3.6	3.0	3.2	24	.....	7.25	4.5	3.15	2.9
9	.....	8.95	6.45	3.6	3.25	3.2	25	.....	7.05	4.45	3.1	2.95
10	.....	8.75	6.1	3.6	3.35	3.1	26	.....	6.9	4.4	3.05	3.0
11	.....	8.65	5.85	3.6	3.5	3.1	27	.....	6.85	4.3	3.0	3.0
12	.....	8.55	5.7	3.6	3.45	3.1	28	9.05	6.65	4.3	3.0	3.05
13	.....	8.4	5.55	3.6	3.2	3.0	29	8.95	6.5	4.25	3.0	3.1
14	.....	8.25	5.35	3.6	3.15	3.0	30	8.55	6.45	4.15	3.0	3.05
15	.....	8.05	5.4	3.6	3.0	3.0	31	.....	6.3	4.0	.....	3.2
16	.....	7.85	5.3	3.6	2.95	3.0						

MISSOURI RIVER NEAR BISMARCK, N. DAK.

This station was established September 28, 1904. It is located near the town of marck, N. Dak.

The channel is straight for one-half mile both above and below the station. The r bank is high and not subject to overflow; the left bank consists of sandy slopes and woo bottoms and is overflowed at extreme flood stages. The bed is sandy and shifts consi ably. At ordinary stages the velocity of the current is moderate.

Discharge measurements are made by means of a cable ferryboat at Fort Lincoln fe about 5 miles southwest of Bismarck. The initial point for soundings is the face of perpendicular bank on the right side of the river. Distances from the initial point obtained by stadia sights from the boat on rods placed on each shore.

A braided-wire gage, which was read during 1905 by Mrs. J. S. Plants, is located on Northern Pacific Railway bridge, about 2 miles west of Bismarck, near the middle of second span of the bridge from the left bank. The bench mark is the top of the raili track on the Northern Pacific Railway bridge at the gage; elevation above the datu the gage, 73.90 feet. The zero of the gage is 1,617.9 feet above sea level.

Information in regard to this station is contained in Water-Supply Paper No. 130, of United States Geological Survey, page 76.

ischarge measurements of Missouri River near Bismarck, N. Dak., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	Chandler and Richards	848	9,400	5.23	6.80	49,200
.....	.....do	808	9,035	5.45	6.70	49,220
.....	R. Richards	820	7,592	3.81	4.20	28,940
.....	.....do	780	4,144	3.20	1.30	13,250
.....	E. F. Chandler	715	2,903	2.77	—.60	8,042

ily gage height, in feet, of Missouri River near Bismarck, N. Dak., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec
.....	3.8	1.6	2.5	0.8	0.2	3.35	6.8	3.65	0.9	—0.9	—0.3	—0.9
.....	3.6	2.0	2.5	.8	.2	3.9	6.95	4.0	.7	— .9	— .6	— .6
.....	3.4	2.2	2.7	.8	.4	3.9	7.4	4.65	.6	— .9	— .25	— .6
.....	3.4	2.2	2.8	.8	.4	3.7	7.8	4.8	.5	— .9	— .4	— .3
.....	3.2	2.5	2.95	.8	.1	3.8	7.75	4.45	.5	— .9	— .5	— .7
.....	3.05	2.6	3.2	.8	.2	4.35	7.4	4.1	.4	— .9	— .5	— .7
.....	2.75	2.6	3.45	.7	.2	4.8	7.4	4.15	.3	— .8	— .2	— .5
.....	2.5	2.6	3.65	.6	.25	5.9	7.15	4.25	.3	— .2	— .1	— .5
.....	2.4	2.6	4.1	.6	.5	7.7	6.95	4.2	.2	.1	+ .1	— .5
.....	2.1	2.6	4.5	.5	.6	7.9	6.7	4.05	.2	.4	.1	— .6
.....	1.85	2.5	4.6	.5	.7	7.2	6.55	3.7	.2	.3	.0	— .4
.....	1.5	2.4	4.5	.3	.8	6.95	6.35	3.4	.2	.4	.0	— .4
.....	1.4	2.4	4.2	.1	.9	7.4	6.15	3.2	.0	.2	.0	— .4
.....	1.4	2.2	4.0	.1	1.25	7.8	6.0	3.1	.1	.2	— .2	— .5
.....	1.75	2.1	4.0	.1	1.35	7.5	5.9	2.85	.3	— .2	— .2	— .5
.....	2.0	1.8	4.15	.0	1.6	7.0	5.6	2.7	.4	— .4	— .3	— .5
.....	2.1	1.8	4.45	.0	1.7	6.8	5.4	2.6	.3	— .5	— .3	— .7
.....	2.45	1.7	4.6	.0	1.8	7.0	5.3	2.5	.3	— .6	— .3	— .8
.....	2.5	1.6	4.95	.0	1.95	7.45	5.3	2.3	.3	— .7	— .3	— .8
.....	2.6	1.5	5.15	.0	2.2	7.35	5.1	2.2	.1	— .8	— .3	— .7
.....	2.6	1.6	5.05	.0	2.4	7.05	4.9	2.2	.1	— .8	— .3	— .1
.....	2.6	1.8	5.7	.0	2.35	6.8	4.9	2.2	.0	— .8	— .3	.0
.....	2.4	2.0	8.6	.2	2.1	6.8	4.85	2.2	.1	— .8	— .3	.3
.....	2.4	2.1	5.1	.2	1.7	7.0	4.7	1.95	.2	— .8	— .3	.5
.....	2.3	2.1	3.05	.1	1.55	6.7	4.6	1.8	.2	— .6	— .3	.6
.....	2.05	2.1	2.0	.1	1.4	6.5	4.35	1.8	— .4	— .6	— .3	.7
.....	1.75	2.5	1.45	.1	1.5	5.9	4.05	1.6	— .5	— .6	— .3	.9
.....	1.7	2.5	1.1	.2	1.8	6.6	4.0	1.5	— .7	— .5	— .6	1.1
.....	1.7	.....	.6	.2	2.2	7.3	3.9	1.5	— .7	— .5	— .6	1.1
.....	1.5	.....	.6	.2	2.55	7.2	3.75	1.3	— .8	— .4	— .9	1.1
.....	1.6	.....	.7	.....	2.9	.....	3.6	1.2	.....	— .3	.....	1.5

River frozen entirely across January 4 to March 6; ice gradually broke up March 7–22; river March 24. Gage heights January 1 to March 7 are to top of ice; after that date to water The following comparative readings were also made:

Date.	Water surface.	Top of ice.	Thickness of ice.
	Feet.	*Feet.*	*Feet.*
5	2.0	2.1	2.6
8	1.6	1.7	2.8
3	1.9	2.0	2.8
7	2.4	2.5	2.0

zen November 30 to December 31. Average thickness of ice, 1 foot. Gage heights are to top

Station rating table for Missouri River near Bismarck, N. Dak., from September 28, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
−0.90	7,680	0.50	10,660	1.90	15,780	4.60	31,800
−0.80	7,810	0.60	10,960	2.00	16,240	4.80	33,260
−0.70	7,950	0.70	11,260	2.20	17,180	5.00	34,760
−0.60	8,110	0.80	11,580	2.40	18,160	5.20	36,280
−0.50	8,280	0.90	11,900	2.60	19,200	5.40	37,840
−0.40	8,460	1.00	12,240	2.80	20,280	5.60	39,440
−0.30	8,660	1.10	12,580	3.00	21,400	5.80	41,060
−0.20	8,880	1.20	12,940	3.20	22,560	6.00	42,700
−0.10	9,100	1.30	13,320	3.40	23,760	6.50	46,940
0.00	9,340	1.40	13,700	3.60	25,000	7.00	51,300
0.10	9,580	1.50	14,100	3.80	26,280	7.50	55,780
0.20	9,840	1.60	14,500	4.00	27,600	8.00	60,320
0.30	10,100	1.70	14,920	4.20	28,960		
0.40	10,380	1.80	15,340	4.40	30,360		

The above table is applicable only for open-channel conditions. It is based on five discharge measurements made during 1905 and one in 1904, and is fairly well defined between gage heights −0.6 foot and 7 feet.

Estimated monthly discharge of Missouri River near Bismarck, N. Dak., in 1904 and 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
1904				
October	10,660	9,340	10,160	624,700
November	12,240	9,340	10,400	618,800
December	28,280	9,340	16,730	1,029,000
1905				
March 24-31	35,520	10,960	16,640	264,000
April	11,580	9,340	10,200	606,900
May	20,840	9,580	13,640	838,700
June	59,440	23,460	46,030	2,739,000
July	58,520	25,009	41,020	2,522,000
August	33,260	12,940	21,490	1,321,000
September	11,900	7,810	9,696	577,000
October	10,380	7,680	8,440	519,000
November	9,580	7,680	8,710	518,300
The period				9,906,000

MISSOURI RIVER AT KANSAS CITY, MO.

This station was established April 13, 1905. It is located at the Hannibal Railway bridge at the foot of Broadway street, Kansas City, Mo.

The channel is slightly curved for one-half mile or more above and below the station. The right bank is high, is covered with railroad tracks and buildings, and does not overflow at this point; the left bank is low, sandy, somewhat timbered, and is liable to overflow. The bed of the stream is composed of sand and is clean except for stones around [illegible] some drift lodged in the bed next to the south [illegible] accuracy of measurements; the piers are the [illegible] medium, becoming sluggish toward the north [illegible] measurements at this point at high stage[s] [illegible] current.

Discharge measurements are made from the downstream side of the bridge to which the gage is attached. The initial point for soundings is at the south end on the downstream side of the bridge.

The gage was read from April 13 to June, 1905, by Charles Sprikle; on the latter date arrangements were made under which the readings are furnished by the United States Weather Bureau. The gage is the Missouri River Commission gage, located 280 feet north of the south end of the bridge, on the downstream side. It is graduated in feet and tenths from 303.5 to 332.0 feet, this being elevation above St. Louis, Mo. To obtain gage heights 303.5 feet must be deducted from all readings on this gage.[a]

Discharge measurements of Missouri River at Kansas City, Mo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.[b]	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 13	W. G. Russell	704	11,900	3.80	8.6	45,200
May 29	do	856	17,170	4.67	12.2	80,240
June 2	Murphy and Russell	983	20,220	6.48	14.9	130,900
June 29	W. G. Russell	945	23,960	5.75	16.5	137,800
July 8	J. C. Stevens	992	23,840	7.54	19.4	179,800
October 8	W. G. Russell	679	13,610	2.49	7.4	33,830
October 27	do	679	13,750	2.50	7.6	34,360

[a] This was the amount used by the Missouri River Commission. The Weather Bureau deducts 303.3 feet, and this amount has been used since July 1, in order to avoid much unnecessary work and the danger of mistakes. The difference seems to occur from a difference in elevation given by two lines of levels run from St. Louis to this point.

Tuttle & Pike, civil engineers, of Kansas City, give the slope of the Missouri at the Hannibal bridge as 0.80 foot per mile. In 1881 a survey from Leavenworth to Lexington, 76 miles, gave 0.78 foot per mile. In 1903 a survey from the Great Western Railway bridge, just above the mouth of Kansas River, to Hannibal bridge, gave 1.62 feet per mile. In 1904 this slope was 1.22 feet per mile. Tuttle & Pike consider the last two abnormal and 0.80 foot per mile correct at Hannibal bridge.

[b] Gage heights obtained by subtracting 303.5 from gage readings.

Daily gage height, in feet, of Missouri River at Kansas City, Mo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	12.55	10.0	14.42	17.2	14.2	8.5	9.25	7.2	8.45
2	11.8	9.8	14.9	18.0	14.2	8.5	9.0	7.1	8.1
3	10.87	9.35	14.65	19.7	13.9	8.3	8.7	7.05	7.45
4	10.32	9.18	14.0	20.0	13.5	7.7	8.5	6.95	6.4
5	9.82	9.78	13.42	19.5	13.0	7.6	8.25	7.0	4.7
6	9.42	8.7	13.28	18.8	12.7	7.4	8.05	7.3	4.65
7	9.15	8.82	13.18	18.8	13.4	7.6	7.7	7.85	4.85
8	8.8	8.85	13.08	19.2	13.2	7.5	7.65	9.3	5.75
9	8.72	9.2	13.8	20.4	13.5	7.3	7.35	9.75	6.25
10	8.65	9.45	12.35	22.0	13.5	7.4	7.25	9.3	5.9
11	8.58	9.55	12.3	22.8	12.7	7.3	7.1	8.85	5.6
12	8.52	11.12	11.9	23.0	11.9	7.2	7.1	8.55	5.8
13	8.58	12.65	11.6	22.1	11.4	7.0	7.0	8.35	6.05
14	8.3	13.6	11.8	20.2	11.1	7.2	6.9	8.15	6.25
15	8.25	13.5	12.4	18.7	10.8	11.1	6.75	7.95	6.2
16	8.07	15.6	15.2	17.9	10.9	14.7	6.65	7.65	6.05
17	8.02	16.55	15.5	17.1	11.3	16.6	6.75	7.5	6.2
18	7.85	15.78	15.7	16.5	11.1	17.3	6.8	7.5	6.15
19	8.05	14.78	15.1	15.7	11.7	18.6	7.05	7.45	6.35
20	7.5	13.98	15.0	15.5	12.5	17.1	7.1	7.65	6.4
21	7.48	13.5	15.8	15.2	12.4	15.9	7.45	7.7	6.4
22	7.4	13.15	16.3	14.7	12.1	14.8	8.05	7.45	6.4
23	8.15	12.68	16.1	14.3	11.9	15.1	8.1	7.2	6.4
24	8.72	12.2	16.1	14.1	12.0	13.8	8.0	7.65	6.45
25	9.42	12.88	16.4	13.7	11.6	12.5	8.05	8.15	6.65
26	9.52	14.95	16.5	13.6	10.8	11.7	8.1	8.65	6.4
27	9.58	14.2	17.3	13.7	10.1	11.0	7.8	8.55	6.3
28	9.85	12.65	17.2	13.2	9.6	10.3	7.55	8.35	6.4
29	10.45	12.32	16.7	13.1	9.2	9.8	7.35	8.45	6.25
30	10.45	12.55	16.7	14.0	9.0	9.2	7.3	8.55	6.3
31	.....	12.52	.....	14.5	8.75	.....	7.3	.....	6.25

n rating table for Missouri River near Kansas City, Mo., from April 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
4.60	16,000	6.70	28,600	8.80	45,600	12.80	87,800
4.70	16,500	6.80	29,300	8.90	46,500	13.00	90,300
4.80	17,000	6.90	30,000	9.00	47,400	13.50	96,700
4.90	17,500	7.00	30,700	9.20	49,200	14.00	103,200
5.00	18,000	7.10	31,400	9.40	51,100	14.50	109,750
5.10	18,550	7.20	32,100	9.60	53,000	15.00	116,600
5.20	19,100	7.30	32,850	9.80	55,000	15.50	123,600
5.30	19,650	7.40	33,600	10.00	57,000	16.00	130,600
5.40	20,200	7.50	34,400	10.20	59,000	16.50	137,600
5.50	20,750	7.60	35,200	10.40	61,000	17.00	144,600
5.60	21,300	7.70	36,000	10.60	63,000	17.50	151,600
5.70	21,900	7.80	36,800	10.80	65,000	18.00	159,000
5.80	22,500	7.90	37,650	11.00	67,100	18.50	166,500
5.90	23,150	8.00	38,500	11.20	69,200	19.00	174,000
6.00	23,800	8.10	39,350	11.40	71,400	19.50	181,500
6.10	24,450	8.20	40,200	11.60	73,700	20.00	189,000
6.20	25,100	8.30	41,100	11.80	76,000	21.00	204,400
6.30	25,800	8.40	42,000	12.00	78,300	22.00	220,000
6.40	26.500	8.50	42,900	12.20	80,600	23.00	236,000
6.50	27.200	8.60	43,800	12.40	83,000		
6.60	27,900	8.70	44,700	12.60	85,400		

above table is applicable only for open-channel conditions. It is based on six discharge measure- made durin · 1905, and is fairly well defined between gage heights 7 feet and 20 feet.

Estimated monthly discharge of Missouri River near Kansas City, Mo., for 1905.

[Drainage area, 492,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	84,800	33,600	48,990	2,915,000	0.100	0.112
.....	138,300	44,700	81,170	4,991,000	.165	.190
.....	148,800	73,700	111,800	6,653,000	.227	.253
.....	236,000	91,550	150,800	9,272,000	.307	.354
st.....	105,800	45,150	77,740	4,780,000	.158	.182
mber.....	168,000	30,700	71,000	4,225,000	.144	.161
er.....	49,680	28,250	35,560	2,185,000	.072	.083
nber.....	54,500	30,350	38,520	2,292,000	.078	.087
ıber.....	42,450	16,250	25,750	1,583,000	.052	.060
The period.....	.....	.....	.....	38,900,000	.....	.....

MISCELLANEOUS MEASUREMENTS.

The following miscellaneous discharge measurements were made in the Missouri Ri basin in 1905:

Miscellaneous discharge measurements made in Missouri River drainage basin in 1904 a 1905.

Date.	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Gage height.	Di char
1904.			*Feet.*	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.*
June 5	Little Sioux	Cherokee, Iowa	137	1,232	2.07	.....	2.
1905.							
June 25	Missouri	Mannhaven, N.Dak.	1,435	9,200	5.65	7.68	52.
May 30	....do	Great Falls, Mont.	.....	1,876	3.24	.....	6.
June 15	....do	....do	961	2,645	4.66	.....	12.
October 7	....do	....do	961	1,082	1.80	.....	1.
June 19	Sixteenmile Creek	Lombard, Mont	.....	50	1.07	.....	
August 16	....do	....do	.....	23	.85	.....	
September 22	....do	....do	.....	17	.93	.....	

SMITH RIVER DRAINAGE BASIN.

SMITH RIVER AT TRULY, MONT.

Smith River rises in the Castle Mountains, in southern Meagher County, Mont., flows nor westward, and enters the Missouri about 15 miles southwest of Great Falls.

The gaging station was established March 7, 1905. It is located at a steel highway br on the county road running up Smith River valley, in the center of sec. 35, T. 19 N., R. Montana prime meridian, near the discontinued post-office of Truly, and about 20 southwest of Great Falls, Mont., whence it is reached by driving.

The channel is straight for 200 feet above and 1,200 feet below the station. Both are high, but the left may overflow in extremely high water. The bed of the stream i posed of gravel and flat pieces of sandstone, is free from vegetation, and is perma There is but one channel at all stages and the current is fairly swift.

Discharge measurements are made from the downstream side of the bridge, which h one span, though there is a trestle approach at the left bank. The initial point for sour is marked with white paint on the end post of the truss on the left side of the bridge above the hand rail.

The gage, which is read twice each day by Henry V. Evans, was originally a vertica set into the bed of the stream and braced to the downstream side of the bridge. This replaced May 11, 1905, by a standard chain gage fastened to the upstream hand rail o bridge, the same datum being used. The length of the chain is 20.40 feet. The ga referred to bench marks as follows: (1) A point marked in black paint on the south corner of the stone abutment, at the north end of the bridge; its elevation is 12.61 feet a the zero of the gage and approximately 3,400 feet above sea level. (2) A nail in the t of a large cottonwood tree at the end of the southwest approach to the bridge, 70 feet from the initial point for soundings on the downstream side of the road; elevation a gage zero, 13.36 feet.

Discharge measurements of Smith River at Truly, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec. ft.*
March 7	Porter and Bird	87	119	1.37	1.80	163
May 11	Stockman and Porter	81	101	1.24	1.62	125
September 1	A. P. Porter	.....	40	.76	1.20	31

Daily gage height, in feet, of Smith River at Truly, Mont., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	1.58	1.6	1.9	2.15	1.7	1.25	1.28	1.43	1.38
2	.....	1.58	1.55	1.9	2.15	1.75	1.28	1.3	1.45	1.4
3	.....	1.6	1.6	1.88	2.1	1.8	1.23	1.3	1.45	1.4
4	.....	1.55	1.6	1.95	2.05	1.65	1.25	1.35	1.53	1.58
5	.....	1.58	1.6	2.05	2.0	1.6	1.23	1.32	1.53	1.6
6	.....	1.55	1.5	2.15	1.92	1.6	1.23	1.3	1.55	1.62
7	1.8	1.58	1.5	2.2	1.88	1.55	1.2	1.3	1.55	1.55
8	1.78	1.6	1.55	2.2	1.85	1.5	1.22	1.3	1.55	1.58
9	1.8	1.7	1.5	2.15	1.85	1.5	1.2	1.3	1.55	1.6
10	1.8	1.55	1.58	2.35	1.75	1.48	1.2	1.3	1.55	1.58
11	1.65	1.55	1.68	2.55	1.72	1.4	1.2	1.32	1.55	1.52
12	1.65	1.6	1.75	2.65	1.65	1.4	1.2	1.35	1.55	1.52
13	1.52	1.5	1.65	2.45	1.6	1.4	1.18	1.4	1.55	1.5
14	1.45	1.58	1.65	2.35	1.6	1.4	1.18	1.4	1.55	1.5
15	1.75	1.6	1.6	2.3	1.6	1.4	1.18	1.4	1.55	1.52
16	1.75	1.6	1.6	2.28	1.6	1.4	1.2	1.4	1.55	1.5
17	1.75	1.6	1.58	2.17	1.68	1.4	1.18	1.42	1.55	1.5
18	1.75	1.6	1.6	2.2	1 6	1.4	1.18	1.45	1.55	1.4
19	1.75	1.6	1.8	2.12	1.6	1.4	1.18	1.45	1.55	1.4
20	1.72	1.6	1.88	2.0	1.62	1.32	1.18	1.32	1.55	1.48
21	1.72	1.6	1.85	2.0	1.6	1.3	1.18	1.4	1.55	1.55
22	1.7	1.6	1.85	2.0	1.6	1.3	1.15	1.4	1.55	1.7
23	1.68	1.6	1.95	2.25	1.58	1.3	1.15	1.5	1.45	1.6
24	1.65	1.6	1.9	2.35	1.52	1.3	1.15	1.5	1.3	1.5
25	1.65	1.6	1.9	2.4	1.5	1.3	1.15	1.53	1.33	1.4
26	1.52	1.6	1.9	2.48	1.5	1.3	1.15	1.5	1.35	1.45
27	1.62	1.6	1.9	2.52	1.52	1.3	1.15	1.53	1.3	1.45
28	1.62	1.6	1.9	2.4	1.85	1.3	1.15	1.5	1.38	1.35
29	1.65	1.6	1.9	2.28	1.72	1.3	1.18	1.53	1.25	1.45
30	1.62	1.6	1.9	2.2	1.65	1.28	1.25	1.65	1.28	1.4
31	1.55	.....	1.9	.....	1.6	1.25	.....	1.5	.....	1.35

NOTE.—Practically open-channel conditions during December.

SUN RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Sun River rises on the eastern slope of the Rocky Mountains in northwestern Montana, flows southward for about 60 miles, then, turning abruptly, flows eastward through a canyon in the confining mountains, emerging on a level plain through which it runs for 75 miles to its junction with the Missouri at Great Falls. The basin lies between Teton River on the north, the Dearborn on the south, the Missouri on the east, and the crest of the main range of the Rockies on the west.

Along its entire course through the plain the river has eroded a broad, level bottom, which averages about 1 mile in width and is from 5 to 25 feet above the surface of the water in the river. This bottom is bordered by a steeply sloping bluff, ranging in height from 300 to 500 feet, the top being the level surface of the plain, which extends north and south as a generally flat bench to the next river channel, where a similar bluff and bottom appear.

A project for reclaiming the bench lands between Sun and Teton rivers is under consideration by the United States Reclamation Service, and for that reason gaging stations have been maintained by the United States Geological Survey during 1905.

Information in regard to this basin is contained in the Annual Reports of the Reclamation Service and in the Annual Reports of the United States Geological Survey as follows:

Description: 11, ii, pp 43.
Irrigation surveys: 11, ii, pp 120–133; 13, iii, pp 56–57, 371–386.

NORTH FORK OF SUN RIVER NEAR AUGUSTA, MONT.

This station was established October 31, 1903. It is located below the head of the Kilraven ditch, near Christian's ranch, 14 miles northwest of Augusta and 21 miles southwest of Choteau, Mont.

The channel is straight for about 200 feet below and 300 feet above the station. The right bank is low and may overflow at flood stages; the left bank is high and rocky. The bed of the stream is of solid rock. The current is sluggish.

Discharge measurements are made by means of a cable, car, tagged wire, and stay wire. The initial point for soundings is the left cable support.

A standard chain gage, which, since March 1, 1905, has been read daily by G. B. Christian, who lives about one-half mile from the gage, is located on the left bank about 250 feet below the cable. The horizontal scale board is painted white and is fastened to three posts set in the ground. The length of the chain is 13.02 feet. The distance from the outside edge of the pulley to the zero of the scale is 4.00 feet. The gage is referred to bench marks as follows: (1) The highest point on a rock in the river, 12 feet upstream from the gage; size of the rock, 4 cubic yards; elevation of bench mark above gage zero, 3.96 feet. (2) A nail in the root of a cottonwood tree 15 feet east of the gage; elevation, 14.47 feet above gage zero. (3) A nail in the post which supports the inshore end of the gage; elevation, 10.69 feet above gage zero.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 99, pp 116–117; 130, p 90.
Discharge monthly: Ann 11, ii, p 94; 12, ii, pp 347, 360; 13, iii, p 93; 130, p 90.
Discharge, yearly: Ann 13, iii, p 98; 20, iv, p 53.
Gage heights: WS 130, p 90.
Hydrograph: Ann 12, ii, p 234.

Discharge measurements of North Fork of Sun River near Augusta, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft*
May 7	L. R. Stockman	115	357	1.41	1.34	5
May 24	Porter and Robbins	135	508	2.63	2.36	1,3
June 6	A. P. Porter	143	769	5.00	3.99	3,8
June 7	do	143	772	5.01	4.01	3,8
September 25	Gordon Edson	86	92	2.21	.70	

Daily gage height, in feet, of North Fork of Sun River near Augusta, Mont., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.7	0.5	1.2	3.4	2.2	1.4	0.8	0.7	0.7	1.0
.....	.65	.5	1.2	3.9	2.4	1.3	.8	,7	,7	1.0
.....	.65	.5	1.3	4.0	2.4	1.3	.8	.7	.7	1.0
.....	.6	.5	1.3	4.0	2.4	1.3	.8	.7	.6	1.0
.....	.6	.5	1.3	3.9	2.4	1.3	.8	.7	.6	1.0
.....	.65	.5	1.3	4.1	2.3	1.3	.8	.7	.6	1.0
.....	.65	.5	1.3	4.0	2.3	1.2	.8	.7	.6	1.0
.....	.65	.5	1.7	3.9	2.3	1.2	.8	.7	.6	1.0
.....	.7	.7	2.2	3.9	2.0	1.2	.8	.7	.6	1.0
.....	.7	.9	2.1	3.5	1.9	1.2	.8	.7	.6	1.0
.....	.65	.9	1.9	3.4	1.9	1.2	.8	.7	.6	1.0
.....	.6	.8	1.8	3.5	1.8	1.1	.8	.7	.6	1.0
.....	.6	.8	1.8	3.5	1.7	1.1	.8	.7	.6	1.0
.....	.6	.8	2.0	3.2	1.8	1.1	.8	.7	.6	1.0
.....	.6	.8	2.0	3.0	1.9	1.1	.8	.7	.6	1.0
.....	.6	.7	2.2	2.8	1.6	1.1	.8	.7	.6	1.0
.....	.6	.7	2.2	2.6	1.6	1.0	.8	.7	.6	1.0
.....	.6	.8	2.4	2.4	1.5	1.0	.8	.7	.6	1.0
.....	.6	.8	2.5	2.3	1.5	1.0	.8	.7	.6	1.0
.....	.6	.8	2.7	2.2	1.5	.9	.8	.7	.6	1.0
.....	.6	.8	2.9	2.3	1.4	.9	.8	.7	.6	1.0
.....	.6	.9	2.7	2.3	1.4	.9	.8	.7	.6	1.0
.....	.6	1.0	2.5	2.3	1.4	.9	.8	.7	.6	1.0
.....	.6	1.3	2.4	2.3	1.4	.9	.7	.7	.6	.9
.....	.6	1.5	2.4	2.3	1.4	.9	.7	.7	.6	.9
.....	.6	1.6	2.4	2.3	1.3	.9	.7	.7	.6	.9
.....	.6	1.5	2.4	2.3	1.3	.8	.7	.7	1.0	.9
.....	.6	1.3	2.3	2.3	1.3	.8	.7	.7	1.0	.9
.....	.6	1.3	2.4	2.3	1.4	.8	.7	.7	1.0	.9
.....	.7	1.3	2.5	2.2	1.3	.8	.7	.7	1.0	.9
.....	.6	.....	3.0	.....	1.4	.8	.....	.7	.....	.9

NOTE.—Readings to top of ice November 27 to December 23.

Station rating table for North Fork of Sun River near Augusta, Mont., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.50	125	1.40	537	2.30	1,280	3.20	2,410
0.60	161	1.50	602	2.40	1,380	3.30	2,570
0.70	199	1.60	672	2.50	1,485	3.40	2,740
0.80	239	1.70	747	2.60	1,595	3.50	2,920
0.90	281	1.80	827	2.70	1,710	3.60	3,100
1.00	325	1.90	912	2.80	1,830	3.70	3,280
1.10	372	2.00	1,002	2.90	1,960	3.80	3,470
1.20	422	2.10	1,092	3.00	2,100	3.90	3,670
1.30	477	2.20	1,185	3.10	2,250	4.00	3,870

The above table is applicable only for open-channel conditions. It is based on ten discharge measurements made during 1904–5. It is well defined between gage heights 0.6 foot and 2.5 feet, and above 2.5 it is based on two flood measurements at 10 feet.

Estimated monthly discharge of North Fork of Sun River near Augusta, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March	199	161	170	10,450
April	672	125	282	16,780
May	2,100	422	1,119	68,800
June	4,070	1,185	2,303	137,000
July	1,380	477	823	50,600
August	537	239	356	21,890
September	239	199	230	13,690
October	199	199	199	12,240
November 1-26	199	161	165	9,818
December 24-31	281	281	281	4,459
The period				345,700

NOTE.—No estimate for ice period.

SOUTH FORK OF SUN RIVER, AT AUGUSTA, MONT.

This station was established December 2, 1904. It is located at the highway bridge on the road from Augusta to Craig, Mont., about one-half mile from Augusta.

The channel above the station is straight for 20 feet and then turns to the right; below the station it is straight for 30 feet and then forks into two branches. Both banks are high and not liable to overflow. The bed of the stream is composed of coarse gravel and cobblestone. The current is sluggish. Two sloughs on the east side and an irrigation ditch on the west side of the bridge carry water past the point of measurement.

Discharge measurements are made from the upstream side of the single-span bridge. The initial point for soundings is at the east end of the hand rail, directly over the face of the right abutment.

The gage, which is read daily by Richard Auchard, is a vertical rod spiked to the crib work of the east or right abutment on the downstream side. The gage is referred to bench marks as follows: (1) The head of a spike surrounded by a ring of nails in the top of the east abutment on the downstream side; elevation, 4.89 feet. (2) A spike in the root of a large cottonwood tree 75 feet west of the west end of the bridge on the north side of the road; elevation, 4.63 feet. Elevations are above zero of gage.

A description of this station, with gage-height and discharge data, is contained in Water Supply Paper No. 130 of the United States Geological Survey, page 90.

Discharge measurements of South Fork of Sun River at Augusta, Mont., in 1905.

Date.	Hydrographer	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 6	Stockman and Porter	26	33	0.47	0.72	16
May 26	A. P. Porter	32	52	1.25	1.27	66
June 5	do	70	107	3.51	2.14	375
August 25	Porter and Edson	31	20	.63	.59	13
November 1	Gordon Edson	18	7.9	.70	.45	5.5

Daily gage height, in feet, of South Fork of Sun River at Augusta, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.3	1.6	1.1	1.0	1.0	1.8	1.9	1.9	0.5	0.6	0.4	1.6
2	1.3	1.8	1.1	1.0	.9	1.7	1.9	1.5	.5	.6	.5	1.6
3	1.2	1.8	1.1	1.0	1.0	1.7	1.8	1.4	.55	.6	.6	1.6
4	1.15	1.8	1.0	1.0	1.0	1.7	1.7	1.3	.6	.7	.6	1.6
5	1.3	1.8	1.0	.9	1.0	2.0	1.7	1.3	.65	.7	.6	1.6
6	1.15	1.9	1.0	.9	1.0	2.1	1.7	1.3	.6	.7	.6	1.6
7	1.2	1.9	1.0	.9	1.0	2.35	1.6	1.2	.6	.8	.7	1.6
8	1.3	1.9	1.0	.9	.6	2.1	1.6	1.2	.6	.8	.7	1.6
9	.....	1.9	1.0	.9	.8	2.45	1.5	1.1	.6	.8	.7	1.6
10	.....	1.9	1.0	.9	1.0	2.4	1.4	1.1	.6	.8	.7	1.6
11	.....	1.9	1.0	.9	1.0	2.4	1.4	1.1	.6	.8	.7	1.6
12	.....	1.9	1.0	.9	1.0	2.25	1.4	1.0	.6	.8	.7	1.6
13	.....	1.9	.9	.9	1.0	2.1	1.35	1.0	.6	.8	.7	1.6
14	.....	1.9	1.1	1.0	1.0	2.1	1.2	1.0	.6	.8	.7	1.4
15	.....	1.9	1.05	.95	1.1	2.0	1.2	1.0	.6	.8	.8	1.4
16	.....	1.9	1.05	.95	1.1	1.9	1.2	.9	.6	.8	.8	1.4
17	.....	2.0	1.05	1.0	1.2	1.78	1.1	.9	.5	.9	.8	1.2
18	.....	2.0	1.05	1.0	1.3	1.7	1.1	.9	.5	.9	.8	1.2
19	.....	2.1	1.1	1.0	1.2	1.65	1.1	.9	.5	.9	.8	1.2
20	.....	2.1	1.1	1.05	1.2	1.6	1.1	.9	.5	.7	.9	.9
21	.....	2.1	1.0	1.0	1.2	1.55	1.1	.8	.5	.8	.9	1.3
22	.....	2.1	1.1	1.0	1.2	1.55	1.0	.8	.5	.8	1.2	1.4
23	.....	2.1	1.0	1.0	1.2	1.62	1.0	.6	.5	.8	1.2	1.4
24	1.6	2.0	1.0	1.0	1.2	1.68	1.0	.6	.5	.7	1.3	1.5
25	.....	1.9	1.0	1.0	1.2	1.78	.9	.6	.5	.7	1.3	1.5
26	.....	1.9	1.0	1.0	1.2	2.2	.9	.6	.5	.6	1.3	1.5
27	.....	1.9	1.0	1.0	1.3	2.2	.9	.6	.6	.6	1.3	1.5
28	.....	1.1	1.0	1.0	1.4	2.05	1.0	.55	.6	.6	1.4	1.5
29	.....	.....	1.0	.9	1.5	2.0	1.0	.5	.6	.6	1.4	1.5
30	.....	.....	1.0	1.0	1.7	1.98	1.0	.5	.6	.4	1.4	1.5
31	.....	.....	1.0	.....	1.7	.....	1.0	.5	.....	.5	.....	1.5

RE.—River frozen and readings to surface of ice January 9 to February 27, inclusive, and Novem- to December 31, inclus e.

tation rating table for South Fork of Sun River at Augusta, Mont., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.40	4	1.00	37	1.60	130	2.10	370
0.50	7	1.10	46	1.70	160	2.20	430
0.60	11	1.20	58	1.80	200	2.30	490
0.70	16	1.30	73	1.90	250	2.40	550
0.80	22	1.40	90	2.00	310	2.50	620
0.90	29	1.50	110				

above table is applicable only for open-channel conditions. It is based on five discharge irements made during 1904–5. It is fairly well defined between gage heights 0.5 foot and 1.2 feet; this point it is based on one measurement at 2.14 feet.

Estimated monthly discharge of South Fork of Sun River at Augusta, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March	46	29	39.4	2,42
April	42	29	34.2	2,03
May	160	11	56.4	3,46
June	585	120	295	17,55
July	250	29	85.5	5,25
August	250	7	43.4	2,66
September	14	7	9.4	55
October	29	4	18.0	1,10
November 1-21	29	4	16.7	69
The period				35,7

NOTE.—No estimate for ice period.

SUN RIVER AT SUN RIVER, MONT.

This station was established July 31, 1905. It is located at the highway bridge at Sun River, Mont., 21 miles west of Great Falls, and is used for the purpose of checking the measurements of the river and the ditches above.

The channel is slightly curved above the station and straight for 100 yards below. Both banks are high and will overflow only at extreme flood stages. The bed of the stream is composed of loose and coarse gravel. The flow is comparatively swift, but there is some backwater effect near the left bank.

Discharge measurements are made from the lower side of the bridge, which has two spans of 100 feet each. The initial point for soundings is the hand rail over the downstream pier at the left bank. Low-water measurements are made by wading at a point 100 feet above the bridge.

Until September 27, 1905, the gage was read occasionally by different employees of the United States Reclamation Service; on the latter date R. A. Lange was employed as a temporary observer, and observations were made daily to the end of the year. The first gage consisted of a strip of galvanized iron nailed to a pile near the left bank of the river 150 feet above the bridge. August 16, 1905, this was replaced by a vertical rod gage fastened to the same pile, and the datum of the gage was lowered 1.52 feet. The gage is referred to bench marks as follows: (1) A nail on the corner of the house nearest the gage; elevation, 14.1 feet. (2) The bottom of the outer eyebar in the lower chord of the bridge, 3 feet from the first panel point from the left (north) end of the bridge, on the upstream side; elevation 13.90 feet. Elevations are above the datum of the gage.

Discharge measurements of Sun River at Sun River, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
July 31	A. P. Porter	91	180	2.38	2.52	4
August 14	do	60	85	3.42	2.10	2
September 27	Gordon Edson	53	43	2.15	1.44	

Daily gage height, in feet, of Sun River at Sun River, Mont., for 1905.

Day.	July.	Aug.	Sept.	Oct.	Nov.	Dec.	Day.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1				1.45	2.0	2.05	17			1.6	1.85	2.05	2.0
2				1.4	2.0	2.05	18		1.9	1.6	1.9	2.05	2.0
3				1.55	2.0	2.05	19			1.6	1.7	2.0	2.0
4				1.82	2.0	2.05	20			1.5	2.0	2.0	2.0
5				1.82	2.0	2.05	21			1.5	2.1	2.0	2.0
6				1.85	2.0	2.05	22			1.5	2.1	2.0	1.9
7				1.85	2.0	2.05	23			1.4	2.1	2.0	1.9
8				1.85	2.0	2.05	24			1.5	2.0	2.0	2.0
9				1.82	2.0	2.05	25			1.5	2.1	2.0	2.0
10		2.21		1.9	2.0	2.05	26		1.8	1.5	2.0	2.0	2.0
11				1.9	2.0	2.0	27			1.5	2.0	2.0	2.0
12				1.85	2.0	2.0	28		1.8	1.5	2.1	2.05	2.0
13				1.9	2.0	2.0	29			1.45	2.0	2.05	2.0
14		2.1		1.9	2.0	2.0	30		1.75	1.45	2.0	2.05	2.0
15				1.9	2.0	2.0	31	2.52			2.1		2.0
16		2.03		1.9	2.05	2.0							

NOTE.—Gage heights all referred to datum established August 16, 1905. River frozen December 2-16; readings to water surface. Ice 4 inches thick December 11.

Estimated monthly discharge of Sun River at Sun River, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
August (7 days)	323	180	239	14,700
September (17–30)	137	80	110	6,545
October	288	80	224	13,770
November	272	256	259	15,410
December	272	225	259	15,920
The period				66,340

NOTE.—These estimates are only approximate owing to lack of measurements.

WILLOW CREEK NEAR AUGUSTA, MONT.

Willow Creek rises in the northern part of Lewis and Clarke County, and flows northeastward into North Fork of Sun River.

The gaging station was established June 8, 1905. It is located at Jordan's ranch, just below the junction of Willow Creek with Little Willow Creek, about 8 miles northwest of Augusta, Mont., in sec. 27, T. 21 N., R. 7 W., from which it is reached by driving.

The channel is straight for 200 feet above and 40 feet below the station. Both banks are fairly high and the left is thickly wooded. The bed of the stream is composed of clean, hard gravel, with an occasional bowlder. There is but one channel at all stages.

Discharge measurements are made from the upstream side of the old wooden footbridge, having a span of 19 feet. The initial point for soundings is directly over the face of the left abutment of the bridge. Low-water measurements are made by wading just above the gage.

Daily gage readings are taken by S. N. Jordan, who lives about 200 yards away. The original gage was a rod located on the left bank of the stream 30 feet above the measuring bridge. August 22, 1905, a standard chain gage was installed on the bank near the rod gage and made to read the same as the latter. The horizontal arm is fastened to three posts set in the bank. The length of the chain is 14.03 feet. The gage is referred to bench

marks as follows: (1) A nail in the head of a 2 by 4 inch stake driven nearly flush with the ground on the top of a little hill on the left side of the path leading from the gage reader's house to the gage; elevation, 9.25 feet. (2) A point on a log on the left abutment, downstream side of the bridge; elevation, 2.86 feet. (3) The zero of the old gage rod, which is just level with the zero of the chain gage. Elevations are above the datum of the gage.

Discharge measurements of Willow Creek near Augusta, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
June 8	Porter and Casen	13	38	1.55	2.12	58
July 13	H. P. Porter	17	12	1.95	1.19	23
August 22	Porter and Edson	16	8	1.43	.95	12
November 2	Gordon Edson	14	4	.77	.61	3

Daily gage height, in feet, of Willow Creek near Augusta, Mont., for 1905.

Day.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1		2.45	2.0	0.9	0.6	0.7	0.65
2		2.3	1.52	.9	.6	.7	.65
3		2.25	1.4	.88	.58	.7	.65
4		2.12	1.38	.88	.58	.7	.65
5		1.95	1.3	.87	.58	.7	.68
6		1.85	1.28	.87	.55	.7	.68
7		1.7	1.2	.85	.55	.7	.7
8	2.15	1.65	1.2	.85	.58	.7	.7
9	2.78	1.6	1.18	.8	.62	.7	.7
10	2.43	1.32	1.12	.78	.62	.8	.7
11	2.22	1.2	1.1	.78	.65	.7	.7
12	2.1	1.18	1.08	.77	.65	.73	.7
13	2.0	1.15	1.08	.77	.65	.75	.7
14	1.9	1.12	1.02	.77	.65	.75	.72
15	1.85	1.05	1.0	.75	.65	.75	.7
16	1.68	1.05	.98	.75	.65	.73	.72
17	1.62	.95	1.0	.75	.65	.73	.75
18	1.5	.92	1.0	.75	.65	.73	.75
19	1.48	.9	1.0	.72	.68	.73	.78
20	1.4	.8	.98	.72	.72	.68	.75
21	1.32	.8	.95	.72	.75	.7	.75
22	1.78	.8	.95	.7	.78	.7	.72
23	2.15	.8	.9	.7	.75	.7	.7
24	2.22	.8	.9	.68	.72	.73	.7
25	2.6	.8	.95	.68	72	.7	.68
26	3.15	.8	.95	.65	.73	.7	.65
27	2.77	.9	.95	.65	.73	.68	.65
28	2.55	.92	.9	.62	.7	.62	.65
29	2.43	1.08	.92	.62	.7	.6	.6
30	2.32	1.1	.9	.6	.7	.6	.6
31		1.18	.9		.7		.6

NOTE. Practically open-channel conditions during December.

MISCELLANEOUS MEASUREMENTS.

ıs discharge measurements made in Sun River drainage basin, Montana, in 1905.

	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Sec.-ft.*
..	B. E. and T. Irrigation Ditch.[a]	Augusta.....	.....	2.8	1.57	4.4
..	Ford Creek.....	.....	14.5	8.7	1.15	10
..	North Fork of North Fork of Sun River.	Dam site, reservoir No. 3.	20	36	1.29	47
...	South Fork of North Fork of Sun River.	.....do.....	47	67	.89	59
...	Bear Creek.....	1 mile above mouth....	7	3.1	1.24	3.8

itch takes water out of South Fork of Sun River just above the gaging station.

BELT CREEK DRAINAGE BASIN.

BELT CREEK NEAR BELT, MONT.

k rises in Little Belt Mountains, flows in a general northerly direction, and enters i about 15 miles northeast of Great Falls.

ıg station was established March 18, 1905. It is located at the highway bridge lont., in the NW ¼, NE ¼, sec. 18, T. 20 N., R. 7 E., 20 miles east of Great Falls, it is reached by driving.

ınel is straight for 50 feet above and below the station and curves to the right ıth banks are high and the right bank is slightly wooded above the station. The tream is composed of rock, is free from vegetation, and is permanent. There is nnel at all stages. The current is very sluggish, the velocity at low water being ıt current-meter measurements can not be taken.

ɔ measurements are made from the upstream side of the bridge, which consists of n. The initial point for soundings is marked with white paint on the upstream bridge just over the face of the right abutment.

is read once each day by Mrs. Anna Epperson. The gage first established was a bolted to the second floor beam from the east end of the bridge on the upstream 12, 1905, a standard chain gage was placed on the upstream side of the bridge o read the same as the old gage. The length of the chain is 16.86 feet. The ʻred to bench marks as follows: (1) A black cross painted on top of a stone in the ıpstream side of the left abutment; elevation, 19.19 feet. (2) A nail in the root cottonwood tree, 25 feet east of the initial point for soundings, and 20 feet north r of the highway; elevation, 10.82 feet. Elevations are above the datum of the

Discharge measurements of Belt Creek near Belt, Mont., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
... Porter and Bird.....	40	45	0.18	1.59	8.0
... L. R. Stockman.....	40	47	.17	1.61	7.8
... A. P. Porter.....	55	160	3.61	3.85	578

Daily gage height in feet, of Belt Creek near Belt, Mont., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Nov.	Dec
1	.....	1.6	1.6	2.5	3.0	1.9	.....	
2	.....	1.55	1.6	2.6	3.0	2.0	.....	
3	.....	1.55	1.6	2.6	3.0	2.0	.....	
4	.....	1.6	1.6	3.1	2.9	2.0	.....	
5	.....	1.6	1.6	3.15	2.9	2.0	.....	
6	.....	1.6	1.6	3.3	2.8	1.9	.....	
7	.....	1.6	1.6	3.35	2.8	1.8	.....	
8	.....	1.6	1.6	3.5	2.8	1.7	.....	
9	.....	1.6	1.6	3.85	2.5	1.5	.....	
10	.....	1.6	1.6	4.1	2.5	1.45	.....	
11	.....	1.6	1.6	4.05	2.5	1.4	.....	
12	.....	1.6	1.6	3.6	2.5	1.4	.....	
13	.....	1.6	1.6	3.6	2.5	1.4	.....	
14	.....	1.65	1.65	3.6	2.5	1.4	.....	
15	.....	1.65	1.65	3.5	2.5	1.5	.....	
16	.....	1.65	1.65	3.35	2.6	1.4	.....	
17	.....	1.65	1.65	3.3	2.5	1.4	.....	
18	1.6	1.6	1.65	3.2	2.4	1.4	.....	
19	1.6	1.6	1.65	3.1	2.3	1.3	.....	
20	1.6	1.6	1.65	3.0	2.3	1.1	.....	
21	1.6	1.6	1.7	3.0	2.3	(a)	.....	
22	1.6	1.6	1.7	3.0	2.3	.....	.....	
23	1.57	1.6	1.7	3.0	2.0	.....	.....	
24	1.55	1.6	2.0	3.2	2.0	.....	.....	
25	1.55	1.6	2.1	3.5	2.0	.....	.....	
26	1.55	1.6	2.3	3.2	2.0	.....	.....	
27	1.55	1.6	2.3	3.0	2.0	.....	.....	
28	1.55	1.6	2.3	3.1	2.0	.....	.....	
29	1.55	1.6	2.4	3.0	2.0	.....	(a)	
30	1.6	1.6	2.4	3.0	2.0	.....	1.1	
31	1.6	.....	2.4	.....	1.9	.....	.....	

a Dry, August 21 to November 29.

NOTE.—Gage height for December, estimated.

HIGHWOOD CREEK DRAINAGE BASIN.

HIGHWOOD CREEK NEAR HIGHWOOD, MONT.

Highwood Creek rises in the Highwood Mountains, flows northwestward, and er Missouri River about 30 miles below Great Falls.

The gaging station was established March 19, 1905. It is located at a highway br leading up Highwood Creek Valley, at Smith's ranch near Highwood, in sec. 5, T. 2(R. 8 E., Montana prime meridian, and 30 miles east of Great Falls, from which it is rea by driving.

The channel is straight for 40 feet above and 30 feet below the station; beyond these li there are curves and rapids. Both banks are high and the right bank is wooded; ne bank is liable to overflow. The bed of the stream is composed of rocks, is free from ve tion, and is permanent. There is but one channel at all stages and the current is rather s

Discharge measurements are made from the upstream side of the two-span pile brid which the gage is attached. The initial point for soundings is on the upstream side o bridge directly over the face of the left abutment.

The gage, which is read twice each day by Richard Smith, consists of a vertical spiked to the cap on the piles at the northwest end of the bridge, upstream side. The ga

ıch marks as follows: (1) The head of a 30-penny spike driven in the end of the
: center bent of the bridge and marked with a cross in black paint; elevation,
The underside of the end plank on top of the stringer at the northwest end of
stream side; elevation, 7.00 feet. Elevations are above the datum of the gage.

ırge measurements of Highwood Creek near Highwood, Mont., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
Porter and Bird	16	9	0.85	0.75	8.0
Stockman and Porter	16	9	.95	.84	8.0
A. P. Porter	25	28	3.21	1.78	91.

ɔage height in feet, of Highwood Creek near Highwood, Mont., for 1905.

.	Mar.	Apr.	May.	June.	July.	Aug.	Oct.	Nov.	Dec.
.....	.....	0.75	0.7	1.0	1.15	0.66	.....	0.55	0.6
.....	.....	.75	.7	.98	1.1	.65	.....	.56	.59
.....	.....	.75	.7	.94	1.08	.52	.....	.58	.6
.....	.....	.75	.69	1.0	1.05	.45	.....	.6	.6
.....	.....	.75	.7	1.25	1.02	.35	.....	.62	.6
.....	.....	.78	.66	1.7	1.02	.32	.....	.61	.61
.....	.....	.78	.68	1.65	.98	.41	.....	.6	.62
.....	.....	.79	.7	1.58	1.05	.5	.....	.6	.62
.....	.....	.82	.75	2.3	1.02	.48	.....	.6	.65
.....	.....	.83	.8	2.2	.92	.48	.....	.6	.64
.....	.....	.8	.82	1.77	.82	.28	.....	.6	.65
.....	.....	.8	.82	1.6	.82	.35	.....	.6	.65
.....	.....	.82	.85	1.5	.75	.18	.....	.6	.65
.....	.....	.83	.86	1.3	.78	.32	.....	.6	.65
.....	.....	.82	.88	1.2	.75	.08	.....	.6	.65
.....	.....	.78	.86	1.18	.72	.1	.....	.6	.66
.....	.....	.75	.88	1.2	.9	.15	.....	.62	.68
.....	.....	.75	.92	1.18	.82	.06	.....	.61	.66
.....	0.78	.75	.95	1.1	.8	.....	.....	.62	.68
.....	.8	.75	.98	1.1	.78	.....	.....	.61	.66
.....	.78	.74	.99	1.05	.75	.....	.....	.62	.65
.....	.75	.78	1.02	1.17	.74	.....	.....	.61	.64
.....	.75	.8	1.02	1.33	.72	.....	.....	.62	.62
.....	.75	.78	1.04	1.3	.7	.....	.....	.61	.61
.....	.75	.8	1.05	1.25	.7	.....	.....	.62	.62
.....	.75	.81	1.01	1.25	.69	.....	.....	.61	.61
.....	.72	.85	1.01	1.28	.7	.....	.....	.62	.62
.....	.73	.84	1.01	1.25	.69	.....	.....	.61	.61
.....	.72	.72	1.02	1.22	.7	.....	0.2	.62	.62
.....	.73	.69	1.04	1.2	.68	.....	.4	.59	.61
.....	.75	.....	1.05	.....	.7	.....	.52	.....	.6

August 19 to October 28. Practically open-channel conditions during December.

MARIAS RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Marias River rises on the eastern slope of the main divide of the Rocky Mountains and flows in a general southeasterly direction to its junction with the Missouri. Throughout its entire length the river flows in a canyon and has a fall not exceeding 5 feet per mile. Its principal tributaries are Cutbank Creek, Willow Creek, and Cottonwood Creek, which enter from the north, and Two Medicine Creek, Birch Creek, and Teton River from the south. The most important of these is the Teton, which has its source in the Rocky Mountains, flows eastward in a course approximately parallel to that of Sun River, crossing and recrossing the sixth standard parallel north, and emptying into Marias River about a mile above the point where the latter joins the Missouri.

The United States Reclamation Service has under consideration a project for diverting water from the head of St. Mary River across both North and South forks of Milk River to Cutbank Creek, allowing it to flow down this creek and Marias River for 100 miles or more and then taking it out of the Marias by a canal to Big Sandy Creek, a tributary of Milk River.

Information in regard to stations in this basin is contained in the Annual Reports of the Reclamation Service and in the Thirteenth Annual Report of the United States Geologic Survey, Part III, pages 59–60.

MARIAS RIVER NEAR SHELBY, MONT.

This station was established April 4, 1902. It is located at the highway bridge near James A. Johnson's ranch, 7 miles south of Shelby, Mont.

The channel is straight for 100 yards above and 200 yards below the station. The right bank is sandy, sloping, and liable to overflow; the left bank is high and is protected by sheet piling and a plank wall. The bed of the stream is composed of sand and gravel, with some cobblestones, and is liable to shift after freshets. There is but one channel and the current flows toward the left bank as it rounds a sharp curve some distance above. The velocity of the current is moderate.

Discharge measurements are made from the highway bridge, the lower chord of which is about 15 feet above low water. The initial point for soundings is the east end of the bridge pier on the lower side of the bridge at the left bank.

A standard chain gage, which has been read during 1905 by Mr. Johnson, is fastened to the upstream guard rail of the bridge. The length of the chain is 21.98 feet. The gage is referred to bench marks as follows: (1) A rivet head in the footplate at the foot of a batter post on the top of the southeast pier; the plate is marked "B. M. 17.54," which is 17.54 feet elevation above gage datum. (2) A spike in the southwest side of a cottonwood stump, 50 feet southeast of the southeast pier; elevation above gage datum, 11.26 feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 84, p 32; 99, pp 112-113; 130, p 91.
Discharge: 66, p 23; 84, p 33; 99, p 113; 130, p 91.
Discharge, monthly: 84, p 34; 99, p 115; 130, p 93.
Gage heights: 84, p 33; 99, pp 113-114; 130, p 92.
Rating tables: 84, p 34; 99, p 114; 130, p 92.

Discharge measurements of Marias River near Shelby, Mont., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	Stockman and Morse	155	362	2.87	2.88	1,040
.....	H. M. Morse	165	435	3.35	3.42	1,455
.....	do	166	460	3.50	3.53	1,610
.....	W. B. Freeman	152	358	2.90	2.92	1,037
.....	H. M. Morse	135	252	1.46	2.22	369
r 9...	W. B. Freeman	122	181	.88	1.78	159
7.....	Freeman and Morse	134	238	1.53	2.22	363
r 20..	W. B. Freeman	127	189	1.08	1.88	204

Daily gage height, in feet, of Marias River near Shelby, Mont., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	3.8	3.5	3.4	2.5	.....	.....	2.3	2.0
.....	3.9	3.6	3.6	2.4	.....	.....	2.3	2.05
.....	4.1	3.5	3.6	2.4	1.85	.....	2.3	2.05
.....	4.1	3.6	3.5	2.3	.....	.....	2.25	2.05
.....	4.1	3.6	3.4	2.3	.....	.....	2.25	2.0
.....	4.0	3.5	3.4	2.3	.....	.....	2.2	2.0
.....	3.9	3.4	3.3	2.3	.....	.....	2.2	2.05
.....	3.8	3.7	3.2	2.2	.....	.....	2.18	2.05
.....	3.7	3.9	3.2	2.2	1.83	.....	2.15	2.07
.....	3.7	4.0	3.1	2.2	.....	.....	2.15	2.07
.....	3.6	3.7	2.9	2.1	.....	.....	2.1	2.07
.....	3.4	3.6	2.9	2.1	.....	.....	2.1	2.07
.....	3.4	3.6	2.8	2.1	.....	.....	2.05	2.07
.....	3.7	3.7	2.8	2.1	.....	.....	2.05	2.07
.....	3.8	3.5	2.7	2.1	.....	.....	2.05	2.1
.....	3.8	3.5	2.7	2.0	.....	.....	2.0	2.1
.....	3.7	3.6	2.6	2.0	.....	2.22	2.0	2.1
.....	3.7	3.5	2.5	2.0	.....	.....	2.0	2.1
.....	3.8	3.4	2.5	1.95	.....	.....	2.0	2.1
.....	3.6	3.25	2.5	1.9	.....	.....	2.0	2.1
.....	3.8	3.3	2.5	1.9	.....	.....	1.95	2.07
.....	3.9	3.25	2.5	1.85	.....	.....	1.95	2.07
.....	4.1	3.2	2.4	.....	.....	.....	1.9	2.07
.....	4.2	3.3	2.4	.....	.....	.....	1.9	2.05
.....	4.8	3.4	2.4	.....	.....	.....	1.9	2.05
.....	4.9	3.5	2.9	.....	.....	.....	1.9	2.07
.....	4.7	3.6	2.5	.....	.....	.....	1.9	2.07
.....	3.6	3.5	2.5	.....	.....	.....	1.9	2.07
.....	3.5	3.5	3.0	.....	.....	2.4	1.9	2.07
.....	3.4	3.4	2.7	.....	.....	2.35	1.95	2.07
.....	3.4	.....	2.5	.....	.....	2.35	.....	2.05

No observations from January 1 to April 30 or from August 23 to October 28. Practically nel conditions during December.

Station rating table for Marias River near Shelby, Mont., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.70	150	2.60	590	3.50	1,550	4.40	2,970
1.80	180	2.70	670	3.60	1,690	4.50	3,160
1.90	215	2.80	760	3.70	1,830	4.60	3,350
2.00	250	2.90	850	3.80	1,970	4.70	3,540
2.10	290	3.00	950	3.90	2,130	4.80	3,740
2.20	340	3.10	1,050	4.00	2,290	4.90	3,940
2.30	390	3.20	1,170	4.10	2,450	5.00	4,160
2.40	450	3.30	1,290	4.20	2,610		
2.50	520	3.40	1,410	4.30	2,790		

The above table is applicable only for open-channel conditions. It is based on 16 discharge measurements made during 1904-5, and is well defined between gage heights 1.8 feet and 4.5 feet.

Estimated monthly discharge of Marias River near Shelby, Mont., for 1905.

[Drainage area 2,610 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
May	3,940	1,410	2,114	130,000	0.810	0.934
June	2,290	1,170	1,585	94,310	.607	.677
July	1,690	450	870	53,490	.333	.384
August 1-22	520	198	321	14,010	.123	.101
November	390	215	279	16,600	.107	.119
December	290	250	276	16,970	.106	.122
The period				325,400		

CUTBANK CREEK AT CUTBANK, MONT.

Cutbank Creek rises on the eastern slope of the Rocky Mountains, flows eastward and then southeastward, and enters Marias River near the town of Cutbank.

The gaging station was established August 4, 1905. It is located in the gorge just below the steel-trestle bridge of the Great Northern Railway, three-fourths of a mile west of Cutbank.

Except for a slight curve just above, the channel is straight for 500 feet or more above and below the cable. At the cable support the right bank is 3 feet higher than the left, which might overflow at the highest stages; both banks are free from brush and vegetation. The bed of the stream is composed of gravel with an occasional bowlder, and the sides are of sandy soil. Fairly accurate results should be obtained, though the current is rather swift and the bottom somewhat rough. Owing to the distance between the gage and the cable the slope of the water surface at the two points is probably somewhat different.

Discharge measurements are made by means of a cable with tag wire, which was established September 18, 1905, 300 yards below the gage. The initial point for soundings is on the tag wire 5 feet out from the cable support on the left bank.

The gage is read twice each day by Frank Mason. The first gage was a rod placed on the left (east) bank of the creek and nailed to the cribbing at the intake of the railroad pumping plant. This was replaced August 31, 1905, by a standard chain gage, located on the left bank 200 feet below the rod gage and made to read the same as the latter. The

horizontal arm is graduated from 1.5 feet to 10 feet and is supported by posts set in the bank. The distance from the center of the standard gage pulley to the zero of the gage scale is 4.98 feet. The length of the chain is 17.35 feet. The gage is referred to bench marks as follows: (1) A black cross painted on the southwest corner of the yellow sandstone block at the foot of the bedplate on the top of the upstream masonry pier nearest the water's edge at the left bank, of the Great Northern Railway steel-trestle bridge over the creek; elevation, 16.64 feet. (2) A cross chiseled on the highest point of a large outcropping rock at the southeast corner of Frank Mason's house, 75 feet north of the gage; elevation, 15.11 feet. (3) A railroad spike driven in the north side of the rear post of the gage 2 feet above ground; elevation, 11.04 feet. Elevations are above the datum of the gage.

Discharge measurements of Cutbank Creek at Cutbank, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
August 31	W. B. Freeman	31	18	1.24	2.81	22
September 27	H. M. Morse	26	12	1.04	2.77	12
October 19	Freeman and Morse	48	44	1.33	3.30	58
November 19	W. B. Freeman	42	22	2.14	3.11	47

Daily gage height, in feet, of Cutbank Creek at Cutbank, Mont., for 1905.

Day.	Aug.	Sept.	Oct.	Nov.	Dec.	Day.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	2.8	2.85	3.2	2.4	17	3.1	2.8	3.25	3.1	3.7
2	.....	2.8	2.9	3.25	2.45	18	3.1	2.8	3.1	3.1	3.7
3	.....	2.8	2.8	3.2	2.55	19	3.1	2.8	3.3	3.1	3.75
4	3.3	2.8	2.85	3.2	3.35	20	3.0	2.75	3.25	3.1	3.7
5	3.3	2.8	3.15	3.25	2.9	21	3.0	2.7	3.25	3.1	3.55
6	3.3	2.8	3.6	3.25	2.8	22	3.0	2.7	3.25	2.9	3.5
7	3.25	2.8	3.5	3.2	2.8	23	3.0	2.7	3.2	3.0	3.4
8	3.2	2.8	3.5	3.2	2.65	24	3.0	2.7	2	3.05	3.35
9	3.2	2.75	3.4	3.2	2.95	25	2.9	2.8	3.2	3.1	3.45
10	3.1	2.7	3.4	3.2	3.95	26	2.9	2.7	3.25	2.95	3.45
11	3.25	2.7	3.4	3.15	4.0	27	2.9	2.8	3.25	2.8	3.65
12	3.2	2.7	3.3	3.1	4.0	28	2.9	2.8	3.3	2.6	3.7
13	3.15	2.7	3.3	3.1	4.0	29	2.8	2.8	3.3	2.5	3.4
14	3.1	2.7	3.3	3.1	3.9	30	2.8	2.85	3.25	2.5	3.3
15	3.1	2.7	3.3	3.	3.9	31	2.8	.....	3.2	.....	3.4
16	3.1	2.7	3.2	3.	3.8						

NOTE.—November 26 to December 31 readings were taken through a hole cut in the ice.

TETON RIVER NEAR BELLEVIEW, MONT.

This station was established November 26, 1904. It is located in sec. 35, T. 25 N., R. 3 W., Montana prime meridian, about 16 miles above Choteau, Mont. The nearest post-office is Belleview, Mont.

The channel above the station is straight for about 200 feet at low water, but at high water the river curves gradually from the left; below the station the channel is straight for 75 feet. Both banks are low and covered with thick underbrush and a few scattered trees. The bed of the stream consists of coarse gravel and cobblestones and is free from vegetation. A bar divides the channel at low water. The current is swift and there are some small rapids down the stream.

Discharge measurements are made by means of a cable, car, and tagged wire a short distance upstream from the gage. The initial point for soundings is the zero of the tagged wire at the left bank.

The gage is read daily by Julius Bjornstad, who lives near. The first gage was spiked to a post on the left bank, about 40 feet above the head of Kroff's irrigation ditch. March 9 1905, it was moved by the observer 250 feet upstream on account of the dam erected at the head of the ditch below. There is no connection between the gage readings before and after that date, probably on account of the difference in slope of the water surface at the two points. May 8, 1905, the gage, which is a rod, was referred to the bench marks, and it was found that the datum had been raised 0.78 foot in moving, while the difference in the level of the water surface at the old and new locations was but 0.10 foot. The gage datum was then lowered 0.20 foot, and it is now 0.58 foot above the original datum. The gage is referred to bench marks as follows: (1) A nail in a 10-inch cottonwood tree 8 feet west of the road and 50 feet from the left bank of the river; elevation, 4.85 feet. (2) A nail in a 5-inch cottonwood tree 2 feet east of the road and 50 feet from the left bank; elevation, 4.45 feet. (3) A nail in a 20-inch cottonwood tree serving as a post in Bjornstad's small corral; elevation, 2.51 feet.

A description of this station, with gage-height and discharge data, is contained in Water Supply Paper No. 130 of the United States Geological Survey, pages 93–94.

Discharge measurements of Teton River near Belleview, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft*
May 8	Stockman and Porter	38	34	1.41	0.40	
October 12	Gordon Edson		38	1.46	.39	
November 4	do	36	37	1.38	.38	

Daily gage height, in feet, of Teton River near Belleview, Mont., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.4	0.3	0.15	0.35	0.4	1.3	1.2	0.65	.....	0.4	0.55	0.25
.....	.4	.3	.2	.3	.45	1.55	1.2	.7	0.5	.4	.25	.25
.....	.4	.3	.2	.3	.4	1.85	1.2	.7	.5	.4	.25	.15
.....	.4	.3	.15	.35	.4	1.8	1.2	.7	.....	.35	.4	.1
.....	.4	.3	.15	.35	.4	1.8	1.15	.7	.4	.....	.35	.0
.....	.4	.3	.15	.35	.4	2.0	1.1	.6	.55	.4	.35	.0
.....	.4	.3	.15	.35	.4	2.2	1.1	.65	.45	.4	.35	.0
.....	.4	.3	.15	.35	.4	2.2	1.1	.6	.45	.4	.35	.0
.....	.4	.3	.35	.3	.5	2.2	1.0	.6	.45	.4	.35	.05
.....	.....	.3	.35	.25	.6	2.0	1.0	.6	.4	.4	.35	.05
.....	.....	.3	.35	.25	.6	1.8	1.0	.55	.4	.4	.35	.1
.....	.....	.3	.35	.25	.6	1.7	1.0	.6	.4	.45	.35	.1
.....	.....	.3	.35	.3	.6	1.7	1.0	.6	.4	.5	.35	.1
.....	.....	.3	.35	.3	.6	1.6	.95	.6	.4	.45	.35	.1
.....	.4	.3	.35	.3	.55	1.45	.9	.6	.4	.45	.35	.1
.....	.4	.3	.35	.3	.55	1.4	.9	.....	.4	.45	.25	.05
.....	.3	.3	.35	.3	.65	1.4	.85	.....	.4	.45	.35	.05
.....	.3	.3	.35	.3	.7	1.3	.8	.5	.4	.45	.35	.05
.....	.3	.3	.35	.3	.8	1.2	.8	.5	.4	.3	.35	.05
.....	.3	.3	.35	.3	.85	1.15	.75	.5	.4	.35	.35	.05
.....	.3	.3	.35	.3	1.0	1.1	.75	.....	.4	.35	.3	.05
.....	.3	.3	.3	.3	1.05	1.15	.8	.....	.4	.35	.3	.05
.....	.....	.3	.3	.3	1.0	1.2	7	.....	.4	.35	.3	.4
.....	.....	.3	.3	.3	.95	1.15	.75	.5	.35	.35	.3	.05
.....	.....	.3	.3	.3	.95	1.15	.7	.5	.35	.35	.3	.05
.....	.3	.3	.3	.4	.9	1.2	.7	.5	.....	.4	.3	.05
.....	.3	.3	.3	.4	.9	1.15	.7	.....	.4	.4	2.3	.0
.....	.3	.1	.3	.4	.9	1.15	.7	.5	.4	.4	.25	.0
.....	.3	.....	.3	.4	.95	1.15	.7	.....	.4	.4	.25	.0
.....	.3	.....	.35	.4	1.0	1.1	.7	.....	.4	.35	.25	.0
.....	.3	.....	.35	.....	1.1	.....	.7	.....	.....	.4	.....	.0

—Readings from March 9 to December 31 have been referred to the datum of May 8, 1905. The prior to March 9 refer to a different datum, there being no connection with the later readings. partly frozen January 1-22, inclusive; readings to the surface of the ice January 26 to February sive. River open after February 28. River blocked with ice November 27 and December 23.

TETON RIVER NEAR CHOTEAU, MONT.

station was established November 30, 1904. It is located at the highway bridge on l from Choteau to Augusta, Mont., and is about 1½ miles from the town of Choteau. hannel is straight for about 200 feet above the station; below it curves slightly to t. The right bank is high; the left is low and is subject to overflow at high stages. l of the stream is covered with rocks and coarse gravel and is free from vegetation. rent is swift.

arge measurements are made from the upstream side of the bridge, which is a wooden e resting on pile bents. The initial point for soundings is at the left side of the

gage is read occasionally by J. W. Shields, a surveyor, who performs this service usly. The original chain gage was fastened to the upstream hand rail of the bridge. s replaced May 9, 1905, by a standard chain gage, fastened to the floor of the bridge former gage, the same datum being maintained; the chain length is 12.33 feet. e is referred to bench marks as follows: (1) A nail in a 3-inch plank just back of the am at the west end of the bridge; elevation above zero of gage, 9.08 feet. (2) A

Daily gage height, in feet, of South Fork of Milk River near Browning, Mont., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		3.5	3.4	3.55	3.4	2.85	3.15
2		3.5	3.4	3.55	3.4	2.85	3.15
3		3.5	3.5	3.6	3.4	2.8	3.15
4		3.5	3.5	3.6	3.3	2.8	3.15
5		3.5	3.4	3.5	3.25	3.0	3.2
6		3.5	3.5	3.5	3.2	3.0	3.2
7		3.5	3.5	3.4	3.2	3.0	3.25
8		3.4	3.55	3.4	3.1	3.0	3.25
9		3.5	3.5	3.35	3.1	2.9	3.22
10		3.7	3.5	3.35	3.1	2.95	3.3
11		3.7	3.5	3.3	3.1	3.0	3.28
12		3.7	3.5	3.2	3.0	2.98	3.25
13		3.7	3.4	3.2	3.0	3.0	3.2
14		3.75	3.4	3.2	3.0	3.0	3.25
15		3.7	3.4	3.2	3.0	2.9	3.3
16		3.65	3.5	3.2	3.0	2.9	3.22
17		3.6	3.5	3.2	3.0	2.9	3.22
18		3.6	3.5	3.2	2.95	2.9	.....
19		3.6	3.45	3.2	2.9	2.9	.....
20		3.6	3.6	3.15	2.9	2.9	.....
21		3.75	3.6	3.1	2.85	2.9	.....
22		3.8	3.6	3.1	2.8	2.8	.....
23		3.75	3.6	3.1	2.8	2.8	.....
24		3.65	3.6	3.1	2.8	2.8	.....
25		3.6	3.65	3.1	2.8	2.8	.....
26		3.55	4.0	3.2	2.8	2.8	.....
27		3.5	4.2	3.3	2.8	2.82	.....
28	3.6	3.5	3.85	3.3	2.8	3.0	.....
29	3.55	3.5	3.75	3.4	2.8	3.08	.....
30	3.5	3.45	3.55	3.45	2.8	3.1	.....
31		3.5	.....	3.4	2.82	.....	.....

NOTE.—Creek frozen over October 18.

Estimated monthly discharge of South Fork of Milk River near Browning, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
May	78	30	51	3,117
June	141	30	49	2,916
July	51	9	24	1,445
August	30	2	8.5	523
September	9	2	4.4	262
October 1–17	23	12	17	587
The period				8,850

NOTE.—These estimates are only a rough approximation.

the international boundary; it then turns to the southeast, passes across the northern part of Montana, and empties into the Missouri.

The valley through which Milk River flows is broad and contains many thousand acres of irrigable land. The summer flow of the stream is not sufficient for the irrigation of any considerable part of this area, and it has been proposed to augment the supply by turning into the headwaters of Milk River the abundant waters of the St. Mary basin, which lies immediately adjacent to the sources of the Milk.

Information in regard to the basin is contained in the Annual Reports of the Reclamation Service and in the following publications of the United States Geological Survey (Ann= Annual Report; WS=Water-Supply Paper):

Description: Ann 19, iv, pp 286–287; 21, iv, p 188; 22, iv, pp 271–273; 22, iv, pp 287–288.
Irrigation surveys: Ann 13, iii, pp 62–63.
See page measurements: WS 130, pp 102–103.

SOUTH FORK OF MILK RIVER NEAR BROWNING, MONT.

This station was established April 28, 1905. It is located at Croff's ranch, about 40 miles northeast of Browning, Mont.

The channel is straight for about 100 yards above and below the station. Both banks are composed of gravel, and the right bank is liable to overflow at extreme high water. The bed of the stream is made up of rocks from 6 to 18 inches in diameter, is free from vegetation, and is fairly permanent. There is but one channel at all stages. The current is sluggish at the wading section and swift about 200 feet above. The depth at ordinary stages is about 2 feet.

High-water discharge measurements are made by means of a cable, car, and tagged wire about 200 feet above the gage. The initial point for soundings is the first marker on the tagged wire at the left bank. Low-water measurements are made by wading between the gage and the cable.

The gage, which was observed twice daily by R. J. Croff, was originally a temporary rod installed on the left bank 200 yards from the observer's house. This was replaced May 8, 1905, by a standard chain gage, located at the same place and fastened to supports in the left bank. The length of the chain is 13.66 feet. The gage is referred to bench marks as follows: (1) A stake driven into the bank above the gage; elevation, 8.00 feet. (2) A nail driven into the southeast corner of the log hen house belowing to Mr. Croff; elevation, 12.80 feet. Elevations are above the datum of the gage.

Discharge measurements of South Fork of Milk River near Browning, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 28	Stockman and Morse	45	55	0.93	3.60	51
May 28	H. M. Morse	46	54	.78	3.52	42
July 21	do	14	7	1.35	3.13	10
August 30	C. C. Babb				2.80	[a] 2

[a] Estimated.

Daily gage height, in feet, of South Fork of Milk River near Browning, Mont., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		3.5	3.4	3.55	3.4	2.85	3.15
2		3.5	3.4	3.55	3.4	2.85	3.15
3		3.5	3.5	3.6	3.4	2.8	3.15
4		3.5	3.5	3.6	3.3	2.8	3.15
5		3.5	3.4	3.5	3.25	3.0	3.2
6		3.5	3.5	3.5	3.2	3.0	3.2
7		3.5	3.5	3.4	3.2	3.0	3.25
8		3.4	3.55	3.4	3.1	3.0	3.28
9		3.5	3.5	3.35	3.1	2.9	3.32
10		3.7	3.5	3.35	3.1	2.95	3.3
11		3.7	3.5	3.3	3.1	3.0	3.28
12		3.7	3.5	3.2	3.0	2.98	3.25
13		3.7	3.4	3.2	3.0	3.0	3.2
14		3.75	3.4	3.2	3.0	3.0	3.25
15		3.7	3.4	3.2	3.0	2.9	3.3
16		3.65	3.5	3.2	3.0	2.9	3.32
17		3.6	3.5	3.2	3.0	2.9	3.32
18		3.6	3.5	3.2	2.95	2.9	.....
19		3.6	3.45	3.2	2.9	2.9	.....
20		3.6	3.6	3.15	2.9	2.9	.....
21		3.75	3.6	3.1	2.85	2.9	.....
22		3.8	3.6	3.1	2.8	2.8	.....
23		3.75	3.6	3.1	2.8	2.8	.....
24		3.65	3.6	3.1	2.8	2.8	.....
25		3.6	3.65	3.1	2.8	2.8	.....
26		3.55	4.0	3.2	2.8	2.8	.....
27		3.5	4.2	3.3	2.8	2.82	.....
28	3.6	3.5	3.85	3.3	2.8	3.0	.....
29	3.55	3.5	3.75	3.4	2.8	3.08	.....
30	3.5	3.45	3.55	3.45	2.8	3.1	.....
31		3.5	.....	3.4	2.82	.....	.....

NOTE.—Creek frozen over October 18.

Estimated monthly discharge of South Fork of Milk River near Browning, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
May	78	30	51	3,117
June	144	30	49	2,916
July	51	9	24	1,445
August	30	2	8.5	523
September	9	2	4.4	262
October 1-17	23	12	17	587
The period	.....	.....	.....	8,850

NOTE.—These estimates are only a rough approximation.

MILK RIVER AT HAVRE, MONT.

This station was established May 15, 1898. It is located at the highway bridge at Havre, Mont.

The channel is straight below the station and for a short distance above, when a sharp curve occurs. Both banks are high, being above ordinary floods, and are slightly wooded. The bed of the stream is liable to change with every freshet. The current is sluggish at ordinary stages.

Discharge measurements were originally made by means of a cable stretched across the river not far from the highway bridge. November 4, 1902, the cable was taken out, and discharge measurements have since been made from the downstream side of the bridge to which the gage is attached. The bridge makes an angle of 20° with the normal to the current at the measuring section. The initial point for soundings is marked on the downstream guard rail at the right bank.

The gage is read daily by L. H. Lang, the United States Weather Bureau observer at Havre. January 12, 1904, the old wire gage was replaced by a standard chain gage, which was made to read the same as the old gage, and was located on the downstream side of the bridge. The length of the chain is 25.21 feet. The gage pulley is located at a point which corresponds to a reading of 2.0 feet on the scale. The gage is referred to bench marks as follows: (1) The top of the highest bolt securing the bedplate to cement on top of the southwest pier of the bridge; elevation, 2,486.51 feet above datum. (2) A 20-penny nail in a cottonwood tree 100 feet southwest of the southwest pier of the bridge; elevation, 2,477.44 feet above datum. (3) A standard United States Geological Survey tablet in the stone pier of a column supporting the Great Northern Railway water tank, one-half mile southeast of the gage and near the roundhouse; elevation, 2,482.46 feet. The elevation of the zero of the gage is 2,461.25 feet above datum. The datum used in the establishment of the bench marks is that of the city of Havre, deduced from a temporary bench mark of the United States Geological Survey, which has since been destroyed.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: Ann 20, iv, p 245; WS 27, pp 68-69; 37, p 209; 49, p 267; 66, pp 15-16; 84, p 28; 99, pp 108-109; 130, pp 95-96.
Discharge: WS 27, p 75; 37, p 209; 49, p 267; 66, p 16; 84, p 29; 99, pp 109-110; 130, p 96.
Discharge, monthly: Ann 20, iv, p 245; 21, iv, p 189; 22, iv, p 288; WS 75, p 122; 84, p 31; 99, p 111; 130, p 96.
Discharge, yearly: Ann 20, iv, p 53.
Gage heights: WS 27, p 72; 37, p 210; 49, p 267; 66, p 16; 84, p. 30; 99, p 110; 130, pp 96 97.
Hydrographs: Ann 20, iv, p 246; 21, iv, p 189; 22, iv, p 288.
Rating tables: WS 27, p 76; 39, p 447; 52, p 516; 66, p. 170; 84, pp 30-31; 99, p 111; 130, p 97.

Discharge measurements of Milk River at Havre, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 7	L. R. Stockman	74	45	1.09	3.30	49
May 2	H. M. Morse	86	67	1.27	3.85	85
May 6	do	85	58	1.22	3.59	71
June 5	do	77	43	1.04	3.44	45
July 11[a]	W. B. Freeman	39	22	.76	3.15	17
July 31	H. M. Morse	82	83	1.36	3.85	113
August 1	do	75	71	.78	3.68	55

[a] Made by wading.

Information in regard to this station is contained in the following Water-Supply Pa of the United States Geological Survey:

Description: 84, pp 26–27; 99, p 103; 130, pp 98–99.
Discharge: 84, p 27; 99, p 104; 130, p 99.
Discharge, monthly: 84, p 28; 99, p 106; 130, p 102.
Gage heights: 84, p 27; 99, pp 104–105; 130, p 100.
Rating tables: 84, p 28; 99, p 105; 130, p 101.

Discharge measurements of Milk River at Malta, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	ch
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	S
May 11	H. M. Morse	20	8.9	0.52	0.73	
June 28	C. T. Prall	69	56	.94	1.25	
July 24	W. B. Freeman				.80	
July 20	do	22	28	1.45	1.19	
August 26	do	9	2.6	.88	.72	
August 26	do	9	2.4	.78	.71	

a Estimated.

Daily gage height, in feet, of Milk River at Malta, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.
1	1.1	1.1	2.2	1.1	0.6	1.0	1.95	2.95
2	1.1	1.1	2.2	1.1	.6	.9	1.45	2.75
3	1.1	1.1	2.4	1.1	.6	.8	1.05	2.25
4	1.1	1.1	2.4	1.0	.6	.9	.95	1.95
5	1.1	1.1	2.6	1.1	.6	.9	.95	1.95
6	1.1	1.1	2.8	1.1	.6	.9	.95	1.75
7	1.1	1.1	2.5	1.0	.6	.9	.85	1.55
8	1.1	1.1	2.3	.9	.6	.9	.85	1.35
9	1.1	1.1	2.1	.9	.7	1.0	1.05	1.45
10	1.1	1.1	2.5	.8	.7	1.1	1.65	1.45
11	1.1	1.1	2.0	.8	.7	1.1	1.45	1.45
12	1.1	1.1	2.1	.7	.7	1.1	1.15	1.25
13	1.1	1.1	2.0	.7	.7	1.1	1.65	1.25
14	1.1	1.1	2.0	.7	.7	1.0	1.45	1.15
15	1.1	1.1	2.0	.7	.7	1.0	1.15	1.15
16	1.1	1.1	1.9	.7	.7	1.0	1.05	1.15
17	1.1	1.1	1.9	.7	.7	1.0	1.05	1.05
18	1.1	1.1	2.0	.7	.7	1.0	1.05	1.05
19	1.1	1.1	2.1	.7	.7	1.0	1.05	1.05
20	1.1	1.1	1.8	.7	.7	1.0	1.05	.75
21	1.1	1.1	1.8	.7	.7	1.0	.95	.75
22	1.1	1.1	1.8	.7	.7	1.0	.95	.75
23	1.1	1.2	1.8	.7	.7	1.0	.95	.75
24	1.1	1.3	1.7	.6	.8	1.0	.85	.65
25	1.1	1.3	1.7	.6	.8	.9	.85	.65
26	1.1	1.2	1.5	.6	.8	.8	.85	.65
27	1.1	1.7	1.4	.6	.9	1.0	1.05	.65
28	1.1	1.7	1.4	.6	1.0	1.3	1.05	.65
29			1.3	.6	1.0	1.3	1.25	.65
30			1.3	.6	1.0	1.9	1.15	.55
31			1.1		1.0		3.05	.55

a River dry remainder of year.

NOTE.—Ice conditions January 1 to March 3.

ation rating table for Milk River at Malta, Mont., from January 1 to December 31, 1905

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.70	1	1.40	74	2.10	294	2.80	618
.80	6	1.50	96	2.20	336	2.90	670
.90	12	1.60	122	2.30	380	3.00	722
1.00	19	1.70	151	2.40	424	3.10	778
1.10	29	1.80	183	2.50	472		
1.20	41	1.90	217	2.60	520		
1.30	56	2.00	254	2.70	568		

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is well defined throughout; above 2 feet the curve is the same as for 1904.

Estimated monthly discharge of Milk River at Malta, Mont., for 1905.

[Drainage area, 14,040 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
nuary			[a]5	307	0.00036	0.00042
bruary			[a]5	278	.00036	.00037
arch	618	29	258	15,860	.018	.021
pril	29	0	8	476	.00057	.00064
ay	19	0	34	2,091	.0024	.0028
ne	217	6	27	1,607	.0019	.0021
ly	750	9	65	2,828	.0046	.0053
ugust	696		97	5,964	.0069	.0080
The period				29,410		

[a] Estimated by C. C. Babb.

NORTH FORK OF MILK RIVER NEAR CHINOOK, MONT.

This station was established April 22, 1905. It is located at Snedecor's ranch, about 4½ iles north of Chinook, Mont.

The channel is straight for 100 yards above and below the station. The banks are composed of sandy soil, covered with brush and cottonwood trees; they are high and do not verflow. The right bank has a slope of about 45°, and the left of about 30°. The bed of he stream is of sand, with a little vegetation near the left bank, and probably shifts slightly fter the highest floods. There is but one channel at all stages and the current is moderate.

Discharge measurements are made by means of a cable, car, and tagged wire just above he gage or by wading at low water. The initial point for soundings is a nail driven into he end of one of the timbers supporting the cable at the left bank.

The gage, which is read once each day by Mrs. R. B. Snedecor, is an inclined rod, which as erected May 22, 1905, to take the place of the temporary rod gage first established. The ew gage is nailed in two sections to posts driven into the left bank. The gage is referred to nch-marks as follows: (1) A spike driven in a post just east of the gage; elevation, 11.26 et. (2) A 20-penny spike in the root of a 10-inch cottonwood tree 20 feet east of the upper d of the gage; elevation, 13.92 feet. (3) A 20-penny spike driven into the root of a nch cottonwood tree 40 feet northeast of the tree to which the east end of the cable is tened; elevation, 16.12 feet. Elevations are above the datum of the gage.

Discharge measurements of North Fork of Milk River near Chinook, Mont.,

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gag heigh
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*
May 22	H. M. Morse	56	37	0.95	1.0
June 2	do	32	31	1.13	1.05
June 16	Stockman and Prall	55	35	.88	1.00
July 3	Babb and Prall	55	45	1.49	1.35
July 18[a]	W. B. Freeman	29	19	.49	.73
August 10[a]	do	25	14	.80	.80
August 23	C. T. Prall				.55

[a] Wading. [b] Estimated.

Daily gage height, in feet, of North Fork of Milk River near Chinook, Mont., for 19

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct	
1		1.28	1.15	1.25	0.92	0.45		
2		1.3	1.05	1.32	1.35	.45		
3		1.3	1.0	1.35	1.05	.43		
4		1.25	1.0	1.32	1.0	.35		
5		1.25	1.0	1.25	1.5	.35		
6		1.25	1.0	1.18	1.25	.32		
7		1.21	1.0	1.25	.98	.3		
8		1.2	1.0	1.15	.92	.3		
9		1.22	.95	1.1	.82	.25		
10		1.25	.9	.98	.8	.25		
11		1.2	.9	.9	.78	.25		
12		1.18	.9	.92	.75			
13		1.15	.9	.95	.72			
14		1.1	.95	.95	.65			
15		1.1	1.02	.9	.65			
16		1.1	1.0	.82	.65			
17		1.1	1.0	.78	.65			
18		1.1	.98	.75	.65			
19		1.1	.95	.75	.65			
20		1.1	1.02	.72	.6			
21		1.05	1.15	.68	.55			
22	1.2	1.08	1.15	.65	.52			
23	1.2	1.08	1.05	.65	.5		0.7	
24	1.18	1.05	1.05	.65	.55		.7	
25	1.15	1.05	1.05	.6	.6		.7	
26	1.18	1.05	1.05	2.7	.58		.7	
27	1.22	1.05	1.22	1.45	.52		.7	
28	1.28	1.05	1.22	1.35	.5		.7	
29	1.28	1.05	1.28	1.0	.5		.7	
30	1.25	1.08	1.3	1.5	.45		.8	
31		1.12		1.05	.45		.8	

NOTE.—September 3 to October 22, no flow. November 28 to December 31, frozen.

ion rating table for North Fork of Milk River near Chinook, Mont., from April 23 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.50	1	1.10	43	1.70	127	2.30	272
.60	3	1.20	53	1.80	147	2.40	302
.70	8	1.30	65	1.90	172	2.50	332
.80	13	1.40	77	2.00	197	2.60	362
.90	23	1.50	92	2.10	222	2.70	392
1.00	33	1.60	107	2.20	247	2.80	422

The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during 1905. It is poorly defined and is a basis for only a rough estimate.

Estimated monthly discharge of North Fork of Milk River near Chinook, Mont., for 1905.

[Drainage area, 1,422 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April 22-30	63	48	55	984	0.039	0.013
May	65	38	48	2,933	.034	.039
June	65	23	37	2,208	.026	.029
July	392	3	48	2,927	.033	.038
August	92	1	16	972	.011	.013
September	1	0	0	0	.000	.000
October	13	0	2.6	160	.0018	.0021
November 1-27	28	13	21	1,119	.015	.015
The period				11,300		

BEAVER CREEK NEAR ASHFIELD, MONT.

Beaver Creek rises in the Little Rocky Mountains, flows to the northeast and east, and enters Milk River near Hinsdale, Mont.

The gaging station was established July 5, 1903, at bridge No. 455 of the Great Northern Railway, one-half mile west of Ashfield, Mont. It was abandoned December 31, 1903, because the results were affected by backwater from a dam erected a mile below about a month after the establishment of the station. A new station was established at a point 2½ miles farther upstream and beyond the influence of the dam. It is near the ranch house of R. H. Thomas, about 18 miles from Malta and 3 miles south of Ashfield, Mont., the nearest post-office.

The channel is straight for 100 yards above and below the cable. Both banks are high and covered with willows. The left bank is steep and the right is sloping. The bottom of the stream is of mud. There is but one channel at all stages and the flow is very sluggish, the velocity being comparatively low even in the highest floods. The stream carries little water except at the time of spring floods or heavy rains, and during the summer the channel is overgrown with weeds and willows, which have to be cleared out occasionally.

Discharge measurements are made from a cable about 225 feet above the gage. The cable has a span of 100 feet between supports, and a tagged wire marked at 5-foot intervals is stretched above. The initial point for soundings is a nail in the cable support at the left bank.

The gage, which is read daily by Mr. Thomas, is an inclined plank on the right bank, securely fastened to posts set in the ground at each end, and has a vertical extension, which

gives minus readings at very low water. Early in 1905 the gage was referred to the marks and was found to have settled, so that the zero mark on the gage read 0.08 high. It has not been corrected. The gage was also found to read 0.01 foot too great foot vertical. The gage is referred to bench marks as follows: (1) A nail driven in top of a 2 by 4-inch stake, 12 feet south of the gage; elevation, 11.43 feet above gage (2) The top of a railroad spike driven in the northwest corner of Mr. Thomas's house above ground; elevation, 13.35 feet above gage datum.

Information in regard to this station is contained in the following Water-Supply the United States Geological Survey:

Description: 99, p 100; 130, pp 108-109.
Discharge: 99, p 100; 130, p. 109.
Discharge, monthly, 130, p 111.
Gage heights: 99, p 101; 130, p 110.
Rating table: 130, p 110.

Discharge measurements of Beaver Creek near Ashfield, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*
June 28	C. T. Prall	53	169	1.00	4.55
July 29	W. B. Freeman	7	5	1.42	.17
July 30	do	20	39	1.16	1.78
July 30	do	20	36	1.15	1.69
July 30	do	20	41	1.20	1.86

Daily gage height, in feet, of Beaver Creek near Ashfield, Mont., for 1905.

Day.	Mar.	June.	July.	Aug.	Day.	Mar.	June.	July.
1			2.70	2.9	17	0.6	1.7	0.6
2			2.1	1.15	18	.5	1.5	.4
3			1.7	1.15	19	.5	1.3	.3
4			1.3	.95	20	.4	1.1	.2
5			1.0	1.7	21	.2	1.0	.1
6			.9	1.55	22	.1	.8	.0
7			.7	.9	23	.05	.8	.0
8			.5	.3	24	—.1	1.1	.0
9			.3	.2	25	—.2	2.0	.2
10			.2	.1	26	—.2	2.5	1.5
11			.2	.0	27	—.2	2.3	1.8
12	2.0	0.8	.6	.0	28	—.25	4.6	1.9
13	1.3	1.2	1.0	.1	29		4.0	.4
14	1.15	1.2	1.1	.1	30		4.3	1.92
15	.9	1.4	1.0	.15	31			3.1
16	.7	1.8	.8	.2				

NOTE.—Creek dry for missing days.

Rating table for Beaver Creek near Ashfield, Mont., from March 12 to August 16, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.00	4	1.00	22	2.00	54	3.00	94
0.10	5	1.10	25	2.10	58	3.20	102
0.20	6	1.20	28	2.20	62	3.40	110
0.30	7	1.30	31	2.30	66	3.60	120
0.40	9	1.40	34	2.40	70	3.80	130
0.50	11	1.50	37	2.50	74	4.00	140
0.60	13	1.60	40	2.60	78	4.20	150
0.70	15	1.70	43	2.70	82	4.40	160
0.80	17	1.80	46	2.80	86	4.60	170
0.90	19	1.90	50	2.90	90		

above table is applicable only for open-channel conditions. It is based on five discharge measure- made during 1905. It is fairly well defined between gage heights 0 and 2 feet, and has been extended d these limits, being based on one measurement at 4.55 feet.

Estimated monthly discharge of Beaver Creek near Ashfield, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
rch	54	0	7.2	428
ne	170	0	34.3	2,041
ly	98	4	24.1	1,482
gust	90	0	10.0	615
The period				4,566

BEAVER CREEK OVERFLOW NEAR BOWDOIN, MONT.

This station was established June 29, 1903. It is located on an overflow channel of aver Creek, about 4 miles southeast of the Great Northern Railway section house at Bow- in, Mont., and is best reached by team from Malta, Mont., 14 miles distant. The water pply is derived partly from the natural drainage of irrigated lands and partly from water sted over the spillway at a dam on Beaver Creek above.

The channel is straight for 200 feet above and 100 feet below the station. During extreme ods both banks are submerged and the whole valley is covered with water. The bed of stream at the station forms a small bar, covered with weeds and swamp grass. The rent is sluggish, and measurements are affected by a check which is frequently erected at gates of a lateral about 1 mile below.

Discharge measurements are made by means of a cable, car, and tagged wire, and also by ling. The initial point for soundings is the east side of a post on the west or left bank. The gage is read daily by John Turmell, who lives about 300 yards distant. It is a ver- l board nailed to a cottonwood tree on the right bank about 100 feet above the cable. All old bench marks have been destroyed, but the zero of the gage is at an elevation of 17.84 feet above sea level, as determined from the datum bench mark at the Malta school se. This is based on the elevation of the rail in front of the Great Northern Railway ion at Malta, Mont. September 15, 1905, two new bench marks were established from gage on the assumption that the readings were at that time correct. These bench marks as follows: (3) The head of a railroad spike driven vertically in a projecting log at the hwest corner of Mr. Turmell's house, 800 feet southwest of the gage; elevation, 21.44 feet ve gage zero. (4) The head of a 20-penny spike driven horizontally in the northwest er of Mr. Turmell's house, 2 feet above the ground; elevation, 19.48 feet above gage zero.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 101–102; 130, p 111.
Discharge: 99, p 102; 130, p 112.
Discharge, daily: 130, p 112.
Discharge, monthly: 130, p 113.
Gage heights: 99, pp 102–103; 130, p 112.

Discharge measurements of Beaver Creek overflow near Bowdoin, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
June 28	C. T. Prall	89	215	0.55	6.4	118
July 30 [a]	W. B. Freeman	56	77	.2	4.8	15

[a] Float measurement.

Daily gage heights, in feet, and discharge, in second-feet, of Beaver Creek overflow near Bowdoin, Mont., for 1905.

Day.	March.		June.		July.		August.	
	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
1					4.8	16	4.4	7
2					4.9	19	4.2	5
3	5.4	43			4.8	16	4.1	4
4	5.3	37			4.7	13	4.0	3
5	5.15	29			4.6	11	3.9	2
6	4.85	18	6.65	138	4.4	7	3.8	2
7	4.85	18	5.0	23	4.3	6	3.7	2
8	4.05	4	4.4	7	4.1	4	3.6	1
9			4.3	6	4.0	3		
10			4.3	6	4.0	3		
11			5.3	37	3.9	2		
12			5.0	23	3.8	2		
13			6.7	143	3.8	2		
14			5.0	23	3.7	2		
15			4.9	19	3.7	2		
16			4.7	13	3.6	1		
17			4.6	11	3.6	1		
18			4.5	9				
19			4.4	7				
20			4.3	6				
21			4.2	5				
22			4.1	4				
23			4.1	4				
24	3.9	2	4.0	3				
25	3.8	2	4.0	3				
26	3.7	2	6.0	83				
27	3.6	1	5.7	61				
28			6.4	116				
29			5.5	49	5.2	31		
30			5.0	23	4.8	16		
31					4.6	11		

NOTE.—No flow on missing days.

Estimated monthly discharge of Beaver Creek overflow near Bowdoin, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum	Minimum.	Mean.	
rch 3-8, 24-27	43	1	16	309
ne 6-30	138	3	33	1,631
y 1-17, 29-31	31	1	8	333
gust 1-8	7	1	3	51
The period				2,324

PRIVATE CANALS IN MILK RIVER VALLEY.

DESCRIPTION OF CANALS.

During 1905 a number of stations were maintained on private canals in Milk River Valley, mainly for the purpose of ascertaining the extent of the private water rights. With one exception—the Rock Creek canal near Hinsdale, in Valley County—these canals are located in Choteau County and are used for the irrigation of lands in the vicinity of Harlem and Chinook.

The canals are all built on small grades and in soil which is easily eroded. In many of them deposition of silt has taken place, and in nearly all there is a growth of weeds and moss. At low stages the water is uniformly sluggish. In order to divert water into the laterals checks are erected in the main channels, and these checks often produce backwater effects for long distances above. They were put up under a great variety of conditions, and as a result many different velocities are found to exist at the same gage height during the season; in order to establish the correct relation between gage height and discharge it has been found necessary to make several rating curves for the same canal station. All the canals except the Rock Creek canal at Hinsdale and the Cook canal at Chinook have more than one station rating curve.

In July, 1905, an injunction suit was brought by the United States Office of Indian Affairs against later appropriators of water on Milk River and its tributaries above, to determine the rights pertaining to the agency ditch which supplies the Fort Belknap Indian Reservation. For that reason the water was shut off from some of the ditches, including the Matheson and Cook canals, during part of the irrigation season.

The gaging stations maintained were as follows:

Paradise Valley canal near Chinook, Mont.
Cook canal near Chinook, Mont.
Matheson canal near Chinook, Mont.
Harlem canal near Zurich, Mont.
Agency ditch near Harlem, Mont.
Fort Belknap canal near Chinook, Mont.

In addition to the canal stations regularly maintained, temporary gaging stations were established on Reser and West Fork ditches, taken from West Fork of Milk River, and miscellaneous information was collected in regard to the Dowen & Buckley, Rokita, and Corregan ditches from North Fork of Milk River; the Winter-Anderson canal from Milk River; and ditches from Parallel Creek. The water rights pertaining to these canals are to be adjudicated in the general lawsuit recently instituted.

PARADISE VALLEY CANAL NEAR CHINOOK, MONT.

This canal is used for the irrigation of bottom lands several miles east of Chinook, Mont. It diverts water from the south side of Milk River about 7 miles below Chinook, and its general course is easterly.

The station was established in June, 1903. It is reached by driving along the south river road from Chinook, Mont.

The channel is straight and the section at the station is semicircular. The bed c canal is composed of mud and sand and the banks are covered with brush and weeds.

Discharge measurements are made from a footbridge. The initial point for soun is the zero on the bridge at the left bank.

The gage was read once each day during the irrigation season of 1905 by Rudolph Fr who lives 300 yards distant. It is a vertical board driven into the bed of the canal a 500 feet below the head gates and just at the footbridge from which the disch measurements are made. The gage is referred to bench marks as follows: (1) A spike di in the top of a 6 by 6 inch post on the left side of the downstream end of the head g elevation, 7.29 feet. (2) A spike in the southwest side of a 12-inch post 40 feet south o south end of the dam and 28 paces east of bench mark No. 1; elevation, 7.38 feet. El tions are above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Pa of the United States Geological Survey:

Description: 99, p 107; 130, p 105.
Discharge: 99, p 107; 130, p 105.
Discharge, daily: 130, p 106.
Discharge, monthly: 130, p 106.
Gage heights: 99, p 107.

Discharge measurements of Paradise Valley canal near Chinook, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D cha
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sc*
April 8	L. R. Stockman	11	5.0	0.70	0.45	
April 24	Stockman and Morse	20	11.5	.87	.76	
May 17	H. M. Morse	18	9.3	.71	.81	
June 3	....do	20	14.6	.54	1.08	
June 17	Stockman and Prall	18	11.0	.43	.98	
June 24	C. T. Prall	18	11.3	.48	1.01	
June 24	....do	18	13.0	.39	1.02	
July 8	Freeman and Morse	18	12.5	.38	1.09	
July 15	C. T. Prall	17	11.0	.31	.98	
July 21	W. B. Freeman	18	11.6	.44	1.01	
July 27	H. M. Morse	19	20.0	.53	1.37	
August 5	W. B. Freeman	9	2.6	.26	.50	

ge height, in feet, and discharge, in second feet, of Paradise Valley canal near Chinook Mont., for 1905.

March.		April.		May.		June.		July.		August.	
Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
.....	.....	0.17	1	0.47	4	1.14	8	1.24	8	0.57	1.0
.....	.....	.15	.5	.56	6	1.17	8	1.30	9	.50	.5
.....	.....	.15	.5	.67	8	1.12	8	1.21	7	.49	.5
.....	.....	.40	3	.78	10	1.05	7	1.21	7	.44	.5
.....	.....	.46	4	.92	13	1.11	8	1.20	7	.50	.5
.....	.....	.47	4	1.17	19	1.15	10	1.19	7	.48	.5
.....	.....	.47	4	1.09	17	1.20	11	1.22	7	.45	.5
.....	.....	.42	3	1.08	17	1.50	16	.92	4	.45	.5
.....	.....	.42	3	1.11	17	1.20	11	1.54	15	.44	.5
.....	.....	.54	5	1.08	17	1.03	6	1.14	6	.43	.5
.....	.....	.75	10	1.13	18	1.08	8	.68	2	.41	.5
.....	.....	1.08	17	1.09	17	1.11	8	.89	3	.40	.3
.....	.....	1.10	17	1.10	17	1.19	11	.90	3	.39	.3
.....	.....	1.02	15	1.17	19	1.04	7	.95	4	.35	.2
.....	.....	.98	15	.84	7	1.07	7	.97	4	.30	.2
.....	.....	.92	13	.81	6.5	1.02	6	1.10	6	.20	.1
.....	.....	.86	12	.78	6.5	.98	5	1.13	6	.10	.....
.....	.....	1.08	17	.82	6.5	.98	5	1.13	6	.....	.....
.....	.....	1.08	17	.80	6.5	.96	4	1.05	5	.....	.....
.....	.....	1.11	17	.80	6.5	1.01	5	1.06	5	.....	.....
.....	.....	1.01	15	.80	6.5	.96	4	1.05	5	.....	.....
.....	.....	.84	12	.82	6.5	.94	4	.94	4	.....	.....
.....	.....	.83	11	.90	7	.94	4	.81	3	.....	.....
.....	.....	.78	10	1.12	8	1.00	5	.73	2	.....	.....
.....	.....	.71	9	1.09	8	1.09	6	.66	2	.....	.....
0.21	1	.64	8	1.11	8	1.09	6	.65	2	.....	.....
.23	1	.49	4	1.07	8	1.15	6	1.60	17	.....	.....
.42	3	.48	4	1.10	8	1.36	10	1.40	11	.....	.....
.48	4	.45	4	1.09	8	1.22	7	1.33	9	.....	.....
.30	2	.41	3	1.10	8	1.25	8	.85	3	.....	.....
.24	1	.....	.....	1.11	8	.....	.....	.69	2	.....	.....

mated monthly discharge of Paradise Valley canal near Chinook, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
31.....	4	1	2	24
.....	17	.5	9	536
.....	19	4	10	615
.....	16	4	7	417
.....	17	2	6	369
.....	1	.1	.4	13
period.....	.....	.....	.....	1,974

COOK CANAL NEAR CHINOOK, MONT.

This canal diverts water from North Fork of Milk River, one of the most constant tributaries of that stream. The head-gates are situated about 3 miles east of Chinook, Mont., and the course of the canal is nearly due south for about 2 miles, beyond which it turns to the east and crosses to the south side of the river, where the greater part of the lands irrigated by the canal are situated.

The station was established April 10, 1905. It is located at a small wooden highway bridge on the road running parallel to the Great Northern Railway about 3 miles east of Chinook.

The channel is straight for 25 feet above and 300 feet below the station, there being a right-angled turn directly above the bridge. The banks are of earth fill and are above the level of the surrounding lands. The bed of the stream is composed of soft mud covered with vegetation, and is permanent. The water has a depth of about 3 feet at ordinary stages and the velocity is low.

Discharge measurements are made from the lower side of the bridge. The initial point for soundings is a paint mark on the floor of the bridge, directly over the right abutment on the downstream side.

The gage, which was read once each day during the irrigation season of 1905 by George W. Hartman, is a vertical rod driven into the bed of the canal near the left bank about one-fourth mile above the bridge. The bench mark is a spike in the west side of a post in the fence just east of the canal; elevation, 4.61 feet above the datum of the gage.

Discharge measurements of Cook canal near Chinook, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec. ft.*
April 10	L. R. Stockman	14	32.8	1.15	3.4	37.7
April 24	Stockman and Morse	13	30.4	1.16	3.28	35.5
May 17	H. M. Morse	13	29.0	.92	3.18	26.7
June 3	do	14	28.2	.72	3.02	20.6
June 17	Stockman and Prall	14	27.0	.80	2.98	21.5
June 24	C. T. Prall	14	30.2	1.01	3.26	30.6
July 3	Babb and Prall	14	17.3	.17	2.39	3.0
July 7	W. B. Freeman	14	17.9	.13	2.22	2.3
July 15	C. T. Prall	14	25.0	.54	2.80	13.4
August 5	W. B. Freeman	14	27.0	.64	2.93	17.6
August 11	H. M. Morse	14	19.0	.30	2.45	6.0

ge heights, in feet, and discharge, in second-feet, of Cook canal near Chinook, Mont., for 1905.

ay.	April.		May.		June.		July.		August.	
	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
.....	.....	.....	3.7	50	1.9	0	.....	0	2.95	19
.....	.....	.....	3.7	50	1.9	0	.....	0	3.0	21
.....	.....	.....	3.65	47	3.02	21	2.39	4	2.9	17
.....	.....	.....	3.6	45	1.8	0	.....	4	2.4	4
.....	.....	.....	.....	0	1.8	0	.....	3	2.93	17
.....	.....	.....	.....	0	1.7	0	.....	2	2.3	3
.....	.....	.....	.....	0	2.0	0	2.22	2	2.4	4
.....	.....	.....	.....	0	3.2	29	2.15	1	2.4	4
.....	.....	.....	.....	0	3.1	25	3.1	25	2.4	4
.....	3.4	38	.....	0	3.1	25	3.0	21	2.3	3
.....	.....	.....	2.75	12	3.1	25	2.9	17	2.45	5
.....	.....	.....	2.8	13	3.2	29	2.1	0	2.4	4
.....	.....	.....	2.95	19	3.2	29	1.2	0	2.0	0
.....	.....	.....	3.0	21	3.1	25	1.3	0	1.75	0
.....	.....	.....	3.1	25	3.0	21	2.8	13	1.7	0
.....	.....	.....	3.15	27	3.1	25	1.3	0	1.7	0
.....	.....	.....	3.2	29	3.0	21	1.3	0	1.5	0
.....	.....	.....	3.15	27	3.0	21	1.3	0	1.55	0
.....	.....	.....	3.2	29	2.9	17	1.25	0	1.82	0
.....	.....	.....	3.1	25	2.9	17	1.2	0	1.4	0
.....	.....	.....	3.15	27	2.9	17	1.9	0	1.4	0
.....	.....	.....	3.1	25	2.9	17	1.25	0	1.35	0
.....	.....	.....	2.6	8	3.0	21	1.2	0	1.35	0
.....	3.28	36	2.0	0	3.1	25	1.2	0	1 3	0
.....	.....	.....	2.0	0	3.3	33	1.2	0	1.25	0
.....	.....	.....	2.0	0	2.9	17	1.3	0	.....	.....
.....	.....	.....	2.0	0	2.9	17	2.4	4	.....	.....
.....	.....	.....	2.0	0	2.9	17	2.6	8	.....	.....
.....	.....	.....	1.95	0	2.2	2	2.8	13	.....	.....
.....	.....	.....	1.9	0	.....	0	2.8	13	.....	.....
.....	.....	.....	1.9	0	.....	.....	2.7	10	.....	.....

Estimated monthly discharge of Cook canal near Chinook, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	.....	.....	[a] 37.0	2,202
.....	50	0	15.5	953
.....	33	0	16.5	982
.....	25	0	4.5	277
1-12.....	21	0	9.0	214
ie period.....	.....	.....	.....	4,628

[a] Estimated.

MATHESON CANAL NEAR CHINOOK, MONT.

This canal diverts water from the south side of North Fork of Milk River. The head-gates are situated about 3½ miles east of Chinook, Mont., and about three-fourths of a mile below the head of the Cook canal. The general course of the canal is easterly and the irrigated lands under it lie along the Great Northern Railway.

The station was established April 10, 1905. It is located at a footbridge 200 feet below the head-gates.

The channel is straight for 200 feet above and below the station. The canal is in a cut and the banks are high; the right is covered with willows and the left with brush. The bed is composed of sand and is covered with vegetation. The velocity is about 1.4 feet per second when the canal is running full.

Discharge measurements are made from the bridge. The initial point for soundings is at the extreme end of the bridge timbers on the right bank.

The gage, which was read once each day during the irrigation season by H. C. Reynolds, is a vertical rod driven into the bed of the canal immediately below the bridge. The gage is referred to bench marks as follows: (1) A 60-penny nail in the root of a 5-inch willow tree, 180 feet south of the head-gates of the canal; elevation, 9.58 feet above the datum of the gage. (2) A nail in a 3-inch willow tree, 180 feet south of the head of the canal, east of bench mark No. 1 and across the road from it; elevation, 9.34 feet above the datum of the gage.

Discharge measurements of Matheson canal near Chinook, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 10	L. R. Stockman	11.0	18.3	1.42	3.15	25.9
April 24	Stockman and Morse	9.3	8.2	.83	2.1	6.8
May 17	H. M. Morse	7.5	5.0	.58	1.76	2.9
June 3	do	9.5	11.8	.68	2.52	8.0
June 17	Stockman and Prall	10.0	15.2	.60	2.85	9.1
June 23	C. T. Prall	10.0	18.6	.68	3.17	12.7
June 23	do	10.0	17.0	.68	3.05	11.5
July 8	Freeman and Morse	.....	5.6	.13	1.85	.7
July 15	C. T. Prall	9.2	10.0	.42	2.29	4.0
July 21	W. B. Freeman	8.0	4.0	.11	1.76	.5
July 27	H. M. Morse	10.0	13.0	.63	2.72	8.0
August 11	do	8.0	4.8	.24	1.79	1.0
August 19	C. T. Prall	.....	.....	.....	1.45	.25

NOTE.—Grass removed from canal bed after June 23.

height, in feet, and discharge, in second-feet, of Matheson canal near Chinook, Mont., for 1905.

	April.		May.		June.		July.		August.	
	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
	.....	26	3.25	28	2.8	9	.....	7	1.6	0.5
	.....	26	2.88	20	2.7	8.5	.....	7	1.55	.4
	.....	26	3.2	27	2.7	8.5	2.38	5	1.5	.3
	.....	26	2.88	20	2.7	8.5	2.5	6	1.5	.3
	.....	26	2.8	18	2.7	8.5	2.0	2	1.5	.3
	.....	26	2.8	18	2.65	8.5	2.0	2	1.5	.3
	.....	26	2.7	16	2.65	8.5	1.9	1	1.3	.0
	.....	26	2.62	15	2.65	8.5	1.8	1	1.2	.0
	.....	26	2.6	14	2.65	8.5	2.3	4	1.7	.0
	3.2	27	2.45	12	2.65	8.5	2.85	9	1.8	1.0
	3.2	27	2.28	9	2.6	8	2.8	9	1.8	1.0
	3.15	26	2.25	9	2.6	8	2.6	7	1.7	.7
	3.12	25	.....	7.5	2.6	8	2.5	6	1.65	.5
	2.96	21	.....	6	2.65	8	2.3	4	1.5	.3
	2.7	16	.....	5	2.65	8	2.25	4	1.5	.3
	2.65	15	.....	4	2.6	8	2.45	5	1.5	.3
	2.6	14	1.76	3	2.85	9	2.4	5	1.7	.7
	2.58	14	2.1	7	2.6	7	1.8	1	1.7	.7
	2.55	13	2.22	8	2.5	6	1.8	1	1.6	.5
	2.55	13	2.72	8.5	2.5	6	1.85	1	1.5	.3
	2.55	13	2.8	9	2.7	8	1.8	1	1.5	.3
	2.9	20	2.92	9	2.7	8	2.2	3	1.65	.6
	3.0	22	2.6	8	3.1	12	1.8	1	.....	.....
	2.1	7	2.55	8	3.0	11	1.8	1	.....	.....
	2.0	6	2.62	8	3.0	11	1.8	1	.....	.....
	2.05	6	2.6	8	2.9	10	2.45	5	.....	.....
	2.05	6	2.7	8.5	2.8	9	2.72	8	.....	.....
	2.1	7	2.75	9	2.85	9	1.85	1	.....	.....
	3.05	23	2.8	9	2.6	7	1.7	1	.....	.....
	3.18	27	2.8	9	3.0	11	1.6	.5	.....	.....
	.....	.....	2.8	9	.....	.....	1.6	.5	.....	.....

-Discharge April 1–9 estimated.

Estimated monthly discharge of Matheson canal near Chinook, Mont., in 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	27	6.0	19.0	1,131
.....	28	3.0	11.0	676
.....	12	6.0	9.0	536
.....	9	.5	3.5	215
-22.....	1	0	.4	17
e period.....	.....	.....	.....	2,575

HARLEM CANAL NEAR ZURICH, MONT.

The Harlem canal is owned by a corporation composed of farmers and is used to irrigate a considerable area of bottom lands near Harlem. It diverts water from the north side of Milk River about 10½ miles below Chinook and flows eastward about 12 miles.

The station was established in June, 1903. It is located about 500 feet below the head-gates of the canal, which are 1½ miles southeast of the Great Northern Railway section house at Zurich and is best reached by driving from Harlem or Chinook.

Discharge measurements are made by wading at the gage. The initial point for soundings is a stake driven into the left bank, near the gage. Flood measurements can be made from a small highway bridge 2 miles below.

The gage was read daily during the irrigation season of 1905 by John Palm, who lives about one-half mile below. It is a vertical board driven into the bed of the canal. The bench-mark is a spike in the downstream face of a 6 by 8 inch post at the left bank, on the downstream side of the head-gate. The spike is 0.8 foot below the top of the cross piece and has an elevation of 11.89 feet above the gage datum.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 106; 130, pp 106–107.
Discharge: 99, pp 106, 136; 130, p 107.
Discharge, monthly, 130, p 108.
Gage heights: 130, p 107.
Rating table: 130, p 108.

Discharge measurements of Harlem canal near Zurich, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 8	L. R. Stockman	16	26	0.4	1.35	10.5
April 24	Stockman and Morse	17	27	.54	1.12	15.0
May 17	H. M. Morse	20	36	.52	1.38	19.0
June 3	do	16	24	.81	1.58	19.0
June 17	Stockman and Prall	19	32	.23	.98	7.3
June 24	C. T. Prall	13	10	.25	.68	2.5
July 8	Freeman and Morse	.....	35	.74	2.21	26.0
July 15	C. T. Prall	.....	20	.51	1.35	10.0
July 21	W. B. Freeman	.....	15	.35	1.05	5.3
July 27	H. M. Morse	.....	52	.97	2.96	51.0
August 5	W. B. Freeman	.....	7	.15	.45	a1.2
August 11	H. M. Morse	.....	20	.67	1.37	14.0

a Leakage through gates.

gage heights, in feet, and discharge, in second-feet, of Harlem canal near Zurich, Mont., for 1905.

	March.		April.		May.		June.		July.		August.	
	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
	.....	.....	1.93	21	1.0	12	1.6	19	1.4	15	1.35	18
	.....	.....	1.93	21	.9	10	1.6	19	1.6	19	.....	0
	.....	.....	1.93	21	.9	10	1.6	19	1.98	22	.....	0
	.....	.....	1.53	14	.8	8	1.5	17	.....	25	.....	0
	2.33	28	1.43	12	.8	8	1.3	13	2.3	28	.45	1
	2.33	28	1.43	12	1.1	14	1.0	8	2.1	24	1.4	15
	2.43	30	1.33	10	.....	17	.9	6	2.28	28	1.2	11
	2.43	30	1.33	10	1.5	21	1.1	10	2.41	30	1.2	11
	2.53	32	1.10	6	1.7	25	1.3	13	2.4	30	1.4	15
	2.43	30	1.10	6	1.8	27	1.6	19	2.45	31	1.5	1.
	2.33	30	1.65	16	1.8	27	1.4	15	2.12	24	1.35	14
	2.73	36	2.50	32	1.75	26	1.2	11	1.96	21	1.25	12
	2.83	38	2.50	32	1.7	25	1.15	10	1.78	18	1.2	11
	2.63	34	2.50	32	1.6	23	1.3	13	1.5	13	1.1	10
	.....	0	2.40	30	1.6	23	1.1	10	1.4	11	.95	7
	2.13	25	2.40	30	1.35	18	1.05	9	1.22	8	.85	5
	.....	0	2.40	30	1.2	15	.98	7	1.17	7	.8	4
	.....	0	1.80	27	1.1	14	.9	6	1.1	6	2.0	26
	2.33	28	1.60	23	1.1	14	.8	4	1.05	5	.85	5
	2.33	28	1.45	20	.85	9	.78	4	1.05	5	.....	0
	2.43	30	1.40	19	.75	7	.75	4	1.0	5	.....	.....
	2.63	34	1.30	17	.8	8	.74	4	1.0	5	.....	.....
	2.33	28	1.20	15	.9	10	.70	3	.98	4	.....	.....
	2.33	28	1.10	14	1.0	12	.68	3	.9	3	.....	.....
	2.23	27	1.10	14	1.15	14	.68	3	.87	3	.....	.....
	2.03	23	1.20	15	1.3	13	.65	2	1.6	15	.....	.....
	2.03	23	1.20	15	1.4	15	.65	2	2.83	48	.....	.....
	2.03	23	1.10	14	.....	16	.85	5	4.05	73	.....	.....
	2.13	25	1.00	12	1.5	17	1.10	10	3.2	56	.....	.....
	2.13	25	1.00	12	1.6	19	1.20	13	1.75	26	.....	.....
	2.13	25	.....	.....	1.6	19	.....	.....	1.5	21	.....	.....

Estimated monthly discharge of Harlem canal near Zurich, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
5–31	38	0	25.5	1,366
	32	6	18	1,071
	27	7	16	984
	19	2	9	536
	73	3	20	1,230
t 1–19	26	0	10	377
The period				5,564

AGENCY DITCH NEAR HARLEM, MONT.

s canal was built by the United States Indian Office and is used for the irrigation of n the Fort Belknap Indian Reservation. It diverts water from the south side of Milk flows southward and eastward for about 11 miles, and has several laterals of consider- ize. The head gates are situated near the agency buildings, about 4 miles south of n, Mont.

The station was established July 14, 1905. It is located at the highway bridge about one-fourth of a mile below the head gates.

The channel is straight for 300 feet above and below the station. Both banks are high and have slopes of about 1½ to 1. The bed of the canal is composed of firm earth, comparatively free from vegetation, and is permanent.

Discharge measurements are made from the downstream side of the wooden-truss bridge, which has a span of 45 feet. The initial point for soundings is a nail at the end of the downstream lower chord of the bridge at the right bank.

The gage, which was read gratuitously once each day during the irrigation season by C. M. Zeibach, chief clerk of the agency, is a vertical rod driven into the bed of the canal 15 feet below the bridge and 5 feet from the right bank. The gage is referred to bench marks as follows: (1) The head of a 60-penny spike driven vertically into an 8 by 8 inch timber on the south end and lower side of the bridge; elevation, 12.68 feet above the zero of the gage. (2) The highest point on a large granite bowlder at the north end and lower side of the bridge; elevation above the zero of the gage, 14.51 feet.

Discharge measurements of Agency ditch near Harlem, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
July 14	Prall and Freeman	20	30	0.81	3.24	24
July 28	W. B. Freeman	24	67	.77	4.82	[a]52
July 28	do	24	60	1.04	4.53	63
August 4	C. T. Prall	24	54	.55	4.3	[a]29
August 17	do	22	44	.33	3.8	[a]14
August 25	do	18	18	1.01	2.5	18
September 5	W. B. Freeman	14	4	.4	1.75	2

[a] Backwater.

Daily gage height, in feet, and discharge, in second feet, of Agency ditch near Harlem, Mont., in 1905.

Day.	July.		August.		September.		Day.	July.		August.		September.	
	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.		Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
1		0	4.4	33	1.9	5	17	3.1	21	3.8	14		
2		0	4.3	29		4	18	2.9	16	3.7	12		
3		0	4.3	29		3	19	2.7	12	3.6	11		
4		0	4.3	29	1.8	3	20	2.6	10	3.5	9		
5		0	4.2	25	1.75	2	21	2.5	8	3.4	8		
6		0	4.2	25		2	22	2.5	8	3.3	8		
7		0	4.2	25		1	23	2.5	8	3.2	7		
8		0	4.2	25		1	24	2.0	2	3.15	6		
9		32	4.2	25		0	25	1.8		2.5	18		
10		32	4.2	25		0	26	1.7			16		
11		32	4.1	22		0	27	1.6	0		14		
12		32	4.1	22			28	4.8	63		11		
13		29	4.1	22			29	5.2	52		9		
14	3.32	27	4.0	19			30	5.3	52		7		
15	2.9	16	3.95	18			31	4.8	51		5		
16	3.1	21	3.9	16									

imated monthly discharge of Agency ditch near Harlem, Mont., in 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	63	0	23	1,049
.....	33	5	18	1,107
8.....	5	1	3	48
iod.....	.....	.....	.....	2,204

FORT BELKNAP CANAL NEAR CHINOOK, MONT.

Belknap canal is owned by a corporation composed of farmers and is used for
n of extensive areas of bottom lands near Chinook, Mont. It diverts water from
de of Milk River about 8 miles above Chinook.
on was established June 21, 1903. It is located at the highway crossing 1 mile
ead gates of the canal and is reached by driving.
nel is curved above and straight below the station. Both banks are sloping, and
omposed of sand and gravel.
measurements are made from the wooden highway bridge, to which the gage is
The initial point for soundings is a spike 15 feet from the gage on the down-
l rail.
was read daily until August 12, 1905, by D. E. Martin, and from that date to the
rrigation season by Morris Jones. The original gage was a vertical board fas-
downstream chord of the highway bridge. This was replaced July 28, 1905, by
riven into the bed of the canal just below the bridge, the same datum being used.
referred to bench marks as follows: (1) A nail at the base of a large cottonwood
t southeast of the gage; elevation, 3.91 feet above the zero of the gage and
t above sea level. (2) A nail in a telephone pole 30 feet northeast of the bridge;
57 feet above gage datum and 2,431.46 feet above sea level. This gage datum is
gher than that of 1903.
on in regard to this station is contained in the following Water-Supply Papers
d States Geological Survey:

; 99, pp 107-108; 130, p 103.
99, p 108; 130, p 104.
monthly: 130, p 105.
s; 99, p. 108; 130, p. 104.
e; 130, p 104.

Discharge measurements of Fort Belknap canal near Chinook, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di cha
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-*
April 10	L. R. Stockman	30.0	51	1.00	2.83	
April 22	do	33.5	55	1.17	2.92	
May 19	H. M. Morse	28.0	46	1.01	2.70	
June 16	Stockman and Prall	27.5	42	.67	2.60	
July 1	H. M. Morse	36.0	63	1.08	3.18	
July 12	C. T. Prall	28.0	42	.52	2.57	
July 20	W. B. Freeman	.....	14	.35	1.50	
July 28	H. M. Morse	.....	86	1.51	3.62	
July 29	do	.....	37	1.49	2.35	
August 3	C. T. Prall	.....	42	1.49	2.68	
August 3[a]	do	.....	56	1.22	3.00	
August 8	W. B. Freeman	.....	60	.98	3.16	
August 15	H. M. Morse	.....	41	.37	2.62	
August 23	C. T. Prall	.....	.....	.....	.65	

[a] Affected by backwater from check in canal. [b] Estimated.

Daily gage heights, in feet, and discharge, in second-feet, of Fort Belknap canal near Chino Mont., for 1905.

Day.	March.		April.		May.		June.		July.		August.	
	Gage height.	Dis-charge.	Gage height.	Dis-charge.	Gage height.	Dis-charge.	Gage height.	Dis-charge.	Gage height.	Dis-charge.	Gage height.	Di cha
1	.....	.....	3.25	82	3.1	73	2.7	48	3.18	68	2.5	
2	.....	.....	3.15	76	3.1	73	2.9	60	.....	55	2.5	
3	.....	.....	3.05	70	3.0	66	2.9	60	2.8	39	3.0	
4	.....	.....	3.05	70	3.0	66	2.7	48	2.8	39	3.0	
5	.....	.....	2.95	63	2.9	60	2.6	46	2.8	39	3.3	
6	.....	.....	2.95	63	2.9	60	2.7	44	2.9	47	3.3	
7	.....	.....	2.95	63	3.0	66	2.7	42	3.0	54	3.3	
8	.....	.....	2.85	57	2.9	60	2.7	40	3.1	62	3.2	
9	.....	.....	2.95	63	2.9	60	2.7	38	3.0	54	3.1	
10	.....	.....	3.05	56	2.9	60	2.7	36	2.9	47	3.0	
11	.....	.....	2.8	54	2.9	60	2.7	34	2.8	39	2.9	
12	.....	.....	2.9	60	2.9	60	2.7	32	2.7	32	2.8	
13	.....	.....	2.9	60	2.8	54	.....	31	2.6	24	.....	
14	.....	.....	2.9	60	2.9	60	.....	30	2.5	20	.....	
15	.....	.....	3.0	66	2.8	54	.....	29	2.4	18	2.6	
16	.....	.....	3.0	66	2.8	54	2.6	28	.....	14	2.4	
17	.....	.....	3.0	66	2.7	48	.....	27	.....	11	2.0	
18	.....	.....	3.0	66	2.7	48	.....	26	.....	8	1.5	
19	.....	.....	3.0	66	2.7	48	2.6	25	.....	7	1.1	
20	.....	.....	3.1	73	2.7	48	2.5	24	1.5	5	1.0	
21	.....	.....	3.0	66	2.5	36	2.5	23	.....	5	.9	
22	.....	.....	2.92	64	2.7	48	2.5	22	.....	4	.8	
23	.....	.....	3.0	66	3.0	66	2.45	21	.....	4	.7	
24	.....	.....	3.0	66	3.1	73	2.45	20	.....	4	.6	
25	.....	.....	3.0	66	3.2	79	.....	19	.....	3	.6	
26	.....	.....	3.0	66	3.1	73	.....	18	.....	3	.6	
27	3.35	100	3.0	66	3.0	66	.....	17	.....	3	.6	
28	3.45	94	2.9	60	2.9	60	.....	16	3.62	130	.6	
29	3.35	88	3.1	73	2.9	60	.....	30	2.35	55	.6	
30	3.25	82	3.2	79	2.8	54	.....	40	2.6	70	.6	
31	3.25	82	.....	.....	2.8	54	.....	.....	2.6	70	.6	

Estimated monthly discharge of Fort Belknap canal near Chinook, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
arch 27–31	100	82	89	883
pril	82	54	66	3,927
ay	79	36	60	3,689
une	60	16	32	1,904
uly	130	3	33	2,029
ugust	65	1	25	1,537
The period				13,970

RESER DITCH NEAR CHINOOK, MONT.

The Reser ditch diverts water from West Fork of Milk River at a point about 12 miles northwest of Chinook. The original dam and some dikes were constructed in 1900, but were destroyed by floods the same year. The present dam was built in 1904 and the ditch was completed and first used in April, 1905. It is designed to serve about 400 acres of land owned by A. H. and E. T. Reser.

A temporary gaging station was established July 10, 1905. It is located about 1 mile below the head-gates of the ditch.

A gage rod, which was observed by A. H. Reser, who furnished the records gratuitously, was driven into the bottom of the ditch about 10 feet above the measuring section. A bench mark was established on the chipped point of a large granite bowlder 75 feet south of the ditch and 250 feet west of the station; elevation of bench mark above the datum of the gage, 3.82 feet.

The ditch was dry during a considerable part of the irrigation season, and for this reason but two measurements of discharge were secured. It was visited five times between June 21 and August 2 by various employees of the Reclamation Service.

Discharge measurements of Reser ditch near Chinook, Mont., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Sq. ft.	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
July 10	C. T. Prall	8.6	0.69	2.50	5.9
August 2	W. B. Freeman	8.1	.79	2.53	6.4

Daily gage height, in feet, and discharge in second-feet of Reser ditch near Chinook, Mont., for 1905.

Day.	April.		May.		June.		July.		August.	
	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
1				3		3		0	2.6	7
2				3		3		0	2.6	7
3				3		3		0	2.6	7
4				3		3		0	2.6	7
5				3		3		0	2.6	6
6				3		3		0		6
7				3		3		0	2.5	6
8				3		3		0	2.5	6
9		[a]3		3		3		0	2.5	6
10		3		3		3	2.5	6		6
11		3		3		3		6		6
12		3		3		3	2.5	6		6
13		3		3		3	2.4	5		6
14		3		3		3	2.7	8		6
15		3		3		3	2.4	5		6
16		3		3			2.3	4		6
17		3		3				0		6
18		3		3				0		6
19		3		3				0		6
20		3		3				0		6
21		3		3		0		0		6
22		3		3		0		0		6
23		3		3		0		0		6
24		3		3		0		0		6
25		3		3		0		0		6
26		3		3		0		0		6
27		3		3		0		0		6
28		3		3		0		0		6
29		3		3		0		0		6
30		3		3		0		0		6
31				3		0	2.5	6		6

[a] Estimated April 9–June 15.

Estimated monthly discharge of Reser ditch near Chinook, Mont., in 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April 9–30			[a]3.0	131
May			[a]3.0	184
June 1–15			[a]3.0	90
July	8	0	1.5	92
August	7	0	1.9	114
The period	8	0		611

[a] Estimated.

WEST FORK DITCH NEAR CHINOOK, MONT.

The West Fork ditch diverts water from West Fork of Milk River about 4 miles north of Chinook, Mont. In 1898 a dam was constructed at this point and a ditch which irrigated about 75 acres. The ditch was extended in subsequent years and now serves, it is claimed, several hundred acres of land. A new dam was constructed in 1904 near the original location. Several individuals were at first interested in the West Fork ditch, but it is now controlled exclusively by the Empire Cattle Company.

A temporary gaging station was established on this ditch June 16, 1905, about 200 feet below the head-gates.

A gage rod was driven into the bottom of the ditch at the measuring section. It was referred to a bench mark consisting of a 20-penny nail driven vertically into a 6 by 12 inch timber on the lower side of the head-gates at left bank; elevation above the datum of the gage, 5.50 feet.

An injunction was served on the owners of this ditch in the latter part of June and the water was turned off until July 11. Several measurements of discharge were made, the results of which are given below:

Discharge measurements of West Fork ditch near Chinook, Mont., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Sq. ft.	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
June 16	Prall and Stockman	7	0.84	2.80	5.9
July 11	Prall and Morse	14	.90	3.43	12.6
July 18	W. B. Freeman	.....	.....	1.70	[a].1
August 2	.....do	11.5	1.03	3.55	12.0
August 10	.....do	12.8	1.03	3.50	13.0
August 15	H. M. Morse	6.8	.97	2.90	6.6

[a] Estimated.

Daily gage heights, in feet, and discharge, in second-feet, of West Fork ditch near Chinook, Mont., for 1905.

Day.	June.		July.		August.	
	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
1		a8.5		0		a12
2		a8.5		0	3.35	12
3		a8.5		0		a12
4		a8.0		0		a12
5		a8.0		0		a12
6		a8.0		0		a12
7		a7.5		0		a12
8		a7.5		0		a13
9		a7.5	0	0		a13
10		a7.0		a13	3.5	13
11		a7.0	3.43	12		a12
12		a7.0		a13		a12
13		a6.0		a13		a10
14		a6.0		a11		a8.6
15		a6.0		a9	2.9	6
16	2.8	5.9		a7		a5
17		4.3		a0		a4
18		3.0	1.7	0.1		0
19		2.0		0		0
20		1.0		0		0
21	0	0		0		0
22		0		0		0
23		0		0	.0	0
24		0		0		0
25		0		0		0
26		0		0		0
27		0		0		0
28		0		0		0
29		0	.0	0		0
30		0		0		0
31				12		0

a Estimated.

Estimated monthly discharge of West Fork ditch near Chinook, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
June	8.5	0	4.2	250
July	13.0	0	2.9	179
August	13.0	0	5.9	364

DOWEN & BUCKLEY DITCH NEAR CHINOOK, MONT.

This ditch, which heads in Canada about 150 feet north of the international boundary, diverts water from North Fork of Milk River at a point about 30 miles north of Chinook, Mont.

Construction was begun on the dam and ditch in 1902, and the works now consist of an earth and rock dam, three flumes, and about 2 miles of ditch. About 40 acres of land were irrigated from the ditch in 1905, and it is probable that 150 acres will ultimately be reclaimed. The water filing attaching to this ditch is for a flow of 12 second-feet, but the

ners testified in a lawsuit that only 50 miner's inches, or 1.25 second-feet, have ever been verted. September 20, 1905, the ditch was visited and a cross section and the slope were termined, from which the capacity of the ditch was estimated at 7.5 second-feet.

ROKITA DITCH NEAR CHINOOK, MONT.

The Rokita ditch diverts water from North Fork of Milk River at a point about 27 miles rth of Chinook, Mont. The dam is well constructed of earth and rock, and the ditch is bout 2 miles long. About 40 acres are irrigated at present, but more land will soon be rought under the ditch. Information is lacking in regard to the date and amount of ater filing, as well as the date on which construction was commenced.

This ditch was visited September 20, 1905, and a cross section and the slope were measured, from which the capacity is estimated at 6 second-feet.

CORREGAN DITCH NEAR CHINOOK, MONT.

The Corregan dam is located in North Fork of Milk River at a point about 22 miles north of Chinook, Mont., and 8 miles below the Dowen & Buckley dam. The head-gates are 5 feet wide and 2.5 high, and the ditch is completed for 2 miles. The upper 1,500 feet are located in a slough, and the ditch is carried across North Fork in a flume about 150 feet long. An appropriation of 20 second-feet was made in October, 1901, and construction was begun on the ditch in 1902. About 55 acres of land are being served at present and probably 150 acres will eventually be irrigated from this ditch. Henry Corregan testified in court that he has used about 100 miner's inches, or 2.5 second-feet, since 1902.

The ditch was visited September 20, 1905, and cross sections and slopes were taken at two different points, from which the capacity of the ditch is estimated at 6 second-feet.

WINTER-ANDERSON CANAL NEAR CHINOOK, MONT.

This canal diverts water from the south side of Milk River at a point about 3 miles southeast of Chinook, Mont. Construction was begun in October, 1900, and a filing was made at that time for 100 second-feet of water. An appropriation of 12 second-feet, dating back to March, 1896, is also claimed for this ditch by Henry Winter. This appropriation was originally made by other parties, whose rights were acquired by Winter in September, 1896. Probably 2,500 acres could be irrigated from the Winter-Anderson canal, but it carried no water during 1905.

This canal was visited October 11, 1905, and from the cross section and slope which were then taken the capacity of the canal was estimated at 45 second-feet.

PARALLEL CREEK DITCHES NEAR HARLEM, MONT.

In the vicinity of Harlem, Mont., are a number of ditches used to divert water from Parallel Creek, a stream which usually discharges a large amount of water in March and April, but goes dry early in the season. A considerable body of land is irrigated from this creek.

The principal ditches are the Nystrom, Fox, Everett & Smith Company, and Forbes.

ROCK CREEK CANAL NEAR HINSDALE, MONT.

This canal is owned by a corporation composed of farmers in the lower Milk River Valley. It diverts water from the east side of Rock Creek, a tributary of Milk River from the north. The head-gates are situated about 7 miles north of Hinsdale, Mont, and the general course of the canal is southerly. The canal is used to irrigate extensive areas north of the river and east of Rock Creek.

The gaging station was established July 5, 1905. It is located about 300 feet below the head-gates of the canal.

The channel is straight for 100 yards above and 200 yards below the section. Both banks are nearly vertical and are composed of earth. The bed is composed of soft mud, with a

very small amount of vegetation, and probably shifts slightly. The current has a veloci of about 1 foot per second in ordinary stages.

Discharge measurements are made by wading about 10 feet below the gage. The initi point for soundings is a stake set in the west bank about 2 feet from the water's edge.

The gage, which was read twice each day by F. E. Halbert from the time of its establis ment to the end of the irrigation season, is a vertical rod driven into the bed of the can near the left bank. The gage is referred to bench marks as follows: (1) The head of a 1 penny nail driven into a notch cut in a large cottonwood tree 100 feet east of the gage; el vation, 8.43 feet above the datum of the gage. (2) The head of a 10-penny nail driven into notch cut in a large cottonwood tree 150 feet northeast of the gage; elevation, 8.74 feet abov the datum of the gage.

Discharge measurements of Rock Creek canal near Hinsdale, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis- charge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-f*
July 5	C. T. Prall	24.5	30.1	1.02	1.0	3
July 24	W. B. Freeman	21.5	9.4	.26	.19	
August 12	do	21.5	13.1	.51	.3	

Daily gage heights, in feet, and discharge, in second-feet, of Rock Creek canal, near Hinsd Mont., for 1905.

Day.	July.		August.		Day.	July.		August.	
	Gage height.	Dis- charge.	Gage height.	Dis- charge.		Gage height.	Dis- charge.	Gage height.	Di cha
1		31	1.25	41	17	0.68	18	0.2	
2		31	.95	29	18	.5	12		
3		31	.9	27	19	.4	9		
4		31	.8	23	20	.38	8		
5	1.0	31	.7	19	21	.3	6		
6	.95	20	.65	17	22	.25	5		
7	1.0	31	.58	15	23	.25	5		
8	.95	29	.5	12	24	.2	3		
9	.85	25	.42	9	25	.1	1		
10	.7	19	.4	9	26	1.4	48		
11	.65	17	.35	7	27	1.4	48		
12	.62	16	.3	6	28	1.25	41		
13	.5	12	.25	5	29	1.3	44		
14	.42	9	.2	3	30	1.3	44		
15	.4	9	.12	2	31	1.2	39		
16	.48	11	.08	1					

Estimated monthly discharge of Rock Creek canal near Hinsdale, Mont., for 1905.

Month.	Discharge in second-feet.			Total acre-fe
	Maximum.	Minimum.	Mean.	
July	48	1	22	1
August	41	0	7.3	

SEEPAGE MEASUREMENTS.

MILK RIVER, MONTANA.

week beginning June 4, 1905, a series of measurements were made by L. R. istant engineer, along Milk River from the head-gates of the Milk River canal, 20 miles northwest of Sweet Grass, down the river to a point 2 miles below police station. This distance is approximately 50 miles. Other measure- ıade from the point where Milk River enters Montana as far down as Havre. is about 60 miles.

Seepage measurements of Milk River, Montana, June, 1905.

Location.	Distance.[a]	Discharge.	Gain or loss.	
			Total.	Per mile.
	Miles.	*Sec.-ft.*	*Sec.-ft.*	*Sec.-ft.*
ıtes	0	49.0	.....	.....
ver	10	56.5	+7.5	+0.75
ı ranch	16	51.4	−5.1	− .32
s ranch	10	47.2	−4.2	− .42
s ranch	14	43.9	−3.3	− .24
ın line	75	39.9	−4.0	− .053
n's ranch	15	37.0	−2.9	− .20
te	19	33.3	−3.7	− .20
d ranch	15	41.6	+8.3	+ .55
.....	10	44.6	+3.0	+ .30

[a] Distances from point to point, measured along the river.

CUTBANK CREEK, MONTANA.

and 22, 1905, a series of measurements were made by H. M. Morse, engineer- ; Cutbank Creek, for the purpose of determining the seepage loss, from a point es above the town of Cutbank, near the ranch of John Bird, to Cutbank.

Seepage measurements of Cutbank Creek, Montana, August, 1905.

Location.	Distance from Cutbank.	Discharge.	Gain or loss.	
			Total.	Per mile.
	Miles.	*Sec.-ft.*	*Sec.-ft.*	*Sec.-ft.*
ird's ranch	20	42.5	.....	.....
's ranch	15	37.0	−5.5	−1.1
ıan's camp, 1 mile above Bud Ellison's ranch	11	40.6	+3.6	+ .9
below Bud Ellison's ranch	8	35.6	−5.0	−1.4
from Cutbank and 1 mile above point where reservation crosses creek	5	34.2	−1.4	− .47
k	0	33.0	−1.2	− .27

MISCELLANEOUS MEASUREMENTS.

Miscellaneous discharge measurements made in Milk River drainage basin in 1905.

Date.	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
June 16	Milk River [a]	Yantic, Mont					[b] 1.0
July 1	do.[a]	do					1.2
July 12	do.[a]	do					1.2
July 20	do.[a]	do					1.2
July 28	do.[a]	do					1.2
July 29	do.[a]	do					[b] 60
August 3	do.[a]	do					[b] 4.0
August 8	do.[a]	do					[b] 1.0
August 15	do.[a]	do					1.2
August 23	do.[a]	do					1.0
June 17	Milk River [c]	Chinook, Mont					[b] 3.0
June 24	do.[c]	do					[b] 3.0
July 8	do.[c]	do		127.0	1.07		136
July 15	do.[c]	do		7.4	.93		6.9
July 21	do.[c]	do					[b] 7.0
July 27	do.[c]	do					[b] 480
August 5	do.[c]	do					[b] 200
August 11	do.[c]	do		38.0	1.38		53
August 19	do.[c]	do					[b] 3.0
June 17	Milk River [d]	Zurich, Mont					[b] 1.5
June 24	do.[d]	do					[b] 2.0
July 8	do.[d]	do	108	184.0	.98		180
July 15	do.[d]	do					[b] 5.0
July 21	do.[d]	do					[b] 4.0
July 27	do.[d]	do					[b] 280
August 5	do.[d]	do	68	90.0	2.32		209
August 11	do.[d]	do	24	19.0	1.88		35
August 19	do.[d]	do					[b] 6.0
August 25	Agency ditch [e]	Fort Belknap Agency, Mont.		21.0	.68		15.0
July 14	Milk River [f]	Harlem, Mont					[b] 4.0
July 28	do.[f]	do	75	380.0	1.08		409
August 4	do.[f]	do					[b] 30
August 17	do.[f]	do					[b] 5.0
August 25	do.[f]	do					[b] 1.0
September 5	do.[f]	do					[b] 2.0
July 24	Milk River	Hinsdale, Mont					[b] 40
August 12	do	do					[b] 65
July 5	Rock Creek [g]	do		23.5	.62	2.0	14.6
July 24	do.[g]	do				1.58	[b] 5
August 12	do.[g]	do				1.6	[b] 5
July 18	West Fork of Milk River.[h]	Chinook, Mont					[b] 9.0
July 11	West Fork of Milk River.[i]	do					[b] 1.0
July 18	do.[i]	do					[b] 7.0

[a] Estimated just below the head of the Fort Belknap canal.
[b] Estimated.
[c] Measured just below the head of the Paradise Valley canal.
[d] Measured just below the head of the Harlem canal.
[e] Measured 1½ miles below head-gates.
[f] Measured just below head of the agency ditch.
[g] Measured just below head of the Rock Creek canal.
[h] Measured below head of the Reservation ditch.
[i] Measured below all diversions.

Miscellaneous discharge measurements made in Milk River drainage basin in 1905—Continued.

Date.	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
July 28-29	West Fork of Milk River.[a]	Chinook, Mont					[b] 200.0
August 2	do.[a]	do		36.0	0.67		24.0
August 8	do.[a]	do		87.0	.44		38.0
August 10	do.[a]	do		33.0	.60		20.0
August 11	do.[a]	do					[b] 15.0
August 15	do.[a]	do					[b].5
August 23	do.[a]	do					[b].5

[a] Measured below all diversions. [b] Estimated.

MUSSELSHELL RIVER DRAINAGE BASIN.

MUSSELSHELL RIVER AT SHAWMUT, MONT.

Musselshell River heads in the Little Belt Mountains, not far from White Sulphur Springs, Meagher County, Mont., runs eastward between the Big Snowy Mountains and the Bull Mountains in a course approximately parallel to that of the Yellowstone to about 107° 30' west longitude, and then turns northward to the Missouri.

The gaging station was established August 12, 1902, for the purpose of determining the amount of water available for irrigation and storage. It is located at Crawford's ranch, one-eighth mile from the post-office at Shawmut, Mont., and 25 miles east of Harlowtown.

The channel is straight for 150 feet above and below the station. The right bank is high and steep and covered with brush; the left is comparatively high and but slightly wooded; both banks may overflow at extreme high water. There is but one channel at all stages.

Discharge measurements are made by means of a cable and car at the new gage. The initial point for soundings is the center of the post supporting the right end of the cable.

The gage is read once each day by Dwight E. Crawford. The original gage was a vertical rod spiked to a cottonwood stump on the right bank of the river, about 200 feet north of Mr. Crawford's house. April 22, 1905, a new rod gage was set into the right bank 400 feet below the old gage, the datum being 1.01 feet below that of the original gage. As the fall of the river is only 0.72 foot between the two points, the new gage reads 0.29 foot greater than the old one; readings for years previous to 1905, to be referred to the new datum, must therefore be increased by that amount. The gage is referred to bench marks as follows: (1) A 30-penny spike below a blaze in an 18-inch cotton wood tree, which stands at the corral fence 75 feet northeast of the old gage rod; elevation, 5.91 feet above zero of the old gage and 6.92 feet above zero of the new gage. (2) A 10-penny spike in a 6-inch cottonwood tree 60 feet southeast of the old gage rod; elevation, 6.14 feet above zero of the old gage and 7.15 feet above zero of the new gage. (3) A bolt in the post supporting the measuring cable at the right bank, established April 22, 1905; elevation, 4.87 feet above zero of the new gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey.

Description: 84, p 31; 99, pp 111-112; 130, p 113.
Discharge: 130, p 114.
Gage heights: 84, p 32; 99, p 112; 130, p 114.

Discharge measurements of Musselshell River at Shawmut, Mont., 1904–5.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis char
1904.		*Feet.*	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.*
November 8	L. R. Stockman	.....	53	1.38	[a]1.44	
1905.						
April 23	J. H. Sloan	55	69	.95	1.01	
May 15	do	55	70	1.18	1.20	
June 20	do	72	159	2.35	2.25	
August 7	do	63	61	.98	1.00	
September 22[b]	do	.....	1.6	1.10	.40	

[a] Referred to new datum. [b] Made at different section.

Daily gage height, in feet, of Musselshell River at Shawmut, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	1.45	1.6	1.9	1.2	0.95	1.6	2.5	2.4	0.55	0.45	0.95	
2	1.45	1.6	1.6	1.2	.9	1.9	2.3	2.0	.55	.45	1.0	
3	1.45	1.6	1.6	1.2	.9	2.3	2.1	1.85	.55	.45	1.1	
4	1.45	1.6	1.55	1.2	1.0	2.6	1.9	1.5	.55	.45	1.05	
5	1.45	1.6	1.5	1.2	1.05	4.58	1.8	1.3	.55	.45	1.05	
6	1.45	1.6	1.5	1.2	1.05	3.78	1.7	1.15	.55	.45	1.05	
7	1.45	1.65	1.55	1.2	1.05	3.4	1.5	1.1	.55	.45	1.05	
8	1.45	1.7	1.5	1.2	1.0	3.4	1.3	.95	.55	.45	1.05	
9	1.45	1.7	1.4	1.3	1.0	4.13	1.3	.85	.5	.45	1.05	
10	1.45	1.7	1.4	1.3	1.0	3.2	1.2	.8	.5	.45	1.05	
11	1.45	1.7	1.3	1.3	1.55	3.6	1.05	.75	.5	.5	1.05	
12	1.45	1.7	1.2	1.3	1.5	3.3	.9	.75	.5	.5	1.05	
13	1.45	1.7	1.2	1.3	1.4	3.3	.8	.7	.45	.5	1.05	
14	1.45	1.7	1.1	1.25	1.3	3.25	.7	.7	.45	.6	1.04	
15	1.45	1.7	1.4	1.25	1.2	3.1	.65	.65	.45	.6	1.04	
16	1.45	1.7	1.3	1.25	1.15	2.75	.6	.65	.45	.6	1.04	
17	1.45	1.7	1.3	1.25	1.1	2.7	1.9	.65	.45	.6	1.0	
18	1.45	1.7	1.3	1.2	1.1	2.6	.8	.65	.45	.7	1.0	
19	1.45	1.7	1.3	1.2	1.2	2.4	.65	.6	.45	.8	1.01	
20	1.45	1.7	1.3	1.2	1.3	2.2	.6	.6	.45	.8	1.01	
21	1.45	1.7	1.25	1.15	1.3	2.1	.6	.6	.45	1.0	1.0	
22	1.5	1.7	1.25	1.15	1.3	2.2	.55	.6	.45	1.1	1.0	
23	1.5	1.75	1.2	.95	1.3	2.3	.55	.6	.4	1.0	.9	
24	1.5	1.8	1.2	1.0	1.3	2.35	.55	.6	.4	1.05	.9	
25	1.5	1.8	1.2	1.0	1.3	2.4	.55	.6	.4	1.05	.9	
26	1.5	1.8	1.2	1.0	1.3	2.4	.85	.6	.4	1.0	1.0	
27	1.5	1.9	1.2	1.0	1.3	2.6	.7	.6	.4	1.0	1.1	
28	1.5	2.05	1.2	.95	1.3	2.45	.7	.6	.4	1.0	1.1	
29	1.6	.....	1.2	.95	1.5	2.25	.9	.55	.4	.9	1.1	
30	1.6	.....	1.2	.95	1.5	2.1	.9	.55	.4	.9	1.1	
31	1.6	.....	1.2	.....	1.5	.....	4.18	.55	.....	.8	.....	

NOTE.—All gage heights refer to the datum established April 22, 1905.

From January 1 to February 12 the river was frozen entirely across; from February 13 to Febr 28 there was an open channel; the river was clear on March 1. Average thickness of ice, 0.8 foot. river was frozen also from November 27 to December 31. Thickness of ice, 0.6 foot, approximately. ing frozen period gage heights are to the top of the ice.

LITTLE MUDDY RIVER DRAINAGE BASIN.

LITTLE MUDDY RIVER NEAR WILLISTON, N. DAK.

luddy River rises in the northwestern part of Williams County, N. Dak., and hward into Missouri River at Williston.

ging station was established February 4, 1904. It is located in sec. 19, T. 155 N., ., the gage in the southwest quarter and the cable in the northeast quarter, about r road from Williston, N. Dak.

annel is straight for about 200 feet above and 1,700 feet below the station. Both high and clean and do not overflow. The bed of the stream is composed of silt rly permanent. There is but one channel at all stages, and the current is sluggish. ge measurements are made at high stage by means of a cable, car, and tagged wire. l point for soundings is a point 0.5 foot behind the top of the cable support at the k. At low stages measurements are made by wading a few rods below the gage. lard chain gage, which was read during 1905 by W. O. Hollar, is attached to a tim- cting horizontally over the stream near the house of the observer. The length of is 22.23 feet. The gage is referred to bench marks as follows: (1) A post driven the surface of the ground under the projecting timber of the gage and marked ass-headed nail in the top; elevation above the datum of the gage, 2.92 feet. (2) ital line of four medium-sized spikes driven into the end of a log in the wall of the about 4 rods west of the chain gage at the corner nearest to it and about 3 feet ound; elevation above gage datum, 13.00 feet.

lined rod gage reading from 1.8 to 10.3 feet was established about 6 rods above gage.

ription of this station, with gage height and discharge data, is contained in Water- aper No 130 of the United States Geological Survey, pages 114–117.

harge measurements of Little Muddy River near Williston, N. Dak., in 1905.

.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis- charge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	F. C. Davis	8.0	6.9	2.32	2.60	16.0
.....	Chandler and Turner	22	9.8	0.97	2.50	9.5
.....	.....do	7.8	5.3	1.72	2.45	9.1
.....	.....do	15.5	6.2	1.47	2.45	9.1
.....	R. Richards	8.5	7.2	2.43	2.54	17.5
.....	F. C. Davis	8.0	7.2	2 12	2.50	15 3
.....	Hanna and Chandler	8.0	6.8	1.71	2.57	11.6
·20..	E. F. Chandler	7.5	4.5	1.32	2.39	5.9

[a] Made at different section.

Daily gage height, in feet, of Little Muddy River near Williston, N. Dak., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	3.9	2.6	2.5	2.5	2.6	2.5	2.4	2.6	2
2	3.9	2.6	2.5	2.5	2.6	2.5	2.5	2.6	2
3	3.9	2.6	2.5	2.5	2.6	2.5	2.5	2.6	2
4	3.9	2.5	2.5	2.55	2.6	2.5	2.5	2.5	2
5	3.8	2.5	2.5	3.2	2.6	2.5	2.4	2.5	2
6	3.6	2.5	2.5	3.45	2.6	2.5	2.4	2.5	2
7	3.5	2.5	2.5	3.2	2.6	2.5	2.4	2.5	2
8	3.2	2.5	2.5	3.1	2.6	2.5	2.4	2.5	2
9	3.0	2.5	2.5	2.95	2.6	2.5	2.4	2.5	2
10	3.0	2.4	2.5	2.8	2.6	2.5	2.4	2.5	2
11	2.9	2.4	2.5	2.8	2.6	2.4	2.4	2.5	2
12	2.9	2.4	2.5	2.7	2.6	2.4	2.4	2.5	2
13	2.9	2.4	2.5	2.6	2.6	2.4	2.4	2.5	2
14	2.9	2.4	2.5	2.6	2.6	2.4	2.4	2.5	2
15	2.8	2.4	2.5	2.6	2.6	2.4	2.4	2.5	2
16	2.8	2.4	2.5	2.6	2.6	2.4	2.4	2.5	2
17	2.8	2.4	2.5	2.6	2.6	2.4	2.4	2.5	2
18	2.7	2.4	2.5	2.6	2.6	2.4	2.4	2.5	2
19	2.8	2.5	2.5	2.5	2.6	2.4	2.4	2.5	2
20	2.7	2.5	2.5	2.6	2.6	2.4	2.4	2.5	2
21	2.7	2.5	2.5	2.6	2.6	2.4	2.4	2.5	2
22	2.7	2.5	2.5	2.5	2.6	2.4	2.4	2.5	2
23	2.7	2.5	2.5	2.5	2.6	2.4	2.4	2.5	2
24	2.6	2.5	2.5	2.5	2.5	2.4	2.4	2.5	2
25	2.6	2.5	2.5	2.5	2.6	2.4	2.4	2.5	2
26	2.6	2.5	2.5	2.5	2.6	2.4	2.4	2.5	2
27	2.6	2.5	2.5	2.5	2.6	2.4	2.4	2.5	2
28	2.6	2.5	2.5	2.65	2.5	2.4	2.4	2.5	2
29	2.6	2.5	2.5	2.65	2.5	2.4	2.4	2.5	2
30	2.6	2.5	2.5	2.6	2.5	2.4	2.4	2.5	.....
31	2.6	.....	2.5	.....	2.5	2.4	.....	2.5	.....

NOTE - River frozen over January 1 to February 28; also November 30 to December 31.

Station rating table for Little Muddy River near Williston, N. Dak., from February 1, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.40	6	3.40	137	4.30	423	5.20	794
2.50	10	3.50	162	4.40	461	5.30	839
2.60	16	3.60	189	4.50	500	5.40	885
2.70	23	3.70	218	4.60	539	5.50	932
2.80	32	3.80	249	4.70	579	5.60	980
2.90	43	3.90	281	4.80	620	5.70	1,030
3.00	57	4.00	315	4.90	662	5.80	1,082
3.10	74	4.10	350	5.00	705	5.90	1,135
3.20	93	4.20	386	5.10	749	6.00	1,189
3.30	114						

The above table is applicable only for open-channel conditions. It is based on 13 discharge measurements made during 1904-5. It is fairly well defined between gage heights 2.4 feet and 5.4 feet; above feet it is estimated.

ated monthly discharge of Little Muddy River near Williston, N. Dak., for 1905.

[Drainage area, 800 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	200	16	58.8	3,615	0.074	0.085
.....	16	6	9.4	559	.012	.013
.....	10	10	10.0	615	.012	.014
.....	150	10	28.1	1,672	.035	.039
.....	16	10	15.0	922	.019	.022
.....	10	6	7.3	448	.0091	.010
ier.....	10	6	6.4	381	.0080	.0089
.....	16	10	10.6	652	.013	.015
ier.....	16	10	11.0	633	.014	.015
ie period.....	.....	.....	.....	9,500	.....	.....

YELLOWSTONE RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

upper Yellowstone rises in the Shoshone Mountains, in northwestern Wyoming, near itheast corner of the Yellowstone National Park, flows northwestward for 40 or 50 and then enters Yellowstone Lake, which may be considered the great source of the iver. This lake is about 15 miles long by 20 miles wide, lies at an elevation of 7,778 ove the sea, and is hemmed in on every side by lofty mountains from whose snow- l slopes its chief supply of water must come, since it receives no important streams. ; from the lake at the north end, the stream flows northwestward for 10 or 15 miles, s over the Great Falls of the Yellowstone, and for the next 20 miles runs through the Canyon, which is impassable throughout. About 80 miles from the lake it emerges he Snow Mountains, and thence runs eastward and northeastward until it joins the ri at Fort Buford, N. Dak.

t leaves the mountains the river is about 600 feet wide and 6 feet deep; thence to Fork, which enters from the south about 15 miles above Billings, Mont., it is character- ; bold, sweeping curves and many islands. Between Clark Fork and the mouth of the n it is from 1,500 to 1,800 feet wide, is free from rapids, and has a current of 3 to 4 an hour. Between the Bighorn and the Powder the main stream increases in width n 2,400 to 2,700 feet, and becomes turbid like the Missouri. Below the mouth of the r the banks are low and caving, and the stream contains some rapids and shoals and ous densely timbered islands.

length of the Yellowstone is about 500 miles; the area of the basin is approximately square miles.

he tributaries of the Yellowstone the most important is the Bighorn, which has its in the many small streams draining the intersecting slopes of the Wind River and ne mountains in northwestern Wyoming, about 30 miles southeast of Yellowstone al Park. For approximately 75 miles it flows southeastward, its volume being con- augmented by small streams from the south heading well back in the Wind River but receiving no important additions from the north. In this portion of its course it is Wind River; but at its southernmost point it is joined by Little Wind River, turns ly to the northeast, and is below known as the Bighorn. Continuing in a winding for about 15 miles, it then turns directly north, passes through a deep canyon in the eek Range, crosses Bighorn County, Wyo., into Montana, and joins the Yellowstone 30 miles north of Fort Custer. The basin is almost surrounded by high mountain

ranges, including the Shoshone and Owl Creek mountains on the north of Wind River, the Wind River, Sweetwater, and Granite ranges on the west and south, and to the east a low range of broken hills which extend to the high plateau forming the divide between the Bighorn and the Powder and North Platte river basins. The reduced Shoshone Indian Reservation is drained by Wind River, while the Crow Reservation is located near the mouth of the Bighorn. On the Indian lands several large canals are being constructed and the science of irrigation is being taught. The soil on the Rocky Mountain slopes is generally a sandy loam, but in the narrow tributary valleys the soil is deeper and of an alluvial character.

The principal tributaries of the Bighorn are, first, Wind, Little Wind, and Popo Agie rivers, which combined carry the great perennial discharge and become the head waters; below the mouth of the Little Wind are Muskrat, Poison, and Badwater creeks, which drain the sand hills to the east, Muddy Creek, which follows the foothills of the Owl Creek Range, Gooseberry Creek, Gray Bull Creek, No Wood Creek, and Shoshone and Little Bighorn rivers.

The Shoshone rises on the eastern slope of the Shoshone Mountains, east of the Yellowstone National Park. It has two chief upper branches, North and South forks, which unite just before entering Shoshone Canyon, at a point about 12 miles southwest of Cody. From the junction of the forks the course of the main river is a little east of northeast to the Bighorn. The head-water region is very mountainous, many of the peaks, which are never entirely free from snow, rising to elevations of nearly 11,000 feet. The valley of North Fork is very narrow and the area of agricultural land in its lower reaches comprises but a few hundred acres. The valley of South Fork is perhaps 2 miles wide at its mouth, gradually narrowing for 10 or 15 miles until it becomes a gulch or canyon. There are 2,000 or 3,000 acres of land under some stage of cultivation. From these two forks the Shoshone receives 99 per cent of all the run-off carried by the stream at any point. The lower basin, on the north of the river, soon flattens out to a low plain with a gentle slope to the southeast; to the south there is a small level bench immediately below Cody, which is soon closed in by a broken headland, spreading out again farther downstream, where another large tract of irrigable land is to be found. Throughout its length the Shoshone is a rapid stream, the fall being very great. On the first benches the soil is a sandy loam resting upon gravel. Salt sage and an extremely light growth of grasses cover the valleys. The site of the Shoshone storage dam, one of the projects of the Reclamation Service, is in Shoshone Canyon about 6 miles west of Cody.

Information in regard to this basin is contained in Annual Reports of the United States Reclamation Service and in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin):

Description: Ann 11, ii, pp 36-38; 12, ii, pp 237-238; 20, iv, pp 246-247; 21, iv, p 190; Bull 131, p 26.
Irrigation surveys: Ann 13, iii, pp 63-73.
Rainfall data: Ann 13, iii, pp 67-68.

YELLOWSTONE RIVER NEAR LIVINGSTON, MONT.

This station was established May 2, 1897. It is located at Carter's bridge, 5 miles south of Livingston, Mont., at the mouth of the lower canyon.

The channel is straight for 100 yards above and below the station. The right bank is low and in flood season a part of the water escapes through a slough on that side, beginning at gage height 4.65 feet. This water is measured separately at the bridge over the slough 125 yards away. The left bank is high and will not overflow. The current is swift.

Discharge measurements are made from the downstream side of the bridge. At high water a stay line is necessary to keep the meter submerged. The initial point for soundings is marked on the guard rail 2 feet east of the center of the northwest pier, which is at the left bank.

Gage readings are taken once each day by Mrs. W. O. Cowan. A vertical rod was first installed, but was replaced by a wire gage located on the lower side of the east span. January 1, 1903, the gage datum was lowered 3 feet, increasing all subsequent readings by that

In April, 1904, the wire gage was replaced by a standard chain gage having the
ım. The length of the chain is 20.77 feet. The gage is referred to bench marks
: (1) The head of a 2-inch nut on the center pin at the foot of the end diagonal of
:am truss of the east pier; elevation, 17.60 feet above the new datum. (2) A
ıt mark on the corner of the top of the shoe at the foot of the batter post on the
ıf the upstream side of the bridge; the batter post is marked in white paint "B.
' it is also marked in red paint "17.20;" elevation above the new gage datum,

.

ation in regard to this station is contained in the following publications of the
:ates Geological Survey (Ann = Annual Report; WS = Water-Supply Paper):

ion: WS 15, p 74; 27, p 69; 37, pp 210-211; 49, p 268; 66, p 22; 84, pp 24-25; 99, p 97; 130, p 117.
e: Ann 20, iv, p 247; WS 15, p 74; 37, p 211; 49, p 268; 66, p 22; 84, p 25; 99, p 98; 130, p 118.
e: monthly: Ann 19, iv, p 289; 20, iv, p 248; 22, iv, p 289; WS 75, p 122; 84, p 26; 99, p 99; 130,

e, yearly: Ann 20, iv, p 53.
ghts: WS 15, p 74; 27, p 73; 37, p 211; 49, p 268; 66, p 22; 84, p 25; 99, p 98; 130, p 118.
aphs: Ann 19, iv, p 289; 20, iv, p 248; 22, iv, p 290; WS 75, p 123.
ables: Ann 19, iv, p 288; WS 27, p 76; 52, p 516; 66, p 170; 84, p 26; 99, p 99; 130, p 119.

scharge measurements of Yellowstone River near Livingston, Mont., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	L. R. Stockman	160	426	2.56	1.80	1,089
.....	J. H. Sloan	179	567	3.68	2.56	2,082
....	.....do	178	543	3.50	2.50	1,900
.....	.....do	.....	1,478	6.93	6.41	10,250
.....	.....do	235	1,440	6.63	6.20	9,548
....	.....do	188	842	5.05	4.12	4,252
....	.....do	182	784	3.94	3.05	3,090
20 ..	.....do	179	540	3.49	2.52	1,884
.....	.....do	.....	490	3.13	2.19	1,536

Daily gage height, in feet, of Yellowstone River near Livingston, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.7	1.3	1.9	1.8	2.35	5.85	6.2	3.95	2.9	2.5	1.95	1.8
2	1.7	5.35	1.8	1.8	2.5	6.35	6.2	3.95	2.8	2.45	1.95	1.8
3	1.7	4.9	1.8	1.8	2.6	6.8	6.1	3.85	2.8	2.45	1.95	1.8
4	1.85	4.25	1.85	1.8	2.45	7.15	6.0	3.85	2.75	2.45	1.95	1.8
5	1.7	4.1	1.85	1.8	2.35	7.4	5.9	3.85	2.75	2.4	1.95	1.8
6	1.7	2.3	1.85	1.8	2.25	6.4	5.7	3.8	2.7	2.4	1.95	1.8
7	1.7	2.0	1.9	1.9	2.35	6.2	5.7	3.75	2.7	2.35	2.0	1.9
8	1.7	1.8	1.9	2.0	2.5	6.85	5.5	3.5	2.7	2.35	2.0	1.9
9	1.5	1.7	1.9	2.1	2.85	7.25	5.3	3.5	2.7	2.35	2.0	1.9
10	1.6	1.5	1.85	2.1	2.8	6.7	5.3	3.5	2.65	2.3	2.0	1.9
11	1.5	1.25	1.8	1.9	2.6	6.4	5.25	3.5	2.6	2.2	2.0	1.9
12	1.2	1.25	1.8	1.9	2.5	6.6	5.2	3.5	2.6	2.2	1.95	1.9
13	1.2	1.25	1.8	1.9	2.5	7.0	5.15	3.5	2.6	2.2	1.95	1.9
14	1.7	1.5	1.9	1.9	2.4	7.2	5.0	3.45	2.6	2.2	1.9	1.9
15	1.9	1.6	1.9	1.95	2.45	6.85	4.9	3.4	2.6	2.2	1.9	1.9
16	1.9	1.6	1.8	1.95	2.5	6.4	5.0	3.35	2.55	2.25	1.8	1.9
17	1.8	1.6	1.85	1.95	2.65	6.2	4.9	3.3	2.5	2.2	1.8	1.9
18	1.9	1.6	1.85	1.95	3.5	6.2	4.7	3.3	2.5	2.2	1.8	1.9
19	1.75	1.65	1.9	2.0	3.4	6.0	4.65	3.2	2.5	2.1	1.8	1.9
20	1.9	1.75	1.95	2.0	3.4	5.8	4.6	3.15	2.5	2.1	1.8	1.9
21	1.9	1.8	1.95	2.1	3.4	5.75	4.55	3.1	2.45	2.2	1.8	1.9
22	1.9	1.8	1.8	2.1	3.5	6.5	4.45	3.1	2.45	2.15	1.8	1.9
23	1.9	1.7	1.85	2.1	3.6	6.2	4.4	3.0	2.35	2.15	1.8	1.9
24	1.9	1.75	1.7	2.2	3.6	6.4	4.3	3.0	2.35	2.15	1.85	1.9
25	1.9	1.85	1.7	2.4	3.6	6.3	4.25	3.0	2.4	2.2	2.00	1.9
36	1.85	1.95	1.7	2.5	3.8	6.5	4.2	3.0	2.4	2.2	1.95	1.9
27	1.85	1.85	1.7	2.75	3.9	6.75	4.15	3.0	2.35	2.2	1.9	1.9
28	1.85	1.85	1.8	2.75	3.85	6.85	4.1	3.0	2.35	2.2	1.75	1.9
29	1.8	.....	1.8	2.5	4.25	6.5	4.05	2.95	2.35	2.1	1.45	1.9
20	1.75	.....	1.85	2.45	4.55	6.4	4.0	2.9	2.5	2.1	1.6	1.9
31	1.5	.....	1.8	.....	4.95	.....	3.95	2.9	.....	2.0	.....	1.9

NOTE.—Ice conditions February 2-14. Gage heights are to the top of the ice.

Station rating table for Yellowstone River near Livingston, Mont., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	500	2.40	1,760	3.80	3,720	5.40	7,120
1.10	560	2.50	1,890	3.90	3,880	5.60	7,680
1.20	630	2.60	2,020	4.00	4,060	5.80	8,280
1.30	700	2.70	2,150	4.10	4,240	6.00	8,900
1.40	770	2.80	2,280	4.20	4,420	6.20	9,540
1.50	850	2.90	2,410	4.30	4,600	6.40	10,200
1.60	930	3.00	2,550	4.40	4,800	6.60	10,880
1.70	1,020	3.10	2,690	4.50	5,000	6.80	11,580
1.80	1,110	3.20	2,830	4.60	5,200	7.00	12,300
1.90	1,200	3.30	2,970	4.70	5,420	7.20	13,060
2.00	1,300	3.40	3,110	4.80	5,640	7.40	13,820
2.10	1,400	3.50	3,250	4.90	5,860		
2.20	1,520	3.60	3,400	5.00	6,100		
2.30	1,640	3.70	3,560	5.20	6,600		

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904-5, and is well defined throughout.

imated monthly discharge of Yellowstone River near Livingston, Mont., for 1905.

[Drainage area, 3,580 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	1,200	630	1,054	64,810	0.294	0.339
ry (15 days).....	1,250	700	1,032	30,700	.288	.161
.....	1,250	1,020	1,139	70,040	.318	.367
.....	2,215	1,110	1,396	83,070	.390	.435
.....	5,980	1,580	2,752	169,200	.769	.887
.....	13,820	8,130	10,670	634,900	2.98	.332
.....	9,540	3,970	6,180	380,000	1.73	1.99
.....	3,970	2,410	3,068	188,600	.857	.988
ber.....	2,410	1,700	1,975	117,500	.552	.616
r.....	1,890	1,300	1,572	96,660	.439	.506
ber.....	1,300	930	1,190	70,810	.332	.370
ber.....	1,250	700	1,025	63,030	.286	.330
he period.....	.....	.....	.....	1,969,000	.....	.....

:.—No estimate for ice period.

YELLOWSTONE RIVER NEAR BILLINGS, MONT.

s station was established May 29, 1904. It is located at the county highway bridge 2 miles east of Billings and 200 feet below the Northern Pacific Railway bridge. A gage is also maintained by the Department of Agriculture at the second highway above, about 4 miles west of the Geological Survey station.

channel is straight for 200 feet above and 400 feet below the station. The right bank gravel, slopes gradually back from the channel, and is not subject to overflow. The ank is low and sandy, overflowing in extremely high water. The bed of the stream is sed of gravel and is free from vegetation. There is but one channel at all stages, and rrent is swift. The masonry piers of the railway bridge, 200 feet above, and an island, et below, have considerable effect on the direction of the current.

charge measurements are made from the lower side of the bridge, which has three resting on steel-jacketed concrete piers. The initial point for soundings is on the left f the bridge.

tandard chain gage, which is read twice each day by James E. Dickie, is attached to idge near the middle of the first span from the west bank. The length of the chain is feet. The gage is referred to bench marks as follows: (1) The top of the third course ne in the left abutment of the Northern Pacific Railway bridge; elevation above the of the gage, 18.99 feet. (2) The top of a nail on the end of the second bent from the nd of the highway bridge on the downstream end of the bent sill; elevation, 18.21 feet the datum of the gage.

scription of this station, with gage-height and discharge data, is contained in Water- Paper No. 130 of the United States Geological Survey, pages 120–122.

Discharge measurements of Yellowstone River near Billings, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis- charge
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-f*
March 25	L. R. Stockman	282	1,627	1.45	1.30	2
April 27	J. H. Sloan	318	1,842	1.95	2.00	3
May 12	do	325	2,099	2.48	3.10	5
June 8	do	455	4,177	5.43	8.26	22
June 28	do	458	4,554	6.25	9.19	28
July 20	do	391	2,618	3.95	4.90	10
August 14	do	324	2,240	3.06	3.40	6
September 12	do	319	1,771	2.32	2.38	4
October 11	do	287	1,666	1.77	1.83	2
October 20	Morse and Sloan	318	1,762	2.12	2.10	3

Daily gage height, in feet, of Yellowstone River near Billings, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	1.1	4.1	5.0	0.9	2.0	6.2	8.6	4.25	2.6	2.3	2.0	2
2	1.1	4.1	4.95	.85	2.3	6.75	8.35	4.4	2.6	2.3	2.0	2
3	1.1	4.1	4.9	.8	2.3	7.2	8.05	4.15	2.6	2.3	2.0	2
4	1.1	4.1	4.7	.9	2.5	8.4	8.0	4.15	2.6	2.2	2.0	2
5	1.1	4.1	4.55	1.0	2.5	9.6	8.0	4.15	2.5	2.2	2.0	2
6	1.1	4.1	4.05	1.0	2.5	9.4	7.75	4.0	2.5	2.1	2.0	2
7	1.1	4.1	3.8	1.1	2.5	8.1	7.3	4.15	2.5	2.1	2.0	2
8	1.1	4.1	3.4	1.1	2.5	8.25	7.15	3.95	2.4	2.2	2.0	2
9	1.1	4.1	2.9	1.5	2.5	9.6	7.0	3.65	2.3	2.25	2.0	2
10	1.1	4.1	2.6	1.8	3.25	9.7	6.7	3.5	2.25	2.2	2.0	2
11	4.4	4.1	2.2	1.8	3.25	8.7	6.8	3.5	2.2	2.0	1.96	2
12	4.4	4.1	1.8	1.8	3.0	8.55	6.55	3.4	2.2	2.05	1.9	2
13	4.4	4.1	1.8	1.7	3.2	9.7	6.55	3.45	2.2	2.1	1.9	2
14	4.4	4.1	1.8	1.5	3.05	9.8	6.1	3.4	2.2	2.0	1.9	2
15	4.4	4.1	1.8	1.5	2.8	9.6	6.0	3.25	2.2	2.0	1.9	2
16	4.4	4.5	1.8	1.5	2.5	8.8	6.15	3.15	2.2	2.0	1.9	2
17	4.1	5.0	1.8	1.6	2.1	8.55	6.25	3.1	2.2	2.05	1.8	1
18	4.1	5.3	1.8	1.7	2.0	8.25	5.65	3.1	2.2	2.2	1.8	1
19	4.1	5.5	1.8	1.8	3.7	7.65	5.3	3.2	2.2	2.2	1.8	1
20	4.1	5.5	1.6	1.8	4.1	7.1	5.35	3.0	2.2	2.2	1.8	1
21	4.1	5.5	1.6	1.8	2.75	7.1	5.5	2.85	2.2	2.1	1.9	1
22	4.1	5.5	1.45	1.85	2.6	7.4	5.6	2.7	2.0	2.0	1.9	1
23	4.1	5.5	1.4	1.9	3.45	8.15	5.5	2.7	2.0	2.0	1.9	1
24	4.1	5.5	1.4	1.95	4.2	8.5	4.6	2.65	2.0	2.0	1.9	1
25	4.1	5.5	1.4	1.8	4.05	8.4	4.5	2.7	2.0	2.0	1.9	1
26	4.1	5.5	1.4	1.8	3.8	8.4	4.5	2.7	2.0	2.0	1.9	1
27	4.1	5.5	1.4	2.0	3.95	8.9	4.45	2.6	2.0	2.0	1.9	1
28	4.1	5.5	1.3	2.2	4.2	9.4	4.45	2.6	2.0	2.0	2.0	1
29	4.1	.....	1.2	2.5	4.1	8.85	4.25	2.6	2.25	2.0	2.0	1
30	4.1	.....	1.0	2.25	4.6	8.65	4.25	2.65	2.4	2.0	2.0	1
31	4.1	.....	1.0	.....	5.5	.....	4.2	2.7	.....	2.0	.....	1

NOTE.—Ice conditions January 1 to March 11; readings to the top of the ice. January 11 to February 22 the river was gorged below the station; thickness of ice increased from 0.2 foot to 1.8 feet. River frozen November 29 to December 31.

tion rating table for Yellowstone River near Billings, Mont., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	1,800	2.70	4,860	4.40	8,790	7.20	18,470
1.10	1,940	2.80	5,085	4.50	9,050	7.40	19,340
1.20	2,085	2.90	5,310	4.60	9,320	7.60	20,250
1.30	2,235	3.00	5,535	4.70	9,600	7.80	21,200
1.40	2,390	3.10	5,760	4.80	9,890	8.00	22,190
1.50	2,550	3.20	5,985	4.90	10,190	8.20	23,190
1.60	2,715	3.30	6,210	5.00	10,500	8.40	24,190
1.70	2,885	3.40	6,435	5.20	11,140	8.60	25,190
1.80	3,060	3.50	6,660	5.40	11,810	8.80	26,200
1.90	3,240	3.60	6,885	5.60	12,490	9.00	27,260
2.00	3,425	3.70	7,110	5.80	13,190	9.20	28,360
2.10	3,615	3.80	7,335	6.00	13,890	9.40	29,490
2.20	3,810	3.90	7,565	6.20	14,590	9.60	30,660
2.30	4,010	4.00	7,800	6.40	15,300	9.80	31,860
2.40	4,215	4.10	8,040	6.60	16,050	10.00	33,060
2.50	4,425	4.20	8,285	6.80	16,840		
2.60	4,640	4.30	8,535	7.00	17,640		

The above table is applicable only for open-channel conditions. It is based on 14 discharge measurements made during 1904–5. It is fairly well defined between gage heights 1 foot and 5 feet, being based on two flood measurements above 5 feet.

Estimated monthly discharge of Yellowstone River near Billings, Mont., for 1905.

[Drainage area, 11,180 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 12–31	3,060	1,800	2,612	103,600	0.234	0.174
April	4,425	1,535	2,747	163,500	.246	.274
May	12,150	3,425	5,943	365,400	.532	.613
June	31,860	14,590	24,700	1,470,000	2.21	2.47
July	25,190	8,285	14,740	906,300	1.32	1.52
August	8,790	4,640	6,218	382,300	.556	.641
September	4,640	3,425	3,933	234,000	.352	.393
October	4,010	3,425	3,615	222,300	.323	.372
November 1–28	3,425	3,060	3,290	182,700	.294	.306
The period				4,030,000		

NOTE.—No estimate for ice period.

YELLOWSTONE RIVER AT GLENDIVE, MONT.

This station, established in 1893 by the United States War Department, was transferred to the Department of Agriculture, which has kept daily records of river height. When a study of the lower Yellowstone Valley was begun in 1903, this station was taken up by the United States Geological Survey, whose records begin August 1, 1903. The station is located at the steel highway bridge leading northward from Glendive, about one-fourth mile from the post-office.

The channel is straight for about 500 feet above and below the bridge. The right bank is composed of clay and gravel, is high, and is riprapped for some distance above and below the bridge; the left bank is low and bordered by sandy flats, covered with trees and brush, extending to the hills, 1 mile distant; these flats are liable to be submerged at high water. The bed of the stream is of clay and sand and shifts at every flood. At low water an island becomes visible between the third and fourth spans from the right, and at flood stages water finds its way through a slough traversing the flats on the left. The water at high stages is very deep and swift. Old piling and cribwork, remains of a former bridge, obstruct the channel on the upstream side.

Discharge measurements are made from the downstream hand rail of the bridge, which spans the channel in four spans of 300 feet each. The initial point for soundings is over the southeast pier at the right bank.

During 1905 the gage was read daily until August 31 by H. A. Sample; after that date the daily observations were taken by the local office of the United States Reclamation Service. The original United States Geological Survey gage was of the wire type, fastened to the upstream hand rail of the first span, about 200 feet from the right bank, the scale graduations being marked on the hand rail. This gage was destroyed October 24, 1904, and one month later a standard chain having the same datum was put in its place. The length of the chain is 39.48 feet. The gage is referred to bench marks as follows: (1) A point on the surface of the cement at the northwest corner of the girder on the pier under station "0," elevation, 26.26 feet above gage datum and 2,060.6 feet above sea level. (2) The top of the west rail of the Northern Pacific Railway track at the right end of the bridge; elevation, 30.19 feet above gage datum. The elevation of the bench marks above sea level was determined from the Northern Pacific elevation of the datum rail at Terry, Mont.; this is 2,249 feet above sea level. The gage readings from 1897 until the establishment of the United States Geological Survey wire gage were referred to a "T" on the top of the southeast anchor bolt in the southeast caisson at the east end of the bridge; its elevation was 25.08 feet above gage datum. The old gage was carried away by ice April 8, 1899, and gage heights during the remainder of that year were determined by measuring down to the water surface from this bench mark. A new bridge was erected in 1901, and it is not known whether this old bench mark was disturbed or not.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 91–92; 130, pp 123–124.
Discharge: 99, p 92; 130, p 124.
Discharge, monthly: 130, p 126.
Gage heights, 99, pp 93–97; 130, pp 124–125.
Rating table: 130, p 25

Discharge measurements of Yellowstone River at Glendive, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 28	L. R. Stockman	705	2,038	2.19	0.73	4,471
April 25	J. H. Sloan	735	2,413	2.31	1.10	5,565
May 9	do	742	3,099	2.50	2.18	7,746
June 4	do	772	6,285	5.26	6.34	33,090
July 1	do	1,010	7,973	6.58	8.09	52,450
July 26	do	763	4,697	3.64	4.53	17,100
August 22	do	746	3,270	2.69	2.42	8,788
September 15	do	740	2,368	2.29	1.30	5,433
October 13	do	746	2,382	2.13	1.11	5,079

Daily gage height, in feet, of Yellowstone River at Glendive, Mont., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	4.4	2.75	6.1	0.7	1.1	4.6	8.3	4.8	1.8	2.1	1.4	2.0
.....	4.4	2.85	6.1	.6	1.4	5.7	7.9	5.4	1.8	2.2	1.4	1.6
.....	4.5	2.85	6.3	.6	1.4	5.8	8.1	4.6	1.8	1.8	1.2	1.3
.....	4.5	2.85	6.4	.6	1.1	6.3	8.3	4.4	1.9	1.4	1.2	1.4
.....	4.6	2.85	7.5	.5	1.2	7.0	7.7	4.3	1.9	2.3	1.2	1.4
.....	4.6	2.85	6.7	.5	1.3	8.2	7.2	3.9	1.8	1.8	1.2	1.5
.....	4.5	2.85	6.3	.5	1.9	9.2	7.1	3.7	1.8	1.6	1.2	1.7
.....	4.5	2.85	5.9	.5	2.4	9.4	6.7	3.5	1.8	1.4	1.3	3.2
.....	4.6	2.85	5.3	.5	2.4	8.3	6.6	3.3	1.8	1.3	1.3	3.8
.....	4.6	2.85	5.2	.4	2.2	8.8	6.4	3.1	1.7	1.2	1.3	4.0
.....	4.1	2.85	5.0	.4	2.2	9.3	6.2	3.1	1.7	1.2	1.2	4.0
.....	3.6	2.85	5.0	.4	2.4	9.3	6.0	3.0	1.6	1.15	1.2	3.8
.....	3.3	2.95	4.9	.4	2.8	8.8	5.9	3.0	1.5	1.15	1.2	3.6
.....	3.1	3.25	4.8	.9	2.9	8.1	5.9	3.0	1.4	1.2	1.2	3.4
.....	3.0	3.85	4.5	.9	2.6	8.2	5.9	3.0	1.3	1.2	1.2	3.0
.....	2.85	3.5	4.1	.8	2.3	8.6	5.8	3.0	1.3	1.2	1.2	2.9
.....	2.75	3.3	3.7	.8	2.2	8.5	5.7	3.0	1.2	1.3	1.1	2.9
.....	2.75	3.0	3.6	.8	2.0	8.2	6.0	2.9	1.3	1.3	1.1	2.8
.....	2.75	2.9	1.5	.9	1.8	7.8	5.4	2.8	1.2	1.4	1.1	2.7
.....	2.75	2.9	1.1	.9	1.8	7.8	5.2	2.7	1.1	1.4	1.1	2.7
.....	2.75	2.9	1.1	.9	1.9	7.8	5.0	2.7	1.0	1.4	1.1	2.7
.....	2.75	3.3	1.0	.9	3.3	7.0	4.9	2.7	1.0	1.4	1.1	2.7
.....	2.75	3.4	1.0	.9	3.3	7.0	4.4	2.5	1.0	1.4	1.1	2.6
.....	2.75	3.4	1.0	.8	3.3	6.9	4.3	2.3	1.0	1.4	1.1	2.5
.....	2.75	4.1	.9	1.1	3.6	7.8	4.3	2.1	.9	1.4	1.1	2.4
.....	2.75	4.5	.9	1.1	4.1	8.0	4.5	2.0	.9	1.4	1.1	2.1
.....	2.75	6.9	.8	.9	4.5	7.7	4.4	1.9	.8	1.4	1.2	2.0
.....	2.75	6.1	.7	.8	4.4	7.7	5.2	1 9	.8	1.4	1.3	1.9
.....	2.75	.....	.7	.9	4.2	7.9	5.2	1.8	.7	1.4	3.2	1.5
.....	2.75	.....	.7	1.0	4.3	8.1	5.4	1.8	.....	1.4	2.5	1.5
.....	2.75	.....	.7	.....	4.3	.....	4.7	1.8	.....	1.5	.....	1.5

—Ice conditions January 1 to March 19; also November 29 to December 31, Readings are to of the ice.

Station rating table for Yellowstone River at Glendive, Mont., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec. ft.*	*Feet.*	*Sec. ft.*	*Feet.*	*Sec. ft.*	*Feet.*	*Sec. ft.*
.40	3,750	2.00	7,300	3.60	12,900	6.40	32,000
.50	3,930	2.10	7,580	3.70	13,350	6.60	34,000
.60	4,120	2.20	7,860	3.80	13,800	6.80	36,000
.70	4,310	2.30	8,160	3.90	14,300	7.00	38,000
.80	4,500	2.40	8,460	4.00	14,800	7.20	40,200
.90	4,700	2.50	8,780	4.20	15,800	7.40	42,400
1.00	4,900	2.60	9,100	4.40	16,900	7.60	44,700
1.10	5,100	2.70	9,450	4.60	18,000	7.80	47,100
1.20	5,300	2.80	9,800	4.80	19,200	8.00	49,500
1.30	5,530	2.90	10,150	5.00	20,400	8.20	52,000
1.40	5,760	3.00	10,500	5.20	21,750	8.40	54,600
1.50	5,990	3.10	10,850	5.40	23,200	8.60	57,200
1.60	6,240	3.20	11,250	5.60	24,750	8.80	59,800
1.70	6,490	3.30	11,650	5.80	26,400	9.00	62,400
1.80	6,740	3.40	12,050	6.00	28,200		
1.90	7,020	3.50	12,450	6.20	30,050		

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904-5, and is fairly well defined throughout.

Estimated monthly discharge of Yellowstone River at Glendive, Mont., for 1905.

[Drainage area, 66,090 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inches
March 20-31	5,100	4,310	4,670	111,200	0.071	0
April	5,100	3,750	4,374	260,300	.066	
May	17,450	5,100	9,663	594,200	.146	
June	67,800	18,000	47,970	2,854,000	.726	
July	53,300	16,350	29,240	1,798,000	.442	
August	23,200	6,740	11,110	683,100	.168	
September 1-29	7,020	4,310	5,751	330,800	.087	
October	8,160	5,200	5,917	363,800	.090	
November 1-28	5,760	5,100	5,294	294,000	.080	
The period				7,289,000		

NOTE.—No estimate for ice period.

CLARK FORK AT FROMBERG, MONT.

Clark Fork enters Yellowstone River from the south, about 15 miles southwest of I ings, Mont.

The gaging station was established June 3, 1905. It is located on the highway bri one-half mile east of the Northern Pacific Railway station at Fromberg, Mont. One sr stream, Rock Creek, flows into the river between the gaging station and its mouth.

The channel is slightly curved for 100 yards above and 300 yards below the station. ' right bank is high, is covered with brush and willows, and does not overflow. The left b is low, is sparsely wooded, and overflows during extremely high water. The bed of

is composed of rock and gravel and is free from vegetation and permanent. There ne channel and the water flows uniformly with a good velocity.
large measurements are made from the downstream side of the bridge to which the attached. The initial point for soundings is directly over the center of the pier on ht bank.
gage, which is read twice daily by Mrs. J. S. Tuggle, was first a temporary rod spiked upstream side of the central pier of the bridge. This was replaced July 25, 1905, by lard chain gage fastened to the upstream side of the bridge not far from the center of eam. The length of the chain is 15.24 feet. The gage is referred to bench marks as : (1) The top of the west end of the cap on the piling on the west bent of the bridge, am side; elevation, 13.36 feet above gage zero. (2) The top of a 10-penny nail into the base of a large cottonwood tree 120 feet southwest of the west end of the ; elevation, 13.06 feet above the zero of the gage.

Discharge measurements of Clark Fork at Fromberg, Mont., in 1905.

ate.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	J. H. Sloan.....	209	845	4.87	6.42	4,118
.....	.....do.....	210	970	5.91	7.25	5,730
.....	.....do.....	185	518	3.00	4.95	1,657
19.....	.....do.....	135	370	1.98	3.98	734
ber 16...	.....do.....	122	309	1.34	3.53	416
r 17.....	.....do.....	122	289	1.30	3.47	372

Daily gage height, in feet, of Clark Fork at Fromberg, Mont., for 1905.

Day.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1		6.6	4.72	3.82	3.5	3.5	3.5
2		6.55	4.68	3.75	3.5	3.5	3.5
3	6.5	6.28	4.95	3.72	3.5	3.5	3.5
4	6.95	6.2	5.1	3.68	3.45	3.58	3.5
5	7.25	6.15	4.8	3.65	3.45	3.6	3.5
6	6.55	5.9	4.6	3.6	3.4	3.55	3.5
7	6.05	5.95	4.5	3.6	3.4	3.55	3.5
8	6.25	6.0	4.5	3.55	3.4	3.55	3.5
9	7.45	6.0	4.38	3.55	3.4	3.5	3.5
10	7.1	6.0	4.28	3.55	3.4	3.5	3.5
11	6.35	6.02	4.35	3.55	3.35	3.5	3.5
12	6.5	5.9	4.3	3.55	3.35	3.5	3.5
13	7.25	5.9	4.3	3.55	3.45	3.5	3.5
14	7.3	5.82	4.22	3.55	3.6	3.5	3.5
15	7.0	5.8	4.18	3.5	3.5	3.5	3.5
16	6.55	5.75	4.12	3.5	3.45	3.5	3.5
17	6.3	5.55	4.08	3.5	3.45	3.5	3.5
18	6.15	5.2	4.0	3.47	3.42	3.5	3.45
19	5.55	5.2	3.9	3.45	3.4	3.5	3.45
20	5.4	5.0	3.85	3.45	3.42	3.5	3.45
21	5.7	5.0	3.8	3.45	3.48	3.5	3.45
22	6.4	4.9	3.8	3.4	3.5	3.5	3.45
23	6.4	5.05	3.8	3.4	3.53	3.5	3.42
24	6.4	5.0	3.75	3.37	3.55	3.5	3.4
25	6.4	5.0	3.75	3.35	3.55	3.5	3.4
26	6.58	4.88	3.7	3.35	3.5	3.5	3.4
27	7.0	5.0	3.85	3.35	3.5	3.8	3.4
28	7.25	4.85	3.85	3.35	3.5	3.8	3.4
29	6.9	4.78	3.9	3.45	3.5	3.8	3.4
30	6.7	4.78	3.88	3.75	3.5	3.8	3.4
31		4.72	3.85		3.5		3.4

NOTE.—November 27-30, rise caused by ice. River frozen November 27 to December 31; readings a to the water surface in a hole in the ice.

Station rating table for Clark Fork at Fromberg, Mont., from June 3 to December 31, 190

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
3.40	346	4.30	999	5.20	1,973	6.20	3,475
3.50	400	4.40	1,094	5.30	2,102	6.40	3,850
3.60	458	4.50	1,192	5.40	2,236	6.60	4,260
3.70	520	4.60	1,293	5.50	2,375	6.80	4,690
3.80	587	4.70	1,397	5.60	2,519	7.00	5,140
3.90	660	4.80	1,504	5.70	2,667	7.20	5,600
4.00	738	4.90	1,615	5.80	2,819	7.40	6,080
4.10	821	5.00	1,730	5.90	2,975		
4.20	908	5.10	1,849	6.00	3,135		

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1905 and is well defined between gage heights 3.5 feet and 7.2 feet.

Estimated monthly discharge of Clark Fork at Fromberg, Mont., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
June 3-30	6,200	2,236	4,294	238,500
July	4,260	1,418	2,511	154,400
August	1,849	520	924	56,820
September	602	321	421	25,050
October	458	321	381	23,430
November 1-26	458	400	407	20,990
The period				519,200

NOTE.—No estimate for ice period.

PRYOR CREEK AT HUNTLEY, MONT.

Pryor Creek rises in the Pryor Mountains, in southeastern Carbon County, Mont., flows northeastward, and enters Yellowstone River from the south about 15 miles northeast of Billings.

The station was established August 6, 1904. It is located at Huntley, the junction of the Northern Pacific and Burlington railroads, 13 miles from Billings, Mont.

No regular station for discharge measurements has yet been established; but low-water measurements have been made by wading above the gage and high-water measurements have been made from the Northern Pacific Railway bridge, 1¼ miles below.

The gage, which is read twice each day by J. W. Day, consists of a rod placed vertically at the right bank about 200 feet south of the Northern Pacific Railway station. The gage is referred to bench marks as follows: (1) The top of the rail of the Northern Pacific Railway track in front of the operator's window; elevation, 14.52 feet. (2) A nail in a pile at the foot of a large tree on the east side of the creek, opposite the station agent's house and the post-office; elevation, 11.46 feet. (3) A spike driven in a large tree 100 feet southwest of the water-tank, 150 feet north of the section house, and 40 feet east of the track; elevation, 12.79 feet. Elevations are above the zero of the gage, which is 3,014.48 feet above sea level.

A description of this station, with gage height and discharge data, is contained in Water-Supply Paper No. 130 of the United States Geological Survey, pages 126–127.

Discharge measurements of Pryor Creek at Huntley, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 17	J. H. Sloan	12	20	1.25	1.45	26
May 12	do	16	25	2.35	1.96	59
June 5	do	40	271	7.31	14.93	1,982
June 26	do	17	26	2.66	2.20	68
July 2	do	34	148	6.34	10.52	936
August 15	do	18	16	1.21	1.20	13
September 14	do		10	1.19	1.18	12

Daily gage height, in feet, of Pryor Creek at Huntley, Mont., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.6	3.05	4.8	1.7	1.55	2.3	7.95	1.3	1.2	2.35	1.75	2.3
2	1.65	3.25	4.4	1.7	1.75	2.45	8.1	1.7	1.2	1.8	1.75	2.3
3	1.55	3.3	3.95	1.8	1.8	2.4	5.4	1.4	1.2	1.65	1.8	2.3
4	1.7	3.4	3.75	1.65	2.15	2.3	3.4	1.3	1.25	1.6	1.9	2.3
5	1.75	3.4	3.55	1.55	3.45	12.7	2.7	1.3	1.2	1.65	1.8	2.3
6	1.65	3.4	3.3	1.65	2.1	5.25	1.85	1.3	1.3	1.55	1.7	2.3
7	1.8	3.45	3.05	1.7	1.65	3.25	1.75	1.3	1.25	1.5	1.7	2.3
8	1.95	3.55	2.65	1.6	1.55	6.3	1.7	1.3	1.2	1.45	1.7	2.3
9	2.1	3.6	2.2	1.75	2.25	8.55	1.7	1.28	1.2	1.4	1.7	2.3
10	2.15	3.6	2.0	1.85	4.8	8.1	1.6	1.25	1.2	1.65	1.7	2.3
11	2.0	3.6	1.9	2.0	3.6	3.8	1.5	1.2	1.3	1.7	1.65	2.3
12	2.15	3.6	1.8	2.05	1.95	3.5	1.6	1.2	1.25	1.6	1.7	2.3
13	2.25	3.6	1.95	2.2	1.8	3.6	1.65	1.2	1.25	1.65	1.7	2.3
14	2.2	3.6	1.85	2.1	1.75	3.55	1.7	1.2	1.3	1.85	1.6	2.3
15	2.35	3.6	1.7	2.05	1.75	3.45	1.65	1.2	1.25	2.1	1.6	2.3
16	2.3	3.7	1.85	2.05	1.7	3.5	1.55	1.2	1.2	1.8	1.65	2.3
17	2.4	3.8	2.0	1.9	1.65	3.65	1.5	1.25	1.2	1.65	1.65	2.35
18	2.2	3.95	1.9	1.85	1.85	3.8	1.4	1.2	1.2	1.6	1.7	2.4
19	2.15	4.15	1.8	1.8	2.05	3.65	1.4	1.2	1.3	1.6	1.65	2.4
20	2.25	4.2	1.65	1.55	2.3	3.25	1.3	1.2	1.3	1.6	1.6	2.4
21	2.25	4.4	1.6	1.45	2.0	3.05	1.3	1.2	1.25	1.6	1.6	2.4
22	2.3	4.5	1.7	1.4	1.9	2.8	1.3	1.2	1.2	1.95	1.7	2.4
23	2.4	4.6	1.75	1.4	2.4	2.75	1.35	1.2	1.2	1.8	1.6	2.4
24	2.4	4.75	1.6	1.5	4.05	3.05	1.35	1.2	1.3	1.75	1.7	2.4
25	2.5	5.1	1.6	1.45	2.9	3.2	1.25	1.2	1.3	1.95	1.7	2.4
26	2.5	5.2	1.7	1.4	2.45	3.05	1.3	1.2	1.25	2.1	1.7	2.4
27	2.5	5.3	1.6	1.5	2.4	3.2	1.25	1.15	1.2	2.15	1.9	2.4
28	2.5	5.15	1.6	1.45	2.3	3.3	1.2	1.2	1.25	2.3	2.05	2.4
29	2.65	.....	1.65	1.4	2.4	3.3	1.35	1.08	1.3	2.4	2.1	2.4
30	2.85	.....	1.7	1.5	2.45	3.3	1.3	1.15	2.0	1.8	2.2	2.4
31	2.9	.....	1.65	.....	2.55	.....	1.3	1.2	.....	1.8	.....	2.5

NOTE.—River frozen and readings to the top of the ice from January 8 to February 14 inclusive and from November 28 to December 31 inclusive; water flowing over the top of the ice February 15 to March 8 inclusive.

tion rating table for Pryor Creek at Huntley, Mont., from August 7, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	6	2.60	96	4.10	203	6.20	388
1.10	9	2.70	102	4.20	211	6.40	408
1.20	13	2.80	109	4.30	219	6.60	428
1.30	18	2.90	115	4.40	227	6.80	448
1.40	23	3.00	122	4.50	235	7.00	470
1.50	28	3.10	128	4.60	243	7.20	492
1.60	33	3.20	135	4.70	251	7.40	514
1.70	39	3.30	142	4.80	259	7.60	536
1.80	45	3.40	149	4 90	268	7.80	558
1.90	51	3.50	156	5.00	277	8.00	582
2.00	57	3.60	163	5.20	295	8.20	606
2.10	63	3.70	171	5.40	313	8.40	631
2.20	70	3.80	179	5.60	331	8.60	657
2.30	76	3.90	187	5.80	349	8.80	683
2.40	83	4.00	195	6.00	368	9.00	710
2.50	89						

The above table is applicable only for open-channel conditions. It is based on nine discharge measurements made during 1904-5 and is well defined between gage heights 1 foot and 2 feet. The table has been extended beyond these limits, being based on two flood measurements, one at 10.52 feet and one at 1.93 feet.

Estimated monthly discharge of Pryor Creek at Huntley, Mont., for 1904–5.

[Drainage area, 800 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
1904.						
ugust 7-31	16	6	8.9	441	0.011	0.010
ptember	18	13	16.1	958	.020	.022
tober	33	16	24.7	1,519	.031	.036
ovember	54	18	30.8	1,833	.038	.042
ecember	51	25	34.1	2,097	.043	.050
The period				6,848		
1905.						
nuary 1-7	45	30	37.3	516	.047	.012
arch 9-31	70	33	43.3	1,975	.054	.046
ril	70	23	39.4	2,344	.049	.055
ay	259	30	77.8	4,784	.097	.112
ne	1,370	76	222	13,210	.278	.310
ly	594	13	78.2	4,808	.098	.113
igust	39	9	15.2	935	.019	.022
ptember	57	13	16.6	988	.021	.023
tober	83	23	44.4	2,730	.056	.065
vember 1-27	51	33	39.0	2,089	.049	.049
The period				34,380		

NOTE.—No estimate for ice period.

BIGHORN RIVER[a] AT THERMOPOLIS, WYO.

This station was established May 28, 1900. It was at first located near the hot spring on the "Mile Square, State Reservation," about half a mile northeast of Thermopolis, in T. 43 N., Rs. 94 and 95 W.; but in 1901 it was transferred to the new iron bridge 400 or 500 feet upstream from the former location.

The channel is straight for some distance above and below the station. The banks are high and do not overflow. The bed of the stream is composed of rock and gravel and is fairly permanent. At ordinary stages all of the water flows beneath the bridge proper, but at flood stages it rises under the approaches at each side. There are no obstructions in the channel above the station.

Discharge measurements are made from the bridge, which is a two-span truss structure, each span 125 feet long, with approaches on each side 15 feet long. Sounding points are marked at 10-foot intervals by brass-headed nails driven into the railing on the down-stream side, beginning at the center pier, which is the initial point, and running toward either bank.

The gage is observed by William M. Necce, superintendent of the State reserve, who lives within 100 yards of the station. The gage used in 1900 was a horizontal rod extending out over the water and fastened to posts firmly set in the ground, with the usual wire and weight attachment. In 1901 a new gage, with relative heights the same as those in use in 1900, was painted on the lower center pier of the recently constructed iron bridge, 400 or 500 feet above the old gage. In March, 1903, another gage, serving as a bench mark and for the observer's use at times of high water, was painted on the lower pier of the bridge on the right bank of the river. This gage, which is not reached by the water until it stands 3 feet above datum, enables the observer to read heights of high water more accurately than they can be read on the regular gage, which is in the center of the stream and exposed to the force of the current, causing a rise and fall of several inches on the gage. In March, 1904, the regular gage was replaced by a new one, consisting of a vertical staff firmly fastened by iron bands to the pier on which the former gage was painted.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann = Annual Report; WS = Water-Supply Paper):

Description: WS 37, p 211; 49, p 269; 66, p 23; 84, pp 23–24; 99, p 89; 130, pp 127–128.
Discharge: WS 37, p 211; 49, p 269; 84, p 24; 99, p 90; 130, p 128.
Discharge, monthly: Ann 22, iv, p 291; WS 75, p 123; 99, p 91; 130, p 130.
Gage heights: WS 49, p 269; 66, p 23; 84, p 24; 99, p 90; 130, p 129.
Hydrograph: Ann 22, iv, p 291.
Rating tables: WS 52, p 516; 66, p 170; 99, p 91; 130, p 130.

Discharge measurements of Bighorn River at Thermopolis, Wyo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 9	A. J. Parshall	177	326	1.67	0.85	545
July 10	do	252	910	5.02	3.45	4,567
July 11	do	252	938	5.15	3.60	4,827
July 12	do	252	960	5.25	3.70	5,043
July 18	C. D. Farmer	252	892	4.72	3.30	4,066
July 23	do	244	787	4.54	3.00	3,572
August 1	do	244	687	4.12	2.60	2,830
August 4	do	220	585	3.83	2.40	2,240
August 18	do	220	510	3.30	1.90	1,683
September 9	do	198	476	3.05	1.50	1,454
September 20	do	170	401	2.27	1.20	910
October 12	do	166	339	2.25	1.00	761

[a] A description of this river is included in the general description of the Yellowstone River basin, p. 91.

Daily gage height, in feet, of Bighorn River at Thermopolis, Wyo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.3	1.1	3.9	4.85	2.65	1.6	1.35	0.8	[b]0.3
.....	.3	1.1	4.65	4.75	2.55	1.55	1.5	0.8	0.3
.....	.5	1.2	4.35	4.55	2.5	2.0	1.4	0.8	0.3
.....	.3	1.2	4.6	4.65	2.35	1.95	1.3	0.7	0.2
.....	.3	1.3	5.75	4.55	2.2	1.8	1.25	0.9	0.25
.....	.3	1.4	6.2	4.35	2.45	1.9	1.35	0.8	0.4
.....	.2	1.45	6.1	4.05	2.45	1.85	1.25	0.95	0.35
.....	.3	1.5	6.15	3.75	2.4	1.75	1.2	0.85	0.3
.....	.4	1.4	4.5	3.6	2.25	1.55	1.1	0.85	0.2
.....	.55	1.3	5.5	3.55	2.2	1.5	1.1	0.9	0.4
.....	.75	1.2	4.8	3.4	2.75	1.4	1.0	0.95	0.4
.....	.8	1.2	3.85	3.35	2.3	1.4	1.0	0.9	0.4
.....	.65	1.25	4.15	3.5	2.3	1.45	1.1	0.8	0.5
.....	.6	1.3	4.45	3.65	2.25	1.3	1.1	0.8	0.45
.....	.8	1.1	4.8	3.6	2.1	1.3	1.2	0.7	0.4
.....	.85	1.05	4.55	3.52	2.0	1.25	1.15	0.7	0.3
.....	.7	1.2	4.3	3.7	2.0	1.2	1.3	0.75	0.3
.....	.7	1.05	4.45	3.6	1.95	1.25	1.2	0.75	0.3
.....	.8	1.05	4.6	3.25	1.9	1.2	1.1	0.9	0.2
.....	.8	1.1	4.5	2.95	1.8	1.15	1.0	0.8	0.2
.....	.8	1.25	4.6	2.95	1.8	1.2	0.95	0.85	0.2
.....	.9	1.4	4.45	3.15	1.7	1.15	0.9	0.9	0.3
.....	.95	1.9	4.25	3.05	1.7	1.1	0.9	0.85	0.25
.....	.8	2.05	3.95	2.9	1.7	1.1	0.9	0.8	0.2
.....	.85	1.85	3.9	2.85	1.8	1.0	0.85	0.7	0.2
.....	1.0	1.9	4.3	2.8	1.8	.95	0.9	0.7	0.2
.....	1.1	2.25	4.65	2.8	1.8	1.0	0.9	0.7	0.2
.....	1.0	2.7	5.05	2.85	1.9	1.0	0.8	0.65	0.3
.....	1.0	4.0	5.0	2.85	1.8	1.05	0.85	[a]0.55	0.3
.....	1.05	4.15	5.05	2.8	1.7	1.25	0.9	0.45	0.4
.....	.....	3.3	.....	3.15	1.65	.....	0.8	.....	0.3

[a] River frozen over. [b] River full of ice.

tation rating table for Bighorn River at Thermopolis, Wyo., from April 1 to October 14, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
.20	150	1.50	1,255	2.80	3,205	4.00	5,615
.30	205	1.60	1,375	2.90	3,390	4.20	6,045
.40	265	1.70	1,500	3.00	3,580	4.40	6,475
.50	330	1.80	1,630	3.10	3,770	4.60	6,905
.60	400	1.90	1,765	3.20	3,965	4.80	7,340
.70	475	2.00	1,905	3.30	4,165	5.00	7,780
.80	555	2.10	2,050	3.40	4,365	5.20	8,220
.90	640	2.20	2,200	3.50	4,570	5.40	8,660
1.00	730	2.30	2,355	3.60	4,775	5.60	9,100
1.10	825	2.40	2,515	3.70	4,985	5.80	9,550
1.20	925	2.50	2,680	3.80	5,195	6.00	10,000
1.30	1,030	2.60	2,850	3.90	5,405	6.20	10,450
1.40	1,140	2.70	3,025				

The above table is applicable only for open-channel conditions. It is based on 11 discharge measurements made during 1905 and is well defined between gage heights 0.8 foot and 3.7 feet.

Station rating table for Bighorn River at Fort Custer, Mont., from June 16, 1904, to Dec. 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.40	1,260	1.60	3,660	2.80	7,460	4.00	12,780
.50	1,400	1.70	3,920	2.90	7,820	4.20	13,940
.60	1,540	1.80	4,200	3.00	8,200	4.40	15,180
.70	1,700	1.90	4,480	3.10	8,580	4.60	16,500
.80	1,860	2.00	4,780	3.20	8,980	4.80	17,900
.90	2,040	2.10	5,080	3.30	9,380	5.00	19,380
1.00	2,240	2.20	5,400	3.40	9,800	5.20	20,940
1.10	2,440	2.30	5,720	3.50	10,240	5.40	22,660
1.20	2,660	2.40	6,060	3.60	10,720	5.60	24,460
1.30	2,900	2.50	6,400	3.70	11,200	5.80	26,340
1.40	3,140	2.60	6,740	3.80	11,720		
1.50	3,400	2.70	7,100	3.90	12,240		

The above table is applicable only for open-channel conditions. It is based on fourteen discharge measurements made during 1904–5, and is fairly well defined between gage heights 0.5 foot and 4.5. The table has been extended beyond these limits, being based on one measurement at 5.55 feet.

Estimated monthly discharge of Bighorn River at Fort Custer, Mont., for 1904–5.

[Drainage area, 20,720 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
1904.						
June 16–30	25,290	13,940	20,670	615,000	0.998	
July	17,540	8,010	12,260	753,800	.592	
August	7,532	2,506	4,583	281,800	.221	
September	3,920	1,700	2,449	145,700	.118	
October	1,860	1,620	1,728	106,300	.083	
November	1,700	1,400	1,558	92,710	.075	
The period				1,995,000		
1905.						
January 1–21	1,700	1,400	1,485	61,850	.072	
March 4–31	4,200	1,260	1,957	108,700	.094	
April	1,896	1,200	1,440	85,690	.069	
May	14,060	1,700	4,318	265,500	.208	
June	24,460	11,460	17,420	1,037,000	.841	
July	15,960	5,400	9,143	562,200	.441	
August	5,400	2,440	3,486	214,300	.168	
September 1–25	2,660	1,470	2,077	103,000	.100	
October 2–31	5,080	1,700	2,202	131,000	.106	
November 1–27	1,860	1,668	1,732	92,750	.084	
The period				2,662,000		

NOTE.—No estimate for ice period.

LITTLE BIGHORN RIVER AT CROW AGENCY, MONT.

iis station was established March 24, 1905. It is located at the Burlington and Missouri :r Railroad bridge, one-fourth mile south of Crow Agency, Mont.

ne channel is straight for 200 feet above and below the station. Both banks are high unwooded. The bed of the stream is covered with rock and gravel, is free from vege- on, and is permanent. All of the water passes between the abutments of the bridge at stages. The velocity of the current is moderate. There are a few large rocks in the r, and about 1,200 feet above the station, at the head of Crow Agency ditch, there is a e and brush dam.

Discharge measurements are made from the upstream side of the single-span bridge to ch the gage is attached. The initial point for soundings is a nail driven in the upstream rd rail directly over the inner face of the right abutment.

Daily gage readings have been taken since the establishment of the station by three suc- sive observers—C. C. Hutton, J. A. Smith, and Thomas W. McHoes. The standard in gage is attached to the upstream side of the bridge, near the center of the river. The gth of the chain is 20.31 feet. The gage is referred to bench marks as follows: (1) A ss on the west end of the south abutment, directly below the figures "1903;" elevation, 37 feet. (2) A bolt head in the guard rail on the upstream side of the bridge, 7 feet south he gage; elevation, 19.33 feet. (3) A nail in the east end of the cap on piles supporting railroad track over Crow Agency ditch; elevation, 14.33 feet. Elevations are above the) of the gage.

Discharge measurements of Little Bighorn River at Crow Agency, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
ch 24	L. R. Stockman	114	85	1.43	2.00	122
il 26	J. H. Sloan	82	83	1.51	2.00	125
11	do	89	165	2.77	3.10	457
e 10	do	99	326	3.85	4.80	1,253
e 26	do	92	262	3.38	4.04	885
18	do	87	148	1.82	2.48	268
ust 18	do	83	91	1.37	2.05	124
ember 13	do	82	68	1.08	1.89	74
ber 19	do	83	69	1.06	1.90	72
ber 30	Morse and Sloan	82	83	1.38	2.06	115

Station rating table for Bighorn River at Fort Custer, Mont., from June 16, 1904, to Dec 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.40	1,260	1.60	3,660	2.80	7,460	4.00	12,780
.50	1,400	1.70	3,920	2.90	7,820	4.20	13,940
.60	1,540	1.80	4,200	3.00	8,200	4.40	15,180
.70	1,700	1.90	4,480	3.10	8,580	4.60	16,500
.80	1,860	2.00	4,780	3.20	8,980	4.80	17,900
.90	2,040	2.10	5,080	3.30	9,380	5.00	19,380
1.00	2,240	2.20	5,400	3.40	9,800	5.20	20,940
1.10	2,440	2.30	5,720	3.50	10,240	5.40	22,660
1.20	2,660	2.40	6,060	3.60	10,720	5.60	24,460
1.30	2,900	2.50	6,400	3.70	11,200	5.80	26,340
1.40	3,140	2.60	6,740	3.80	11,720		
1.50	3,400	2.70	7,100	3.90	12,240		

The above table is applicable only for open-channel conditions. It is based on fourteen disc measurements made during 1904–5, and is fairly well defined between gage heights 0.5 foot and 4.5 The table has been extended beyond these limits, being based on one measurement at 5.55 feet.

Estimated monthly discharge of Bighorn River at Fort Custer, Mont., for 1904–5.

[Drainage area, 20,720 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dep inc
1904.						
June 16–30	25,290	13,940	20,670	615,000	0.998	
July	17,540	8,010	12,260	753,800	.592	
August	7,532	2,506	4,583	281,800	.221	
September	3,920	1,700	2,449	145,700	.118	
October	1,860	1,620	1,728	106,300	.083	
November	1,700	1,400	1,558	92,710	.075	
The period				1,995,000		
1905.						
January 1–21	1,700	1,400	1,485	61,850	.072	
March 4–31	4,200	1,260	1,957	108,700	.094	
April	1,896	1,200	1,440	85,690	.069	
May	11,000	1,700	4,318	265,500	.208	
June	21,460	11,460	17,420	1,037,000	.841	
July	15,960	5,400	9,113	562,200	.441	
August	5,400	2,440	3,486	214,300	.168	
September 1–25	2,660	1,470	2,077	103,000	.100	
October 2–31	5,080	1,700	2,202	131,000	.106	
November 1–27	1,860	1,668	1,732	92,750	.084	
The period				2,662,000		

NOTE.—No estimate for ice period.

LITTLE BIGHORN RIVER AT CROW AGENCY, MONT.

station was established March 24, 1905. It is located at the Burlington and Missouri Railroad bridge, one-fourth mile south of Crow Agency, Mont.

channel is straight for 200 feet above and below the station. Both banks are high nwooded. The bed of the stream is covered with rock and gravel, is free from vege-, and is permanent. All of the water passes between the abutments of the bridge at ages. The velocity of the current is moderate. There are a few large rocks in the , and about 1,200 feet above the station, at the head of Crow Agency ditch, there is a and brush dam.

scharge measurements are made from the upstream side of the single-span bridge to ch the gage is attached. The initial point for soundings is a nail driven in the upstream rd rail directly over the inner face of the right abutment.

Daily gage readings have been taken since the establishment of the station by three suc-sive observers—C. C. Hutton, J. A. Smith, and Thomas W. McHoes. The standard ain gage is attached to the upstream side of the bridge, near the center of the river. The gth of the chain is 20.31 feet. The gage is referred to bench marks as follows: (1) A ss on the west end of the south abutment, directly below the figures "1903;" elevation, 87 feet. (2) A bolt head in the guard rail on the upstream side of the bridge, 7 feet south the gage; elevation, 19.33 feet. (3) A nail in the east end of the cap on piles supporting e railroad track over Crow Agency ditch; elevation, 14.33 feet. Elevations are above the ro of the gage.

Discharge measurements of Little Bighorn River at Crow Agency, Mont., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
arch 24	L. R. Stockman	114	85	1.43	2.00	122
pril 26	J. H. Sloan	82	83	1.51	2.00	125
lay 11	do	89	165	2.77	3.10	457
une 10	do	99	326	3.85	4.80	1,253
une 26	do	92	262	3.38	4.04	885
uly 18	do	87	148	1.82	2.48	268
ugust 18	do	83	91	1.37	2.05	124
eptember 13	do	82	68	1.08	1.89	74
October 19	do	83	69	1.06	1.90	72
October 30	Morse and Sloan	82	83	1.38	2.06	115

Discharge measurements of Shoshone River near Cody, Wyo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 7	A. J. Parshall	128	359	1.98	2.70	7[illegible]
June 4	J. Ahern	178	909	6.72	5.70	6,0[illegible]
June 20	Brundage and Soper	158	647	4.69	4.20	3,0[illegible]
June 26	do	185	909	7.19	5.70	6,5[illegible]
June 28	do	193	965	7.82	5.95	7,5[illegible]
July 8	do	168	784	6.02	5.05	4,7[illegible]
July 14	A. J. Parshall	160	648	5.71	4.50	3,7[illegible]
July 15	do	159	635	5.48	4.40	3,4[illegible]
August 26	do	131	385	2.22	2.75	[illegible]
September 16	Brundage and Soper	123	294	1.46	2.27	[illegible]
December 1	do	90	202	1.09	1.79	[illegible]

[a] Made by wading above bridge.

Daily gage height, in feet, of Shoshone River near Cody, Wyo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.0	1.9	2.5	2.8	2.2	5.0	5.0	3.5	2.7	2.0	2.1	1.8
2	2.1	1.9	2.5	2.8	2.3	5.1	5.0	3.4	2.7	1.9	2.0	1.8
3	2.1	2.0	2.6	2.8	2.5	5.5	5.3	3.2	2.8	1.8	2.1	1.9
4	2.0	2.0	2.6	2.8	2.7	5.7	5.2	3.8	2.8	1.9	2.0	1.8
5	1.9	1.9	2.6	2.9	3.0	6.0	5.1	3.5	2.7	1.8	2.1	1.8
6	1.9	1.8	2.5	2.9	3.0	5.5	4.7	3.5	2.6	2.0	2.2	2.1
7	1.9	1.7	2.7	2.8	2.7	5.0	4.7	3.5	2.6	2.1	2.1	2.0
8	1.8	1.7	2.7	2.9	2.7	5.8	4.8	3.9	2.5	2.0	2.0	2.0
9	1.8	1.6	2.6	2.9	2.8	5.5	4.8	4.0	2.6	2.0	2.0	1.8
10	1.8	1.6	2.6	2.8	3.0	5.0	4.7	3.8	2.6	1.9	2.1	1.8
11	1.8	1.7	2.5	2.9	2.9	5.2	4.6	3.0	2.7	1.8	2.2	1.7
12	1.9	1.7	2.6	2.9	2.9	5.2	5.3	3.1	2.6	1.9	2.0	2.0
13	1.9	1.8	2.7	2.9	2.9	5.7	4.6	3.0	2.6	2.1	1.9	2.1
14	2.0	1.8	2.5	2.8	3.0	5.8	4.5	2.9	2.5	2.1	1.8	2.0
15	2.0	1.8	2.5	2.9	2.8	5.6	4.5	3.0	2.4	2.0	1.9	2.0
16	2.0	1.9	2.6	2.9	3.1	5.6	4.7	2.9	2.3	2.0	2.0	1.9
17	1.9	2.0	2.7	3.0	3.0	4.7	4.8	2.9	2.3	2.1	2.0	1.8
18	1.9	2.0	2.7	3.0	3.1	4.7	4.5	2.8	2.3	1.9	2.0	1.8
19	1.9	2.1	2.7	3.0	3.0	4.5	4.2	2.7	2.3	2.0	2.0	1.9
20	1.8	2.1	2.8	3.1	3.5	4.2	4.4	2.7	2.2	1.8	2.1	2.0
21	1.8	2.2	2.9	3.1	3.5	4.5	4.5	2.7	2.2	2.1	2.0	1.9
22	1.7	2.2	2.9	2.9	3.8	5.0	4.1	2.7	2.2	2.1	1.9	2.0
23	1.7	2.4	2.9	3.0	3.5	5.0	4.1	2.7	2.2	2.1	2.0	1.8
24	1.7	2.5	2.8	2.8	3.0	5.0	4.1	2.8	2.2	2.1	2.0	1.8
25	1.6	2.5	3.0	2.7	3.3	5.0	4.0	2.8	2.1	2.0	2.0	2.0
26	1.6	2.4	3.0	2.8	3.5	5.7	4.0	2.8	2.1	2.0	2.0	2.0
27	1.8	2.5	3.1	2.9	3.6	5.9	4.4	2.8	2.0	2.0	1.9	1.9
28	1.8	2.5	2.8	3.0	3.5	5.8	4.4	2.8	1.9	2.1	1.9	2.0
29	1.8	.....	2.9	2.5	4.0	5.8	4.4	2.7	1.9	1.9	1.8	2.0
30	1.9	.....	2.9	2.5	4.3	5.5	4.3	2.9	2.0	1.8	1.9	[illegible]
31	1.9	.....	3.0	.....	4.5	.....	3.6	3.0	.....	2.1	.....	.....

NOTE.—The gage heights for this station as reported
have been corrected and adjusted on the basis of 30
phers and by the use of the Marquette station gage h

Estimated monthly discharge of Shoshone River near Cody, Wyo., for 1905.

[Drainage area, 1,480 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	365	190	270	16,600	0.182	0.210
y.....	630	190	351	19,490	.237	.247
.....	1,230	630	833	51,220	.563	.649
.....	1,230	630	972	57,840	.657	.733
.....	3,705	420	1,401	86,140	.947	1.09
.....	7,850	3,070	5,747	342,000	3.88	4.33
.....	5,720	1,965	3,891	239,200	2.63	3.03
.....	2,675	800	1,286	79,070	.869	1.00
ber.....	900	255	559	33,260	.378	.422
r.....	350	220	295	18,140	.199	.229
ber.....	410	220	303	18,030	.205	.229
ber.....	350	190	270	16,600	.182	.210
he year.....	7,850	190	1,348	977,600	.911	12.38

:.—The greater part of the published gage heights for December, 1904, are probably 1 foot too low, to inaccurate gage reading, thus causing great error in published estimates for that month. The timates are based on two rating curves.

SOUTH FORK OF SHOSHONE RIVER AT MARQUETTE, WYO.

th Fork, which furnishes about 25 per cent of the discharge of Shoshone River, rises Shoshone Mountains, near the southeast corner of the Yellowstone National Park, ows northeastward about 50 miles to the entrance of the canyon, where it joins North It receives numerous small tributaries which enter from both sides.

gaging station was established April 26, 1903, but was discontinued during 1904. It ated at the county highway bridge at Marquette, Wyo., 12 miles west of Cody, in sec. 52 N., R. 103 W.

channel forms the arc of a long curve extending about 200 feet above and below the . The banks do not overflow, but at highest stages the water rises a few feet against ridge abutments on either side. The bed of the stream is rocky and stable. The flows in a single channel under the bridge, the greatest depth being near the center. rocks near the left bank interfere somewhat with the accuracy of discharge measure-s.

charge measurements are made from the bridge, sounding points being indicated by painted at 10-foot intervals on the lower railing. The initial point for sounding is abutment on the left bank.

gage, which is read twice daily by C. P. MacGlashan, is a vertical timber set well the stream and fastened to a strong post placed 1 foot deep in the rocky bed of the el and securely braced to the sleeper of the bridge. The bench mark is the lower e of the iron plate at the bottom of the bridge stringer at the gage rod; elevation, feet above the zero of the gage.

escription of this station, with gage-height and discharge data, is contained in Water-Paper No. 99 of the United States Geological Survey, pages 85–87.

Discharge measurements of South Fork of Shoshone River at Marquette, Wyo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 25	J. Ahern	85	88	2.16	0.70	190
May 8	A. J. Parshall	118	113	2.52	1.00	285
June 6	J. Ahern	144	275	4.61	2.40	1,269
June 15	Brundage and Saunders	144	338	5.36	2.80	1,812
June 19	Brundage and Soper	144	228	4.14	1.95	943
June 27	do	144	430	5.95	3.35	2,559
July 1	do	144	343	5.42	2.75	1,860
July 15	A. J. Parshall	144	262	5.09	2.35	1,335
September 16	Brundage and Soper	85	67	1.94	.63	130
September 19 [a]	do	72	91	1.22	.62	112

[a] Made by wading 250 feet above usual point.

Daily gage height, in feet, of South Fork of Shoshone River at Marquette, Wyo., for 1905.

Day	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	0.7	2.65	3.0	1.45	0.8	0.7	0.5
2	.75	2.65	2.75	1.4	.8	.7	.6
3	.85	2.8	2.45	1.35	.85	.6	.6
4	.9	3.0	2.3	1.35	.85	.6	.6
5	.85	2.9	2.45	1.25	.8	.6	.6
6	.9	2.3	2.5	1.35	.75	.6	.6
7	.95	2.3	2.7	1.3	.75	.55	.6
8	1.0	2.8	2.6	1.3	.7	.5	.6
9	.9	2.8	2.6	1.15	.75	.55	.6
10	.9	2.85	2.35	1.15	.75	.6	.55
11	.9	2.4	2.7	1.1	.8	.5	.55
12	.8	2.3	2.4	1.1	.75	.5	.6
13	.8	2.7	2.45	.95	.75	.6	.7
14	.7	2.85	2.6	.9	.65	.6	.65
15	.8	2.9	2.5	.95	.65	.55	.7
16	.75	2.7	2.45	1.05	.7	.6	.7
17	1.1	2.15	2.6	.95	.7	.6	.7
18	1.7	2.15	2.45	1.0	.65	.6	.7
19	1.4	2.0	1.8	.85	.65	.65	.7
20	1.55	2.0	2.2	.85	.6	.7	.65
21	1.65	2.1	1.95	.8	.6	.6	.7
22	1.6	2.7	1.8	.85	.6	.5	.65
23	1.65	2.3	2.65	.8	.6	.6	.65
24	1.45	2.6	2.3	.85	.6	.6	.7
25	1.45	3.05	1.7	.8	.5	.6	.6
26	1.55	3.4	2.1	.9	.5	.6	.55
27	1.5	3.8	2.5	.85	.4	.6	.5
28	1.7	3.15	2.25	.9	.5	.5	.4
29	2.3	3.0	1.8	.9	.55	.5	.35
30	2.2	2.85	1.7	.85	.6	.5	.35
31	2.55	.....	1.5	.9	.....	.5	.....

...rating table for South Fork of Shoshone River at Marquette, Wyo., from May 1 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.40	63	1.30	460	2.20	1,180	3.10	2,235
.50	87	1.40	525	2.30	1,280	3.20	2,365
.60	115	1.50	590	2.40	1,385	3.30	2,500
.70	149	1.60	660	2.50	1,495	3.40	2,635
.80	189	1.70	735	2.60	1,610	3.50	2,775
.90	235	1.80	815	2.70	1,730	3.60	2,915
1.00	285	1.90	900	2.80	1,850	3.70	3,055
1.10	340	2.00	990	2.90	1,975	3.80	3,200
1.20	400	2.10	1,085	3.00	2,105		

...bove table is applicable only for open-channel conditions. It is based on eight discharge meas-...its made during 1905, and is well defined.

...ated monthly discharge of South Fork of Shoshone River at Marquette, Wyo., for 1905.

[Drainage area, 500 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	1,552	149	474	29,140	0.948	1.09
.....	3,200	990	1,724	102,600	3.45	3.85
.....	2,105	590	1,335	82,090	2.67	3.08
...ist.....	558	189	314	19,310	.628	.724
...ember.....	212	63	143	8,509	.286	.319
...ber.....	149	87	110	6,764	.220	.254
...ember.....	149	53	117	6,962	.234	.261
The period.....	.....	.....	.....	255,400	.....	.....

PINEY CREEK AT KEARNEY, WYO.

...iney Creek rises on the eastern slope of the Bighorn Mountains, in the extreme north-...stern part of Johnson County, Wyo., in the elevated plateau region east of Cloud Peak, ...d flows in a general northeasterly direction until it joins Clear Creek, a branch of Powder ...er. Its entire length is between 40 and 50 miles, and its total drainage area about 160 ...uare miles. It receives a number of small tributaries, among which may be mentioned ...tle Piney Creek, which enters from the south near the gaging station at Kearney, and Box-...er Creek, which comes in a few miles above the junction of Piney and Clear creeks. Box-...er Creek probably obtains a part of its limited discharge by seepage from De Smet Lake, ...mall lake without outlet on the divide between this basin and that of Clear Creek to the ...th. The valley of Piney Creek is narrow, and is so largely composed of rock, bowlders, ...d cobblestones that little effort has been made to use it for agricultural purposes. The ...of the rolling uplands and side hills is a rich, deep, sandy loam, generally covered with a ...ll growth of sagebrush and thick, luxuriant grasses. A few thousand acres, including ...ral sidehill tracts, comprise the arable land within the Piney basin proper to which the ...r supply has been applied. Two large ditches, taken out at the point where the creek ...s the mountain slopes to enter the valley, have been carried from Piney Creek across ...ow divide to the Prairie Dog basin, where the soil conditions are similar. Near the

head of Piney Creek are several small lakes, at one of which—Piney Lake—an earthen dam was constructed some years ago to conserve waters for use on the northern slope of the northern Piney divide. This dam, which was not well planned or constructed, gave way when nearly filled and caused considerable destruction to properties below.

The gaging station was established September 6, 1902. It is located at the highway bridge about 100 yards south of the Kearney post-office, at the crossing of the stage road from Buffalo to Sheridan, on the water front of the Geier ranch. This ranch is one of the most productive properties on Piney Creek and is built on the site of old Fort Kearney.

The channel is straight for 600 feet above and below the station. The right bank is high and does not overflow; the left bank overflows at extreme flood stages, when a slough about 100 yards from the bank carries a small amount of water. The bed of the stream is composed of gravel. There is but one channel. The current is very swift during high water and sluggish at low-water periods. There are no obstructions in the channel, either above or below.

Discharge measurements are made from the bridge. The initial point is a zero painted on the floor of the bridge at the right bank.

The gage is read once daily at ordinary stages and twice daily during times of greatest fluctuations, by A. J. Sinsel, who lives one-fourth mile distant. The gage is a vertical staff, spiked to the lower abutment of the bridge on the right bank. The bench mark is the United States Geological Survey bench at Geier's ranch, about 60 feet south of the gage; it is marked "Sher. 4662," and its elevation is 4,661.77 feet above sea level. The elevation of the zero of the gage is 4,645.96 feet; the range of gage heights is about 2.5 feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 84, p 21; 99, p 77; 130, p 138.
Discharge: 84, p 21; 99, pp 77-78; 130, p 139.
Discharge, monthly: 99, p 79; 130, p 140.
Gage heights: 84, p 21; 99, p 78; 130, p 139.
Rating table: 99, p 79; 130, p 140.

Discharge measurements of Piney Creek at Kearney, Wyo., for 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 15	A. J. Parshall	40	57	0.54	1.40	31
May 10	do	41	81	1.32	2.00	107
May 11	do	41	80	1.18	1.92	94
June 5	do	42	137	7.33	3.40	1,004
June 6 [a]	do	42	95	5.36	2.80	509
July 6	do	41	89	1.66	1.95	148
July 6	do	41	91	1.46	1.90	133
July 7	do	41	88	1.39	1.85	122
July 18	do	40	80	1.21	1.70	97
August 24	do	40	62	.82	1.40	52
September 30	do	40	53	.45	1.10	24

[a] Measured above bridge.

Daily gage height, in feet, of Piney Creek at Kearney, Wyo., for 1905.

Day	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	1.4	1.8	2.88	2.35	1.6	1.25	1.15	1.4
.....	1.4	1.9	3.1	2.3	1.6	1.25	1.2	1.4
.....	1.4	1.8	3.3	2.3	1.55	1.2	1.15	1.4
.....	1.4	1.7	3.7	2.2	1.4	1.2	1.15	1.4
.....	1.4	1.7	3.5	2.15	1.2	1.2	1.15	1.4
.....	1.45	1.8	2.78	2.05	1.2	1.2	1.15	1.4
.....	1.45	1.85	2.88	1.9	1.2	1.2	1.15	1.4
.....	1.5	1.85	3.25	1.9	1.1	1.2	1.15	1.4
.....	1.5	1.9	3.25	1.9	1.1	1.2	1.15	1.4
.....	1.5	1.9	2.88	1.9	1.1	1.15	1.1	1.35
.....	1.5	1.95	2.75	1.9	1.2	1.15	1.1	1.35
.....	1.5	2.0	2.72	1.9	1.3	1.15	1.1	1.35
.....	1.55	1.95	2.82	1.9	1.3	1.15	1.1	1.35
.....	1.55	1.95	2.75	1.9	1.2	1.15	1.1	1.35
.....	1.55	2.0	2.68	2.1	1.2	1.15	1.15	1.35
.....	1.5	2.0	2.62	2.0	1.2	1.15	1.15	1.35
.....	1.5	2.1	2.45	1.95	1.2	1.15	1.15	1.35
.....	1.5	2.2	2.35	1.8	1.2	1.15	1.15	1.35
.....	1.5	2.3	2.30	1.7	1.2	1.15	1.15	1.3
.....	1.5	2.2	2.35	1.9	1.2	1.15	1.2	1.3
.....	1.5	2.3	2.38	1.85	1.3	1.15	1.25	1.3
.....	1.5	2.35	2.38	1.75	1.3	1.2	1.3	1.3
.....	1.5	2.75	2,38	1.7	1.4	1.2	1.35	1.3
.....	1.55	2.55	2.3	1.7	1.45	1.15	1.4	1.3
.....	1.6	2.5	2.3	1.7	1.4	1.15	1.4	1.3
.....	1.7	2.5	2.42	1.7	1.4	1.15	1.45	1.3
.....	1.85	2.45	2.45	1.8	1.3	1.15	1.4	1.3
.....	1.75	2.5	2.45	1.75	1.3	1.15	1.4	1.3
.....	1.7	2.65	2.25	1.65	1.3	1.15	1.4	1.3
.....	1.75	2.75	2.3	1.65	1.3	1.15	1.4	1.3
.....	.....	2.85	.....	1.6	1.25	.....	1.4	.....

rating table for Piney Creek at Kearney, Wyo., from January 1, 1904, to June 5, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.20	15	1.80	76	2.40	262	3.00	660
1.30	21	1.90	96	2.50	310	3.10	750
1.40	29	2.00	118	2.60	364	3.20	850
1.50	38	2.10	144	2.70	430	3.30	960
1.60	48	2.20	178	2.80	500	3.40	1,080
1.70	60	2.30	218	2.90	580	3.50	1,200

ove table is applicable only for open-channel conditions. It is based on nine discharge measure-ade during 1904, and is well defined between gage heights 1.3 feet and 3 feet.

Station rating table for Piney Creek at Kearney, Wyo., from June 6 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.10	24	1.70	94	2.30	262	2.90	505
1.20	32	1.80	113	2.40	302	3.00	675
1.30	41	1.90	136	2.50	347	3.10	765
1.40	52	2.00	162	2.60	400	3.20	880
1.50	64	2.10	192	2.70	460	3.30	960
1.60	78	2.20	225	2.80	525		

The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made subsequent to June 5, 1905. It is well defined between gage heights 1.1 feet and 2 feet.

Estimated monthly discharge of Piney Creek at Kearney, Wyo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet
	Maximum.	Minimum.	Mean.	
April	86	29	42.2	2,5
May	540	60	196	12,0
June	1,450	244	510	30,3
July	282	78	142	8,7
August	78	24	41.3	2,5
September	36	28	29.7	1,7
October	58	24	35.3	2,1
November	52	41	45.8	2,7
The period				62,8

MISCELLANEOUS MEASUREMENT.

A measurement of Clark Fork at Bridger, Mont., made June 1, 1905, gave the following Area of section, 755 square feet; mean velocity, 5.42 feet per second; discharge, 4,088 second-feet.

LITTLE MISSOURI RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

The Little Missouri rises in the central part of Crook County, in northeastern Wyoming flows northeastward, crossing the southeast corner of Montana and the northwest corner c South Dakota, and empties into the Missouri in North Dakota, in the Fort Berthold India Reservation. The upper portion of the basin is mountainous, but the stream flows for th most part through a rolling country bounded in places by ranges of steep hills carrying son timber. The soil is partly a sandy loam and partly gumbo, and there is little land und cultivation. The stream receives numerous small tributaries, most of which are dry for t greater part of the year. The main floods occur during March, May, June, and Ju During the rainy season some water is diverted from the tributaries and a small quantity stored for irrigation.

LITTLE MISSOURI RIVER AT ALZADA, MONT.

This station was established April 3, 1904. It is located at the highway bridge on the c Spearfish and Miles City stage road, about one-half mile northwest of Alzada, Mont.

The channel is straight both above and below the station for about 200 feet. Both ban are high, but are liable to overflow at extreme high water. The bed of the stream is co posed of fine silt and is fairly permanent. The current is moderately swift, except at l

There is but one channel, broken by the middle crib pier of the bridge. This pier e ice breaker just above are the only obstructions in the channel at the station. Wild brush on the banks tend to retard the flow during high water. Below the station llows grow in some places so that their branches reach nearly across the channel. The n is frozen from about December 20 to March 10, and observations are discontinued g that time.

charge measurements are made at high stages from the downstream side of the bridge. nitial point for soundings is a bolt in the downstream hand rail near the left end of the e. Low-water measurements are made by wading one-half mile above the gage.

e gage, which was read during 1905 once each day by Miss Elsie King, consists of a plain attached vertically to the downstream side of the crib pier supporting the middle of the e. The gage is referred to bench marks as follows: (1) A spike driven into the base of e about 50 feet west of the left end of the bridge; elevation above the zero of the gage, feet. (2) A United States Geological Survey standard bench mark in front of the la post-office, about 2,000 feet distant; elevation above sea level, 3,428 feet, and above ero of the gage, 26.82 feet. The elevation of the gage zero above sea level is 3,401.18

lescription of this station, with gage height and discharge data, is contained in Waterly Paper No. 130 of the United States Geological Survey, pages 140 to 143.

Discharge measurements of Little Missouri River at Alzada, Mont., in 1905.

ate.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
1	H. D. Comstock	6	1.5	1.0	1.10	1.5
	do	6	2.1	2.14	1.24	4.5
	do	21	13.0	2.29	1.90	3.0
24	do				1.10	3.0

Daily gage height, in feet, of Little Missouri River at Alzada, Mont., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov
1		1.6	1.2	1.1	1.4	2.2	1.5	5.3	1
2		1.6	1.5	1.1	3.6	1.9	2.8	4.0	1
3		1.5	4.4	2.0	13.0	1.2	2.2	3.3	1
4		1.5	11.4	2.0	13.1	1.0	1.8	2.3	1
5		1.1	12.6	1.8	3.8	2.0	1.4	1.4	1
6		1.1	9.95	1.4	3.7	1.2	1.2	1.2	1
7		1.1	4.6	1.2	3.4	1.2	1.2	1.1	1
8		1.1	2.9	1.2	3.2	1.2	1.2	1.0	1
9		1.1	1.6	3.0	2.7	1.2	1.2	1.0	1
10		1.1	1.6	2.2	2.6	1.2	1.2	1.0	1
11		1.1	1.6	1.5	2.5	1.2	1.2	1.0	1
12		1.1	1.5	1.3	2.4	3.0	1.2	1.0	1
13		1.1	1.3	1.2	2.3	6.0	1.2	1.0	1
14		1.1	1.3	1.1	3.0	4.0	1.0	1.0	1
15	1.4	1.1	1.3	8.5	3.5	2.0	1.0	1.0	1
16	1.4	1.4	1.2	3.0	2.2	1.5	1.0	1.0	1
17	1.4	1.4	1.2	9.7	4.0	1.2	1.0	1.0	1
18	1.4	1.4	1.1	14.0	3.2	1.2	1.0	1.0	1
19	1.4	1.3	1.1	12.6	2.0	1.2	1.0	1.0	1
20	1.4	1.2	1.2	11.5	7.0	1.2	1.0	1.0	1
21	1.4	1.2	1.2	4.0	6.5	1.0	1.0	1.0	1
22	1.4	1.2	1.2	2.2	4.5	1.0	1.0	1.4	1
23	1.4	1.2	1.3	2.5	3.0	1.0	1.0	3.8	1
24	1.4	1.2	1.1	2.7	2.0	1.0	1.0	2.4	1
25	1.4	1.2	1.1	3.0	3.0	1.0	1.0	1.2	1
26	1.4	1.2	1.2	3.2	4.3	1.0	1.0	1.2	1
27	1.4	1.2	1.2	2.0	5.0	1.0	1.0	1.0	1
28	1.7	1.2	1.1	1.6	4.0	1.2	1.0	1.0	1
29	1.7	1.2	1.1	1.5	7.0	1.0	1.0	1.0	1
30	1.7	1.2	1.1	1.4	3.9	1.0	6.0	1.0	1
31	1.7	.....	1.1	.....	2.6	10.0	.....	1.0	.....

Station rating table for Little Missouri River at Alzada, Mont., from March 15, to November 3 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	1	2.30	67	3.60	178	4.90	300
1.10	2	2.40	75	3.70	187	5.00	310
1.20	4	2.50	83	3.80	196	5.10	320
1.30	7	2.60	91	3.90	205	5.20	330
1.40	10	2.70	99	4.00	214	5.30	340
1.50	14	2.80	107	4.10	223	5.40	350
1.60	19	2.90	115	4.20	232	5.50	360
1.70	24	3.00	124	4.30	241	5.60	370
1.80	30	3.10	133	4.40	250	5.70	380
1.90	37	3.20	142	4.50	260	5.80	390
2.00	44	3.30	151	4.60	270	5.90	400
2.10	51	3.40	160	4.70	280	6.00	411
2.20	59	3.50	169	4.80	290		

The above table is applicable only for open-channel conditions. It is based on 12 discharge measurements made during 1904–5, and is well defined between gage heights 1 foot and 6 feet. Above 3 feet table is the same as that for 1904. Above 6 feet the discharge is only approximate.

Estimated monthly discharge of Little Missouri River at Alzada, Mont., for 1905.

[Drainage area, 600 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
h 15–31	24	10	13.3	449	0.022	0.014
	19	2	5.6	333	.0093	.010
	1,173	2	124	7,624	.207	.239
	1,354	2	212	12,620	.353	.394
	1,237	10	245	15,060	.408	.470
	861	1	60.2	3,702	.100	.115
emi er	411	1	22.6	1,345	.038	.042
ber	340	1	35.4	2,177	.059	.068
ember	1	1	1.0	60	.0017	.0019
The period				43,370		

LITTLE MISSOURI RIVER AT CAMP CROOK, S. DAK.

his station was established September 2, 1903. It is located near the old highway lge on the road from Camp Crook to Belle Fourche, about one-half mile from Camp ok, in T. 18 N., R. 1 E.

he channel is straight for 300 feet above and 400 feet below the station. Both banks sparsely wooded, and the left bank overflows at high water. The bed is sandy and some- it shifting. There is but one channel at all stages. The current is sluggish at low water. river is frozen from about December 20 to March 10, and observations are discontinued ing that time. Gage heights range from zero to 10 feet.

ligh-water measurements are made from a car and cable 200 feet above the old bridge. cable is marked at 10-foot intervals with white paint. The initial point for soundings he left cable support. Low-water measurements are made by wading near the cable. gage was read once each day during 1905 by Paul A. Chuning. The original gage was troyed by floods in the spring of 1904. The present temporary gage, established April 20, 5, consists of three parts—a staff driven in the center of the channel, a staff driven on left bank, and a timber spiked to the left abutment of the old bridge. This gage will be laced by a permanent gage on the steel bridge now being erected. The gage is referred bench marks as follows: (1) A spike driven in a blaze 6 inches above ground on a tree r the road, 100 feet from the right end of the bridge; elevation, 10.53 feet above the zero he gage. (2) A spike driven in a blaze 6 inches above ground on a tree across the road n bench mark No. 1 and 175 feet farther downstream; elevation above the zero of the , 12.89 feet.

nformation in regard to this station is contained in the following Water-Supply Papers ie United States Geological Survey:

scription: 99, p 73; 130, pp 143–144.
charge: 99, p 74; 130, p 144.
charge, monthly: 130, p 146.
ge heights: 99, p 74; 130, p 145.
ing table: 130. p 145.

Discharge measurements of Little Missouri River at Camp Crook, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 20	H. D. Comstock	64	24	1.00	0.45	24
June 4	do	28	17	.61	.34	10.3
June 6	do	21	5.5	1.42	.31	7.8
July 25	do	114	197	2.12	2.15	418
July 26	do	110	166	1.77	1.90	294
August 23	Stevens and Comstock	68	48	1.10	.69	53

NOTE.—Measurements made at different sections.

Daily gage height, in feet, of Little Missouri River at Camp Crook, S. Dak., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1		0.3	0.4	1.1	4.0	5.0	0.4	0.9
2		.3	.4	3.2	3.5	5.6	3.7	.8
3		.3	.4	5.85	2.7	3.0	2.9	.7
4		1.1	.4	6.7	1.9	2.25	2.7	.7
5		3.0	.4	6.0	1.7	2.0	2.6	.6
6		4.0	.4	5.1	1.7	1.8	2.4	.6
7		4.0	.3	2.2	1.6	1.7	1.7	.6
8		2.6	.3	1.9	1.4	1.7	1.2	.5
9		1.6	.4	1.8	1.2	1.7	.7	.5
10		1.3	.4	2.0	1.0	.7	.5	.5
11		1.3	.4	2.0	.9	.6	.5	.5
12		.9	.5	2.0	.8	.5	.5	.5
13		.8	.9	1.8	.7	.5	.5	.4
14		.8	.85	1.8	.7	.5	.5	.4
15		.6	.8	1.4	2.0	.5	.5	.4
16		.55	4.9	2.0	2.1	.5	.5	.4
17		.5	5.6	6.8	1.7	.5	.5	.4
18		.5	7.0	5.1	1.0	.5	.5	.4
19		.5	7.6	3.0	.9	.4	.7	.4
20	0.45	.5	5.6	2.4	.7	.4	.7	.4
21	.5	.5	4.5	1.5	.7	.3	.9	.4
22	.5	.5	3.3	1.6	.7	.3	1.0	.5
23	.4	.4	2.5	2.6	.6	.3	1.5	.5
24	.4	.4	1.6	2.6	.6	.3	1.6	.5
25	.4	.3	1.4	2.1	.6	.3	1.9	.5
26	.35	.3	1.8	1.7	.6	.3	2.5	.5
27	.3	.4	1.7	.8	.6	.3	1.9	.4
28	.3	.4	1.7	1.8	.6	.3	1.8	.4
29	.3	.4	1.6	4.2	.5	.3	1.5	.4
30	.3	.4	1.5	6.0	.5	.4	1.4	.4
31		.4		6.15	.5		1.0	

m rating table for Little Missouri River at Camp Crook, S. Dak., from April to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.20	3	1.00	93	1.70	270	2.40	523
.30	7	1.10	111	1.80	302	2.50	565
.40	16	1.20	132	1.90	335	2.60	608
.50	26	1.30	156	2.00	370	2.70	652
.60	37	1.40	182	2.10	406	2.80	697
.70	49	1.50	210	2.20	444	2.90	743
.80	62	1.60	239	2.30	483	3.00	790
.90	77						

he above table is applicable only for open-channel conditions. It is based on sixteen discharge measments made during 1903–1905, and is well defined between gage heights 0.3 foot and 2.6 feet. The disrge above 3 feet is only approximate.

Estimated monthly discharge of Little Missouri River at Camp Crook, S. Dak., for 1905.

[Drainage area, 1,900 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
pril 20-30	26	7	14.6	319	0.0077	0.0032
lay	1,320	7	170	10,450	.089	.103
une	3,480	7	608	36,180	.320	.357
uly	3,000	62	961	59,090	.506	.583
ugust	1,320	26	208	12,790	.109	.126
eptember	2,280	7	244	14,520	.128	.143
ctober	1,147	16	229	14,080	.121	.140
lovember	77	16	27.2	1,618	.014	.016
The period				149,000		

LITTLE MISSOURI RIVER AT MEDORA, N. DAK.

This station was established May 12, 1903. It is located at the Northern Pacific Railway ridge, one-third mile west of the railroad station at Medora, N. Dak.

The channel is straight for 100 feet above the station and 300 feet below. The right bank s clean, low, and overflows at very high stages; the left bank is almost perpendicular and as a height of 30 feet above gage datum. The bed of the stream is of clay and sand, and ometimes scours from 5 to 8 feet during floods; at ordinary stages the bed changes only ightly. There is but one channel, broken by three piers, according to the stage of the iver. In the latter part of 1903 the cross section at the bridge was temporarily changed uring repairs to the bridge by the railroad company, continuing several months.

Discharge measurements are made from the railroad bridge to which the gage is attached. he initial point for soundings is the left end of the guard rail on the lower side of the bridge, 9 feet west of the east face of the concrete abutment.

The gage was read during 1905 by W. A. Brubaker and P. E. Anderson. A standard ain gage is located on the lower side of the railroad bridge at a point 91 feet from the tial point for soundings. There is also a vertical board gage reading from 1 foot to 9 t, fastened to a pile in the river about 200 feet above the bridge. August 7, 1905, on ount of the bridge having been changed by the railroad, a chain length of 30.92 feet was

established, which made the readings agree with the timber gage. The bench mark is the top of the southwest corner of the concrete abutment on the left bank; elevation above gage datum, 30.11 feet. The top of the gage pulley is 31.6 feet above the gage datum, which is about 2,230 feet above sea level, as determined by hand level from the railroad station at Medora, N. Dak.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 70–71; 130, pp 146–147.
Discharge: 99, p 71; 130, p 147.
Discharge, monthly: 99, p 73; 130, p 149.
Gage heights: 99, pp 71–72; 130, pp 147–148.
Rating table: 99, p 72; 130, p 148.

Discharge measurements of Little Missouri River at Medora, N. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 26	E. F. Chandler	59	130	.95	3.60	123
July 7	Chandler and Richards	183	1,026	4.19	8.45	4,302
July 8	do	180	959	4.73	8.08	4,539
Do	E. F. Chandler	180	966	4.27	8.13	4,124
Do	R. Richards	181	975	4.30	8.18	4,195
August 6	do	143	456	2.75	5.96	1,256
August 7	do	135	398	2.61	5.61	1,038
August 24	do	88	173	1.55	4.01	269
October 16	do	74	186	.87	3.72	161

Daily gage height, in feet, of Little Missouri River at Medora, N. Dak., for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	.....	7.2	3.3	2.6	3.2	9.8	5.8	3.5	4.0	3.6
2	.....	7.0	3.2	2.6	3.2	10.2	5.6	3.5	4.0	5.1
3	.....	6.5	3.2	2.6	3.1	9.8	6.8	3.4	4.0	5.0
4	.....	6.5	3.2	2.6	8.7	7.6	7.2	3.4	4.0	4.8
5	.....	6.3	3.2	2.6	9.4	8.8	7.3	3.4	4.0	5.0
6	.....	5.4	3.2	2.6	8.5	9.2	6.4	6.0	5.0	4.9
7	.....	4.2	3.2	2.6	9.3	8.6	5.1	5.6	5.0	4.7
8	.....	4.1	3.2	2.6	8.2	8.2	6.0	5.0	5.0	4.4
9	.....	4.0	3.1	2.8	7.3	7.9	6.1	4.7	4.9	4.2
10	.....	4.0	3.1	2.9	6.1	7.4	5.9	4.5	4.8	4.0
11	.....	4.0	3.0	3.5	6.0	7.2	5.5	4.3	4.6	3.8
12	.....	4.0	3.0	3.5	5.8	7.2	5.1	4.1	4.4	3.6
13	.....	4.0	3.0	3.8	5.2	6.7	4.9	4.0	4.2	3.6
14	.....	4.0	3.0	3.8	6.3	6.0	4.3	4.0	4.0	3.5
15	.....	3.9	3.0	3.7	5.8	5.3	4.0	4.0	4.0	3.5
16	.....	3.9	2.9	3.6	6.4	5.0	8.8	3.8	4.0	3.5
17	.....	3.9	2.9	3.6	5.4	4.7	4.0	3.6	3.9	3.5
18	.....	3.9	2.9	3.6	5.1	4.5	4.2	3.4	3.8	3.5
19	.....	3.8	2.9	3.6	4.6	5.2	4.0	3.4	3.8	3.4
20	.....	3.8	2.8	3.6	6.6	8.8	3.8	3.2	3.7	3.4
21	.....	3.8	2.8	3.6	7.8	8.5	3.7	3.0	3.6	3.4
22	.....	3.7	2.8	3.5	7.9	8.3	3.7	3.0	3.6	3.4
23	.....	3.6	2.7	3.5	9.2	8.8	3.7	2.8	3.6	3.4
24	.....	3.6	2.7	3.5	8.2	9.0	3.7	2.8	3.5	3.4
25	3.0	3.6	2.6	3.4	8.6	7.9	3.7	2.6	3.4	3.4
26	3.3	3.5	2.6	3.3	7.0	7.3	3.7	2.6	3.6	3.4
27	4.5	3.5	2.6	3.3	6.8	7.2	3.6	2.5	3.4	3.4
28	4.9	3.5	2.6	3.3	6.6	7.0	3.6	2.4	3.4	3.4
29	.....	3.4	2.6	3.2	6.5	7.7	3.6	4.5	3.4	.....
30	.....	3.4	2.6	3.2	6.3	6.1	3.5	4.0	3.3	.....
31	.....	3.3	.....	3.2	.....	6.1	3.5	.....	3.3	.....

NOTE.—River frozen January 1 to February 28, during part of the time frozen to bottom in places, the discharge being very small. Also frozen November 28 to December 31.

Station rating table for Little Missouri River at Medora, N. Dak., from February 28 to November 28, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.40	1.9	3.90	223	5.30	870	7.40	2,405
2.50	2.2	4.00	260	5.40	925	7.60	2,600
2.60	2.7	4.10	298	5.50	980	7.80	2,805
2.70	3.3	4.20	338	5.60	1,035	8.00	3,015
2.80	4.1	4.30	380	5.70	1,095	8.20	3,230
2.90	5.2	4.40	424	5.80	1,155	8.40	3,450
3.00	6.8	4.50	470	5.90	1,215	8.60	3,675
3.10	9.8	4.60	520	6.00	1,280	8.80	3,905
3.20	15	4.70	570	6.20	1,410	9.00	4,140
3.30	29	4.80	620	6.40	1,555	9.20	4,380
3.40	54	4.90	670	6.60	1,710	9.40	4,620
3.50	85	5.00	720	6.80	1,870	9.60	4,860
3.60	118	5.10	770	7.00	2,040	9.80	5,100
3.70	152	5.20	820	7.20	2,220	10.00	5,340
3.80	187						

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5, and is well defined between gage heights 3.2 feet and 6 feet. It has been extended beyond these limits, being based on three high-water measurements near 8 feet gage height. Above 6 feet the table can be considered as only approximate.

Estimated monthly discharge of Little Missouri River at Medora, N. Dak., for 1905.[a]

[Drainage area, 5,785[a] square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inches
March	2,220	29	467	28,720	0.081	0.09
April	29	2.7	8.1	483	.0014	.00
May	187	2.7	60.5	3,720	.010	.01
June	4,620	9.8	2,016	120,000	.349	.38
July	5,580	470	2,696	165,800	.467	.53
August	3,905	85	781	48,020	.135	.15
September	1,280	1.9	235	13,980	.041	.04
October	720	29	271	16,660	.047	.05
November 1-28	770	54	236	13,110	.041	.04
The period				410,500		

[a] Revised since 1904 report.

KNIFE RIVER DRAINAGE BASIN.

KNIFE RIVER AT BRONCHO, N. DAK.

Knife River rises in the northeastern part of Billings County, N. Dak., flows southeastward, then northeastward, and unites with the Missouri near Stanton, Mercer County, N. Dak.

The gaging station was established May 29, 1903. Its first location was at a point about 600 feet east of H. M. Haven's ranch house, where the Broncho post-office was situated at that time, and about 23 miles north of Hebron, N. Dak., on the Northern Pacific Railway. Owing to the abandonment of the Haven ranch and the removal of the post-office to the

F. M. Smith, in the SE. ¼ sec. 4, T. 142, R. 90 W., about 3 miles up the valley, the was abandoned and a new station was established at the ranch of Mr. Smith. As ns enter the river between the two points the run-off will be practically identical. ıannel is straight for 150 feet above the station and 400 feet below. Both banks and grassy and not subject to overflow. The bed of the stream is composed of firm silt and may scour a little, but does not shift. The current at the cable is sluggish t high stages.

ırge measurements are made by means of a cable and car. The initial point for gs is at the cable support on the right bank. Distances from the initial point are ıed by a tagged line of heavy telegraph wires. Low-water measurements are made ıg a few rods below the gage.

ıge, which was read during 1905 by Sara J. Smith, is of the standard chain type, l on a projecting timber extending horizontally out over the water and substan- aced and guyed. The length of the chain is 32.65 feet. The distance from the the gage pulley to the zero of the scale is 11.7 feet, and the diameter of the pulley ıot. The elevation of the center of the pulley, referred to the gage datum, is 20.86 le that of the horizontal gage scale timber at the shore end is 21.03 feet. Supple- to the chain gage are two rod gages driven into the left bank about 75 feet down- rom the chain gage, consisting of timbers braced to posts in the bank. The lower eads from 2.6 to 9 feet; the upper reads from 9 to 13.9 feet. The chain gage is to bench marks as follows: (1) A cross on the top of a gray granite bowlder 1 foot ter, set flush with the ground in the line of the gage timber prolonged 5 feet behind r end of same; elevation above the zero of the gage, 21.15 feet. (2) A horizontal ve nails driven into a joint of the stone foundation of the observer's house, 3 inches southeast corner; elevation above the gage datum, 31.25 feet.

ıation in regard to this station is contained in the following Water-Supply Papers nited States Geological Survey:

tion: 99, p 68; 130, pp 149–150.
ge: 99, p 69; 130, p 150.
ge, monthly: 99, p 70.
ghts: 99, p 69; 130, p 150.
table: 99, p 70.

Discharge measurements of Knife River at Broncho, N. Dak., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	E. F. Chandler	10	8.6	2.12	3.89	18
.....	Chandler and Richards	10	8.4	1.16	3.60	9.8
.....	.....do	52	261	2.42	7.51	632
.....	.....do	47	233	2.09	6.92	486
.....	R. Richards	32	40	1.09	4.05	44
5	.....do	11	2.9	.70	3.35	2
7	.....do	9	6.3	.50	3.37	3.1

-Measurements made at different sections.

Daily gage height, in feet, of Knife River at Broncho, N. Dak., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1		3.7	3.4	3.5	3.6	3.35	3.2	3.45	3.3
2		3.7	3.4	3.45	3.6	3.4	3.2	3.3	3.3
3		3.65	3.4	3.4	3.6	5.8	3.2	3.35	3.4
4		3.65	3.42	3.8	3.6	4.2	3.2	3.4	3.4
5		3.6	3.6	6.1	7.2	3.95	3.15	3.3	3.4
6		3.6	3.6	4.4	6.5	3.65	3.1	3.4	3.4
7		3.6	3.6	7.4	4.8	3.6	3.1	3.3	3.4
8		3.6	3.6	6.5	4.4	3.6	3.1	3.3	3.4
9		3.55	3.6	6.0	4.2	3.5	3.2	3.3	3.45
10		3.55	3.8	4.65	4.1	3.45	3.2	3.3	3.45
11		3.55	3.7	4.3	3.9	3.45	3.2	3.3	3.4
12		3.52	3.9	4.15	3.95	3.45	3.2	3.3	3.4
13		3.5	3.8	4.1	3.9	3.4	3.2	3.3	3.4
14		3.5	3.8	3.9	3.85	3.5	3.3	3.3	3.4
15		3.5	3.8	3.9	3.7	3.5	3.25	3.3	3.5
16		3.5	3.7	3.9	3.9	3.5	3.25	3.35	3.4
17		3.5	3.7	3.9	5.0	3.5	3.2	3.35	3.4
18		3.5	3.65	4.1	4.4	3.45	3.2	3.35	3.4
19		3.5	3.6	4.1	4.0	3.45	3.3	3.35	3.4
20		3.45	3.6	4.0	3.9	3.4	3.4	3.3	3.4
21		3.45	3.55	4.05	3.8	3.4	3.3	3.3	3.4
22		3.4	3.5	4.15	3.8	3.3	3.2	3.3	3.4
23	3.9	3.4	3.5	4.0	3.6	3.3	3.4	3.3	3.4
24	3.8	3.4	3.55	3.9	3.6	3.3	3.2	3.3	3.4
25	3.9	3.4	3.5	3.8	3.53	3.3	3.3	3.3	3.4
26	3.8	3.4	3.45	3.7	3.5	3.25	3.25	3.3	3.4
27	3.8	3.4	3.45	3.7	3.5	3.25	3.25	3.3	.....
28	3.75	3.4	3.4	3.7	3.5	3.25	3.25	3.3	.....
29	3.7	3.4	3.5	3.6	3.45	3.25	3.25	3.3	.....
30	3.7	3.4	3.55	3.6	3.45	3.2	3.4	3.3	.....
31	3.7	.....	3.65	.....	3.4	3.2	.....	3.3	.....

NOTE.—River frozen over November 27.

HEART RIVER DRAINAGE BASIN.

HEART RIVER NEAR RICHARDTON, N. DAK.

Heart River rises in eastern Billings County, N. Dak., flows eastward and southeastward for about 100 miles by general course, then turns abruptly to the north and northeast and enters the Missouri near Bismarck, N. Dak.

The gaging station was established May 18, 1903. It is located at the iron highway bridge 10 miles south of the Northern Pacific Railway station at Richardton, N. Dak.

The channel is straight for 150 feet above and below the station. Both banks are high and covered with brush. The bed of the stream is sandy and shifting. The velocity of the current is moderate.

Discharge measurements are made from the bridge to which the gage is attached. The initial point for soundings is the end of the guard rail on the lower side of the bridge, at the left bank.

A standard chain gage, which was read once each day during 1905 by W. F. Church, is located on the lower side of the bridge. The length of the chain is 24.34 feet. The gage is referred to bench marks as follows: (1) The top of the foot-guard rail at a distance of 45 feet from the initial point for soundings; elevation above gage datum, 25.58 feet. (2) On top of the iron flanges around the top of the downstream eastern edge of the concrete iron pier on the lower side of the bridge, on the left bank; elevation above gage datum, 24.79 feet.

the gage pulley has the same elevation as bench mark No. 1. Gage datum is bove sea level, as determined by carrying an aneroid barometer six times between and the railroad station at Richardton.

tion in regard to this station is contained in the following Water-Supply Papers ted States Geological Survey:

on: 99, p 66; 130, p 151.
: 99, p 66; 130, p 151.
, monthly: 99, p 68; 130, p 153.
hts: 99, p 67; 130, p 152.
ble: 99, p 67; 130, p 152.

Discharge measurements of Heart River near Richardton, N. Dak., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
E. F. Chandler	36	24	0.70	4.64	17
do	66	203	1.60	6.88	325
R. Richards	15.5	6.6	.75	4.24	5.0
do	4.6	1.3	.64	4.00	.9
do	7.0	4.5	.64	4.14	2.9

Measurements made at different sections.

Daily gage height, in feet, of Heart River near Richardton, N. Dak., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
	6.6	4.5	4.1	4.2	4.4	4.3	3.8	4.1	4.2
	7.25	4.5	4.1	4.2	4.4	4.3	3.8	4.1	4.2
	6.8	4.5	4.1	4.2	4.4	4.3	3.8	4.1	4.2
	6.1	4.4	4.2	4.2	4.4	4.3	3.8	3.9	4.2
	6.1	4.4	4.3	6.7	9.1	4.3	3.8	3.9	4.2
	6.1	4.4	4.3	5.4	9.1	4.3	3.8	3.9	4.2
	5.6	4.3	4.3	5.1	7.4	4.3	3.8	3.9	4.3
	5.5	4.3	4.3	5.5	6.2	4.2	3.8	3.9	4.3
	5.5	4.3	4.3	5.7	5.6	4.2	3.8	4.2	4.3
	5.5	4.3	4.4	5.1	5.3	4.2	3.8	4.3	4.3
	5.5	4.3	4.4	4.9	5.1	4.2	3.8	4 3	4.3
	5.4	4.3	4.4	4.9	5.0	4.2	3.8	4.2	4.3
	5.1	4.3	4.3	4.7	4.9	4.2	3.8	4.2	4.3
	5.0	4.3	4.3	4.6	4.8	4.2	3.8	4.1	4.3
	4.9	4.3	4.3	4.6	5.55	4.2	3.8	4.1	4.3
	4.9	4.3	4.3	4.5	7.05	4.2	3.8	4.1	4.3
	4.8	4.2	4.3	4.5	6.6	4.1	3.8	4.0	4.3
	4.8	4.2	4.3	4.6	6.0	4.1	3.8	4.0	4.3
	4.8	4.2	4.3	4.7	5.7	4.1	3.8	4.0	4.3
	4.8	4.2	4.3	4.7	5.0	4.1	4.5	4.0	4.4
	4.7	4.2	4.3	4.6	5.1	4.1	4.5	4.0	4.4
	4.7	4.2	4.3	4.6	4.6	4.0	4.4	4.0	4.4
	4.7	4.2	4.3	4.7	4.6	4.0	4.3	4.0	4.4
	4.6	4.2	4.3	4.8	4.6	4.0	4.3	4.0	.....
	4.6	4.2	4.3	4.7	4.5	4.0	4.3	4.1	.....
	4.6	4.2	4.3	4.7	4.5	4.0	4.2	4.1	.....
	4.6	4.2	4.3	4.6	4.5	4.0	4.2	4.1	.....
	4.6	4.1	4.2	4.5	4.4	4.0	4.1	4.1	.....
	4.5	4.1	4.2	4.5	4.4	3.9	4.1	4.2	.....
	4.5	4.1	4.2	4.4	4.4	3.9	4.1	4.2	.....
	4.5	.....	4.2	.....	4.4	3.9	.....	4.2	.....

River frozen January 1 to February 26 and November 24 to December 31.

Station rating table for Heart River near Richardton, N. Dak., from March 1 to November 23, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
3.90	0.5	5.00	42	6.10	187	7.40	430
4.00	1	5.10	51	6.20	204	7.60	471
4.10	2	5.20	61	6.30	221	7.80	513
4.20	4	5.30	72	6.40	238	8.00	556
4.30	6	5.40	84	6.50	256	8.20	600
4.40	9	5.50	97	2.60	274	8.40	645
4.50	12	5.60	110	6.70	292	8.60	692
4.60	16	5.70	124	6.80	310	8.80	740
4.70	21	5.80	139	6.90	330	9.00	788
4.80	27	5.90	155	7.00	350		
4.90	34	6.00	171	7.20	390		

The above table is applicable only for open-channel conditions. It is based on five discharge m urements made during 1905 and one high-water measurement during 1904. It is well defined bet gage heights 4 feet and 5 feet, and has been extended beyond these limits, being based on one mea ment at 6.9 feet and one at 11 feet. Above 7 feet the estimate can be considered only approximat

Estimated monthly discharge of Heart River near Richardton, N. Dak., for 1905.

[Drainage area, 1,250 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	De in
March	400	12	83.1	5,110	0.066	
April	12	2	5.8	345	.0046	
May	9	2	5.6	344	.0045	
June	292	4	36.3	2,160	.029	
July	812	9	125	7,686	.100	
August	6	.5	3.1	191	.0025	
September	12	.0	2.2	131	.0017	
October	6	.5	2.2	135	.0017	
November 1-23	9	4	6.0	274	.0048	
The period				16,380		

APPLE CREEK DRAINAGE BASIN.

APPLE CREEK NEAR BISMARCK, N. DAK.

A temporary station was established on Apple Creek 6 miles east of Bismarck, N. Dak., at the bridge on the township line between sec. 3, T. 138, and sec. 34, T. 139. The gage was read by William S. Hedges.

Discharge measurements of Apple Creek near Bismarck, N. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 2	Walter Skelton	16	10.8	0.99	3.20	10.7
March 6	do	27	95	2.12	6.10	200
March 8	do	21	84	2.10	5.50	159
March 24	do	9.5	15.3	1.02	1.05	15.8
April 5	do	8.5	13.6	1.12	.90	15.2
April 19	do	6	7.0	.94	.35	6.6
May 29	do	6	7.3	.80	.50	5.8
June 6	do	18	52	1.19	2.90	62
June 7	do	18	38	1.06	2.30	40
June 9	do	35	159	1.53	6.65	243
June 10	do	24	90	1.44	4.60	130

Daily gage height, in feet, of Apple Creek near Bismarck, N. Dak., for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	Day.	Feb.	Mar.	Apr.	May.	June.
1	.....	3.4	0.95	0.3	0.5	17	.....	2.6	.3	1.0	1.5
2	.....	3.4	.8	.3	.5	18	.....	2.4	.3	1.0	1.4
3	.....	3.45	.8	.3	.5	19	.....	2.3	.35	.9	1.4
4	.....	3.75	.95	.3	.5	20	.....	2.2	.3	.7	1.3
5	.....	4.4	.9	.4	2.45	21	.....	2.15	.3	.6	1.3
6	.....	6.05	.9	.3	2.95	22	.....	.....	.3	.6	1.3
7	.....	6.45	.8	.3	2.35	23	.....	.....	.3	.6	1.3
8	.....	5.7	.7	.3	3.45	24	.....	1.05	.3	.6	1.3
9	.....	5.4	.7	.4	6.59	25	.....	1.1	.3	.6	1.3
10	.....	5.2	.6	.5	4.6	26	.....	1.1	.3	.5	1.4
11	.....	4.0	.5	.6	4.8	27	3.4	1.1	.3	.5	1.4
12	.....	3.75	.5	.7	4.0	28	3.4	1.1	.2	.5	2.1
13	.....	3.2	.5	.7	2.0	29	.....	1.05	.2	.5	.....
14	.....	3.0	.5	.8	1.5	30	.....	1.0	.2	.5	.....
15	.....	2.8	.5	.9	1.5	31	.....	1.0	.....	.5	.....
16	.....	2.6	.4	1.0	1.5						

NOTE.—Flow commenced February 27.

Estimated monthly discharge of Apple Creek near Bismarck, N. Dak., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March	307	10	54.7	3,363
April	15	5	8.8	524
May	16	5	9.0	553
June 1-21	244	6	50.0	2,082

NOTE.—These estimates are only approximate.

CANNON BALL RIVER DRAINAGE BASIN.

CANNON BALL RIVER AT STEVENSON, N. DAK.

Cannon Ball River is formed by two chief branches—North and South forks. North Fork rises in White Butte, in southern Billings County, N. Dak., flows northeastward for about 20 miles and then turns abruptly to the southeast; South Fork rises in Whetstone Butte, in the western part of Hettinger County, runs southeastward for approximately 40 miles and then turns northeastward; the two streams unite about 5 miles south of Three Buttes, in south-central Morton County, whence the main stream flows to the north and east, entering the Missouri about 25 miles southeast of Bismarck, N. Dak.

The gaging station was established June 10, 1903. It is located one-half mile west-northwest of the post-office at Stevenson, in sec. 20, T. 133 N., R. 82 W., and about 40 miles south of Mandan, N. Dak.

The channel is straight for 100 feet above the station and 400 feet below. The right bank is low, slopes gradually up from the water's edge, and is covered with timber and brush; the left bank is steep and about 25 feet high. The bed of the stream consists of clay, soft mud, and loose stones, and probably shifts somewhat. The depth varies from 2 to 5 feet at low stages. The current velocity is ordinarily sluggish.

Discharge measurements are made from a car and cable about 200 feet above the gage. A tagged wire is stretched above the cable. The initial point for soundings is a point 2 feet back from the cable support on the left bank.

The gage, which was read during 1905 by Donald Stevenson, is of the chain type and was put in June 30, 1905, to replace the old gage, which was in bad condition. The new gage has a chain length of 21.76 feet. The gage is supported by four solidly set posts on top of which is a horizontal timber, and is well braced and guyed. The pulley diameter is 0.31 foot and the distance from its center to the zero of the scale is 5.57 feet. The elevation of the highest point (marked with a cross), which is near the east corner of the flat top of a large granite rock, 4 by 9 feet, rising out of a pool to the right of its middle a few feet below the gage, is 4.84 feet above gage datum. The datum of the gage is about 1,700 feet above sea level, as determined by carrying an aneroid barometer six times between this station and Mandan, N. Dak.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 64; 130, pp 153-154.
Discharge: 99, p 65; 130, p 154.
Gage heights, 99, p 65; 130; p 154-155.

Discharge measurements of Cannon Ball River at Stevenson, N. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 28	E. F. Chandler	114	168	0.59	3.56	99
June 29[a]	do	40	56	2.19	3.45	123
June 30[a]		68	132	.87	3.49	114
August 3[a]	R. Richards	68	120	.85	3.52	102
August 28[a]	do	38	32	.62	2.88	20
August 29[a]	do	34	21	.92	2.85	19
October 17[a]	E. F. Chandler	14	9.6	.50	2.61	4.8

[a] Made by wading.

ily gage height, in feet, of Cannon Ball River at Stevenson, N. Dak., for 1905.

	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	.....	7.4	3.7	2.8	2.5	3.5	3.0	2.9	2.0	3.0
.....	.....	7.2	3.5	2.9	2.7	3.5	3.3	2.9	1.8	3.0
.....	.....	7.0	3.5	3.2	2.8	3.5	3.5	2.7	1.8	3.1
.....	.....	6.9	3.4	4.1	2.8	4.1	3.2	2.7	1.9	3.2
.....	.....	6.2	3.3	5.2	6.2	4.3	3.8	2.6	1.9	3.2
.....	.....	6.2	3.3	5.7	6.2	4.5	3.3	2.5	1.9	3.2
.....	.....	6.0	3.3	5.7	6.1	4.8	3.0	2.5	1.9	3.1
.....	.....	3.9	3.2	5.6	7.1	5.2	2.8	2.4	1.5	3.1
.....	.....	4.0	3.2	5.1	6.5	4.7	2.6	2.3	1.5	2.9
.....	.....	4.1	3.2	4.8	3.6	4.5	2.6	2.6	1.5	2.7
.....	.....	4.2	3.1	4.8	3.5	4.3	2.4	2.6	1.3	2.7
.....	.....	4.2	3.1	4.3	3.5	5.2	2.6	2.5	1.0	2.7
.....	.....	4.2	3.2	3.8	3.2	5.0	2.6	2.3	.8	2.7
.....	.....	4.1	3.2	3.6	2.9	4.5	2.7	2.3	.8	2.8
.....	.....	4.1	3.3	3.3	2.9	4.4	2.7	2.5	.8	2.8
.....	.....	3.9	3.1	3.3	2.8	4.6	2.8	2.6	2.4	2.8
.....	.....	3.9	3.1	3.2	2.6	5.3	2.9	2.8	2.6	2.9
.....	.....	3.7	3.0	3.2	2.6	5.0	2.9	2.8	2.6	2.9
.....	.....	3.7	3.0	3.0	2.4	4.7	3.9	2.7	2.6	2.9
.....	.....	3.7	3.0	3.0	2.4	4.7	3.9	2.7	2.7	2.9
.....	.....	3.8	2.9	3.0	2.9	3.5	3.8	2.5	2.7	2.8
.....	.....	4.0	2.8	3.1	2.9	3.3	3.8	2.5	2.8	2.9
.....	4.7	3.7	2.8	3.1	3.9	3.5	4.0	2.6	2.8	2.9
.....	5.7	3.5	2.8	2.9	3.8	3.4	4.0	2.4	2.9	3.0
.....	6.4	3.4	2.7	2.8	3.4	3.2	3.8	2.4	2.9	3.0
.....	8.4	3.5	2.7	2.6	3.3	3.2	2.9	2.3	2.8	.....
.....	8.9	3.4	2.7	2.6	3.3	3.0	3.0	2.2	2.8	.....
.....	8.0	3.6	2.6	2.6	2.6	3.0	3.2	2.2	2.7	.....
.....	.....	3.6	2.8	2.5	2.9	2.8	3.2	2.0	2.8	.....
.....	.....	3.7	2.8	2.5	3.5	2.8	3.1	2.0	2.8	.....
.....	.....	3.8	.....	2.5	.....	3.0	3.0	.....	2.9	.....

River frozen November 26.

GRAND RIVER DRAINAGE BASIN.

GRAND RIVER AT SEIM, S. DAK.

River is formed by North and South forks, which rise in the hills of northwestern akota and unite at Seim, whence the main stream flows eastward to its point of with the Missouri. The country drained is gently rolling and the soil is a sandy here is very little land under cultivation. The only timber is along the banks of and its few tributaries. The main floods occur in March, May, June, and July. ging station was established June 6, 1904. It is located just below the junction and South forks, about 800 feet east of the store at Seim. The channel is curved 200 feet above and 300 feet below the station. The right bank is low, somewhat vith scattered trees, and is subject to overflow; the left bank is high and clean and overflow. The bed is composed of sand and gravel and is free from vegetation anent. There is but one channel at high water, but during low stages there are annels above the gage and one channel below. The current is swift. The flow r a month or more in August and September. Gage heights range from 1.5 to 10

rge measurements are made by wading near the gage or, during high water, by The initial point for soundings is the 3-foot mark of the gage.

The gage, which was read during 1905 once each day by James McGee, is inclined and in two sections. It is fastened to a tree and to posts set in the left bank. The gage is referred to bench marks as follows: (1) A railroad spike in the tree to which the upper section of the gage is attached; elevation, 9.10 feet above the zero of the gage. (2) A railroad spike driven into a cottonwood tree 125 feet from the left bank, opposite the gage; elevation, 14.08 feet above the zero of the gage.

A description of this station, with gage height and discharge data, is contained in Water-Supply Paper No. 130 of the United States Geological Survey, pages 155-156.

Discharge measurements of Grand River at Seim, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage. height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 1	H. D. Comstock	18	5.4	1.07	1.64	5.8
May 1	do	18	6.0	1.05	1.64	6.3
July 16	do	56	57.0	2.21	2.45	126
August 21	Stevens and Comstock	50	38.0	1.53	2.09	58

Daily gage height, in feet, of Grand River at Seim, S. Dak., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Oct.	Nov.
1	.....	1.7	2.0	2.2	2.1	.....	1.7
2	2.0	1.7	2.0	2.2	2.0	.....	1.7
3	2.0	2.0	2.0	4.0	2.0	.....	1.6
4	2.0	3.0	2.0	3.6	2.1	1.8	1.6
5	2.0	3.0	2.0	3.5	2.1	1.8	1.6
6	2.0	2.8	2.6	3.0	2.0	1.7	1.6
7	2.0	1.6	2.6	2.7	1.9	1.6	1.7
8	2.0	1.6	2.5	2.5	1.9	1.6	1.7
9	2.0	1.6	9.4	2.5	1.8	1.6	1.6
10	1.9	1.6	3.2	2.4	1.8	1.6	1.6
11	1.9	1.6	3.2	2.4	1.8	1.6	1.6
12	1.8	1.6	3.2	2.2	1.8	1.6	1.6
13	1.8	1.6	3.6	2.2	1.8	1.6	(a)
14	1.8	1.5	3.6	2.2	1.8	1.6	.....
15	1.7	1.5	3.6	2.1	1.8	1.6	.....
16	1.7	1.5	3.6	2.4	1.8	1.7	1.7
17	1.7	1.5	3.6	2.5	4.5	1.7	1.6
18	1.7	1.5	4.0	2.6	3.2	1.7	1.7
19	1.7	1.5	4.9	2.6	2.6	1.6	1.6
20	1.7	1.5	4.6	2.8	2.3	1.6	1.6
21	1.7	1.6	4.5	2.9	2.3	1.7	1.6
22	1.7	1.7	3.0	2.7	2.0	1.7	1.7
23	1.7	1.7	2.8	2.5	1.8	1.7	1.6
24	1.7	2.0	2.5	2.3	1.6	1.7	.....
25	1.7	2.0	2.5	2.3	1.6	1.6	.....
26	1.7	1.8	2.5	2.3	1.6	1.6	.....
27	1.7	1.8	2.4	2.2	1.6	1.6	.....
28	1.7	1.8	2.4	2.1	1.6	1.6	.....
29	1.7	1.9	2.2	2.6	(a)	1.7	.....
30	1.7	1.9	2.2	2.4	.....	1.7	.....
31	.....	2.0	.....	2.1	.....	1.8	.....

a No flow; water standing in pools, August 29 to October 3, and November 13 to 15, inclusive.

on rating table for Grand River at Seim, S. Dak., from June 6, 1904, to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.50	1	2.10	60	2.70	190	3.30	388
1.60	4	2.20	76	2.80	219	3.40	424
1.70	10	2.30	94	2.90	250	3.50	461
1.80	20	2.40	115	3.00	283		
1.90	32	2.50	138	3.10	317		
2.00	45	2.60	163	3.20	352		

he above table is applicable only for open-channel conditions. It is based on six discharge measure-its made during 1904–5, and is well defined between gage heights 1.5 feet and 3.5 feet. The discharge ve 3.5 feet is only approximate.

Estimated monthly discharge of Grand River near Seim, S. Dak., for 1904.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
ne 6–30	669	60	168	8,331
y 1–20	60	0	40.2	1,595

OTE.—Dry after July 20.

Estimated monthly discharge of Grand River at Seim, S. Dak., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
ril 2–30	45	10	22.2	1,277
ay	283	1	37.7	2,318
ne	3,500	45	423	25,170
ly	669	60	167	10,270
gust 1–28	909	4	79.9	4,913
tober 4–31	20	4	7.9	439
vember (1–12) (16–23)	10	4	6.1	242
The period				44,630

NOTE.—No flow August 29 to October 3 and November 13 to 15, inclusive. Water standing in pools.

MOREAU RIVER DRAINAGE BASIN.

MOREAU RIVER AT BIXBY, S. DAK.

Moreau River rises near the western boundary of South Dakota and flows eastward into e Missouri. The country drained is high and rolling and the soil is a sandy loam. There very little land under cultivation. There is no timber except along the banks of the river nd its tributaries, of which the chief are North and South Forks, Rabbit Creek, and Thun-er Butte Creek. The principal floods occur in March, May, June, and July.

The gaging station was established June 4, 1904. It is located one-fourth mile southeast f Bixby, S. Dak., in T. 14 N., R. 13 E., about 1,000 feet below the ford.

The channel is straight for 1,000 feet above and below the gage. The left bank is high nd clean and does not overflow; the right bank is timbered and is liable to overflow t extremely high water. The bed of the stream is composed of sandstone, contains uch clay and fine sand, and is free from vegetation and permanent. There is but one annel at all stages. The current is swift at high water, but becomes sluggish at low water.

Gage heights range from 1 to 10 feet. The river is frozen from about December 1 to March 10, and observations are discontinued during that period.

High-water measurements are made by means of a car and cable 200 feet above the gage. The initial point for soundings is the right cable support. The cable is marked at 10-foot intervals with red paint. Low-water measurements are made by wading 100 feet below the gage.

A staff gage, which was read once each day during 1905 by J. A. Hudgins, is driven in an inclined position into the bed of the stream and is firmly spiked to two small trees on the right bank. In order that the gage heights may be read during floods, a second section is attached to a large cottonwood tree 50 feet from the bank. The gage is referred to bench marks as follows: (1) A railroad spike driven into the base of a cottonwood tree 75 feet from the gage on the right bank; elevation, 13.98 feet above the zero of the gage. (2) A railroad spike driven into the base of a cottonwood tree 100 feet from the gage and 75 feet downstream from the first bench mark; elevation, 13.95 feet above the zero of the gage.

A description of this station, with gage height and discharge data, is contained in Water-Supply Paper No. 130 of the United States Geological Survey, pages 156–159, 192.

Discharge measurements of Moreau River at Bixby, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 28[a]	H. D. Comstock	32	4.8	0.96	1.35	4.6
May 3[a]	do	85	76	1.67	2.10	127
May 5[a]	do	82	124	2.00	2.60	249
May 6	do	82	211	3.10	3.54	654
May 6	do	82	228	3.16	3.72	721
May 7	do	90	300	3.90	4.47	1,170
May 7	do	91	331	4.12	4.85	1,365
July 15[a]	do	86	140	2.17	2.91	304
July 17[a]	do	91	191	2.56	3.32	489
August 19	Stevens and Comstock	84	212	2.78	3.65	589

[a] Made 100 feet below cable.

Daily gage height, in feet, of Moreau River at Bixby, S. Dak., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	.....	1.5	1.3	1.5	1.7	1.7	4.6	1.5	1.7
.....	.....	1.5	1.4	1.6	2.1	1.6	3.5	1.5	1.7
.....	.....	1.5	2.1	2.0	6.1	1.55	2.4	1.5	1.6
.....	.....	1.5	2.5	1.8	5.3	1.5	2.0	1.5	1.6
.....	.....	1.4	2.65	1.6	4.1	1.5	1.8	1.5	1.6
.....	.....	1.4	3.7	1.5	2.8	1.5	1.7	1.45	1.6
.....	.....	1.4	4.6	1.5	2.35	1.5	1.6	1.45	1.6
.....	.....	1.4	3.4	1.5	2.0	1.5	1.6	1.5	1.6
.....	.....	1.3	3.0	1.5	1.9	1.5	1.6	1.5	1.6
.....	.....	1.35	2.8	1.45	1.8	1.4	1.6	1.5	1.6
.....	.....	1.4	2.5	1.45	1.7	1.4	1.6	1.5	1.6
.....	.....	1.4	2.15	1.4	1.6	1.4	1.6	1.5	1.6
.....	.....	1.4	1.9	1.4	6.9	1.6	1.6	1.5	1.6
.....	1.5	1.4	1.9	1.5	3.9	1.5	1.6	1.5	1.6
.....	1.5	1.4	1.85	1.9	2.5	1.5	1.6	1.5	1.6
.....	1.5	1.5	1.7	2.9	2.4	4.8	1.6	1.5	1.6
.....	1.5	1.5	1.6	3.0	3.3	7.0	1.5	1.5	1.6
.....	1.5	1.5	1.5	6.75	2.5	5.5	1.5	1.5	1.6
.....	1.5	1.7	1.5	6.4	3.3	3.7	1.5	1.7	1.6
.....	1.5	1.7	1.5	4.8	3.1	2.8	1.5	1.7	1.6
.....	1.5	1.5	1.5	3.4	2.15	2.0	1.5	1.7	1.6
.....	1.5	1.5	1.5	3.0	1.9	1.8	1.5	1.7	1.6
.....	1.5	1.5	1.4	2.15	1.8	1.6	1.5	1.7	1.6
.....	1.5	1.4	1.4	2.0	1.7	1.6	1.5	1.7	1.6
.....	1.5	1.4	1.4	1.9	1.7	1.6	1.5	1.7	1.6
.....	1.45	1.4	1.4	1.85	1.7	1.6	1.5	1.7	.....
.....	1.45	1.3	1.4	2.0	2.5	1.6	1.5	1.7	.....
.....	1.45	1.35	1.4	1.9	2.25	1.5	1.5	1.7	.....
.....	1.45	1.3	1.45	1.85	1.9	1.5	1.5	1.85	.....
.....	1.5	1.3	1.45	1.6	1.8	1.5	1.5	1.75	.....
.....	1.5	.....	1.4	.....	1.75	6.4	.....	1.7	.....

tion rating table for Moreau River at Bixby, S. Dak., from March 14 to November 25, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.30	0	2.30	158	3.30	490	4.20	958
1.40	5	2.40	184	3.40	534	4.30	1,020
1.50	12	2.50	211	3.50	580	4.40	1,084
1.60	23	2.60	240	3.60	628	4.50	1,151
1.70	37	2.70	271	3.70	678	4.60	1,220
1.80	53	2.80	303	3.80	730	4.70	1,292
1.90	71	2.90	337	3.90	784	4.80	1,366
2.00	91	3.00	372	4.00	840	4.90	1,442
2.10	112	3.10	409	4.10	898	5.00	1,520
2.20	134	3.20	448				

he above table is applicable only for open-channel conditions. It is based on 15 discharge measure-ts made during 1904-5, and is well defined between gage heights 1.3 feet and 5 feet. Above 5 feet the harge is approximate.

Estimated monthly discharge of Moreau River at Bixby, S. Dak., for 1905.

[Drainage area, 1,600 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean		Second-feet per square mile.	Dep inc
March 14-31	12	8	11.1	398	0.0069	0
April	37	0	8.6	512	.0054	
May	1,220	0	142	8,731	.089	
June	3,044	5	323	19,220	.202	
July	3,196	23	415	25,520	.259	
August	3,300	5	348	21,400	.218	
September	1,220	12	85.4	5,082	.053	
October	62	8	23.3	1,433	.015	
November 1-25	37	23	24.1	1,195	.015	
The period				83,400		

CHEYENNE RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Cheyenne River rises in the eastern part of Wyoming, flows eastward around the sout border of the Black Hills, turns to the northeast, and unites with the Missouri in the ce part of South Dakota. It drains a long narrow valley bordered by high table-lands occasional low flats containing a few thousand acres each. In the Black Hills region, w many of the tributaries rise, extensive forests occur, and there is also considerable tir along the main stream. The soil is partly a sandy loam and partly gumbo, and ther many cultivated tracts.

The principal tributaries are Beaver and Hat creeks, Fall River, Battle, Spring, R and Boxelder creeks, Belle Fourche River, and Sulphur Creek. The chief tributaries o Belle Fourche are Redwater River and Whitewood Creek, and the Redwater has one l tributary, Spearfish Creek.

The rainfall varies from 21 inches in the Black Hills region to 12 inches on the prairies. main floods occur in March, May, June, and July. Many of the streams rising in the B Hills are fed to a large extent by springs. Fall River, in particular, gets much of its w from hot springs and mineral springs.

There is considerable power development on the Black Hills tributaries, especiall Rapid and Whitewood creeks. Some water is diverted for irrigation from practically al tributaries, and work is now in progress on the Belle Fourche project by the United S Reclamation Service, which proposes to divert and store nearly all the flow of the Fourche at the town of Belle Fourche and to irrigate about 90,000 acres.

Information in regard to this basin is contained in the annual reports of the reclam service and in the Fourth Annual Report of the United States Geological Survey, Par pages 251–253.

CHEYENNE RIVER AT EDGEMONT, S. DAK.

ıtation was established June 19, 1903. It is located at the highway bridge just eam from the Chicago, Burlington and Quincy Railway bridge, in the SE. ¼ sec. 36, R. 2 E., just above the mouth of Cottonwood Creek.

hannel is straight above and below the station. The right bank is high and clean s not overflow; the left bank is low, has a few scattered trees, and is liable to over- The bed of the stream is sandy and shifting. There is usually but one channel. ocity is sluggish at low water. Gage heights range from 1 to 11 feet. The river is rom about December 1 to March 10.

arge measurements are made from the highway bridge. The initial point for sound- ı brass-headed tack surrounded by similar tacks in the first post of the lower hand he south end of the bridge.

ıg 1905 the gage was read once each day by Hubert Wiedenfeld. The standard age, installed May 17, 1905, is bolted to the lower chord of the downstream truss of ıt span of the bridge, 50 feet from the right end. The length of the chain is 13.45 The gage is referred to bench marks as follows: (1) A nail surrounded by a circle of ıcks driven into a knot on the south side of a cottonwood tree 250 feet north of the nd of the highway bridge; elevation, 11.29 feet above the zero of the gage. (2) The of the abutment at the north end of the railroad bridge, on the fourth step of the ınt and on the corner on the east side away from the bridge; elevation above the zero age, 20.23 feet.

mation in regard to this station is contained in the following Water-Supply Papers United States Geological Survey:

ption: 99, pp 55–56; 130, p 159.
arge: 49, p 272; 99, p 56; 130, p 160.
heights: 99, p 56; 130, p 160.

Discharge measurements of Cheyenne River at Edgemont, S. Dak., in 1905.

te.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
8	F. M. Madden	57	20.0	1.50	1.80	30
	H. D. Comstock	28	15.8	1.39	1.75	22
	do	15	4.7	1.32	2.28	6.2
	do	84	98	2.78	2.75	272
	do	72	77	2.23	2.50	172
	do	150	382	3.50	4.20	1,336
	do	148	247	2.43	3.30	599
	do	147	206	2.28	3.10	469
	do	300	1,652	5.60	9.75	9,259
	do	154	575	4.31	4.62	2,477
	do	154	474	3.53	4.00	1,674
4	do	162	578	3.34	4.23	1,930
5	do	162	274	2.46	2.95	674
6	do	270	1,285	5.62	8.00	7,222
6	do	250	1,157	5.09	7.55	5,893
6	do	220	968	4.96	6.80	4,803
7	do	175	730	4.77	5.60	3,485
8	do	162	359	2.82	3.64	1,014
ber 6	Stevens and Comstock	94	45	1.44	2.35	65

[a] Made at different sections.

Daily gage height, in feet, of Cheyenne River at Edgemont, S. Dak., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.7	3.8	4.0	1.8	1.7	2.5	2.7	6.3	2.5	2.3	2.2	2.1
2	2.9	3.8	3.8	2.8	2.8	2.5	9.35	5.3	2.7	3.0	2.1	2.1
3	3.0	3.8	3.6	2.0	3.8	2.5	5.8	5.0	2.8	2.6	2.1	.....
4	3.0	3.8	3.5	2.0	2.5	2.5	5.0	4.0	2.6	2.6	2.2	.....
5	3.0	4.0	3.0	1.8	2.0	2.5	4.0	2.95	2.4	2.4	2.1	.....
6	3.0	4.0	2.5	1.8	2.0	2.5	3.0	7.95	2.2	2.4	2.1	.....
7	3.0	4.0	2.4	1.8	2.5	2.5	2.3	4.0	2.2	2.0	2.1	.....
8	3.0	4.0	2.4	1.8	2.5	2.6	3.4	3.7	2.2	2.3	2.1	.....
9	3.0	4.0	2.4	1.8	2.5	2.6	2.8	3.0	2.1	2.3	2.1	.....
10	3.0	4.0	2.4	1.8	2.3	2.6	2.8	2.2	2.1	2.3	2.1	.....
11	3.0	4.0	2.4	1.8	2.3	5.0	2.8	5.0	2.1	2.2	2.1	.....
12	3.0	4.0	2.4	1.8	2.3	4.2	2.7	8.4	2.1	2.3	2.1	.....
13	3.0	4.3	2.3	1.8	2.3	4.2	2.5	5.8	2.1	2.3	2.1	.....
14	3.0	4.3	2.3	2.2	2.3	5.0	2.8	4.0	2.1	2.4	2.1	.....
15	3.0	4.3	2.0	2.0	2.3	5.5	2.7	3.3	2.2	2.4	2.1	.....
16	3.0	4.3	2.0	2.0	2.2	3.8	2.6	3.0	2.2	2.4	2.1	.....
17	3.0	4.3	2.0	2.0	2.2	5.45	2.5	2.4	2.2	2.4	2.1	.....
18	3.0	4.3	2.0	2.0	2.3	9.65	2.3	2.3	2.1	2.3	2.1	.....
19	3.0	4.3	2.0	2.0	2.3	4.4	2.1	2.3	2.1	2.3	2.1	.....
20	3.0	4.3	2.0	2.0	2.4	3.4	7.7	2.2	2.1	2.1	2.1	.....
21	3.0	4.3	2.0	2.0	2.4	2.6	5.9	2.0	2.0	2.1	2.1	.....
22	3.3	4.5	1.9	2.0	2.4	2.6	4.8	2.6	2.0	2.1	2.1	.....
23	3.3	4.5	1.9	2.0	4.5	2.4	3.3	2.0	2.0	2.1	2.1	.....
24	3.3	5.0	1.9	2.0	4.8	3.0	2.8	1.9	2.0	2.1	2.1	.....
25	3.3	4.7	1.9	1.9	2.8	3.0	2.6	2.0	2.0	2.1	2.1	.....
26	3.3	4.5	1.9	1.9	2.8	2.7	2.4	2.6	2.0	2.1	2.1	.....
27	3.3	4.3	1.8	1.8	2.4	2.6	4.1	2.4	2.0	2.1	2.1	.....
28	3.3	4.2	1.8	1.7	2.4	2.4	6.0	2.3	2.0	2.1	2.1	.....
29	3.5	.....	1.8	1.7	2.3	2.0	10.7	2.3	2.0	2.0	2.1	.....
30	3.5	.....	1.8	1.7	2.3	2.6	9.7	2.3	2.0	2.0	2.1	.....
31	3.5	.....	1.8	.....	2.6	.....	6.0	2.3	.....	2.0	.....	.....

NOTE.—Ice conditions January 1 to February 22, inclusive.

rily discharge, in second-feet, of Cheyenne River at Edgemont, S. Dak., 1903–1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1903.											
						375	1,685	318	10	4	57
						318	3,005	226	8	4	57
						23	1,795	130	8	4	57
						14	1,472	106	8	5	57
						10	1,092	75	8	5	57
						5	848	75	8	5	75
					85	4	630	75	4	5	75
					66	2	435	57	4	2	.....
					269	2	246	117	4	2	.....
					130	2	171	117	4	2	.....
					75	4,290	95	106	4	2	.....
					41	5,170	3,330	106	4	2	.....
					34	1,740	1,320	5,720	5	2	.....
					23	665	1,050	1,472	5	2	.....
					18	405	665	925	5	2	.....
					106	171	530	700	5	2	.....
					171	6,680	345	405	5	2	.....
					85	4,150	246	246	5	10	.....
					49	1,320	171	171	5	28	.....
					41	292	142	117	5	28	.....
					34	206	75	75	5	28	.....
					226	117	57	57	2	28	.....
					66	66	57	57	2	28	.....
					57	188	41	28	4	41	.....
					49	1,472	885	18	4	41	.....
					49	562	595	10	4	41	.....
					49	925	1,050	10	4	41	.....
					2,080	700	885	10	4	41	.....
					1,850	435	735	10	4	75	.....
					1,740	562	562	10	4	57	.....
						1,180	435	.....	4	.....	.....
1904.											
			57	665	2,940	117	18	735	4	1	.....
			57	562	2,080	3,730	18	246	4	1	.....
			57	345	6,760	3,135	18	95	4	1	.....
			57	772	4,010	925	18	292	4	1	.....
			57	435	2,440	345	18	117	4	1	.....
			57	206	1,180	2,565	18	57	4	1	.....
			57	171	848	1,850	18	34	4	1	.....
			41	130	665	1,525	18	34	4	1	.....
			41	106	3,395	1,320	18	14	4	1	.....
			41	85	1,472	1,135	10	8	4	1	.....
			28	66	885	885	10	8	8	1	.....
			28	49	562	735	10	8	14	1	.....
			28	34	292	1,225	10	4	34	4	.....
			18	34	142	665	10	1	156	8	.....
			18	41	95	405	5	1	188	4	.....
		142	18	41	772	246	5	1	130	4	.....
		117	18	41	595	171	5	1	106	1	.....
		95	18	41	292	117	4	1	66	1	.....
		57	18	41	142	75	4	0	34	1	.....
		57	18	41	95	57	4	0	8	1	.....
		57	18	4,290	75	57	4	0	8	14	.....
		57	10	3,330	965	41	1	0	8	14	.....

Daily discharge, in second-feet, of Cheyenne River at Edgemont, S. Dak., 1903–1905—Cont

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
1904.											
23		57	10	2,200	665	57	1	0	4	34	
24		57	8	1,050	405	41	1	0	4	66	
25		57	4	848	292	28	1	0	4	85	
26		57	4	700	142	28	1	0	4	85	
27		57	4	595	345	18	1	0	4		
28		57	4	530	246	18	0	23	4		
29		57	4	465	206	18	0	23	4		
30		57	4	405	171	18	595	8	1		
31		57		595		18	1,320		1		
1905.											
1		1,135	28	18	171	345	4,290	117	57	41	
2		965	292	292	171	8,665	2,940	171	246	28	
3		810	57	965	171	3,460	2,565	206	117	28	
4		735	57	171	171	2,440	1,420	142	117	41	
5		405	28	57	171	1,320	562	95	75	28	
6		171	28	57	171	530	6,842	41	75	28	
7		142	28	117	171	117	1,420	41	18	28	
8		142	28	117	206	665	1,050	41	57	28	
9		142	28	117	206	292	530	28	57	28	
10		142	28	75	206	292	142	28	57	28	
11		142	28	57	2,200	292	2,440	28	41	28	
12		142	28	57	1,320	246	7,420	28	57	28	
13		117	28	57	1,320	171	3,460	28	57	28	
14		117	95	57	2,200	292	1,320	28	75	28	
15		57	57	57	2,815	246	735	41	75	28	
16		57	57	41	965	206	465	41	75	28	
17		57	57	41	2,752	171	171	41	75	28	
18		57	57	57	9,175	117	142	28	57	28	
19		57	57	57	1,850	75	142	28	57	28	
20		57	57	75	885	6,280	117	28	28	28	
21		57	57	75	345	3,595	57	18	28	28	
22		41	57	75	345	2,200	206	18	28	28	
23	1,630	41	57	1,630	246	735	57	18	28	28	
24	2,200	41	57	1,965	595	405	41	18	28	28	
25	1,850	41	41	292	595	292	57	18	28	28	
26	1,630	41	41	292	345	206	171	18	28	28	
27	1,420	28	28	142	292	1,420	117	18	28	28	
28	1,320	28	18	142	206	3,730	95	18	28	28	
29		28	18	117	95	10,960	95	18	18	28	
30		28	18	117	292	9,260	95	18	18	28	
31		28		206		3,730	95		18		

NOTE.—The daily discharge has been obtained by the indirect method.

nated monthly discharge of Cheyenne River at Edgemont, S. Dak., 1903–1905.

[Drainage area, 7,350 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
1903.						
.....	2,080	18	308	14,660	0.042	0.037
.....	6,680	2	1,034	63,580	.141	.163
.....	3,330	41	795	48,880	.108	.124
.....	5,720	10	385	22,910	.524	.585
.....	10	2	5.0	307	.00068	.00078
.....	75	2	18.0	1,071	.0024	.0027
1–7.....	75	57	62.1	862	.0082	.0021
riod.....	.....	.....	.....	152,300	.....	.....
1904.						
1.....	142	57	68.4	2,171	.0093	.0055
.....	57	4	26.7	1,589	.0036	.0040
.....	4,290	34	610	37,510	.083	.096
.....	6,760	75	1,106	65,810	.150	.167
.....	3,730	18	696	42,800	.095	.110
.....	1,320	0	69.8	4,292	.0095	.011
.....	735	0	57.0	3,392	.0078	.0087
.....	188	1	26.9	1,654	.0037	.0043
1–26.....	85	1	12.8	6,601	.0017	.0017
eriod.....	.....	.....	.....	165,800	.....	.....
1905.						
3–28.....	2,200	1,320	1,675	19,930	.228	.051
.....	1,135	28	195	11,990	.027	.031
.....	292	18	50.5	3,005	.0069	.0077
.....	1,965	18	245	15,060	.033	.038
.....	9,175	95	1,022	60,810	.139	.155
.....	10,960	75	2,024	124,400	.275	.317
.....	7,420	41	1,266	77,840	.172	.198
.....	206	18	47.0	2,797	.0064	.0071
.....	246	18	56.5	3,474	.0077	.0089
.....	41	28	28.9	1,720	.0039	.0044
eriod.....	.....	.....	.....	321,000	.....	.....

lo estimate for ice period.

BEAVER CREEK NEAR EDGEMONT, S. DAK.

Creek rises in the northern part of Weston County, Wyo., flows southeastward, s Cheyenne River in the northwestern part of Fall River County, S. Dak.

ging station was established April 7, 1905. It is located at Anderson's ranch, miles northwest of Edgemont, S. Dak., and about 2 miles west of the Argentine k on the Chicago, Burlington and Quincy Railroad, just below the mouth of Pass the S. ½ sec. 16, T. 7 S., R. 1 E.

nnel is straight for 200 feet above and below the station. Both banks are low and to overflow during high water. The bed of the stream at the measuring section is nd cobblestones and is fairly permanent; at the gage the bed is composed of mud. asuring section there is one channel at high water, but at low water there are two at the gage there is but one channel at all stages. The current is fairly swift. hts range from 1 foot to 9 feet. The stream is frozen from about December 1 to and *observations are discontinued during* that time.

Daily discharge, in second-feet, of Cheyenne River at Edgemont, S. Dak., 1903–1905—Cont

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
1904.											
23		57	10	2,200	665	57	1	0	4	34	
24		57	8	1,050	405	41	1	0	4	66	
25		57	4	848	292	28	1	0	4	85	
26		57	4	700	142	28	1	0	4	85	
27		57	4	595	345	18	1	0	4		
28		57	4	530	246	18	0	23	4		
29		57	4	465	206	18	0	23	4		
30		57	4	405	171	18	595	8	1		
31		57		595		18	1,320		1		
1905.											
1		1,135	28	18	171	345	4,290	117	57	41	
2		965	292	292	171	8,665	2,940	171	246	28	
3		810	57	965	171	3,460	2,565	206	117	28	
4		735	57	171	171	2,440	1,420	142	117	41	
5		405	28	57	171	1,320	562	95	75	28	
6		171	28	57	171	530	6,842	41	75	28	
7		142	28	117	171	117	1,420	41	18	28	
8		142	28	117	206	665	1,050	41	57	28	
9		142	28	117	206	292	530	28	57	28	
10		142	28	75	206	292	142	28	57	28	
11		142	28	57	2,200	292	2,440	28	41	28	
12		142	28	57	1,320	246	7,420	28	57	28	
13		117	28	57	1,320	171	3,460	28	57	28	
14		117	95	57	2,200	292	1,320	28	75	28	
15		57	57	57	2,815	246	735	41	75	28	
16		57	57	41	965	206	465	41	75	28	
17		57	57	41	2,732	171	171	41	75	28	
18		57	57	57	9,173	117	142	28	57	28	
19		57	57	57	1,850	75	142	28	57	28	
20		57	57	75	965	6,220	117	28	28	28	
21		57	57	75	345	3,385	57	18	28	28	
22		41	57	75	345	2,200	206	18	28	28	
23		28	57	1,850	206	735	57	18	28	28	
24		28	57	1,850	206	465	41	18	28	28	
25		28	57	292	206	292	57	18	28	28	
26		28	41	292	345	206	171	18	28	28	
27		57	57	41	292	1,420	117	18	28	28	
28		57	57	41	206	3,730	95	18	28	28	
29			57	41		21,600	95	18	28	28	
30			57		292	4,200	95	18	28	28	
31			57	206		3,730	95		28		

[illegible] method.

	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]

...estimate [illegible]

BEAVER [illegible]

Creek rises [illegible]
n Cheyenne River [illegible]
ging station was [illegible]
miles northwest of [illegible]
nk on the Chicago, Burlington [illegible] Railroad [illegible]
in the S. ½ sec. [illegible]
channel is straight for 30 [illegible]
ble to overflow during [illegible]
nd and cobblestones and [illegible]
measuring section there [illegible]
ils; at the gage there is [illegible]
heights range from 1 foot to [illegible]
ch 30, and observations are [illegible]

Discharge measurements are made by wading near a ford 1,000 feet below the gage. The initial point for soundings is a stake on the right bank in line with a crotched fence post and a dead tree.

The gage, which was read once each day during 1905 by H. Anderson, is a post supporting a plank step on the right bank, graduated from zero to 4 feet; a second post, higher up on the bank, about 30 yards from the house of the observer, is graduated from 4 to 8.5 feet. The bench mark is a spike driven 6 inches above the base of a cottonwood tree 100 feet above the gage; elevation, 9.59 feet above zero of gage.

Discharge measurements of Beaver Creek near Edgemont, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 7	H. D. Comstock	38	24.0	0.87	1.21	20
May 17	do	22	7.8	.59	.85	4.6
June 14	do	28	14.0	1.74	1.24	24
June 17	do	24	9.6	.98	.98	9.4
August 4	do	80	99.0	3.15	2.90	312
August 8	do	52	41.0	2.37	1.80	98
September 7	Stevens and Comstock	25	10.7	1.06	1.00	11.4

Daily gage height, in feet, of Beaver Creek near Edgemont, S. Dak., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1		1.05	2.7	3.2	3.4	1.0	1.0	1.1
2		1.55	2.0	8.4	6.9	1.2	2.0	1.2
3		1.4	1.2	7.45	5.4	1.1	2.5	1.2
4		1.2	1.0	5.8	3.5	1.0	1.6	1.15
5		1.1	.9	3.1	2.2	1.0	1.4	1.1
6		1.0	1.2	2.2	4.2	1.0	1.2	1.1
7	1.2	1.2	1.1	3.25	2.6	1.0	1.1	1.1
8	1.2	1.1	1.0	2.9	1.85	1.0	1.1	1.0
9	1.2	1.1	.9	1.8	1.7	1.0	1.0	1.0
10	1.3	1.1	2.9	1.4	1.8	1.0	1.0	1.0
11	1.25	1.0	3.35	1.4	1.85	1.0	1.0	1.0
12	1.2	.9	2.9	1.35	1.4	1.0	1.0	1.0
13	1.2	.8	1.5	1.3	1.4	1.0	1.0	1.0
14	1.2	.8	1.3	2.4	2.8	1.0	1.0	1.05
15	1.2	.8	1.2	1.65	2.1	1.0	1.0	1.05
16	1.2	.8	1.1	1.4	1.6	1.0	1.0	1.05
17	1.25	.8	1.0	1.25	1.4	1.0	1.0	1.1
18	1.2	.8	1.25	1.2	1.3	1.0	1.0	1.1
19	1.2	1.3	1.3	1.1	1.25	1.0	1.0	1.1
20	1.15	1.4	1.2	3.95	1.2	1.0	1.0	1.1
21	1.15	1.2	1.2	3.45	1.15	1.0	1.0	1.1
22	1.1	1.1	1.2	4.5	1.15	1.0	1.0	1.1
23	1.15	1.4	1.2	2.3	1.1	1.0	1.1	1.1
24	1.15	1.2	1.15	1.7	1.0	1.0	1.1	1.1
25	1.1	1.78	1.48	1.4	1.0	1.0	1.1	1.1
26	1.1	1.6	1.4	1.35	1.0	1.0	1.1	1.1
27	1.1	1.3	1.3	5.25	1.0	1.0	1.1	1.1
28	1.1	1.2	1.2	4.4	1.0	1.0	1.1	1.1
29	1.05	1.2	1.1	8.6	1.0	1.0	1.1	1.1
30	1.05	1.2	1.1	6.7	1.0	1.0	1.1	.....
31	.....	1.1	.....	4.4	1.0	.....	1.1	.....

HAT CREEK NEAR EDGEMONT, S. DAK.

Creek enters Cheyenne River from the south in the central part of Fall River County,
.

gaging station was established April 8, 1905. It is located at Brady's ranch, about 1
bove the mouth of the creek, 13 miles east of Edgemont, S. Dak., in the SE. ¼ sec. 24,
., R. 4 E.

channel is straight for about 500 feet above and below the station. The right bank
lium high, is clean, and overflows at very high floods; the left bank is high and clean
oes not overflow. The bed of the stream is composed of gravel and mud and is fairly
anent. There is but one channel at all stages and the current is swift. The stream is
over from about December 1 to March 10, and observations are discontinued during
period. Gage heights range from 0.5 foot to 11 feet.

scharge measurements are made by wading 50 feet above the gage. The initial point
oundings is the bench mark.

ne gage, which was read once each day during 1905 by Clarence Brady, consists of a ver-
staff spiked to the crib work of an old pumping plant near the house of the observer.
bench mark is a spike in a cottonwood tree on the left bank, 50 feet above the gage and
eet from the water's edge; elevation above zero of gage, 10.22 feet.

Discharge measurements of Hat Creek near Edgemont, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
il 8	H. D. Comstock	15	7.6	1.55	0.71	11.8
18	do	23	12.3	1.01	.80	12.4
e 15	do	18	8.4	1.46	.73	12.3
ust 7 [a]	do	115	408	4.80	5.10	1,958
ust 9	do	32	34	2.50	1.70	85
tember 6 [b]	Stevens and Comstock				1.10	8

[a] Float measurement.
[b] Bar below gage causes backwater; discharge estimated.

Daily gage height, in feet, of Hat Creek near Edgemont, S. Dak., for 1905.

Day.	April.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	.....	0.6	1.6	5.4	2.0	1.1	1.0	
2	.....	1.68	1.15	2.8	1.9	1.1	1.0	
3	.....	2.65	1.0	4.1	2.9	1.1	.95	
4	.....	4.5	.9	2.5	1.9	1.1	.95	
5	.....	2.9	.9	1.9	1.6	1.1	1.0	
6	.....	1.9	.8	1.5	5.7	1.1	1.0	
7	.....	1.45	.8	1.5	5.2	1.1	.95	
8	.....	1.2	.75	1.4	2.45	1.1	.9	
9	0.6	1.0	.7	1.9	1.75	1.1	.9	
10	.7	1.0	2.72	1.55	2.0	1.1	.9	
11	.7	.9	2.0	1.45	2.3	1.1	.95	
12	.8	.85	1.2	1.3	11.0	1.1	.95	
13	.8	.9	.9	1.2	8.0	1.1	1.0	
14	1.6	.85	1.8	1.1	3.0	1.1	1.0	
15	1.3	.8	.8	1.1	2.2	1.1	1.0	
16	1.1	.8	2.45	1.0	1.8	1.1	1.0	
17	1.2	.8	.8	1.0	1.6	1.1	1.25	
18	1.1	.8	5.0	1.0	1.5	1.1	1.25	
19	1.0	.8	6.3	1.0	1.5	1.1	1.15	
20	1.0	.8	2.6	1.2	1.5	1.1	1.1	
21	.9	1.8	2.3	1.1	1.5	1.1	1.1	
22	.8	1.25	2.8	2.65	1.45	1.05	1.0	
23	.75	1.0	7.0	2.5	1.3	1.05	1.0	
24	.7	.9	3.4	1.2	1.3	1.0	1.0	
25	.7	.9	3.5	1.0	1.2	1.0	1.0	
26	.65	.75	2.3	1.0	1.2	1.0	1.0	
27	.6	.75	1.85	1.0	1.2	.95	1.0	
28	.7	.75	1.7	.9	1.2	.9	1.0	
29	.7	.8	1.55	4.5	1.15	.95	1.0	
30	.65	1.85	1.8	8.5	1.1	1.0	1.0	
31	.....	2.5	.....	6.2	1.1	.....	1.0	.....

Estimated monthly discharge of Hat Creek near Edgemont, S. Dak., for 1905.

Month.	Discharge in second-feet.			Total acre-fe
	Maximum.	Minimum.	Mean.	
April 9–30	111	6	24.8	1
May	1,660	6	134	8
June	3,460	10	448	26
July	5,300	23	519	31
August	9,150	8	698	42
September	8	0	6.3	
October	21	0	3.6	
November	2	2	2.0	
The period	.....	.....	.....	111

NOTE.—This estimate is only approximate.

SPRING CREEK NEAR RAPID, S. DAK.

Spring Creek has its source in the Black Hills in western South Dakota, flows southeastward and then northeastward and enters Cheyenne River near Creston, S. Dak.

The gaging station was established June 27, 1903. It is located on the highway from Rapid to Hermosa, on the property of Frank Blair, in the SE. ¼ sec. 3, T. 1 S., R. 7 E.

The channel is straight for 100 feet above and 75 feet below the station. Both banks are low and subject to overflow. At the station the bed of the stream is gravelly, but above and below this point the bottom is muddy. The current is sluggish above and below the footbridge, but is swift at the point where measurements are made. The stream is frozen from about December 1 to March 10, and observations are discontinued during that period. Gage heights range from 0.5 foot to 5 feet.

Discharge measurements are made from a small plank footbridge.

The gage, which was read once each day during 1905 by Lydia Blair, is a vertical timber, spiked to a tree at the water's edge, about 100 feet above the footbridge. The gage is referred to bench marks as follows: (1) A steel nail driven into the tree to which the gage is attached; elevation, 2.14 feet. (2) A nail driven into the base of a tree about 50 feet upstream from the gage; elevation, 4.14 feet. (3) A nail driven into the roots of a tree about 75 feet downstream from the gage; elevation, 3.36 feet. Elevations are above the zero of the gage. This station was discontinued December 1, 1905.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 53; 130, pp 160–161.
Discharge: 99, p 53; 130, p 161.
Discharge, monthly: 130, p 163.
Gage heights: 99, pp 53–54; 130, pp 161–162.
Rating table: 130, p 162.

Discharge measurements of Spring Creek near Rapid, S. Dak., for 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 20	H. D. Comstock	11	5.5	1.02	0.91	5.6
June 24	do	30	27	.72	1.15	19.4
July 3	do	23	34	2.08	1.89	70
August 14	do	22	34	2.27	1.80	78
September 4	Stevens and Comstock	24	29	.82	1.25	24

Daily gage height, in feet, of Spring Creek near Rapid, S. Dak., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1		1.1	1.1	3.8	1.3	1.0	1.1
2		1.2	1.4	2.2	1.3	1.0	1.1
3		1.1	1.7	2.2	1.3	1.0	1.1
4	1.5	1.1	1.6	2.0	1.3	1.0	1.1
5	.8	1.1	1.6	1.8	1.3	1.0	1.1
6	.9	1.1	1.6	1.8	1.3	1.0	1.1
7	1.0	1.1	1.6	1.8	1.3	1.0	1.1
8	1.0	1.0	2.0	1.7	1.3	1.0	1.1
9	1.0	1.0	2.0	1.6	1.3	1.0	1.1
10	1.0	1.1	1.9	1.6	1.3	1.0	1.1
11	1.0	1.1	1.9	1.9	1.3	1.0	1.1
12	.9	1.2	1.9	1.9	1.3	1.0	1.1
13	.9	1.1	1.7	1.9	1.3	1.0	1.1
14	.9	1.0	1.6	1.8	1.2	1.0	1.1
15	.9	1.0	1.5	1.8	1.2	1.0	1.1
16	.9	1.1	1.4	1.8	1.2	1.0	1.1
17	.9	1.2	1.4	1.7	1.2	1.0	1.0
18	.9	1.2	1.4	1.7	1.2	1.0	1.0
19	.9	1.2	1.4	1.7	1.2	1.1	1.0
20	.9	1.2	1.7	1.6	1.2	1.2	1.0
21	.9	1.2	1.7	1.6	1.2	1.1	1.0
22	.9	1.2	2.25	1.5	1.1	1.1	1.0
23	.9	1.2	1.7	1.5	1.1	1.1	1.0
24	1.0	1.2	1.5	1.5	1.1	1.1	1.0
25	1.0	1.2	1.5	1.5	1.1	1.1	1.0
26	1.0	1.2	3.8	1.5	1.1	1.1	1.0
27	1.0	1.2	1.6	1.5	1.1	1.1	1.0
28	1.0	1.2	3.9	1.4	1.1	1.1	.9
29	1.2	1.1	1.8	1.3	1.0	1.1	.9
30	1.2	1.1	1.6	1.3	1.0	1.1	.9
31	1.1	.....	1.6	1.3	.....	1.1	.....

Station rating table for Spring Creek near Rapid, S. Dak., from May 4 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.80	4	1.60	57	2.40	160	3.20	289
.90	6	1.70	67	2.50	175	3.30	307
1.00	10	1.80	79	2.60	190	3.40	325
1.10	15	1.90	91	2.70	206	3.50	343
1.20	21	2.00	103	2.80	222	3.60	361
1.30	29	2.10	117	2.90	238	3.70	379
1.40	37	2.20	131	3.00	255	3.80	397
1.50	47	2.30	145	3.10	272	3.90	415

The above table is applicable only for open-channel conditions. It is based on 15 discharge measurements made during 1903–1905, and is not well defined.

Estimated monthly discharge of Spring Creek near Rapid, S. Dak., for 1905.

[Drainage area, 205 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
May 1-31	47	4	10.2	566	0.050	0.052
June	21	10	17.1	1,018	.083	.093
July	415	15	86.2	5,239	.416	.480
August	397	29	77.8	4,784	.380	.438
September	29	10	22.3	1,327	.109	.122
October	21	10	12.3	756	.060	.069
November	15	6	12.3	732	.060	.067
The period				14,420		

RAPID CREEK AT RAPID, S. DAK.

Rapid Creek, which enters Cheyenne River near Creston, S. Dak., has its source in the Black Hills and flows southeastward.

The gaging station was established June 10, 1903. It is located at a highway bridge one-half mile downstream from the Rapid River Milling Company's mill, and one-fourth mile north of the Chicago and Northwestern Railway in the S. E. ¼ sec. 36, T. 2 N., R. 7 E.

The channel is straight for 150 feet above and 100 feet below the station. The banks are from 12 to 15 feet high and are liable to overflow only at extreme high water. The bed of the stream is composed of mud, with embedded bowlders. At high water there are two channels, one of which is very small. The velocity is good at all stages. The stream is subject to rapid fluctuations in height, owing to the opening and closing of the head-gates on a ditch above the station. Gage heights range from 1 foot to 5 feet. The stream is frozen from about December 20 to March 10, and observations are discontinued during that time.

Discharge measurements are made from the downstream side of the highway bridge. The initial point for soundings is the center one of a group of five brass-headed tacks driven into the downstream face of the end post at the south end of the bridge.

The gage, which was read twice each day during 1905 by John Merritt, is a timber securely spiked to a timber at the south abutment of the bridge. The gage is referred to bench marks as follows: (1) A railroad spike driven near the base of the second tree from the southeast corner of a dwelling across the street from the School of Mines dormitory; elevation, 13.92 feet above the zero of the gage. (2) A railroad spike driven near the base of the first tree from the corner south of the School of Mines dormitory; elevation, 12.81 feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 50-51; 130, pp 163-164.
Discharge: 49, p 272; 99, p 51; 130, p 164.
Discharge, monthly: 99, p 52; 130, p 166.
Gage heights: 99, pp 51-52; 130, p 165.
Rating table: 99, p 52; 130, pp 165-166.

Discharge measurements of Rapid Creek at Rapid, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 10[a]	H. D. Comstock	33	38	2.48	1.70	95
May 19	do	30	77	2.31	2.10	178
May 26	do	30	72	1.99	1.95	143
June 26	do	30	70	1.91	1.91	134
July 3	do	32	104	5.38	2.95	559
July 5	do	32	102	5.08	2.9	518
August 12	do	32	115	2.15	2.21	247
September 2	do	35	106	1.10	1.69	117

[a] Made by wading.

Daily gage height, in feet, of Rapid Creek at Rapid, S. Dak., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	1.5	.....	1.48	1.6	1.38	2.0	2.42	2.22	1.72	1.5	1.62
2	1.6	.....	1.5	1.75	1.75	1.98	2.58	2.22	1.75	1.58	1.55
3	1.62	.....	.....	1.65	1.9	1.9	2.98	2.28	1.75	1.58	1.48
4	1.55	.....	.....	1.6	1.95	1.85	3.0	2.3	1.58	1.5	1.45
5	1.55	.....	.....	1.6	1.85	1.82	2.95	2.08	1.6	1.5	1.4
6	1.62	.....	.....	1.58	1.82	1.82	2.72	2.35	1.7	1.42	1.55
7	.....	.....	.....	1.58	1.85	1.8	2.18	2.2	1.62	1.58	1.5
8	.....	.....	.....	1.62	2.08	1.8	2.62	2.0	1.7	1.45	1.42
9	.....	.....	.....	1.65	2.22	1.78	2.68	2.18	1.55	1.48	1.48
10	.....	.....	.....	1.7	2.25	1.78	2.68	2.22	1.62	1.4	1.55
11	.....	.....	.....	1.65	2.3	1.92	2.58	2.08	1.65	1.45	1.42
12	.....	.....	.....	1.58	2.28	1.88	2.52	2.2	1.68	1.4	1.5
13	.....	.....	.....	1.75	2.25	1.78	2.45	2.2	1.6	1.35	1.38
14	.....	.....	.....	1.7	2.22	1.78	2.48	2.08	1.65	1.45	1.55
15	.....	.....	.....	1.5	2.25	2.12	2.45	2.05	1.68	1.42	1.48
16	.....	.....	1.48	1.6	2.22	1.85	2.32	2.05	1.75	1.42	1.35
17	.....	.....	1.62	1.6	2.15	1.85	2.32	2.0	1.52	1.4	1.45
18	.....	.....	1.6	1.6	2.18	1.98	2.28	2.0	1.58	1.4	1.52
19	.....	.....	1.5	1.6	2.15	2.35	2.2	2.0	1.5	1.48	1.52
20	.....	.....	1.55	1.58	2.1	1.95	2.3	1.88	1.55	1.52	1.55
21	.....	1.3	1.58	1.6	2.08	1.85	2.52	1.92	1.5	1.55	1.38
22	.....	1.4	1.6	1.6	2.02	1.95	2.45	1.85	1.52	1.58	1.45
23	.....	1.48	1.5	1.55	1.98	1.98	2.38	1.82	1.48	1.45	1.32
24	.....	1.48	1.4	1.58	2.02	1.95	2.25	1.82	1.52	1.5	1.42
25	.....	1.42	1.68	1.58	2.02	1.95	2.22	1.95	1.52	1.48	1.51
26	.....	1.48	1.58	1.52	1.98	1.85	3.18	1.88	1.45	1.45	1.48
27	.....	1.42	1.6	1.4	1.95	1.85	2.88	1.75	1.52	1.5	1.4
28	.....	1.5	1.52	1.58	2.02	1.82	3.38	1.85	1.62	1.45	.....
29	.....	.....	1.55	1.65	2.15	1.78	2.35	1.88	1.58	1.58	.....
30	.....	.....	1.4	1.58	2.2	1.72	2.2	1.65	1.55	1.58	.....
31	.....	.....	1.58	.....	2.12	.....	2.22	1.72	.....	1.55	.....

NOTE.—Ice conditions January 7 to February 20, inclusive.

: ı ,n rating table for Rapid Creek at Rapid, S. Dak., from January 1 to July 28, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.30	51	1.90	131	2.50	316	3.00	587
1.40	60	2.00	154	2.60	360	3.10	658
1.50	70	2.10	180	2.70	409	3.20	734
1.60	82	2.20	209	2.80	462	3.30	814
1.70	96	2.30	241	2.90	521	3.40	897
1.80	112	2.40	277				

The above table is applicable only for open-channel conditions. It is based on nine discharge measurements made during 1904–5, and is well defined between gage heights 1.5 feet and 3 feet.

ution rating table for Rapid Creek at Rapid, S. Dak., from July 29 to November 27, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.30	61	1.60	101	1.90	159	2.20	243
1.40	73	1.70	118	2.00	183	2.30	279
1.50	86	1.80	137	2.10	211	2.40	320

The above table is applicable only for open-channel conditions. It is based on two discharge measurements made during 1905.

Estimated monthly discharge of Rapid Creek at Rapid, S. Dak., for 1905.

[Drainage area, 410 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January 1–6	85	70	79.0	940	0.193	0.043
February 21–28	70	51	63.6	1,009	.155	.046
March	93	60	72.5	4,458	.177	.204
April	104	60	83.2	4,951	.203	.226
May	241	58	173	10,640	.422	.486
June	259	99	131	7,795	.320	.357
July	880	203	359	22,070	.876	1.01
August	299	110	195	11,990	.476	.549
September	128	80	102	6,069	.249	.278
October	98	67	84.2	5,177	.205	.236
November 1–27	104	64	82.3	4,407	.201	.202
The period				79,510		

NOTE.—Discharge interpolated March 3–15.

BOXELDER CREEK AT BLACKHAWK, S. DAK.

Boxelder Creek rises in the Black Hills in the southeastern part of Lawrence County, S. Dak., and flows southeastward into Cheyenne River.

The gaging station was established June 27, 1903. It is located at the bridge on the road leading past the church at Blackhawk, in the SE. ¼ sec. 9, T. 2 N., R. 7 E.

The channel is straight for 150 feet above and curved for 75 feet below the station. Both banks are high and cleared, but may overflow in extreme high water. The bed of the stream is stony, with soft mud near the edges, and there is considerable water grass just below the station. The bridge makes an angle of about 30° with the normal to the current. Gage heights range from 0.5 foot to 5 feet. The stream is frozen from about December 1 to March 10, and observations are discontinued during that period.

Discharge measurements are best made by wading, but at high water they may be made from the bridge. The initial point for soundings is a brass tack driven into the hand rail vertically above the gage.

The gage, which was read once each day during 1905 by R. H. Haedt, is a vertical timber securely spiked to a pile on the upstream side of the east end of the bridge. The gage is referred to bench marks as follows: (1) A spike driven about 6 inches above the base of a large fence post at the corner of the barnyard 300 feet east of the station; elevation, 16.84 feet. (2) A spike driven about 6 inches above the base of the south gatepost of a gate near a house about 500 feet from the station along the road toward Rapid; elevation, 16.81 feet. (3) A drift bolt driven in the base of a large cottonwood tree on the right bank, about 75 feet above the bridge; elevation, 4.34 feet. Elevations are above the zero of the gage. This station was discontinued December 1, 1905.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 49; 130, pp 166-167.
Discharge: 99, p 50; 130, p 167.
Discharge, monthly: 130, p 169.
Gage heights: 99, p 50; 130, pp 167-168.
Rating tables: 130, p 168.

Discharge measurements of Boxelder Creek at Blackhawk, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 20	H. D. Comstock	40	80	1.34	2.10	107
June 21[a]	do	22	18.5	2.22	1.49	41
July 3	do	48	225	2.43	4.60	546
August 14[a]	do	26	24	3.29	1.72	79
September 4[a]	Stevens and Comstock	26	29	1.07	1.11	31

[a] Made by wading.

Daily gage height, in feet, of Boxelder Creek at Blackhawk, S. Dak., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	.....	1.6	1.1	3.3	1.2	0.9	0.7
.....	.....	1.55	5.1	2.5	1.15	.9	.8
.....	.....	1.55	4.7	2.3	1.2	.9	.75
.....	.....	1.5	4.3	2.15	1.11	.9	.75
.....	.....	1.4	3.7	2.1	1.08	.85	.8
.....	.....	1.4	3.4	2.0	1.05	.85	.8
.....	.....	1.4	3.0	1.95	1.1	.8	.8
.....	.....	1.3	3.0	1.9	1.1	.85	.8
.....	2.0	1.28	3.2	1.8	1.1	.85	.8
.....	2.5	1.28	2.7	1.7	1.05	.85	.8
.....	2.65	1.6	2.7	1.88	1.0	.88	.75
.....	2.6	1.5	2.65	1.9	1.1	.9	.75
.....	2.55	1.4	2.4	1.9	1.1	.9	.75
.....	2.5	1.3	2.35	1.75	1.05	.9	.75
.....	2.4	1.2	2.2	1.7	1.0	.9	.75
.....	2.35	1.3	2.08	1.6	1.0	.9	.75
.....	2.25	1.4	2.0	1.52	1.0	.9	.7
.....	2.1	1.58	1.9	1.5	1.0	.9	.7
.....	2.05	1.6	1.8	1.5	.95	.88	.7
.....	2.05	1.55	2.1	1.45	.95	.85	.7
.....	2.0	1.5	2.4	1.4	.9	.82	.7
.....	1.9	1.55	2.05	1.35	.9	.8	.65
.....	1.8	1.55	2.0	1.3	.85	.8	.7
.....	1.9	1.5	1.8	1.3	.85	.8	.75
.....	1.8	1.5	1.8	1.25	.85	.8	.7
.....	1.8	1.4	2.2	1.22	.8	.8	.7
.....	1.8	1.35	3.28	1.3	.9	.8	.7
.....	1.8	1.25	2.7	1.3	.9	.8	.6
.....	1.9	1.18	2.5	1.25	.9	.75	.55
.....	1.9	1.05	1.9	1.2	.9	.7	.5
.....	1.75	.....	1.8	1.2	.....	.7	.....

n rating table for Boxelder Creek at Blackhawk, S. Dak., from May 9 to July 1, 1905

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	7	1.50	42	2.00	95	2.50	161
1.10	12	1.60	51	2.10	107	2.60	176
1.20	18	1.70	61	2.20	120	2.70	191
1.30	25	1.80	72	2.30	133		
1.40	33	1.90	83	2.40	147		

above table is applicable only for open-channel conditions. It is based on three discharge measits made during 1905, and is not well defined.

Station rating table for Boxelder Creek at Blackhawk, S. Dak., from July 2 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
.50	2	1.30	42	2.10	128	2.90	241
.60	4	1.40	50	2.20	141	3.00	277
.70	7	1.50	59	2.30	154	3.10	273
.80	11	1.60	69	2.40	168	3.20	289
.90	16	1.70	80	2.50	182	3.30	306
1.00	21	1.80	91	2.60	196	3.40	323
1.10	27	1.90	103	2.70	211		
1.20	34	2.00	115	2.80	226		

The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during the latter part of 1905, and is not well defined.

Estimated monthly discharge of Boxelder Creek at Blackhawk, S. Dak., for 1905.

[Drainage area, 157 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
May 9-31	184	66	109	4,972	0.694	0.594
June	51	9	35.4	2,106	.225	.251
July	650	27	210	12,910	1.34	1.54
August	306	34	84.5	5,196	.538	.620
September	34	11	21.6	1,285	.138	.154
October	60	7	19.0	1,168	.121	.140
November	11	2	8.1	482	.052	.058
The period				28,120		

BELLE FOURCHE RIVER AT BELLE FOURCHE, S. DAK.

Belle Fourche River, the largest tributary of the Cheyenne, rises near Middle Butte, in the western part of Weston County, Wyo., flows northeastward to a point near the Wyoming-Montana boundary line, then turns abruptly to the southeast, skirting the northern border of the Black Hills, and unites with the Cheyenne in the southeastern part of Meade County, S. Dak.

The gaging station was established May 26, 1903. It is located at the county highway bridge on the western outskirts of Belle Fourche, S. Dak., in the NW. ¼, sec. 10, T. 8 N., R. 2 E.

The channel is straight for 225 feet above the bridge and 300 feet below. The left bank is high, with a few scattered trees; the right bank is low, sparsely wooded, and subject to overflow at flood stages. The bed of the stream is of gravel and fairly permanent. The water flows in a single channel except at low stages, when it is divided by a gravel bar below the bridge. The current is swift. Gage heights range from 0.5 foot to 11 feet.

Discharge measurements are made from the lower side of the bridge. The initial point for soundings is the center of the north pile in the first bent on the east end.

The gage, which was read twice each day during 1905 by Raymond Giles, consists of a vertical timber spiked to a pile on the north side of the bridge on the third bent from the east end. The gage is referred to bench-marks as follows: (1) A spike in a cottonwood tree on the east bank 50 feet below the bridge; elevation, 8.05 feet above the zero of the

(2) The top of the iron breakwater on the east pier of the railroad bridge 300 feet he highway bridge; elevation, 8.13 feet above the zero of the gage. (3) A United eological Survey standard bench mark located in the Butte County court-house yard; n, 18.70 feet above the zero of the gage and 3,011.34 feet above sea level, making ation of gage datum above sea level 2,992.64 feet.

mation in regard to this station is contained in the following Water-Supply Papers of ited States Geological Survey:

ption: 99, p 57; 130, pp 169–170.
arge: 99, p 57; 130, p 170.
arge, monthly: 99, p 59; 130, p 172.
eights: 99, p 58; 130, p 171.
g table: 99, p 58; 130, p 171.

ischarge measurements of Belle Fourche River at Belle Fourche, S. Dak., for 1905.

te.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
a	F. M. Madden	54	65	1.45	1.80	94
a	H. D. Comstock	62	57	1.25	1.68	71
	do	70	89	1.64	2.00	146
	do	70	89	1.70	2.00	151
	do	134	414	4.44	4.88	1,838
	do	105	191	3.12	3.19	595
	do	93	143	2.37	2.41	339
	do	93	143	2.40	2.41	343
2	do	120	261	3.89	3.79	1,015
16	J. C. Stevens	131	333	4.30	4.56	1,433

a Made by wading.

Daily gage height, in feet, of Belle Fourche River at Belle Fourche, S. Dak., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.68	4.25	4.95	1.7	1.58	1.85	1.95	4.85	2.1	1.6	1.7	1.6
2	1.55	5.0	4.35	1.72	2.08	1.9	1.92	3.32	2.1	1.6	1.7	1.6
3	1.35	5.75	3.95	1.65	3.15	1.85	4.3	2.78	2.1	1.6	1.7	.....
4	1.15	6.4	3.4	1.65	3.0	1.8	3.45	3.75	1.75	2.55	1.7	.....
5	.95	6.8	2.8	1.65	2.5	1.75	4.82	3.4	1.7	2.35	1.7	.....
6	.95	7.0	2.85	1.65	2.18	1.7	3.85	3.4	1.58	2.15	1.7	.....
7	.95	7.0	2.25	1.65	2.1	1.7	3.35	3.4	1.5	1.92	1.7	.....
8	1.0	7.0	2.25	1.65	2.18	1.7	3.48	2.15	1.5	1.82	1.7	.....
9	1.02	7.0	2.25	1.72	2.28	1.7	2.75	2.38	1.5	1.72	1.7	.....
10	1.05	6.7	2.25	1.82	2.68	1.75	3.52	3.2	1.45	1.7	1.7	.....
11	1.12	6.45	2.25	1.75	2.38	1.75	2.4	2.35	1.45	1.62	1.7	.....
12	1.3	6.2	2.05	1.7	2.25	1.75	2.6	2.35	1.45	1.65	1.7	.....
13	1.5	6.0	2.0	1.7	2.25	1.75	2.6	2.2	1.52	1.7	1.7	.....
14	1.72	5.9	2.0	1.75	2.2	1.75	2.3	6.38	1.55	1.7	1.7	.....
15	2.05	5.65	2.0	1.75	2.0	3.75	2.1	5.25	1.55	1.7	1.7	.....
16	2.22	5.35	2.0	1.75	1.95	3.15	2.6	4.35	1.55	1.7	1.7	.....
17	2.0	5.3	1.92	1.7	1.85	3.42	2.4	3.18	1.55	1.7	1.65	.....
18	2.0	5.15	1.82	1.7	1.85	.....	2.3	2.72	1.55	1.7	1.65	.....
19	3.0	4.98	1.72	1.7	1.85	2.85	2.05	2.5	1.55	1.7	1.65	.....
20	2.45	4.85	1.65	1.65	1.85	3.65	2.15	2.32	1.55	1.7	1.6	.....
21	2.38	4.8	1.65	1.65	1.85	3.32	2.4	2.2	1.55	1.7	1.6	.....
22	2.15	4.8	1.65	1.65	1.85	3.5	2.45	2.1	1.55	1.7	1.6	.....
23	1.08	4.8	1.6	1.65	1.85	2.85	3.45	2.02	1.55	1.7	1.6	.....
24	2.6	4.72	1.6	1.65	2.0	2.75	3.35	1.95	1.52	1.7	1.6	.....
25	3.0	4.7	1.6	1.65	2.82	2.8	3.35	1.9	1.5	1.7	1.6	.....
26	3.25	4.6	1.6	1.65	3.08	2.8	3.25	1.85	1.5	1.7	1.6	.....
27	3.45	4.6	1.6	1.65	2.38	2.35	4.32	1.8	1.5	1.7	1.6	.....
28	3.55	5.02	1.68	1.65	2.2	2.45	2.35	1.75	1.5	1.7	1.6	.....
29	3.38	.....	1.78	1.65	2.15	3.1	2.5	1.75	1.5	1.7	1.6	.....
30	3.18	.....	1.72	1.6	1.92	3.05	2.25	1.7	1.5	1.7	1.6	.....
31	3.0	.....	1.7	.....	1.9	.....	3.4	2.0	.....	1.7	.....	.....

NOTE.—Ice conditions January 1 to March 6, inclusive.

Station rating table for Belle Fourche River at Belle Fourche, S. Dak., from January 1 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.40	50	2.50	290	3.60	850	4.70	1,630
1.50	60	2.60	330	3.70	920	4.80	1,705
1.60	75	2.70	370	3.80	990	4.90	1,780
1.70	90	2.80	410	3.90	1,060	5.00	1,855
1.80	110	2.90	450	4.00	1,130	5.20	2,005
1.90	130	3.00	500	4.10	1,200	5.40	2,155
2.00	150	3.10	550	4.20	1,270	5.60	2,305
2.10	175	3.20	610	4.30	1,340	5.80	2,455
2.20	200	3.30	670	4.40	1,410	6.00	2,610
2.30	230	3.40	730	4.50	1,480	6.20	2,770
2.40	260	3.50	790	4.60	1,555	6.40	2,930

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5, and is well defined between gage heights 1 foot and 5.5 feet.

ed monthly discharge of Belle Fourche River at Belle Fourche, S. Dak., for 1905.

[Drainage area, 3,250 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	215	75	127	6,298	0.039	0.036
.....	114	78	87.7	5,218	.027	.030
.....	580	72	219	13,470	.067	.077
.....	955	90	344	20,470	.106	.118
.....	1,720	134	531	32,650	.163	.188
.....	2,914	90	531	32,650	.163	.188
.....	175	55	76.6	4,558	.024	.027
.....	310	75	105	6,456	.032	.037
.....	90	75	83.7	4,980	.026	.029
eriod.....	.....	.....	.....	126,800	.....	.....

o estimate for ice period.

REDWATER RIVER AT BELLE FOURCHE, S. DAK.

er River rises in the eastern part of Crook County, Wyo., flows eastward and h the Belle Fourche at Belle Fourche, S. Dak.

ing station was established July 20, 1903. It is located at the county highway he eastern limits of Belle Fourche, S. Dak., in the NW. ¼, sec. 11, T. 8 N., R. 2 E., ove the junction with Belle Fourche River.

nnel is straight for 50 feet above and below the station. The left bank is suffi- h to prevent overflow, but the right bank is low and subject to overflow; there long both banks. The bed of the stream is rocky and is fairly permanent. There channel except at very high stages, and the current is swift. At very high stages eights may be affected by backwater from Belle Fourche River. There is con- "dead water" at low stages.

ge measurements are made from the north side of the bridge. The initial point ngs is the center of the pile on the north side and at the east end of the bridge e, which was read twice each day during 1905 by Raymond Giles, consists of a ked to the north pile of the west bent of the bridge. The gage is referred to ks as follows: (1) The stone water table at the north corner of the public school elevation, 26.05 feet above the zero of the gage. (2) The top of the end of the pipe projecting from the northeast corner of the public school building; eleva- 7 feet above the zero of the gage. (3) The United States Geological Survey bench mark in the Butte County court-house yard; elevation, 18.46 feet above f the gage and 3,011.34 feet above sea level, making the elevation of the gage ove sea level 2,992.88 feet.

ation in regard to this station is contained in the following Water-Supply Papers ited States Geological Survey:

on: 99, p 59; 130, pp 172–173.
e: 99, p 59; 130, p 173.
e, monthly: 99, p 60; 130, p 175.
hts: 99, p 60; 130, pp 173–174.
able: 99, p 60; 130, p 174.

Discharge measurements of Redwater River at Belle Fourche, S. Dak., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity	Gage height.	Dis-charg
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-*
March 30	F. M. Madden	62	150	1.39	2.95	
April 18	H. D. Comstock	62	152	1.32	2.95	
May 11	do	65	251	3.76	4.50	
May 13	do	63	220	3.12	4.05	
June 9	do	60	111	1.28	2.80	
July 7	do	62	172	2.22	3.80	
August 16	J. C. Stevens	62	170	1.52	3.16	

Daily gage height, in feet, of Redwater River at Belle Fourche, S. Dak., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	N
1	3.3	10.0	2.85	2.95	2.9	3.25	3.25	3.4	2.7	2.92	
2	3.3	13.0	2.85	2.95	3.05	3.1	3.25	3.4	2.7	2.95	
3	3.3	13.0	2.85	2.95	3.85	3.15	4.7	3.42	2.7	2.95	
4	3.22	13.0	3.0	2.95	3.82	3.05	4.75	3.35	2.8	2.95	
5	3.15	13.0	2.95	2.95	3.58	3.0	4.2	3.3	2.88	2.95	
6	3.15	13.0	2.85	2.95	3.62	2.95	4.0	3.25	2.95	2.95	
7	3.2	13.0	2.85	2.95	3.42	2.9	3.75	3.25	2.95	2.95	
8	3.25	13.0	2.85	3.0	3.82	2.85	4.28	3.15	2.95	2.95	
9	3.32	13.0	2.85	3.0	4.42	2.85	3.98	3.1	2.95	2.95	
10	3.42	13.0	2.88	3.0	4.82	2.85	3.9	3.1	2.95	2.95	
11	3.55	13.0	2.75	3.0	4.62	2.95	3.7	3.1	2.92	2.95	
12	3.75	13.0	2.85	3.0	4.2	2.95	3.65	3.15	2.85	2.95	
13	4.08	13.0	2.85	3.0	4.15	2.85	3.6	3.2	2.82	2.95	
14	4.95	13.0	2.85	2.95	4.1	2.85	3.65	3.35	2.8	2.95	
15	4.85	11.75	2.85	2.95	4.0	2.85	3.48	3.2	2.85	2.95	
16	5.05	9.5	2.85	2.95	3.88	2.98	3.4	3.2	2.85	3.02	
17	5.18	8.65	2.85	2.95	3.78	3.35	3.4	3.15	2.95	3.32	
18	5.28	8.45	2.85	2.95	3.75	.....	3.4	3.15	2.92	3.5	
19	5.45	8.25	2.86	2.95	3.75	3.5	3.25	3.15	2.9	3.5	
20	5.28	7.35	2.85	2.92	3.72	3.48	3.25	3.08	2.95	3.5	
21	4.9	5.9	2.85	2.9	3.7	3.4	3.75	3.0	2.92	3.5	
22	4.55	4.9	2.85	2.9	3.65	3.4	3.72	2.95	2.9	3.5	
23	4.5	4.5	2.85	2.9	4.0	3.4	3.75	2.95	2.9	3.5	
24	4.65	3.75	2.85	2.9	3.85	3.4	3.5	2.92	2.88	3.5	
25	4.88	3.35	2.9	2.9	3.72	2.9	3.45	2.9	2.85	3.5	
26	5.15	3.05	2.9	2.9	3.65	3.0	3.4	2.85	2.9	3.5	
27	5.32	2.95	2.9	2.9	3.55	3.25	3.7	2.8	2.88	3.5	
28	5.42	2.88	3.0	2.95	3.5	3.0	3.45	2.75	2.85	3.5	
29	5.52	.....	2.95	2.92	3.45	3.25	3.92	2.75	2.85	3.5	
30	5.65	.....	2.95	2.9	3.35	3.25	3.95	2.75	2.9	3.5	
31	5.95	.....	2.95	.....	3.3	.....	3.48	2.7	.....	3.5	...

NOTE.—Ice conditions January 1 to February 24, inclusive.

Station rating table for Redwater River at Belle Fourche, S. Dak., from January 1 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.70	120	3.30	323	3.90	607	4.50	942
2.80	148	3.40	365	4.00	660	4.60	1,002
2.90	178	3.50	410	4.10	714	4.70	1,064
3.00	210	3.60	457	4.20	769	4.80	1,130
3.10	245	3.70	505	4.30	825	4.90	1,200
3.20	283	3.80	555	4.40	883	5.00	1,265

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1905, and is well defined between gage heights 2.7 feet and 4.9 feet.

Estimated monthly discharge of Redwater River at Belle Fourche, S. Dak., for 1905.

[Drainage area, 1,015 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March	210	134	171	10,510	0.168	0.194
April	210	178	192	11,420	.189	.211
May	1,144	178	554	34,060	.546	.630
June	410	163	256	15,230	.252	.281
July	1,097	303	520	31,970	.512	.590
August	374	120	247	15,190	.243	.280
September	194	120	170	10,120	.167	.186
October	410	184	296	18,200	.292	.337
November	457	410	445	26,480	.438	.489
The period				173,200		

NOTE.—No estimate for ice period.

SPEARFISH CREEK NEAR SPEARFISH, S. DAK.

Spearfish Creek rises in the Black Hills in western Lawrence County, S. Dak., and flows northward into Redwater River.

The gaging station was established March 30, 1904. It is located at the Chicago, Burlington and Quincy Railroad bridge at Bradley's ranch, 1 mile above Spearfish, S. Dak., in the SW. ¼, sec. 14, T. 6 N., R. 2 E. It replaces the temporary station maintained during a part of 1903 at Toomey's ranch, 6 miles from Spearfish, and was placed at this point to get above the ditches which take water from Spearfish Creek in the town of Spearfish.

The channel is very crooked and the current is swift and full of rapids. Both banks are low, are covered with trees and brush, and overflow only when the stream freezes and the water runs over the ice. The bed is composed of coarse gravel and cobblestones and is not subject to much change. There is but one channel at all stages. Gage heights range from 0.8 foot to 7 feet.

Discharge measurements are made by wading at the gage. In high water they can be made from the bridge to which the gage is attached.

A staff gage, which was read during 1905 once each day by Bessie L. Bradley, is spiked vertically to a pile supporting the bridge near the right bank on the lower side. The gage is referred to bench marks as follows: (1) A drift bolt driven into the base of a cottonwood tree on the right bank, 50 feet below the gage; elevation, 4.02 feet above the zero of the gage. (2) The top of the head of a bolt in a pile in the first bent from the gage; the bolt

marked by a spike driven through a flaw in the washer; elevation above the zero of gage, 6.25 feet.

A description of this station, with gage-height and discharge data, is contained in Water Supply Paper No. 130 of the United States Geological Survey, pages 175–177, 192.

Discharge measurements of Spearfish Creek near Spearfish, S. Dak., in 1905.

Date.	Hydrographer	Width.	Area of section.	Mean velocity.	Gage height.	ch
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sc*
April 6	H. D. Comstock	25	22	3.26	0.96	
May 16	do	44	54	4.80	1.85	
June 13	do	31	31	4.16	1.28	
August 3	do	32	30	4.83	1.24	
August 26	Stevens and Comstock	34	29	3.72	1.12	

Daily gage height, in feet, of Spearfish Creek near Spearfish, S. Dak., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	
1	0.95	1.3	0.85	0.95	1.15	1.25	1.3	1.25	1.1	1.05	1.05	
2	.95	1.5	.85	.95	1.3	1.25	2.02	1.25	1.05	1.05	1.0	
3	.95	2.65	.85	.95	1.3	1.25	2.5	1.25	1.05	1.05	1.0	..
4	.95	3.05	.85	.9	1.3	1.25	2.05	1.2	1.05	1.05	1.0	..
5	.9	3.3	.85	.9	1.3	1.35	1.75	1.2	1.05	1.05	1.0	..
6	.9	3.15	.85	.95	1.3	1.25	1.75	1.2	1.05	1.05	1.0	..
7	.85	3.4	.85	.95	1.45	1.25	1.65	1.2	1.1	1.05	1.0	..
8	.85	3.1	.85	.95	1.7	1.25	1.65	1.2	1.1	1.05	1.05	..
9	.95	2.9	.85	.95	2.25	1.3	1.55	1.2	1.1	1.05	1.05	..
10	1.05	2.0	.85	.95	2.45	1.3	1.45	1.2	1.05	1.05	1.05	..
11	2.45	1.0	.85	1.0	2.15	1.3	1.45	1.2	1.05	1.05	1.05	..
12	2.45	1.0	.85	1.0	2.0	1.3	1.45	1.2	1.05	1.05	1.05	..
13	2.45	2.0	.85	.95	2.0	1.3	1.4	1.2	1.05	1.05	1.05	..
14	2.9	3.75	.85	.95	2.0	1.25	1.4	1.2	1.05	1.05	1.05	..
15	3.7	3.75	.85	.95	1.95	1.25	1.3	1.15	1.05	1.05	1.05	..
16	3.35	3.75	.85	.95	1.85	1.35	1.25	1.15	1.05	1.05	1.05	..
17	3.3	3.5	.85	.95	1.75	1.35	1.25	1.15	1.05	1.05	1.05	..
18	3.2	3.5	.85	.95	1.75	1.45	1.25	1.15	1.05	1.05	1.05	..
19	3.2	3.5	.85	.95	1.75	1.45	1.25	1.15	1.05	1.05	1.05	..
20	.85	3.4	.85	.95	1.75	1.45	1.55	1.15	1.05	1.05	1.05	..
21	.85	3.35	.85	.95	1.75	1.45	1.45	1.15	1.05	1.05	1.05	..
22	.9	2.85	.85	1.0	1.75	1.45	1.35	1.1	1.05	1.05	1.05	..
23	.85	.85	.85	1.0	1.6	1.45	1.3	1.1	1.05	1.05	1.05	..
24	.95	.85	.85	1.05	1.5	1.45	1.3	1.1	1.05	1.05	1.05	..
25	1.0	.85	.85	1.1	1.5	1.45	1.25	1.1	1.05	1.05	1.05	..
26	.85	.85	.85	1.15	1.45	1.45	1.25	1.1	1.05	1.05	1.05	..
27	.85	.85	.85	1.15	1.4	1.45	1.25	1.1	1.05	1.05	1.05	..
28	.85	.85	.9	1.15	1.4	1.4	1.25	1.1	1.05	1.05	1.05	..
29	.85	.....	.9	1.15	1.35	1.4	1.25	1.1	1.05	1.05	1.05	..
30	.65	.....	.95	1.15	1.35	1.35	1.25	1.1	1.05	1.05	1.05	..
31	.85	.....	.95	.....	1.3	.....	1.25	1.1	.....	1.05	.....	..

NOTE.—Ice conditions January 1 to February 22, inclusive.

lation rating table for Spearfish Creek near Spearfish, S. Dak., from February 23 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.90	61	1.40	164	1.80	265	2.20	397
1.00	80	1.50	187	1.90	295	2.30	435
1.10	100	1.60	211	2.00	327	2.40	475
1.20	121	1.70	237	2.10	361	2.50	517
1.30	142						

The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during 1904–5, and is not well defined.

Estimated monthly discharge of Spearfish Creek near Spearfish, S. Dak., for 1905

[Drainage area, 230 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
February 23–28	52	52	52.0	619	0.226	0.050
March	70	52	53.7	3,302	.233	.269
April	110	61	79.1	4,707	.344	.384
May	496	110	231	14,200	1.00	1.15
June	176	132	153	9,104	.665	.742
July	517	132	185	11,380	.804	.927
August	132	100	113	6,948	.491	.566
September	100	90	91.3	5,433	.397	.443
October	90	90	90.0	5,534	.391	.451
November	90	80	88.0	5,236	.383	.427
The period				66,460		

NOTE.—No estimate for ice period.

REDWATER CANAL AT MINNESELA, S. DAK.

This station was established May 7, 1904. It is located on the bridge across the canal in the town of Minnesela, 4 miles from Belle Fourche, S. Dak., in sec. 24, T. 8 N., R. 2 E.

The channel is straight for 200 feet above and below the station. The bed is composed of soft mud covered with water grass, which in the late summer lessens the flow of the canal considerably. There is but one channel at all stages, and the current is medium. Water is turned off the canal from about October 20 to May 20, and observations are discontinued during that period. Gage heights range from 1.5 to 3.5 feet.

Discharge measurements are made from the bridge to which the gage is attached. The initial point for soundings is a spike in the bridge over the edge of the canal at the right bank, downstream side.

The gage, which was read twice each day during 1905 by Robert H. Mitchell, is a vertical staff fastened to the bridge. The bench mark is a spike in a tree on the left bank about 100 feet from the gage; elevation, 4.00 feet above the zero of the gage.

A description of this station, with gage height and discharge data is contained in Water-Supply Paper No. 130 of the United States Geological Survey, pages 178-179.

Discharge measurements of Redwater canal at Minnesela, S. Dak., for 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis charg
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-*
May 30	H. D. Comstock	16	25	1.52	2.51	
June 9	do	16	31	1.94	2.95	
July 12	do	16	23	1.07	2.40	
July 31	do	16	10	.10	1.60	

[a] Estimated.

Daily gage height, in feet, of Redwater canal at Minnesela, S. Dak., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Day.	May.	June.	July.	Aug.	Sept.	
1		2.5	2.1	3.0	3.0	2.7	17		0.95	2.5	3.0	2.9	
2		2.65	2.05	3.0	3.0	2.7	18		1.0	2.2	3.0	2.9	
3		2.8	2.0	3.0	3.0	2.7	19		1.3	1.9	3.0	2.95	
4		2.8	2.0	3.0	3.0	2.7	20		2.0	1.9	3.0	2.9	
5		2.8	2.0	3.0	3.0	2.7	21		2.0	1.9	3.0	2.9	
6		2.8	2.0	3.0	3.0	2.7	22		2.0	2.0	3.0	2.75	
7		2.8	2.0	3.2	3.0	2.5	23		2.4	2.5	3.0	2.6	
8		2.85	2.0	3.4	3.0	2.5	24		2.55	2.5	3.0	2.6	
9		2.95	2.05	3.4	3.0	2.5	25		2.5	2.25	3.0	2.7	
10		3.0	2.45	3.4	3.0	2.5	26		2.4	2.0	3.0	2.7	
11		3.0	2.45	3.4	3.0	2.5	27		2	2.0	3.0	2.7	
12		3.0	2.5	3.4	3.0	2.25	28		2.0	2.95	3.0	2.7	
13		3.05	2.5	3.2	3.0	2.0	29		2.0	3.1	3.0	2.7	
14		3.2	2.5	3.0	3.0	2.0	30		2.4	2.0	3.0	3.0	2.7
15		3.3	2.45	3.0	2.95	2.0	31		2.42		3.0	3.0	
16		2.0	2.5	3.0	2.9	2.0							

Daily discharge, in second-feet, of Redwater canal at Minnesela, S. Dak., 1904–5.

Day.	1904.						1905.					
	May.	June.	July.	Aug.	Sept.	Oct.	May.	June.	July.	Aug.	Sept.	Oct.
1	.....	67	30	97	24	29	.....	37	12	60	55	36
2	.....	35	35	97	24	32	.....	46	0	60	55	36
3	.....	9	28	97	24	29	.....	56	9	60	55	36
4	.....	9	44	97	29	26	.....	56	9	60	55	36
5	.....	9	60	97	29	26	.....	51	9	60	55	36
6	.....	9	64	97	29	24	.....	51	9	60	55	36
7	.....	9	64	99	46	24	.....	51	9	74	55	26
8	44	9	64	81	66	24	.....	54	9	89	55	26
9	41	4	64	97	81	18	.....	62	10	89	55	26
10	41	2	64	97	46	16	.....	65	28	89	55	26
11	47	0	64	97	37	4	.....	65	28	89	55	26
12	47	0	64	97	32	.....	.....	65	30	89	55	26
13	38	0	64	97	29	.....	.....	68	30	74	55	7
14	35	0	64	97	26	.....	.....	79	30	60	55	7
15	41	0	64	97	26	.....	.....	87	28	60	52	7
16	38	0	64	81	40	.....	.....	11	30	55	48	7
17	35	0	64	81	34	.....	.....	0	30	55	48	4
18	41	2	60	81	29	.....	.....	0	16	55	48	2
19	41	38	56	70	1	.....	.....	0	6	55	52	2
20	41	47	50	59	1	.....	.....	11	6	55	48	2
21	35	47	60	59	0	.....	.....	11	6	55	48	2
22	53	47	74	59	0	.....	.....	11	9	55	39	1
23	67	44	74	59	5	.....	.....	28	30	55	31	0
24	67	41	67	59	6	.....	.....	36	30	55	31	.....
25	74	47	70	70	6	.....	.....	33	18	55	36	.....
26	74	47	67	81	9	.....	.....	25	9	55	36	.....
27	81	30	32	81	9	.....	.....	25	9	55	36	.....
28	67	30	35	81	10	.....	.....	9	56	55	36	.....
29	67	30	89	77	12	.....	.....	9	67	55	36	.....
30	67	30	89	73	20	.....	32	9	60	55	36	.....
31	67	.....	81	73	.....	.....	33	.....	60	55	.....	.....

NOTE.—The daily discharge is based on a series of parallel curves, each covering a short period of time.

Estimated monthly discharge of Redwater canal at Minnesela, S. Dak., 1904–5.

Month.	Discharge in second-feet.			Total acre-f
	Maximum.	Minimum.	Mean.	
1904.				
May 8–31	81	35	52.0	
June	67	0	21.4	
July	89	28	60.3	
August	97	59	83.3	
September	81	0	24.3	
October 1–11	32	4	22.9	
The period				1
1905.				
June	87	0	37.0	
July	67	6	22.6	
August	89	55	63.0	
September	55	31	47.7	
October 1–23	36	0	18.0	
The period				1

WHITE RIVER DRAINAGE BASIN.

WHITE RIVER AT INTERIOR, S. DAK.

White River rises in the northwestern part of Nebraska, flows northeastward, then ward, and empties into the Missouri in southeastern Lyman County, S. Dak. The gr part of its course lies through the Bad Lands, which consist of white-clay cliffs and br bottoms. There is little timber along the river and almost no land under cultivation. main floods occur in March, May, June, and July.

The gaging station was established June 24, 1904. It is located at the ford about fourth mile northeast of Interior, S. Dak., in T. 3 S., R. 18 E.

The channel is curved for about 1,000 feet above and 500 feet below the station. banks are high and clean and overflow only at extreme high water. The bed is comp of sand and gravel and is shifting. There is but one channel at all stages except the lowest, when there may be several channels. The slope at the station is about 3 fee mile. The current is sluggish at low water. Gage heights range from 1 foot to 16 The stream is frozen from about December 20 to March 10, and observations are di tinued during that period.

Discharge measurements are made by wading at the gage. The initial point for so ings is the top of the inclined gage.

The gage was read once each day during 1905 by George L. Johnson. Originall inclined gage in two sections was attached to posts set in the bed and left bank o stream. This gage and bench mark No. 1 were destroyed July 3, 1905. Records referred to a temporary mark until August 31, 1905, when a new gage was established is inclined, consists of three sections, and is graduated to read direct. It is fastened post driven in the left bank, and a stump to a post driven near, both about 200 feet a the old gage, and to a post driven in the middle of the channel. Bench mark No. 1 spike driven in a blaze on a tree 50 feet above the old gage on the left bank; elevation, feet above the zero of the gage. Bench mark No. 2 is a 60-penny spike in a 30-inch blazed, 100 feet northeast of the new high-water gage; elevation, 14.83 feet above the of the gage.

A description of this station, with gage-height and discharge data, is contained in W Supply Paper No. 130 of the United States Geological Survey, pages 181–183.

Discharge measurements of White River at Interior, S. Dak., in 1905.

...e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	H. D. Comstock	112	60	1.47	1.80	88
.....	...do	133	214	2.24	3.06	479
31.....	...do	105	59	1.49	2.03	88

Daily gage height, in feet, of White River at Interior, S. Dak., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	.....	3.0	1.9	2.8	3.75	.....	2.05	1.8	2.1
.....	.....	4.1	2.5	5.5	9.2	5.05	1.95	1.8	2.5
.....	.....	4.9	4.2	5.3	13.5	4.35	1.95	1.9	2.0
.....	.....	3.0	7.5	4.2	.....	4.05	2.3	1.9	2.0
.....	.....	2.5	6.5	2.0	.....	3.35	2.25	1.9	2.0
.....	.....	2.4	6.3	1.8	.....	3.05	2.15	1.9	2.0
.....	.....	2.2	4.8	1.8	.....	2.85	1.95	1.9	2.0
.....	.....	2.25	3.4	1.9	4.95	2.35	1.85	1.9	2.0
.....	.....	2.2	2.9	1.8	4.65	2.25	1.85	1.9	2.0
.....	.....	2.2	2.8	1.65	4.35	2.25	1.9	1.9	2.0
.....	.....	2.2	2.5	1.6	5.0	2.15	1.9	1.95	2.0
.....	.....	2.0	2.4	1.8	4.95	5.2	1.9	1.95	2.0
.....	.....	2.6	2.3	1.6	4.25	5.15	1.9	1.95	2.0
.....	.....	2.6	2.1	1.9	3.85	4.35	1.9	2.0	2.0
.....	.....	3.5	2.1	2.3	3.05	4.45	1.9	2.0	2.0
.....	.....	3.5	2.0	3.0	2.95	4.1	1.9	2.0	2.0
.....	.....	3.0	1.9	4.2	2.75	3.95	1.9	1.95	2.0
.....	.....	2.8	1.9	16.0	2.45	3.85	1.9	1.9	2.0
.....	2.8	2.6	1.8	6.0	2.35	3.65	1.9	2.0	2.0
.....	2.7	2.5	1.8	6.0	4.05	3.35	1.9	2.3	2.0
.....	2.7	2.4	1.8	5.2	2.95	3.05	1.9	2.2	2.0
.....	2.65	2.4	1.7	5.0	5.05	2.65	1.9	2.2	2.0
.....	2.65	2.3	1.9	4.7	3.35	2.45	1.9	2.2	2.0
.....	2.7	2.0	1.8	4.5	3.15	2.25	1.9	2.1	2.0
.....	2.7	2.0	1.9	4.3	2.85	2.25	1.9	2.1	2.0
.....	2.9	1.9	1.9	4.2	2.75	2.15	1.8	2.1	2.0
.....	2.95	1.9	1.9	3.0	2.65	2.15	1.8	2.1	2.1
.....	2.9	1.9	1.9	3.45	4.25	2.15	1.8	2.2	2.2
.....	2.95	1.9	5.6	4.05	.....	2.15	1.7	2.2	2.2
.....	2.2	1.9	3.3	3.95	.....	2.15	1.7	2.2	2.2
.....	2.1	.....	3.0	.....	.....	2.15	.....	2.1	.....

—Water over top of gage July 4–7 and July 29 to August 1.

NIOBRARA RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

...ara River rises in the mountains of eastern Wyoming, flows eastward through the ...n portion of Nebraska, and empties into the Missouri in Knox County at the city ...rara. Its drainage basin is narrow in the upper portion, but broadens considerably ...r the mouth; it comprises about 9,012 square miles.

...ghout the middle portion of its course the river runs in a deep canyon, varying in ...om 100 to 300 feet. Beyond the canyon are high, rolling, and sometimes broken

table-lands, traversed here and there by deep canyons cut by the numerous tributaries of the river. Large areas of rolling sand hills border these table-lands in portions of Sheridan, Cherry, Brown, Rock, and Holt counties. Formerly these sand hills were very shifting, but within recent years they have become overgrown with a comparatively luxuriant growth of grasses which serves to render them more permanent.

The soil throughout the region is generally sandy, and there is little or no timber except for a few pines on the bluffs of the canyons of the main stream and its tributaries. Lying generally in an east-west direction between the sand hills are extensive hay flats, and on the firmer soils considerable farming is done, for though the annual rainfall is small, most of it occurs during the growing months, and comparatively large quantities of corn, wheat, melons, etc., are produced. By far the greater part of the drainage area of the stream, however, is given over to range land for cattle. The Niobrara Forest Reserve, which lies between Niobrara and Snake rivers, consists almost wholly of sand hills, except along the borders.

Precipitation within the basin varies from 15 to 18 inches in the upper portion, from 18 to 21 inches in the middle portion, and from 21 to 24 inches in the lower portion. Evaporation is 6, 5, and 4½ feet in the upper, middle, and lower portions, respectively. Sixty-nine per cent of the precipitation falls during April, May, June, July, and August, and about one-half of the remainder is snowfall.

The river is not subject to periodic rises of any extent, owing to the fact that the sand hills which form so large a portion of its drainage area act as storage reservoirs for the rain and snow, which are afterwards fed to the stream in the form of spring water, thus equalizing the flow and making the constancy of the discharge almost phenomenal.

In the southern part of Cherry County are numerous small lakes which form the headwaters of tributaries. These lakes are subject to slight periodic rises which lag considerably behind the periods of greatest rainfall, and on one of them, Red Deer Lake, a gaging station was established in order that this characteristic might be studied.

The principal tributaries are Verdigris, Keya Paha, and Snake rivers, and Minnechaduza Creek. The drainage area of the Snake is similar in nearly all respects to that of the western part of the Niobrara.

The water resources of the Niobrara are at present almost wholly undeveloped, irrigation being limited to the low, narrow flood plains in the bottoms of the canyons. On Minnechaduza Creek, at Valentine, an artificial lake has been formed by a dam, and a power plant has been installed for lighting and for furnishing the city with water. On the lower portion of the Niobrara a number of mills are in operation, receiving their power from small tributaries. On Snake River possibilities for power development are phenomenal, but long transmission lines would be required to make it of practical value.

Detailed information in regard to this drainage basin is contained in the following reports:

A reconnaissance of Niobrara River and its tributaries, by J. C. Stevens: Third Ann. Rept. U. S. Reel. Service (2d ed.), 1905, pp. 338 et seq.

Preliminary report on the geology and water resources of Nebraska west of the 103d meridian, by N. H. Darton: Nineteenth Ann. Rept. U. S. Geol. Survey, pt. 4, 1898, pp. 719 et seq.

NIOBRARA RIVER NEAR VALENTINE, NEBR.

This station was established July 22, 1897, and was known as the Fort Niobrara station. June 26, 1901, it was moved about 3 miles farther upstream to the Borman Bridge, in sec. 4, T. 34, R. 28, about 3 miles southeast of the town of Valentine.

At the gaging station the stream lies on an easy curve. The banks are heavily wooded and high and are not liable to overflow. The bed is composed of cobblestones and sand, which at times of high water scours out, leaving the rocks comparatively bare. The shifting of the sand renders the development of a good rating curve a difficult matter, and the method of applying a rating table indirectly has been largely used. There are no natural obstructions in the stream and the current is always swift. The range of gage heights seldom exceeds 2 feet except in the case of a "cloudburst," when the very lowest bottom

been flooded for a few hours. The river seldom freezes completely over, and 04 and 1905 records of gage heights were obtained throughout the winter.
ge measurements are made from a single-span steel bridge. The initial point ings is the zero mark on the upstream hand rail in line with the west face of the

ge, which is observed by John Borman, is of the wire and weight type, and is bout 1,000 feet upstream from the bridge on the left bank. The length of the 90 feet. The gage is referred to bench marks as follows: (1) The head of a nail the stump of a boxelder tree—one of a clump of four—just east of Mr. Borman's evation above the zero of the gage, 17.26 feet. (2) A 2 by 6 inch pine head block, the gate of Borman's fence rests when closed; elevation above the zero of the gage, t. As a check, the elevation of the water surface at the time of making the nents is referred to the bottom of the upstream end of the second floor beam from f the bridge on the left bank.
ation in regard to this station is contained in the following publications of the tates Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

ion: Ann 20, iv, p 255; WS 66, p 25; 84, p 18; 99, p 46; 130, pp 183–184.
ge: Ann 18, iv, p 193; 20, iv, pp 255, 301; WS 66, p 25; 84, p 18; 99, p 46; 130, p 184.
ge, daily WS 130, p 185.
re, monthly: WS 84, p 20; 99, p 48; 130, p 186.
ghts: WS 66, p 25; 84, p 19; 99, p 47; 130, p 184.
ables: WS 84, p 19; 99, p 47.

Discharge measurements of Niobrara River near Valentine, Nebr., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	E. L. Thomas	117	220	4.13	1.64	910
.....	H. C. Gardner	120	253	4.51	1.85	1,142
.....	.....do	120	227	4.89	1.80	1,111
.....	G. W. Bates	120	203	4.06	1.50	818
.....	H. C. Gardner	105	204	4.78	1.65	978
.....	.....do	120	228	3.65	1.55	834
15..	G. W. Bates	115	207	4.28	1.65	886
27...	.....do	110	208	4.53	1.75	940

Daily gage height, in feet, of Niobrara River near Valentine, Nebr., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	2.15	2.78	2.3	1.65	1.53	1.76	1.76	1.88	1.48	1.45	1.57	
2	1.9	2.8	2.15	1.8	1.55	1.75	3.15	1.82	1.5	1.43	1.6	
3	2.15	3.35	2.0	1.78	1.62	1.86	2.8	1.75	1.45	1.47	1.56	
4	2.03	3.6	1.78	1.8	2.03	1.68	2 4	1.7	1.44	1.45	1.59	
5	2.05	3.77	1.75	1.71	1.8	1.65	2.32	1.67	1.48	1.5	1.62	
6	2.02	3.9	1.8	1.65	1.75	1.5	2.15	1.68	1.45	1.52	1.57	
7	2.0	3.85	1.78	1.6	1.68	1.48	2.05	1.65	1.49	1.49	1.59	
8	2.03	3.7	1.75	1.62	1.65	1.5	1.82	1.67	1.53	1.55	1.61	
9	1.9	3.6	1.7	1.6	1.6	1.55	1.93	1.66	1.55	1.57	1.59	
10	2.07	3.67	1.64	1.82	1.63	1.75	1.85	1.58	1.5	1.53	1.58	
11	2.45	3.95	1.62	1.68	1.7	1.7	1.8	1.55	1.47	1.45	1.61	
12	3.2	4.0	1.6	1.57	1.63	1.55	1.68	1.55	1.45	1.44	1.6	
13	3.6	3.9	1.64	1.55	1.55	1.58	1.65	1.58	1.42	1.45	1.59	
14	3.15	3.9	1.60	1.62	1.64	1.56	1.6	1.72	1 5	1.5	1.63	
15	3.9	3.65	1.63	1.7	1.6	1.55	1.62	1.64	1.49	1.55	1.64	
16	3.85	3.6	1.67	1.66	1.65	1.6	1.65	1.6	1.52	1.48	1.6	
17	3.15	3.35	1.66	1.65	1.53	1.57	1.68	1.55	1.47	1.48	1.63	
18	3.2	3.55	1.73	1.6	1.5	1.93	1.57	1.53	1.55	1.49	1.65	
19	2.77	3.38	1.7	1.57	1.53	1.75	2.48	1.51	1.48	1.55	1.65	
20	2.5	3.16	1.62	1.55	1.52	1.95	2.15	1.48	1.45	1.5	1.66	
21	2.2	3.1	1.65	1.53	1.52	1.6	1.95	1.5	1.45	1.52	1.67	
22	2.38	3.18	1.63	1.54	1.53	1.77	1.76	1.53	1.47	1.5	1.7	
23	2.33	2.85	1.7	1.53	1.5	1.63	1.75	1.5	1.5	1.48	1.72	
24	2.45	2.74	1.68	1.67	1.48	1.78	1.6	1.5	1,45	1.49	1.74	
25	2.83	2.6	1.65	1.68	1.52	2.04	1.73	1.45	1.42	1.5	1.73	
26	2.25	3.0	1.6	1.73	1.53	1.8	1.62	1.42	1.5	1.5	1.7	
27	2.33	2.7	1.62	1.6	1.78	2.5	1.6	1.45	1.52	1.53	1.75	
28	2.57	2.48	1.75	1.6	1.65	1.95	1.6	1.43	1.45	1.54	1.77	
29	2.85	.....	1.65	1.55	2.2	1.72	1 61	1.49	1.5	1.58	1.56	
30	1.9	.....	1.58	1.5	1.95	1.85	1.87	1.45	1.47	1.56	1.35	
31	2.0	.....	1.61	.....	1.85	.....	1.8	1.48	.....	1.59	.....	

aily discharge, in second-feet, of Niobrara River near Valentine, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	.....	905	740	1,005	1,065	1,375	760	725	820
.....	.....	1,125	760	990	3,420	1,270	785	705	855
.....	.....	1,095	835	1,160	2,845	1,150	730	745	805
.....	.....	1,125	1,490	895	2,165	1,070	720	725	835
.....	1,070	985	1,090	860	2,044	1,025	760	780	870
.....	1,150	900	1,015	695	1,755	1,040	730	800	810
.....	1,120	835	910	680	1,600	990	770	765	830
.....	1,070	860	870	700	1,210	1,015	815	835	850
.....	995	835	810	750	1,400	1,005	840	855	825
.....	910	1,150	845	1,005	1,280	990	780	810	815
.....	880	935	935	935	1,200	850	750	725	845
.....	860	795	845	750	1,020	850	730	715	830
.....	910	775	750	785	980	885	700	725	815
.....	860	855	855	765	915	1,085	780	775	865
.....	895	960	805	755	950	930	770	834	880
.....	950	905	865	815	1,000	905	805	750	825
.....	935	890	730	780	1,055	845	750	750	860
.....	1,035	825	700	1,310	900	820	840	760	880
.....	990	790	725	1,020	2,420	795	760	825	880
.....	880	770	715	1,345	1,855	765	725	765	890
.....	915	745	715	820	1,515	785	725	785	900
.....	890	755	725	1,055	1,190	820	750	760	940
.....	985	745	695	860	1,170	785	780	740	965
.....	955	910	675	1,075	940	785	725	750	995
.....	910	925	710	1,515	1,135	730	700	755	980
.....	845	995	720	1,110	965	700	780	755	935
.....	870	820	1,035	2,300	935	730	800	785	1,005
.....	1,055	820	855	1,365	935	710	725	795	1,030
.....	910	760	1,740	990	1,005	770	780	840	760
.....	820	710	1,310	1,200	1,365	730	745	815	575
.....	855	.....	1,140	.....	1,240	760	.....	845	.....

.—The daily discharge was obtained by the indirect method. Owing to the uncertainty of ice ons and lack of high-water measurements no estimate was made January 1 to March 4 nor De- 1–31.

Estimated monthly discharge of Niobrara River near Valentine, Nebr., for 1905.

[Drainage area, 6,070 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
3–31.....	1,150	820	945	50,610	0.156	0.157
.....	1,150	710	883	52,540	.145	.162
.....	1,740	675	890	54,720	.147	.170
.....	2,300	680	1,010	60,100	.166	.185
.....	3,420	900	1,402	86,200	.231	.266
.....	1,375	700	902	55,460	.149	.172
ber.....	840	700	760	45,220	.125	.140
r.....	855	705	774	47,590	.128	.148
ber.....	1,030	575	866	51,530	.143	.160
he period.....	.....	.....	.....	504,000	.....	.....

RED DEER LAKE NEAR WOODLAKE, NEBR.

This station was established August 12, 1904. The lake is located in secs. 16, 17, 20, and 21, T. 30 N., R. 27 W., about 16 miles south of Woodlake post-office and about 30 miles south of Valentine, Nebr., and is representative of the numerous lakes of this region. The station was established for the purpose of determining the cause and amount of the periodic rise of these lakes, which, according to local authorities, is often several feet, beginning in April or May.

The lake covers about 1 square mile of surface and is merely a valley or flat in the sand hills, filled with water. The depth varies from 1 foot to 15 feet, the average being probably about 8 feet. The bed is entirely of sand, and the margin is thickly grown with rushes, etc.

The gage was observed by J. S. Brosius. It consists of a staff fastened to a post at the end of the boat landing 200 yards south of Cochran's ranch house near the east end of the lake. The bench mark is a group of three spikes driven horizontally near the base of a cottonwood tree 12 inches in diameter, located 40 feet south and 20 feet east of the southwest corner post of the large windmill tower just west of Cochran's house; elevation above the zero of the gage, 9.61 feet.

The station was discontinued October 31, 1905.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper of the United States Geological Survey No. 130, pages 186-187.

Daily gage height, in feet, of Red Deer Lake near Woodlake, Nebr., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1				4.39			4.75			
2									4.3	
3		4.46	4.36			4.55				
5					4.49			4.71		
6	4.4									
7				4.43						4.16
8							4.82			
9									4.32	
10			4.29			4.62				
11		4.5								
12								4.59		
13					4.52					
14	4.41						4.72			4.23
15				4.4						
16									4.3	
17		4.49	4.35			4.6				
19								4.5		
20	4.4				4.41					
21				4.36						
22							4.68			4.24
23									4.3	
24						4.7				
25		4.44	4.3							
26								4.4		
27					4.52					
28	4.41									
29				4.4			4.65			4.3
30									4.2	

MISCELLANEOUS MEASUREMENTS.

discharge measurements made in Niobrara River drainage basin, Nebraska, in 1905.

Stream.	Locality.	Area of section.	Mean velocity.	Discharge.
		Sq. ft.	*Ft. per sec.*	*Sec.-ft.*
South Fork of Eagle Creek ..	Sec. 9, T. 30 N., R. 13 W.....	15	1.66	25
North Fork of Eagle Creek ..	Sec. 26, T. 31 N., R. 13 W.....	4.3	1.88	8.1
Beaver Creek.....	Sec. 19, T. 32 N., R. 16 W.....	18	1.12	20
Keya Paha River.....	.....	58	2.34	136

PLATTE RIVER DRAINAGE BASIN.

GENERAL FEATURES.

only with regard to the extent of area drained, the Platte is the most impor-
y of the Missouri. It is formed by two forks, North Platte and South Platte,
spectively, in northern and in central Colorado and unite a little southwest
of Nebraska. Its entire drainage basin comprises about 90,000 square miles,
ound numbers 36,000 square miles belong to the North Platte and 24,000 to
ıtte. The lower course of the river is fairly well settled, but farther west the
more scattered.
ıience the description of the basin is divided, and the North Platte, South
'latte River proper are considered separately.

NORTH PLATTE RIVER.

DESCRIPTION OF BASIN.

of the North Platte is in North Park, Colorado, or rather in the mountains
to elevations from 4,000 to 5,000 feet above its general level, hem it in on all
the steep slopes of these mountains numerous small streams descend, unite
rge creeks, and flow outward to the center of the basin. The two which may
rm the real head of the North Platte are Grizzly and Little Grizzly creeks.
ıe park the river is joined by four large tributaries, Roaring Fork and North
e west and Michigan and Canadian creeks from the east. Leaving the park,
kes a bold curve northward into Wyoming, but near Caspar, on the north
'aspar Range, it turns abruptly to the east and southeast, maintaining the
to its point of junction with the South Platte in central Nebraska.
rth Park the topographic features are diversified, including every degree of
ɔn the snow-capped peaks of the Park and Medicine Bow ranges to the level
along the lower portion of the stream. Dense forests occur in the mountain
eaviest being those on the east slope of the Park and the west slope of the
v ranges. At an elevation of 8,500 feet above sea level the forests give way
prairie country, which, with the exception of the dense growth of willows
r bottoms, is entirely free from forests of any description. The soil, composed
gravelly and sandy loam on the mesas and of sandy and black loam along
toms, is in general fertile, but climatic conditions are such that the agricul-
s are limited to wild hay, roots, and a few of the hardier grains.
hward course through Wyoming the stream receives many tributaries, the
e on the east contributing its drainage through Douglas, French, and Brush
the northeast slope of the Sierra Madre is drained by Beaver, Big Cow, and
and Grand Encampment River. Medicine Bow and Sweetwater rivers are

added to the North Platte between Saratoga and Caspar, beyond which the only important tributary is the Laramie, which enters at old Fort Laramie.

The greater part of the region below Saratoga is a rolling, undulating prairie. The soil throughout Wyoming is a sandy loam of sufficient depth to produce meadows of rich grasses, even up to elevations of 7,000 feet. At lower elevations the soil becomes more friable and deeper.

Throughout its course in western Nebraska the valley of the North Platte is 10 to 15 miles wide. The present floor, consisting of sediments deposited in a former greater valley, is bordered by terraces and table-lands scarred by numerous tributaries and arroyos. The stream is broad and shallow, with a flood plain from 1 mile to 4 miles wide.

The character of the river bed at the Big Bend and at the Seminole Mountains, in Wyoming, seems to indicate a considerable underflow. A part of this is collected at the Big Bend, and probably the entire amount is brought to the surface as the river passes through the Seminole Range. In its lower course the bed of the stream is of fine quicksand, underlain at a depth of from 15 to 20 feet by a hard layer which seems to be clay.

Agricultural efforts in the basin of the North Platte have been largely confined to the valleys of the tributaries. No important work has been undertaken except on the Laramie and this on the plains before that stream has passed through the Laramie Mountains and received the drainage of their eastern slope. On tributaries of the North Platte, however, the available lands are all occupied over the entire basin.

The stream is subject to periodic floods, which reach their maximum at the mouth some time during the latter part of June and are caused by the melting snow on the high ranges in which the headwater streams rise. The river runs lowest in winter, when it freezes thickly. High water prevails from the middle of April to the middle of July, when the river runs bank full.

In the mountain districts the precipitation, which is mostly in the form of snow during the winter and spring months, varies from 7 to 15 inches, the average being about 11 inches. Throughout the lower portion of the basin the precipitation is from 15 to 18 inches and the evaporation from water surface is from 5 to 6 feet.

Information in regard to the basin is contained in the Annual Reports of the Reclamation Service and in the Annual Reports of the United States Geological Survey, as follows: Thirteenth, pt. 3, pp. 78–82; Nineteenth, pt. 4, pp. 304–306, 772–774; Twenty-second, pt. 4, pp. 310–311.

GRIZZLY CREEK AT HEBRON, COLO.

Grizzly Creek rises on the northern slope of the Continental Divide in North Park, Colorado, flows northward, and unites with Little Grizzly Creek to form the North Platte. Its principal tributaries are Colorado, Arapahoe, and Buffalo creeks.

The gaging station was established May 13, 1904. It is located at the highway bridge at Hebron, Colo., about 2 miles above the junction with Little Grizzly Creek and 10 miles from Walden, Colo., in sec. 29, T. 8 N., R. 80 W.

The channel is straight for about 50 feet above and below the station. The banks are about 3 feet high and neither is liable to overflow. The current is at a right angle to the gaging section and is uniform and medium at all stages. The bed of the stream is composed of gravel, with cobblestones and mud on the left side. There is but one channel at all stages. Gage heights have a range of about 3 feet. The stream is frozen over during the greater part of the winter season, making gage readings impossible.

At very high stages discharge measurements are made from the downstream side of the two-span bridge to which the gage is attached. The initial point for soundings is the face of the left abutment at the zero marked on the hand rail. At low and ordinary stages discharge measurements are made by wading near the gage.

The gage, which is read once each day by James [illegible] from 2 to 9.5 feet spiked to the left downstream [illegible] 2-foot mark rests on the bed of the stream. The [illegible]

(1) A 30-penny nail driven vertically into the [illegible]

abutment of the bridge; elevation, 9.76 feet above the zero of the gage. (2) A iron bench-mark post 4 feet east of the fence on the west side of the road, 60 of the river bank; elevation, 8.82 feet above the zero of the gage. The elevation sea level is approximately 8,100 feet.

ption of this station, with gage-height and discharge data, is contained in Water-per No. 131 of the United States Geological Survey, pages 53–55.

Discharge measurements of Grizzly Creek at Hebron, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	W. A. Lamb.....	54	173	1.73	5.70	299
.....	....do.....	53	76	2.71	.....	206
.....	....do.....	30	29	2.28	4.35	66
.....	....do.....	17	8.8	1.28	3.62	11
.....	....do.....	15	5.8	.86	3.50	5
.....	....do.....	8	1.7	.29	3.26	.5
&.	....do.....	9	2.5	.84	3.40	2.1

easurements made at different sections.

Daily gage height, in feet, of Grizzly Creek at Hebron, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	.....	5.35	5.55	3.9	3.5	3.3	3.3
.....	.....	5.65	5.7	3.9	3.55	3.3	3.2
.....	.....	5.55	5.75	3.98	3.6	3.45	3.45
.....	.....	5.3	5.88	3.98	3.58	3.45	3.45
.....	.....	5.92	5.9	3.98	3.6	3.45	3.45
.....	.....	4.95	5.92	3.9	3.55	3.45	3.45
.....	.....	4.7	5.75	4.0	3.55	3.45	3.45
.....	.....	4.45	5.55	4.1	3.5	3.45	3.45
.....	.....	5.95	5.8	4.18	3.5	3.45	3.45
.....	.....	5.25	5.78	4.15	3.5	3.4	3.45
.....	.....	4.9	5.95	4.22	3.5	3.4	3.45
.....	.....	4.5	5.82	4.48	3.5	3.35	3.45
.....	.....	4.55	5.7	4.5	3.5	3.35	3.45
.....	.....	4.9	5.45	4.4	3.5	3.3	3.45
.....	.....	4.8	5.75	4.38	3.5	3.3	3.45
.....	.....	5.12	5.6	4.45	3.4	3.3	3.48
.....	4.2	5.52	5.68	4.45	3.4	3.3	3.5
.....	4.25	5.35	5.45	4.25	3.3	3.3	3.5
.....	4.68	5.65	5.05	3.85	3.3	3.3	3.5
.....	4.38	5.35	5.0	3.5	3.32	3.3	3.5
.....	4.3	5.7	5.1	3.5	3.3	3.3	3.5
.....	4.32	5.95	5.0	3.48	3.25	3.3	3.5
.....	4.3	5.7	4.95	3.48	3.25	3.3	3.5
.....	4.2	5.7	4.85	3.48	3.2	3.3	3.5
.....	4.28	5.6	4.45	3.5	3.2	3.3	3.45
.....	4.5	5.55	4.38	3.4	3.2	3.3	3.45
.....	5.55	5.5	4.2	3.45	3.2	3.3	3.45
.....	5.12	5.6	4.05	3.5	3.2	3.35	3.45
.....	4.8	5.4	3.95	3.5	3.3	3.35	3.45
.....	5.15	5.55	3.9	3.5	3.5	3.35	3.48
.....	.....	5.5	.....	3.5	3.3	.....	3.48

Station rating table for Grizzly Creek at Hebron, Colo., from April 17 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-feet.*
3.20	1	4.00	35	4.80	131	5.60	281
3.30	2	4.10	43	4.90	147	5.70	303
3.40	4	4.20	52	5.00	164	5.80	325
3.50	7	4.30	62	5.10	182	5.90	347
3.60	11	4.40	74	5.20	200	6.00	370
3.70	16	4.50	87	5.30	219		
3.80	22	4.60	101	5.40	239		
3.90	28	4.70	116	5.50	260		

The above table is applicable only for open-channel conditions. It is based on 13 discharge measurements made during 1904–5, and is well defined between gage heights 3.3 and 5.6 feet.

Estimated monthly discharge of Grizzly Creek at Hebron, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April (14 days)	270	52	104	2,8
May	358	80	227	13,9
June	358	28	226	13,4
July	87	4	34.0	2,0
August	11	1	5.1	3
September	6	2	3.1	1
October	7	1	5.7	3
The period				33,2

LITTLE GRIZZLY CREEK AT HEBRON, COLO.

Little Grizzly Creek rises on the eastern slope of the Park Range in North Park, Colorad flows eastward and unites with Grizzly Creek to form the North Platte.

The gaging station was established June 3, 1904. It is located at the wagon bridge o James Hill's ranch, one-half mile southwest of Hebron, Colo., and one-fourth mile west c the road from Hebron to Spicer, in sec. 32, T. 8 N., R. 80 W.

The channel is straight for 150 feet above and below the station. Both banks are low an liable to overflow. The bed of the stream is composed of gravel and small cobblestones an is firm. There is but one channel at all stages, broken by the middle pier of the bridge, an the current has a medium and uniform velocity. Gage heights have a range of about 3 feet The creek is frozen over during the greater part of the winter.

High-water discharge measurements are made from the downstream side of the two-spa bridge to which the gage is attached. The initial point for soundings is on the east edge c the pier at the left bank of the stream. Low-water measurements are made by wading 3 feet above the gage.

The gage is read once each day by John Peterson, who lives one-half mile distant. It is staff nailed vertically to the northwest corner of the center pier of the bridge. The gage referred to bench marks as follows: (1) A nail driven into the north end of the second log the west abutment; elevation above the zero of the gage, 5.90 feet. (2) A nail driven in the north end of a log in the right abutment; elevation above the zero of the gage, 6.37 fe (3) Top of regulation iron bench-mark post 80 feet east and 20 feet north of the gage; e vation above the zero of the gage, 6.79 feet. The elevation is approximately 8,100 f above sea level.

iption of this station, with gage-height and discharge data, is contained in Water-
ıper No. 131 of the United States Geological Survey, pages 55–57.

Discharge measurements of Little Grizzly Creek at Hebron, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
....	W. A. Lamb	38	87	1.95	4.15	170
....	.....do	44	142	3.00	5.45	426
....	.....do	38	117	2.74	4.75	321
....	.....do	22	34	1.41	3.20	48
....	.....do	28	14	1.14	2.83	16
....	.....do	18	21	.33	2.68	6.9
26..	.....do	18	54	.87	2.68	4.7

easurements made at different sections.

Daily gage height, in feet, of Little Grizzly Creek at Hebron, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	.....	4.25	4.55	3.95	2.9	2.6	2.8
.....	.....	4.25	5.05	4.88	2.95	2.6	2.85
.....	.....	4.25	5.15	4.88	2.82	2.6	2.82
.....	.....	3.9	5.48	4.9	2.88	2.6	2.8
.....	.....	3.88	5.45	4.95	2.92	2.6	2.8
.....	.....	3.82	5.6	5.0	2.85	2.6	2.8
.....	.....	3.65	5.45	4.88	2.85	2.6	2.8
.....	.....	4.05	5.45	4.85	2.85	2.6	2.8
.....	.....	3.4	5.55	4.82	2.85	2.6	2.8
.....	.....	4.1	5.55	4.78	2.85	2.62	2.8
.....	.....	3.5	5.92	4.78	2.85	2.65	2.8
.....	.....	3.75	5.65	4.1	2.85	2.65	2.8
.....	.....	3.6	5.45	3.3	2.85	2.65	2.8
.....	.....	3.65	5.45	3.45	2.75	2.65	2.8
.....	.....	3.65	5.4	3.55	2.65	2.65	2.82
.....	.....	3.7	5.5	3.45	2.62	2.65	2.85
.....	3.25	4.15	5.6	3.2	2.5	2.65	2.9
.....	3.08	4.65	5.4	3.32	2.55	2.65	2.9
.....	3.12	3.9	5.42	3.15	2.6	2.65	2.9
.....	3.38	4.0	5.42	2.9	2.68	2.65	2.9
.....	3.52	4.0	5.35	3.1	2.65	2.65	2.9
.....	2.78	4.4	5.35	3.12	2.65	2.65	2.9
.....	3.15	4.95	4.85	3.1	2.65	2.65	2.9
.....	3.25	4.95	4.55	2.95	2.82	2.67	2.9
.....	3.2	4.95	4.48	3.0	2.7	2.68	2.9
.....	3.2	4.95	4.5	2.9	2.7	2.75	2.9
.....	3.3	4.7	4.6	2.9	2.8	2.75	2.9
.....	3.88	4.7	4.65	3.0	2.7	2.75	2.9
.....	3.85	4.55	4.55	3.0	2.6	2.78	2.9
.....	3.98	4.35	4.52	3.1	2.6	2.82	3.0
.....	.....	4.8	.....	3.0	2.6	.....	3.0

Station rating table for Little Grizzly Creek at Hebron, Colo., from April 17 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.50	1	3.40	71	4.30	196	5.20	396
2.60	4	3.50	83	4.40	215	5.30	422
2.70	9	3.60	95	4.50	235	5.40	448
2.80	15	3.70	108	4.60	255	5.50	475
2.90	22	3.80	121	4.70	276	5.60	502
3.00	30	3.90	134	4.80	298	5.70	530
3.10	39	4.00	148	4.90	321	5.80	558
3.20	49	4.10	163	5.00	345	5.90	586
3.30	60	4.20	179	5.10	370	6.00	615

The above table is applicable only for open-channel conditions. It is based on 13 discharge measurements made during 1904-5 and is fairly well defined between gage heights 2.7 feet and 5 feet.

Estimated monthly discharge of Little Grizzly Creek at Hebron, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April 17-30	145	14	68.6	1,905
May	333	71	182	11,190
June	502	231	401	23,800
July	345	22	138	8,485
August	26	1	12.3	756
September	16	4	6.9	411
October	30	15	19.2	1,181
The period				47,700

ROARING FORK OF NORTH PLATTE RIVER NEAR HEBRON, COLO.

Roaring Fork rises in the Park Range at the crest of the Continental Divide, flows eastward, and enters the North Platte about 3 miles below the junction of Grizzly and Little Grizzly creeks. The basin is very rugged, a large portion extending above the timber line and reaching an altitude of 13,000 feet above sea level. The headwaters consist of a number of branches, occupying small valleys separated by high, precipitous hills, and deriving their water supply from banks of perpetual snow and ice. The valley of the main stream is narrow, varying in width from a few hundred feet to half a mile, with bluffs on each side bounded by high, rolling mesa lands. The soil on the first bottom consists of black sandy loam and is generally very fertile. That on the mesas is of gravel and sandy loam. The forests about the headwaters comprise a heavy growth of white pine and spruce timber, with an abundance of underbrush and shrubbery. The bottom and first mesa land near the mouth are under cultivation, hay being practically the only crop.

The gaging station was established May 14, 1904. It is located at the highway bridge about 2 miles above J. E. Mallan's ranch house, 4 miles west of Hebron, Colo., and one-half mile above the mouth of the fork, in sec. 11, T. 8 N., R. 81 W.

The channel is straight for about 100 feet above and 50 feet below the station. The banks, which are about 5 feet high above and 3 feet high below the bridge, are lined with willows, and are not liable to overflow except at extremely high stages. The bed of the stream is composed of coarse gravel and cobblestones and is uniform and stable. There is but

nel at all stages and the current is uniform and moderately swift. During an season gage heights have a range of about 3 feet. In the winter months the s obstructed by ice, and gage readings are unreliable.

ge measurements are made from the single-span bridge to which the gage is The initial point for soundings is the south face of the north abutment, and is by a spike driven in the bridge floor. Low-water measurements are made by ear the gage.

ge was read twice each day during 1905 by Mrs. Stella Bohn, who lives 200 yards ne station. A standard chain gage was established June 14, 1904. It is located st side of the bridge, 18 feet from the south face of the north abutment. The the chain is 7.70 feet. The gage is referred to bench marks as follows: (1) The spike driven horizontally into the east end of the second timber from the top of n abutment; elevation above gage datum, 2.86 feet. The head of a nail driven into the north end of the gage rod is 2.55 feet above this bench mark. (2) Top on rod 16 inches long, 1 inch square at the lower end and tapering to a point at r end, set on a bowlder sunk in the ground by the side of the lane fence, 50 feet of the north pier of the bridge; elevation above gage datum, 7.14 feet. The above sea level is approximately 8,100 feet.

ription of this station, with gage-height and discharge data, is contained in Water-aper No. 131 of the United States Geological Survey, pages 55–59.

measurements of Roaring Fork of North Platte River near Hebron, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	W. A. Lamb.....	24	22	1.77	1.63	39
.....	.....do.....	41	81	4.58	3.59	371
.....	.....do.....	41	75	4.44	3.30	333
.....	.....do.....	34	38	2.34	2.02	89
.....	.....do.....	25	24	1.71	1.70	41
.....	.....do.....	20	17	1.29	1.48	22
r 25..	.....do.....	15	7.4	1.07	1.25	7.9

Measurements made at different sections.

Daily gage height, in feet, of Roaring Fork of North Platte River near Hebron, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		1.35	2.35	2.55	1.88	1.35	1.2
2			2.65	2.48	1.85	1.3	1.2
3			3.02	2.4	1.85	1.3	1.2
4		1.4	3.65	2.25	1.78	1.3	1.2
5			3.82	2.02	1.72	1.3	1.2
6		1.4	3.45	1.98	1.7	1.3	1.2
7			3.35	2.02	1.72	1.3	1.2
8		1.35	3.7	2.08	1.7	1.3	1.2
9			3.92	2.08	1.7	1.25	1.2
10		1.35	3.7	1.95	1.65	1.25	1.2
11			3.38	1.9	1.65	1.25	1.2
12			3.28	1.92	1.65	1.25	1.2
13		1.35	3.38	2.15	1.62	1.25	1.2
14			3.42	2.0	1.58	1.2	1.2
15		1.1	3.52	2.08	1.52	1.2	1.2
16			3.65	2.15	1.5	1.2	1.2
17	1.5		3.52	2.1	1.5	1.2	1.2
18		1.62	3.45	1.98	1.5	1.25	1.2
19		1.72	3.3	1.98	1.45	1.25	1.2
20	1.6	1.65	3.22	1.92	1.45	1.25	1.2
21		1.8	3.3	1.98	1.45	1.25	1.2
22	1.4	1.9	3.3	1.9	1.45	1.25	1.4
23		2.05	3.55	1.88	1.48	1.25	1.4
24	1.3	2.08	3.8	1.8	1.4	1.25	1.4
25		2.1	3.25	1.8	1.4	1.25	1.4
26	1.2	2.08	3.25	1.8	1.35	1.25	1.4
27		2.12	3.12	1.9	1.35	1.2	1.4
28		2.12	2.98	1.82	1.35	1.2	1.4
29	1.4	2.08	2.8	1.95	1.35	1.2	1.4
30		1.98	2.65	1.92	1.35	1.25	1.4
31		2.02		1.92	1.35		1.4

Station rating table for Roaring Fork of North Platte River near Hebron, Colo., from April 17 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.10	4	1.90	71	2.70	205	3.40	342
1.20	7	2.00	85	2.80	224	3.50	362
1.30	11	2.10	100	2.90	243	3.60	383
1.40	17	2.20	116	3.00	262	3.70	404
1.50	24	2.30	133	3.10	282	3.80	425
1.60	33	2.40	150	3.20	302	3.90	446
1.70	44	2.50	168	3.30	322	4.00	467
1.80	57	2.60	186				

The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during 1905, and is not well defined.

imated monthly discharge of Roaring Fork of North Platte River near Hebron, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
il 17-30 a	33	7	17.6	489
	103	4	43.6	2,681
	450	142	327	19,460
	177	57	89.5	5,503
ust	68	14	31.5	1,937
ember	14	7	9.2	547
ober	23	7	13.0	799
The period				31,420

a Missing gage heights interpolated.

NORTH FORK OF NORTH PLATTE RIVER AT HIGHO, COLO.

orth Fork of North Platte River rises in the Park Range near the Colorado-Wyoming , flows southeastward to a point about 2 miles west of Higho, Colo., and thence east- d into the North Platte at a point about 4 miles below the mouth of Roaring Fork. stream flows through a narrow valley separated from the open prairie land of North k by a high bluff, which slopes up gradually from the east side and then descends rather uptly on the west to the river bottoms. The basin is mountainous in character, and ch of it is covered with a heavy forest, consisting of several varieties of white pine and uce and much quaking aspen and underbrush. The tributaries head among the snow ks in the highest portions of the Park Range, and after descending through narrow, cipitous canyons, enter the more or less rolling country at the foot of the range. The l along the river bottoms consists of a black sandy loam and is well adapted to the rais- of hay.

The gaging station was established May 14, 1904. It is located at the footbridge at gho post-office, 7 miles northwest of Hebron and 12 miles west of Walden, Colo., in 9 N., R. 81 W.

The channel is straight for about 150 feet above and 50 feet below the station, and the rent is medium. The right bank is about 3 feet high above and for a short distance low the gage, beyond which point it rises to a height of about 10 feet; the left bank is rer than the right and consists of a low bar, covered with willows and sloping gradually t from the stream. There is but one channel at low-water stages, but at high stages a ond channel begins about 100 yards above the bridge, flows through the low sand bar a distance of 50 yards from the left end of the bridge, and enters the main stream 150 rds below. The stream does not overflow the banks of either channel, except at very h stages, when the low land between the two channels may be submerged. The bed the stream is composed of gravel and small cobblestones, and is free from vegetation l permanent. The current is swift at high stages and medium during ordinary stages. gh-water measurements are somewhat affected by eddying currents and backwater sed by the pier at the left end of the bridge. Gage heights have a range of 1.5 feet. adings are discontinued during the winter months on account of ice forming around the ge rod.

Discharge measurements are made at high water from the single-span footbridge to which gage is attached. The initial point for soundings is a nail driven into the walk-log at left end of the bridge. Low-water measurements are made by wading near the bridge. The gage was read twice each day during 1905 by Mrs. Esther Bergquist, who lives near station. It consists of a vertical staff spiked to the southwest face of the left abut- nt on the downstream side. The gage is referred to bench marks as follows: (1) A nail

driven into the top of the east end of the bottom log of the north abutment; elevation above the zero of the gage, 1.76 feet. (2) A point on the foundation stone under the northeast corner of the house of Charles Bergquist, marked "B.M.U.S.G.S."; elevation above the zero of the gage, 12.42 feet. The elevation above sea level is approximately 8,025 feet.

A description of this station, with gage height and discharge data, is contained in Water-Supply Paper No. 131 of the United States Geological Survey, pages 23-25.

Discharge measurements of North Fork of North Platte River at Higho, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 18	W. A. Lamb	28	38	1.45	1.50	55
June 18	do	29	57	3.26	2.05	185
June 24	do	29	59	3.19	2.05	188
July 15	do	34	56	2.12	1.85	119
August 8	do	34	44	1.57	1.70	69
August 23	do	30	35	1.37	1.50	48
September 25	do	26	20	.65	1.09	13

NOTE.—Measurements made at different sections.

Daily gage height, in feet, of North Fork of North Platte River at Higho, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	1.42	1.95	1.7	1.95	1.8	1.45	1.15
2	1.48	1.95	1.75	1.95	1.8	1.45	1.15
3	1.45	1.8	1.8	1.9	1.75	1.4	1.2
4	1.38	1.55	2.01	1.8	1.7	1.4	1.2
5	1.32	1.62	2.05	1.75	1.74	1.4	1.2
6	1.38	1.65	1.91	1.72	1.71	1.48	1.2
7	1.6	1.62	1.92	1.78	1.7	1.5	1.25
8	1.7	1.62	2.3	2.0	1.68	1.42	1.3
9	1.82	1.7	2.18	1.92	1.68	1.4	1.3
10	1.78	1.52	2.15	1.75	1.72	1.4	1.28
11	1.65	1.32	2.05	1.7	1.7	1.4	1.25
12	1.52	1.25	2.0	1.78	1.78	1.4	1.25
13	1.6	1.22	1.98	1.72	1.7	1.4	1.3
14	1.65	1.2	2.02	1.75	1.6	1.32	1.3
15	1.65	1.22	2.02	1.78	1.6	1.28	1.3
16	1.6	1.22	2.1	1.72	1.62	1.2	1.35
17	1.6	1.3	2.05	1.72	1.6	1.18	1.3
18	1.65	1.5	2.25	1.7	1.55	1.1	1.3
19	1.78	1.52	2.25	1.64	1.5	1.1	1.22
20	1.72	1.55	1.98	1.75	1.5	1.1	1.2
21	1.52	1.52	1 92	2.0	1.48	1.1	1.25
22	1.65	1 6	1.95	2.0	1.47	1.1	1.22
23	1.75	1.65	2.05	1.85	1.47	1.38	1.2
24	1.7	1.72	2.05	1.85	1.47	1.38	1.2
25	1.62	1.65	2.02	1.82	1.5	1.1	1.15
26	1.68	1.67	2.02	1.8	1.47	1.1	1.18
27	1.95	1.68	1.98	1.88	1.47	1.1	
28	2.0	1.58					
29	1.9	1.					
30	1.9						
31							

tion rating table for North Fork of North Platte River at Higho, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-feet.*
1.10	15	1.50	50	1.80	100	2.10	195
1.20	22	1.60	64	1.90	126	2.20	235
1.30	30	1.70	80	2.00	158	2.30	280
1.40	39						

The above table is applicable only for open-channel conditions. It is based on 15 discharge measurements made during 1904–5, and is well defined between gage heights 1.4 feet and 2.2 feet.

Estimated monthly discharge of North Fork of North Platte River at Higho, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	158	32	76.3	4,540
May	142	22	61.9	3,806
June	280	80	162	9,640
July	158	70	107	6,579
August	100	44	65.8	4,046
September	50	15	29.6	1,761
October	34	18	25.3	1,556
The period				31,930

NORTH PLATTE RIVER NEAR HEBRON, COLO.

This station was established May 13, 1904. It is located at a highway bridge below the junction of Grizzly and Little Grizzly creeks, about 4 miles northwest of Hebron, Colo., in T. 9 N., R. 80 W.

The bridge lies in a curve of about 150 feet radius. The banks are about 5 feet high, lined with willows, and not liable to overflow. The bed of the stream is composed of gravel, sand, and small cobblestones, and is uniform, permanent, and free from vegetation. There is but one channel at all stages. The current is very sluggish at low water, but medium at high stages. Gage heights have a range of about 4 feet. Discharge measurements are affected by dead water, by backwater caused by the wooden piers of the bridge, and by driftwood which collects at the upper side of the bridge. Gage readings are impracticable during the winter months on account of the formation of ice around the gage rod.

Discharge measurements are made from the downstream side of the three-span bridge to which the gage is attached. The initial point for soundings is the inner face of the left abutment, marked zero.

The gage is read each day by J. E. Mallon, who lives one-half mile distant. It consists of a vertical staff fastened to the northeast corner of the first pier from the left bank. The gage is referred to bench marks as follows: (1) A nail driven flush with the top of the cap timber on the west side of the crib pier to which the gage is fastened, just across the pier from the gage; elevation, 9.44 feet above the zero of the gage. (2) A cross cut on a ledge of rock in the cliff on the left bank of the river about 50 feet north of the west end of the bridge, marked "B.M.;" elevation, 17.80 feet above the zero of the gage. The elevation above sea level is about 8,025 feet.

A description of this station with gage height and discharge data is contained in Water-Supply Paper No. 131 of the United States Geological Survey, pages 20–23.

Discharge measurements of North Platte River near Hebron, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 18	W. A. Lamb	83	284	1.38	5.30	392
June 17	do	84	390	2.53	6.60	986
June 25	do	88	365	1.94	5.95	708
July 14	do	66	68	2.29	4.45	156
August 8	do	58	32	1.91	3.90	61
August 24	do	32	27	.89	3.50	24
September 25	do	28	21	1.05	3.31	22

NOTE.—Measurements made at different sections.

Daily gage height, in feet, of North Platte River near Hebron, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		5.7	6.0	5.25	4.3	3.45	3.35
2		5.8	6.4	5.25	4.2	3.45	3.35
3		5.5	6.6	5.15	4.2	3.45	3.35
4		5.2	7.0	4.9	4.15	3.45	3.4
5		5.0	7.45	4.75	4.1	3.4	3.4
6		5.0	7.15	4.65	4.05	3.45	3.4
7		4.9	6.8	4.6	4.0	3.45	3.4
8		5.0	6.9	4.65	3.9	3.5	3.4
9	4.6	5.2	7.4	4.5	3.9	3.35	3.4
10	4.6	5.4	7.55	4.4	3.9	3.35	3.4
11	5.0	5.1	7.0	4.4	3.9	3.35	3.4
12	4.5	4.95	6.9	4.35	3.9	3.35	3.45
13	4.5	4.9	6.7	4.55	3.9	3.3	3.45
14	4.6	4.9	6.8	4.4	3.85	3.3	3.45
15	4.6	4.85	6.8	4.45	3.8	3.3	3.45
16	4.55	5.0	6.8	4.5	3.7	3.3	3.45
17	4.5	5.2	6.7	4.4	3.7	3.3	3.45
18	4.6	5.3	6.6	4.35	3.6	3.3	3.45
19	4.65	5.6	6.4	4.3	3.6	3.35	3.45
20	4.6	5.7	6.2	4.35	3.6	3.35	3.5
21	4.55	5.75	6.1	4.45	3.6	3.35	3.5
22	4.55	6.0	6.0	4.25	3.55	3.35	3.55
23	4.65	6.1	6.1	4.15	3.55	3.35	3.6
24	4.9	6.3	6.2	4.15	3.5	3.35	3.6
25	4.5	6.55	6.0	4.15	3.45	3.35	3.65
26	4.75	6.05	5.9	4.15	3.45	3.35	3.7
27	5.1	5.95	5.75	4.15	3.45	3.35	3.7
28	5.0	5.7	5.6	4.3	3.45	3.35	3.7
29	5.2	5.6	5.45	4.2	3.45	3.35	3.7
30	5.4	5.6	5.3	4.2	3.45	3.35	3.7
31		5.8		4.3	3.45		3.7

ion rating table for North Platte River near Hebron, Colo., from April 9 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec. ft.*	*Feet.*	*Sec. ft.*	*Feet.*	*Sec. ft.*	*Feet.*	*Sec. ft.*
3.30	15	4.20	110	5.10	315	6.00	705
3.40	20	4.30	125	5.20	355	6.20	800
3.50	25	4.40	140	5.30	395	6.40	900
3.60	35	4.50	160	5.40	435	6.60	1,000
3.70	45	4.60	180	5.50	480	6.80	1,100
3.80	55	4.70	200	5.60	525	7.00	1,200
3.90	65	4.80	225	5.70	570	7.20	1,310
4.00	80	4.90	250	5.80	615	7.40	1,420
4.10	95	5.00	280	5.90	660	7.60	1,530

The above table is applicable only for open-channel conditions. It is based on seven discharge measements made during 1905, and is well de ined between gage heights 3.3 feet and 6.5 feet.

Estimated monthly discharge of North Platte River near Hebron, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
pril 9–30	435	160	215	9,382
ay	975	238	479	29,450
ne	1,502	395	950	56,530
ly	375	102	164	10,080
ugust	125	22	54.3	3,339
eptember	25	15	18.5	1,101
ctober	45	18	27.4	1,685
The period				111,600

NORTH PLATTE RIVER NEAR COWDREY, COLO.

This station was established May 10, 1904. It is located at the wagon bridge about 2 miles northwest of Cowdrey, Colo., in T. 10 N., R. 80 W.

The channel is straight for 600 feet above and 900 feet below the station. Both banks are high and clean and are not subject to overflow. The bed of the stream is composed of coarse gravel and small cobblestones and is stable and uniform. There is but one channel at either high or low water. The current has a medium velocity at high and ordinary stages, but is sluggish at low stages. At the station the fall of the river is 4.2 feet per mile. During the winter months ice forms at the gage rod and gage readings are impracticable.

Discharge measurements are made by means of a car, cable, and tagged wire, one-fourth mile below the highway bridge. Soundings are marked on the tagged wire at 5-foot intervals, the initial point being the zero of the tagged wire near the left bank. At extreme low stages measurements are made by wading at convenient points near the bridge.

The gage, which was read twice each day during 1905 by C. M. Hendrickson, consists of a vertical staff spiked to the northeast corner of the first crib pier from the west end of the highway bridge above the cable. The foot marks are numbered from 2 to 12 feet, the 2-foot mark resting on the bed of the stream. The gage is referred to bench marks as follows: (1) The top of a 30-penny nail driven flush with the top of the cap timber on the north end of the right abutment of the bridge; elevation, 13.22 feet above gage datum. (2) An iron wagon skein set in the right bank 10 feet north of the bridge, the top of the hub being 2 inches above the surface of the ground, the base resting on a stone 1 foot below the surface;

a witness stake is beside the bench-mark post; elevation of bench mark, 10.89 feet above gage datum. The elevation above sea level is about 7,860 feet.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 131 of the United States Geological Survey, pages 25–28.

Discharge measurements of North Platte River near Cowdrey, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 19	W. A. Lamb	110	292	1.80	8.17	[illegible]
May 23	do	110	327	2.34	8.44	[illegible]
June 19	do	109	385	2.87	8.91	1,[illegible]
June 23	do	109	383	2.77	8.80	1,[illegible]
July 17	do	103	226	1.26	7.84	[illegible]
August 7	do	95	176	.84	7.59	[illegible]
Augus t22[a]	do	56	49	1.57	7.40	[illegible]
September 22[a]	do	26	29	.76	7.15	[illegible]

[a] Made at different section.

Daily gage height, in feet, of North Platte River near Cowdrey, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	8.6	8.1	8.4	8.42	7.75	7.45	7.[illegible]
2	8.65	8.2	8.7	8.25	7.75	7.42	7.[illegible]
3	8.6	8.15	8.85	8.2	7.7	7.4	7.[illegible]
4	8.6	7.95	9.05	8.18	7.72	7.45	7.[illegible]
5	8.5	7.8	9.3	8.12	7.72	7.5	7.[illegible]
6	7.85	7.7	9.5	7.98	7.72	7.75	7.[illegible]
7	7.85	7.7	9.25	7.88	7.7	7.82	7.[illegible]
8	7.8	7.7	9.0	7.82	7.7	7.75	7.[illegible]
9	7.95	7.8	9.6	7.75	7.72	7.65	7.[illegible]
10	8.05	7.95	9.6	7.82	7.7	7.65	7.[illegible]
11	7.65	8.05	9.45	7.75	7.7	7.5	7.[illegible]
12	7.6	7.95	9.2	7.75	7.7	7.45	7.[illegible]
13	7.65	7.85	9.05	7.75	7.65	7.45	7.[illegible]
14	7.55	7.85	9.1	7.75	7.6	7.05	7.3
15	7.75	7.85	9.05	7.78	7.6	7.08	7.3
16	7.6	7.85	9.05	7.75	7.6	7.12	7.3
17	7.7	7.95	9.15	8.02	7.55	7.2	7.3
18	7.6	8.1	8.85	7.8	7.55	7.2	7.3
19	7.7	8.15	8.9	7.8	7.55	7.2	7.3
20	7.7	8.2	8.75	7.8	7.5	7.2	7.3
21	7.6	8.3	8.65	7.85	7.52	7.2	7.3
22	7.55	8.35	8.7	7.9	7.48	7.18	7.3
23	7.65	8.45	8.7	7.92	7.45	7.15	7.3
24	7.7	8.55	8.7	7.75	7.45	7.15	7.3
25	7.6	8.65	8.7	7.7	7.55	7.15	7.3
26	7.7	8.55	8.7	7.7	7.5	7.18	7.3
27	7.8	8.55	8.65	7.75	7.5	7.2	7.3
28	7.95	8.45	8.68	7.72	7.5	7.22	7.3
29	8.0	8.45	8.52	7.72	7.48	7.35	7.3
30	8.05	8.5	8.52	7.72	7.4	7.35	7.35
31	.....	8.3	.....	7.72	7.4	.....	7.35

tion rating table for North Platte River near Cowdrey, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
7.10	12	7.80	270	8.50	793	9.20	1,523
7.20	27	7.90	334	8.60	880	9.30	1,650
7.30	47	8.00	398	8.70	974	9.40	1,781
7.40	75	8.10	466	8.80	1,070	9.50	1,916
7.50	108	8.20	540.	8.90	1,172	9.60	2,056
7.60	154	8.30	622	9.00	1,282		
7.70	208	8.40	707	9.10	1,400		

The above table is applicable only for open-channel conditions. It is based on nineteen discharge measurements made during 1904–5 and is well defined between gage heights 7.5 feet and 9 feet. It has been extended beyond these limits, being based on one measurement at 7.2 feet. Above 7.5 feet the table is the same as for 1904.

Estimated monthly discharge of North Platte River near Cowdrey, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	926	130	345	20,530
May	926	208	505	31,050
June	2,056	707	1,246	74,150
July	724	208	316	19,430
August	238	75	156	9,592
September	283	5	76.7	4,564
October	91	47	58.3	3,585
The period				162,900

CANADIAN RIVER AT COWDREY, COLO.

Canadian River rises in North Park, Colorado, among the highest peaks of the Medicine Bow Range, flows northwestward, and enters the North Platte about 1 mile below the mouth of Michigan Creek. The upper part of the drainage basin is exceedingly mountainous and the small tributaries find their way through canyons to the valley below. In its lower course the stream traverses a narrow valley which it has worn in the lake beds of the park and which extends some distance into the foothill region. This valley differs from the other river valleys of the park in the more uniform slope and regular shape of its sides, in the character of the mesa lands on the right, and in the sandy nature of its soil. The mesa on the right contains numerous sand dunes and in some places near the foothills extensive deposits of sand and coarse, disintegrated granite. The soil of the river bottom is principally a sandy loam. Hay is the only crop raised. The storage or diversion of the water of this stream is impracticable.

The gaging station was established May 10, 1904. It is located at the highway bridge one-half mile east of Cowdrey, Colo., in sec. 7, T. 10 N., R. 79 W.

The channel is straight for 150 feet above and 40 feet below the station. Each bank is about 2 feet high and is clean and well sodded; the left overflows during extreme high water. The bed of the stream is composed of sand and silt, with a few stones from the riprap at the west end of the bridge, and is shifting. As the changes occur at irregular intervals it is a difficult matter to obtain a good rating curve. There is but one channel at all stages, broken by four pile bents of the bridge, and the current has a medium velocity. The ordinary range of gage heights is about 1.6 feet. Gage readings are impracticable during the winter months on account of the formation of ice around the gage rod.

At all normal stages discharge measurements are made by wading a short distance above the pile bridge to which the gage is attached. At exceedingly high stages measurements are made from the bridge, the downstream guard rail of which is marked at 2-foot intervals. The initial point for soundings is a 20-penny nail driven into the floor of the bridge over the face of the left abutment on the downstream side.

The gage, which was read twice each day during 1905 by C. M. Hendrickson, consists of a vertical staff graduated from 2 to 8 feet, attached to the west face of the first pile from the left bank on the downstream side of the bridge. The 2-foot mark rests on the bed of the stream. The gage is referred to bench marks as follows: (1) A 30-penny nail driven flush with the top of the cap timber above the gage rod; elevation, 9.80 feet. (2) A 30-penny nail driven horizontally into the north face of a telephone pole 60 feet south of the left end of the bridge, 3 feet above the ground; elevation, 9.80 feet. (3) A regulation iron bench-mark post 3 feet south of the fence on the north side of the road, 40 feet west of the gage rod; elevation, 8.02 feet. Elevations of bench marks are above the datum of the gage. The elevation above sea level is about 7,860 feet.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 131 of the United States Geological Survey, pages 64–66.

Discharge measurements of Canadian River at Cowdrey, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 20	W. A. Lamb	34	56	1.41	4.85	79
June 20	do	35	76	2.23	5.10	125
June 23	do	53	65	1.95	5.05	127
July 17	do	28	26	1.58	4.47	41
August 7	do	31	25	1.36	4.43	34
August 22	do	15	13	1.23	4.10	16
September 22	do	14	9	1.11	4.05	10

NOTE.—Measurements made at different sections.

Daily gage height, in feet, of Canadian River at Cowdrey, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	5.5	4.8	4.9	4.68	4.55	4.05	4.2	4.35
.....	5.6	4.9	5.05	4.65	4.45	4.05	4.2	.....
.....	5.6	4.8	5.25	5.35	4.45	4.05	4.2	.....
.....	5.75	4.7	5.6	5.15	4.45	4.02	4.2	.....
.....	5.9	4.6	5.85	4.85	4.45	4.0	4.2	.....
.....	5.8	4.5	5.9	4.7	4.45	4.1	4.2	.....
.....	5.8	4.5	5.75	4.55	4.35	4.25	4.25	.....
.....	5.75	4.4	5.8	4.4	4.3	4.18	4.25	.....
.....	5.9	4.5	5.85	4.45	4.3	4.15	4.25	.....
.....	5.9	4.55	6.15	4.48	4.3	4.15	4.25	.....
.....	6.0	4.6	5.95	4.45	4.35	4.15	4.25	.....
.....	5.7	4.6	5.6	4.45	4.4	4.15	4.25	.....
.....	5.5	4.5	5.55	4.45	4.4	4.12	4.28	.....
.....	5.25	4.4	5.65	4.5	4.4	4.1	4.35	.....
.....	5.35	4.4	5.6	4.5	4.35	4.1	4.35	.....
.....	5.05	4.4	5.6	4.5	4.35	4.1	4.35	.....
.....	4.9	4.4	5.6	4.48	4.25	4.1	4.35	.....
.....	4.65	4.7	5.3	4.48	4.1	4.1	4.32	.....
.....	4.8	4.8	5.25	4.48	4.1	4.1	4.3	.....
.....	4.7	4.9	5.1	4.45	4.1	4.05	4.3	.....
.....	4.7	4.9	4.95	4.42	4.15	4.05	4.3	.....
.....	4.75	4.9	4.95	4.42	4.1	4.08	4.3	.....
.....	5.65	4.9	4.95	4.4	4.08	4.1	4.3	.....
.....	4.65	4.9	4.98	4.25	4.02	4.1	4.3	.....
.....	4.4	5.0	5.0	4.15	3.95	4.1	4.3	.....
.....	4.6	5.0	4.92	4.2	3.85	4.05	4.3	.....
.....	4.7	4.95	4.88	4.25	3.88	4.05	4.3	.....
.....	4.9	4.9	4.85	4.25	3.95	4.05	4.3	.....
.....	4.85	5.05	4.8	4.25	3.98	4.22	4.35	.....
.....	4.75	5.1	4.7	4.4	4.05	4.22	4.35	.....
.....	.....	4.95	.....	4.42	4.02	.....	4.35	.....

ation rating table for Canadian River at Cowdrey, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
3.80	1	4.50	40	5.10	130	5.70	350
3.90	3	4.60	50	5.20	155	5.80	400
4.00	6	4.70	60	5.30	185	5.90	450
4.10	10	4.80	75	5.40	220	6.00	510
4.20	15	4.90	90	5.50	260	6.10	570
4.30	22	5.00	110	5.60	300	6.20	630
4.40	30						

The above table is applicable only for open-channel conditions. It is based on 15 discharge measurements made during 1904–5, and is well defined between gage heights 4 feet and 5.5 feet. It has been ended beyond these limits, being only approximate above 5.5 feet.

Estimated monthly discharge of Canadian River at Cowdrey, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	510	30	218	12,970
May	130	30	69.4	4,267
June	600	60	225	13,390
July	202	12	44.4	2,730
August	45	2	19.3	1,187
September	18	6	10.3	613
October	26	15	20.8	1,279
The period				37,086

MICHIGAN CREEK NEAR WALDEN, COLO.

Michigan Creek, the largest tributary of the North Platte in North Park from the east side, rises in the Rabbit Ears and Medicine Bow ranges, flows northwestward, and enters the main stream at a point 3 miles northwest of Cowdrey, Colo. The basin is rugged and mountainous, comprising the highest portion of the Medicine Bow Range in Colorado. The small tributaries of the creek extend far back into the range and interlace with tributaries of Grand and Cache la Poudre rivers. These small streams unite and emerge from the high mountainous areas into the more or less broken and rolling slopes and foothills which border the level prairie land of the park itself. The lower portion of the stream flows through a narrow valley, varying in width from one-fourth mile to 1 mile, bordered on either side by long bench-like ridges and rolling prairie land. The soil along the stream bottom is a black sandy loam and is very fertile, but on account of the great altitude practically the only crop grown is hay. The headwaters of the stream are well protected by heavy forests of white pine and spruce timber and a dense growth of quaking aspen and underbrush.

Illinois Creek, which joins Michigan Creek 2 miles below Walden, is the principal tributary stream. Its headwaters drain a low portion of the Rabbit Ears Range and its flow during the early part of the summer is large.

Water is being diverted from the headwaters of Michigan Creek to the Cache la Poudre on the eastern slope of the Rocky Mountains at a point known as Cameron Pass.

Two gaging stations were maintained on Michigan Creek during 1905, the first near Walden, the second at Cowdrey.

The Walden station was established May 9, 1904. It is located at the highway bridge 1½ miles north of Walden, Colo., in sec. 21, T. 9 N., R. 79 W., and is about 1 mile above the mouth of Illinois Creek.

The channel is straight for about 75 feet above and 50 feet below the station. The banks are about 3 feet high, are bordered with flat meadow lands, and do not overflow at this point. The bed of the stream is composed of sand and gravel and is free from vegetation and fairly permanent. There is but one channel at all stages, broken by the middle pier of the bridge. The current is swift at high stages and medium at low stages. High-water measurements are affected by backwater and eddies caused by the abutments and center pier of the bridge. Gage heights have a range of about 2 feet during an ordinary season. Gage readings in winter are impracticable owing to ice conditions.

High-water measurements are made from the downstream side of the two-span bridge to which the gage is attached. The initial point for soundings is a 30-penny nail driven into the floor at the west end of the bridge. At ordinary stages discharge measurements are made by wading a short distance above the bridge.

The gage, which was read twice each day during 1905 by H. E. Holdredge, consists of a staff graduated from 4 to 10 feet, fastened to the southwest corner of the center pier of the bridge, the 4-foot mark resting on the bed of the stream. The gage is referred to bench

arks as follows: (1) The top of a nail driven into the left abutment of the bridge on the wnstream side; elevation, 7.91 feet above gage datum. (2) The top of a 20-penny nail iven into the top of a sandstone bowlder under the cliff on the north side of the river, out 275 feet northeast of the north end of the bridge, marked "B. M. U. S. G. S.;" elation above gage datum, 15.34 feet. Elevation above sea level is about 7,975 feet.

This station was discontinued October 31, 1905.

A description of this station, with gage height and discharge data, is contained in Water-upply Paper No. 131, of the United States Geological Survey, pages 59–61.

Discharge measurements of Michigan Creek near Walden, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 19	W. A. Lamb	48	42	2.95	4.95	124
June 19	do	48	113	3.47	5.65	392
June 24	do	49	106	2.97	5.50	315
July 16	do	40	36	2.69	4.91	97
August 8	do	36	21	2.05	4.56	43
August 22	do	24	15	1.47	4.40	22
September 23	do	16	14	.71	4.32	10

NOTE.—Measurements made at different sections.

Daily gage height, in feet, of Michigan Creek near Walden, Colo., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Day.	May.	June.	July.	Aug.	Sept.	Oct.
1	.....	5.22	5.25	4.7	4.25	4.32	17	.....	5.72	4.8	4.52	4.25	4.35
2	.....	5.32	5.35	4.7	4.3	4.32	18	.....	5.68	4.78	4.48	4.25	4.35
3	.....	5.42	5.28	4.68	4.22	4.32	19	4.98	5.6	4.78	4.48	4.25	4.32
4	.....	5.48	5.25	4.62	4.22	4.3	20	5.05	5.45	4.75	4.42	4.22	4.32
5	.....	5.7	5.12	4.62	4.28	4.3	21	5.05	5.4	4.72	4.4	4.22	4.35
6	.....	5.9	5.0	4.58	4.32	4.32	22	5.1	5.42	4.7	4.4	4.2	4.38
7	.....	5.8	4.92	4.58	4.4	4.32	23	5.18	5.38	4.68	4.38	4.2	4.38
8	.....	5.82	4.9	4.48	4.38	4.32	24	5.2	5.5	4.7	4.32	4.2	4.4
9	.....	5.92	4.88	4.5	4.38	4.32	25	5.15	5.48	4.7	4.32	4.28	4.4
10	.....	6.05	4.88	4.58	4.32	4.32	26	5.08	5.42	4.68	4.35	4.28	4.4
11	.....	6.08	4.85	4.6	4.3	4.32	27	5.12	5.45	4.68	4.3	4.28	4.42
12	.....	5.85	4.8	4.65	4.25	4.32	28	5.02	5.4	4.7	4.3	4.28	4.42
13	.....	5.8	4.82	4.68	4.25	4.32	29	5.12	5.38	4.7	4.28	4.28	4.42
14	.....	5.95	4.85	4.58	4.22	4.32	30	5.1	5.3	4.7	4.28	4.3	4.42
15	.....	5.88	4.8	4.48	4.22	4.32	31	5.1	.....	4.7	4.25	.....	4.42
16	.....	5.78	4.8	4.52	4.2	4.38							

Station rating table for Michigan Creek near Walden, Colo., from May 19, to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
4.20	5	4.70	60	5.20	190	5.70	410
4.30	10	4.80	80	5.30	225	5.80	465
4.40	20	4.90	100	5.40	265	5.90	520
4.50	30	5.00	125	5.50	310	6.00	580
4.60	45	5.10	155	5.60	360	6.10	640

The above table is applicable only for open-channel conditions. It is based on fourteen measurements made during 1904–5, and is well defined between gage heights 4.3 feet and 5.8 feet.

Estimated monthly discharge of Michigan Creek near Walden, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
May (19-31)	190	120	155	[illegible]
June	628	197	377	[illegible]
July	245	57	97.5	[illegible]
August	60	8	31.2	[illegible]
September	20	5	8.9	[illegible]
October	22	10	15.1	[illegible]
The period				[illegible]

MICHIGAN CREEK[a] NEAR COWDREY, COLO.

This station was established May 9, 1904. It is located 100 feet above the wagon bridge 1½ miles west of Cowdrey, Colo., in sec. 11, T. 10 N., R. 80 W., and is below all tributaries. The channel is straight for 50 feet above and 100 feet below the station. The right bank is a gradually sloping gravel bar which extends back about 80 feet; the left bank is about 5.5 feet high and is well sodded. At high stages the stream overflows the right bank for a distance of 75 feet from the main channel. The bed is composed of gravel and is free from vegetation, uniform, and permanent. There is but one channel at all stages. In some places the current is swift and uniform; in others backwater, eddies and dead water occur. Near the bridge the channel is in poor condition, being obstructed by piles and ruined piers of the bridge. The ordinary range of gage heights is about 3 feet. The channel at the gage is almost entirely frozen over during the winter months, making gage readings impossible.

Discharge measurements are made at high stages from the downstream side of the wagon bridge. Low-water measurements are made by wading at convenient points above the bridge.

The gage, which was read twice each day during 1905 by C. M. Hendrickson, consists of an inclined staff spiked firmly to posts set into the left bank about 75 feet above the bridge. This gage was washed out during the high water of June, 1905, but was replaced in its original position and datum. The gage is referred to bench marks as follows: (1) A 30-penny nail driven into the top of the south end of the cap timber of the first pile bent at the east end of the bridge; a witness nail is driven in beside it; elevation of bench mark above the zero of the gage, 6.23 feet. (2) A standard iron-post bench mark, located 3 feet south of the fence on the south side of the road, 75 feet north of the gage rod and 50 feet west of the river bank; elevation above the zero of the gage, 6.26 feet. The elevation above sea level is about 7,870 feet.

This station was discontinued October 31, 1905.

A description of this station, with gage-height and discharge data, is contained in Water Supply Paper No. 131 of the United States Geological Survey, pages 61–64.

[a] For description of creek see p. 190.

Discharge measurements of Michigan Creek near Cowdrey, Colo., in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	W. A. Lamb.....	40	47	2.84	2.60	134
.....	.....do.....	80	130	3.09	3.65	402
.....	.....do.....	77	118	2.87	3.40	339
.....	.....do.....	40	40	2.05	2.40	82
.....	.....do.....	37	30	1.70	2.23	51
2.....	.....do.....	28	17	1.24	1.90	21
r 22..	.....do.....	20	6.6	.98	1.67	6.5

-Measurements made at different sections.

Daily gage height, in feet, of Michigan Creek near Cowdrey, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	2.5	3.0	3.4	3.2	2.45	1.7	1.8	2.0
.....	2.55	3.15	3.6	3.1	2.4	1.7	1.8	.....
.....	2.5	3.2	3.7	3.1	2.42	1.7	1.8	.....
.....	3.15	2.85	4.0	2.98	2,42	1.75	1.8	.....
.....	3.35	2.8	4.4	2.9	2.4	1.85	1.8	.....
.....	3.2	2.6	4.6	2.85	2.42	1.9	1.8	.....
.....	3.0	2.4	4.6	2.7	2.4	1.95	1.8	.....
.....	2.65	2.4	4.6	2.68	2.32	1.88	1.8	.....
.....	2.7	2.5	4.7	2.55	2.28	1.85	1.8	.....
.....	2.7	2.6	4.5	2.52	2.35	1.85	1.8	.....
.....	2.55	2.6	4.4	2.55	2.32	1.78	1.8	.....
.....	2.55	2.5	4.3	2.5	2.3	1.75	1.8	.....
.....	2.55	2.3	4.2	2.5	2.3	1.75	1.8	.....
.....	2.55	2.3	4.1	2.5	2.3	1.75	1.85	.....
.....	2.45	2.25	4.0	2.5	2.3	1.75	1.92	.....
.....	2.4	2.2	3.9	2.48	2.25	1.75	1.95	.....
.....	2.45	2.3	3.8	2.42	2.2	1.75	1.95	.....
.....	2.4	2.5	3.7	2.38	2.08	1.75	1.95	.....
.....	2.45	2.5	3.6	2.38	2.0	1.75	1.9	.....
.....	2.45	2.55	3.5	2.38	2.0	1.72	1.9	.....
.....	2.45	2.85	3.4	2.4	2.0	1.7	1.9	.....
.....	2.4	2.95	3.4	2.38	1.9	1.7	1.9	.....
.....	2.4	3.1	3.4	2.42	1.9	1.7	1.9	.....
.....	2.4	3.3	3.38	2.42	1.88	1.7	1.9	.....
.....	2.4	3.5	3.35	2.35	1.82	1.75	1.9	.....
.....	2.4	3.4	3.3	2.35	1.82	1.72	1.9	.....
.....	2.6	3.4	3.25	2.38	1.85	1.7	1.9	.....
.....	2.75	3.3	3.28	2.4	1.82	1.72	1.9	.....
.....	2.8	3.35	3.18	2.4	1.75	1.8	1.92	.....
.....	2.85	3.5	3.15	2.5	1.65	1.8	1.95	.....
.....	.....	3.35	.....	2.45	1.65	.....	1.98	.....

Gage heights estimated June 10-20, inclusive.

Station rating table for Michigan Creek near Cowdrey, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.60	4	2.40	85	3.20	270	4.00	515
1.70	7	2.50	105	3.30	300	4.10	550
1.80	12	2.60	125	3.40	330	4.20	585
1.90	20	2.70	145	3.50	360	4.30	620
2.00	30	2.80	170	3.60	390	4.40	655
2.10	40	2.90	195	3.70	420	4.50	690
2.20	55	3.00	220	3.80	450	4.60	725
2.30	70	3.10	245	3.90	480	4.70	760

The above table is applicable only for open-channel conditions. It is based on 12 discharge measurements made during 1904–5. It is well defined between gage heights 1.7 feet and 2.6 feet and fairly well defined to 3.6 feet. It has been extended beyond these limits.

Estimated monthly discharge of Michigan Creek near Cowdrey, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	315	85	133	7,914
May	360	55	186	11,440
June	760	258	466	27,730
July	270	78	122	7,501
August	95	6	50.7	3,117
September	25	7	10.9	649
October	28	12	17.5	1,076
The period				59,430

NORTH PLATTE RIVER AT SARATOGA, WYO.

This station was established June 9, 1903. It is located at a point about 100 yards below the two-span iron-truss bridge which connects East and West Saratoga, in T. 17 N., R. 84 W.

The middle pier of the bridge divides the stream into two channels with almost equal capacity in high or low water periods. The banks are high and do not overflow. The bed of the stream is composed of rock and gravel and is subject to little change. The current is swift at ordinary stages, but at extreme low water a sort of basin is formed by the backing up of the water by the riffles below, and the undercurrent is very sluggish. There are no obstructions in the river above or below the station to interfere with the natural flow, but at certain seasons each year a "tie drive" blocks the stream for a few days. The range of gage readings is about 6 feet.

Discharge measurements are made from the bridge. The initial point for soundings during high water is at the pier on the east end of the bridge and at ordinary stages is at the center pier.

The gage was read twice daily during 1905 by J. M. Sterrett, who lives about one-fourth of a mile distant. It consists of a flexible Gurley rod fastened securely to a timber spiked to the cribwork at the northeast corner of what was formerly the Saratoga Club property. The bench mark is a spike driven into a cottonwood tree 7 inches in diameter standing 30 feet northwest of the gage; elevation, 9.84 feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey.

Description. 99, p 174, 131, pp 30-31.
Discharge: 84, p 94; 99, p 175; 131, p 31.
Discharge, monthly: 99, p 176; 131, p 33.
Gage heights: 99, p 175; 131, p 32.
Rating table: 99, p 176; 131, p 33.

Discharge measurements of North Platte River at Saratoga, Wyo., for 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	A. J. Parshall	203	487	0.85	1.91	416
.....	do	221	610	1.37	2.40	835
.....	J. M. Sterrett	226	721	2.15	2.90	1,550
.....	do	232	776	2.43	3.10	1,885
.....	do	234	850	3.06	3.50	2,604
.....	do	243	936	3.53	3.80	3,308
.....	do	244	1,010	4.30	4.10	4,344
.....	do	248	1,138	4.93	4.60	5,603
.....	do	250	1,212	5.54	4.95	6,717
.....	do	251	1,304	5.72	5.25	7.455
.....	do	251	1,385	6.22	5.55	8,610
.....	do	251	1,524	7.32	6.10	11,153
.....	do	251	1,442	6.78	5.80	9,790
r 9[a]..	A. J. Parshall	105	126	2.35	1.70	296

[a] Made by wading one-fourth mile below station.

Daily gage height, in feet, of North Platte River at Saratoga, Wyo., for 1905.

ay.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.72	2.02	3.25	4.72	3.68	2.35	1.55	1.68	1.54	1.79
.....	1.72	2.05	3.45	4.92	3.58	2.32	1.52	1.68	1.68	1.87
.....	1.72	2.02	3.45	5.18	3.78	2.28	1.52	1.66	1.82	1.85
.....	1.78	2.02	3.28	5.6	3.6	2.22	1.52	1.66	1.94	1.87
.....	1.78	2.0	3.08	6.0	3.38	2.2	1.55	1.66	1.95	1.82
.....	1.85	2.1	2.95	5.68	3.22	2.15	1.62	1.62	1.89	1.7
.....	2.02	2.18	2.88	5.65	3.08	2.08	1.7	1.6	1.88	1.62
.....	1.8	2.32	2.9	5.65	3.0	1.95	1.78	1.57	1.83	1.78
.....	1.75	2.6	3.12	6.1	3.0	1.9	1.72	1.6	1.8	1.69
.....	1.75	2.72	3.2	6.05	2.95	1.9	1.66	1.58	1.7	.....
.....	1.78	2.68	3.15	5.7	2.85	1.95	1.62	1.58	1.68	.....
.....	1.8	2.45	3.05	5.58	2.7	2.18	1.56	1.62	1.66	.....
.....	1.85	2.55	2.95	5.48	2.65	2.18	1.56	1.62	1.66	.....
.....	1.85	2.68	2.9	5.3	2.6	2.08	1.51	1.7	1.68	.....
.....	1.9	2.55	2.85	5.2	2.68	1.98	1.48	1.69	1.78	.....
.....	1.92	2.48	2.9	5.18	2.6	1.92	1.44	1.68	1.8	.....
.....	1.95	2.4	3.12	5.22	2.58	1.88	1.4	1.72	1.83	.....
.....	1.98	2.38	3.5	4.95	2.52	1.82	1.42	1.72	1.86	.....
.....	2.0	2.4	3.8	4.7	2.42	1.72	1.44	1.69	1.79	.....
.....	1.98	2.55	4.05	4.55	2.6	1.7	1.46	1.68	1.64	.....
.....	2.02	2.5	4.22	4.5	2.62	1.68	1.42	1.62	1.64	.....
.....	2.05	2.42	4.52	4.5	2.6	1.62	1.41	1.72	1.6	.....
.....	2.0	2.45	4.7	4.48	2.52	1.6	1.42	1.74	1.63	.....
.....	2.02	2.5	4.82	4.5	2.38	1.6	1.4	1.78	1.7	.....
.....	1.98	2.5	4.7	4.4	2.25	1.58	1.42	1.8	1.74	.....
.....	2.02	2.48	4.7	4.32	2.2	1.55	1.44	1.82	1.7	.....
.....	2.08	2.62	4.68	4.22	2.18	1.55	1.48	1.82	1.82	.....
.....	2.02	2.88	4.7	4.1	2.18	1.55	1.47	1.81	1.78	.....
.....	1.9	3.05	4.48	3.9	2.2	1.52	1.51	1.82	1.72	.....
.....	2.02	3.05	4.38	3.8	2.2	1.5	1.59	1.82	1.53	.....
.....	2.05	.....	4.48	.....	2.25	1.5	.....	1.68	.....	.....

Gage heights estimated March 1–4.

Station rating table for North Platte River at Saratoga, Wyo., from March 1 to December 9, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.40	180	2.50	970	3.60	2,905	4.70	5,945
1.50	215	2.60	1,095	3.70	3,145	4.80	6,265
1.60	255	2.70	1,230	3.80	3,390	4.90	6,590
1.70	300	2.80	1,375	3.90	3,645	5.00	6,920
1.80	355	2.90	1,530	4.00	3,905	5.20	7,590
1.90	415	3.00	1,695	4.10	4,175	5.40	8,270
2.00	485	3.10	1,870	4.20	4,455	5.60	8,960
2.10	565	3.20	2,055	4.30	4,740	5.80	9,660
2.20	655	3.30	2,250	4.40	5,030	6.00	10,360
2.30	750	3.40	2,455	4.50	5,325		
2.40	855	3.50	2,675	4.60	5,630		

The above table is applicable only for open-channel conditions. It is based on 14 discharge measurements made during 1905, and is well defined between gage heights 1.7 feet and 6 feet.

Estimated monthly discharge of North Platte River at Saratoga, Wyo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March	549	311	425	26,1
April	1,778	485	952	56,6
May	6,330	1,452	3,329	204,7
June	10,710	3,390	7,019	417,7
July	3,341	637	1,404	86,3
August	802	215	430	26,4
September	344	180	226	13,4
October	367	243	299	18,3
November	450	227	334	19,9
December 1-9	397	264	344	6,1
The period				875,9

NORTH PLATTE RIVER AT GUERNSEY, WYO.

This station was established June 14, 1900. It was originally located at the highw bridge about half a mile northwest of Guernsey, Wyo., in sec. 35, T. 27 N., R. 66 W., b at the opening of the season of 1902 the gage rod was removed to the railroad bridge 3 feet above the first location.

The channel is straight both above and below the station. The banks are high and n liable to overflow. The bed of the stream is sandy but fairly permanent. The channel broken by two piers and six rows of piling, but no other obstructions above or below inte fere with the flow. The ordinary range of gage heights is about 7 feet. At the highw bridge the bed of the channel is more changeable, but the velocity is more uniform.

Discharge measurements are still made from the highway bridge. The initial point f soundings is on the left bank.

The gage was observed during 1905 by W. F. Peterson, who lives about 100 yards dista The 1902 gage was fastened to one of the piers of the railroad bridge and was placed 1 fo lower than the original gage had been. In the latter part of 1903 the 1902 gage was replac by a new one with its zero at the same elevation as that of the old gage. The new r was attached to the pile of the railroad bridge, which had been recently reconstructe

nch mark was a spike driven into the sleeper of the highway bridge at an eleva-
l feet above gage datum. The 1903 bench mark is a United States Geological
ument 125 feet east of the gage rod; elevation above the zero of the gage, 13.72
levation of the zero of the gage above sea level is 4,317 feet. The reconstruc-
bridge under which the gage was placed interfered somewhat with conven-
; and in 1905 a secondary gage rod was placed nearer the bank for use during
of water.

on in regard to this station is contained in the following publications of the
es Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

: WS 49, p 275; 66, p 27; 84, pp 68-69; 99, pp 165-166; 131, pp 35-36.
WS 49, p 275; 66, p 27; 84, p 69; 99, p 166; 131, p 36.
monthly: Ann 22, iv, p 312; WS 75; p 125; 84, p 70; 99, p 167; 131, p 38.
ts: WS 49, p 275; 66, p 27; 84, p 69; 99, p 166; 131, p 37.
1: WS 75, p 126.
es: WS 52, p 516; 66, p 171; 84, p 70; 99, p 167; 131, p 38.

charge measurements of North Platte River at Guernsey, Wyo., for 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
..	A. J. Parshall	208	428	2.54	1.00	1,089
..	do	296	625	3.28	1.65	2,052
..	do	329	1,214	4.95	3.50	6,007
..	do	330	1,306	5.24	3.80	6,838
..	do	330	1,156	4.41	3.20	5,094
..	do	330	1,855	5.80	5.25	10,760
..	do	330	1,751	5.52	5.00	9,660
..	do	330	1,697	5.33	4.80	9,053
..	do	330	2,073	6.11	6.00	12,670
..	do	330	2,078	6.14	6.00	12,760
..	do	297	585	2.71	1.45	1,586
..	do	297	580	2.67	1.42	1,549
..	do	312	713	3.37	1.95	2,405
..	do	311	620	3.15	1.65	1,949
..	do	287	613	3.05	1.58	1,870
..	do	201	360	2.19	.85	788
..	do	200	354	2.12	.80	749
..	do	195	300	1.45	.38	434
..	do	189	263	1.29	.20	340
..	do	186	250	1.20	.10	300
..	do	196	307	1.55	.45	478

Daily gage height, in feet, of North Platte River at Guernsey, Wyo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov
1	1.0	2.85	5.25	3.85	1.85	0.55	0.1	0.
2	1.0	3.05	5.0	5.3	1.85	.25	.3	.
3	1.0	3.5	4.88	3.75	1.45	.25	.38	.
4	1.0	3.8	4.95	3.45	1.3	.25	.3	.
5	1.0	3.7	5.05	3.25	1.1	.2	.32	.
6	1.1	3.7	5.25	3.1	1.0	.2	.38	.
7	1.12	3.75	5.6	3.25	1.0	.2	.45	.
8	1.2	3.8	5.95	3.15	1.25	.25	.5	.
9	1.2	3.9	6.0	2.85	1.0	.3	.45	.
10	1.28	3.8	6.0	2.55	1.0	.4	.4	.
11	1.38	3.6	6.0	2.35	1.0	.45	.35	.
12	1.4	3.3	6.4	2.15	1.3	.5	.3	.
13	1.45	3.2	6.3	2.05	1.8	.4	.3	.
14	1.65	3.2	6.15	2.0	1.15	.48	.3	.
15	1.9	3.1	6.05	2.0	1.0	.4	.3	.
16	2.0	3.05	5.95	1.88	.9	.4	.35	.
17	1.8	3.0	5.75	1.75	.8	.4	.32	.
18	1.8	2.9	5.65	1.65	.8	.4	.35	.
19	1.85	2.9	5.55	1.55	.95	.35	.35	.
20	1.95	3.1	5.45	1.48	.9	.3	.35	.
21	2.15	3.2	5.25	1.72	.85	.25	.35	.
22	2.1	3.4	4.95	1.7	.6	.2	.4	.
23	2.15	5.15	4.75	1.5	.7	.2	.4	.
24	2.4	4.3	4.45	1.4	.62	.15	.4	.
25	3.15	4.35	4.35	1.4	.55	.12	.4	.
26	3.3	4.7	4.25	1.5	.5	.1	.45	.
27	3.05	5.0	4.15	1.6	.48	.1	.45	.
28	3.25	5.1	4.1	1.7	.5	.1	.5	.
29	3.4	5.2	4.0	1.5	.48	.1	.5	.
30	3.0	5.35	3.9	2.0	1.2	.1	.5	.
31	.....	5.4	.....	1.65	1.0	.....	.5	.....

Station rating table for North Platte River at Guernsey, Wyo., from April 1 to June 12, 190

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	1,090	2.10	2,795	3.20	5,125	4.60	8,770
1.10	1,225	2.20	2,970	3.30	5,370	4.80	9,310
1.20	1,365	2.30	3,150	3.40	5,620	5.00	9,860
1.30	1,510	2.40	3,340	3.50	5,870	5.20	10,410
1.40	1,660	2.50	3,540	3.60	6,125	5.40	10,970
1.50	1,815	2.60	3,750	3.70	6,385	5.60	11,540
1.60	1,970	2.70	3,965	3.80	6,645	5.80	12,120
1.70	2,130	2.80	4,185	3.90	6,905	6.00	12,700
1.80	2,290	2.90	4,410	4.00	7,170	6.20	13,300
1.90	2,455	3.00	4,640	4.20	7,700	6.40	13,900
2.00	2,625	3.10	4,880	4.40	8,230		

The above table is applicable only for open-channel conditions. It is based on ten discharge mea urements made during the first part of 1905, and is fairly well defined. Owing to shifting conditio this table is not applicable subsequent to high water.

tation rating table for North Platte River at Guernsey, Wyo., from June 13, to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-ft.*
0.10	295	0.80	765	1.50	1,670	2.20	2,925
.20	335	.90	865	1.60	1,835	2.30	3,125
.30	385	1.00	975	1.70	2,005	2.40	3,330
.40	445	1.10	1,095	1.80	2,180	2.50	3,540
.50	515	1.20	1,225	1.90	2,360		
.60	590	1.30	1,365	2.00	2,545		
.70	675	1.40	1,515	2.10	2,730		

The above table is applicable only for open-channel conditions. It is based on eleven discharge measurements made during the latter part of 1905, and is fairly well defined. Above 2.5 feet the table is the same as the preceding one.

Estimated monthly discharge of North Platte River at Guernsey, Wyo., for 1905.

[Drainage area, 16,240 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	5,620	1,090	2,544	151,400	0.157	0.175
May	10,970	4,298	6,745	414,700	.415	.478
June	13,900	6,905	10,580	629,600	.651	.726
July	10,690	1,515	3,289	202,200	.203	.234
August	2,270	501	1,041	64,010	.064	.074
September	552	295	382	22,730	.024	.027
October	515	295	435	26,750	.027	.031
November	675	515	559	33,260	.034	.038
The period				1,545,000		

NORTH PLATTE RIVER AT ALCOVA, WYO.

This station was established February 19, 1904, by John E. Field. It is located at the highway bridge 1,000 feet southwest of the post-office at Alcova, Wyo. There are no running tributaries entering the river in this vicinity.

The channel is straight for 1,500 feet above and 800 feet below the station. The current is swift in the center and sluggish near the banks. Both banks are high, clean, and not liable to overflow. The bed of the stream is rocky, covered with small bowlders, and is permanent. The river is divided by the bridge piers into ten channels at low water and thirteen channels at high water. The bottom at the measuring section is rough and uneven, and this may affect the accuracy somewhat.

Measurements are made from the downstream side of the bridge. The initial point for soundings is the north end of the downstream hand rail.

The gage is a staff fastened to the northeast corner of the crib pier supporting the center of the bridge. During 1905 the gage was read twice a day by A. F. Hollebaugh. The bench mark is a standard United States Geological Survey iron post located at the west quarter corner of sec. 19, T. 30 N., R. 82 W. It is about 1,000 feet due north of the post-office. Its elevation is 5,366 feet above sea level and 36.67 feet above the gage datum.

July 20, 1905, a measurement was made by L. V. Branch with the following result: Area of section, 670 square feet; mean velocity, 1.68 feet per second; gage height, 5.42 feet; discharge, 1,126 second-feet.

A description of this station, with gage height and discharge data, is contained in Wate Supply Paper No. 131 of the United States Geological Survey, pages 34–35.

Daily gage height, in feet, of North Platte River at Alcova, Wyo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
1	3.8	3.85	4.32	5.0	6.85	9.5	7.6	5.0	3.9	4.0	4.18	
2	3.7	3.8	4.35	5.05	6.85	9.7	7.4	5.1	3.9	3.95	4.3	
3	3.85	3.8	4.38	5.05	7.15	9.9	7.25	5.2	3.8	4.3	4.22	
4	3.85	3.8	4.48	5.08	7.35	10.1	7.3	5.1	3.8	4.25	4.15	
5	3.85	3.8	4.7	5.12	7.35	10.8	7.3	5.05	3.9	4.1	4.15	
6	3.85	3.75	4.75	5.05	7.05	11.35	7.15	4.95	4.25	4.1	4.32	
7	3.85	3.75	4.82	4.95	6.85	11.3	6.85	4.9	4.4	4.1	4.4	
8	3.85	3.8	4.8	5.02	6.65	11.05	6.6	4.9	4.25	4.1	4.58	
9	3.75	3.8	4.78	5.05	6.52	11.0	6.45	4.8	4.4	4.05	4.52	
10	3.7	3.7	4.8	5.2	6.6	11.3	6.28	4.7	4.3	4.0	4.52	
11	3.85	3.65	4.75	5.65	7.0	11.5	6.2	4.65	4.3	4.0	4.48	
12	3.75	3.8	4.85	6.1	7.15	11.1	6.05	4.65	4.2	4.0	4.4	
13	3.65	3.8	4.9	5.9	7.0	10.6	5.95	4.55	4.1	4.0	4.4	
14	3.5	3.8	4.92	5.75	6.78	10.55	5.8	4.7	4.1	4.0	4.28	
15	3.6	3.8	4.95	5.65	6.7	10.2	5.7	5.0	4.0	4.0	4.22	
16	3.75	3.8	5.1	5.8	6.55	10.15	5.6	4.95	3.9	4.0	4.2	
17	3.85	3.8	5.35	5.85	6.55	10.05	5.6	4.75	3.9	4.12	4.32	
18	3.9	3.85	5.32	5.8	6.65	10.0	5.5	4.6	3.9	4.18	4.4	
19	3.85	3.95	5.2	5.7	7.1	9.8	5.4	4.45	3.9	4.18	4.42	
20	3.85	4.0	5.15	5.68	7.75	9.35	5.45	4.4	3.8	4.2	4.45	
21	3.9	4.05	5.15	5.7	8.45	9.0	5.5	4.3	3.78	4.3	4.5	
22	3.95	4.0	5.15	5.85	8.8	8.8	5.45	4.25	3.75	4.25	4.42	
23	3.9	4.05	5.15	5.85	9.15	8.7	5.4	4.2	3.75	4.2	4.38	
24	3.9	4.1	5.15	5.82	9.55	8.7	5.4	4.2	3.8	4.12	4.22	
25	3.95	4.1	5.15	5.9	9.75	8.7	5.25	4.1	3.78	4.15	3.65	
26	4.0	4.15	5.1	6.15	9.9	8.5	5.15	4.0	3.75	4.2	3.82	
27	4.0	4.15	5.1	6.15	9.85	8.4	5.05	4.0	3.7	4.35	3.9	
28	4.05	4.25	5.15	6.08	9.8	8.15	4.95	4.0	3.7	4.22	4.05	
29	4.05	.....	5.12	6.28	9.95	8.05	4.9	3.9	3.7	4.32	4.25	
30	4.05	.....	5.05	6.75	9.75	7.75	5.2	3.9	3.9	4.42	3.8	
31	3.85	.....	5.05	.....	9.5	.....	5.1	3.9	.....	4.35	.....	

NOTE.—Probable ice condition January, February, March, and December.

ating table for North Platte River at Alcova, Wyo., from February 21, 1904, to December 31, 1905.

Gage eight.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
3.40	110	4.90	760	6.40	2,200	8.80	6,325
3.50	130	5.00	830	6.50	2,330	9.00	6,770
3.60	155	5.10	900	6.60	2,465	9.20	7,225
3.70	180	5.20	975	6.70	2,600	9.40	7,685
3.80	210	5.30	1,055	6.80	2,740	9.60	8,155
3.90	245	5.40	1,140	6.90	2,885	9.80	8,635
4.00	285	5.50	1,230	7.00	3,030	10.00	9,120
4.10	325	5.60	1,320	7.20	3,330	10.20	9,630
4.20	370	5.70	1,415	7.40	3,645	10.40	10,160
4.30	415	5.80	1,515	7.60	3,980	10.60	10,720
4.40	465	5.90	1,620	7.80	4,335	10.80	11,300
4.50	520	6.00	1,730	8.00	4,700	11.00	11,900
4.60	575	6.10	1,840	8.20	5,080	11.20	12,150
4.70	635	6.20	1,955	8.40	5,475	11.40	13,130
4.80	695	6.30	2,075	8.60	5,890		

above table is applicable only for open-channel conditions. It is based on eight discharge measits made during 1904–5, and is fairly well defined between gage heights 4.5 feet and 9.5 feet. Below the table is uncertain.

Estimated monthly discharge of North Platte River at Alcova, Wyo., for 1904–5.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
1904.				
	2,958	747	1,729	102,900
	11,450	3,210	5,900	362,800
	8,395	3,485	6,758	402,100
	3,517	695	1,808	111,200
t	816	440	582	35,790
nber	1,302	210	389	23,150
er	647	361	482	29,640
nber 1–19	465	110	307	11,570
The period				1,079,000
1905.				
	2,670	795	1,394	82,950
	8,998	2,357	4,707	289,400
	13,440	4,245	8,855	526,900
	3,980	760	1,817	111,700
t	975	245	574	35,290
ıber	465	180	273	16,240
r	476	265	347	21,340
ber	564	168	406	24,160
he period				1,108,000

.—No estimate for ice period.

NORTH PLATTE RIVER NEAR MITCHELL, NEBR.

This station was established June 3, 1902. It is located at a highway bridge 1 mile south of Mitchell, Nebr., in sec. 27, T. 23 N., R. 56 W., and replaces the station at Gering, Nebr.

The channel is straight for 2,000 feet above and below the station. Both banks are low and sandy, but are not liable to overflow. The bed of the stream is composed entirely of shifting sand to a depth of 20 feet or more. At high stages there are three channels and at low stages there are from three to forty channels. The current is never sluggish, even at extreme low water. The river is frozen during the winter months. The range of gage heights is about 5.5 feet.

Discharge measurements are made from the upstream side of the highway bridge, which has a total span of 1,565 feet and is supported on pile bents 20 feet apart. The initial point for soundings is the zero mark at the north end of the bridge.

A standard chain gage, which was read during 1905 by B. H. Newbold, is fastened to the upstream end of the hand rail near the center of the bridge. The length of the chain is 10.00 feet. The gage is referred to bench marks as follows: (1) A cross cut in the floor of the bridge at the gage; elevation, 9.74 feet. (2) The head of a nail in the top of the west end of the cap of the first bent at the north end of the bridge; elevation, 8.56 feet. (3) A standard aluminum bench-mark cap, marked "U. S. G. S. B. M.," leaded into the top of a 2-inch gas pipe 4 feet long, located 138 feet north and 30 feet east of the north end of the downstream hand rail; elevation, 8.64 feet. Elevations are above gage datum.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 66, p 28; 84, p 66; 99, pp 162–163; 131, p 39.
Discharge: 66, p 28; 84, p 67; 99, p 163; 131, p 40.
Discharge, monthly: 75, p 126; 84, p 68; 99, p 165; 131, p 41.
Gage heights: 66, p 28; 84, p 67; 99, p 164; 131, p 40.
Rating tables: 84, p 68; 99, p 164; 131, p 41.

Discharge measurements of North Platte River near Mitchell, Nebr., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 29	H. C. Gardner	1,575	648	1.83	2.40	1,18
May 12	.....do	1,225	2,385	3.61	4.15	8,61
June 13	.....do	1,037	3,954	4.24	5.20	16,77
July 11	.....do	1,050	1,513	2.54	3.25	3,85
July 20	.....do	800	760	2.13	2.50	1,62
August 3	.....do	762	871	2.31	2.75	2,01
September 21	F. S. Dobson	450	215	1.77	1.92	38
September 7	H. C. Gardner	450	266	2.39	1.95	63

aily gage height, in feet, of North Platte River near Mitchell, Nebr., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	1.87	1.67	2.72	2.5	4.1	5.0	4.1	2.7	2.1	1.9
.....	1.79	.....	2.65	2.6	4.1	4.9	4.1	2.6	2.0	1.9
.....	1.77	.....	2.4	2.6	4.2	4.8	4.1	2.7	2.0	1.9
.....	1.8	.....	2.37	2.55	4.3	4.8	3.9	2.7	2.0	1.9
.....	1.81	.....	2.35	2.5	4.4	4.8	3.8	2.6	2.0	1.9
.....	1.76	.....	2.34	2.5	4.3	4.8	3.7	2.6	1.9	1.9
.....	1.77	.....	2.32	2.5	4.4	4.8	3.6	2.6	1.9	1.9
.....	1.78	.....	2.3	2.5	4.5	4.9	3.6	2.5	2.0	1.9
.....	1.75	.....	2.34	2.5	4.4	5.1	3.5	2.5	2.0	1.9
.....	1.74	.....	2.35	2.5	4.4	5.0	3.4	2.5	1.95	1.9
.....	1.65	.....	2.34	2.6	4.3	5.0	3.2	2.5	1.9	1.9
.....	1.64	.....	2.25	2.7	4.2	5.0	3.2	2.5	1.9	1.9
.....	1.64	.....	2.3	2.7	4.2	5.2	3.1	2.65	1.9	1.9
.....	1.65	.....	2.27	2.8	4.15	5.2	3.0	2.8	1.9	2.0
.....	1.66	.....	2.35	2.8	4.1	5.0	2.9	2.6	1.9	2.0
.....	1.76	.....	2.38	2.9	4.1	4.9	2.85	2.5	1.9	2.0
.....	1.71	.....	2.41	3.0	4.1	4.8	2.8	2.4	1.9	1.9
.....	1.82	.....	2.35	3.1	4.0	4.8	2.7	2.3	1.9	1.9
.....	1.86	.....	2.4	3.1	3.9	4.8	2.6	2.3	1.9	1.9
.....	1.88	.....	2.35	3.1	3.9	4.7	2.6	2.25	1.9	2.0
.....	1.95	.....	2.4	3.1	4.0	4.7	2.5	2.2	1.9	2.0
.....	2.0	2.1	2.45	3.3	4.1	4.6	2.5	2.3	1.9	2.0
.....	2.05	2.15	2.5	3.4	4.2	4.4	2.55	2.3	1.9	2.0
.....	2.1	2.25	2.45	3.5	4.9	4.3	2.6	2.2	1.9	2.0
.....	1.87	2.3	2.35	3.6	4.7	4.25	2.6	2.2	1.9	2.0
.....	2.07	2.53	2.42	4.1	4.6	4.2	2.5	2.2	1.9	2.0
.....	2.09	2.55	2.4	4.2	4.6	4.1	2.7	2.15	1.9	2.0
.....	2.01	2.6	2.36	4.1	4.7	4.0	2.8	2.1	1.9	2.0
.....	1.8	.....	2.42	4.3	4.8	4.0	2.8	2.0	1.9	2.05
.....	1.72	.....	2.45	4.2	4.9	4.0	2.75	2.0	1.9	2.1
.....	1.69	.....	2.42	.....	4.9	.....	2.7	2.0	.....	2.1

ce conditions during January and February.

rating table for North Platte River near Mitchell, Nebr., from January 1 to October 31, 1905.

ge ght.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
et.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.90	380	2.80	2,260	3.70	6,050	4.60	11,900
2.00	520	2.90	2,570	3.80	6,600	4.70	12,700
2.10	670	3.00	2,900	3.90	7,150	4.80	13,500
2.20	840	3.10	3,260	4.00	7,700	4.90	14,300
2.30	1,030	3.20	3,650	4.10	8,300	5.00	15,100
2.40	1,250	3.30	4,070	4.20	8,900	5.10	15,900
2.50	1,480	3.40	4,520	4.30	9,600	5.20	16,800
2.60	1,720	3.50	5,000	4.40	10,300		
2.70	1,980	3.60	5,500	4.50	11,100		

ve table is applicable only for open-channel conditions. It is based on eight discharge meas- made during 1905 and is fairly well defined.

Estimated monthly discharge of North Platte River near Mitchell, Nebr., for 1905.

[Drainage area, 24,400 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dep inc
March	2,036	935	1,239	76,180	0.051	
April	9,600	1,480	3,573	212,600	.146	
May	14,300	7,150	10,010	615,500	.410	
June	16,800	7,700	12,760	759,300	.523	
July	8,300	1,480	3,594	221,000	.147	
August	2,260	520	1,296	79,690	.053	
September	670	380	420	24,990	.017	
October	670	380	460	28,280	.019	
The period				2,018,000		

NOTE.—No estimate for ice period.

NORTH PLATTE RIVER AT BRIDGEPORT, NEBR.

This station was established May 4, 1902. It is located at the highway bridge on public road about one-half mile north of Bridgeport, Nebr., in sec. 28, T. 20 N., R. 5

At the gaging section the channel is narrowed by a dike built as a bridge approach, is straight for a considerable distance both above and below. The banks are low, but not liable to overflow. The bed is composed of shifting sand. There is but one chann ordinary or high stages, but at low water the stream is divided into many winding chan The water is never sluggish.

Discharge measurements are made from the upstream side of the highway bridge, w is supported by pile bents about 20 feet apart. The initial point for soundings is the mark on the hand rail at the south end of the bridge.

The gage, which was read during 1905 by Porter Hannawald, is of the wire and we type and is fastened to theupstream hand rail of the bridge. The length of the wire is 1 feet. The gage is referred to bench marks as follows: (1) A 6 by 6 inch stone, ma "U. S. C.& G. S.," in the NE. ¼, sec. 32, T. 20 N., R. 50 W., of the sixth principal meri 130 feet east of the east gate of the stock yards and 300 feet northwest of the northwest ner of the public school building; elevation, 9.94 feet. (2) A standard aluminum U States Geological Survey bench-mark cap set in a 20 by 12 by 6 inch stone located abo feet south and a little east of the northeast corner of lot No. 4, block No. 2, of the Rive addition to Bridgeport, Nebr.; elevation, 11.32 feet. (3) The head of a nail in the t the west end of the cap of the south bent of the bridge; elevation, 10.14 feet. Eleva are above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply P of the United States Geological Survey:

Description: 84, p 64; 99, pp 159-160; 131, p 42.
Discharge: 84, p 65; 99, pp 160-161; 131, p 43.
Discharge, monthly: 84, p 66; 99, p 162; 131, p 44.
Gage heights: 84, p 65; 131, p 43.
Rating tables: 84, p 66; 99, p 162; 131, p 44.

Discharge measurements of North Platte River at Bridgeport, Nebr., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	H. C. Gardner.....	2,200	845	1.67	5.10	1,417
.....	.....do.....	2,200	4,150	2.66	6.30	11,040
.....	.....do.....	2,190	4,904	3.57	7.00	17,550
.....	.....do.....	2,190	2,039	2.26	5.65	4,608
.....	.....do.....	1,960	1,287	1.84	5.40	2,367
.....	.....do.....	2,060	1,298	1.92	5.45	2,504
13..	A. Dobson.....	639	232	1.57	4.91	366

Daily gage height, in feet, of North Platte River at Bridgeport, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	.....	5.5	6.45	6.83	6.25	5.46	4.8	4.86
.....	.....	5.7	6.43	6.81	6.25	5.54	4.84	4.9
.....	.....	5.52	6.4	6.75	6.25	5.37	4.93	4.92
.....	.....	5.3	6.4	6.65	6.35	5.44	4.87	4.94
.....	.....	5.27	6.37	6.62	6.2	5.48	4.94	4.95
.....	.....	5.27	6.5	6.55	6.0	5.36	4.9	4.93
.....	.....	5.25	6.41	6.57	5.95	5.35	4.87	4.9
.....	.....	5.32	6.43	6.78	5.88	5.37	4.9	4.9
.....	.....	5.35	6.45	6.86	5.85	5.31	4.9	4.9
.....	.....	5.32	6.4	6.8	5.8	5.3	4.96	4.93
.....	.....	5.43	6.46	6.9	5.75	5.33	4.94	4.95
.....	.....	5.36	6.33	6.9	5.68	5.21	4.93	4.97
.....	.....	5.42	6.3	6.95	5.6	5.27	4.91	4.98
.....	.....	5.35	6.25	6.98	5.5	5.16	4.95	5.23
.....	.....	5.37	6.25	7.0	5.35	5.3	4.9	5.15
.....	.....	5.3	6.3	6.95	5.43	5.39	4.87	5.1
.....	.....	5.38	6.25	6.8	5.43	5.13	4.87	5.1
.....	.....	5.62	6.28	6.8	5.4	5.05	4.89	5.08
.....	.....	5.6	6.25	6.8	5.34	5.0	4.97	5.03
.....	.....	5.9	6.28	6.7	5.25	4.96	5.0	5.02
.....	.....	5.57	6.15	6.6	5.37	4.9	4.95	5.07
.....	.....	5.62	6.26	6.65	5.37	4.98	4.9	5.05
.....	.....	5.8	6.25	6.6	5.05	4.95	4.9	5.1
.....	.....	6.0	6.6	6.6	5.32	4.9	4.9	5.08
.....	.....	6.0	6.53	6.5	5.16	4.86	4.92	5.08
.....	.....	6.02	6.5	6.35	5.13	5.06	4.87	5.06
.....	.....	6.2	6.52	6.3	5.43	5.07	4.88	5.08
.....	.....	6.2	6.6	6.25	5.42	4.9	4.87	5.0
.....	5.1	6.2	6.55	6.2	5.38	4.88	4.86	5.1
.....	5.25	6.4	6.57	6.15	5.54	4.9	4.88	5.08
.....	5.27	.....	6.7	.....	5.43	4.88	.....	5.1

Station rating table for North Platte River at Bridgeport, Nebr., from March 29 to July 11, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
5.10	1,400	5.60	4,400	6.10	8,750	6.60	13,700
5.20	1,900	5.70	5,250	6.20	9,700	6.70	14,700
5.30	2,400	5.80	6,100	6.30	10,700	6.80	15,700
5.40	3,000	5.90	6,950	6.40	11,700	6.90	16,700
5.50	3,700	6.00	7,800	6.50	12,700	7.00	17,700

The above table is based on four discharge measurements made during 1905 and is fairly well defined between gage heights 5.1 feet and 7 feet.

From July 12 to 21 the rating table was applied indirectly. After July 21 the following table was used:

Station rating table for North Platte River at Bridgeport, Nebr., from July 22 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
4.80	200	5.10	930	5.30	1,720	5.50	2,920
4.90	350	5.20	1,270	5.40	2,300	5.60	3,600
5.00	600						

The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during 1905 and the general form of the 1904 curve. It is not well defined.

Estimated monthly discharge of North Platte River at Bridgeport, Nebr., for 1905.

[Drainage area, 23,190 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	11,700	2,150	4,822	286,900	0.208	0.23
May	14,700	9,225	11,710	720,000	.505	.58
June	17,700	9,225	14,430	858,600	.622	.69
July	11,200	765	4,536	278,900	.196	.22
August	3,192	280	1,316	80,920	.057	.07
September	600	200	370	22,020	.016	.02
October	1,405	290	685	42,120	.030	.03
The period				2,289,000		

NORTH PLATTE RIVER AT NORTH PLATTE, NEBR.

is station was established October 5, 1894. It is located 3½ miles above the junction orth and South Platte rivers, at a highway bridge about one-half mile north of the city orth Platte, in sec. 28, T. 14 N., R. 30 W. It is the lowest station on the river.

he channel is nearly straight for about 500 feet both above and below the station. The ks are low, but are rarely, if ever, overflowed. The bed is composed of shifting sand. river flows in two channels separated by a large island. The north channel is narrow except in moderately high water is dry. At low stages the water is confined to a few nnels along the right bank. The only obstructions in the channel are the pile bents and ined ice guards of the bridge. The current is never sluggish, even at low stages. One ll tributary, Birdwood Creek, maintains a small flow of water at the gaging station dur- months when the river itself would otherwise be entirely dry. During the winter nths the river often freezes almost solid, since it is very shallow.

Discharge measurements are made from the highway bridge, which consists of 93 spans pported on pile bents 20 feet apart. The initial point for soundings is on the right bank. The gage, which was read during 1905 by H. E. Dress, is a vertical staff spiked to the pil- of the Union Pacific Railroad bridge 2 miles below the wagon bridge. The bench mark the top of the east rail directly over the top of the gage rod; elevation, 12.00 feet. It is stomary to refer the elevation of the water surface at the gaging section during measure- nts to the top of the upstream end of the cap of the second bent from the right-bank end the highway bridge.

Information in regard to this station is contained in the following publications of the ited States Geological Survey (Ann=Annual Report; Bull.=Bulletin; WS=Water-Sup- y Paper):

Description: Ann 18, iv, pp 156–157; 19, iv, p 306; Bull 131, p 30; 140, pp 99–100; WS 15, p 86; 27, p 76; , pp 220–221; 49, p 277; 66, p 28; 84, p 62; 99, pp 157–158; 131, pp 44–45.
Discharge: Ann 13, iii, p 82; 18, iv, p 157; 20, iv, pp 301, 302; Bull 131, p 92; 140, p 100; WS 15, p 86; 27, 8; 37, p 221; 49, p 277; 66, p 28; 84, p 62; 99, p 158; 131, p 45.
Discharge, monthly: Ann 18, iv, p 158; 19, iv, p 310; 20, iv, pp 263, 269; 21, iv, p 199; Bull 140, p 102; WS , p 64; 99, p 159; 131, p 47.
Discharge, yearly: Ann 20, iv, p 54.
Gage heights: Bull 140, p 102; WS 11, p 52; 15, p 86; 27, p 81; 37, p 221; 49, p 278; 66, p 29; 84, p 63; 99, 158, 161; 131, p 46.
Hydrographs: Ann 19, iv, p 310; 21, iv, p 199.
Rainfall and run-off relation: Ann 20, iv, p 266.
Rating tables: Ann 18, iv, pp 157–158; Bull 140, p 101; WS 27, p 88; 39, p 447; 84, p 63; 99, p 159; 131, 6.

Discharge measurements of North Platte River at North Platte, Nebr., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
rch 31	G. W. Bates	1,460	1,020	2.11	2.40	2,157
16	do	1,960	3,002	3.08	3.35	9,677
e 12	H. C. Gardner	1,950	5,213	3.37	3.95	17,570
e 20	do	1,970	4,875	3.28	3.75	16,010
13	do	3,740	2,336	2.51	2.75	5,878
22	do	1,760	1,500	2.34	2.40	3,513
ust 5	do	1,120	1,294	1.98	2.20	2,564
ember 20	F. S. Dobson	.....	426	1.65	1.80	703
ber 24	Dobson and Bates	1,020	563	1.87	1.98	1,056
ember 9	H. C. Gardner	.....	462	1.59	1.70	735

Daily gage height, in feet, of North Platte River at North Platte, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	.....	2.58	3.18	3.65	3.4	2.52	1.6	1.6
2	.....	2.62	3.32	3.88	3.65	2.48	1.55	1.5
3	.....	2.65	3.45	3.88	3.68	2.45	1.5	1.5
4	.....	2.75	3.38	3.88	3.38	2.3	1.52	1.5
5	2.85	2.7	3.38	3.68	3.28	2.22	1.62	1.5
6	2.75	2.62	3.4	3.58	3.38	2.22	1.7	1.6
7	2.62	2.48	3.45	3.5	3.18	2.18	1.72	1.6
8	2.5	2.38	3.48	3.48	3.1	2.15	1.7	1.6
9	2.4	2.25	3.5	3.52	3.0	2.18	1.7	1.6
10	2.45	2.28	3.4	3.72	2.9	2.1	1.72	1.6
11	2.5	2.38	3.48	3.88	2.82	2.05	1.7	1.7
12	2.4	2.35	3.5	4.02	2.8	2.0	1.65	1.7
13	2.4	2.42	3.5	3.95	2.75	2.2	1.65	1.6
14	2.5	2.45	3.55	3.9	2.62	2.2	1.75	1.6
15	2.42	2.5	3.4	4.08	2.52	2.18	1.85	1.8
16	2.68	2.45	3.35	4.28	2.42	2.02	1.68	1.7
17	2.82	2.45	3.2	4.08	2.32	2.0	1.58	1.7
18	2.7	2.48	3.18	3.9	2.2	1.92	1.68	1.7
19	2.82	2.45	3.18	3.8	2.28	1.95	1.82	1.8
20	2.65	2.42	3.28	3.75	2.42	2.02	1.9	1.9
21	2.5	2.8	3.2	3.6	2.5	1.85	1.8	1.9
22	2.4	2.8	3.1	3.6	2.42	1.8	1.75	1.9
23	2.32	2.72	3.05	3.62	2.28	1.75	1.8	1.8
24	2.28	2.9	3.1	3.62	2.28	1.68	1.72	1.9
25	2.28	3.12	3.28	3.42	2.3	1.68	1.68	1.8
26	2.25	3.1	3.28	3.32	2.18	1.7	1.62	1.9
27	2.25	3.0	3.82	3.28	2.2	1.68	1.58	1.9
28	2.38	2.9	3.65	3.18	2.18	1.65	1.55	2.0
29	2.4	3.05	3.78	3.12	2.38	1.6	1.6	2.0
30	2.38	3.22	3.7	3.22	2.1	1.75	1.6	2.0
31	2.4	.....	3.65	.....	2.18	1.72	.....	2.0

Station rating table for North Platte River at North Platte, Nebr., from March 5 to June 15, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.30	1,630	2.80	4,620	3.30	9,080	3.80	15,440
2.40	2,150	2.90	5,370	3.40	10,200	3.90	16,900
2.50	2,700	3.00	6,190	3.50	11,400	4.00	18,400
2.60	3,290	3.10	7,080	3.60	12,680	4.10	19,930
2.70	3,930	3.20	8,040	3.70	14,030		

The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during 1905, and is poorly defined. Owing to the shifting character of the stream bed, all estimates based on this and the following table are merely rough approximations.

tion rating table for North Platte River at North Platte, Nebr., from June 16 to September 10, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.50	360	2.30	3,050	3.00	7,910	3.70	15,430
1.60	530	2.40	3,600	3.10	8,810	3.80	16,690
1.70	740	2.50	4,200	3.20	9,770	3.90	17,970
1.80	1,000	2.60	4,850	3.30	10,790	4.00	19,270
1.90	1,310	2.70	5,540	3.40	11,870	4.10	20,590
2.00	1,670	2.80	6,280	3.50	13,010	4.20	21,930
2.10	2,080	2.90	7,070	3.60	14,200	4.30	23,280
2.20	2,540						

The above table is applicable only for open-channel conditions. It is based on five discharge measurements made during 1905. From September 11 to October 31 the discharge was obtained by the direct method.

Estimated monthly discharge of North Platte River at North Platte, Nebr., for 1905.

[Drainage area, 28,520 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 5-31	4,695	1,390	2,727	146,000	0.096	0.096
April	8,248	1,390	3,743	222,700	.131	.146
May	15,730	6,635	10,270	631,500	.360	.415
June	23,010	9,002	14,700	874,700	.515	.575
July	15,180	2,080	5,983	367,900	.210	.242
August	4,330	530	1,862	114,500	.065	.075
September	1,000	260	585	34,810	021	.023
October	1,270	200	616	37,880	.022	.025
The period				2,430,000		

LARAMIE RIVER AT GLENDEVEY, COLO.

Laramie River rises on the east side of the Medicine Bow Range in Colorado, flows northwestward into Wyoming, and thence north and northeast until it joins the North Platte at Fort Laramie, Wyo. The drainage basin, which is narrow and very mountainous in its upper portion, broadens considerably in the middle and lower portions. The middle portion comprises the Laramie plains and surrounding foothills. The plains are about 30 miles wide and 80 miles long, extend north and south, and are bounded by the Laramie Hills on the east and the foothills of the Medicine Bow Range on the west. After passing around the Laramie Hills the river flows out on the Great Plains until it joins the North Platte. The soil throughout the entire area is sandy and along the river bottoms is fertile. Above the Laramie Plains the altitude is too great to permit the raising of crops other than hay and a few of the hardier cereals. Numerous small ditches divert the water of the stream to the hay lands along the first bottom and to a considerable extent to the higher lands on either side. Cattle raising is the chief industry. In the lower portion of the valley irrigation is practiced to some extent, and large crops are produced each year. There are extensive forests of pine and spruce on the headwaters of the stream, which lie in the Medicine Bow Forest Reserve.

The largest tributary from the west is the Little Laramie, which rises near the center of the Medicine Bow Range, flows eastward out on the Laramie Plains, and enters the main river

10 miles north of the city of Laramie. Its drainage area is similar in every respect to thi the upper and middle portions of the Laramie. The principal tributary of the Laramie the right bank is Chugwater Creek, which rises in the Laramie Hills and joins the r about 18 miles above its mouth. The valley of Chugwater Creek is broad and fertile and entire stream is used for irrigation during the summer season.

McIntyre Creek, the largest tributary of the Laramie in Colorado, is described on p 215, in connection with the gaging station at Gleneyre, Colo.

The Glendevey gaging station was established June 24, 1904. It is located at the high bridge at Glendevey, Colo., on the State road between Walden and Fort Collins, in T. 9 R. 76 W.

The channel is straight for about 100 feet above and 300 feet below the station. B banks are high and covered with a dense growth of willows and the stream does not o flow even at very high stages. The bed is composed of bowlders and coarse gravel an free from vegetation and permanent. There is but one channel at all stages, broken three piers. Gage heights have an ordinary range of about 2.5 feet. During the win months the channel is obstructed by ice and gage readings are impracticable. The curren swift at high stages and medium at low stages. Discharge measurements are affected the bowlders on the bed of the stream and by the piers of the bridge.

Discharge measurements are made from the downstream side of the three-span bridge which the gage is attached. The initial point for soundings is a 30-penny nail driven into guard log directly above the east face of the wooden pier at the left end of the bridge.

The gage, which was read twice each day during 1905 by E. S. Graves, consists of a ve cal staff, graduated from 1 foot to 8 feet, attached to the northwest corner of the first p from the right bank. The 1-foot mark rests on the bed of the stream. The gage is refer to bench marks as follows: (1) A cross cut in the top of a granite bowlder 18 inches in dia ter, 10 feet northwest of the initial point for soundings; elevation, 7.32 feet above the zer the gage. (2) A cross cut in the top of a granite bowlder 3 feet in diameter, 75 feet no west of the initial point for soundings; elevation, 16.84 feet above the zero of the gage.

A description of this station, with gage-height and discharge data, is contained in Wa Supply Paper No. 131 of the United States Geological Survey, pages 66–67.

Discharge measurements of Laramie River at Glendevey, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di cha
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Se*
May 22	W. A. Lamb	52	76	4.00	2.72	
June 22	do	50	92	4.61	3.05	
July 20	do	45	52	2.42	2.30	
August 5	do	35	41	1.80	2.10	
August 20	do	34	33	1.36	1.99	
September 20	do	25	26	.96	1.91	

Daily gage height, in feet, of Laramie River at Glendevey, Colo., for 1905.

Day.	Apr.	May	June	July	Aug.	Sept.	Oct.
.....	1.82	2.25	3.4	2.7	2.25	1.95	1.8
.....	1.82	2.25	3.45	2.7	2.2	2.0	1.8
.....	1.82	2.25	3.85	2.65	2.2	1.9	1.8
.....	1.82	2.2	4.1	2.45	2.2	1.9	1.8
.....	1.85	2.15	4.1	2.4	2.15	1.9	1.8
.....	1.9	2.15	3.9	2.3	2.1	1.9	1.8
.....	1.9	2.15	3.8	2.3	2.1	1.9	1.8
.....	1.9	2.22	4.0	2.35	2.1	1.9	1.8
.....	1.9	2.22	4.3	2.4	2.1	1.9	1.8
.....	1.9	2.25	4.15	2.35	2.1	1.9	1.8
.....	1.85	2.25	3.6	2.4	2.15	1.9	1.8
.....	1.9	2.25	3.6	2.45	2.15	1.9	1.8
.....	1.9	2.25	3.55	2.4	2.1	1.9	1.8
.....	1.9	2.2	3.5	2.4	2.1	1.9	1.8
.....	1.9	2.2	3.65	2.4	2.1	1.85	1.8
.....	1.88	2.28	3.65	2.3	2.05	1.8	1.8
.....	1.9	2.4	3.65	2.35	2.0	1.8	1.8
.....	1.88	2.45	3.45	2.35	2.0	1.9	1.85
.....	1.88	2.48	3.2	2.35	2.0	1.9	1.9
.....	1.88	2.58	3.05	2.3	2.0	1.85	1.9
.....	1.92	2.75	3.05	2.3	1.95	1.8	1.8
.....	1.92	2.9	3.05	2.3	1.9	1.8	1.8
.....	1.92	3.1	3.15	2.2	1.9	1.8	1.8
.....	1.92	3.28	3.1	2.2	1.9	1.8	1.8
.....	1.95	3.35	3.1	2.25	1.9	1.8	1.8
.....	1.95	3.1	3.1	2.3	1.9	1.8	1.8
.....	2.05	3.05	3.1	2.35	1.9	1.8	1.8
.....	2.15	3.1	3.0	2.4	1.95	1.8	1.8
.....	2.15	3.05	2.85	2.35	1.95	1.8	1.8
.....	2.15	3.0	2.75	2.3	1.9	1.8	1.8
.....	.....	3.25	.....	2.3	1.9	.....	1.8

ating table for Laramie River at Glendevey, Colo., from June 24, 1904, to October 31, 1905.

Gage ight.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	Sec.-ft.	Feet.	Sec.-ft.	Feet.	Sec.-ft.	Feet.	Sec.-ft.
1.80	7	2.50	205	3.20	495	3.90	830
1.90	25	2.60	245	3.30	540	4.00	880
2.00	50	2.70	285	3.40	585	4.10	930
2.10	75	2.80	325	3.50	630	4.20	985
2.20	105	2.90	365	3.60	680	4.30	1,040
2.30	135	3.00	405	3.70	730		
2.40	170	3.10	450	3.80	780		

bove table is applicable only for open-channel conditions. It is based on ten discharge meas-ts made during 1904-5, and is well defined between gage heights 2 feet and 3 feet. The table has tended beyond these limits.

Estimated monthly discharge of Laramie River at Glendevey, Colo., for 1904–5.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
1904.				
June 24–30	405	265	299	4,151
July	405	90	165	10,140
August	90	50	63.4	3,895
September	50	25	31.7	1,886
October	50	7	26.6	1,636
The period				21,710
1905.				
April	90	11	31.3	1,862
May	562	90	263	16,170
June	1,040	305	627	37,319
July	285	105	162	9,961
August	120	25	60.7	3,733
September	50	7	18.5	1,101
October	25	7	8.5	523
The period				70,699

LARAMIE RIVER NEAR JELM, WYO.

This station was established June 22, 1904. It is located at a wagon bridge at H. T. Decker's ranch, one-half mile south of the Colorado-Wyoming State line, near Jelm, Wyo., in sec. 22, T. 12 N., R. 77 W., below all tributaries in Colorado.

The channel is straight for about 50 feet above and 300 feet below the station. Both banks are high and covered with willows and are not liable to overflow. The bed of the stream is composed of gravel and bowlders and is firm. There is but one channel at all stages, broken by the three piers of the bridge. The water is swift at high stages and medium at low stages. Discharge measurements are affected by large bowlders in the channel and also by the piers of the bridge. Gage heights have an ordinary range of about 4 feet. During the winter months the channel is obstructed by ice and gage readings are impracticable.

Discharge measurements are made from the downstream side of the four-span bridge to which the gage is attached. The initial point for soundings is a 30-penny nail driven into the left end of the downstream guard rail.

The gage, which was read during 1905 by Mr. Decker, consists of a staff fastened in a vertical position to the northwest corner of the center pier of the bridge. The bench mark is a 30-penny nail driven into the lower log at the southwest corner of Mr. Decker's house; elevation, 12.35 feet above the zero of the gage.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 131 of the United States Geological Survey, pages 67-68.

Discharge measurements of Laramie River near Jelm, Wyo., in 1905.

te.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	W. A. Lamb.....	57	123	4.47	3.80	550
.....	.....do.....	59	148	4.93	4.20	730
.....	.....do.....	57	75	2.27	2.55	170
6.....	.....do.....	43	63	1.86	2.40	117
21.....	.....do.....	39	47	1.51	2.31	71
ber 21 [a]	.....do.....	36	45	.93	1.98	42

[a] Made by wading.

Daily gage height, in feet, of Laramie River near Jelm, Wyo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	1.8	2.45	5.25	3.55	2.6	2.0	1.9
.....	1.8	2.55	5.4	3.55	2.6	2.0	1.9
.....	1.8	2.5	5.6	3.55	2.6	2.0	1.9
.....	1.8	2.4	5.9	3.35	2.5	2.0	1.8
.....	1.9	2.4	6.15	3.1	2.5	2.0	1.8
.....	1.9	2.4	5.8	2.9	2.5	2.1	1.8
.....	2.0	2.4	5.8	2.8	2.5	2.1	1.8
.....	2.0	2.5	5.95	2.8	2.5	2.1	1.8
.....	2.1	2.65	6.2	2.9	2.5	2.0	1.9
.....	2.0	2.6	6.0	2.8	2.5	2.0	1.9
.....	2.0	2.5	5.3	2.7	2.5	2.0	1.9
.....	2.0	2.5	5.3	2.7	2.5	2.0	1.9
.....	2.0	2.5	5.4	2.75	2.4	2.0	1.9
.....	2.0	2.5	5.25	2.7	2.4	2.0	1.9
.....	2.0	2.5	5.25	2.7	2.3	1.9	1.9
.....	2.0	2.5	5.15	2.65	2.3	1.9	1.9
.....	2.0	2.8	5.15	2.6	2.2	1.9	1.9
.....	2.0	3.2	4.8	2.6	2.2	1.9	1.8
.....	2.0	3.45	4.4	2.6	2.2	1.9	1.8
.....	2.05	3.8	4.35	2.7	2.2	1.9	1.8
.....	2.0	4.0	4.25	2.7	2.2	1.9	1.8
.....	2.1	4.5	4.25	2.6	2.1	1.8	1.8
.....	2.0	4.85	4.2	2.5	2.1	1.8	1.8
.....	2.0	4.95	4.2	2.45	2.1	1.8	1.9
.....	2.05	4.75	4.05	2.45	2.1	1.9	1.9
.....	2.1	4.7	3.95	2.5	2.1	1.9	1.9
.....	2.25	4.7	3.9	2.55	2.1	1.9	1.9
.....	2.35	4.7	3.9	2.6	2.1	2.0	1.8
.....	2.35	4.5	3.7	2.6	2.1	2.0	1.8
.....	2.4	4.5	3.5	2.6	2.1	1.9	1.8
.....	.....	4.85	.....	2.6	2.0	.....	1.8

Station rating table for Laramie River near Jelm, Wyo., from April 1 to October 31, 190

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-ft.*	*Feet.*	*Second-ft.*	*Feet.*	*Second-ft.*	*Feet.*	*Second-ft.*
1.80	22	2.80	210	3.80	555	4.80	1,045
1.90	33	2.90	240	3.90	600	4.90	1,100
2.00	45	3.00	270	4.00	645	5.00	1,155
2.10	58	3.10	300	4.10	690	5.20	1,270
2.20	73	3.20	330	4.20	735	5.40	1,390
2.30	91	3.30	365	4.30	785	5.60	1,515
2.40	112	3.40	400	4.40	835	5.80	1,645
2.50	135	3.50	435	4.50	885	6.00	1,780
2.60	185	3.60	475	4.60	935	6.20	1,920
2.70	160	3.70	515	4.70	990		

The above table is applicable only for open-channel conditions. It is based on six discharge m urements made during 1905 and two during 1904, and is not well defined.

Estimated monthly discharge of Laramie River near Jelm, Wyo., for 1905.

Month.	Discharge in second-feet.			Total acre-f
	Maximum.	Minimum.	Mean.	
April	112	22	50.1	1
May	1,128	112	458	2
June	1,920	435	1,160	6
July	455	124	212	1
August	160	45	97.8	
September	58	22	39.6	2
October	33	22	27.7	1
The period				12

M'INTYRE CREEK AT GLENEYRE, COLO.

McIntyre Creek rises in the Medicine Bow Mountains, flows northeastward, and ur with Laramie River at Gleneyre, Colo., about 12 miles south of the Colorado-Wyon State line. The entire basin is mountainous, and the greater portion of it is covered heavy forests of pine and spruce and dense growths of quaking aspen and underbrush. irrigation is carried on except near the mouth, where water is diverted to the bottom l along the stream. A project is being considered to divert water from the head of the str by means of a canal, inverted siphon, and tunnel, to the headwaters of Cache la Po River.

The gaging station was established June 23, 1904. It is located at the wagon bridg Joseph Smith's ranch at Gleneyre, Colo., in sec. 20, T. 11 N., R. 76 W.

The channel is straight for about 200 feet above and 30 feet below the station. right bank is low, is partly covered by willows, and at high water overflows for a distanc 40 feet from the main channel. The left bank is high and covered with willows. The be the stream is covered with gravel and small bowlders, and is firm. There is but one cha at all stages. The velocity is swift at high water and medium at low water. The curre the upper side of the bridge is somewhat obstructed by bowlders in the bed of the str Gage heights have an ordinary range of 3 feet. During [redacted] channel to such an extent as to make gage readings i[redacted]

At all normal stages discharge measurements are [redacted] below the bridge. High-water measurements are [redacted]

bridge to which the gage is attached. The initial point for soundings is a nail driven the guard rail of the upstream side of the bridge directly above the gage rod.
ıe gage was read twice daily during 1905 by Elbert E. Smith, who lives about three-ıhs of a mile south of the station. It consisted originally of a staff attached vertically post driven into the bed of the stream and fastened at the top to the end of the bridge. gage was washed out June 11, 1905, and was replaced by a sloping gage, which was ted 2 feet above the original one. The rod is set sloping in the bank and fastened to e posts set firmly in the ground. It reads from 0.5 foot to 5 feet. The datum of the gage is the same as that of the old one. The bench mark is the top of an iron rod, e-fourths of an inch in diameter and 2½ feet long, with an L-shaped bend at the r end, resting on a granite bowlder, 14 inches in diameter, which is set 2 feet under nd, 30 feet northeast of the gage; elevation, 5.31 feet above the zero of the gage.
description of this station, with gage-height and discharge data, is contained in Water-ply Paper No. 131 of the United States Geological Survey, pages 69–70.

Discharge measurements of McIntyre Creek at Gleneyre., Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
22.....	W. A. Lamb.....	32	52	3.71	3.20	193
22.....	.....do.....	33	59	2.59	2.85	153
19.....	.....do.....	24	20	1.65	1.90	33
ust 6.....	.....do.....	21	14	1.50	1.75	21
ıst 20.	.....do.....	12	15	.80	1.63	12
ember 21...	.....do.....	10	13	.60	1.55	7.8

ɔTE.—Measurements made at different sections.

Daily gage height, in feet, of McIntyre Creek at Gleneyre, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept	Day.	Apr.	May.	June.	July.	Aug.	Sept.
.....	1.52	1.75	4.15	2.75	1.82	1.58	17.....	1.58	1.88	3.75	1.82	1.62	.....
.....	1.52	1.8	4.15	2.55	1.82	1.58	18.....	1.58	1.88	3.55	1.82	1.62	.....
.....	1.52	1.8	4.35	2.5	1.78	1.58	19.....	1.58	1.88	3.35	1.8	1.62	.....
.....	1.55	1.8	4.35	2.48	1.78	.....	20.....	1.58	1.85	3.25	2.0	1.62	.....
.....	1.55	1.8	4.3	2.25	1.78	.....	21.....	1.58	3.1	3.2	1.92	1.62	.....
.....	1.55	1.8	4.1	2.35	1.75	.....	22.....	1.58	3.1	2.75	1.92	1.62	.....
.....	1.55	1.8	3.95	2.35	1.72	.....	23.....	1.58	3.2	2.92	1.92	1.62	.....
.....	1.55	1.8	3.95	2.08	1.72	.....	24.....	1.58	3.2	2.88	1.9	1.62	.....
.....	1.55	1.8	3.95	2.02	1.72	.....	25.....	1.58	3.2	2.88	1.92	1.62	.....
.....	1.55	1.8	4.05	2.02	1.72	.....	26.....	1.58	3.2	2.82	1.92	1.62	.....
.....	1.62	1.8	4.05	1.98	1.72	.....	27.....	1.58	3.2	2.8	1.92	1.62	.....
.....	1.68	1.85	4.75	1.98	1.72	.....	28.....	1.65	3.5	2.75	1.88	1.64	.....
.....	1.68	1.82	4.55	1.98	1.72	.....	29.....	1.65	3.62	2.75	1.88	1.62	.....
.....	1.58	1.88	4.35	1.98	1.72	.....	30.....	1.65	3.95	2.75	1.88	1.58	.....
.....	1.58	1.88	4.15	1.98	1.72	.....	31.....	.....	4.05	.....	1.88	1.58	.....
.....	1.58	1.88	3.95	1.98	1.72	.....							

ɔTE.—Gage heights estimated June 11–19.

Station rating table for McIntyre Creek at Gleneyre, Colo., from April 1 to September 3, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.50	5	2.40	92	3.30	212	4.20	340
1.60	11	2.50	105	3.40	226	4.30	355
1.70	18	2.60	118	3.50	240	4.40	370
1.80	26	2.70	131	3.60	254	4.50	385
1.90	35	2.80	144	3.70	268	4.60	400
2.00	45	2.90	157	3.80	282	4.70	415
2.10	56	3.00	170	3.90	296	4.80	430
2.20	68	3.10	184	4.00	310		
2.30	80	3.20	198	4.10	325		

The above table is applicable only for open-channel conditions. It is based on twelve discharge measurements made during 1904–5, and is well defined between gage heights 1.6 feet and 3.2 feet.

Estimated monthly discharge of McIntyre Creek at Gleneyre, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	14	6	10.1	6
May	318	22	98.2	6,0
June	422	138	263	15,6
July	138	26	52.5	3,2
August	28	10	17.0	1,0
The period				26,5

SOUTH PLATTE RIVER.

DESCRIPTION OF BASIN.

The headwaters of the South Platte have their sources in the mountainous region su rounding the large basin near the center of the State of Colorado known as South Park an in the long eastern slopes of the high mountains forming the Continental Divide. Th general course of the stream is eastward to Lake George, thence through Platte Canyo northward to the junction with Cache la Poudre River near Greeley, and thence eastwar until it joins the North Platte at the town of North Platte, Nebr.

The drainage basin, which is about 20,000 square miles in extent above Julesburg, Colo. is bisected in an irregular way by the channel of the South Platte. To the north and wes lies the mountainous portion, which consists of a long, narrow strip lying in a north-south direction along the foothills from a point a short distance within Wyoming to Palmer Lake Colo. This area produces at least 90 per cent of the total run-off of the basin. South and east of the river the basin lies entirely within the plains region.

The mountainous region consists of peaks and jagged masses of granite, with sedimentary rocks cut and gashed by stream channels along the foothills. The stream gradients are steep, and many of the streams consist of series of cascades and rapids. The soil cover as a whole is light, and except during spring freshets or heavy storms the streams are remark ably free from sediments in suspension. The forest cover of the mountains, consistin originally of coniferous trees, is rapidly disappearing, but through the occurrence of fires foothold has been furnished for the deciduous aspen, which is gradually increasing i dominion. The South Platte, Plum Creek, and Medicine Bow forest reserves are in pa comprised within this area.

The lower basin, somewhat broken and scarred along the foothills, gradually merges fa ther east into the undulating prairies so characteristic of the Great Plains east of the Rock

The soils of the plains are the product of the disintegration of shales and sand-
he Laramie formation and range from adobe clays to sandy loams. The con-
etation is largely native grasses, the only timber being a few bunches of scraggly
ls along the stream channels and small patches of pine, cedar, and piñon along
portions.

ıtion varies from 25 inches along the Continental Divide, where the greater part
wfall, to 14 to 17 inches among the foothills. Evaporation records are meager.
ıountainous region the flow of the South Platte and its tributaries is perennial;
plains area the volume is greatly diminished, owing to the fact that the normal
completely diverted for irrigation, the acreage capacity of the canals far exceed-
ıacity of the river. At North Platte, Nebr., just above the mouth of the river,
channel is dry for the greater part of the year or consists of several small chan-
ng a few second-feet of water.

utaries of the South Platte comprise, first, the small streams that rise on the
pes of the Rocky Mountains, and, second, the plains streams. The mountain
nish a perennial supply of water, the amount of which, however, varies with the
eing light during the latter part of the summer and in the fall and winter, and
ıg the spring floods. This water is almost entirely diverted for irrigation and
ıach the South Platte except in times of heavy floods. The principal streams of
ıre Bear, Clear, Boulder, and St. Vrain creeks and Big Thompson and Cache la
ers. The plains streams are all intermittent in their nature and furnish water
g storms or in the season of melting snow. The chief streams of this class are
ıne Tree, Kiowa, Boxelder, Bijou, Beaver, and Pawnee creeks.

th Platte is subject to periodic floods, which occur in May and June, the magni-
ng from year to year with seasonal precipitation and temperature. At Julesburg,
tern margin of the basin in Colorado, the stream may vary from no flow up to
ınd-feet.

tion in regard to this basin is contained in the following publications of the
ıtes Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-
per):

ın: Ann 18, iv, p 159; 19, iv, p 311; 20, iv, pp 277-279; 21, iv, p 200; Bull 140, pp 102-103.
areas: Bull 140, p 103.
surveys: Ann 13, iii, pp 82-91.
nd river stations, map: WS 75, p 131.
ata: WS 75, pp 131-135, 137. *See also* WS 74.
ırage possibilities: Ann 22, iv, pp 314-317.

SOUTH PLATTE RIVER AT SOUTH PLATTE, COLO.

tion was established March 28, 1902, at the wagon bridge crossing the South
ut 150 feet below the junction of North and South forks at the town of South
tation on the Colorado and Southern Railway about 9 miles above the mouth of
ı. May 7, 1905, the old station was abandoned and a new station established at
) feet below the county bridge. The station is very near the Colorado and South-
ıy station and is easily accessible from Denver.

tion is of special importance, its location being above the diverting gates of all
ditches and also above the intake of the Denver Union Water Company, which
ı greater part of its supply from the South Platte, a few miles below. The loca-
ı Cheesman storage reservoir on the South Fork 20 miles above this station and
ıplated installation of large power plants on the two forks at points above also
importance of the station as a base from which to secure data. Bridges across
above the main station allow of measurements being made on these streams,
ıecking all gagings on the main stream.

vagon bridge the channel is straight for 250 feet above and 400 feet below. The
is the side of the mountain. At ordinary stages the left bank is part of the old
about 100 feet wide. At extremely high water the Colorado and Southern road-

bed forms the left bank. The stream is divided into two channels by the central pier of the bridge, the right channel being the deeper and carrying most of the water. The current is rough and rapid beneath the bridge, but becomes more even below. An old abutment foundation directly under the left end of the bridge interferes with the current at high stages.

At the station established May 7, 1905, the channel is straight for about 150 feet above and 75 feet below the cable section and is fairly uniform in width. The right bank is composed of granite bowlders and stands about 12 feet above low water. The left bank is the Colorado and Southern Railway embankment and is lined with a light growth of willows. Each bank has a slope of about 45°, and neither overflows. The bed of the stream is composed primarily of granite bowlders, the interstices being filled in with cobblestones and gravel. Upon this bed a loose deposit of disintegrated granite shifts constantly. During high water this deposit is entirely scoured out, but is immediately replaced with decreased flow. There is but one channel at all stages. The current is swift at high water and moderate at low. During extreme cold weather the channel is entirely covered with ice, but owing to the high gradient and the shifting bed accurate gage heights can not be obtained.

At the original station high-water measurements were made from the lower side of the two-span highway bridge to which the gage was attached, the initial point for soundings being the river face on the right abutment. At a gage height of 2.3 feet or less measurements were made by wading about 250 feet below the bridge.

Discharge measurements at the new station are made by means of a car, cable, and tagged and stay lines. The initial point for soundings is the zero on the tagged wire, about halfway between low water and the top of the right bank. At low water discharge measurements may be made by wading.

The original gage consisted of a vertical timber, reading from zero to 7 feet, fastened to the upper side of the center pier of the highway bridge. This gage was referred to a regulation metal bench-mark tablet in the cliff about 75 feet from the south end of the bridge; elevation, 18.43 feet above zero of gage.

The gage established May 7, 1905, was read twice daily, morning and evening, by Miss E. H. Jardine. It consists of an inclined staff, graduated from 1 foot to 9 feet, and is bolted to a bowlder on the right bank 100 feet above the cable. The bench mark is a standard United States Geological Survey tablet cemented into the top of a granite shelf near the south end of the cable and just above the gage rod; elevation, 17.63 feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey.

Description: 84, pp 89–90; 99, pp 203–204; 131, pp 70–71.
Discharge: 84, p 90; 99, pp 204, 207; 131, p 72.
Discharge, monthly: 84, p 92; 99, p 206; 131, p 73.
Gage heights: 84, p 91; 99, pp 204–205; 131, p 72.
Rating tables: 84, p 91; 99, pp 205–206; 131, p 73.

Discharge measurements of South Platte River at South Platte, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	R. I. Meeker	.....	.....	.....	1.42	203
.....	M. C. Hinderlider	78	271	4.42	3.75	1,197
.....	M. P. Beeson	83	342	4.92	4.35	1,683
.....	Hinderlider and Hoyt	82	296	4.22	4.02	1,249
.....	M. P. Beeson	83	360	5.39	4.90	1,940
.....	.....do	78	220	3.77	3.20	830
.....	.....do	77	176	2.90	2.50	510
.....	.....do	75	119	2.25	1.90	268
.....	.....do	75	123	2.13	1.90	262
.....	.....do	75	139	2.48	2.20	345
5...	R. I. Meeker	76	103	2.78	2.18	286
5...	.....do	75	121	3.02	2.40	365
6...	M. P. Beeson	75	132	2.82	2.38	373
7...	R. I. Meeker	75	119	2.87	2.32	342
12...	.....do	75	100	2.69	2.10	269
13...	.....do	75	98	2.74	2.10	269
.....	.....do	74	73	2.16	1.67	158

the sum of the measurements on two forks. The gage height is doubtful. The old gage 62 feet.

Daily gage height, in feet, of South Platte River at South Platte, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	.....	4.35	4.3	2.4	2.3	2.2	1.7	1.7
.....	.....	4.35	4.15	2.35	2.5	2.2	1.7	1.78
.....	.....	4.1	4.35	2.35	2.38	2.2	1.7	1.78
.....	.....	4.0	4.5	2.2	2.32	2.2	1.7	1.8
.....	.....	3.95	4.75	2.1	2.25	2.3	1.7	1.8
.....	1.65	3.75	4.55	2.1	2.3	2.4	1.7	1.78
.....	1.98	3.65	4.75	2.1	2.3	2.32	1.7	1.9
.....	2.18	3.5	5.05	2.15	2.2	2.3	1.7	1.8
.....	2.35	3.45	4.95	2.2	2.2	2.3	1.6	1.8
.....	2.55	3.7	4.9	2.2	2.1	2.25	1.6	1.75
.....	2.35	3.7	4.85	2.1	2.1	2.2	1.7	1.7
.....	2.3	3.7	4.5	2.1	2.3	2.12	1.7	1.75
.....	2.35	3.8	4.6	2.1	2.38	2.1	1.7	1.75
.....	2.32	3.75	4.5	2.1	2.35	2.1	1.7	1.82
.....	2.45	3.65	4.2	2.1	2.25	2.02	1.72	1.8
.....	2.32	3.7	3.95	2.05	2.15	2.0	1.75	1.8
.....	2.35	3.8	3.8	1.92	2.08	2.0	1.82	1.8
.....	2.5	3.85	3.6	1.8	1.95	2.0	1.8	1.8
.....	2.65	3.9	3.38	1.8	1.9	2.0	1.8	1.6
.....	2.45	4.1	3.2	1.9	1.9	2.0	1.7	1.6
.....	2.3	4.1	3.05	2.0	1.8	2.0	1.7	1.75
.....	2.45	4.05	2.95	2.0	1.8	1.9	1.78	1.65
.....	2.55	4.2	2.9	2.0	1.8	1.9	1.8	1.65
.....	2.62	4.35	2.85	2.3	1.95	1.8	1.75	1.6
.....	2.55	4.4	2.7	2.15	2.0	1.7	1.7	1.6
.....	2.85	4.4	2.6	2.0	2.0	1.7	1.7	1.6
.....	3.15	4.45	2.55	2.1	2.1	1.7	1.7	1.6
.....	3.65	4.3	2.4	2.15	2.1	1.7	1.7	1.6
.....	3.9	4.0	2.4	2.2	2.1	1.7	1.8	.....
.....	4.05	3.95	2.4	2.2	2.3	1.7	1.8	.....
.....	.....	4.0	.....	2.2	2.2	.....	1.75	.....

Station rating table for South Platte River at South Platte, Colo., from April 6 to July 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.60	185	2.50	495	3.40	950	4.30	1,550
1.70	210	2.60	540	3.50	1,010	4.40	1,625
1.80	240	2.70	585	3.60	1,075	4.50	1,700
1.90	270	2.80	630	3.70	1,140	4.60	1,775
2.00	305	2.90	680	3.80	1,205	4.70	1,850
2.10	340	3.00	730	3.90	1,270	4.80	1,930
2.20	375	3.10	780	4.00	1,340	4.90	2,010
2.30	415	3.20	835	4.10	1,410	5.00	2,090
2.40	455	3.30	890	4.20	1,480	5.10	2,170

The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during the first part of 1905, and is fairly well defined between gage heights 1.9 fee and 5 feet. Owing to shifting conditions between July 24 and September 5 the rating tables have been applied indirectly.

Station rating table for South Platte River at South Platte, Colo., from August 1 to November 28, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.60	142	1.90	210	2.20	300	2.50	420
1.70	162	2.00	237	2.30	335	2.60	465
1.80	185	2.10	267	2.40	375		

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during the latter part of 1905, and is well defined between gage heights 1.7 feet and 2. feet.

Estimated monthly discharge of South Platte River at South Platte, Colo., for 1905.

[Drainage area, 2,612 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth i inches
April 6-31	1,375	198	563	27,920	0.216	0.2
May	1,662	980	1,321	81,220	.506	.5
June	2,130	455	1,259	74,920	.482	.5
July	455	240	340	20,900	.130	.1
August	405	190	306	18,830	.117	.1
September	375	162	253	15,060	.097	.1
October	190	142	167	10,270	.064	.0
November 1-28	210	142	169	9,386	.065	.0
The period				258,500		

SOUTH FORK OF SOUTH PLATTE RIVER AT SOUTH PLATTE, COLO.

This station was established May 8, 1905, for the purpose of collecting data in regard the run-off of the South Fork drainage basin and also to furnish information concerni power and irrigation possibilities on the stream. It is located about 500 feet above t junction of North and South forks of South Platte River, in T. 7 S., R. 20 W., and is abo 700 feet above the wagon bridge at which the old station on the South Platte was locate

nel is straight for about 300 feet above and 150 feet below the station. The right oam and gravel and slopes up to a narrow strip of bottom land which is covered ıwood trees. The left bank is more abrupt and about 7 feet high; it is com- ıvel, but has a scant growth of vegetation. Both banks overflow at extreme high ıe bed of the stream is primarily of cobblestones, which are covered by a shifting disintegrated granite along the right bank. This deposit is comparatively uni- ·ven throughout. There is but one channel at all stages. The current is swift ter and moderate at low water. Gage heights range from 1 foot to 6 feet.

e measurements are made by means of a cable, car, and stay and tagged lines. point for soundings is the zero of the tagged wire, which is located above ordi- ıater line on the right bank. Measurements at low water may be made by the cable station.

', which was read twice daily during 1905 by Miss E. H. Jardine, consists of an ıber firmly bolted in place to a cottonwood tree on the left bank. It is graduated o 8.6 feet. The bench mark is a spike driven horizontally 1 foot above the ground ıt side of a 6-inch cottonwood tree to which the cable is fastened on the left bank; bove the zero of the gage, 8.19 feet.

neasurements of South Fork of South Platte River at South Platte, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec. ft.*
...	R. I. Meeker	42	52	23.3	1.60	121
...	M. C. Hinderlider	59	171	4.87	3.48	83ɔ
...	M. P. Beeson	62	175	46.7	3.50	818
...	....do	63	183	4.60	3.65	843
...	Hoyt and Hinderlider	60	156	4.26	3.20	665
...	M. P. Beeson	63	214	4.11	4.30	879
...	....do	59	111	3.48	2.50	387
...	....do	56	80	2.36	1.90	189
...	....do	56	58	1.60	1.50	93
...	....do	56	65	1.51	1.50	98
...	....do	55	63	2.44	1.80	154
...	....do	58	72	2.90	2.20	209
...	R. I. Meeker	58	73	3.12	2.20	228
...	M. P. Beeson	58	79	2.85	2.17	225
...	R. I. Meeker	58	75	3.03	2.16	227
2...	....do	56	66	2.83	2.00	187
3...	....do	56	65	2.77	1.97	180
4...	....do	55	62	2.68	1.90	166
...	....do	54	51	2.18	1.60	111

Daily gage height, in feet, of South Fork of South Platte River at South Platte, Colo., for 19

Day.	May.	June.	July.	Aug.	Sept.	Oct.	No
1	.....	3.3	1.7	2.0	2.1	1.4	
2	.....	3.3	1.65	2.2	2.2	1.4	
3	.....	3.3	1.65	2.2	2.2	1.4	
4	.....	3.65	1.55	2.18	2.2	1.4	1
5	.....	4.0	1.5	2.1	2.1	1.4	1
6	.....	4.0	1.5	2.1	2.3	1.4	1
7	.....	3.95	1.5	2.0	2.2	1.4	1
8	2.6	4.0	1.55	2.0	2.2	1.4	1
9	2.95	4.3	1.6	2.0	2.2	1.4	1
10	3.4	4.35	1.6	1.95	2.15	1.45	1
11	3.5	4.18	1.6	1.9	2.1	1.4	1
12	3.45	3.8	1.6	2.05	2.0	1.4	1
13	3.5	3.3	1.6	2.2	2.0	1.4	1
14	3.5	3.2	1.6	2.2	1.9	1.45	1
15	3.4	3.1	1.6	2.08	1.9	1.52	1
16	3.4	2.95	1.45	2.0	1.9	1.55	1
17	3.45	2.82	1.38	2.0	1.8	1.6	1
18	3.4	2.7	1.35	1.8	1.8	1.6	1
19	3.55	2.65	1.35	1.8	1.8	1.6	1
20	3.6	2.6	1.42	1.7	1.8	1.6	1
21	3.5	2.4	1.5	1.6	1.8	1.6	1
22	3.5	2.3	1.48	1.6	1.8	1.6	1
23	3.55	2.3	1.5	1.6	1.7	1.55	1
24	3.65	2.25	1.8	1.65	1.62	1.5	1
25	3.65	2.0	1.75	1.65	1.5	1.5	1
26	3.55	2.0	1.6	1.7	1.5	1.5	1
27	3.55	1.9	1.75	1.8	1.5	1.5	1
28	3.45	1.7	1.85	1.8	1.5	1.5	1
29	3.3	1.7	1.9	1.8	1.5	1.6	.....
30	3.2	1.7	1.9	2.0	1.5	1.6	.....
31	3.15	.....	1.9	2.05	.....	1.55	.....

Station rating table for South Fork of South Platte River at South Platte, Colo., from May 8 to November 28, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec. ft.*	*Feet.*	*Sec. ft.*	*Feet.*	*Sec. ft.*	*Feet.*	*Sec. ft.*
1.30	70	2.10	215	2.90	505	3.70	980
1.40	80	2.20	240	3.00	560	3.80	1,045
1.50	95	2.30	270	3.10	615	3.90	1,110
1.60	110	2.40	300	3.20	670	4.00	1,175
1.70	125	2.50	335	3.30	730	4.10	1,240
1.80	145	2.60	370	3.40	790	4.20	1,310
1.90	165	2.70	410	3.50	850	4.30	1,380
2.00	190	2.80	455	3.60	915	4.40	1,450

The above table is applicable only for open-channel conditions. It is based on fifteen dischs measurements made during 1905, and is fairly well defined between gage heights 1.5 feet and 3.5 f The table has been extended beyond these limits.

Estimated monthly discharge of South Fork of South Platte River at South Platte, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
May 8-31	948	370	798	37,990
June	1,415	125	638	37,960
July	165	75	112	6,887
August	240	110	176	10,820
September	270	95	171	10,180
October	110	80	93.4	5,743
November 1-28	110	95	104	5,776
The period				115,400

SOUTH PLATTE RIVER AT DENVER, COLO.

In the spring of 1895 a river station was established at the Twenty-third Street Viaduct in the city of Denver, but observations were discontinued June 18 of the same year, as the location was found to be unfavorable for accurate measurements and the water had fallen below the gage. In July, 1895, a station was established at the Fifteenth Street Bridge. The present station is located at a point immediately below the mouth of Cherry Creek, which enters between the Fourteenth and Fifteenth street bridges.

The station is important principally from the fact that it is used as a training station for the instruction of young hydrographers in the field use of current meters.

The channel is straight at low water for 100 feet above and 500 feet below the gage rod and at high water for several blocks each way from the Fifteenth Street Bridge. The average section of the bridge is 200 feet in width, confined by slag levees which overflow only in extreme floods. There is but one channel at all stages. The current is sluggish at low water and swift at high water. Gage heights range from 0.5 foot to 6 feet.

Discharge measurements are made at low water by wading at a point above or below the gage; high-water measurements are made from the 200-foot single-span steel bridge at Fifteenth street, the initial point for sounding being the edge of the right abutment of the bridge.

During 1905 the gage was read twice each day by Clarence Crisman. The original gage consisted of inclined timbers fastened to posts driven into the bank. In August, 1898, another inclined gage rod, reading the same as the one on the right bank, was placed on the left side. This gage rod was washed out by the high water of June, 1900, which also removed the sand bar in front of the rod on the right hand side, making it available at low-water stages, and since that time readings have been taken from the latter rod or from rods which replaced it and were located at the same point. May 15, 1901, a T rail was placed on the site of the right-bank rod, which had been stolen. This rail was embedded in an inclined position in the slag bank. All readings were taken from this rail from May 15, 1901, to June 9, 1903, when it was stolen. June 10, 1903, a vertical timber was placed at the same point and fastened to a cottonwood tree, the zero of the rod being set at the same elevation as the zero of the old gage. The gage is located on the right bank about 60 feet above the Sixteenth Street Viaduct; the rod is graduated from zero to 7 feet. The original bench mark is a cross on top of the east abutment of the Fifteenth Street Bridge, on the north corner, 107 feet southwest of the gage; it is marked "B. M.," and its elevation is 6.15 feet above the 9-foot mark on the original Fifteenth street gage rod, which has since been destroyed. The bench mark for the present gage is a cross cut in the capstone of the south end of the south abutment of the right masonry pier of the Sixteenth Street Viaduct; elevation, 11.90 feet above the zero of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull.=Bulletin; WS=Water-Supply Paper.

Description: Ann 18, iv, pp 162-163; Bull 140, pp 104-105; WS 15, p 88; 27, p 77; 37, p 225; 49, p 281; 66, p 30; 84, pp 86-87; 99, pp 199-200; 131, pp 74-75.

Discharge: Ann 13, iii, p 85; 18, iv, p 163; Bull 140, p 105; WS 15, p 88; 27, p 86; 37, p 225; 49, p 281; 66, p 30; 84, p 87; 99, p 201; 131, p 75.

Discharge, daily: WS 131, p 76.

Discharge, monthly: Ann 18, iv, p 165; 19, iv, p 314; 20, iv, pp 263, 279; 21, iv, p 202; 22, iv, p 319; Bull 140, p 106; WS 75, pp 127, 136; 84, p 88; 99, p 203; 131, p 77.

Discharge, yearly: Ann 20, iv, p 54.

Gage heights: Bull 140, p 105; WS 11, p 53; 15, p 88; 27, p 84; 37, p 226; 49, p 282; 66, p 30; 84, p 88; 99, pp 201-202.

Hydrographs: Ann 13, iii, p 85; 18, iv, p 166; 19, iv, p 314; 20, iv, p 280; 21, iv, p 202; 22, iv, p 319.

Rainfall and run-off relation: Ann 20, iv, p 266; WS 75, p 137.

Rating tables: Ann 18, iv, pp 164-165; 19, iv, p 313; Bull 140, p 105; WS 27, p 89; 39, p 448; 52, p 517; 66, p 171; 84, p 88; 99, p 202.

Discharge measurements of South Platte River at Denver, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
February 25	M. P. Beeson	60	91	2.91	1.75	265
March 4[a]	do	64	81	2.0	1.40	162
March 11	do	50	61	1.36	1.00	83
Do	do	50	61	1.34	1.00	82
March 25	do	55	90	2.39	1.41	215
April 4	do	89	155	3.09	2.11	479
April 8	do	92	155	3.67	2.30	569
April 8[a]	do				2.30	555
April 15	do	90	154	3.56	2.20	549
April 22	do	90	186	3.56	2.45	662
April 25	do	184	322	4.15	3.10	1,335
April 27	do	185	404	4.53	3.42	1,840
May 5	do	166	389	4.49	3.20	1,747
June 10	do	175	441	3.93	3.00	1,732
June 29	do	162	188	2.40	1.86	451
July 12	do	140	121	2.08	1.45	252
July 29[a]	do	105	132	2.28	1.50	301
September 16	do	129	105	1.71	1.25	180
November 4	W. A. Lamb	92	59	2.15	1.00	127
November 14[a]	do	62	58	1.09	.90	63
November 25[a]	do	68	49	1.88	.84	92
December 8	do	94	82	1.85	1.29	152

[a] Made at different section.

Daily gage height, in feet, of South Platte River at Denver, Colo., for 1905.

›y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.9	0.88	1.55	1.75	3.5	3.0	1.8	1.85	1.18	0.8	0.96	0.75
.....	.88	.78	1.48	2.05	3.48	3.0	1.8	1.82	1.25	.75	.95	.7
.....	.9	.72	1.5	2.15	3.52	3.02	1.72	1.75	1.25	.75	.9	.7
.....	.9	.7	1.4	1.95	3.5	3.2	1.65	1.7	1.35	.78	.9	.7
.....	.9	1.0	1.35	1.95	3.4	3.4	1.58	1.6	1.42	.8	.9	.75
.....	.9	1.0	1.35	2.05	3.25	3.25	1.42	1.6	1.55	.75	.9	.8
.....	.9	.9	1.45	2.22	3.12	3.08	1.5	1.5	1.4	.8	.9	.8
.....	.88	.9	1.4	2.35	3.12	3.02	1.7	1.45	1.3	.8	.95	1.1
.....	.8	.82	1.15	2.52	3.18	3.02	1.68	1.35	1.35	.8	.98	1.25
.....	.75	.78	1.0	2.7	3.5	3.05	1.6	1.38	1.35	.75	.9	1.0
.....	.72	.72	1.0	2.85	3.42	3.0	1.5	1.58	1.32	.75	.9	.9
.....	.65	.7	1.0	2.45	3.4	3.0	1.42	1.55	1.45	.78	.9	.88
.....	.6	.7	.95	2.25	3.42	2.6	1.45	1.55	1.3	.88	.95	.85
.....	.6	.75	.95	2.2	3.38	1.95	1.25	1.5	1.15	.92	1.0	.82
.....	.6	.8	1.05	2.3	3.3	1.82	1.22	1.5	1.12	1.05	.92	.8
.....	.7	.8	1.18	2.25	3.3	1.8	1.28	1.4	1.1	1.15	.9	.8
.....	.98	.85	1.25	2.25	3.3	1.82	1.05	1.25	1.15	1.22	.9	.8
.....	1.55	.9	1.35	2.25	3.35	1.82	.98	1.2	1.15	1.25	.9	.8
.....	1.2	1.02	1.45	2.3	3.35	1.6	1.12	1.15	1.05	1.28	.9	.8
.....	1.0	1.22	1.9	2.28	3.42	1.6	1.15	.98	1.02	1.2	.9	.8
.....	1.0	1.45	1.75	2.32	3.5	1.5	1.28	1.02	1.0	1.1	.9	.8
.....	1.0	1.75	1.7	2.35	3.5	1.5	1.4	1.0	1.08	.75	.85	.8
.....	1.12	1.88	1.55	2.6	3.48	2.0	1.55	.95	1.0	.9	.82	.8
.....	1.18	1.78	1.45	2.8	3.45	2.08	1.52	.92	.92	.9	.82	.82
.....	1.12	1.68	1.15	3.08	3.4	2.02	1.42	1.0	1.0	.85	.8	.82
.....	1.12	1.65	1.1	3.1	3.38	2.1	1.42	1.02	1.02	.82	.8	.78
.....	1.18	1.5	1.25	3.4	3.45	2.05	1.48	1.05	1.05	.82	.8	.7
.....	1.1	1.42	1.45	3.55	3.32	2.0	1.5	1.02	1.02	.9	.8	.7
.....	.95	.....	1.5	3.5	3.22	1.8	1.5	1.02	1.02	.8	.8	.68
.....	.95	.....	1.35	3.55	3.0	1.8	1.55	1.02	1.12	.9	.8	.7
.....	.9	.....	1.35	.....	3.0	.....	1.75	1.08	.....	1.0	.....	.7

Daily discharge, in second-feet, of South Platte River at Denver, Colo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	87	77	196	330	2,014	1,392	410	440	167	92	115	
2	84	64	175	455	1,982	1,392	410	426	184	84	115	
3	87	57	169	505	2,046	1,420	378	398	184	84	106	
4	87	55	159	410	1,014	1,685	350	378	214	88	106	
5	87	95	149	410	1,854	1,998	322	338	235	92	106	
6	87	95	149	455	1,745	1,760	260	338	282	84	106	
7	87	79	169	542	1,434	1,505	290	298	229	92	106	
8	84	79	159	620	1,434	1,420	370	278	199	92	115	
9	73	69	110	736	1,520	1,420	362	242	214	92	121	
10	73	64	85	890	2,014	1,462	330	252	214	84	106	
11	62	56	82	1,045	1,934	1,434	282	322	199	84	101	
12	54	54	82	685	1,902	1,434	252	310	238	88	101	
13	50	54	78	560	1,934	950	263	310	193	88	110	
14	50	59	78	530	1,870	485	199	290	157	112	119	
15	50	65	96	590	1,745	422	190	290	151	137	105	
16	59	65	119	560	1,745	414	208	252	147	157	101	
17	98	72	139	560	1,745	422	151	205	157	171	101	
18	226	78	165	560	1,822	422	137	190	157	178	101	
19	139	96	202	590	1,822	334	165	175	137	187	101	
20	101	96	366	578	1,934	334	171	141	131	167	101	
21	98	175	314	602	2,110	302	220	143	127	147	101	
22	98	270	302	620	2,110	302	260	139	143	84	93	
23	112	322	249	800	2,078	520	318	129	127	108	88	
24	131	282	220	990	2,030	566	306	123	137	108	88	
25	119	246	149	1,324	1,950	530	266	139	127	100	85	
26	119	235	135	1,350	1,918	578	266	143	105	95	82	
27	131	190	165	1,790	2,030	548	290	149	92	95	82	
28	115	169	220	2,030	1,822	520	298	143	88	108	81	
29	90	.....	235	1,950	1,670	422	298	143	84	92	79	
30	90	.....	220	2,030	1,350	422	318	143	92	92	78	
31	82	.....	190	.....	1,350	.....	398	163	.....	127	.....	

NOTE.—The daily discharge was obtained by the indirect method.

Estimated monthly discharge of South Platte River at Denver, Colo., for 1905.

[Drainage area, 3,840 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inch
January	226	50	93.9	5,774	0.024	0
February	322	54	118	6,553	.031	
March	366	78	172	10,580	.045	
April	2,030	330	837	49,800	.218	
May	2,110	1,350	1,836	112,900	.478	
June	1,998	302	894	53,200	.233	
July	410	137	282	17,340	.073	
August	440	123	240	14,760	.062	
September	282	84	164	9,759	.043	
October	187	84	110	6,764	.029	
November	121	78	100	5,950	.026	
December	145	54	71.8	4,415	.019	
The year	2,110	50	410	297,800	.107	

SOUTH PLATTE RIVER NEAR KERSEY, COLO.

This station was established April 7, 1901. It is located at a bridge about 1½ miles north the railroad station at Kersey, which is on the Union Pacific Railroad about 6 miles east Greeley, in T. 5 N., R. 64 W., and was intended to take the place of the station previously aintained at Orchard, Colo. The station was discontinued in the fall of 1903, but was reesblished March 5, 1905, to satisfy the demand for hydrographic data pertaining to the storge of flood waters. The station is below all the important tributaries of the South Platte hich derive their supply from the mountain region and is at about the point where water ould be used to best advantage for storage in reservoirs along the South Platte in northastern Colorado.

The channel is straight for 300 feet above and 400 feet below the station. The banks are mposed of alluvial material, and vary from 5 to 8 feet in height. The right bank is high nd is not liable to overflow except at extremely high water. The left bank is low and not ell defined, as it extends into high timber and overflows at extreme flood stages. The tream bed is composed of shifting sand and gravel. The channel is entirely covered only at extreme high water. At ordinary stages there are two channels and at low water the tream runs very close to the right bank. Scattered trees and brush dot the portion of the ed to the left of the center of the channel. Pile bents with 20-foot centers interfere at low ater by catching drift and also by causing eddy water. The current is fairly swift at igh stages and moderate at low. Gage heights range from 2 to 8 feet on the gage.

Discharge measurements are ordinarily made from the downstream side of the bridge, but t low water measurements are occasionally made by wading. The initial point for soundings is the north face of the right abutment of the bridge on the downstream side. The ridge is of piling, and is about 15° askew.

The gage, which was read once each day by E. K. Plumb, consists of a vertical staff graduated from zero to 8 feet, spiked to the downstream side of the third pile of the bridge from he south end. There is no bench mark, but a spike has been driven at each foot mark into he pile, to which the gage is attached.

Information in regard to this station is contained in the following Water-Supply Papers f the United States Geological Survey:

Description: 66, p 37; 84, p 77; 99, pp 183–184.
Discharge: 66, p 38; 84, p 77; 99 p 184, 207.
Discharge, monthly: 75, pp 130, 136; 84, p 79; 99, p 186.
Gage heights: 66, p 38; 84, p 78; 99, pp 184–185.
Hydrograph: 75, p 132.
Rating tables: 66, p 171; 84, p 78; 99, p 185.

Discharge measurements of South Platte River near Kersey, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
y 6	M. C. Hinderlider	490	1,580	3.82	6.22	6,032
ne 1	Brick and Beeson	529	1.947	3.73	6.80	7,274
y 11	M. P. Beeson	141	172	1.09	2.40	188
tober 3	M. C. Hinderlider	131	142	1.18	2.50	168
tober 12 [a]	do	125	130	2.02	2.72	262

[a] Made at different section.

Daily gage height, in feet, of South Platte River near Kersey, Colo., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.4	2.5	6.3	6.8	2.6	2.75	2.3	2.5	3.2	2.9
2	2.4	3.0	6.1	6.9	2.55	2.75	2.3	2.5	3.3	2.9
3	2.4	3.6	6.22	6.9	2.5	2.5	2.3	2.5	3.3	2.9
4	2.5	3.4	6.5	6.8	2.45	2.5	2.3	2.5	3.3	2.8
5	2.5	3.4	6.35	6.8	2.4	2.5	2.3	2.5	3.3	2.8
6	2.5	3.4	6.3	6.9	2.4	2.4	2.35	2.5	3.3	2.8
7	2.5	3.4	6.25	7.0	2.4	2.4	2.35	2.5	3.3	2.8
8	2.5	3.2	6.2	7.5	2.4	2.4	2.4	2.5	3.0	2.8
9	2.45	3.3	6.1	7.4	2.35	2.4	2.4	2.5	2.95	2.7
10	2.4	3.3	6.0	7.2	2.35	2.4	2.4	2.6	2.95	2.7
11	2.4	3.7	6.0	7.2	2.35	2.4	2.4	2.65	2.9	2.7
12	2.4	3.9	6.1	6.0	2.35	2.5	2.4	2.7	2.9	2.7
13	2.4	4.0	6.0	5.8	2.3	2.5	2.4	2.8	2.9	2.7
14	2.4	4.0	5.95	5.5	2.3	2.45	2.4	2.9	2.9	2.6
15	2.4	3.9	5.9	5.0	2.3	2.45	2.4	2.9	2.85	2.5
16	2.45	3.9	5.85	5.0	2.3	2.45	2.4	2.9	2.85	2.5
17	2.5	3.8	5.8	5.0	2.35	2.45	2.4	2.9	2.8	2.
18	2.6	3.8	5.7	4.5	2.35	2.4	2.4	2.9	2.8	2.
19	2.55	3.9	5.8	4.0	2.35	2.4	2.4	2.9	2.8	2.
20	2.5	3.9	6.0	3.5	2.35	2.4	2.4	2.9	2.8	2.
21	2.55	3.9	6.0	3.2	2.35	2.4	2.4	2.95	2.8	2.
22	2.6	4.0	6.0	3.1	2.35	2.35	2.4	2.95	2.8	2.
23	3.0	3.8	7.75	3.0	2.35	2.35	2.4	2.95	2.85	2.
24	3.0	4.25	7.0	3.0	2.35	2.35	2.4	2.95	2.85	2.
25	2.9	6.0	6.8	2.9	2.3	2.3	2.4	2.95	2.9	2.
26	2.8	5.95	6.6	2.9	2.3	2.3	2.45	2.95	2.9	2.
27	2.75	6.1	6.6	2.8	2.3	2.3	2.45	3.0	2.9	2.
28	2.65	6.25	6.8	2.7	2.3	2.3	2.5	3.0	2.9	2.
29	2.5	6.5	6.9	2.7	2.3	2.3	2.5	3.0	2.9	2.
30	2.5	6.4	7.2	2.6	2.3	2.3	2.5	3.1	2.9	2.
31	2.5	.....	7.25	.....	2.3	2.3	.....	3.1	.....	2.

NOTE. Gage heights estimated March 1–4.

Station rating table for South Platte River near Kersey, Colo., from March 1 to December 3 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.30	140	3.50	1,200	4.70	3,160	5.90	5,410
2.40	160	3.60	1,340	4.80	3,340	6.00	5,610
2.50	190	3.70	1,490	4.90	3,520	6.20	6,010
2.60	230	3.80	1,640	5.00	3,700	6.40	6,420
2.70	280	3.90	1,790	5.10	3,890	6.60	6,840
2.80	350	4.00	1,950	5.20	4,080	6.80	7,260
2.90	440	4.10	2,120	5.30	4,270	7.00	7,680
3.00	550	4.20	2,290	5.40	4,460	7.20	8,110
3.10	670	4.30	2,460	5.50	4,650	7.40	8,550
3.20	800	4.40	2,630	5.60	4,840	7.60	8,990
3.30	930	4.50	2,800	5.70	5,030	7.80	9,450
3.40	1,060	4.60	2,980	5.80	5,220		

The above table is applicable only for open-channel conditions. It is based on five discharge measurements made during 1905 and two during 1903, and is fairly well defined between gage heights 2 feet and 7 feet.

Estimated monthly discharge of South Platte River near Kersey, Colo., for 1905.

[Drainage area, 9,470 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March	550	160	227	13,960	0.024	0.028
April	6,630	190	2,348	139,700	.248	.277
May	9,335	5,030	6,301	387,400	.665	.767
June	8,770	230	4,084	243,000	.431	.481
July	230	140	154	9,469	.016	.018
August	315	140	170	10,450	.018	.021
September	190	140	160	9,521	.017	.019
October	670	190	383	23,550	.040	.046
November	930	350	533	31,720	.056	.062
December	440	280	339	20,840	.036	.042
The period				889,600		

SOUTH PLATTE RIVER NEAR JULESBURG, COLO.

This station was established April 2, 1902. It is located at the wagon bridge crossing the South Platte about 1 mile southeast of Julesburg, Colo., a station at the junction of the main line and the Denver branch of the Union Pacific Railroad.

As this is the last station on the South Platte in Colorado, and as it is also below all irrigation ditches taking water from the South Platte in Colorado with the exception of one, it is of considerable importance for obtaining data relative to the flow of return waters as well as to the natural flow of the main channel.

The channel is straight for 600 feet above and 400 feet below the bridge. The banks are composed of alluvial material and are likely to overflow. The bed, which is about half a mile wide, is composed of shifting sands and at ordinary stages the section is broken by islands covered with undergrowth and vegetation. As a result the stream flow is usually divided into a number of small threads, some of which are too small to measure and at low water are generally estimated. The bed of the stream is dry the larger part of the year. The current is swift during high water but moderate at low. Records are usually discontinued during the winter months.

High-water measurements are made from the bridge, which is one-half mile long and is supported on piles at intervals of 20 feet. The initial point for soundings is the north abutment on the left bank. At low water the flow is divided into a number of small channels which are measured by wading.

The gage, which was read during 1905 by Volney Parker, consists of a vertical staff spiked to a pile of the bridge about 1,600 feet from the north end on the downstream side. The bench mark is a spike driven into the south face of the cap timber on the piling to which the gage is spiked; it is directly over the gage, and is inclosed in a circle of white paint and marked "B. M.;" the elevation of the center of the spike above the zero of the gage is 8.00 feet. The gage is read once daily except during high water, when several observations may be made each day.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: WS 49, p 283; 84, pp 73-74; 99, p 179; 131, pp 77-78.
Discharge: Ann 20, iv, p 302; Bull 140, p 114; WS 49, p 283; 84, p 74; 99, p 180; 131, pp 78, 87.
Discharge, monthly: WS 84, p 75; 99, p 181; 131, p 80.
Gage heights: WS 84, p 74; 99, p 180; 131, p 79.
Rating tables: WS 84, p 75; 99, p 181; 131, p 79.

Discharge measurements of South Platte River, near Julesburg, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis-charg
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-f*
May 6	T. W. Jenkins	1,823	2,253	2.50	3.75	5
May 10	M. C. Hinderlider	1,378	1,968	2.65	3.50	5
May 20	T. W. Jenkins	1,134	1,543	2.68	3.27	4
May 25	do	1,371	1,830	2.59	3.48	4
May 27	do	1,703	2,744	2.69	3.99	7
October 4[a]	M. C. Hinderlider	66	27	1.37	1.05	

[a] Made by wading.

Daily gage height, in feet, of South Platte River near Julesburg, Colo., for 1905.

Day.	Jan.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	I
1	2.55	2.0	1.95	3.65	4.35	0.75	1.63	1.2	1.05	1.5	
2	2.6	2.0	2.5	3.75	4.35	1.5	1.85	1.15	1.05	1.65	
3	2.6	2.0	1.95	3.85	4.0	1.4	2.05	1.15	1.05	1.85	
4	2.6	2.0	1.9	3.85	3.85	1.2	3.0	1.1	1.05	1.9	
5	2.6	2.0	1.95	3.8	3.8	.7	2.8	1.15	1.05	2.0	
6	2.7	2.15	1.95	3.75	3.85	.6	2.9	1.2	1.05	2.0	
7	2.8	2.05	2.5	3.7	3.9	.55	2.75	1.2	1.05	2.0	
8	2.8	2.1	2.5	3.75	4.0	.5	2.3	1.35	1.05	2.25	
9	2.75	2.15	2.5	3.75	4.5	.5	2.2	1.15	1.05	2.0	
10	2.7	2.0	2.1	3.6	4.0	.45	2.15	1.15	1.05	1.9	
11	.....	2.0	2.15	3.45	4.95	.4	2.5	1.1	1.05	1.9	
12	.....	2.5	2.25	3.35	4.95	.4	2.45	1.1	1.15	1.9	
13	2.65	1.95	2.25	3.45	4.0	2.0	2.35	1.1	1.25	2.0	
14	2.65	2.0	2.25	3.5	3.95	1.9	2.3	1.1	1.2	2.0	
15	2.65	2.5	2.5	3.5	3.55	1.8	2.0	1.1	1.25	1.9	
16	2.65	2.1	2.4	3.45	3.5	1.75	2.1	1.15	1.35	1.8	
17	2.7	2.5	2.5	3.35	3.3	1.9	2.15	1.2	1.25	1.75	
18	2.8	2.5	2.55	3.35	3.1	1.8	2.2	1.15	1.3	1.65	
19	2.95	2.2	2.4	3.4	3.0	1.85	2.25	1.15	1.35	1.7	
20	3.15	2.1	2.75	3.3	3.0	1.75	1.75	1.1	1.32	1.6	
21	3.25	2.0	2.7	3.45	2.85	1.7	1.65	1.1	1.35	1.65	
22	.....	1.9	2.65	3.45	2.4	2.0	1.6	1.1	1.4	1.6	
23	.....	1.95	2.7	3.45	1.0	1.95	1.45	1.1	1.4	1.75	
24	.....	1.95	3.5	3.5	.85	1.9	1.3	1.05	1.35	1.65	
25	.....	1.9	3.2	3.5	.95	1.85	1.2	1.05	1.5	1.65	
26	.....	1.9	3.1	4.0	1.0	1.7	1.15	1.05	1.5	1.65	
27	.....	1.9	3.5	4.0	.95	1.65	1.1	1.05	1.45	1.65	
28	.....	1.9	3.4	4.2	.95	1.6	1.1	1.05	1.5	1.65	
29	.....	1.9	3.6	4.3	.95	1.65	1.1	1.0	1.5	1.65	
30	.....	1.8	3.6	4.3	.9	1.75	1.12	1.15	1.5	1.65	
31	.....	1.95	.....	4.35	.....	1.7	1.12	.....	1.5	.....	

NOTE. Gage heights estimated March 1–4.

ation rating table for South Platte River near Julesburg, Colo., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
0.40	9	1.60	175	2.80	2,140	4.00	7,450
0.50	10	1.70	230	2.90	2,490	4.10	7,950
0.60	12	1.80	295	3.00	2,870	4.20	8,460
0.70	15	1.90	375	3.10	3,270	4.30	8,970
0.80	19	2.00	470	3.20	3,690	4.40	9,490
0.90	24	2.10	590	3.30	4,130	4.50	10,010
1.00	30	2.20	730	3.40	4,580	4.60	10,530
1.10	37	2.30	890	3.50	5,040	4.70	11,060
1.20	50	2.40	1,080	3.60	5,510	4.80	11,590
1.30	70	2.50	1,300	3.70	5,980	4.90	12,120
1.40	98	2.60	1,550	3.80	6,460	5.00	12,650
1.50	131	2.70	1,830	3.90	6,950		

The above table is applicable only for open-channel conditions. It is based on ten discharge measurements made during 1904–5, and is fairly well defined between gage heights 1 foot and 4 feet.

Estimated monthly discharge of South Platte River near Julesburg, Colo., for 1905.

[Drainage area, 20,600 square miles.]

0 Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
anuary (19 days)	3,910	1,425	2,018	76,050	0.098	0.069
larch	1,300	295	581	35,720	.028	.032
pril	5,510	375	1,903	113,200	.092	.103
lay	9,230	4,130	5,913	363,600	.287	.331
une	12,380	24	4,804	285,800	.233	.260
uly	470	9	199	12,240	.0097	.011
ugust	2,870	37	695	42,730	.034	.039
eptember	84	34	41.8	2,487	.0020	.0022
ctober	131	34	68.8	4,230	.0033	.0038
ovember	810	131	310	18,450	.015	.017
ecember	810	202	565	34,740	.027	.031
The period				989,200		

CLEAR CREEK AT FORKSCREEK, COLO.

Clear Creek rises on the eastern slope of the Rocky Mountains, flows eastward, and unites ith the South Platte about 6 miles north of Denver. Its drainage basin comprises a nar- w strip of exceedingly mountainous country, consisting entirely of granitic rocks, in many aces barren of soil, covered with scattered patches of coniferous trees, such as pine, spruce, d fir, remnants of the once extensive forests of the area. The basin includes also a small rtion of Great Plains territory. Two of Colorado's oldest mining districts lie wholly ithin this basin, and in these districts the water of the upper tributaries of Clear Creek is ed to such an extent that the name has long since become a misnomer. From Forkscreek Golden, a distance of 13 miles, the creek flows in a canyon and has a total fall of 1,225 et, an average of 94 feet per mile. Before the stream leaves the canyon a large volume water is diverted by the canals that wind sinuously along the steep, rocky canyon sides,

and the entire normal flow of the creek between Golden and Denver is used for the ir tion of lands in Clear Creek Valley.

The gaging station was established May 29, 1899. It is located at the United States logical Survey bridge, just below the Colorado and Southern Railway bridge at the rail station, in T. 33 S., R. 72 W.

The station is important because of its location above all diversions and also becau contemplated power development.

The channel is narrow and straight for 30 feet above and 150 feet below the station. right bank is the side of the mountain; the left is the retaining wall of the Colorado Southern Railway embankment; both banks are high and can not overflow. The be the stream is composed of cobblestones and bowlders, over which a shallow deposit of forms during low-water stages, which is scoured out at high water. There is but one c nel at all stages. The current is swift at low water and very rapid at high water. surface of the water is rough and high-water measurements are difficult to obtain. Du the winter ice blocks the channel and interferes with gage readings.

Discharge measurements are made from a substantial single-span footbridge, to whicl gage is attached. The initial point for soundings is a brass-headed nail in the hand ra the end of the bridge, and is marked zero with white paint.

The chain gage, which was read twice each day during 1905 by C. W. Hoisington, was inally fastened to the retaining wall on the left bank 30 feet below the footbridge. Jul 1905, the gage was removed to the footbridge on account of the settling of the crib wo which it was attached. The length of the chain is 19.37 feet. The bench mark is a stan aluminum cap set in the bowlder, to which the downstream stay line of the bridge is anch on the right bank; elevation above the zero of the gage, 9.50 feet.

Information in regard to this station is contained in the following publications o United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 37, pp 228–229; 49, pp 285–286; 66, p 31; 84, p 84; 99, pp 197–198; 131, p 80.
Discharge: WS 37, p 229; 49, p 286; 66, p 31; 84, p 84; 99, p 198; 131, p 81.
Discharge, monthly: Ann 21, iv, p 205; 22, iv, p 322; WS 75, p 128; 84, p 86; 99, p 199; 131, p 82.
Gage heights: WS 37, p 229; 49, p 286; 66, p 32; 84, p 85; 99, p 198; 131, p 81.
Hydrographs: Ann 21, iv, p 205; 22, iv, p 322.
Rating tables: WS 39, p 448; 52, p 517; 66, p 171; 84, p 85; 99, p 199; 131, p 82.

Discharge measurements of Clear Creek at Forkscreek, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D ch
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Se*
April 14	T. E. Brick	29	32	4.12	2.23	
June 2	M. P. Beeson	36	121	8.61	3.85	
June 16	do	36	138	9.00	4.10	
July 19	do	36	83	3.19	2.94	
July 19	J. C. Stevens	36	85	4.22	2.94	
July 27	M. P. Beeson	36	83	3.37	2.79	
October 19	R. I. Meeker	28	28	2.57	1.74	
October 19	do	28	26	2.23	1.62	

Daily gage height, in feet, of Clear Creek at Forkscreek, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
	1.83	2.7	3.96	3.45	2.68	2.23	2.03
	1.83	2.78	3.99	3.4	2.62	2.23	1.98
	1.83	2.8	4.14	3.4	2.62	2.23	1.98
	1.73	2.8	4.39	3.35	2.58	2.2	1.93
	1.68	2.6	4.59	3.38	2.58	2.16	1.9
	1.83	2.66	4.49	3.32	2.58	2.16	1.88
	2.03	2.66	4.49	3.32	2.6	2.13	1.86
	2.08	2.7	4.56	3.3	2.62	2.13	1.88
	2.05	2.86	4.59	3.28	2.58	2.13	1.83
	2.13	2.8	4.52	3.22	2.5	2.1	1.83
	2.03	2.86	4.36	3.12	2.84	2.08	1.82
	2.18	2.86	4.39	3.12	2.7	2.08	1.82
	2.18	2.83	4.32	3.18	2.5	2.08	1.82
	2.18	2.8	4.24	3.3	2.5	2.06	1.77
	2.16	2.72	4.22	3.35	2.48	2.03	1.77
	2.16	2.76	4.22	3.32	2.48	2.03	1.77
	2.16	2.89	4.15	3.32	2.52	2.03	1.85
	2.2	3.09	4.08	3.35	2.4	2.03	1.85
	2.2	3.16	4.05	3.2	2.3	2.03	1.77
	2.13	3.26	3.95	2.95	2.3	2.0	1.72
	2.1	3.44	3.95	2.92	2.25	1.98	1.72
	2.16	3.59	3.88	2.88	2.25	1.98	1.75
	2.16	3.64	3.82	2.82	2.22	1.98	1.72
	2.13	3.69	3.78	2.82	2.25	1.98	1.62
	2.16	3.56	3.78	2.82	2.22	1.98	1.57
	2.26	3.59	3.65	2.78	2.25	1.98	1.67
	2.5	3.64	3.55	2.78	2.25	1.98	1.67
	2.6	3.76	3.52	2.82	2.24	1.98	1.67
	2.6	3.79	3.5	2.72	2.24	1.98	1.67
	2.6	3.76	3.45	2.7	2.22	1.98	1.57
	.....	3.89	.....	2.7	2.21	.....	1.52

ion rating table for Clear Creek at Forkscreek, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.50	47	2.30	160	3.10	390	3.90	1,010
1.60	55	2.40	180	3.20	440	4.00	1,130
1.70	65	2.50	200	3.30	500	4.10	1,260
1.80	75	2.60	230	3.40	560	4.20	1,400
1.90	90	2.70	260	3.50	630	4.30	1,540
2.00	105	2.80	290	3.60	710	4.40	1,690
2.10	120	2.90	320	3.70	800	4.50	1,850
2.20	140	3.00	350	3.80	900	4.60	2,010

above table is applicable only for open-channel conditions. It is based on seven discharge meas-
its made during 1905 and four older measurements. It is fairly well defined between gage
s 1.6 feet and 4 feet.

Estimated monthly discharge of Clear Creek at Forkscreek, Colo., for 1905.

[Drainage area, 345 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dep inc
April	230	63	131	7,795	0.380	
May	999	230	472	29,020	1.37	
June	1,994	595	1,291	76,820	3.74	
July	595	260	420	25,820	1.22	
August	302	142	193	11,870	.556	
September	146	102	116	6,902	.336	
October	110	49	75.3	4,630	.218	
The period				162,900		

MISCELLANEOUS MEASUREMENTS.

Miscellaneous discharge measurements made in South Platte River drainage basin for

Date.	Stream.	Locality.	Area of section.	Mean velocity.	I ch
			Sq. ft.	*Ft. per sec.*	*Se*
March 31	South Platte	North Platte, Nebr.	236	1.62	
June 14	do	do	2,781	2.74	
July 13	do	do	89	1.92	
April 8	Cherry Creek	Denver, Colo.			

PLATTE RIVER.

DESCRIPTION OF BASIN.

From the point of junction of North and South Platte rivers the main stream winds ward across Nebraska, uniting with the Missouri at Plattsmouth, about 10 miles sou Omaha. Its course lies for the most part through a broad, level bottom, rather san places, but for the most part fertile, bordered by bluffs varying in height from 50 to 3 400 feet. From its source to a point near Ashland, Saunders County, it is a broad, sh stream, flowing in many places as a network of interlacing channels among numerous is and sand bars, but farther east it is confined between heavily wooded limestone bluff

The drainage basin lies wholly to the north of a line bordering closely the south ba the stream and consists generally of rolling prairie land in the middle portion, which t east and west gives way to extensive areas of sand hills. Along the main stream ar tributaries is a deep flood plain, composed of loam, sand, and gravel in the valleys a talus on the slopes. Outside of this flood plain the soil is mostly loess, consisting of y clays and fine sandy loam. There is little timber except in the immediate vicinity c small tributaries.

The average annual precipitation is about 23 inches, of which 69 per cent falls durin five months of the growing season, from April to August; about half of the remain snowfall. The stream is subject to periodic floods, caused by the melting of snows i headwater regions of North and South Platte rivers; these floods reach a maximu June and July and often do considerable damage to property on the lower portions o stream. In the western part of the drainage area the waters of the river are extensively for irrigation.

The principal tributaries of the Platte are the Elkhorn and the Loup, both draining long, row valleys north of the river.

nformation in regard to the basin is contained in the following publications of the United tes Geological Survey (Ann=Annual Report; Bull=Bulletin; W. S. Water-Supply per):

escription: Ann 12, ii, pp 238-239; 22, iv, p 306; Bull 131, p 28; WS 75, pp 124-125; 84, pp 50-51; 99, pp -138; 131, p 201.
rrigation surveys: Ann 13, iii, pp 73-91.
ainfall and river stations, map: Ann 20, iv, p 256.
ainfall and run-off relation: Ann 20, iv, pp 265-266.
ainfall data: Ann 13, iii, pp 76-77; 20, iv, pp 256-266.

PLATTE RIVER NEAR LEXINGTON, NEBR.

This station was established April 2, 1902. It is located at a highway bridge 3 miles uth of Lexington, Nebr., in sec. 20, T. 9 N., R. 21 W.

The channel is straight both above and below the station. The banks are low and not ible to overflow, and the bed is composed of shifting sand. There are no obstructions in e channel other than the bridge piling, and the current is never sluggish, even at low water, hen the stream some times flows in as many as forty channels of varying widths and depths. age heights have a range of about 3 feet. Records of winter flow are not obtained, as the ver, on account of its shallowness, often freezes solid.

Discharge measurements are made from the upstream side of the highway bridge, which nsists of 187 spans of 20 feet each, supported on piles. The initial point for soundings is e zero mark on the hand rail at the north (left) bank of the stream. A second, smaller annel, about one-fourth mile to the south, is measured from a similar pile bridge having total span of 60 feet.

On account of the extreme width of the section (3,720 feet) and the shallowness of the ream, and also to partly eliminate the effect of wind, two gages are maintained at this station, the observer being E. J. Duryee, a mail carrier, who reads both gages as he crosses the ridge, no observations being taken on Sundays or holidays. The gages are of the standard hain type. One of them is located at the north end of the bridge, downstream side, and the ther at the south end, upstream side, with their zeros at the same elevation. The wind ometimes creates a difference of over a foot between the two gages, but this difficulty is largely eliminated by using the means of the readings in computations of discharge. The eros of the gages are referred to three bench marks: (1) The top of the east end of the first cap at the north end of the bridge; elevation, 7.66 feet. (2) The top of the upstream end of the cap of the third bent from the north end of the bridge, marked with a cross; elevation, 9.22 feet. (3) The top of the upstream end of the cap of the third bent from the south end of the bridge, marked with a cross; elevation, 9.03 feet. Bench mark No. 1 is 2,392 feet above sea level.

Information in regard to this station is contained in the following Water-Supply Papers f the United States Geological Survey:

Description: 84, pp 59-60; 99, p 155; 131, pp 47-48.
Discharge: 84, p 60; 99, p 155; 131, p 48.
Discharge, monthly: 84, p 61; 99, p 157; 131, p 50.
Gage heights: 84, pp 60-61; 99, p 156; 131, p 49.
Rating tables: 84, p 61; 99, p 156; 131, p 49.

Discharge measurements of Platte River near Lexington, Nebr., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 11	G. W. Bates	3,720	1,421	1.73	3.50	2,473
May 16	.do	3,790	5,046	2.77	4.25	13,930
June 12	H. C. Gardner	3,720	8,223	3.14	4.93	25,690
July 10	.do	3,800	4,705	2.34	3.93	11,010
July 18	.do	2,900	1,681	1.71	3.38	2,882
August 2	.do	3,140	1,765	1.63	3.48	2,877
August 23	H. O. Smith					0
September 6	H. C. Gardner	1,480	637	1.55	3.25	980
September 20	F. S. Dobson	1,540	502	1.61	3.10	760

Daily gage height, in feet, of Platte River near Lexington, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		3.45	4.2	4.9	4.05	3.6	3.15	3.15
2		3.52	4.2	4.9	4.25	3.48	3.2	3.15
3		3.58	4.28	4.9	4.48	3.6	3.2	3.15
4		3.62	4.3	4.85	4.33	3.55	3.2	3.15
5		3.62	4.32	4.8	4.18	3.48	3.35	3.15
6		3.62	4.32	4.65	4.05	3.45	3.25	3.15
7		3.6	4.36	4.55	4.2	3.42	3.22	3.15
8		3.55	4.4	4.5	4.08	3.42	3.2	3.16
9		3.48	4.35	4.5	4.0	3.45	3.2	3.16
10		3.4	4.35	4.75	3.92	3.5	3.16	3.12
11		3.45	4.42	4.82	3.92	3.35	3.12	3.1
12		3.42	4.52	4.9	3.85	3.3	3.12	3.16
13		3.52	4.52	4.8	3.82	3.3	3.15	3.15
14		3.5	4.44	4.72	3.75	3.32	3.12	3.25
15		3.5	4.35	5.0	3.65	3.38	3.12	3.28
16		3.5	4.25	5.15	3.6	3.42	3.28	3.28
17		3.52	4.28	5.05	3.55	3.45	3.33	3.3
18		3.55	4.25	4.95	3.42	3.3	3.38	3.3
19		3.52	4.22	4.82	3.40	3.28	3.32	3.33
20		3.52	4.3	4.78	3.42	3.28	3.28	3.28
21		3.72	4.3	4.68	3.4	3.28	3.28	3.25
22		3.82	4.3	4.58	3.62	3.42	3.3	3.3
23		3.85	4.2	4.75	3.56	3.4	3.3	3.3
24	3.55	3.88	4.15	4.7	3.5	3.28	3.25	3.3
25	3.42	4.05	4.12	4.55	3.42	3.25	3.2	3.3
26	3.45	4.12	4.25	4.42	3.42	3.25	3.2	3.32
27	3.45	4.15	4.3	4.32	3.4	3.22	3.18	3.3
28	3.38	4.15	.....	4.2	3.32	3.18	3.15	3.32
29	3.42	4.12	4.75	4.12	3.38	3.2	3.1	3.25
30	3.50	4.16	4.72	4.1	3.42	3.18	3.12	3.28
31	3.50	.....	4.78	.....	3.45	3.18	.....	3.4

NOTE.—Sunday and holiday gage heights interpolated. These gage heights are the mean of the two gages.

PLATTE RIVER NEAR COLUMBUS, NEBR.

ation was established June 4, 1895. It is located at the Meridian Bridge, about 3 ith of Columbus, Nebr., in sec. 31, T. 17, R. 1 E. The bridge lies on the sixth prin- ridian.

ver at this point flows in three channels, known as the main, middle, and south , having widths of 1,940 feet, 320 feet, and 75 feet, respectively, and each channel is by a pile bridge. The main channel is crossed by the Meridian Bridge, which con- ixty-five 30-foot spans; the middle-channel bridge consists of sixteen 20-foot spans, cated 1½ miles south of the Meridian Bridge; the south channel is spanned by a pile bout 80 feet long, located one-eighth mile south of the middle-channel bridge.

e the bridges the channels are straight for 5,000 feet in the main channel, 200 feet in dle channel, and 100 feet in the south channel; below the bridges the channel is for 3,000 feet in the main channel, 300 feet in the middle channel, and 500 feet in h channel. The sections are broad and shallow, with rapid velocity, and shifting, eds. The banks are low but are not subject to overflow. At low stages the river many shallow channels, so that the measurement of discharge is mainly a matter of on. A small tributary furnishes a supply of water in the south channel, even when r channels are entirely dry. The only obstructions are the piling bents. Discharge ments are made from the upstream side of all three bridges, whose hand rails are at intervals of 10 or 20 feet. The initial point for soundings is the zero mark on ream hand rail at the north end of the main-channel bridge and at the south ends iddle and south channel bridges.

ndard chain gage, which is read by W. D. Benson, is fastened to the downstream l of the Meridian Bridge approach. The length of the chain is 16.21 feet. The gage ed to two bench marks, as follows: (1) A standard United States Geological Survey ark, located 60 feet north of the north end of the bridge truss and 10 feet west of a ood tree 6 feet in diameter; elevation, 7.06 feet above the zero of the gage. (2) A f three spikes driven in the top of the second piling from the downstream end of the ent from the north end of the bridge, counting approach bent "one;" elevation, above the gage datum. In past years deposits of sand about the gage have caused able trouble, and the records have been frequently interrupted.

nation in regard to this station is contained in the following publications of the States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Paper):

tion: Ann 18, iv, p 188; Bull 140. pp 121-122; WS 15, p 98; 27, p 78; 37, p 242; 50, p 307; 66, p 39; 99, pp 152-153; 131, pp 50-51.
rge: Ann 18, iv, p 189; 20, iv, p 302; Bull 131, p 92; 140, p 122; WS 15, p 98; 27, p 87; 37, p 242; 50, p 39; 84, p 58; 99, p 153; 131, p 51.
rge, daily: Ann 18, iv, p 190.
rge, flood: Ann 18, iv, pp 184-186.
rge, monthly: Ann 19, iv, p 334; 20, iv, pp 264, 295; 22, iv, p 329; WS 75, p 138; 84, p 59; 99, p 154;

rge, yearly: Ann 20, iv, p 55.
ights: Bull 140, p 122; WS 15, p 98; 27, p 85; 37, p 243; 50, p 308; 66, p 39; 84, p 58; 99, pp 153-154;

graphs: Ann 18, iv, p 190; 19, iv, p 334; 20, iv, p 296; WS 75, p 138.
l and run-off relation: Ann 20, iv, p 266.
tables: Ann 18, iv, p 189; 19, iv, p 333; Bull 120, p 122; WS 39, p 449; 84, p 59; 99, p 154; 131, p 52.

Discharge measurements of Platte River near Columbus, Nebr., in 1905.

Date	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 16	Dobson, Bates, and Gardner	2,310	1,473	2.70	3.08	3,978
April 27	H. C. Gardner	2,330	4,153	3.28	4.45	13,630
May 16	do	2,300	7,384	4.52	5.60	33,410
June 21	do	2,280	7,256	3.79	5.10	27,570
July 8	do	2,285	5,899	3.36	4.45	19,760
July 14	do	2,295	3,336	2.55	3.50	8,524
August 12	do	1,660	1,060	2.31	2.25	2,448
September 27	F. S. Dobson	1,486	880	1.98	2.10	1,739
October 13	do	.....	586	1.52	1.80	891

Daily gage height, in feet, of Platte River near Columbus, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	.....	2.6	4.8	5.35	4.6	2.75	1.5	1.7
2	.....	2.4	4.6	5.55	4.65	3.2	.75	1.55
3	.....	2.6	4.4	5.5	4.85	3.2	.7	1.5
4	.....	2.7	4.15	5.35	5.3	3.4	.75	1.5
5	.....	2.6	4.75	5.3	4.95	3.2	1.6	1.3
6	.....	3.0	5.6	5.2	5.5	3.25	1.8	1.3
7	.....	3.2	4.5	5.2	4.7	3.15	2.35	1.25
8	.....	3.1	4.4	5.2	4.55	3.0	2.85	1.2
9	.....	3.1	4.5	4.95	4.2	2.8	2.65	1.35
10	.....	2.9	4.3	5.25	4.15	2.5	2.4	1.2
11	.....	2.9	4.6	5.1	4.0	2.35	2.2	1.15
12	.....	2.8	4.55	5.3	3.75	2.25	1.9	1.15
13	.....	2.6	5.3	5.3	3.55	2.25	1.85	1.2
14	.....	2.7	5.75	5.25	3.35	2.2	2.6	1.35
15	.....	2.6	6.2	5.3	3.15	2.2	2.55	1.4
16	.....	2.6	5.45	5.3	3.0	2.25	2.2	1.3
17	3.1	2.8	5.6	5.8	2.85	2.5	2.25	1.35
18	3.6	2.8	5.15	5.35	2.7	2.55	3.5	1.3
19	3.2	2.8	4.6	5.45	2.5	2.6	3.45	1.35
20	3.8	3.4	4.55	5.15	2.3	2.35	3.35	1.4
21	3.7	3.8	4.35	5.15	2.3	2.35	3.25	1.5
22	3.6	4.0	4.35	4.95	2.2	2.25	3.15	1.6
23	3.7	4.2	4.25	6.35	2.25	2.3	3.0	1.65
24	3.5	4.4	4.2	5.4	2.1	1.95	2.95	1.85
25	3.3	4.6	4.1	5.25	2.1	1.9	2.45	2.0
26	3.1	4.8	4.25	5.25	2.85	2.1	2.2	1.9
27	3.0	5.0	4.15	5.3	3.15	2.2	2.05	1.9
28	2.8	5.3	4.45	5.0	2.85	1.75	1.9	2.0
29	2.7	5.15	5.1	4.95	2.7	1.55	1.75	2.5
30	2.6	5.1	5.25	4.85	2.65	1.35	1.7	2.5
31	2.6	.....	5.5	.....	2.6	1.15	.....	2.5

NOTE.—Gage heights estimated April 22-27.

Station rating table for Platte River near Columbus, Nebr., from March 17 to May 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.40	1,750	3.40	5,530	4.40	13,170	5.40	29,400
2.50	2,000	3.50	6,100	4.50	14,260	5.50	31,450
2.60	2,280	3.60	6,720	4.60	15,500	5.60	33,550
2.70	2,580	3.70	7,380	4.70	16,900	5.70	35,700
2.80	2,910	3.80	8,080	4.80	18,450	5.80	37,900
2.90	3,270	3.90	8,820	4.90	20,100	5.90	40,150
3.00	3,650	4.00	9,600	5.00	21,800	6.00	42,450
3.10	4,060	4.10	10,420	5.10	23,600	6.10	44,800
3.20	4,510	4.20	11,280	5.20	25,450	6.20	47,200
3.30	5,000	4.30	12,190	5.30	27,400		

The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during 1905. Owing to the shifting character of the stream bed, estimates based on the above table and on that following can only be considered rough approximations.

Station rating table for Platte River near Columbus, Nebr., from June 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.40	80	2.40	2,780	3.40	8,040	4.80	23,300
1.50	260	2.50	3,180	3.50	8,780	5.00	26,350
1.60	460	2.60	3,600	3.60	9,570	5.20	29,600
1.70	670	2.70	4,040	3.70	10,420	5.40	32,950
1.80	900	2.80	4,500	3.80	11,330	5.60	36,500
1.90	1,150	2.90	4,990	3.90	12,280	5.80	40 150
2.00	1,430	3.00	5,520	4.00	13,280	6.00	44,000
2.10	1,730	3.10	6,090	4.20	15,450	6.20	48,000
2.20	2,050	3.20	6,700	4.40	17,830	6.40	52,150
2.30	2,400	3.30	7,350	4.60	20,450		

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1905, and is fairly well defined between gage heights 1.8 feet and 5 feet. See note to preceding table.

Estimated monthly discharge of Platte River near Columbus, Nebr., for 1905.

[Drainage area, 56,870 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 17-31	8,080	2,280	4,914	146,200	0.086	0.048
April	27,400	1,758	7,800	464,100	.137	.153
May	47,200	10,420	19,360	1,190,000	.340	.392
June	51,100	24,050	31,180	1,855,000	.548	.611
July	34,700	1,730	10,770	662,200	.189	.218
August	8,040	0	3,217	197,800	.057	.066
September	8,780	0	2,978	177,200	.052	.058
October	3,180	0	604	37,140	.011	.013
The period				4,730,000		

LOUP RIVER AT COLUMBUS, NEBR.

The Loup and its branches, which form the most important tributaries of the Platte, drain an area 13,540 square miles in extent, lying in the heart of Nebraska. The Loup proper is formed by the junction of North and Middle Loup rivers, which unite near the city of St. Paul, the Middle Loup in turn receiving the South Loup in the southwestern part of Howard County. The principal tributaries are Beaver, Cedar, Calamus, and Dismal creeks.

The country drained is generally rolling, with an occasional high plain or table-land. The headwaters of the North and Middle Loup lie in a region of sand hills, among which are found numerous lakes varying in size from small ponds up to those with an area of several square miles. The immediate valleys of the streams are composed of alluvial deposits of sand, gravel, and loam, with areas of yellow clay and fine sandy loam beyond. The region abounds in springs, caused by the percolation of the precipitation through the sandy soil to the impervious clays below, and this fact no doubt accounts for the remarkable constancy of flow of the streams. The soil is generally fertile, and large quantities of hay, grain, etc., are grown. The streams are subject to a succession of floods during the spring and early summer, the result of melting snows and heavy rainfall in the spring months. As a large part of the area is grass grown, evaporation is considerable, averaging 5 feet.

A comparatively small amount of water is diverted for irrigation, the ditches generally being small and covering limited areas. A number of power plants are in operation, and others of considerable extent have been proposed, particularly one near Columbus, by which it is believed that about 20,000 continuous horse-power may be developed.

The gaging station was established October 13, 1894. It is located about 75 yards above the Union Pacific Railroad bridge and 6 miles above the mouth of the river, in sec. 23, T. 17 N., R. 1 W.

At the measuring section the river is straight for about 1,000 feet above and a considerable distance below. The left bank is high; the right is low and overflows at high water. The bed is composed entirely of shifting sand. There is but one channel at all stages, and the current is rapid. The channel is unobstructed. At the lower gaging station the river flows chiefly in a deep channel near the right bank, obstructed by the piling of an old bridge a short distance below the existing highway bridge. Gage heights range from 3 to 12 feet, excessive floods being very rare and usually caused by ice gorges.

Discharge measurements are made by means of a cable and car. The initial point for soundings is the zero-mark on the cable. In the spring of 1905 the cable at this station, which consisted of a five-eighths inch steel wire, was broken by the ice. Later in the season it was replaced by a new three-fourths inch steel cable. During the time that the cable was out measurements were made from the highway bridge or from the Union Pacific Railroad bridge near the station.

Two gages are maintained at this station—one a vertical staff spiked to piling at the cable, the other a standard chain gage at the highway bridge 1½ miles below. The gage heights here reported are those of the gage at the highway bridge, the observer being W. D. Benson. The length of the chain is 24.50 feet. These gages are referred to two bench marks as follows: (1) A standard United States Geological Survey bench mark, located 72 feet east of the upper gage; elevation 21.83 feet above the zero of the lower gage and 13.27 feet above the zero of the upper gage. (2) A cross cut on the west end of the cap of the first bent at the north end of the highway-bridge approach; elevation 10.91 feet above the zero of the lower gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Papers):

Description: Ann 18, iv, p 182; Bull 131, p 32; 140, p 118; WS 15, p 97; 27, p 78; 37 pp 240-241; 50, pp 306-307; 66, p. 38; 84, p 55; 99, p 145; 131, pp 82-83.

Discharge: Ann 18, iv, p 182; Bull 131, p 91; 140, p 118; WS 15, p 97; 27, p 87; 35, p 16; 37, p 241; 50, p 307; 66, p 38; 84, p 56; 99, p 146; 131, p 84.

daily: Ann 18, iv, pp 183–184; 131, p 85.
flood: Ann 18, iv, pp 184–186.
monthly: Ann 18, iv, p 187; 19, iv, p 332; 20, iv, pp 263, 294; 22, iv, p 328; Bull 140, p 120; WS p 57; 99, p 147; 131, p 86.
yearly: Ann 20, iv, p 55.
ts: Bull 140, p 119; WS 15, p 97; 27, p 85; 37, p 241; 50, p 307; 66, p 39; 84, p 56; 99, p 146;

hs: Ann 18, iv, p 184; 19, iv, p 333; 20, iv, p 295; 22, iv, p 328.
d run-off relation: Ann 20, iv, p 266.
les: Ann 18, iv, p 183; 19, iv, pp 331–332; Bull 140, p 119; WS 39, p 449; 84, p 57; 99, p 147.

Discharge measurements of Loup River at Columbus, Nebr., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
...	H. C. Gardner	820	1,046	4.45	4.40	4,659
..	.....do	295	870	5.72	4.55	4,982
..	.....do	740	2,162	5.96	5.90	12,890
..	.....do	660	1,695	3.13	4.65	5,316
..	.....do	800	2,040	4.54	5.30	9,263
..	.....do	540	1,144	3.60	4.80	4,126
..	.....do	800	1,945	2.62	4.20	5,089
..	F. S. Dobson	180	774	4.07	[a]4.03	3,153
..	.... do	330	965	4.26	4.18	4,113

[a] New rod; old rod read 4.30 feet.

Daily gage height, in feet, of Loup River at Columbus, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	4.3	4.6	5.2	6.85	4.8	4.4	4.25	4.2	.....
2	.....	4.4	4.55	5.0	6.25	6.8	4.35	4.4	4.15	.....
3	.....	4.5	4.7	5.5	6.7	5.9	4.3	4.35	4.1	.....
4	.....	4.9	4.6	5.0	6.55	5.0	4.3	4.3	4.1	.....
5	.....	4.6	4.75	4.7	5.85	4.75	4.5	4.2	4.25	.....
6	.....	4.4	4.85	4.65	5.7	4.4	4.6	4.2	4.5	.....
7	.....	4.2	4.8	4.35	5.8	4.45	4.85	4.2	4.35	.....
8	.....	4.1	4.7	4.25	5.4	4.5	4.85	4.2	4.3	4.5
9	.....	4.2	4.75	4.45	5.22	4.4	4.55	4.3	4.3	5.7
10	.....	4.3	5.6	4.35	5.0	4.35	4.5	4.3	4.35	5.7
11	.....	4.3	5.0	4.6	4.95	4.35	4.45	4.3	4.35	5.75
12	.....	4.2	4.9	4.6	4.9	4.3	4.4	4.3	4.4	5.7
13	.....	4.2	5.8	4.55	4.75	4.3	4.45	4.35	4.4	5.8
14	.....	4.3	6.35	4.45	4.5	4.25	4.95	4.4	4.45	6.5
15	.....	4.4	6.9	4.5	5.0	4.3	5.5	4.4	4.35	6.0
16	.....	4.3	5.8	4.6	4.95	4.55	5.1	4.6	4.35	5.85
17	4.4	4.3	5.4	4.7	4.85	4.45	4.95	4.5	4.35	5.85
18	4.6	4.3	5.0	4.6	4.8	4.6	5.25	4.45	4.45	.....
19	4.7	4.2	4.95	4.6	4.8	5.5	6.25	4.55	4.4	.....
20	4.9	5.6	4.9	4.7	4.8	4.5	5.3	4.45	4.4	.....
21	4.7	5.2	4.9	4.85	4.85	4.5	4.85	4.3	4.35	.....
22	4.7	5.15	4.8	5.0	4.85	4.85	4.65	4.4	4.3	.....
23	4.6	5.1	4.75	6.4	4.95	4.55	4.4	4.35	4.65	.....
24	4.4	5.05	4.65	6.5	5.15	4.6	4.3	4.2	4.55	.....
25	4.5	5.0	4.6	5.65	4.95	4.7	4.45	4.2	4.65	.....
26	4.5	4.95	4.9	5.2	7.95	4.55	4.1	4.2	4.5	.....
27	4.6	4.95	4.95	4.95	6.4	4.55	4.3	4.2	4.6	.....
28	4.4	4.95	5.1	6.9	5.4	4.4	4.25	4.25	4.5	.....
29	4.3	4.9	6.95	7.0	5.2	4.4	4.25	4.35	3.95	.....
30	4.2	4.7	6.1	6.05	4.95	4.4	4.25	4.25	5.45	.....
31	4.3	.....	5.75	.....	4.5	4.4	.....	4.25	.....	.....

NOTE.--Gage height estimated April 22-27, inclusive. River frozen November 30 to December 7 inclusive.

Daily discharge, in second-feet, of Loup River at Columbus, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1		3,950	5,400	8,700	19,020	6,700	5,000	3,180	3,670
2		4,400	5,150	7,500	15,120	19,190	4,700	3,910	3,450
3		4,900	5,000	10,500	18,050	13,600	4,420	3,750	3,210
4		6,950	5,400	7,500	17,080	8,270	4,380	3,580	3,210
5		5,400	6,150	5,900	12,600	7,000	5,300	3,200	3,900
6		4,400	6,675	5,650	11,700	5,300	5,770	3,250	5,100
7		3,500	6,400	4,175	12,300	5,700	7,000	3,300	4,380
8		3,050	5,900	3,725	9,900	6,110	6,980	3,350	4,110
9		3,500	6,150	4,650	8,370	5,720	5,300	3,880	4,110
10		3,950	11,100	4,175	6,750	5,600	5,010	3,940	4,380
11		3,950	7,500	5,400	6,050	5,750	4,700	4,000	4,380
12		3,500	6,950	5,400	5,400	5,600	4,410	4,070	4,600
13		3,500	12,300	5,150	4,270	5,550	4,600	4,350	4,600
14		3,950	15,780	4,650	2,900	5,250	7,110	4,600	4,850
15		4,400	19,350	4,900	5,220	5,450	10,250	4,600	4,380
16		3,950	12,300	5,400	5,100	6,700	8,400	5,600	4,380
17	4,400	3,950	9,900	5,900	4,730	6,110	6,950	5,100	4,380
18	5,400	3,950	7,500	5,400	4,650	6,850	8,580	4,850	4,850
19	5,900	3,500	7,225	5,400	4,800	12,100	14,600	5,330	4,600
20	6,950	11,100	6,950	5,900	4,920	6,200	8,710	4,850	4,600
21	5,900	8,700	6,950	6,675	5,310	6,150	6,130	4,110	4,380
22	5,900	8,400	6,400	7,500	5,460	8,000	5,050	4,600	4,110
23	5,400	8,100	6,150	16,100	6,130	6,300	3,810	4,380	5,850
24	4,400	7,800	5,650	16,750	7,400	6,500	3,310	3,670	5,350
25	4,900	7,500	5,400	11,400	6,430	7,000	3,950	3,670	5,850
26	4,900	7,225	6,950	8,700	25,800	6,110	2,400	3,670	5,100
27	5,400	7,225	7,225	7,225	15,450	6,050	3,150	3,670	5,600
28	4,400	7,225	8,100	19,350	9,450	5,230	3,000	3,900	5,100
29	3,950	6,950	19,680	20,000	8,430	5,170	3,050	4,380	2,600
30	3,500	5,900	14,150	13,820	7,320	5,100	3,120	3,900	2,600
31	3,950	.....	12,000	.....	4,970	5,050	.....	3,900	.....

NOTE.—The daily discharge was obtained from a rating table March 17 to July 10; and by the indirect method for the remainder of the year.

Estimated monthly discharge of Loup River at Columbus, Nebr., for 1905.

[Drainage area, 13,540 square miles.]

Month.	Discharge in second-feet.			Run-off.		
	Maximum.	Minimum.	Mean.	Total in acre-feet.	Second-feet per square mile.	Depth in inches.
March 17-31	6,950	3,500	5,017	149,300	0.371	0.207
April	11,100	3,050	5,492	326,800	.406	.453
May	19,680	5,150	8,665	532,800	.640	.738
June	20,000	3,725	8,117	483,000	.599	.668
July	25,800	2,900	9,067	557,500	.670	.772
August	19,190	5,050	6,949	427,300	.513	.591
September	14,600	2,400	5,637	335,400	.416	.464
October	5,600	3,180	4,082	251,000	.301	.347
November	5,850	2,600	4,389	261,200	.324	.362
The period				3,324,000		

NOTE.—No estimate for ice period.

KANSAS RIVER DRAINAGE BASIN.

GENERAL FEATURES.

The drainage basin of Kansas river lies between the basins of the Platte and the Arkansas, entirely within the region of the Great Plains and extends through the arid, semiarid, and humid regions. It extends from Eastern Colorado to Missouri river, a distance of 485 miles.

The country presents throughout the same general appearance so far as contour of surface is concerned. It is a rolling prairie, through which the streams meander in winding courses in broad, fertile bottoms flanked on either side by bluffs. In the eastern part of Kansas the rivers are fringed with groves of timber; but to the west this becomes more and more scant practically disappearing at the ninety-ninth meridian.

The principal tributaries are Smoky Hill and Republican rivers, whose union forms the main stream, and Blue River.

REPUBLICAN RIVER.

DESCRIPTION OF BASIN.

Republican River rises in the arid plains of Eastern Colorado, flows northeastward into southwestern Nebraska, then eastward through the southern tier of counties to Superior where it turns to the southeast, enters Kansas, and about 2 miles northeast of Junction unites with Smoky Hill River to form Kansas River. The length of the basin east and west approximately 360 miles, its greatest width is 120 miles, and the total area drained 25,840 square miles. The river is wide and rather shallow, with a rapid descent, and the bed is largely shifting quicksand of the most unstable character.

In the upper portion of its course the Republican receives many tributaries, chiefly from the south. Nearly all of these flow through a region where the rainfall is less than 22 inches but as this part of the basin is covered with buffalo grass, which sheds rain like a roof, the per cent of rainfall reaching the streams is great. Near the mouth the drainage area is very narrow, and the tributaries are small and unimportant; but here the rainfall is 28 to 30 inches. Many small springs occur along the main stream and its branches and the ground water lies generally at medium depth. There are no lakes or marshes of any considerable extent in the area.

The soil of the middle part of the basin is a porous, sandy loam and about 55 per cent of the land is under cultivation; along the lower course the soil is black loam and clay and about 75 per cent of the land is cultivated. The rainfall in the lower basin is considered sufficient for all growing crops and there are no irrigation works.

The Republican is subject to sudden rises and falls and occasionally overflows its banks. The most notable flood since 1895, when the gaging station at Junction was established, occurred in May and June, 1903. This covered all the low bottom lands and washed away fences, houses, crops, railway tracks, bridges, stock, and everything movable.

Information in regard to the basin is contained in the following Annual Reports of the United States Geological Survey: Eighteenth, Part IV, page 194; Twenty-first, Part IV, page 219.

REPUBLICAN RIVER NEAR BOSTWICK, NEBR.

This station was established June 6, 1904. It is located at a highway bridge 1 mile south of Bostwick, Nebr., in sec. 23, T. 1 N., R. 8 W., and replaces a station established at Superior, Nebr., in 1895.

The channel is straight both above and below the station. The left bank is high, but the right bank is low and subject to overflow at high stages. The bed of the stream is composed of shifting sands. The channel is somewhat obstructed by ice breakers and piers, but not seriously so. The current is never sluggish, even at low stages. Gage height have a range of about 10 feet.

Discharge measurements are made from the bridge, which has three 150-foot spans resting on tubular concrete piers. The initial point for soundings is the zero mark on the hand rail in line with the south face of the north downstream pier.

The gage was read during 1905 by M. A. McPherson, who lives one-fourth mile distant. It is of the standard chain type and the length of the chain is 20.52 feet. The gage is referred to bench marks as follows: (1) The top of the cast-iron bearing shoe at the north end of the downstream truss of the north span; the shoe rests on rollers on the top of the pier and has three openings, the east opening being the bench mark; elevation, 15.75 feet. (2) The northwest cardinal point of the rim or edge of the cover plate of the pier at the south end of truss described above; elevation, 15.89 feet. Elevations are above the zero of the gage.

A description of this station with gage height and discharge data is contained in Water-Supply Paper No. 131 of the United States Geological Survey, pages 102–104.

Discharge measurements of Republican River near Bostwick, Nebr., in 1905.

Date.	Hydrographer	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 22	H. C. Gardner	430	639	1.85	2.45	1,181
April 29	do	930	830	2.40	3.00	2,009
June 7	do	420	585	1.78	2.55	1,045
July 6	do	440	3,188	4.66	8.30	14,870
July 26	do	430	1,806	3.27	5.45	5,915
August 10	do	410	1,141	2.70	3.55	3,082
September 30	F. S. Dobson	120	359	1.80	1.32	648

Daily gage height, in feet, of Republican River near Bostwick, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		2.15	2.75	3.3	6.25	6.35	1.2	1.25
2		2.15	2.55	3.3	8.7	6.45	1.2	1.15
3		2.2	2.5	4.1	9.3	6.9	1.9	1.15
4		2.15	2.45	3.7	10.4	7.3	1.9	1.15
5		2.15	2.45	2.9	9.5	5.65	1.9	1.1
6		2.15	2.35	2.65	7.65	5.3	1.9	1.1
7		2.5	2.35	2.55	5.5	5.5	1.5	1.1
8		2.4	2.35	2.35	4.75	4.65	1.3	1.1
9		2.35	2.4	2.25	4.5	4.05	1.3	1.05
10		2.25	2.45	2.35	4.6	3.8	1.9	1.0
11		2.2	6.1	2.4	4.1	3.5	1.3	1.0
12		2.2	2.7	2.5	3.6	3.05	1.3	1.0
13		2.1	3.0	4.0	3.35	2.8	1.1	.95
14		2.1	3.05	3.0	3.05	2.5	1.1	.95
15		2.1	3.15	2.7	2.9	2.35	1.1	.95
16		2.05	5.4	4.15	2.85	2.5	1.2	1.0
17		2.1	4.1	4.55	2.8	2.65	1.1	.95
18		2.05	3.15	5.5	2.7	2.85	1.3	1.0
19		2.05	2.95	3.85	2.65	2.55	1.2	1.0
20		2.0	2.7	3.5	4.1	2.15	1.4	1.05
21		2.25	2.5	3.0	2.5	2.0	1.45	1.05
22	2.45	2.05	2.45	2.85	2.4	1.85	1.4	1.05
23	2.5	2.2	2.35	5.2	2.35	1.75	1.35	1.1
24	2.45	2.45	2.45	5.75	2.25	1.7	1.45	1.1
25	2.4	2.6	2.35	6.05	2.15	1.65	1.6	1.1
26	2.4	2.95	2.25	5.85	5.7	1.65	1.55	1.1
27	2.4	2.8	2.45	5.5	3.65	1.6	1.55	1.1
28	2.3	3.1	2.25	4.15	3.5	1.5	1.5	1.1
29	2.3	3.0	5.4	3.85	5.4	1.3	1.4	1.1
30	2.25	2.9	3.9	4.15	4.65	1.3	1.35	1.1
31	2.2	.....	3.7	.....	4.9	1.3	.....	1.1

Station rating table for Republican River near Bostwick, Nebr., from June 6, 1904, to July 1, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	110	2.10	845	3.20	1,995	4.60	4,090
1.10	160	2.20	930	3.30	2,120	4.80	4,450
1.20	215	2.30	1,020	3.40	2,250	5.00	4,830
1.30	275	2.40	1,115	3.50	2,385	5.20	5,210
1.40	335	2.50	1,210	3.60	2,555	5.40	5,610
1.50	400	2.60	1,310	3.70	2,670	5.60	6,030
1.60	465	2.70	1,415	3.80	2,815	5.80	6,460
1.70	535	2.80	1,525	3.90	2,965	6.00	6,900
1.80	605	2.90	1,635	4.00	3,115	6.20	7,360
1.90	680	3.00	1,750	4.20	3,420		
2.00	760	3.10	1,870	4.40	3,750		

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1904 and three made in 1905, and is well defined between gage-heights 1.5 feet and 3.5 feet. Estimates based on the above and following tables are liable to considerable error, owing to the shifting character of the stream bed.

Station rating table for Republican River near Bostwick, Nebr., from July 2 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	440	2.60	1,750	4.20	3,850	6.60	8,860
1.10	500	2.70	1,860	4.30	4,010	6.80	9,460
1.20	560	2.80	1,970	4.40	4,170	7.00	10,080
1.30	630	2.90	2,080	4.50	4,340	7.20	10,720
1.40	700	3.00	2,200	4.60	4,510	7.40	11,400
1.50	770	3.10	2,320	4.70	4,680	7.60	12,120
1.60	850	3.20	2,440	4.80	4,860	7.80	12,880
1.70	930	3.30	2,570	4.90	5,040	8.00	13,640
1.80	1,010	3.40	2,700	5.00	5,220	8.20	14,400
1.90	1,090	3.50	2,830	5.20	5,600	8.40	15,200
2.00	1,180	3.60	2,970	5.40	6,000	8.60	16,000
2.10	1,270	3.70	3,110	5.60	6,410	8.80	16,850
2.20	1,360	3.80	3,250	5.80	6,840	9.00	17,750
2.30	1,450	3.90	3,390	6.00	7,300	9.20	18,650
2.40	1,550	4.00	3,540	6.20	7,780	9.40	19,550
2.50	1,650	4.10	3,690	6.40	8,300		

The above table is applicable only for open-channel conditions. It is based on four discharge measurements made during 1905, and is poorly defined. See note to preceding table.

Estimated monthly discharge of Republican River near Bostwick, Nebr., for 1905.

[Drainage area, 23,270 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 22-31	1,210	930	1,082	21,460	0.046	0.017
April	1,870	760	1,060	63,070	.046	.051
May	7,130	975	1,927	118,500	.083	.096
June	7,015	975	2,949	175,500	.127	.142
July	24,500	1,315	5,734	352,600	.246	.284
August	11,060	630	3,082	189,500	.132	.152
September	1,090	500	725	43,140	.031	.035
October	595	410	479	29,450	.021	.024
The period				993,200		

REPUBLICAN RIVER AT BENKELMAN, NEBR.

This station was established November 1, 1894, discontinued September 7, 1895, and reestablished May 20, 1903, at a point some distance below the original location. It is located about one-half mile east of Benkelman, Nebr., on the line between secs. 17 and 20, T. 1 N., R. 37 W.

The river is nearly straight both above and below the station. The banks are low, but seldom overflow. The bed is composed of shifting sand. The channel is slightly obstructed by the piling of the bridge, on which considerable débris lodges at times of high water. The current is never sluggish, even at low stages. Gage heights have a range of about 4 feet. It is impossible to obtain records of winter flow.

Discharge measurements are made from the upstream side of the highway bridge. The initial point for soundings is the zero mark on the upstream hand rail at the east end of the bridge.

The gage, which was read during 1905 by Leon L. Hines, is a vertical staff 6 feet long spiked to the downstream side of the second bent from the west end of the bridge. The gage is referred to five bench marks, as follows: (1) The top of the south end of the concrete foundation for the west upright bent of the elevated track in the Burlington and Missouri River Railroad yards; elevation, 16.14 feet. Nos. 2, 3, 4, and 5 are, respectively, the tops of the south ends of the first, second, third, and fourth bents from the west end of the bridge; elevations, respectively, 6.88, 6.74, 6.34, and 6.19 feet above the zero of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Bull 131, p 33; 140, pp 125–127; WS 99, pp 220–221; 131, p 95.
Discharge: Ann 18, iv, p 206; 20, iv, p 302; Bull 131, pp 33, 92; 140, p 126; WS 50, p 311; 84, p 113; 99, 221; 131, p 95.
Discharge, mean daily: WS 131, p 97
Discharge, monthly: WS 99, p 222; 131, p 98.
Gage heights: Bull 140, p 129; WS 99, p 221; 131, p 96.
Rating table: Bull 140, p 128; WS 99, p 222.

Discharge measurements of Republican River at Benkelman, Nebr., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 21	H. C. Gardner	160	6[illegible]	1.16	1.20	171
May 2	do	230	69	2.26	1.35	156
June 6	do	45	34	1.79	1.25	61
July 5	do	65	24	1.50	1.10	36
July 31	G. W. Bates		7[illegible]	2.29	1.40	160
August 28	H. C. Gardner	2[illegible]	6.7	1.60	.80	10
September 28	F. S. Dobson	130	35	1.40	1.10	49

Daily gage height, in feet, of Republican River at Benkelman, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		1.45	1.3	1.4	1.3	1.2	0.8	1.2
2		1.5	1.25	1.35	1.4	1.1	.....	1.2
3		1.35	1.3	1.25	1.25	1.2	.8	1.2
4		1.2	1.3	1.2	1.15	1.15	.....	1.2
5		1.3	1.3	1.25	1.1	1.05	.....	1.2
6		1.25	1.3	1.2	1.1	1.2	1.05	1.2
7		1.25	1.3	1.15	1.1	1.1	1.1	1.2
8		1.3	1.4	1.1	1.18	1.05	1.05	1.15
9		1.3	1.4	1.15	1.25	1.05	1.3	1.1
10		1.35	1.4	1.3	1.25	1.05	1.3	1.2
11		1.3	1.3	1.4	1.25	1.15	1.2	1.2
12		1.3	1.3	1.35	1.1	1.25	1.1	1.2
13		1.3	1.3	1.35	1.1	1.15	1.2	1.2
14		1.3	1.25	1.2	1.05	1.05	1.2	1.2
15		1.3	1.25	1.2	1.0	1.05	1.1	1.3
16		1.3	1.25	1.25	1.0	1.05	1.2	1.2
17		1.25	1.25	1.45	1.1	1.0	1.1	1.2
18		1.25	1.3	1.35	1.05	1.0	1.2	1.2
19	1.4	1.25	1.4	1.25	1.0	.95	1.3	1.2
20	1.35	1.3	1.3	1.2	1.1	.95	1.3	1.2
21	1.2	1.35	1.35	1.2	1.15	.95	1.2	1.25
22	1.0	1.3	1.3	1.4	1.2	.95	1.2	1.3
23	1.1	1.52	1.3	1.2	1.15	.8	1.2	1.25
24	1.1	1.75	1.45	1.2	1.15	.8	1.1	1.25
25	1.05	1.5	1.45	1.15	1.1	.8	1.2	1.25
26	1.15	1.4	1.4	1.2	1.1	.85	1.2	1.25
27	1.2	1.3	1.4	1.2	1.1	.95	1.2	1.3
28	1.2	1.35	1.4	1.15	1.35	.8	1.2	1.35
29	1.1	1.4	1.6	1.15	1.35	.8	1.1	1.45
30	1.0	1.35	1.5	1.15	1.8	.78	1.1	1.55
31	1.25	.....	1.4	.....	1.3	.75	.....	1.6

SOUTH FORK OF REPUBLICAN RIVER AT BENKELMAN, NEBR.

This station was established November 1, 1894, discontinued September 5, 1895, and reestablished May 20, 1903. It is located at the highway bridge about three-fourths of a mile east of Benkelman, on the line between secs. 17 and 20, T. 1 N., R. 37 W., and is about one-fourth mile above the mouth of the South Fork.

The channel is straight both above and below the station. The banks are low, but seldom overflow. The bed is composed of shifting sand. The piling of the bridge obstructs the

a limited extent. The current is never sluggish, even at low stages. Gage
e a range of about 4 feet.
e measurements are made from the upstream side of the highway bridge. The
t for soundings is the zero mark on the upstream hand rail at the east end of

, which was read during 1905 by Leon L. Hines, is a vertical staff 5.5 feet long
ıe upstream side of the first bent in the channel from the east bank of the stream.
ed to five bench marks, as follows: (1) The top of the south end of the concrete
for the first upright bent of the elevated track in the Burlington and Missouri
oad yards; elevation, 18.29 feet. Nos. 2, 3, 4, and 5 are, respectively, the tops of
nds of the first, second, third, and fourth bents from the west end of the bridge;
respectively, 6.62, 6.48, 6.38, and 6.20 feet above the zero of the gage.
ion in regard to this station is contained in the following publications of the
ates Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-
per):

n: Bull 131, p 33; 140, p 130; WS 99, pp 222-223; 131, pp 98-99.
: Ann 18, iv, p 206; Bull 140, p 130; WS 50, p 311; 84, p 113; 99, p 223; 131, p 99.
. mean daily: WS 131. p 101.
. monthly: WS 99, p 224; 131, p 102.
ıts: Bull 140, pp 130-131; WS 99, pp 223-224; 131, p 100.
ble: WS 99, p 224.

measurements of South Fork of Republican River at Benkelman, Nebr., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
...	H. C. Gardner	108	77	1.82	1.77	140
...	....do	210	73	1.52	1.65	111
...	....do	60	25	1.36	1.30	34
...	....do	100	29	1.91	1.40	51
...	G. W. Bates	85	44	1.63	1.45	72
...	H. C. Gardner	.....	.....	.....	.....	0
3..	F. S. Dobson	75	16	1.28	1.20	21

Daily gage height, in feet, of South Fork of Republican River at Benkelman, Nebr., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		1.85	1.7	1.65	1.6	1.6		
2		1.9	1.65	1.55	1.55	1.5		
3		2.05	1.65	1.5	1.6	1.5		
4		1.95	1.7	1.45	1.5	1.5		
5		1.9	1.7	1.35	1.4	1.4	1.35	
6		1.8	1.6	1.35	1.4	1.35		
7		1.75	1.6	1.3	1.4	1.3		
8		1.75	1.6	1.25	1.35	1.25		
9		1.75	1.65	1.35	1.35	1.25		
10		1.75	1.7	1.85	1.25	1.2	1.45	
11		1.75	1.7	1.6	1.2	1.25		
12		1.55	1.7	1.55	1.2	1.25		
13		1.5	1.5	1.35	1.15	1.3		
14		1.4	1.55	1.35	1.1	(a)		
15		1.4	1.55	1.3	1.0			
16		1.4	1.55	13.5	1.1			
17	2.1	1.5	1.5	2.2	1.0			
18	1.95	1.45	1.45	1.7	1.1	1.55		
19	2.1	1.45	1.6	1.6	1.0		1.5	
20	1.95	1.55	1.7	1.55	1.0		1.5	
21	1.85	1.6	1.4	1.2	1.1			
22	1.8	1.5	1.75	1.55	1.15			
23	1.8	1.8	1.45	1.45	1.1			
24	1.8	2.1	1.45	1.45	1.1			
25	1.75	2.25	1.45	1.35	1.1			1.35
26	1.7	2.05	1.65	1.35	1.1			1.35
27	1.6	2.05	1.65	1.35	1.05			1.4
28	1.7	2.0	1.6	1.25	1.1			1.45
29	1.7	1.8	1.75	1.25	1.2			1.5
30	1.7	1.75	1.65	1.25	1.8			1.55
31	1.78		1.75		1.7			1.6

(a) Channel obstructed by sand August 14 to October 31.

Station rating table for South Fork of Republican River at Benkelman, Nebr., from March 17 to August 13, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.00	5	1.40	52	1.70	123	2.00	215
1.10	10	1.50	73	1.80	152	2.10	249
1.20	21	1.60	96	1.90	183	2.20	283
1.30	35						

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1905. Estimates based on this table are liable to considerable error owing to the shifting character of the stream beds.

Estimated monthly discharge of South Fork of Republican River at Benkelman, Nebr., for 1905.

[Drainage area, 5,910 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 17–31	249	96	159	4,730	0.027	0.015
April	300	52	141	8,390	.024	.027
May	137	52	100	6,149	.017	.020
June	283	21	68.6	4,082	.012	.013
July	152	5	35.4	2,177	.006	.0069
August 1–13	96	21	47.7	1,230	.0081	.0039
The period				26,760		

REPUBLICAN RIVER AT JUNCTION, KANS.

This station was established April 26, 1895. It is located at the wagon bridge at the north end of Washington street, Junction, about 2 miles above the mouth of the river.

The channel is straight for about 300 feet both above and below the station and is broken by three piers. The right bank is high, but the left is low and may overflow at high water. The bed of the stream is sandy and liable to change. The flow is moderately rapid. The flood of 1903 cut a new channel, about 220 feet wide, north of the wagon bridge, and for a time this carried most of the water. This channel was at first bridged by a pile bridge, but later it was filled, so that now all the water flows in the old channel. The slope of the river at the gage October 3, 1905, was 0.0024544 foot per foot for a distance of 658 feet.

Discharge measurements are made from the downstream side of the bridge, to which the gage is attached. The initial point for soundings is at the south end of the bridge.

The gage, which was read during 1905 by J. H. Rathert, is in two sections. The first section is an inclined timber, graduated from zero to 11 feet, spiked to a pile and to a large cottonwood tree; the second section is graduated from 11 to 25 feet, and spiked in an upright position to a large cottonwood tree. The gage is referred to bench marks as follows: (1) A spike driven into the west side of an 18-inch cottonwood tree standing 10 feet west of the bridge on the right bank of the river; the spike is about 2 feet above the ground and has an elevation of 12.36 feet above the zero of the gage. (2) The top of a stone, marked with a cross and the letters "B. M.," at the base of the abutment south of No. 3; elevation, 14.28 feet above the zero of the gage.

This station was discontinued October 31, 1905.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 18, iv, p 203; Bull 140, pp 136-137; WS 16, p 109; 27, p 90; 37, p 248; 50, p 313; 66, p 43; 84, p 100; 99, p 214; 131, p 105.

Discharge: Ann 18, iv, p 204; Bull 140, p 137; WS 16, p 109; 27' p 95; 37, p 248; 50, p 313; 66, p 43; 84, p 100; 99, p 214; 131, p 105.

Discharge, monthly: Ann 18, iv, p 205; 19, iv, p 340; 20, iv, pp 312, 318; 21, iv, p 221; 22, iv, p 333; Bull 140, p 138; WS 75, p 141; 84, p 102; 99, p 216; 131, p 108.

Discharge, yearly: Ann 20, iv, p 55.

Gage heights: Bull 140, p 137; WS 11, p 57; 16, p 109; 27, p 92; 37, p 249; 50, p 314; 66, p 43; 84, p 101; 99, p 215; 131, p 106.

Hydrographs: Ann 18, iv, p 204; 19, iv, p 340; 20, iv, p 318; 21, iv, p 221; 22, iv, p 333; WS 75, p 141.

Rainfall and run-off relation: Ann 20, iv, p 313.

Rating tables: Ann 18, iv, p 205; 19, iv, p 339; WS 27, p 96; 39, p 449; 52, p 517; 66, p 171; 84, p 101; 99 p 215; 131, p 107.

Discharge measurements of Republican River at Junction, Kans., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di cha
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec*
March 28	W. G. Russell	163	410	3.33	4.20	
April 11	do	163	389	2.97	4.10	
May 23	do	186	557	3.98	4.70	
June 26	do	248	1,964	4.57	8.70	
June 27	do	246	1,887	4.46	8.45	
July 22	do	313	1,051	3.46	5.70	
August 15	do	248	858	3.43	5.30	
October 4	do	248	446	2.17	3.65	

Daily gage height, in feet, of Republican River at Junction, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	O
1	3.9	4.1	7.42	4.0	4.65	7.98	7.4	8.28	4.0	
2	3.9	4.1	6.1	4.0	4.95	6.75	9.3	7.55	3.98	
3	3.9	4.1	5.95	4.0	4.88	5.5	10.65	7.45	3.9	
4	4.05	4.1	5.65	4.0	4.68	5.7	11.0	7.85	3.9	
5	4.1	3.9	5.48	3.95	4.58	6.5	11.1	7.88	3.92	
6	4.1	3.8	5.48	3.95	4.4	6.12	11.2	8.55	4.1	
7	4.1	3.7	5.12	3.95	4.4	5.9	12.55	8.58	4.1	
8	4.02	3.5	4.78	3.92	4.4	5.18	15.3	7.45	4.28	
9	3.88	3.2	4.68	3.9	6.3	4.85	12.25	6.95	4.35	
10	3.85	3.2	4.5	3.9	5.45	4.65	7.65	6.4	4.35	
11	3.85	3.2	4.42	4.02	4.42	4.6	7.2	5.9	4.15	
12	3.85	3.2	4.3	4.15	4.4	4.6	6.5	5.65	4.05	
13	3.85	3.15	4.3	4.08	5.35	4.35	6.3	5.5	4.0	
14	3.85	3.15	4.22	4.08	7.15	4.08	6.0	5.4	4.15	
15	3.85	3.15	4.15	3.9	5.45	4.15	5.6	5.28	4.02	
16	3.85	3.15	4.25	3.85	4.8	4.9	5.4	5.5	4.0	
17	3.85	3.15	4.28	3.8	4.9	5.6	4.8	5.2	3.9	
18	3.85	3.15	4.3	3.8	5.45	5.05	5.02	5.05	3.9	
19	3.85	3.15	4.3	3.75	7.35	5.1	4.7	4.9	3.82	
20	3.92	3.15	4.3	3.7	6.1	6.85	4.65	4.88	3.8	
21	3.98	4.75	4.32	3.7	5.35	7.55	4.6	5.05	3.75	
22	4.08	5.9	4.38	3.78	5.02	6.35	5.3	5.0	3.72	
23	4.1	6.2	4.4	3.8	4.72	5.95	6.35	4.6	3.68	
24	4.1	5.85	4.25	3.9	4.55	8.55	5.68	4.5	3.75	
25	4.1	5.45	4.38	4.62	9.0	8.1	4.8	4.4	3.8	
26	4.1	5.22	4.35	4.45	7.7	8.7	5.15	4.4	3.65	
27	4.1	7.05	4.32	4.5	6.1	8.35	5	4.4	3.65	
28	4.1	7.2	4.28	5.25	5.52	8.3	9.0	4.3	3.65	
29	4.1	.....	4.2	5.22	5.35	11.15	8.65	4.28	3.8	
30	4.1	.....	4.0	4.95	6.4	9.3	8.48	4.15	3.85	
31	4.1	.....	4.0	.....	9.0	.....	7.7	4.08	.....	

tion rating table for Republican River at Junction, Kans., from January 1 to May 13, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
3.10	250	4.20	1,320	5.30	2,950	6.40	4,730
3.20	310	4.30	1,460	5.40	3,100	6.50	4,905
3.30	380	4.40	1,600	5.50	3,250	6.60	5,085
3.40	460	4.50	1,750	5.60	3,400	6.70	5,265
3.50	550	4.60	1,900	5.70	3,560	6.80	5,450
3.60	650	4.70	2,050	5.80	3,720	6.90	5,640
3.70	750	4.80	2,200	5.90	3,880	7.00	5,830
3.80	850	4.90	2,350	6.00	4,050	7.20	6,230
3.90	960	5.00	2,500	6.10	4,220	7.40	6,650
4.00	1,080	5.10	2,650	6.20	4,390		
4.10	1,200	5.20	2,800	6.30	4,560		

The above table is applicable only for open-channel conditions. It is based on five discharge measurements made during the first part of 1905, and is fairly well defined.

tion rating table for Republican River at Junction, Kans., from May 14 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
3.20	600	4.70	2,210	6.40	4,730	9.40	11,660
3.30	680	4.80	2,340	6.60	5,085	9.60	12,230
3.40	760	4.90	2,470	6.80	5,450	9.80	12,830
3.50	850	5.00	2,600	7.00	5,830	10.00	13,450
3.60	950	5.10	2,735	7.20	6,230	10.50	15,020
3.70	1,050	5.20	2,870	7.40	6,650	11.00	16,700
3.80	1,150	5.30	3,010	7.60	7,080	11.50	18,450
3.90	1,250	5.40	3,150	7.80	7,525	12.00	20,200
4.00	1,360	5.50	3,295	8.00	7,995	12.50	22,200
4.10	1,470	5.60	3,440	8.20	8,480	13.00	24,200
4.20	1,580	5.70	3,590	8.40	8,980	14.00	28,700
4.30	1,700	5.80	3,745	8.60	9,490	15.00	33,700
4.40	1,820	5.90	3,900	8.80	10,010		
4.50	1,950	6.00	4,060	9.00	10,550		
4.60	2,080	6.20	4,390	9.20	11,100		

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1905 and five during 1904, and is fairly well defined. The table has been extended beyond these limits.

Estimated monthly discharge of Republican River at Junction, Kans., for 1905.

[Drainage area, 25,840 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	1,200	905	1,056	64,930	0.041	0.047
February	6,230	280	1,562	86,750	.060	.06[illegible]
March	6,692	1,080	2,043	125,600	.079	.09[illegible]
April	2,875	750	1,233	73,370	.048	.05[illegible]
May	10,550	1,600	3,589	220,700	.139	.16[illegible]
June	17,220	1,448	5,184	308,500	.201	.22[illegible]
July	35,350	2,080	8,559	526,300	.331	.38[illegible]
August	9,439	1,448	4,048	248,900	.157	.18[illegible]
September	1,760	1,000	1,293	76,940	.050	.06[illegible]
October	1,150	720	847	52,080	.033	.03[illegible]
The period				1,784,000		

NOTE.—Ice conditions uncertain; discharge applied as for open channel.

MISCELLANEOUS MEASUREMENT.

July 18, 1905, a measurement of the North Fork of Republican River at Benkelman, Nebr., gave the following results: Area of section, 70 square feet; mean velocity, 2.29 feet per second; discharge, 160 second-feet.

SMOKY HILL RIVER.

DESCRIPTION OF BASIN.

Smoky Hill River rises near the boundary between Kansas and Colorado, pursues a winding, but on the whole easterly, course through Kansas, and near Junction unites with Republican River to form Kansas River. Its length is 335 miles and the extreme width of its basin is about 100 miles. The river runs close to the northern border of the Arkansas basin, and its chief tributaries are from the north. Solomon and Saline rivers are the most important, the former draining the northern part of Kansas and the latter the territory between the Solomon and the Smoky Hill.

The headwater region is a rolling, upland prairie, sparsely timbered along the streams with cottonwood, box elder, hackberry, elm, and willow trees. To the east the stream is bordered by bluffs rising from 100 to 250 feet above the bottoms. The middle portion of the basin is an undulating prairie, well adapted to stock raising and farming. The eastern section is a rich agricultural country, the soil being a black, sandy loam, which produces large and varied crops. There are no lakes or marshes in the area.

The precipitation varies from about 12 inches, in the extreme western part of the basin, to 30 inches in the eastern part. Nearly all of this is rain which falls during the growing season. The snowfall is generally light, is very dry, and never causes any high water. There is an abundant supply of underground water in the western part of the area, but as a rule it is deep. In other sections the supply is good. Numerous springs occur along the banks of the river and its tributaries. There are several good dam sites in the basin, but the flood water carries so much sand and silt that any reservoir would soon fill up.

Floods seldom occur in the upper and middle sections of the river, but in the lower part they are more frequent. The most notable flood in the upper river was that in July, 1895, but this did little damage farther down. The great floods in the lower river occurred in 1903 and 1904. The 1903 flood did much damage.

nation in regard to the basin is contained in United States Geological Survey pub-
s as follows: Eighteenth Annual Report, Part IV, page 207; Twenty-first Annual
Part IV, page 223; Bulletin No. 140, page 138.

SMOKY HILL RIVER AT ELLSWORTH, KANS.

station was established April 16, 1895. It is located at the highway bridge on
s avenue, Ellsworth, Kans.

channel is straight above and below the station at high water, but at other times is
curved. Both banks are low, wooded, and subject to overflow. The bed of the
is composed of sand and is free from vegetation and shifting. The current is medium
nd swift at high stages. The slope of the stream above the gage is 1.44 feet in 2,536
0.000568 foot per foot.

arge measurements are made from the downstream side of the bridge, which is 293
g between abutments and consists of three spans. The initial point for soundings
e noth end of the bridge, downstream side.

gage, which was read during 1905 by Thomas Coyne, is in two sections. The first
is an inclined timber, graduated from zero to 4 feet, securely fastened to the iron
he bridge and to posts driven into the bed of the river. The second section is gradu-
m 3.7 to 21 feet, and spiked to the same pier. The gage is referred to bench marks
ws: (1) A nail driven into the base of a box elder tree near the southeast corner of
lge, 90 feet from the gage; elevation above the zero of the gage, 13.07 feet. (2) The
nail driven into the root on the north side of an elm tree 2 feet in diameter about
west of bench mark No. 1; elevation about 11.34 feet above the zero of the gage.

mation in regard to this station is contained in the following publications of the
States Geological Survey. (Ann.=Annual Report; Bull.=Bulletin. WS.=Water-
Paper):

ption: Ann 18, iv, pp 212-213; Bull 140, p 142; WS 16, p 114; 27, p 90; 37, p 251; 50, p 316; 66, p
110; 99, p 230; 131, pp 108–109.

rge: Ann 18, iv, p 213; Bull 140, p 143; WS 16, p 114; 27, p 95; 37, p 251; 50, p 316, 66, p 45; 84 p
231; 131, p 109.

rge, monthly: Ann 18, iv, p 214; 19, iv, p 347; 20, iv, p 315; 21, iv, p 225; 22, iv, p 336; Bull 140,
S 75, p 143; 84, p 112; 99, p 232; 131, p 111.

rge, yearly: Ann 20, iv, p 56.

eights: Bull 140, p 143; WS 11, p 58; 16, p 114; 27, p 93; 37, p 252; 50, p 317; 66, p 45; 84, p 111;
131, p 109.

graphs: Ann 18, iv, p 215; 19, iv, p 347; 20, iv, p 315; 21, iv, p 226; 22, iv, p 336.

tables: Ann 18, iv, p 214; 19, iv, p 346; WS 27, p 96; 39, p 449; 52, p 517; 66, p 172; 84, p 111; 99,
l. p 110.

Discharge measurements of Smoky Hill River at Ellsworth, Kans., in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	W. G. Russell.....	57	80	2.04	1.55	163
8.....	.....do.....	150	206	1.73	2.25	356

Daily gage height, in feet, of Smoky Hill River at Ellsworth, Kans., for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1		1.8	0.9	1.4	4.0	9.15	2.8	0.9	0.9
2		1.6	.9	1.3	3.2	6.4	3.6	.9	.9
3		1.5	.95	1.3	2.8	6.0	3.2	.9	.85
4		1.5	.9	1.2	3.0	5.0	2.6	.9	.85
5		1.4	.9	1.15	2.6	5.8	2.25	.9	.85
6		1.4	.9	1.1	2.3	4.3	2.2	1.3	.85
7		1.3	.85	1.05	2.1	4.6	2.1	1.1	.85
8		1.25	.85	1.0	2.0	3.4	1.9	1.0	.85
9		1.2	.85	8.5	1.8	3.0	1.8	1.0	.85
10		1.2	.85	2.7	1.7	2.7	1.7	1.0	.85
11		1.2	.85	1.8	1.65	2.6	1.6	1.0	.8
12		1.15	.8	1.6	1.6	2.4	1.5	.95	.8
13		1.15	.8	1.5	1.55	2.3	6.0	.95	.8
14		1.1	.8	1.35	1.5	3.2	4.3	.95	.8
15		1.1	.85	1.3	1.4	2.4	3.6	1.0	.75
16		1.05	.85	1.3	2.2	2.1	3.4	1.0	.75
17		1.05	.8	1.25	1.7	1.9	2.6	1.0	.75
18		1.15	.8	1.2	1.7	1.7	2.0	1.0	.75
19	1.7	1.15	.85	1.25	1.65	1.6	1.7	.95	.75
20	1.7	1.1	.9	1.2	1.8	1.5	1.6	.95	.75
21	3.3	1.1	.9	1.2	1.6	1.55	1.55	.95	.75
22	3.4	1.1	.9	1.2	1.5	1.65	1.5	.9	.7
23	2.1	1.05	.85	1.2	1.4	1.9	1.5	.9	.7
24	1.9	1.05	.9	1.4	1.9	1.85	1.4	.95	.7
25	1.7	1.05	.95	2.5	1.7	1.6	1.35	.95	.9
26	1.8	1.0	.95	1.8	1.5	1.6	1.2	.95	.9
27	1.85	1.0	.95	1.6	1.45	1.5	1.1	.95	.85
28	1.8	.95	1.0	5.5	1.4	1.4	1.1	.95	.85
29		.95	1.5	4.4	1.8	1.6	1.05	.9	.85
30		.95	1.45	3.6	8.4	1.7	1.05	.9	.85
31		.9	.....	3.1	.....	1.7	1.0	.....	.85

NOTE. River frozen January 1 to February 18.

BEAVER RIVER (LADDER CREEK) NEAR SCOTT CITY, KANS.

Beaver River rises in eastern Colorado and flows southeastward, eastward, and then northward to its junction with Smoky Hill River. Its basin, which lies entirely within the Great Plains and chiefly in the arid belt, has a length, east and west, of about 90 miles and an extreme width of not over 25 miles, the total area, measured at the mouth, being 1,464 square miles. The stream has no mountain tributaries but depends for its supply on the precipitation, which ranges from an annual average of about 12 inches at the source to 18 inches near the mouth. There is very little timber in the basin and that is of poor quality. Throughout its middle and lower course the stream flows in a narrow valley between hills 150 to 200 feet high, affording sites for dams and reservoirs; but the dams would be long and expensive and the supply of water from the basin would be insufficient. The tributaries are few and small and furnish little water except in the wet season. Along the lower course of the creek there are very fine springs which furnish water for a small amount of irrigation.

The gaging station was established May 18, 1904. It is located about 18 miles north of Scott City, Kans., at the Hatheway ranch, about 250 yards southwest of H. H. Hatheway's residence.

At low water the channel is very crooked, but after the water covers the bottom the channel is straight for about 100 feet above and below the station. The right bank is high and

ed and does not overflow: the left bank is low and wooded and overflows at high . The bed of the stream is composed of mud and is covered with vegetation and per- nt. There is but one channel at all stages. A heavy growth of willows and other brush along the channel prevents very accurate measurements.

charge measurements are made at low water by wading; at high water the flow must mputed from the cross section and slope, both of which were taken at the time the gage stablished. The initial point for soundings is at the right bank.

e gage, which was read daily by James H. Drain, is a staff, spiked in a perpendicular ion to a willow tree on the left bank. The bench mark is the top of a nail driven into oot of a willow tree about 8 inches in diameter, located on the right bank of the creek t 20 feet northeast of the gage; it is near the surface of the ground and has an elevation 4 feet above the zero of the gage.

description of this station, with gage-height and discharge data, is contained in Water- ly Paper No. 131 of the United States Geological Survey, pages 112–113.

discharge measurement of this creek, made May 18, 1905, by W. G. Russell, gave the ving results: Width, 6 feet; area of section, 5.4 square feet; mean velocity, 1.69 feet per d; gage height, 1.30 feet; discharge, 9.1 second-feet.

y gage height, in feet, of Beaver River (Ladder Creek) near Scott City, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	1.7	1.7	1.8	1.75	3.0	3.0	4.8	8.0	1.5	1.5	1.5
.....	1.7	1.7	1.8	1.6	2.9	2.0	6.0	3.0	1.5	1.5	1.5
.....	1.7	1.8	1.9	1.6	2.9	1.5	5.5	2.5	1.5	1.5	2.0
.....	1.7	1.8	2.0	1.7	2.8	1.0	4.5	2.5	1.5	1.5	2.0
.....	1.7	2.0	1.6	1.7	2.75	1.0	4.0	2.0	2.0	1.5	2.0
.....	1.7	2.0	1.6	1.7	2.65	1.0	3.0	1.5	2.5	1.5	1.5
.....	1.7	2.0	1.6	1.7	2.0	1.0	2.0	1.5	6.0	1.5	1.5
.....	1.8	2.0	1.6	1.7	2.0	1.0	2.0	1.5	5.5	1.5	1.5
.....	1.8	2.0	1.7	1.8	2.0	1.0	1.5	1.5	2.5	1.5	1.5
.....	1.8	2.0	1.7	1.8	1.95	1.0	1.5	1.5	2.5	1.5	1.5
.....	1.8	2.0	1.7	1.9	1.8	4.0	1.5	1.5	2.5	1.5	2.0
.....	1.8	2.0	2.0	1.9	1.75	3.0	1.5	2.0	2.5	1.5	2.0
.....	1.9	2.0	2.0	1.9	1.6	2.5	1.5	1.5	2.5	1.5	1.5
.....	2.0	2.0	2.0	1.9	1.3	2.0	1.5	1.5	2.5	1.5	1.5
.....	2.0	2.0	2.0	1.9	1.3	1.5	1.5	1.5	2.0	1.5	1.5
.....	1.1	2.1	2.0	1.95	1.3	1.5	1.5	1.5	2.0	1.5	1.5
.....	1.1	2.1	2.0	1.95	1.3	1.5	1.5	1.5	2.5	1.5	1.5
.....	1.1	2.1	2.0	1.95	1.3	1.5	1.5	1.5	2.5	1.5	1.5
.....	1.9	2.2	1.9	1.95	1.3	1.5	1.5	1.5	2.5	1.5	1.5
.....	1.9	2.2	1.9	2.0	1.3	4.0	1.5	1.5	2.5	1.5	1.5
.....	1.8	2.2	1.9	2.0	1.3	3.0	1.5	1.5	1.5	1.5	1.5
.....	1.8	2.2	1.85	2.0	1.3	1.5	1.5	1.5	1.5	1.5	1.5
.....	1.8	2.2	1.8	2.0	1.3	1.5	1.5	1.5	1.5	1.5	1.5
.....	1.7	2.2	1.8	2.0	6.0	1.5	3.5	1.5	1.5	1.5	1.5
.....	1.7	2.2	1.8	2.3	4.0	1.5	2.0	1.5	1.5	1.5	1.5
.....	1.7	1.6	1.8	2.3	3.0	1.5	2.0	1.5	1.5	1.5	1.5
.....	1.7	1.6	1.8	2.5	2.5	1.5	1.5	1.5	2.0	1.5	1.5
.....	1.7	1.6	1.8	2.6	6.5	1.5	3.5	1.5	2.0	1.5	1.5
.....	1.7	.....	1.75	2.9	6.5	1.5	2.5	1.5	2.0	1.5	1.5
.....	1.7	.....	1.75	3.0	5.0	5.0	4.5	1.5	2.0	1.5	1.5
.....	1.7	.....	1.75	.....	4.3	.....	3.0	1.5	.....	1.5	.....

KANSAS RIVER.

DESCRIPTION OF BASIN.

Kansas River as such is a comparatively short stream, being formed by the union of Smoky Hill and Republican rivers in Geary County, Kans., whence it flows eastward, entering the Missouri at Kansas City, Mo.

The immediate basin, which comprises the richest portion of the State of Kansas, consists of bottoms and rolling uplands, well timbered with oak, cottonwood, ash, elm, hickory, etc. The section is under a high state of cultivation and produces a great variety of crops.

The river flows through a rich alluvial bottom land. The banks are sandy and easily cave in. In places the bed contains rock and bowlders, but in general it is composed of sand and at many points of quicksand. The channel as a rule hugs one bank or the other and is somewhat shifting. Islands are formed here and there by the deposit of sediment during high water, drift lodges upon them, and a thick growth of brush, mainly cottonwood, soon springs up. At Topeka the river is 900 feet wide between banks. At ordinary low water the channel occupies 150 to 200 feet of this width and has a depth of 8 to 9 feet; at mean high water the average depth of the water is probably 10 feet for the entire distance between banks.

The most important feeder of the Kansas below the junction of Smoky Hill and Republican rivers is the Blue, which rises in southeastern Nebraska, flows to the southeast and south into Kansas, and joins Kansas River at Manhattan. The principal tributary of the Blue is the Little Blue, which rises in southern Nebraska, flows southeastward, and unites with the main stream near Blue Rapids. The Blue runs through a bottom land 1½ miles wide, bordered by bluffs 300 feet high. The banks are of loam and range in height from 10 to 30 feet. The bed is sandy and gravelly, with many limestone ledges. In its lower course the river is about 250 feet wide, and at medium low water has a depth of perhaps 4 feet and a moderate current. The soil of the basin is chiefly a sandy loam with some clay and is generally porous; the region is in a high state of cultivation.

Both the Kansas and the Blue have periods of high water nearly every year, but disastrous floods are rare. The most notable flood on record is that which occurred in May and June, 1903, when the water covered all the low bottom lands, destroying many lives and millions of dollars worth of property.

There are no irrigation projects in the basin, as it is claimed that the rainfall is ample and timely. Good natural dam sites are lacking.

Information in regard to the basin is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Altitudes in: Bull 140, p 124.

Description: Ann 18, iv, p 194; 18, iv, p 215; 19, iv, pp, 337–338; 20 iv, pp 304–305; 21, iv, p 228; 22, iv, p 331; Bull 131, pp 32–33; 140, pp 123–125; WS 75, p 140; 84, p 95; 99, p 208; 131, pp 87–88.

Drainage areas: Bull 140, p 124.

Rainfall and river stations, map: Ann 20, iv, p 305.

Rainfall and run-off relation: Ann 20, iv, p 313.

Rainfall data: Ann 20, iv, pp 305–313.

See also WS 74.

KANSAS RIVER AT LECOMPTON, KANS.

on was established April 16, 1899. It is located at the new wagon bridge at Kans.

el is somewhat curved at the bridge and has a width of 800 feet, broken by four The bridge is slightly oblique to the direction of the current. The left bank is ect to overflow during high water. The bed of the stream is composed of sand, ck, and changes slightly.

measurements are made from the bridge to which the gage is attached. The for soundings is at the first set of piers at the south end of the bridge.

as read during 1905 by A. D. McAdow. The original gage having been broken, as established June 24, 1900. Later a pine board 10 feet long was spiked on top ge, at the same elevation. November 5, 1904, a new gage was put in. This ree sections. The first section is a pine board, graduated from zero to 3 feet, ile 23 feet north of the initial point; the second section is painted on the down- f the second set and graduated from 3 to 10 feet; the third section is painted on pier of the first set and is graduated from 10 to 29.5 feet. October 26, 1900, k was established on top of the bottom flange of the iron strut connecting the ders at the south end of the highway bridge over the river; the bench mark is at of the strut, next to the cylinder; its elevation is 12.19 feet above the zero of the

n in regard to this station is contained in the following publications of the s Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Ann 18, iv, pp 218–219; WS 37, p 253; 50, p 318; 66, p 46; 84, p 95; 99, p 208; 131, pp 91–92.
WS 27, p 95; 37, p 253; 50, p 318; 66, p 46; 84, p 96; 99, p 209; 131, p 92.
nonthly: Ann 21, iv, p 228; 22, iv, p 338; WS 75, p 144; 84, p 97; 99, p 211; 131, p 94.
s: WS 11, p 59; 37, p 254; 50, p 319; 66, p 47; 84, p 96; 99, p 209; 131, p 92.
s: Ann 21, iv, p 229; 22, iv, p 338; WS 75, p 144.
s: WS 39, p 449; 52, p 518; 66, p 172; 84, p 97; 99, p 210; 131, pp 93–94.

scharge measurements of Kansas River at Lecompton, Kans., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
W. G. Russell	744	2,104	2.55	3.20	5,366
do	778	6,164	3.39	7.80	20,920
do	771	5,546	3.39	7.00	18,800
Murphy and Russell	767	5,065	3.02	6.55	15,310
W. G. Russell	777	5,347	3.74	7.55	20,000
J. C. Stevens	801	9,866	5.00	12.35	49,310
W. G. Russell	764	4,573	3.34	6.60	15,250
do	774	4,999	1.91	7.40	9,535
do	644	1,497	2.22	3.30	3,330

[a] Affected by backwater of Delaware River.

Daily gage height, in feet, of Kansas River at Lecompton, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.9	4.1	7.7	4.6	4.2	9.0	9.9	7.3	4.1	5.6	2.6	4.6
2	1.9	4.1	7.7	4.6	4.1	9.9	9.0	7.0	4.0	5.6	2.6	4.55
3	1.9	4.1	7.7	4.6	4.1	9.2	12.3	7.0	3.95	5.6	2.6	4.5
4	1.9	4.1	7.5	4.55	4.0	7.15	11.25	6.6	3.9	5.5	2.6	4.4
5	1.9	4.1	7.4	4.45	4.0	6.5	10.65	7.0	3.9	5.5	2.75	4.3
6	1.9	4.0	7.1	4.4	3.9	6.1	10.7	7.0	3.9	5.5	4.5	4.25
7	1.9	4.0	7.0	4.35	3.9	5.9	10.55	6.8	3.85	5.45	5.4	4.2
8	2.15	4.0	6.85	4.3	3.8	5.5	10.85	6.7	3.8	3.4	5.05	4.2
9	2.35	4.0	6.7	4.1	3.8	5.2	12.1	6.7	3.8	3.4	5.0	4.2
10	2.7	4.0	6.35	3.85	3.7	5.05	12.0	6.7	3.8	3.4	4.15	4.1
11	3.1	4.0	6.25	3.65	5.6	4.7	9.9	6.6	3.7	3.3	3.65	4.0
12	3.6	3.9	6.2	3.45	5.6	4.45	8.95	6.6	3.7	3.3	3.5	3.9
13	3.85	3.9	6.2	3.3	5.6	4.35	8.4	6.6	3.65	3.25	3.5	3.85
14	4.0	3.9	6.2	3.2	5.45	4.05	6.65	6.5	3.9	3.2	3.4	3.8
15	4.05	3.9	6.1	3.2	7.85	4.0	6.3	6.5	10.05	3.15	3.35	3.7
16	4.15	3.8	6.1	3.1	8.45	4.0	5.75	6.4	11.75	3.1	3.3	3.6
17	4.3	3.8	6.1	3.1	7.0	3.95	5.7	6.4	11.8	3.1	3.2	3.5
18	4.3	3.8	6.1	3.0	5.8	3.95	5.0	6.4	12.95	3.1	3.2	3.5
19	4.3	3.8	6.0	2.95	5.6	5.0	4.8	7.0	12.45	3.0	3.2	3.5
20	4.3	3.8	6.0	2.9	5.8	5.0	4.8	7.75	10.25	3.0	3.1	3.4
21	4.3	3.95	5.9	2.9	6.3	4.9	4.7	7.65	8.85	2.95	3.1	3.4
22	4.3	4.3	5.9	2.8	5.9	4.95	4.65	7.25	6.8	2.9	3.05	3.4
23	4.2	4.8	5.85	2.8	5.5	5.75	4.6	6.8	5.95	2.9	3.4	3.4
24	4.2	5.55	5.8	2.8	5.1	6.0	4.6	6.2	5.85	2.85	4.05	3.3
25	4.2	6.8	5.75	2.8	11.5	6.0	4.6	5.35	5.8	2.8	5.4	3.3
26	4.2	7.15	5.7	3.7	10.9	6.6	4.5	4.45	5.75	2.8	5.0	3.3
27	4.2	7.9	5.6	3.7	7.4	7.9	4.5	4.3	5.7	2.7	4.8	3.25
28	4.2	7.7	5.5	4.7	7.15	7.55	4.5	4.25	5.65	2.7	4.75	3.2
29	4.2	.....	5.0	4.5	6.7	8.0	5.1	4.2	5.6	2.7	4.7	3.2
30	4.2	.....	4.7	4.2	6.25	9.0	7.0	4.15	5.6	2.7	4.65	3.2
31	4.15	.....	4.6	.....	7.0	.....	6.85	4.1	.....	2.7	.....	3.2

Station rating table for Kansas River at Lecompton, Kans., from January 1 to September 21, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
1.90	2,525	3.40	5,600	4.90	9,600	7.80	21,100
2.00	2,700	3.50	5,850	5.00	9,900	8.00	22,100
2.10	2,875	3.60	6,100	5.20	10,500	8.20	23,100
2.20	3,050	3.70	6,350	5.40	11,100	8.40	24,200
2.30	3,250	3.80	6,600	5.60	11,750	8.60	25,300
2.40	3,450	3.90	6,850	5.80	12,450	8.80	26,400
2.50	3,650	4.00	7,100	6.00	13,200	9.00	27,500
2.60	3,850	4.10	7,375	6.20	13,950	9.50	30,300
2.70	4,050	4.20	7,650	6.40	14,750	10.00	33,300
2.80	4,250	4.30	7,925	6.60	15,550	10.50	36,550
2.90	4,475	4.40	8,200	6.80	16,400	11.00	39,800
3.00	4,700	4.50	8,475	7.00	17,300	11.50	43,200
3.10	4,925	4.60	8,750	7.20	18,200	12.00	46,900
3.20	5,150	4.70	9,025	7.40	19,100		
3.30	5,375	4.80	9,300	7.60	20,100		

The above table is applicable only for open-channel conditions. It is based on seven dischar measurements made during 1905, and is well defined between gage heights 6 feet and 8 feet.

n rating table for Kansas River at Lecompton, Kans., from September 22 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
2.60	2,000	3.60	4,500	4.60	7,850	5.60	11,500
2.70	2,200	3.70	4,825	4.70	8,200	5.70	11,875
2.80	2,400	3.80	5,150	4.80	8,550	5.80	12,250
2.90	2,625	3.90	5,475	4.90	8,900	5.90	12,650
3.00	2,850	4.00	5,800	5.00	9,250	6.00	13,050
3.10	3,100	4.10	6,125	5.10	9,625	6.20	13,850
3.20	3,350	4.20	6,450	5.20	10,000	6.40	14,675
3.30	3,625	4.30	6,800	5.30	10,375	6.60	15,525
3.40	3,900	4.40	7,150	5.40	10,750	6.80	16,400
3.50	4,200	4.50	7,500	5.50	11,125	7.00	17,300

e above table is applicable only for open-channel conditions. It is based on three discharge urements made during 1905, and is not well defined.

Estimated monthly discharge of Kansas River at Lecompton, Kans., for 1905.

[Drainage area, 58,550 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ary	7,925	2,525	5,932	364,700	0.101	0.116
ary	21,600	6,600	9,008	500,300	.154	.160
h	20,600	8,750	14,370	883,600	.245	.282
	9,025	4,250	6,402	380,600	.109	.122
	43,200	6,350	13,930	856,500	.238	.274
	32,700	6,975	14,180	843,800	.242	.270
	49,150	8,475	21,850	1,344,000	.373	.430
ist	20,850	7,375	14,640	900,200	.250	.288
mber	54,300	6,225	16,570	986,000	.283	.316
ber	11,500	2,200	4,811	295,800	.082	.095
mber	10,750	2,000	5,337	317,600	.091	.102
mber	7,850	3,350	5,035	309,600	.086	.099
The year	54,300	2,000	11,010	7,983,000	.188	2.55

OTE.—Ice conditions uncertain; discharge applied as for open channel.

BLUE RIVER NEAR MANHATTAN, KANS.

his station was established April 12, 1895. It is located at the county bridge 4 miles h of Manhattan, Kans.

he channel is straight for 200 feet above and below the station and has a width of 225 at ordinary stages. Both banks are subject to overflow during very high floods, the left ; being the lower of the two. The bed of the stream is composed of sand, clay, and silt is free from vegetation and slightly shifting. There is but one channel at low stages; luring very high floods there are five channels or more. The current is sluggish at low swift at high stages.

scharge measurements are made from the bridge, which ordinarily spans the entire nel. The initial point for soundings is at the south end of the bridge.

e gage, which was read once each day during 1905 by J. M. Deckert, is in three sections. irst section, used for low-water readings, is a chain gage on the hand railing on the east

side and south end of the bridge, reading from zero to 14 feet from a scale spiked to the hand rail. The second section is an oak rod, reading from 11.3 to 17 feet, spiked to the north face of the south pier. The third section is a similar rod, graduated from 17 to 30 feet, bolted to the south side of the south pier. The gage is referred to bench marks, as follows: (1) A cross cut in the capstone of the south bridge pier immediately above the upper gage; elevation, 32.14 feet above gage datum. (2) A cross near the top of the second stone from the ground in the northwest corner of the south abutment; elevation, 27.32 feet above the zero of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper).

Description: Ann 18, iv, pp 215–216; Bull 140, p 144; WS 16, p 115; 27, p 90; 37, p 252; 50, p 317; 66, p 46; 84, pp 97-98; 99, p 211; 131, p 111.

Discharge: Ann 18, iv, p 216; Bull 140, p 144; WS 16, p 115; 27, p 95; 37, p 252; 50, p 317; 66, p 46; 84, p 98; 99, p 212; 131, p 114.

Discharge, monthly: Ann 18, iv, p 218; 19, iv, p 348; 20, iv, pp 312, 319; 21, iv, p 227; 22, iv, p 337; WS 75, p 143; 84, p 99; 99, p 213; 131, p 117.

Discharge, yearly: Ann 20, iv, p 56.

Gage heights: Bull 140, p 145; WS 11, p 59; 16, p 115; 27, p 94; 37, p 253; 50, p 318; 66, p 46; 84, p 98; 99, p 212; 131, p 115.

Hydrographs: Ann 18, iv, p 219; 19, iv, p 349; 20, iv, p 319; 21, iv, p 227; 22, iv, p 337.

Rainfall and run-off relation: Ann 20, iv, p 313.

Rating tables: Ann 18, iv, p 217; 19, iv, p 348; WS 27, p 96; 39, p 449; 52, p 518; 66, p 172; 84, p 99; 99, p 213; 131, p 116.

Discharge measurements of Blue River near Manhattan, Kans., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 24	W. G. Russell	215	1,135	2.35	7.60	2,670
July 10	J. C. Stevens	223	1,470	2.67	9.33	3,826
August 16	W. G. Russell	208	556	1.86	5.80	1,032
October 5	do	212	601	2.06	6.10	1,234

Daily gage height, in feet, of Blue River near Manhattan, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	5.8	5.9	14.4	6.0	7.5	18.85	9.1	7.2	5.9	6.7
.....	5.9	5.8	13.5	6.0	7.1	17.6	11.1	7.0	5.8	6.4
.....	5.9	5.8	13.3	5.95	6.9	12.8	12.5	7.3	5.6	6.4
.....	6.0	5.8	12.9	6.0	6.7	10.7	13.0	8.4	5.55	6.3
.....	5.9	5.9	12.4	6.0	6.5	9.75	13.1	7.9	5.5	6.1
.....	5.8	6.0	11.7	5.95	6.4	10.3	12.1	7.2	5.6	6.0
.....	5.8	6.1	9.7	5.9	6.2	10.1	11.0	6.8	5.6	6.0
.....	5.7	6.0	8.7	5.9	6.1	8.2	10.8	9.0	5.65	5.9
.....	5.7	6.0	8.2	6.0	6.1	7.7	11.4	7.3	5.6	5.8
.....	5.7	6.0	7.8	5.8	9.2	7.4	9.8	7.1	5.6	5.8
.....	5.8	6.1	7.5	5.9	7.75	7.15	8.85	7.4	5.6	5.75
.....	5.7	6.1	7.2	5.9	6.5	6.9	7.9	6.8	5.7	5.7
.....	5.9	6.0	7.1	5.85	6.8	6.8	7.45	6.3	5.8	5.65
.....	5.6	5.0	6.9	5.8	13.2	6.75	7.1	6.15	6.45	5.6
.....	5.7	5.0	6.8	5.7	14.5	6.6	6.9	6.0	5.8	5.6
.....	5.8	5.1	6.7	5.7	12.8	6.6	6.7	5.8	16.2	5.65
.....	5.8	5.1	6.75	5.65	10.8	7.0	6.6	5.75	21.1	5.7
.....	5.9	5.1	6.8	5.7	10.65	8.7	6.45	5.6	13.5	5.7
.....	5.9	5.2	7.1	5.65	12.3	7.9	6.3	15.2	13.5	5.75
.....	5.9	5.2	7.0	5.6	11.6	8.1	6.2	13.1	14.1	5.8
.....	5.8	5.3	6.85	5.6	9.8	7.7	7.0	8.65	10.5	5.75
.....	5.8	7.1	6.7	5.8	8.9	7.45	7.6	8.2	9.7	6.4
.....	5.8	9.0	6.7	6.5	8.2	8.2	7.1	8.55	9.5	6.0
.....	5.8	9.8	6.65	6.1	7.6	8.1	6.9	8.5	9.45	5.85
.....	5.7	10.0	6.6	6.2	11.3	7.85	6.7	7.5	9.1	5.8
.....	5.7	12.8	6.5	8.7	8.9	8.0	6.75	7.7	8.65	5.7
.....	5.8	14.9	6.4	9.6	7.2	7.8	6.8	6.9	8.2	5.6
.....	5.7	14.0	6.3	8.25	7.7	7.9	7.3	6.7	7.7	5.6
.....	5.7	.....	6.2	8.0	9.2	9.6	7.5	6.45	7.3	5.5
.....	5.9	.....	6.1	7.8	12.5	10.8	7.9	6.2	6.9	5.45
.....	6.0	.....	6.1	.....	17.8	.....	8.0	6.1	.....	5.5

ution rating table for Blue River near Manhattan, Kans., from January 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*	*Feet.*	*Sec.-ft.*
5.00	650	6.50	1,510	8.00	2,680	11.00	5,810
5.10	700	6.60	1,580	8.20	2,850	11.50	6,470
5.20	750	6.70	1,650	8.40	3,020	12.00	7,190
5.30	800	6.80	1,720	8.60	3,190	12.50	7,940
5.40	850	6.90	1,790	8.80	3,370	13.00	8,690
5.50	900	7.00	1,860	9.00	3,550	13.50	9,440
5.60	960	7.10	1,930	9.20	3,740	14.00	10,200
5.70	1,020	7.20	2,010	9.40	3,940	14.50	10,990
5.80	1,080	7.30	2,090	9.60	4,150	15.00	11,800
5.90	1,140	7.40	2,170	9.80	4,370	15.50	12,640
6.00	1,200	7.50	2,255	10.00	4,600	16.00	13,490
6.10	1,260	7.60	2,340	10.20	4,830	16.50	14,340
6.20	1,320	7.70	2,425	10.40	5,070	17.00	15,190
6.30	1,380	7.80	2,510	10.60	5,310	17.50	16,040
6.40	1,440	7.90	2,595	10.80	5,560	18.00	16,900

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1903 and 1905, and is fairly well defined.

Estimated monthly discharge of Blue River near Manhattan, Kans., for 1905.

[Drainage area, 9,490 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dep inc
January	1,200	1,020	1,062	66,530	0.114	
February	11,640	650	2,346	130,300	.247	
March	10,830	1,260	3,237	199,000	.341	
April	4,150	960	1,460	86,880	.154	
May	16,550	1,260	4,282	263,300	.451	
June	18,440	1,580	4,034	240,000	.425	
July	8,840	1,320	3,433	211,100	.362	
August	12,130	960	2,555	157,100	.269	
September	22,770	900	3,827	227,700	.403	
October	1,650	875	1,113	68,440	.117	
The period				1,650,000		

OSAGE RIVER DRAINAGE BASIN.

OSAGE RIVER AT OTTAWA, KANS.

Osage (Marais des Cygnes) River rises in the prairies of eastern Kansas, about 30 southwest of Topeka, and flows southeastward to its junction with the Missouri, near J son City, Mo. The entire length of the stream, measured along the general trend of th ley, the minor bends being neglected, is about 280 miles, but its actual length is probal least 500 miles, and the total area of the basin is about 15,300 square miles.

The eastern portion of the basin has a diversified surface, varying from the level all bottoms of the streams to broken hilly uplands. It is covered with a thick growth of tii including oak, elm, walnut, ash, maple, and many other varieties of trees. To the we surface of the country becomes more gently undulating, the timber gradually disap from the uplands, and the region finally merges with the great prairies which e unbroken to the Rocky Mountains. The river winds through an alluvial bottom approaching first one bluff and then the other. The bed is generally gravel, especial the shoals. The banks are gravelly and stable and range from 18 to 35 feet in height low water. The stream has no mountain tributaries, but depends for its water s entirely on the precipitation within its basin. This ranges from 35 to 40 inches each The basin contains no lakes or marshes of any extent.

The region is rich in mineral resources, and the gently rolling prairies of the weste and the valleys and river bottoms of the eastern half are well adapted to agriculture. 62 per cent of the area is under cultivation and 10 per cent is timbered. Large quar of coal are mined at Osage, Burlingame, Scranton, and Carbondale.

High water is frequent in the stream, but there is little danger of floods unless the r is very heavy, sudden, or of long duration. The danger line is about 25 feet on the The worst flood since the establishment of the gaging station at Ottawa was in 1904, the water rose to 34.4 feet and flooded all the lower bottom lands, doing much dam farms, towns, and cities along the course and stopping all railroad traffic for some tim

The gaging station was established August 26, 1902. It is located at the highway on Main street near the center of the town of Ottawa, Kans.

The channel is slightly curved at the station, and both banks are high, but overflow treme flood stages. The bed of the stream is composed of rock, with small bowlders.

Discharge measurements are made from the highway bridge, which has a span of 1 between abutments and is somewhat oblique to the trend of the stream. The initial

for soundings is the south end of the bridge, downstream side. At low stages the discharge can be measured by wading a short distance below the bridge.

The gage was read once each day during 1905 by W. H. Blacksten. The first gage was of the old wire type, with its scale spiked to the bridge floor. This gage was destroyed by the flood of May 30, 1904. A temporary gage was installed June 3, 1904. A new gage was put in September 9, 1904, as the water had left the temporary gage. This is a standard chain gage, placed on the outside of the hand rail on the downstream side of the bridge. The length of the chain is 30.9 feet. The gage rod is bolted to the hand rail and graduated from zero to 32 feet. The bench mark is the top of the hydrant cap on the north side of the river about 50 feet from the northeast corner of the bridge; elevation 31.34 feet above gage datum.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 41; 130, p 187.
Discharge: 99, p 42; 130, p 188.
Gage heights: 99, p 42; 130, p 188.

Discharge measurements of Osage River at Ottawa, Kans., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 28	W. G. Russell	130	192	3.16	2.40	607
May 11	do	129	128	1.73	1.90	221
May 30	do	133	486	4.19	4.60	2,039
June 17	do	75	58	.67	1.40	39
August 17	do	77	64	.97	1.50	62
September 20	do	138	3,401	4.68	26.15	15,920
September 21	do	138	3,159	4.34	24.45	13,710
September 21	do	138	2,675	3.76	20.80	10,060
September 22	do	133	951	2.80	7.07	2,659
October 10	do	87	83	1.48	1.30	123

Daily gage height, in feet, of Osage River near Ottawa, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	O
1	1.4	1.3	2.5	2.9	1.9	2.5	1.9	2.6	1.35	
2	1.4	1.3	2.0	2.6	1.8	2.2	6.55	2.2	1.3	
3	1.4	1.3	2.0	2.4	1.7	2.1	24.8	2.0	1.3	
4	1.4	1.3	1.9	2.3	1.7	2.0	25.45	2.1	1.8	
5	1.3	1.3	1.8	2.2	1.7	2.0	23.2	3.1	1.6	
6	1.3	1.3	1.6	2.15	1.7	1.9	9.25	2.3	1.7	
7	1.3	1.3	1.6	2.1	1.7	1.8	3.2	2.0	1.7	
8	1.3	1.3	1.6	2.1	1.7	1.8	2.7	1.8	1.7	
9	1.3	1.3	1.5	1.9	2.1	1.6	2.6	1.7	2.3	
10	1.3	1.3	1.6	1.9	2.2	1.6	2.7	1.6	12.35	
11	1.3	1.3	1.5	1.8	2.0	1.5	2.5	1.6	8.6	
12	1.3	1.3	1.4	1.7	1.8	1.5	2.2	1.5	3.1	
13	1.3	1.3	1.5	1.7	2.2	1.5	2.15	1.5	2.2	
14	1.3	1.3	1.5	1.7	2.1	1.45	2.0	1.5	2.1	
15	1.3	1.3	1.5	1.7	2.1	1.4	1.9	1.6	15.35	
16	1.3	1.3	1.5	1.6	2.0	1.4	1.9	1.5	23.45	
17	1.3	1.3	1.45	1.6	1.9	1.4	1.8	1.4	17.85	
18	1.3	1.3	2.9	1.6	1.8	1.35	1.7	3.55	21.95	
19	1.3	1.3	3.3	1.6	1.7	1.6	1.7	10.8	26.28	
20	1.3	1.3	3.1	1.55	1.6	1.8	1.7	3.4	26.18	
21	1.3	1.3	2.5	1.6	1.6	1.7	1.6	2.9	22.15	
22	1.3	2.15	1.65	1.55	1.5	1.6	1.6	2.0	5.35	
23	1.4	4.2	2.2	1.6	1.5	1.6	1.6	1.8	2.7	
24	1.3	5.9	2.9	1.5	1.5	1.5	1.5	1.7	2.6	
25	1.2	6.0	3.05	1.6	3.55	1.5	1.5	1.7	2.2	
26	1.4	4.9	2.4	2.3	16.08	1.4	1.5	1.5	2.0	
27	1.3	3.3	2.15	2.6	14.45	1.5	7.5	1.5	1.9	
28	1.3	2.8	11.27	2.4	3.48	1.5	9.7	1.4	1.7	
29	1.2	.....	17.0	2.1	4.35	2.2	3.75	1.4	1.7	
30	1.2	.....	12.4	2.0	4.4	2.0	2.5	1.4	1.6	
31	1.3	.....	4.2	.....	3.2	.....	2.6	1.4	.....	

GASCONADE RIVER DRAINAGE BASIN.

GASCONADE RIVER AT ARLINGTON, MO.

Gasconade River is formed by Piney, Lock, and Osage forks, which rise in southern souri and unite in Laclede and Pulaski counties. From he junction of the forks to point where the Gasconade enters the Missouri he distance by general course is abou miles, but accurately measured along the stream it is probably over 100 miles. The b comprises a total area of 3,667 square miles. The headwater region is an elevated table- belonging to the Ozark Range of hills. The surface is irregular and along the stream comes very rough and broken. The streams, which are bordered by alluvial bottom l varying in width from a few hundred feet to a half mile, are supplied by a great numb springs, many of which are of large size.

The valley averages half a mile in width and is bordered by bluffs 100 to 200 feet l The bed is usually gravel on the shoals, with considerable sand and mud in the pools. banks are about 20 feet high on the lower river and show a deposit of alluvial soil with s and gravel underneath. The rock occurring along the stream is mainly limestone and stone.

The gaging station was established April 11, 1903. It was at first located about 2 1 below Arlington, on the right bank of the river; but owing to the impossibility of main ing a cable across the river during high water the station was moved July 27, 1904, t

nd San Francisco railroad bridge, 1¼ miles upstream from the cable and one- west of Arlington, Mo.

ınel is straight for about 1,000 feet above and below the bridge. Both banks are partly wooded, and not liable to overflow except during very high stages. The stream is composed of clean gravel and rock and is practically permanent. swift, direct current. At all stages the water passes between the abutments ge.

e measurements are made from the three-span railroad bridge, which has a total 31 feet between abutments. The meter is operated from the upstream lower e trusses. The initial point for soundings is at the top of the inner face of the ıent.

· was read during 1905 by C. W. Harrison. The gage at the old location was a l fastened to a leaning willow tree. The new gage is of the standard chain type. of the chain is 33.50 feet. The pulley center is 0.53 foot to the left of the zero of vhich is 117.01 feet from the initial point for soundings. The bench mark is the top surface of a cap on the upstream lower chord just to the right of the fifth from the right abutment and is designated by a dent in the upper surface of the ion above gage datum 28.85 feet. The elevation of the pulley center above the gage is 32.75 feet.

ıion in regard to this station is contained in the following Water-Supply Papers of States Geological Survey:

n: 99, p 36; 130, pp 188–189.
99, p 36; 130, p 190.
monthly: 99, p 38; 130, p 191.
ıts: 99, p 37: 130, p 190.
ıle: 99, p 37; 130, p 191.

scharge measurements of Gasconade River at Arlington, Mo., 1904–5.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
...	F. W. Hanna	410	2,415	3.32	6.85	8,025
...	.....do	410	4,029	4.20	10.75	16,910
...	Hanna and Murphy	410	1,138	1.78	4.07	2,032
...	M. S. Brennan	318	1,104	1.52	3.80	1,677
...	S. K. Clapp	413	1,944	2.93	5.75	5,700
...	F. W. Hanna	276	838	1.01	2.85	844
...	M. S. Brennan	416	2,049	2.58	6.16	5,283
...	.....do	323	1,071	1.38	3.81	1,479
...	.....do	312	982	1.36	3.55	1,334
...	.....do	301	948	1.32	3.41	1,255

age heights all refer to gage established July 26, 1904, at St. Louis and San Francisco ige.

Daily gage height, in feet, of Gasconade River at Arlington, Mo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	2.85	2.65	6.8	3.95	4.1	4.0	3.7	10.3	4.3	4.3	5.8	
2	2.8	2.7	6.4	3.9	4.0	3.85	3.45	9.5	4.1	4.15	5.2	
3	2.85	2.85	5.9	3.85	4.5	4.0	3.4	8.4	3.8	4.0	4.85	
4	2.8	2.8	5.1	3.8	3.8	3.95	4.0	7.8	3.8	3.9	4.6	
5	2.8	2.85	4.9	3.75	3.75	3.8	4.15	7.7	3.6	3.75	5.5	
6	2.85	2.85	4.7	3.7	3.3	3.4	4.0	6.7	3.65	3.5	6.0	
7	2.8	2.9	5.0	3.65	3.5	3.0	3.85	6.5	4.4	3.45	6.8	
8	2.75	2.85	10.5	3.6	5.1	2.85	3.7	6.4	4.5	3.4	6.9	
9	2.9	2.9	13.5	3.2	6.5	2.5	3.25	4.9	4.6	3.3	6.8	
10	2.85	2.9	11.5	3.15	6.3	2.5	3.45	4.5	4.6	3.6	6.4	
11	2.9	2.9	7.5	3.6	6.2	2.6	3.9	4.3	6.3	3.5	5.0	
12	2.9	2.85	6.5	3.55	5.8	2.55	6.0	3.95	5.8	3.45	4.85	
13	3.0	2.8	5.0	3.7	5.9	2.4	5.7	3.7	5.1	3.2	4.5	
14	2.95	2.85	4.5	3.65	5.8	2.25	5.5	4.5	4.8	3.3	4.3	
15	2.8	2.8	4.3	3.7	7.0	2.2	5.3	4.4	4.0	3.3	4.15	
16	2.95	2.8	4.25	3.75	9.0	3.1	5.25	4.6	3.95	3.15	4.2	
17	2.95	2.85	4.2	3.7	8.0	3.5	4.9	5.4	13.8	3.5	4.0	
18	3.0	2.8	4.3	3.4	5.5	3.15	3.8	5.4	12.5	5.4	3.85	
19	3.1	2.85	4.5	3.35	5.0	3.0	3.6	7.4	16.5	9.3	4.2	
20	3.2	2.8	4.3	3.3	4.5	3.5	3.4	7.0	13.6	7.6	4.3	
21	3.1	2.85	4.1	3.3	4.4	3.3	8.5	7.5	14.0	5.0	4.15	
22	3.05	2.95	3.9	3.25	4.5	3.2	15.7	7.2	10.4	4.85	4.0	
23	3.05	3.0	3.75	3.2	6.1	2.95	20.3	7.5	7.4	4.5	4.05	
24	2.9	3.35	4.0	3.1	5.1	2.9	8.5	7.8	6.3	4.45	3.85	
25	2.8	4.4	3.9	3.4	5.5	2.7	6.3	7.6	5.8	8.5	3.8	
26	2.8	5.9	3.85	4.5	5.1	2.8	5.8	7.3	5.8	9.4	3.6	
27	2.75	6.4	3.7	4.7	4.9	2.75	5.4	6.8	5.0	8.8	3.6	
28	2.8	7.4	3.55	4.8	4.5	2.7	10.9	5.1	4.8	8.5	3.65	
29	2.75	.....	3.75	4.8	4.3	3.2	16.3	5.0	4.7	5.9	3.6	
30	2.7	.....	3.8	4.2	4.0	3.4	19.1	5.1	3.95	5.6	3.45	
31	2.7	.....	3.9	.....	3.8	.....	18.4	4.8	.....	5.7	.....	

NOTE.--Ice conditions not sufficient to modify flow.

Station rating table for Gasconade River at Arlington, Mo., from July 26, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-feet.*	*Feet.*	*Sec.-feet.*
2.20	300	3.70	1,520	5.40	4,710	9.00	12,700
2.30	350	3.80	1,660	5.60	5,130	9.50	13,850
2.40	400	3.90	1,820	5.80	5,560	10.00	15,050
2.50	450	4.00	1,990	6.00	6,000	10.50	16,250
2.60	510	4.10	2,160	6.20	6,440	11.00	17,500
2.70	570	4.20	2,340	6.40	6,880	11.50	18,800
2.80	630	4.30	2,520	6.60	7,320	12.00	20,100
2.90	700	4.40	2,710	6.80	7,760	12.50	21,440
3.00	780	4.50	2,900	7.00	8,200	13.00	22,800
3.10	870	4.60	3,100	7.20	8,640	13.50	24,200
3.20	965	4.70	3,300	7.40	9,080	14.00	25,600
3.30	1,060	4.80	3,500	7.60	9,520	15.00	28,400
3.40	1,160	4.90	3,700	7.80	9,960	16.00	31,400
3.50	1,270	5.00	3,900	8.00	10,400	17.00	34,400
3.60	1,390	5.20	4,300	8.50	11,550	18.00	37,600

The above table is applicable only for open-channel conditions. It is based on twelve discharge measurements made during 1904–5, and is well defined between gage heights 2.8 feet and 10.75 feet. The table has been extended beyond these limits; above gage height 17 feet the rating curve is a tangent, the difference being 320 per tenth.

Estimated monthly discharge of Gasconade River at Arlington, Mo., for 1904 and 1905.

[Drainage area, 2,725 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
1904.						
July	9,108	965	2,580	158,600	0.947	1.09
August	3,900	630	1,256	77,230	.461	.532
September	1,330	740	903	53,730	.331	.369
October	1,110	570	743	45,680	.273	.315
November	700	510	571	33,980	.210	.234
December	740	510	647	39,780	.237	.273
The period				409,000		
1905.						
January	965	570	696	42,800	0.255	0.294
February	9,080	540	1,456	80,860	.534	.556
March	24,200	1,330	4,908	301,800	1.80	2.08
April	3,500	870	1,641	97,650	.602	.672
May	12,700	1,060	4,341	266,900	1.59	1.83
June	1,990	300	899	53,490	.330	.368
July	44,960	1,012	9,534	586,200	3.50	4.04
August	15,770	1,520	6,744	414,700	2.47	2.85
September	32,900	1,390	7,710	458,800	2.83	3.16
October	13,620	918	4,195	257,900	1.54	1.78
November	7,980	1,215	3,350	199,300	1.23	1.37
December	1,660	600	1,104	67,880	.405	.467
The year	44,960	300	3,882	2,828,000	1.42	19.46

NOTE.—The estimate for July 26 to August 11, as published in the 1904 report, has been revised.

INDEX.

A.

Page

nowledgements and cooperation..... 11-12
–foot, definition of..... 3
ncy Ditch at—
Fort Belknap Agency, Mont.:
discharge..... 86
gage heights..... 86
Harlem, Mont.:
description..... 75-76
discharge..... 76
discharge, monthly..... 77
gage heights..... 76
ova, Wyo.
North Platte River at:
description..... 199-200
discharge monthly..... 201
gage heights..... 200
rating table..... 201
ada, Mont.
Little Missouri River at:
description..... 120-121
discharge..... 121
discharge, monthly..... 123
gage heights..... 122
rating table..... 122
ple Creek near—
Bismarck, N Dak.:
description..... 133
discharge..... 133
discharge, monthly..... 133
gage heights..... 133
lington, Mo.
Gasconade River at:
description..... 266-267
discharge..... 267
discharge, monthly..... 269
gage heights..... 268
rating table..... 269
shfield, Mont.
Beaver Creek near:
description..... 63-64
discharge..... 64
discharge, monthly..... 65
gage heights..... 64
rating table..... 65
ugusta, Mont.
B. E. and T. irrigation ditch at:
discharge..... 45
Sun River, North Fork, near:
description..... 38
discharge..... 38
discharge, monthly..... 40
gage heights..... 39
rating table..... 39
Sun River, South Fork, at:
description..... 40
discharge..... 40

Augusta, Mont.—Continued.
Sun River, South Fork, a
discharge, monthly..
gage heights.....
rating table.....
Willow Creek near:
description.....
discharge.....
gage heights.....

B.

B. E. and T. irrigation ditch
Augusta, Mont:
discharge.....
Beaver Creek near—
Ashfield, Mont.:
description.....
discharge.....
discharge, monthly..
gage heights.....
rating table.....
Beaver Creek near—
Edgemont, S. Dak.:
description.....
discharge.....
gage heights.....
Beaver Creek, Nebr., in—
Sec. 19, T. 32 N., R. 16 W
discharge.....
Beaver Creek overflow near–
Bowdoin, Mont.:
description.....
discharge.....
discharge, monthly.
gage heights.....
Beaver River (Ladder Creek
Scott City, Kans.:
description.....
discharge, monthly.
gage heights.....
Belle Fourche River at—
Belle Fourche, S. Dak.:
description.....
discharge.....
discharge, monthly.
gage heights.....
rating table.....
Belle Fourche, S. Dak.
Belle Fourche River at:
description.....
discharge.....
discharge, monthly.
gage heights.....
rating table.....

Belle Fourche, S. Dak.—Continued. Page
Redwater Creek at:
description 159
discharge 160
discharge, monthly 161
gage heights 160
rating table 161
Belleview, Mont.
Teton River near:
description 52
discharge 52
Belt Creek near—
Belt, Mont.:
description 45
discharge 45
discharge, monthly 46
Belt, Mont.
Belt Creek near:
description 45
discharge 45
gage heights 46
Benkelman, Nebr.
Republican River at:
description 247
discharge 248
gage heights 248
Republican River, South Fork, at:
description 249
discharge 249
discharge, monthly 251
gage heights 250
rating table 250
Republican River, North Fork, at:
discharge 254
Bighorn River at—
Fort Custer, Mont.:
description 108
discharge 109
discharge, monthly 110
gage heights 109
rating table 110
Thermopolis, Wyo.:
description 106
discharge 106
discharge, monthly 108
gage heights 107
rating table 107
Billings, Mont.
Yellowstone River near:
description 95
discharge 96
discharge, monthly 97
gage heights 96
rating table 97
Bismarck, N. Dak.
Apple Creek near:
description 133
discharge 133
discharge, monthly 133
gage heights 133
Missouri River near:
description 30
discharge 31
discharge, monthly 32
gage heights 31
rating table 32
Bixby, S. Dak.
Moreau River at:
description
discharge
discharge, monthly
gage heights
rating table
Blackhawk, S. Dak.
Boxelder Creek at:
description
discharge
discharge, monthly
gage heights
rating table
Blue River near—
Manhattan, Kans.:
description
discharge
discharge, monthly
gage heights
rating table
Bostwick, Nebr.
Republican River near:
description
discharge
discharge, monthly
gage heights
rating table
Bowdoin, Mont.
Beaver Creek overflow near:
description
discharge
discharge, monthly
gage heights
Boxelder Creek at—
Blackhawk, S. Dak.:
description
discharge
discharge, monthly
gage heights
rating table
Bridgeport, Nebr.
North Platte River:
description
discharge
discharge, monthly
gage heights
rating table
Broncho, N. Dak.
Knife River at:
description
discharge
gage heights
Browning, Mont.
Milk River, South Fork near:
description
discharge
discharge, monthly
gage heights

C.

Cable station, figure showing
Camp Crook, S. Dak.
Little Missouri River at:
description
discharge

ıued. Page.
-Continued.
..... 125
..... 124
..... 125
..... 187–188
..... 188
..... 190
..... 189
..... 189
..... 134
..... 134
..... 135
..... 24
..... 25
..... 26
..... 25
..... 26
..... 36
..... 234
..... 141
..... 141
..... 143–144
..... 145
..... 142
..... 140
..... 70
..... 70
..... 71
..... 71
..... 83
near:
..... 82–83
:
..... 77
..... 78
..... 79
..... 78
..... 72
..... 72
..... 73
..... 73
..... 86
..... 86
near:
..... 61
..... 62

Chinook, Mont.—Continued. Page.
Milk River, North Fork, near—Cont'd.
discharge, monthly..... 63
gage heights 62
rating table..... 63
Milk River, West Fork, at:
discharge..... 86
gage heights..... 86
Paradise Valley canal near:
description..... 67–68
discharge..... 68
discharge, monthly..... 69
gage heights..... 69
Reser ditch near:
description..... 79
discharge..... 79
discharge, monthly..... 80
gage heights..... 80
Roketa ditch near:
description..... 83
West Fork ditch near:
description. 81
discharge..... 81
discharge, monthly..... 82
gage heights 82
Winter Anderson canal near:
description..... 83
Chouteau, Mont.
Teton River near:
description..... 53–54
discharge..... 54
gage heights..... 54
Clark Fork at—
Fromberg, Mont.:
description..... 100–101
discharge..... 101
discharge, monthly..... 103
gage heights..... 102
rating table..... 102
Clear Creek at
Forkscreek, Colo.:
description..... 231–232
discharge..... 232
discharge, monthly..... 234
gage heights..... 233
rating table..... 233
Cody, Wyo.
Shoshone River near:
description..... 113
discharge..... 114
discharge, monthly..... 115
gage heights..... 114
Columbus, Nebr.
Loup River at:
description..... 240–241
discharge..... 241
discharge, daily..... 243
discharge, monthly..... 243
gage heights..... 242
Platte River near:
description..... 237
discharge..... 238
discharge, monthly..... 239
gage heights..... 238
rating table..... 230

Page.

Corregan ditch near—
Chinook, Mont.:
description ... 83
Computation, methods of ... 10–12
rules for ... 4
Cook Canal near—
Chinook, Mont:
description ... 70
discharge ... 70
discharge, monthly ... 71
gage heights ... 71
Cooperation and acknowledgments ... 11–1
Cowdrey, Colo.
Canadian River at:
description ... 187–188
discharge ... 188
discharge, monthly ... 190
gage heights ... 189
rating table ... 189
Michigan Creek near:
description ... 192
discharge ... 193
discharge, monthly ... 194
gage heights ... 193
rating table ... 194
North Platte River near:
description ... 185–186
discharge ... 186
discharge, monthly ... 187
gage heights ... 186
rating table ... 187
Crow Agency, Mont.
Little Bighorn River at:
description ... 111
discharge ... 111
discharge, monthly ... 113
gage heights ... 112
rating table ... 112
Current meters, classes of ... 8
methods of using ... 8–9
Cutbank Creek at—
Cutbank, Mont.:
description ... 50
discharge ... 51
gage heights ... 51
seepage measurements ... 85
Cutbank, Mont.
Cutbank Creek at:
description ... 50
discharge ... 51
gage heights ... 51

D.

Denver, Colo.
South Platte River at:
description ... 223–224
discharge ... 224
discharge, daily ... 226
discharge, monthly ... 226
gage heights ... 225
Dowen and Buckley ditch near—
Chinook, Mont.:
description ... 82–83
Drainage basins, list of ... 2–3

E.

Eagle Creek, North Fork at—
Sec. 26, T. 31 N., R. 13 W., Nebr.:
discharge ... 173
Eagle Creek, South Fork at—
Sec. 9, T. 30 N., R. 13 W., Nebr.:
discharge ... 173
Edgemont, S. Dak.
Beaver Creek near:
description ... 145–146
discharge ... 146
gage heights ... 146
Cheyenne River at:
description ... 1
discharge ... 143
discharge, daily ...
discharge, monthly ...
gage heights ...
Hat Creek near:
description ...
discharge ...
discharge, monthly ...
gage heights ...
Ellsworth, Kans.
Smoky Hill River at:
description ...
discharge ...
gage heights ...
Equivalents, table of ...

F.

Floats, use of, in measuring discharge ...
Ford Creek, Mont.
discharge ...
Forkscreek, Colo.
Clear Creek at:
description ... 231–
discharge ...
discharge, monthly ...
gage heights ...
rating table ...
Fort Belknap Agency—
Milk River at:
discharge ...
gage heights ...
Fort Belknap canal near—
Chinook, Mont.:
description ...
discharge ...
discharge, monthly ...
gage heights ...
Fort Custer, Mont.
Bighorn River at:
description ... 1
discharge ... 1
discharge, monthly ... 1
gage heights ... 1
rating table ... 1
Fromberg, Mont.
Clark Fork at:
description ... 100–
discharge ...
discharge, monthly ...
gage heights ...
rating table ...

G.

Gaging stations, equipment of ...
Gallatin River at—
Logan, Mont.:
description ... 1
discharge ...
discharge, monthly ...
gage heights ...
rating table ...

Page.

rande River at—
Hington, Mo.:
description 266–267
discharge 267
discharge, monthly 269
gage heights 268
rating table 269
ney, Colo.
ramie River at:
description 209–210
discharge 210
discharge, monthly 212
gage heights 211
rating table 211
ve, Mont.
ellowstone River at:
description 97–98
discharge 98
discharge, monthly 100
gage heights 99
rating table 100
yre, Colo.
cIntyre Creek at:
description 214–215
discharge 215
discharge, monthly 216
gage heights 215
rating table 216
ad River at—
Selm, S. Dak.:
description 135–136
discharge 136
discharge, monthly 137
gage heights 136
rating table 137
eat Falls, Mont.
Missouri River at:
description 26–27
discharge 36
Water used by Boston and Montana Smelter 27–28
rizzly Creek at—
Hebron, Colo.:
description 174–175
discharge 175
discharge, monthly 176
gage heights 175
rating table 176
uernsey, Wyo.
North Platte River at:
description 196–197
discharge 197
discharge, monthly 199
gage heights 198
rating table 198–199

H.

Harlem Canal near—
Zurich, Mont.:
description 74
discharge 74
discharge, monthly 75
gage heights 75
Harlem, Mont.
Agency ditch near:
description 75–76
discharge 76
discharge, monthly 77
gage heights 76

Harlem, Mont.—Continued. Page.
Milk River at:
description 86
discharge 86
gage heights 86
Parallel Creek ditches near:
description 83
Hat Creek near—
Edgemont, S. Dak.:
description 147
discharge 147
discharge, monthly 148
gage heights 148
Havre, Mont.
Milk River at:
description 57
discharge 57
discharge, monthly 59
gage heights 58
rating table 58–59
Heart River near—
Richardton, N. Dak.:
description 130–131
discharge 131
discharge, monthly 132
gage heights 131
rating table 132
Hebron, Colo.
Grizzly Creek at:
description 174–175
discharge 175
discharge, monthly 176
gage heights 175
rating table 176
Hebron, Colo.
Little Grizzly Creek at:
description 176–177
discharge 177
discharge, monthly 178
gage heights 177
rating table 178
North Platte River near:
description 183
discharge 184
discharge, monthly 185
gage heights 184
rating table 185
North Platte River, Roaring Fork near:
description 178–179
discharge 179
discharge, monthly 181
gage heights 180
rating table 180
Higho, Colo.
North Platte River, North Fork, at:
description 181–182
discharge 182
discharge, monthly 183
gage heights 182
rating table 183
Highwood Creek near—
Highwood, Mont.:
description 46
discharge 47
gage heights 47
Highwood, Mont.
Highwood Creek near:
description 46

Highwood, Mont.—Continued. Page.
Highwood Creek, near—Continued.
discharge 47
gage heights 47
Hinsdale, Mont.
Milk River at:
discharge 86
gage heights 86
Rock Creek:
discharge 86
gage heights 86
Rock Creek canal near:
description 83-84
discharge 84
discharge, monthly 84
gage heights 84
Huntley, Mont.
Pryor Creek at:
description 103
discharge 103
discharge, monthly 105
gage heights 104
rating tables 105
Hydrographic surveys, annual appropriations for 1
organization and scope of 1-3

I.

Ice-covered streams, methods of measuring flow of 9-10
Interior, S. Dak.
White River at:
description 166
discharge 167
gage heights 167

J.

Jefferson River near—
Sappington, Mont.:
description 13-14
discharge 14
discharge, monthly 16
gage heights 15
rating table 15
Jelm, Wyo.
Laramie River near:
description 212
discharge 213
discharge, monthly 214
gage heights 213
rating table 214
Julesburg, Colo.
South Platte River near:
description 229
discharge 230
discharge, monthly 231
gage heights 230
rating table 231
Junction, Kans.
Republican River at:
description 251-252
discharge 252
discharge, monthly 254
gage heights 252
rating table 253

K.

Kansas City, Mo.
Missouri River at:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Kansas River at—
Lecompton, Kans.:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Kansas River drainage basin:
description .....
miscellaneous measurements in ...
Kearney, Wyo.
Piney Creek at:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating tables .....
Kersey, Colo.
South Platte River near:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating tables .....
Keya Paha River:
discharge .....
Knife River at—
Broncho, N. Dak.:
description .....
discharge .....
gage heights .....

L.

Ladder Creek. *See* Beaver River.
Laramie River at—
Glendevey, Colo.:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Jelm, Wyo.:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Lecompton, Kans.
Kansas River at:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Lexington, Nebr.
Platte River near:
description .....

ington, Nebr.—Continued. Page.
Platte River near—Continued.
discharge ... 236
gage heights ... 236
tle Bighorn River at—
Crow Agency Mont.:
description ... 111
discharge ... 111
discharge, monthly ... 113
gage heights ... 112
rating table ... 112
tle Grizzly Creek at—
Hebron, Colo.:
description ... 176–177
discharge ... 177
discharge, monthly ... 178
gage heights ... 177
rating tables ... 178
tle Missouri River at—
Alzada, Mont.:
description ... 120–121
discharge ... 121
discharge, monthly ... 123
gage heights ... 122
rating table ... 122
Camp Crook, S. Dak.:
description ... 123
discharge ... 124
discharge, monthly ... 125
gage heights ... 124
rating table ... 125
Medora, N. Dak.:
description ... 125–126
discharge ... 126
discharge, monthly ... 128
gage heights ... 127
rating table ... 128
ittle Missouri River basin—
description ... 120
ittle Muddy River near—
Williston, N. Dak.:
description ... 89
discharge ... 89
discharge, monthly ... 91
gage heights ... 90
rating table ... 90
ittle Sioux River at—
Cherokee, Iowa:
discharge ... 36
ivingston, Mont.
Yellowstone River at:
description ... 92–93
discharge ... 93
discharge, monthly ... 95
gage heights ... 94
rating table ... 94
ogan, Mont.
Gallatin River at:
description ... 18–19
discharge ... 19
discharge, monthly ... 21
gage heights ... 20
rating table ... 20
ombard, Mont.
Sixteen Mile Creek at:
discharge ... 36
Loup River at— Page.
Columbus, Nebr.:
description ... 240–241
discharge ... 241
discharge, daily ... 243
discharge, monthly ... 243
gage heights ... 242

M.

McIntyre Creek at—
Gleneyre, Colo.:
description ... 214–215
discharge ... 215
discharge, monthly ... 216
gage heights ... 215
rating table ... 216
Madison River (including Cherry Creek) near—
Norris, Mont.:
description ... 16
discharge ... 17
discharge, monthly ... 18
gage heights ... 17
rating table ... 18
Malta, Mont.
Milk River at:
description ... 59–60
discharge ... 60
discharge, monthly ... 61
gage heights ... 60
rating table ... 61
Manhattan, Kans.
Blue River near:
description ... 261–262
discharge ... 262
discharge, monthly ... 264
gage heights ... 263
rating table ... 263
Mannhaven, N. Dak.
Missouri River at:
discharge ... 36
Marias River near—
Shelby, Mont.:
description ... 48
discharge ... 49
discharge, monthly ... 50
gage heights ... 49
rating table ... 50
Marias River basin:
description ... 48
Marquette, Wyo.
Shoshone River, South Fork, at:
description ... 115
discharge ... 116
discharge, monthly ... 117
gage heights ... 116
rating table ... 117
Matheson canal near—
Chinook, Mont.:
description ... 72
discharge ... 72
discharge, monthly ... 73
gage heights ... 73
Medora, N. Dak.
Little Missouri at:
description ... 125–126
discharge ... 126

Medora, N. Dak.—Continued. Page.
Little Missouri at—Continued.
discharge, monthly 128
gage heights 127
rating table 128
Methods of computing run-off 10–11
of measuring stream flow 6–10
Michigan Creek near—
Cowdrey, Colo.:
description 192
discharge 193
discharge, monthly 194
gage heights 193
rating table 194
Walden, Colo.:
description 190–191
discharge 191
discharge, monthly 192
gage heights 191
rating table 191
Milk River at—
Chinook, Mont.:
discharge 86
gage heights 86
Harlem, Mont.:
discharge 86
gage heights 86
Havre, Mont.:
description 57
discharge 57
discharge, monthly 59
gage heights 58
rating table 58–59
Hinsdale, Mont.:
discharge 86
gage heights 86
Seepage measurements 85
Yantic, Mont.:
discharge 86
gage heights 86
Zurich, Mont.:
discharge 86
gage heights 86
Milk River, North Fork, near—
Chinook, Mont.:
description 61
discharge 62
discharge, monthly 63
gage heights 62
rating table 63
Milk River, South Fork near—
Browning, Mont.:
description 55
discharge 55
discharge, monthly 56
gage heights 56
Milk River, West Fork at—
Chinook, Mont.:
description .....
discharge 86
gage heights 86
Milk River basin:
description 54–55
miscellaneous measurements in 86
Milk River Valley—
Private canals in:
description 67
discharge 67–84
Miner's inch, definition of .....
Minnesela, S. Dak.
Redwater Canal at:
description .....
discharge .....
discharge, daily .....
discharge, monthly .....
gage heights .....
Missouri River at and near—
Bismarck, N. Dak.
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Cascade, Mont.:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Great Falls, Mont.:
description .....
discharge .....
water used by Boston a
Smelter .....
Kansas City, Mo.:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Mannhaven, N Dak.:
discharge .....
Washburn, N. Dak.
description .....
gage heights .....
Williston, N. Dak.:
description .....
discharge .....
gage heights .....
Missouri River basin:
description .....
miscellaneous measurements
Mitchell, Nebr.
North Platte River near:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Moreau River at—
Bixby, S. Dak.:
description .....
discharge .....
discharge, monthly .....
gage heights .....
rating table .....
Multiple-point method of mea
charge, description o
Musselshell River at—
Shawmut, Mont.:
description .....
discharge .....
gage heights .....
Niobrara River
Valentine,
descri

Page.
[illegible] River near—Continued.
[illegible]ntine, Nebr.—Continued.
discharge 169
discharge, daily 171
discharge, monthly 171
gage heights 170
[illegible] River basin:
[illegible]cription 167–168
[illegible]cellaneous measurements 173
[illegible] Mont.
[illegible]dison River (including Cherry Creek) near:
description 16
discharge 17
discharge, monthly 18
gage heights 17
rating tables 18
[illegible] Fork Milk River. *See* Milk River, North Fork.
[illegible] Platte, Nebr.
[illegible]rth Platte River at:
description 207
discharge 207
discharge, monthly 209
gage heights 208
rating table 208
[illegible]uth Platte River at:
discharge 234
[illegible] Platte River at and near—
[illegible]coya, Wyo.:
description 199–200
discharge, monthly 201
gage heights 200
rating table 201
[illegible]ridgeport, Nebr.:
description 204
discharge 205
discharge, monthly 206
gage heights 205
rating table 206
[illegible]owdrey, Colo.:
description 185–186
discharge 186
discharge, monthly 187
gage heights 186
rating table 187
Guernsey, Wyo.:
description 196–197
discharge 197
discharge, monthly 199
gage heights 198
rating table 198–199
Hebron, Colo.:
description 183
discharge 184
discharge, monthly 185
gage heights 184
rating table 185
[illegible]itchell, Nebr.:
description 202
discharge 202
discharge, monthly 204
gage heights 202
rating table 202
North Platte, Nebr.:
description 207
discharge 207

Page.
North Platte River at and near—Cont'd.
North Platte, Nebr.—Continued.
discharge, monthly 209
gage heights 208
rating table 208
Saratoga, Wyo.:
description 194
discharge 195
discharge, monthly 196
gage heights 195
rating table 196
North Platte basin:
description 173–174
North Platte River, North Fork, at—
Higho, Colo.:
description 181–182
discharge 182
discharge, monthly 183
gage heights 182
rating tables 183
North Platte River, Roaring Fork, near—
Hebron, Colo.:
description 178–179
discharge 179
discharge, monthly 181
gage heights 180
rating table 180

O.

Osage River at—
Ottawa, Kans.:
description 264–265
discharge 265
gage heights 266
Ottawa, Kans.
Osage River at:
description 264–265
discharge 265
gage heights 266

P.

Paradise Valley canal near—
Chinook, Mont.:
description 67–68
discharge 68
discharge, monthly 69
gage heights 69
Parallel Creek ditches near—
Harlem, Mont.:
description 83
Piney Creek at—
Kearney, Wyo.:
description 117–118
discharge 118
discharge, monthly 120
gage heights 119
rating table 120
Platte River near—
Columbus, Nebr.:
description 237
discharge 238
discharge, monthly 239
gage heights 238
rating table 239
Lexington, Nebr.:
description 235

Platte River near—Continued. Page.
Lexington, Nebr.—Continued.
discharge ... 236
gage heights ... 236
Platte River basin:
description ... 173, 234-235
Pryor Creek at—
Huntley, Mont.:
description ... 103
discharge ... 103
discharge, monthly ... 105
gage heights ... 104
rating table ... 105

R.

Rapid Creek at—
Rapid, S. Dak.:
description ... 151
discharge ... 152
discharge, monthly ... 153
gage heights ... 152
rating table ... 153
Rapid, S. Dak.
Rapid Creek at:
description ... 151
discharge ... 152
discharge, monthly ... 153
gage heights ... 152
rating table ... 153
Spring Creek near:
description ... 149
discharge ... 149
discharge, monthly ... 151
gage heights ... 150
rating table ... 150
Rating curves, methods of constructing ... 10-11
Rating tables, methods of constructing ... 10, 11
Red Deer Lake near—
Woodlake, Nebr.:
description ... 172
gage heights ... 172
Redwater canal at -
Minnesela, S. Dak.:
description ... 163
discharge ... 164
discharge, daily ... 165
discharge, monthly ... 166
gage heights ... 164
Redwater Creek at-
Belle Fourche, S. Dak.:
description ... 159
discharge ... 160
discharge, monthly ... 161
gage heights ... 160
rating table ... 161
Republican River at and near
Benkelman, Nebr.:
description ... 247
discharge ... 248
gage heights ... 248
Bostwick, Nebr.:
description ... 244-245
discharge ... 245
discharge, monthly ... 247
gage heights ... 245
rating table ... 246
Junction, Kans.:
description ... 251-252
discharge ... 252
Republican River at and near—Cor
Junction, Kans.—Continued.
discharge, monthly ...
gage heights ...
rating table ...
Republican River basin:
description ...
Republican River, North Fork, at-
Benkelman, Nebr.
discharge ...
Republican River, South Fork, at-
Benkelman, Nebr.:
description ...
discharge ...
discharge, monthly ...
gage heights ...
rating table ...
Reser ditch near—
Chinook, Mont.:
description ...
discharge ...
discharge, monthly ...
gage heights ...
Richardton, N. Dak.
Heart River near:
description ...
discharge ...
discharge, monthly ...
gage heights ...
rating table ...
Roaring Fork River. *See* North River, Roaring Fork.
Rock Creek at—
Hinsdale, Mont.:
discharge ...
gage heights ...
Rock Creek canal near—
Hinsdale, Mont.:
description ...
discharge ...
discharge, monthly ...
gage heights ...
Rok ta ditch near—
Chinook, Mont.:
description ...
Rules for computation ...
Run-off, office methods of computi
in inches, definition of ...

S.

Salesville, Mont.
West Gallatin River near:
description ...
discharge ...
discharge, monthly ...
gage heights ...
rating table ...
Sappington, Mont.
Jefferson River near:
description ...
discharge ...
discharge, monthly ...
gage heights ...
rating table ...
Saratoga, Wyo.
North Platte River at:
description ...
discharge ...
discharge, monthly ...

Page

toga, Wyo.—Continued.
North Platte River at—Continued.
gage heights ... 195
rating table ... 196
t City, Kans.
Beaver River (Ladder Creek) near:
description ... 256-257
gage heights ... 257
ond-foot, definition of ... 3
page measurements:
Cutbank Creek, Mont. ... 85
Milk River, Mont. ... 85
n, S. Dak.
Grand River at:
description ... 135-136
discharge ... 136
discharge, monthly ... 137
gage heights ... 136
rating table ... 137
awmut, Mont.
Musselshell River at:
description ... 87
discharge ... 88
gage heights ... 88
elby, Mont.
Marias River near:
description ... 48
discharge ... 49
discharge, monthly ... 50
gage heights ... 49
rating table ... 50
oshone River near—
Cody, Wyo.:
description ... 113
discharge ... 114
discharge, monthly ... 115
gage heights ... 114
oshone River, South Fork, at—
Marquette, Wyo.:
description ... 115
discharge ... 116
discharge, monthly ... 117
gage heights ... 116
rating table ... 117
ingle-point method of measuring discharge, description of ... 9
ixteen Mile Creek at—
Lombard, Mont.:
discharge ... 36
lope method of measuring discharge, use and value of ... 6
mith River at—
Truly, Mont.:
description ... 36
discharge ... 37
gage heights ... 37
moky Hill River basin:
description ... 254
moky Hill River at—
Ellsworth, Kans.:
description ... 255
discharge ... 255
gage heights ... 256
uth Fork Milk River. *See* Milk River, South Fork.
uth Fork Republican River. *See* Republican River, South Fork.

Page

South Fork South Platte River. *See* South Platte River, South Fork.
South Platte, Colo.
South Platte River at:
description ... 217-218
discharge ... 219
discharge, monthly ... 220
gage heights ... 219
rating table ... 220
South Platte River South Fork, at:
description ... 220-221
discharge ... 221
discharge, monthly ... 223
gage heights ... 222
rating table ... 222
South Platte River at and near—
Denver, Colo.:
description ... 223-224
discharge ... 224
discharge, daily ... 226
discharge, monthly ... 226
gage heights ... 225
Julesburg, Colo.:
description ... 229
discharge ... 230
discharge, monthly ... 231
gage heights ... 230
rating table ... 231
Kersey, Colo.:
description ... 227
discharge ... 227
discharge, monthly ... 229
gage heights ... 228
rating table ... 228
North Platte, Nebr.:
description ... 234
South Platte, Colo.
description ... 217-218
discharge ... 219
discharge, monthly ... 220
gage heights ... 219
rating table ... 220
South Platte basin:
description ... 216-217
miscellaneous measurements ... 234
South Platte River, South Fork, at—
South Platte, Colo.:
description ... 220-221
discharge ... 221
discharge, monthly ... 223
gage heights ... 222
rating table ... 222
Spearfish Creek near—
Spearfish, S. Dak.:
description ... 161-162
discharge ... 162
discharge, monthly ... 163
gage heights ... 162
rating tables ... 163
Spearfish, S. Dak.
Spearfish Creek near:
description ... 161-162
discharge ... 162
discharge, monthly ... 163
gage heights ... 162
rating tables ... 163

Spring Creek near— Page
Rapid, S. Dak.:
description 149
discharge 149
discharge, monthly 151
gage heights 150
rating tables 150
Stevenson, N. Dak.
Cannon Ball River at:
description 134
discharge 134
gage heights 135
Stream flow, field methods of measuring 6–10
Sun River at—
Sun River, Mont.:
description 42
discharge 42
discharge, monthly 43
gage heights 43
Sun River basin:
description 37–38
miscellaneous measurements 45
Sun River, Mont.
Sun River at:
description 42
discharge 42
discharge, monthly 43
gage heights 43
Sun River, North Fork near—
Augusta, Mont.:
description 38
discharge 38
discharge, monthly 40
gage heights 39
rating tables 39
Sun River, South Fork at—
Augusta, Mont.:
description 40
discharge 40
discharge, monthly 42
gage heights 41
rating tables 41

T.

Tables, explanation of 4
Teton River near
Belleview, Mont.:
description 52
discharge 52
gage heights 53
Choteau, Mont.:
description 53–54
discharge 54
gage heights 54
Thermopolis, Wyo.
Bighorn River at:
description 106
discharge 106
discharge, monthly 108
gage heights 107
rating table 107
Truly, Mont.
Smith River at:
description 36
discharge 37
gage heights 37

V. Page
Valentine, Nebr.
Niobrara River near:
description 168–169
discharge 169
discharge, daily 171
discharge, monthly 171
gage heights 170
Velocity method of measuring discharge, description of 7–9
Vertical-integration method of measuring discharge, description of 9
Vertical-velocity-curve method of measuring discharge, description of 8–9

W.

Walden, Colo.
Michigan Creek near:
description 190–191
discharge 191
discharge, monthly 192
gage heights 191
rating table 191
Washburn, N. Dak.
Missouri River at:
description 30
gage heights 30
Weir method of measuring discharge, requirements of 6–7
West Fork ditch near—
Chinook, Mont.:
description 81
discharge 81
discharge, monthly 82
gage heights 82
West Gallatin River near—
Salesville, Mont.:
description 21
discharge 22
discharge, monthly 24
gage heights 23
rating table 23
White River at—
Interior, S. Dak.:
description 166
discharge 167
gage heights 167
Williston, N. Dak.
Little Muddy River at:
description 89
discharge 89
discharge, monthly 91
gage heights 90
rating table 90
Missouri River near:
description 28–29
discharge 29
gage heights 29
Willow Creek near—
Augusta, Mont.:
description 43–44
discharge 44
gage heights 44
Winter-Anderson
Chinook, M
desc

Woodlake, Nebr. Page.
Red Deer Lake near:.
description 172
gage heights 172

Y.

Yantic, Mont.
Milk River at:
discharge 86
gage heights 86
Yellowstone River at and near—
Billings, Mont.:
description 95
discharge 96
discharge, monthly 97
gage heights 96
rating table 97
Glendive, Mont.:
description 97-98
discharge 98
discharge, monthly 100
gage heights 99
Yellowstone River at and near—Cont'd. Page.
Glendive, Mont.—Continued.
rating table 100
Livingston, Mont.:
description 92-93
discharge 93
discharge, monthly 95
gage heights 94
rating table 94
Yellowstone River basin:
description 91-92

Z.

Zurich, Mont.
Harlem Canal near:
description 74
discharge 74
discharge, monthly 75
gage heights 75
Milk River at:
discharge 86
gage heights 86

CLASSIFICATION OF THE PUBLICATIONS OF THE UNITED STATES GEOLOGICAL SURVEY.

[Water-Supply Paper No. 172.]

The publications of the United States Geological Survey consist of (1) Annual Reports, (2) Monographs, (3) Professional Papers, (4) Bulletins, (5) Mineral Resources, (6) Water-Supply and Irrigation Papers, (7) Topographic Atlas of United States—folios and separate sheets thereof, (8) Geologic Atlas of United States—folios thereof. The classes numbered 2, 7, and 8 are sold at cost of publication; the others are distributed free. A circular giving complete lists may be had on application.

Most of the above publications may be obtained or consulted in the following ways:

1. A limited number are delivered to the Director of the Survey, from whom they may be obtained, free of charge (except classes 2, 7, and 8), on application.
2. A certain number are delivered to Senators and Representatives in Congress, for distribution.
3. Other copies are deposited with the Superintendent of Documents, Washington, D. C., from whom they may be had at practically cost.
4. Copies of all Government publications are furnished to the principal public libraries in the large cities throughout the United States, where they may be consulted by those interested.

The Professional Papers, Bulletins, and Water-Supply Papers treat of a variety of subjects, and the total number issued is large. They have therefore been classified into the following series: A, Economic geology; B, Descriptive geology; C, Systematic geology and paleontology; D, Petrography and mineralogy; E, Chemistry and physics; F, Geography; G, Miscellaneous; H, Forestry; I, Irrigation; J, Water storage; K, Pumping water; L, Quality of water; M, General hydrographic investigations; N, Water power; O, Underground waters; P, Hydrographic progress reports.

Series P.—The hydrographic progress reports contain the results of stream measurements. A report is issued for every calendar year, containing the results of data collected during that year. These reports were first published as a part of the Director's annual report or as a bulletin; they are now published as water-supply and irrigation papers. The following is a list, by years, of the publications containing the progress reports of stream measurements. A detailed index of these reports (1888–1903) is published as Water-Supply Paper No. 119.

1888. Tenth Annual Report, Part II.
1889. Eleventh Annual Report, Part II.
1890. Twelfth Annual Report, Part II.
1891. Thirteenth Annual Report, Part III.
1892. Fourteenth Annual Report, Part II.
1893. Bulletin No. 131.
1894. Bulletin No. 131; Sixteenth Annual Report, Part II.
1895. Bulletin No. 140.
1896. Water-Supply Paper No. 11; Eighteenth Annual Report, Part IV.
1897. Water-Supply Papers Nos. 15 and 16; Nineteenth Annual Report, Part IV.
1898. Water-Supply Papers Nos. 27 and 28; Twentieth Annual Report, Part IV.
1899. Water-Supply Papers Nos. 35, 36, 37, 38, and 39; Twenty-first Annual Report, Part IV.
1900. Water-Supply Papers Nos. 47, 48, 49, 50, 51, and 52; Twenty-second Annual Report, Part IV.
1901. East of Mississippi River, Water-Supply Papers Nos. 65 and 75.
West of Mississippi River, Water-Supply Papers Nos. 66 and 75.

1902. East of Mississippi River, Water-Supply Papers Nos. 82 and 83.
West of Mississippi River, Water-Supply Papers Nos. 84 and 85.
1903. East of Mississippi River, Water-Supply Papers Nos. 97 and 98.
West of Mississippi River, Water-Supply Papers Nos. 99 and 100.
1904. East of Mississippi River, Water-Supply Papers, Nos. 124, 125, 126, 127, 128, and 129.
West of Mississippi River, Water-Supply Papers Nos 130, 131, 132, 133, 134, and 135.
1905. East of Mississippi River, Nos. 165, 166, 167, 168, 169, 170, and 171.
West of Mississippi River, Nos. 171, 172, 173, 174, 175, 176, 177, and 178.

The Geological Survey and the Reclamation Service have suboffices in different parts of the United States, from which hydrographic and reclamation work in the respective localities is carried on, and where data may be obtained on application. These offices are located as follows:

Boston, Mass., 6 Beacon street; Utica, N. Y., 75 Arcade; Atlanta, Ga., 409 Temple court; Austin, Tex., University of Texas; Chicago, Ill., 876 Federal Building; Belle Fourche, S. Dak.; Cody, Wyo.; Denver, Colo., Chamber of Commerce Building; Salt Lake, Utah; Los Angeles, Cal., 1108 Union Trust Building; Phoenix, Ariz.; Carlsbad, N. Mex.; El Paso, Tex.; Billings, Mont.; Huntley, Mont.; Hazen, Nev.; Boise, Idaho; North Yakima, Wash.; Portland, Oreg., 351 Washington street.

Correspondence should be addressed to

THE DIRECTOR,
UNITED STATES GEOLOGICAL SURVEY,
WASHINGTON, D. C.

AUGUST, 1906.

O

Water-Supply and Irrigation Paper No. 173 Series P, Hydrographic Progress Reports, 49

DEPARTMENT OF THE INTERIOR
UNITED STATES GEOLOGICAL SURVEY
CHARLES D. WALCOTT, DIRECTOR

REPORT

OF

PROGRESS OF STREAM MEASUREMENTS

FOR

THE CALENDAR YEAR 1905

PREPARED UNDER THE DIRECTION OF F. H. NEWELL

PART IX.—Meramec, Arkansas, Red, and Lower Western Mississippi River Drainages

BY

M. C. HINDERLIDER, J. M. GILES, and J. C. HOYT

WASHINGTON
GOVERNMENT PRINTING OFFICE
1906

CONTENTS.

	Page.
.....	1
tion and scope of work	1
ns	3
ion of tables	4
nt equivalents	5
thods of measuring stream flow	6
thods of computing run-off	10
ion and acknowledgments	12
er drainage basin	12
on of basin	12
River near Meramec, Mo	13
River near Eureka, Mo	14
Spring near Meramec, Mo	17
Creek at Scotia, Mo	18
er drainage basin	19
on of basin	19
River near Canyon, Colo	21
River at Pueblo, Colo	24
River near Syracuse, Kans	28
River near Dodge, Kans	30
River at Hutchinson, Kans	32
River at Arkansas City, Kans	34
of Arkansas River near Alva, Okla	36
of Arkansas River near Tonkawa, Okla	38
er drainage basin	39
on of basin	39
y River at Trinidad, Colo	40
y River near Alfalfa, Colo	41
er drainage basin	44
on of basin	44
River near Kenton, Okla	45
River near Garrett, Okla	46
River at Arkalon, Kans	48
River near Waynoka, Okla	50
r drainage basin	51
on of basin	51
River near Independence, Kans	52
River near Catoosa, Ind. T	52
r at Fall River, Kans	54
drainage basin	55
on of basin	55
iver at Fort Gibson, Ind. T	56

Page.
Canadian River drainage basin 58
Description of basin 58
Canadian River at Calvin, Ind. T 58
Canadian River near Logan, N. Mex 60
Mora River at La Cueva, N. Mex 60
Sapello River at Los Alamos, N. Mex 63
Ute Creek near Logan, N. Mex 64
Beaver Creek at Beaver, Okla 66
North Fork of Canadian River near Woodward, Okla 67
North Fork of Canadian River near Elreno, Okla 69
Red River drainage basin 72
Description of basin 72
Red River at Arthur City, Tex 72
North Fork of Red River near Granite, Okla 73
North Fork of Red River near Snyder, Okla 75
North Fork of Red River near Headrick, Okla 76
Elm Fork of Red River near Mangum, Okla 79
Elk Creek near Hobart, Okla 82
Otter Creek near Mountain Park, Okla 83
Horse Creek near Mountain Park, Okla 87
Dry Fork of Otter Creek near Mountain Park, Okla 88
Salt Fork of Red River at Mangum, Okla 91
Turkey Creek near Olustee, Okla 94
Washita River at Anadarko, Okla 95
Ouachita River near Malvern, Ark 99
Ouachita River at Arkadelphia, Ark 99
Index 101

ILLUSTRATIONS.

Page.
PLATE I. Map of the United States showing location of principal river stations maintained during 1905 2
FIG. 1. Cable station showing section of river, car, gage, etc 7
2. Rating, area, and mean-velocity curves for South Fork of Skykomish River near Index, Wash 10

PROGRESS REPORT OF STREAM MEASUREMENTS FOR THE CALENDAR YEAR 1905.

PART IX.

By M. C. HINDERLIDER, J. M. GILES, and J. C. HOYT.

INTRODUCTION.

ORGANIZATION AND SCOPE OF WORK.

The hydrographic work of the United States Geological Survey includes the collection of facts concerning and the study of conditions affecting the behavior of water from the time it reaches the earth as rain or snow until it joins the oceans or great navigable rivers. These investigations became a distinct feature of the work of the Survey in the fall of 1888, when an instruction camp was established at Embudo, N. Mex. The first specific appropriation for gaging streams was made by the act of August 18, 1894, which contained an item of $12,500 "for gauging the streams and determining the water supply of the United States, including the investigation of underground currents and artesian wells in the arid and semi-arid sections." (28 Stat. L., p. 398.)

Since that time the appropriations have been gradually increased, as shown by the following table:

Annual appropriation for hydrographic surveys for fiscal years ending June 30, 1895 to 1906.

1895	$12,500	1901	$100,000
1896	20,000	1902	100,000
1897	50,000	1903	200,000
1898	50,000	1904	200,000
1899	50,000	1905	200,000
1900	50,000	1906	200,000

As a result of the increased appropriations the work has been greatly extended, and at the same time it has been more thoroughly systematized by the adoption of standard methods and by grouping the States into districts, in each of which a district hydrographer and a corps of assistants carry on a comprehensive study of the hydrographic resources.

The chief features of the hydrographic work are the collection of data relating to the flow of the surface waters and the study of the conditions affecting this flow. Information is also collected concerning river profiles, duration and magnitude of floods, water power, etc., which may be of use in hydrographic studies. This work includes the study of the hydrography of every important river basin in the United States, and is of direct value in the commercial and agricultural development of the country.

In order to collect the material from which estimates of daily flow are made, gaging stations are established. The selection of a site for a gaging station and the length of time it is maintained depend largely on the physical features and the needs of each locality. If the water is to be used for power, special effort is made to obtain information concerning

the minimum flow; if water is to be stored, the maximum flow receives special attention. In all sections of the country permanent gaging stations are maintained for general statistical purposes to show the conditions existing through long periods. They are also used as primary stations, and their records, in connection with short series of measurements, serve as bases for estimating the flow at other points in the drainage basin.

During the calendar year 1905 the division of hydrography has continued measuring the flow of streams on the same general lines as in previous years. Many new and improved methods have been introduced by which the accuracy and value of the results have been increased. Approximately 800 regular gaging stations were maintained during the year, and an exceptionally large number of miscellaneous measurements and special investigations were made. The "Report of Progress of Stream Measurements," which contains the results of this work, is published in a series of fourteen Water-Supply and Irrigation Papers, Nos. 165–178, as follows:

No. 165. Atlantic coast of New England drainage.
No. 166. Hudson, Passaic, Raritan, and Delaware river drainages.
No. 167. Susquehanna, Gunpowder, Patapsco, Potomac, James, Roanoke, and Yadkin river drainages.
No. 168. Santee, Savannah, Ogeechee, and Altamaha rivers and eastern gulf of Mexico drainages.
No. 169. Ohio and lower eastern Mississippi river drainages.
No. 170. Great Lakes and St. Lawrence River drainages.
No. 171. Hudson Bay and upper eastern and western Mississippi River drainages.
No. 172. Missouri River drainage.
No. 173. Meramec, Arkansas, Red, and lower western Mississippi river drainages.
No. 174. Western Gulf of Mexico and Rio Grande drainages.
No. 175. Colorado River drainage.
No. 176. The Great Basin drainage.
No. 177. The Great Basin and Pacific Ocean drainages in California.
No. 178. Columbia River and Puget Sound drainages.

These papers embody the data collected at the regular gaging stations, the results of the computations based on the observations, and such other information as may have a direct bearing on the study of the subject, and include, as far as practicable, descriptions of the basins and the streams draining them.

For the purpose of introducing uniformity into the reports for the various years, the drainages of the United States have been divided into eleven grand divisions, which have been again divided into secondary divisions, as shown in the following list. The Progress Report has been made to conform to this arrangement, each part containing the data for one or more of the secondary divisions. The secondary divisions have in most cases been redivided, and the facts have been arranged, as far as practicable, geographically.

List of drainage basins in the United States.

NORTHERN ATLANTIC DRAINAGE BASINS.

St. John.
St. Croix.
Penobscot.
Kennebec.
Androscoggin.
Presumpscot.
Saco.
Merrimac.
Connecticut.
Blackstone.
Thames.
Housatonic.
Hudson.
Passaic.
Raritan.
Delaware.
Susquehanna.
Potomac.
Minor Chesapeake Bay.
Minor northern Atlantic.

SOUTHERN ATLANTIC DRAINAGE BASINS.

James.
Chowan.
Roanoke.
Tar.
Neuse.
Cape Fear.
Great Pedee (Yadkin).
Santee.
Savannah.
Ogeechee.
Altamaha.
Minor southern Atlantic.


127° 125° 123° 81° 79° 77° 75° 73° 71° 69° 67°
MAINE
VT.
N. H.
MASS.
CONN. R.I.
NEW YORK
PENNSYLVANIA
NEW JERSEY
DEL.
MD.
WEST VIRGINIA
VIRGINIA
OHIO
KENTUCKY
TENNESSEE
NORTH CAROLINA
SOUTH CAROLINA
GEORGIA
FLORIDA
500 miles
119° 117° 115° 85° 83° 81° 79° 77°

DURING 1905.

A
WASH.
OREGON
CALIFORNIA
NEVADA
IDAHO
MONT.
WYO.
COLO.
N. DAK.
S. DAK.
NEBR.
KANS.
OKLA.
TEX.
MINN.
IOWA
MO.
ARK.
LA.
WIS.
ILL.
MICH.
IND.
OHIO
KY.
TENN.
MISS.
ALA.
GA.
FLA.
S. C.
N. C.
VA.
W. VA.
PA.
N. Y.
VT.
N. H.
MAINE
MASS.
CONN.
R. I.
N. J.
MD.
DEL.
500 miles

DURING 1905.

EASTERN GULF OF MEXICO DRAINAGE BASINS.

	Pearl.
ola.	Minor eastern Gulf of Mexico.

EASTERN MISSISSIPPI RIVER DRAINAGE BASINS.

tern Mississippi.	Upper eastern Mississippi.

ST. LAWRENCE RIVER DRAINAGE BASINS.

erior.	Niagara River.
ıigan.	Lake Ontario.
on.	Lake Champlain (Richelieu River).
lair.	Minor St. Lawrence.

WESTERN MISSISSIPPI RIVER DRAINAGE BASINS.

stern Mississippi.	Lower western Mississippi.
	Arkansas.
	Red.

WESTERN GULF OF MEXICO DRAINAGE BASINS.

	Guadelupe.
	San Antonio.
	Nueces.
	Rio Grande.
(of Texas).	Minor western Gulf of Mexico.

COLORADO RIVER DRAINAGE BASIN.

THE GREAT BASIN.

Mountains.	Sierra Nevada.
t.	Minor streams in Great Basin.

PACIFIC COAST DRAINAGE BASINS.

Pacific.	Columbia.
isco Bay.	Puget Sound.
Pacific.	

HUDSON BAY DRAINAGE BASINS.

DEFINITIONS.

olume of water flowing in a stream—the "run-off" or "discharge"—is expressed s terms, each of which has become associated with a certain class of work. These ıy be divided into two groups: (1) Those which represent a rate of flow, as second-ons per minute, miner's inch, and run-off in second-feet per square mile; and (2) ich represent the actual quantity of water, as run-off in depth in inches and acre-ıey may be defined as follows:

ıd-foot" is an abbreviation for cubic foot per second, and is the rate of discharge flowing in a stream 1 foot wide and 1 foot deep at a rate of 1 foot per second. erally used as a fundamental unit from which others are computed.

ns per minute" is generally used in connection with pumping and city water

niner's inch" is the rate of discharge of water passing through an orifice 1 inch nder a head which varies locally. It has been commonly used by miners and throughout the West, and is defined by statute in each State in which it is used. States the California miner's inch is used, which is the fiftieth part of a second-foot.

ıd-feet per square mile" is applied to the average number of cubic feet of water ıer second from each square mile of area drained, on the assumption that the distributed uniformly both as regards time and area.

"Run-off in inches" is the depth to which the drainage area would be covered if all the water flowing from it in a given period were conserved and uniformly distributed on the surface. It is used for comparing run-off with rainfall, which is usually expressed in depth in inches.

"Acre-foot" is equivalent to 43,560 cubic feet, and is the quantity required to cover an acre to the depth of 1 foot. It is commonly used in connection with storage for irrigation work. There is a convenient relation between the second-foot and the acre-foot. One second-foot flowing for twenty-four hours will deliver 86,400 cubic feet, or approximately 2 acre-feet.

EXPLANATION OF TABLES.

For each regular gaging station are given, as far as available, the following data:

1. Description of station.
2. List of discharge measurements.
3. Gage-height table.
4. Rating table.
5. Table of estimated monthly and yearly discharges and run-off, based on all the facts obtained to date.

The descriptions of stations give such general information about the locality and equipment as would enable the reader to find and use the station. They also give, as far as possible, a complete history of all the changes since the establishment of the station that would be factors in using the data collected.

The discharge-measurement table gives the results of the discharge measurements made during the year, including the date, the name of the hydrographer, the gage height, the area of cross section, the mean velocity, and the discharge in second-feet.

The table of daily gage heights gives the daily fluctuations of the surface of the river as found from the mean of the gage readings taken each day. The gage height given in the table represents the elevation of the surface of the water above the zero of the gage. At most Stations the gage is read in the morning and in the evening.

The rating table gives discharges in second-feet corresponding to each stage of the river as given by the gage heights.

In the table of estimated monthly discharge, the column headed "Maximum" gives the mean flow for the day when the mean gage height was highest, and it is the flow as given in the rating table for that mean gage height. As the gage height is the mean for the day, there might have been short periods when the water was higher and the corresponding discharge larger than given in this column. Likewise in the column of "Minimum" the quantity given is the mean flow for the day when the mean gage height was lowest. The column headed "Mean" is the average flow for each second during the month. On this are based the computations for the three remaining columns, which are defined above.

In the computations for the tables of this report the following general and special rules have been used:

Fundamental rules for computation.

1. The highest degree of precision consistent with the rational use of time and money is imperative.
2. All items of computation should be expressed by at least two and not more than four significant figures.
3. Any measurement in a vertical velocity, mean velocity, or discharge curve whose per cent of error is five times the average per cent of error of all the other measurements should be rejected.
4. In reducing the number of significant figures, or the number of decimal places, by dropping the last figure, the following rules apply:

(a) When the figure in the place to be rejected is less than 5, drop it without changing the preceding figure. Example: 1,827.4 becomes 1,827.

(b) When the figure in the place to be rejected is greater than 5, drop it and increase the preceding figure by 1. Example: 1,827.6 becomes 1,828.

(c) When the figure in the place to be rejected is 5, and it is preceded by an even figure, drop the 5. Example: 1,828.5 becomes 1,828.

(d) When the figure in the place to be rejected is 5, and it is preceded by an odd figure, drop the 5 and increase the preceding figure by 1. Example: 1,827.5 becomes 1,828.

Special rules for computation.

Rating tables are to be constructed as close as the data on which they are based will warrant. No
mals are to be used when the discharge is over 50 second-feet.
Daily discharges shall be applied directly to the gage heights as they are tabulated.
. Monthly means are to be carried out to one decimal place when the quantities are below 100 second-
t. Between 100 and 10,000 second-feet, the last figure in the monthly mean shall be a significant fig-
. This also applies to the yearly mean.
t. Second-feet per square mile and depth in inches for the individual months shall be carried out to
least three significant figures, except in the case of decimals where the first significant figure is pre-
ded by one or more naughts (0), when the quantity shall be carried out to two significant figures.
mple: 1.25; 0.125; 0.012; 0.0012. The yearly means for these quantities are always to be expressed
three significant figures and at least two decimal places.

CONVENIENT EQUIVALENTS.

1 second-foot equals 50 California miner's inches.
1 second-foot equals 38.4 Colorado miner's inches.
1 second-foot equals 40 Arizona miner's inches.
1 second-foot equals 7.48 United States gallons per second; equals 448.8 gallons per minute; equals 646,272 gallons for one day.
1 second-foot equals 6.23 British imperial gallons per second.
1 second-foot for one year covers one square mile 1.131 feet deep, 13.572 inches deep.
1 second-foot for one year equals 0.000214 cubic mile; equals 31,536,000 cubic feet.
1 second-foot equals about 1 acre-inch per hour.
1 second-foot falling 10 feet equals 1.136 horsepower.
100 California miner's inches equal 15 United States gallons per second.
100 California miner's inches equal 77 Colorado miner's inches.
100 California miner's inches for one day equal 4 acre-feet.
100 Colorado miner's inches equal 2.60 second-feet.
100 Colorado miner's inches equal 19.5 United States gallons per second.
100 Colorado miner's inches equal 130 California miner's inches.
100 Colorado miner's inches for one day equal 5.2 acre-feet.
100 United States gallons per minute equal 0.223 second-foot.
100 United States gallons per minute for one day equal 0.44 acre-feet.
1,000,000 United States gallons per day equal 1.55 second-feet.
1,000,000 United States gallons equal 3.07 acre-feet.
1,000,000 cubic feet equal 22.95 acre-feet.
1 acre-foot equals 325,850 gallons.
1 inch deep on 1 square mile equals 2,323,200 cubic feet.
1 inch deep on 1 square mile equals 0.0737 second-foot per year.
1 inch equals 2.54 centimeters.
1 foot equals 0.3048 meter.
1 yard equals 0.9144 meter.
1 mile equals 1.60935 kilometers.
1 mile equals 1,760 yards; equals 5,280 feet; equals 63,360 inches.
1 square yard equals 0.836 square meter.
1 acre equals 0.4047 hectare.
1 acre equals 43,560 square feet; equals 4,840 square yards.
1 acre equals 209 feet square, nearly.
1 square mile equals 259 hectares.
1 square mile equals 2.59 square kilometers.
1 cubic foot equals 0.0283 cubic meter.
1 cubic foot equals 7.48 gallons; equals 0.804 bushel.
1 cubic foot of water weighs 62.5 pounds.
1 cubic yard equals 0.7646 cubic meter.
1 cubic mile equals 147,198,000,000 cubic feet.
1 cubic mile equals 4,667 second-feet for one year.
1 gallon equals 3.7854 liters.
1 gallon equals 8.36 pounds of water.
1 gallon equals 231 cubic inches (liquid measure).
1 pound equals 0.4536 kilogram.
1 avoirdupois pound equals 7,000 grains.
1 troy pound equals 5,760 grams.
1 meter equals 39.37 inches. Log. 1.5951654.
1 meter equals 3.280833 feet. Log. 0.5159842.
1 meter equals 1.093611 yards. Log. 0.0358629.
1 kilometer equals 3,281 feet; equals five-eighths mile, nearly.

1 square meter equals 10.764 square feet; equals 1.196 square yards.
1 hectare equals 2.471 acres.
1 cubic meter equals 35.314 cubic feet; equals 1.308 cubic yards.
1 liter equals 1.0567 quarts.
1 gram equals 15.43 grains.
1 kilogram equals 2.2046 pounds.
1 tonneau equals 2,204.6 pounds.
1 foot per second equals 1.097 kilometers per hour.
1 foot per second equals 0.68 mile per hour.
1 cubic meter per minute equals 0.5886 second-foot.
1 atmosphere equals 15 pounds per square inch; equals 1 ton per square foot; equals 1 kilogram per square centimeter.
Acceleration of gravity equals 32.16 feet per second every second.
1 horsepower equals 550 foot-pounds per second.
1 horsepower equals 76 kilogram-meters per second.
1 horsepower equals 746 watts.
1 horsepower equals 1 second-foot falling 8.8 feet.
1½ horsepowers equals about 1 kilowatt.
To calculate waterpower quickly: Sec.-ft. × fall in feet = Net horsepower on water wheel, realizing 11 80 per cent of the theoretical power.
Quick formula for computing discharge over weirs: Cubic feet per minute equals $0.4025\ l\sqrt{h^3}$; l length of weir in inches; h = head in inches flowing over weir, measured from surface of still water.
To change miles to inches on map:
Scale 1 : 125,000, 1 mile = 0.50688 inch.
Scale 1 : 90,000, 1 mile = 0.70400 inch.
Scale 1 : 62,500, 1 mile = 1.01376 inches.
Scale 1 : 45,000, 1 mile = 1.40800 inches.

FIELD METHODS OF MEASURING STREAM FLOW.

The methods used in collecting these data and in preparing them for publication are given in detail in Water-Supply Papers No. 94 (Hydrographic Manual, U. S. Geol. Survey) and No. 95 (Accuracy of Stream Measurements). In order that those who use this report may readily become acquainted with the general methods employed, the following brief description is given.

Streams may be divided, with respect to their physical conditions, into three classes: (1) Those with permanent beds; (2) those with beds which change only during extreme low or high water; (3) those with constantly shifting beds. In estimating the daily flow special methods are necessary for each class. The data on which these estimates are based and the methods of collecting them are, however, in general the same.

There are three distinct methods of determining the flow of open-channel streams: (1) By measurements of slope and cross section and the use of Chezy's and Kutter's formulas; (2) by means of a weir; (3) by measurements of the velocity of the current and the area of the cross section. The method chosen for any case depends on the local physical conditions, the degree of accuracy desired, the funds available, and the length of time that the record is to be continued.

Slope method.—Much information has been collected relative to the coefficients to be used in the Chezy formula, $v = c\sqrt{Rs}$. This has been utilized by Kutter, both in developing his formula for c and in determining the values of the coefficient n which appears therein. The results obtained by the slope method are in general only roughly approximate, owing to the difficulty in obtaining accurate data and the uncertainty of the value for n to be used in Kutter's formula. The most common use of this method is in estimating the flood discharge of a stream when the only data available are the cross section, the slope as shown by marks along the bank, and a knowledge of the general conditions.

Weir method.—When funds are available and the conditions are such that sharp-crested weirs can be erected, these offer the best facilities for determining flow. If dams are suitably situated and constructed they may be utilized for obtaining reliable estimates of flow. The conditions necessary to insure good results may be divided into two classes—(1) those relating to the physical characteristics of the dam itself, and (2) those relating to the diversion and use of water around and through the dam.

physical requirements are as follows: (a) Sufficient height of dam, so that back- will not interfere with free fall over it; (b) absence of leaks of appreciable magnitude; pography or abutments which confine the flow over the dam at high stages; (d) level , which are kept free from obstructions caused by floating logs or ice; (e) crests of a for which the coefficients to be used in $Q=c\,b\,h^{\frac{3}{2}}$, or some similar standard weir for- , are known (See Water-Supply Paper No. 150); (f) either no flash boards or exceptional in reducing leaking through them and in recording their condition.

eferably there should be no diversion of water through or around the dam. Generally, ver, the dam is built for purposes of power or navigation, and part or all of the water ng past it is diverted for such uses. This water is measured and added to that passing the dam. To insure accuracy in such estimates the amount of water diverted should be onably constant. Furthermore, it should be so diverted that it can be measured, r by a weir, a current meter, or a simple system of water wheels which are of standard e, or which have been rated as meters under working conditions and so installed that gate openings, the heads under which they work, and their angular velocities may be urately observed.

he combination of physical conditions and uses of the water should be such that the mates of flow will not involve, for a critical stage of considerable duration, the use of a d, on a broad-crested dam, of less than 6 inches. Moreover, when all other conditions



FIG. 1.—Cable station, showing section of river, car, gage, etc.

good, the cooperation of the owners or operators of the plant is still essential if reliable lts are to be obtained.

gaging station at a weir or dam has the general advantage of continuity of record ugh the periods of ice and floods, and the disadvantages of uncertainty of coefficient to' sed in the weir formula and of complications in the diversion and use of the water.

elocity method.—The determination of the quantity of water flowing past a certain sec- of a stream at a given time is termed a discharge measurement. This quantity is the luct of two factors—the mean velocity and the area of the cross section. The mean city is a function of surface slope, wetted perimeter, roughness of bed, and the channel litions at, above, and below the gaging section. The area depends on the contour of bed and the fluctuations of the surface. The two principal ways of measuring the city of a stream are by floats and current meters.

reat care is taken in the selection and equipment of gaging stations for determining dis- ge by velocity measurements in order that the data may have the required degree of racy. Their essential requirements are practically the same whether the velocity is rmined by meters or floats. They are located, as far as possible, where the channel is ght both above and below the gaging section; where there are no cross currents, back- r, or boils; where the bed of the stream is reasonably free from large projections of a manent character, and where the banks are high and subject to overflow only at flood

stages. The station must be so far removed from the effects of tributary streams and dams or other artificial obstructions that the gage height shall be an index of the discharge.

Certain permanent or semipermanent structures, usually referred to as "equipment," are generally pertinent to a gaging station. These are a gage for determining the fluctuations of the water surface, bench marks to which the datum of the gage is referred, permanent marks on a bridge or a tagged line indicating the points of measurement, and, where the current is swift, some appliance (generally a secondary cable) to hold the meter in position in the water. As a rule, the stations are located at bridges if the channnel conditions are satisfactory, as from them the observations can more readily be made and the cost of the equipment is small.

The floats in common use are the surface, subsurface, and tube or rod floats. A corked bottle with a flag in the top and weighted at the bottom makes one of the most satisfactory surface floats, as it is affected but little by wind. In case of flood measurements, good results can be obtained by observing the velocity of floating cakes of ice or débris. In case of all surface-float measurements coefficients must be used to reduce the observed velocity to the mean velocity. The subsurface and tube or rod floats are intended to give directly the mean velocity in the vertical. Tubes give excellent results when the channel conditions are good, as in canals.

In measuring velocity by a float observation is made of the time taken by the float to pass over the "run"—a selected stretch of river from 50 to 200 feet long. In each discharge measurement a large number of velocity determinations are made at different points across the stream, and from these observations the mean velocity for the whole section is determined. This may be done by plotting the mean positions of the floats as indicated by the distances from the bank as ordinates and the corresponding times as abscissas. A curve through these points shows the mean time of run at any point across the stream, and the mean time for the whole stream is obtained by dividing the area bounded by this curve and its axis by the width. The length of the run divided by the mean time gives the mean velocity.

The area used in float measurements is the mean of the areas at the two ends of the run and at several intermediate sections.

The essential parts of the current meters in use are a wheel of some type so constructed that the impact of flowing water causes it to revolve and a device for recording or indicating the number of revolutions. The relation between the velocity of the moving water and the revolutions of the wheel is determined for each meter. This rating is done by drawing the meter through still water for a given distance at different speeds and noting the number of revolutions for each run. From these data a rating table is prepared which gives the velocity per second for any number of revolutions.

Many kinds of current meters have been constructed. They may, however, be classed in two general types—those in which the wheel is made up of a series of cups, as the Price, and those having a screw-propeller wheel, as the Haskell. Each meter has been developed for use under some special condition. In the case of the small Price meter, which has been largely developed and extensively used by the United States Geological Survey, an attempt has been made to get an instrument which could be used under practically all conditions.

Current-meter measurements may be made from a bridge, cable, boat, or by wading, and gaging stations may be classified in accordance with such use. Fig. 1 shows a typical cable station.

In making the measurement an arbitrary number of points are laid off on a line perpendicular to the thread of the stream. The points at which the velocity and depth are observed are known as measuring points, and are usually fixed at regular intervals, varying from 2 to 20 feet, depending on the size and condition of the stream. Perpendiculars dropped from the measuring points divide the gaging section into strips. For each strip or pair of strips the mean velocity, area, and discharge are determined independently, so that conditions existing in one part of the stream may not be extended to parts where they do not apply.

Three classes of methods of measuring velocity with current meters are in general use—multiple point, single point, and integration.

The three principal multiple-point methods in general use are the vertical velocity-curve, 0.2 and 0.8 depth, and top, bottom, and mid depth.

In the vertical velocity-curve method a series of velocity determinations are made in each vertical at regular intervals, usually from 0.5 to 1 foot apart. By plotting these velocities as abscissas and their depths as ordinates and drawing a smooth curve among the resulting points the vertical velocity-curve is developed. This curve shows graphically the magnitude and changes in velocity from the surface to the bottom of the stream. The mean velocity in the vertical is then obtained by dividing the area bounded by this velocity curve and its axis by the depth. On account of the length of time required to make a complete measurement by this method, its use is limited to the determination of coefficients for purposes of comparison and to measurements under ice.

In the second multiple-point method the meter is held successively at 0.2 and 0.8 of the depth, and the mean of the velocities at these two points is taken as the mean velocity for that vertical. Assuming that the vertical-velocity curve is a common parabola with horizontal axis, the mean of the velocities at 0.22 and 0.79 of the depth will give (closely) the mean velocity in the vertical. Actual observations under a wide range of conditions show that this second multiple-point method gives the mean velocity very closely for open-water conditions where the depth is over 5 feet and the bed comparatively smooth, and moreover the indications are that it will hold nearly as well for ice-covered rivers.

In the third multiple-point method the meter is held at mid depth at 0.5 foot below the surface and at 0.5 foot above the bottom, and the mean velocity is determined by dividing by 6 the sum of the top velocity, 4 times the mid-depth velocity, and the bottom velocity. This method may be modified by observing at 0.2, 0.6, and 0.8 depth.

The single-point method consists in holding the meter either at the depth of the thread of mean velocity or at an arbitrary depth for which the coefficient for reducing to mean velocity has been determined.

Extensive experiments by vertical velocity curves show that the thread of mean velocity generally occurs at from 0.5 to 0.7 of the total depth. In general practice the thread of mean velocity is considered to be at 0.6 depth, at which point the meter is held in a majority of the measurements. A large number of vertical velocity-curve measurements taken on many streams and under varying conditions show that the average coefficient for reducing the velocity obtained is 0.6 depth to mean velocity is practically unity.

In the other principal single-point method the meter is held near the surface, usually 1 foot below, or low enough to be out of the effect of the wind or other disturbing influences. This is known as the "subsurface" method. The coefficient for reducing the velocity taken at the subsurface to the mean has been found to be from 0.85 to 0.95, depending on the stage, velocity, and channel conditions. The higher the stage the larger the coefficient. This method is specially adapted for flood measurements or when the velocity is so great that the meter can not be kept at 0.6 depth.

The vertical-integration method consists in moving the meter at a slow uniform speed from the surface to the bottom and back again to the surface and noting the number of revolutions and the time taken in the operation. This method has the advantage that the velocity at each point of the vertical is measured twice. It is well adapted for measurements under ice and as a check on the point methods.

The area, which is the other factor in the velocity method of determining the discharge of a stream, depends on the stage of the river, which is observed on the gage, and on the general contour of the bed of the stream, which is determined by soundings. The soundings are usually taken at each measuring point at the time of the discharge measurement, either by using the meter and cable or by a special sounding line or rod. For streams with permanent beds standard cross-sections are usually taken during low water. These sections serve to check the soundings which are taken at the time of the measurements, and from them any change which may have taken place in the bed of the stream can be detected. They are

also of value in obtaining the area for use in computations of high-water measurements, as accurate soundings are hard to obtain at high stages.

In computing the discharge measurements from the observed velocities and depths at various points of measurement the measuring section is divided into elementary strips, as shown in fig. 1, and the mean velocity, area, and discharge are determined separately for either a single or a double strip. The total discharge and the area are the sums of those for the various strips, and the mean velocity is obtained by dividing the total discharge by the total area.

The determination of the flow of an ice-covered stream is difficult, owing to diversity and instability of conditions during the winter period and also to lack of definite information in regard to the laws of flow of water under ice. The method now employed is to make frequent discharge measurements during the frozen periods by the vertical velocity-curve method and to keep an accurate record of the conditions, such as the gage height to the surface of the water as it rises in a hole cut in the ice, the thickness and character of the ice, etc. From these data an approximate estimate of the daily flow can be made by constructing a rating curve (really a series of curves) similar to that used for open channels, but considering in addition to gage heights and discharge varying thickness of ice. Such data as are available in regard to this subject are published in Water Supply paper No. 146, pages 141–148.


MEAN VELOCITY, AREA AND RATING CURVES FOR SKYKOMISH RIVER (SO. FORK) NEAR INDEX, WASH.
MEASUREMENTS IN 1902 NO. 1 TO 7
" " 1903 " 8 " 12
RATING CURVE
AREA CURVE
MEAN VELOCITY CURVE
GAGE HEIGHT IN FEET
AREA IN SQUARE FEET
VELOCITY IN FEET PER SECOND
DISCHARGE IN SECOND-FEET

FIG. 2.—Rating, area, and mean-velocity curves for South Fork of Skykomish River near Index, Wash.

OFFICE METHODS OF COMPUTING RUN-OFF.

There are two principal methods of estimating run-off, depending on whether or not the bed of the stream is permanent.

For stations of streams with permanent beds the first step in computing the run-off is the construction of a rating table, which shows the discharge corresponding to any stage of the stream. This rating table is applied to the record of stage to determine the amount of water flowing. The construction of the rating table depends on the method used in measuring flow.

For a station at a weir or dam the basis for the rating table is some standard weir formula. The coefficients to be used in its application depend on the type of dam and other conditions near its crest. After inserting in the weir formula the measured length of crest and assumed coefficient the discharge is computed for various heads and the rating table constructed.

The data necessary for the construction of a rating table for a velocity-area station are the results of the discharge measurements, which include the record of stage of the river at the

e of measurement, the area of the cross-section, the mean velocity of the current, and the ntity of water flowing. A thorough knowledge of the conditions at and in the vicinity he station is also necessary.

he construction of the rating table depends on the following laws of flow for open per- nent channels: (1) The discharge will remain constant so long as conditions at or near gaging station remain constant. (2) The discharge will be the same whenever the eam is at a given stage if the change of slope due to the rise and fall of the stream be glected. (3) The discharge is a function of and increases gradually with the stage.

he plotting of results of the various discharge measurements, using gage heights as ordi- tes, and discharge, mean velocity, and area as abscissas, will define curves which show the charge, mean velocity, and area corresponding to any gage height. For the development these curves there should be, therefore, a sufficient number of discharge measurements to er the range of the stage of the stream. Fig. 2 shows a typical rating curve with its cor- ponding mean-velocity and area curves.

As the discharge is the product of two factors, the area and the mean velocity, any change either factor will produce a corresponding change in the discharge. Their curves are refore constructed in order to study each independently of the other.

he area curve can be definitely determined from accurate soundings extending to the its of high water. It is always concave toward the horizontal axis or on a straight line ess the banks of the stream are overhanging.

he form of the mean-velocity curve depends chiefly on the surface slope, the roughness he bed, and the cross section of the stream. Of these, the slope is the principal factor. accordance with the relative changes of these factors the curve may be either a straight , convex, or concave toward either axis, or a combination of the three. From a careful dy of the conditions at any gaging station the form which the vertical velocity curve will e can be predicted, and it may be extended with reasonable certainty to stages beyond limits of actual measurements. Its principal use is in connection with the area curve in ting errors in discharge measurements and in constructing the rating table.

he discharge curve is defined primarily by the measurements of discharge, which are died and weighted in accordance with the local conditions existing at the time of each surement. The curve may, however, best be located between and beyond the measure- nts by means of curves of area and mean velocity. The discharge curve under normal ditions is concave toward the horizontal axis and is generally parabolic in form.

n the preparation of the rating table the discharge for each tenth or half tenth on the gage aken from the curve. The differences between successive discharges are then taken and usted according to the law that they shall either be constant or increasing.

he determination of daily discharge of streams with changeable beds is a difficult prob- . In case there is a weir or dam available, a condition which seldom exists on streams of class, estimates can be obtained by its use. In case of velocity-area stations frequent charge measurements must be made if the estimates are to be other than rough approxi- tions. For stations with beds which shift slowly or are materially changed only during ds, rating tables can be prepared for periods between such changes, and satisfactory ults obtained with a limited number of measurements, provided that some of them are en soon after the change occurs. For streams with continually shifting beds, such as the orado and Rio Grande, discharge measurements should be made every two or three days, the discharges for intervening days obtained either by interpolation modified by gage ght or by Professor Stout's method, which has been described in full in the Nineteenth ual Report of the United States Geological Survey, Part IV, page 323, and in Engineer- News of April 21, 1904. This method, or a graphical application of it, is also much used stimating flow at stations where the bed shifts but slowly.

COOPERATION AND ACKNOWLEDGMENTS.

Most of the measurements presented in this paper have been obtained through local hydrographers. Acknowledgment is extended to other persons and corporations who have assisted local hydrographers or have cooperated in any way, either by furnishing records of the height of water or by assisting in transportation.

The following list, arranged alphabetically by States, gives the names of the district hydrographers and others who have assisted in furnishing and preparing the data contained in this report:

Arkansas.—District hydrographer, Thomas U. Taylor.[a]

Colorado.—District and resident hydrographer, M. C. Hinderlider,[b] assisted by R. I. Meeker, Wm. A. Lamb, H. G. Graham, A. A. Weiland, O. H. Timmerman, Melvin Beeson, Thomas E. Brick, and F. L. Meeker. Acknowledgements are due the Denver and Rio Grande, Colorado and Southern, Burlington and Missouri River, Union Pacific, Rio Grande Southern, and Atchison, Topeka and Santa Fe railroads for free transportation over their lines.

Kansas.—District hydrographer, M. C. Hinderlider, resident hydrographer, W. G. Russell. Acknowledgments are due the Atchison, Topeka, and Santa Fe; Union Pacific: Missouri, Kansas and Texas; Missouri Pacific; and Chicago, Rock Island and Pacific railroads for annual passes issued to Mr. Russell.

Missouri.—District hydrographer, F. W. Hanna,[c] assisted by M. S. Brennan and S. K. Clapp. Acknowledgment should be made to the St. Louis and San Francisco Railroad for transportation furnished to Messrs. Hanna and Brennan.

New Mexico.—[d] The hydrographic work in the northern portion of this territory was carried on under the direction of M. C. Hinderlider, district hydrographer, assisted as follows: The work in the north-central portion was in charge of R. I. Meeker and the work in the northern-western portion was in charge of O. H. Timmerman. For many favors and courtesies in the form of free accommodations to hydrographers and for assistance in securing records of flow on Mora River acknowledgments are due D. C. Duel, Hugh Loudon, and J. J. Baer, of La Cueva, N. Mex.; also to James D. Hand, of Los Alamos, N. Mex. Transportation in the form of annual passes was furnished Mr. Meeker by the Denver and Rio Grande and the Atchison, Topeka, and Santa Fe railroads.

The work in the southern and eastern portions was under the direction of J. M. Giles, assisted by Earl Patterson. Acknowledgments are due the St. Louis and San Francisco; Chicago, Rock Island and Pacific; Southern Kansas; Fort Worth and Denver City; and Texas and Pacific railroads for transportation furnished Mr. Giles; and to the Pecos Valley lines for transportation furnished Mr. Patterson.

Oklahoma and Indian Territory.—The work in the southern part of Oklahoma and Indian Territory was under the direction of J. M. Giles, district hydrographer, assisted by Earl Patterson and E. E. Kerby. The work in the northern part was by W. G. Russell, resident hydrographer. Acknowledgments are due the Atchison, Topeka and Santa Fe; Missouri, Kansas and Texas; and Chicago, Rock Island and Pacific railroads for transportation furnished Mr. Russell; to the Southern Kansas of Texas; Chicago, Rock Island and Pacific; St. Louis and San Francisco; Fort Worth and Denver City; and Texas and Pacific railroads and Pecos Valley lines for transportation furnished Mr. Giles; to the Chicago, Rock Island and Pacific; and the St. Louis and San Francisco railroads for transportation furnished Mr. Kerby; and to the Southern Kansas of Texas and the Pecos Valley lines for transportation furnished Mr. Patterson.

Texas.—District hydrographer, Thomas U. Taylor.

MERAMEC RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Meramec River rises in Dent County, Mo., flows northeast, and enters the Mississippi near St. Louis. This river drains a rugged, hilly, and comparatively thinly populated country. There are, however, numerous good sites for dams, and the United States Geological Survey is studying the river in connection with the possible water-power developments and for its possible use as a future water supply for the city of St. Louis.

The total drainage area of Meramec River is 3,619 square miles; at Eureka it is 3,497 square miles. The drainage area above Dry Fork is 340 square miles, and that of Dry Fork is 360 square miles.

---

[a] Office of the district hydrographer for Arkansas, Texas, and Louisiana, Austin, Tex.
[b] Office of district hydrographer for Colorado, Kansas, Nebraska, northern New Mexico, and Wyoming, Chamber of Commerce Building, Denver, Colo.
[c] District hydrographer for Missouri during 1906, A. H. Horton,
[d] District hydrographer for southern and eastern New Mexico
Indian Territory, J. M. Giles, Carlsbad, N. Mex.

MERAMEC RIVER NEAR MERAMEC, MO.

This station was established February 28, 1903, by I. W. McConnell. It is located out 600 feet below the mouth of Spring Branch and about 1 mile from the post road tween Meramec and St. James, Mo. The nearest railroad station is St. James, 7 miles rthwest of the gaging station. The drainage area at this station is 340 square miles.

The channel is straight for about 300 feet above the station and for 2,000 feet below. e current velocity is sufficient for accurate measurement except at low stages, when it comes sluggish. Both banks are low, and at high water the river spreads over wide flats. e bed of the stream is shifting.

Discharge measurements are made by means of a cable, boat, and tagged wire. The itial point for soundings has been taken at the tree to which the cable is attached on e left bank. At low stages measurements are obtained by wading the river about 200 et above the mouth of Meramec Spring and adding to this discharge the flow of Meramec pring.

The gage is a staff driven into the bed of the river and nailed at the top to a leaning ee. During 1905 the gage was read by C. C. Smallwood. The bench mark is a point n a bowlder on the left bank at the foot of the cliff near the mouth of Spring Branch; levation, 10.44 feet above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers f the United States Geological Survey:

Description: 99, p 233; 131, p 118.
Discharge: 99, p 234; 131, p 119.
Discharge, monthly: 99, p 235.
Gage heights: 99, p 234; 131, p 119.
Rating tables: 99, p 235.

Discharge measurements of Meramec River near Meramec, Mo., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Second-feet.*
e 22	M. S. Brennan	2.79	164
r 26	do	3.60	438
tember 8	do	2.79	168
ober 12	do	2.92	174
mber 20	do	2.96	256

Daily gage height, in feet, of Meramec River near Meramec, Mo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.75	2.75	4.5	4.4	3.7	3.0	3.1	3.4	2.9	3.3	3.7	3.1
2	2.75	2.75	4.1	4.1	3.6	2.9	3.1	3.3	2.9	3.2	3.6	3.6
3	2.75	2.75	3.9	3.9	3.5	2.9	3.0	3.2	2.8	3.1	3.5	3.8
4	2.75	2.75	3.8	3.7	3.4	3.0	3.0	3.1	2.8	3.1	3.5	3.6
5	2.75	2.75	3.8	3.6	3.4	2.9	2.9	3.0	2.8	3.1	4.9	4.3
6	2.75	2.75	5.1	3.6	3.3	2.9	2.9	3.0	2.8	3.0	4.8	3.4
7	2.75	2.75	7.2	3.5	4.6	2.9	2.8	3.4	2.8	3.0	4.3	3.3
8	2.75	2.75	8.0	3.4	4.1	2.8	2.8	3.3	2.8	3.0	4.1	3.2
9	2.75	2.75	6.4	3.3	4.0	2.8	2.9	3.2	2.8	3.0	4.1	3.1
10	2.75	2.75	5.0	3.3	3.8	2.8	3.2	3.1	3.0	3.0	3.7	3.05
11	2.75	2.75	4.8	3.6	3.8	2.8	4.5	3.3	2.9	2.95	3.6	3.0
12	2.75	2.75	4.4	3.6	3.8	2.8	3.7	3.0	2.8	2.9	3.5	3.0
13	2.75	2.75	4.1	3.6	3.7	2.8	3.6	3.0	2.8	2.9	3.4	3.0
14	2.75	2.75	3.9	3.4	7.2	2.8	3.4	2.9	1.8	2.9	3.3	2.95
15	2.75	2.75	3.8	3.3	4.8	2.8	3.3	3.4	1.8	2.9	3.3	2.95
16	2.75	2.75	3.7	3.1	4.4	2.8	3.2	3.1	2.75	2.9	3.3	2.9
17	2.75	2.75	3.7	3.1	4.2	2.8	3.0	3.0	7.0	2.9	3.2	2.9
18	2.8	2.75	3.5	3.1	4.0	2.8	3.0	3.0	8.2	2.9	3.2	2.9
19	2.8	2.8	3.5	3.0	3.8	2.8	2.9	3.0	7.8	3.6	4.7	2.9
20	2.9	2.8	3.5	3.0	3.5	2.7	2.9	2.9	6.0	3.4	4.9	2.95
21	2.9	2.9	3.4	2.9	3.4	2.9	6.9	2.8	5.6	3.3	4.3	2.95
22	3.1	3.0	3.4	2.9	3.4	2.7	6.1	5.4	5.1	3.2	3.9	2.95
23	3.1	3.9	3.4	2.9	4.0	2.7	4.8	4.2	4.3	3.1	3.7	3.0
24	3.1	4.0	3.5	2.9	3.9	2.7	4.0	3.9	4.2	3.6	3.6	3.0
25	3.0	5.6	3.6	2.9	3.6	2.8	3.7	3.8	3.9	4.4	3.5	3.0
26	2.9	5.3	3.4	4.1	3.5	2.9	3.6	3.4	3.7	5.9	3.4	2.95
27	2.9	5.9	3.4	4.0	3.4	2.9	3.7	3.1	3.5	4.0	3.3	2.95
28	2.8	4.6	3.3	3.8	3.4	2.9	3.7	3.1	3.4	3.9	3.3	3.0
29	2.75	.....	3.6	3.8	3.3	3.1	3.7	3.0	3.4	3.9	3.2	3.4
30	2.75	.....	5.3	3.8	3.4	3.1	3.4	3.0	3.3	3.9	3.2	3.3
31	2.75	.....	4.9	.....	3.1	.....	3.4	2.9	.....	3.8	.....	.....

MERAMEC RIVER NEAR EUREKA, MO.

This station was established August 26, 1903, by F. W. Hanna. It is located at the highway bridge on the road between Crescent and Eureka, Mo., about 1½ miles from Eureka, 2 miles below the mouth of Big River, and 2 miles above the Frisco Railroad bridge.

The channel is straight for about 250 feet above and 1,000 feet below the station. The right bank is high and rocky and not subject to overflow. It is wooded above the high-water line. The left bank is somewhat lower and is composed of alluvial soil, and it also is wooded above the high-water line. The bed of the stream is composed of coarse gravel and stones. The current is never sluggish. There is but one channel, and it is broken by the center pier of the bridge.

Discharge measurements are made from the two-span highway bridge with a length between abutments of 450 feet. The initial point for soundings is the inner face of the right abutment on the upstream side.

A standard chain gage is attached to the floor of the bridge; length of chain, 42.46 feet. During 1905 the gage was read by Mrs. Rhoda Hilderbran. Bench marks were established as follows: (1) A notch cut into the high rock cliff just below the bridge, marked by a painted cross and the letters "U. S. G. S.;" elevation, 38.26 feet. (2) A red mark on the top of the downstream guard rail, just above the gage box; elevation, 42.56 feet.

painted cross, surrounded by the letters "U. S. G. S," on the lower wing of the ıutment; elevation, 36.29 feet. Elevations refer to the datum of the gage.
ɔrmation in regard to this station is contained in the following Water-Supply Papers United States Geological Survey:

ription: 99, p 240; 131, p 120.
harge: 99, p 240; 131, p 120.
harge, monthly: 99, p 242; 131, p 123.
: heights: 99, p 241; 131, p 121.
ng table: 99, p 241; 131, p 122.

Discharge measurements of Meramec River near Eureka, Mo., in 1905.

ate.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	M. S. Brennan	193	739	3.98	5.55	2,944
.....	S. K. Clapp	223	932	4.16	6.05	3,881
.....	M. S. Brennan	189	624	3.47	4.74	2,167
.....	.....do	245	1,212	3.88	7.30	4,700
ıber 7...	.....do	151	372	2.11	3.35	784
r 11.....	.....do	145	422	2.69	3.80	1,136
ber 19...	.....do	161	491	2.84	4.14	1,396

Daily gage height, in feet, of Meramec River near Eureka, Mo., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	3.1	4.1	10.8	9.4	8.5	5.8	4.0	4.5	3.9	4.6	6.9	5.0
.....	3.1	4.0	9.8	7.7	6.9	6.0	5.4	4.3	4.0	4.5	8.4	5.1
.....	3.1	3.7	8.3	7.0	5.7	4.8	7.2	4.1	4.0	4.4	7.2	7.0
.....	3.0	3.7	7.5	6.4	5.4	4.4	6.4	4.0	3.8	4.3	6.3	6.4
.....	3.0	3.8	6.7	6.0	6.0	4.1	5.5	4.0	3.5	4.2	7.5	6.1
.....	3.1	3.9	6.2	5.6	5.8	4.0	4.7	3.9	3.3	4.1	8.8	5.8
.....	3.2	3.9	6.3	5.3	10.2	3.8	4.5	4.1	3.3	4.0	10.7	5.4
.....	3.2	3.8	15.4	5.1	8.3	3.7	4.5	4.1	3.4	3.9	8.7	5.2
.....	3.2	3.9	19.8	5.0	7.6	3.6	4.7	4.0	3.5	3.9	7.3	5.0
.....	3.1	3.9	19.6	4.8	7.8	3.5	4.8	3.9	3.9	3.8	6.6	4.9
.....	3.0	3.8	17.5	5.6	8.5	3.5	7.0	3.7	4.2	3.8	6.0	4.8
.....	3.6	3.8	9.7	6.8	7.0	3.5	10.7	3.7	4.0	3.7	5.5	4.7
.....	4.2	3.8	8.0	6.4	6.0	3.4	7.5	4.1	4.2	3.6	5.3	4.6
.....	5.0	3.7	7.3	5.9	6.9	3.4	7.7	4.0	4.0	3.6	5.1	4.5
.....	4.9	3.6	6.5	5.6	7.8	3.4	7.1	4.0	3.8	3.6	4.9	4.4
.....	4.7	3.6	6.0	5.3	9.4	3.4	6.6	4.0	4.9	3.6	4.8	4.3
.....	4.5	3.6	5.7	5.0	7.3	3.3	5.4	4.1	18.4	3.6	4.7	4.2
.....	4.5	3.6	5.5	4.8	6.0	3.3	4.8	4.5	20.9	4.3	4.5	4.2
.....	5.2	3.7	5.4	4.5	5.8	3.2	4.5	4.7	24.5	4.5	5.4	4.2
.....	5.9	3.7	5.2	4.3	5.2	3.4	4.4	4.5	29.7	7.2	10.0	4.1
.....	6.2	3.7	5.0	4.4	4.9	4.7	5.2	4.3	28.5	6.2	12.2	4.1
.....	6.2	3.9	4.9	4.3	4.7	3.9	9.1	5.7	24.5	5.1	10.7	4.1
.....	6.0	6.1	4.8	4.3	6.2	3.7	13.4	4.7	13.5	4.8	7.8	4.1
.....	5.9	9.4	5.3	4.2	6.8	3.6	11.5	9.2	7.4	4.5	6.8	4.1
.....	5.4	11.0	5.4	4.2	6.1	3.4	6.9	10.2	6.6	6.8	6.4	4.1
.....	4.9	12.0	5.2	6.0	5.6	3.3	5.7	6.4	5.9	13.3	6.1	4.1
.....	4.6	14.0	5.1	8.2	4.9	3.4	5.3	5.4	5.6	16.0	5.9	4.1
.....	4.6	12.5	5.0	10.4	4.7	3.4	5.0	4.9	5.2	14.8	5.7	4.2
.....	4.5	.....	5.1	12.2	4.5	3.5	4.7	4.5	5.0	8.5	5.5	5.3
.....	4.3	.....	9.2	10.3	6.0	3.6	5.1	4.4	4.8	7.2	5.2	5.0
.....	4.2	.....	11.1	.....	5.2	.....	4.9	4.0	.....	6.8	.....	5.6

Station rating table for Meramec River near Eureka, Mo., from August 8, 1903, to Decem 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.60	460	4.40	1,700	6.40	3,810	9.80	8,050
2.70	490	4.50	1,790	6.60	4,030	10.00	8,330
2.80	530	4.60	1,880	6.80	4,250	10.50	9,040
2.90	580	4.70	1,980	7.00	4,470	11.00	9,790
3.00	640	4.80	2,080	7.20	4,710	11.50	10,540
3.10	710	4.90	2,180	7.40	4,950	12.00	11,340
3.20	780	5.00	2,280	7.60	5,190	12.50	12,190
3.30	850	5.10	2,380	7.80	5,430	13.00	13,090
3.40	920	5.20	2,490	8.00	5,670	13.50	14,040
3.50	990	5.30	2,600	8.20	5,920	14.00	15,040
3.60	1,060	5.40	2,710	8.40	6,180	14.50	16,040
3.70	1,130	5.50	2,820	8.60	6,440	15.00	17,050
3.80	1,200	5.60	2,930	8.80	6,700	16.00	19,100
3.90	1,280	5.70	3,040	9.00	6,960	17.00	21,100
4.00	1,360	5.80	3,150	9.20	7,220	18.00	23,100
4.10	1,440	5.90	3,260	9.40	7,490	19.00	25,100
4.20	1,520	6.00	3,370	9.60	7,770	20.00	27,120
4.30	1,610	6.20	3,590				

The above table is applicable only for open-channel conditions. It is based on 20 discharge measurements made during 1903–1905. It is well defined between gage heights 2.8 feet and 6.2 feet. Two flood measurements at 11.6 and 25 feet gage heights, respectively, define the curve above this limit. Above gage height 20 feet the rating curve is a tangent, the difference being 210 per tenth. The left bank overflows at the approximate gage height of 22.2 feet. It has been estimated that the overflow at 36.2 feet gage height was 7,000 second-feet, or 50 second-feet. per tenth gage height.

Estimated monthly discharge of Meramec River near Eureka, Mo., for 1905.

[Drainage area, 3,497 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inches
January	3,590	640	1,727	106,200	0.494	0
February	15,040	1,060	3,055	169,700	.874	
March	26,640	2,080	6,715	412,900	1.92	2
April	11,680	1,520	3,694	219,800	1.06	1
May	8,610	1,790	3,991	245,400	1.14	1
June	3,370	780	1,255	74,680	.359	
July	13,850	1,360	3,836	235,900	1.10	1
August	8,610	1,130	2,102	129,300	.601	
September	51,160	850	9,451	562,400	2.70	3
October	19,040	1,060	3,532	217,200	1.01	
November	11,680	1,790	4,511	268,400	1.29	
December	4,470	1,440	2,119	130,300	.606	
The year	51,160	640	3,832	2,772,000	1.10	1

MERAMEC SPRING NEAR MERAMEC, MO.

iis station was established February 28, 1903, by I. W. McConnell. It is located on ng Branch, 500 feet from the spring, at a footbridge. This point is about 1 mile from mouth of Spring Branch and 2 miles above the mouth of Dry Fork.

he channel is straight for 50 feet above and 500 feet below the station. Both banks are ay and gravel and are about 6 feet high. They will overflow only at unusual flood stages. bed of the stream is composed of gravel with some bowlders and is clean. The water is y swift, making accurate gage readings very difficult.

Discharge measurements are made from the footbridge. The initial point for soundings t the tree at the end of the footbridge on the right bank. The bridge was washed out 1904 and was rebuilt about 50 feet downstream from its old location.

The gage is a staff 10 feet long located near the bridge. During 1905 it was read by C. Smallwood. The bench mark is located on the left corner stone of the breast wheel the tail race just below the old breast wheel, and is designated by a cross on the top sur- e of the stone; elevation, 4.75 feet above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers the United States Geological Survey:

Descripton: 99, pp 235-236; 131, p 123.
Discharge: 99, p 236; 131, p 124.
Discharge, monthly: 99, p 237; 131, p 125.
Gage heights: 99, pp 236-237; 131, p 124.
Rating table: 99, p 237; 131, p 125.

Discharge measurements of Meramec Spring near Meramec, Mo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
r 15.....	S. K. Clapp.....	55	75	6.50	1.70	488
e 22.....	M. S. Brennan.....	27	41	2.30	.37	95
26.....	.....do.....	29	51	3.98	.95	203
ember 8...	.....do.....	27	42	2.24	.40	94
ber 12.....	.....do.....	27	43	2.63	.52	113
mber 20..	.....do.....	27	41	2.51	.40	103

Daily gage height, in feet, of Meramec Spring near Meramec, Mo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	0.25	0.25	0.9	1.0	0.9	0.7	0.5	0.8	0.5	0.8	0.9	0.6
2	.25	.25	.8	.9	.8	.7	.5	.7	.5	.8	.9	.8
3	.25	.25	.7	.9	.7	.6	.45	.7	.5	.75	.85	.8
4	.25	.25	.6	.8	.7	.6	.4	.6	.5	.75	.8	.
5	.25	.25	.5	.8	.7	.5	.4	.5	.5	.7	1.2	.
6	.25	.25	.7	.7	.7	.5	.4	.8	.5	.7	1.2	.
7	.25	.25	1.5	.7	.8	.5	.4	.7	.5	.7	1.1	.
8	.25	.25	2.5	.6	.7	.5	.4	.7	.45	.6	1.0	.
9	.25	.25	2.1	.6	.8	.4	.4	.6	.45	.6	.95	.
10	.25	.25	1.9	.6	.8	.4	.6	.6	.55	.6	.9	.
11	.25	.25	1.5	.7	.8	.4	1.1	.7	.5	.55	.8	.
12	.25	.25	1.4	.7	.8	.4	1.0	.7	.5	.55	.8	.
13	.25	.25	1.2	.6	.8	.4	.8	.5	.45	.5	.75	.
14	.25	.25	1.1	.6	1.9	.4	.7	.5	.45	.5	.7	.
15	.25	.25	1.0	.6	1.7	.4	.7	.5	.45	.5	.7	.
16	.25	.25	.9	.5	1.4	.4	.7	.5	.45	.5	.7	.
17	.25	.25	.8	.5	1.2	.4	.6	.5	1.8	.5	.6	.
18	.3	.25	.8	.5	1.0	.4	.5	.5	2.9	.5	.6	.
19	.3	.25	.7	.5	.9	.4	.5	.5	2.6	.9	1.4	.
20	.3	.3	.7	.4	.8	.4	.5	.5	2.3	.8	1.5	.
21	.3	.3	.6	.4	.8	.5	1.9	.4	2.1	.6	1.3	.
22	.3	.4	.6	.4	1.2	.45	2.0	.7	2.0	.6	1.2	.
23	.3	.5	.6	.4	1.1	.4	1.7	1.1	1.9	.55	1.0	.
24	.3	.7	.7	.4	1.0	.4	1.5	.9	1.3	.8	.95	.
25	.25	.9	.8	.4	1.0	.4	1.1	.9	1.2	2.0	.9	.
26	.25	1.5	.8	1.5	.9	.4	1.15	.8	1.0	2.8	.8	.
27	.25	1.2	.7	1.2	.9	.4	.9	.8	.9	2.5	.8	.
28	.25	1.1	.6	1.0	.9	.4	1.1	.8	.9	1.1	.75	.
29	.25	.....	.9	1.0	.8	.4	1.0	.7	.8	.95	.7	.
30	.25	.....	1.2	1.0	.8	.4	.6	.6	.8	.9	.65	.
31	.25	.....	1.1	.....	.8	.....	.8	.5	.....	.9	.....	.....

COURTOIS CREEK AT SCOTIA, MO.

This station was established November 11, 1904. It is located at Scotia, a post-office miles south of Leasburg, a small town on the St. Louis and San Francisco Railroad. T station may be reached by livery from Leasburg during low-water stages of Meramec Riv and from Steelville by livery at all times.

The channel is straight for more than 200 feet above and below the station. The rig bank is low, alluvial, and liable to overflow at ordinary high stages. The left bank is hi and rocky and seldom overflows. The bed of the stream is clean below the overflow li and consists of coarse gravel. The current is direct and swift.

Discharge measurements are made by wading except at high stages, when a boat and t line are used. A large tree at the wagon ford on the left bank is taken as the initial poi for soundings.

The gage is a staff nailed to a leaning tree about 200 feet below the Scotia ford, on t left bank. The original gage and bench mark were destroyed, and a new gage and bench ma were put in at the same place April 9, 1905, but with the datum approximately 1.35 f lower. All 1905 gage heights refer to the new datum. During 1905 the gage was read Harry Lea. The bench mark is a spike driven into the tree at the gage; elevation, 6.69 f above the datum of the new gage.

Discharge measurements of Courtois Creek at Scotia, Mo., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
M. S. Brennan	122	167	2.04	3.00	340
S. K. Clapp	120	227	3.29	4.10	746
M. S. Brennan	109	81	2.22	2.13	180
do	115	138	3.05	3.15	426
do	110	99	2.54	2.57	252
do	111	85	2.34	2.35	199

Daily gage height, in feet, of Courtois Creek at Scotia, Mo., for 1905.

Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
2.35	2.65	4.65	.....	3.2	5.8	3.4	2.3	2.8	3.7	4.0	3.1
2.35	2.55	4.85	.....	3.0	4.0	2.2	2.4	2.7	3.5	3.8	3.0
2.35	2.45	4.35	.....	2.3	4.4	2.3	2.4	2.6	3.1	3.8	2.8
2.35	2.35	4.15	.....	2.4	4.0	2.5	2.4	2.4	3.1	3.4	2.8
2.35	2.85	4.35	.....	5.6	3.4	2.0	2.3	2.0	2.8	3.3	2.7
2.35	2.75	4.15	.....	6.0	3.2	2.1	3.0	1.0	2.8	3.3	2.7
2.35	2.55	.....	.....	6.0	3.0	1.1	3.2	1.8	2.8	3.2	2.7
2.35	2.45	.....	.....	5.8	2.9	1.3	3.4	1.0	2.7	3.0	2.7
2.35	2.15	8.35	.....	5.4	2.8	2.1	3.2	1.0	2.7	2.8	2.8
2.35	1.85	7.35	2.3	5.0	2.4	2.8	2.0	2.3	2.7	2.8	2.6
2.35	1.75	6.95	5.3	4.8	2.3	4.7	2.0	2.0	3.0	2.7	2.6
3.55	3.25	4.55	4.3	6.0	2.2	5.0	2.0	2.8	2.9	2.4	2.6
4.35	3.05	4.45	3.0	5.0	2.1	5.2	2.8	2.4	2.9	2.4	2.6
3.85	2.85	4.35	3.0	5.0	2.0	5.0	2.4	2.0	2.9	2.3	2.4
3.55	2.85	4.15	3.0	4.8	1.9	4.0	3.0	1.8	2.9	2.3	2.4
3.65	2.65	3.95	3.0	4.4	1.7	.....	3.6	1.8	2.9	2.2	2.4
3.75	2.55	3.85	2.8	4.2	1.6	.....	3.0	1.7	2.8	2.1	2.2
3.85	2.35	3.35	2.6	3.8	1.8	.....	2.8	1.7	2.8	1.8	2.2
3.85	2.75	3.35	2.4	3.7	1.8	.....	2.7	1.6	2.8	1.8	2.2
3.85	2.95	3.75	2.0	3.4	2.6	.....	2.3	.....	3.0	1.8	3.0
4.25	3.15	5.75	3.0	3.2	2.4	.....	2.0	.....	3.6	1.8	3.0
3.65	3.35	5.55	3.2	3.0	2.2	.....	2.0	.....	3.2	5.8	3.0
2.35	3.75	5.35	3.2	2.8	2.1	4.0	.....	6.0	2.8	5.0	2.8
2.65	4.35	.....	2.8	2.0	2.1	3.8	.....	5.0	2.8	4.6	2.7
2.75	5.85	.....	2.4	2.5	2.0	3.6	5.0	4.0	2.8	4.1	2.6
2.95	5.85	.....	4.0	2.4	2.0	3.4	5.4	4.8	2.8	3.8	2.4
2.95	5.55	.....	5.8	2.3	1.9	3.2	5.2	4.2	3.6	3.8	2.4
2.85	5.35	.....	4.3	3.2	1.8	3.0	4.0	4.0	.....	3.6	2.4
3.05	.....	.....	3.0	2.0	3.0	2.8	3.8	4.0	.....	3.3	2.4
2.95	.....	.....	3.4	.....	4.0	2.3	3.4	3.8	5.0	3.2	2.3
2.75	.....	.....	.....	6.0	.....	2.4	3.0	.....	4.0	.....	2.3

ter over gage March 7-8, May 30, August 23-24, September 20-22 October 28-29. Gage ry 1 to March 31 may be somewhat in error, due to uncertainty of change in datum.

ARKANSAS RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

rn rim of the Arkansas basin is formed by three of the highest mountain ranges —the Saguache, Sangre de Cristo, and Culebra, each having summits reaching feet in altitude. The melting of the almost perpetual snow which mantles the

high peaks near the north end of this rim furnishes water for three small creeks, known, respectively, as East, Lake, and Tennessee forks, and these, uniting near Leadville, form the Arkansas.

From the junction of the forks the river flows a little east of south for about 75 miles, then turns to the east and cuts through a canyon whose perpendicular walls attain elevations of over 2,000 feet above the water's edge, emerging finally into the plains region near Canyon. From Canyon to the Colorado-Kansas State line its general course is eastward for about 200 miles. Entering Kansas the river runs for 140 miles by general course a little south of east; it then makes a bold curve to the north, forming what is known as the Great Bend, below which it flows southeastward across Indian Territory to its junction with the Mississippi in northeastern Arkansas. The entire length of the stream from source to mouth, measured along the general course, is about 1,100 miles.

For about 120 miles from its source the river is a typical mountain torrent, descending in this distance from an elevation of 10,100 feet to about 5,300 feet. Its waters are clear and its bed is rocky. As it enters the plains region its gradient diminishes, its breadth increases it becomes unable at ordinary stages to carry the load of detritus collected in the more rapid portion above, and this detritus is gradually deposited, forming low, sandy banks and bars which block the course and cause the stream to shift its bed. At high stages this material is again caught up, the banks are eaten away, and very considerable changes of channel result from a single flood. The lower course of the river is bordered by wide alluvial bottoms, and the valley gradually merges with the valley of the Mississippi.

The drainage area as a whole is located a little south of the center of the United States, touching at its northernmost point latitude 39° 22′ N., and extending southward to latitude 33° 49′ N. Its eastern boundary is Mississippi River, its western the Rocky Mountains. The tract of country thus embraced comprises an area of approximately 188,000 square miles, and includes portions of Colorado, New Mexico, Kansas, Indian Territory, Texas, Missouri, and Arkansas. An area so immense necessarily presents great diversity in topography and resources. In the high mountains on the western border of the basin the passes range from 8,000 to 10,000 feet above sea, and some of the peaks tower to heights of over 14,000 feet. West of the one hundred and fifth meridian the country is generally mountainous and heavily timbered, and abounds in mineral wealth. Eastward stretch the seemingly endless rolling prairies of Colorado, Kansas, and Missouri. Throughout Indian Territory and Arkansas the country is more broken and includes a rough, mountainous section which extends across the northwest corner of Arkansas into southern Missouri. In the central part of Arkansas the surface is less rough and is largely a rolling prairie, with more or less timber interspersed. Toward the mouth of the river the country is low and heavily timbered and has a rich, black alluvial soil.

In its upper course the Arkansas is fed by numerous small streams, generally short, which lie wholly in or have their sources in the mountains. Those which head in the mountains and flow out onto the prairies are used more or less for irrigation. The most important of these tributaries are Greenhorn, Huerfano, Apishapa, and Purgatory rivers. East of the mountains the streams are all distinctively of the prairie type, and are bordered by bottom lands ranging from half a mile to 3 miles or more in width. In eastern Colorado and western Kansas the bottoms are light and sandy, but farther east they are alluvial in character. Rounded bluffs, 50 to 300 feet high, rise on both sides, and the country beyond is open and rolling. The stream beds are sandy—often quicksand—and muddy, there are no abrupt falls, and the streams run smoothly, with comparatively uniform descent. The plains tributaries include Black Squirrel, Horse, Two Butte, and Big Sandy creeks, Salt Fork, Cimarron, Verdigris, Grand, and Canadian rivers, and scores of smaller streams. The largest of these is Canadian River

The principal source of the water which the river bears to the plains is the precipitation along the crest of the high ranges. This is mainly in the form of snow and amounts to 20 o 30 inches each year. From the foothills to Arkansas City the precipitation ranges from 1

i inches, being 25 to 35 inches in the last 100 miles below Hutchinson. The natural ge in the basin is limited to a few mountain lakes of glacial origin.

e streams of this drainage area are subject to floods of two kinds—the annual spring s caused by the melting of the snows in the headwater regions; and floods caused by iolent storms, locally known as cloudbursts, in the foothills and plains regions. Occa- lly, too, the river runs dry, and many of the tributaries are intermittent in character.

ARKANSAS RIVER NEAR CANYON, COLO.

e gaging station at Canyon, Colo., was established April 17, 1889, by Robert Robert- It is located at the suspension footbridge at the Hot Springs Hotel, about 1 mile above State penitentiary. This station is but a short distance below the mouth of Grape c, and at a point where the river leaves the mountains. Although there is an occa- l break in the records, due to absence or changeof observer, they cover a period of iteen years.

e station is of special importance, being located at the mouth of the canyon, at a point ically above the diversion of all water to the plains region, except the North and h Canyon ditches, both of which head above the station. During the irrigation season of these ditches carries from 25 to 60 second-feet, according to the needs of the irriga- and their discharge should be added to the discharge at the station in order to obtain otal run-off at the mouth of the canyon. No accurate records have been kept of the int of water passing through these canals, although miscellaneous measurements have made when measurements were made at the regular station. The estimated monthly arges of Arkansas River at Canyon station do not include the water taken out by these ls.

e channel is straight for 500 feet above and 300 feet below the measuring section, and width of about 150 feet. The bed of the stream is rough, being composed of small ders, cobblestones, coarse gravel, and sand, and is not permanent from year to year, ging considerably with each high water. Both banks are high and rugged and are not e to overflow. At times there are two channels, the main channel under the left bank, a narrow channel discharging a few second-feet along the right bank. At high water e is but one channel. The gage heights range from 3 to 8 feet. The current is swift at tages, exceptionally so at high water, and has a rough surface. Accurate measure- ts are difficult to obtain.

ischarge measurements were at first made from a cable and car, the bridge from which surements were originally made by the State engineer having been destroyed. Later a suspension bridge was constructed in front of the hotel, necessitating the removal and acement of the gage, and subsequent measurements were made from this bridge. The ial point for soundings is marked on the floor of the bridge at the right bank, down- am side. A stay line is used for high-water measurements.

he gage established by Mr. Robertson in 1889 was an inclined staff attached to the crib n old bridge, on the right bank of the river, almost directly in front of the hotel. Bench ks for this gage were as follows: (1) On the top of a log of the crib; elevation, 10.01 feet. In the cleft of a red bowlder at the foot of a charred stump 50 feet downstream and on same side of the river; elevation, 9.60 feet. (3) A bedded rock 40 feet from the north of the cable, marked "B. M. No. 3, U. S. G. S.," 10 feet from the river bank; elevation 8 feet. Elevations refer to the datum of the gage.

new gage was established October 4, 1895, on the opposite side of the stream, at the e datum. The channel had filled in about the Robertson gage and the top of the gage broken off, making high-water readings impossible. December 27, 1895, the station inspected, and it was found that readings had been made from the old rod, which at the e of water prevailing recorded 0.40 foot above the new rod. When the water was high extended with unbroken surface from bank to bank the readings were the same, but at ater the observations on the old rod were misleading, owing to the accumulation of and gravel in front of the gage.

August 26, 1902, because of the shifting of the channel, a new inclined gage rod was placed at the site of the previous rod, just below the north end of the suspension bridge. The datum of the gage was unchanged.

The present gage was established September 2, 1903, by the State engineer. It is located on the right bank just below the bridge, and consists of an inclined section reading from 0 to 7.3 feet, and a vertical section reading from 7.3 to 12 feet. The datum is the same as that of the preceding gage. During 1905 the gage was read twice each day by Dr. J. L. Prentiss. The bench mark is a cross cut in a bedded granite bowlder, 80 feet southeast of the south end of the suspension bridge, near the river bank; elevation, 16.07 feet above the datum of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Reports; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 11, ii, pp 47–48; 18, iv, p 225; Bull 131, pp 35–36; 140, p 156; WS 16, p 119; 28, p 107; 37, pp 258–259; 50, pp 323–324; 66, pp 48–49; 84, pp 133–134; 99, pp 297–298; 131, pp 126–128.

Discharge: Ann 14 ii, p 107; 18, iv, p 226; Bull 131, pp 90, 91, 92; 140, p 157; WS 16, p 119; 28, p 116; 37, p 259; 50, p 324; 66, p 49; 84, p 135; 99, p 299; 131, pp 128, 179.

Discharge, monthly: Ann 11, ii, pp 48, 97; 12, ii, pp 349, 360; 13, iii, p 94; 14, ii, pp 108–109; 18, iv, p 227; 19, iv, p 356; 20, iv, pp 329, 331–335; 21, iv, p 231; 22, iv, p 341; WS 75, p 145; 84, p 136; 99, p 301; 131, p 130.

Discharge, yearly: Ann 13, iii, p 99; 20, iv, p 56.

Gage heights: Bull 131, pp 36–37; 140, p 157; WS 11, p 60; 16, p 119; 28, p 110; 37, p 259; 50, p 324; 66, p 49; 84, p 135; 99, p 299; 131, p 129.

Hydrographs: Ann 12, ii, p 242; 14, ii, p 107; 19, iv, p 357; 20, iv. p 336; 21, iv, p 231; 22, iv, p 341.

Rainfall and run-off relation: Ann 20, iv, p 330.

Rating tables: Ann 18, iv, p 226; 19, iv, p 355; Bull 131, p 36; WS 28, p 117; 39, p 450; 52, p 518; 66, p 172; 84, p 135; 99, p 300; 131, p 129.

Discharge measurements of Arkansas River near Canyon, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
March 17	R. I. Meeker	78	125	4.52	4.10	565
May 11	do	88	153	5.31	4.40	813
June 19	do	102	452	7.37	5.98	3,333
June 20	do	102	438	7.32	5.85	3,204
July 8	do	85	221	4.04	4.10	892
August 15	do	90	165	3.09	3.60	510
September 23[a]	do	60	104	2.91	3.20	303

[a] Made at different section.

Daily gage height, in feet, of Arkansas River near Canyon, Colo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	3.8	3.75	3.8	3.8	4.65	5.6	5.0	4.25	3.5	3.0	3.35	3.4
2	3.8	3.7	3.8	3.8	4.9	6.05	4.85	4.4	3.4	3.05	3.4	3.45
3	3.75	3.8	3.8	3.8	4.75	6.65	4.65	4.35	3.35	3.3	3.4	3.5
4	3.7	3.8	3.85	3.7	4.5	7.1	4.5	4.25	3.4	3.35	3.45	3.4
5	3.7	3.8	3.9	3.75	4.5	7.4	4.35	4.2	3.35	3.35	3.65	3.4
6	3.7	3.8	4.05	3.8	4.4	7.0	4.2	4.1	3.3	3.25	3.7	3.4
7	3.7	3.8	4.35	4.05	4.4	7.05	4.2	4.05	3.3	3.1	3.7	3.4
8	3.7	3.7	4.2	4.1	4.4	7.25	4.15	4.0	3.3	3.1	3.6	3.4
9	3.7	3.7	3.85	4.15	4.5	7.5	4.15	3.85	3.3	3.1	3.55	3.3
10	3.6	3.65	3.75	4.4	4.5	7.65	4.25	3.8	3.3	3.0	3.4	3.3
11	3.6	3.55	3.7	4.0	4.4	7.25	4.25	3.75	3.3	3.0	3.4	3.3
12	3.5	3.4	3.7	4.0	4.4	7.05	4.25	3.75	3.3	3.0	3.3	3.3
13	3.45	3.55	3.7	4.1	4.35	7.0	4.25	3.75	3.2	3.05	3.25	3.3
14	3.5	3.7	3.7	4.15	4.3	6.9	4.25	3.7	3.2	3.1	3.2	3.3
15	3.65	3.65	3.75	4.1	4.25	7.0	4.25	3.75	3.2	3.2	3.3	3.3
16	3.85	3.75	4.05	4.1	4.35	6.65	4.25	3.92	3.2	3.25	3.3	3.35
17	3.85	3.95	4.1	4.0	4.45	6.4	4.2	3.9	3.2	3.3	3.3	3.4
18	3.8	3.95	4.0	3.9	4.65	6.15	3.95	3.85	3.2	3.3	3.3	3.3
19	3.8	3.9	4.0	4.0	4.75	5.95	4.05	3.8	3.2	3.3	3.3	3.3
20	3.8	3.9	4.0	4.0	4.95	5.8	4.15	3.75	3.2	3.3	3.3	3.25
21	3.8	3.9	3.9	4.0	5.1	5.6	4.3	3.75	3.2	3.3	3.3	3.2
22	3.8	3.9	3.8	3.9	5.25	5.8	4.3	3.8	3.2	3.25	3.3	3.2
23	3.8	3.9	3.75	4.1	5.45	5.6	4.25	3.8	3.15	3.3	3.3	3.2
24	3.8	3.9	3.75	4.35	5.5	5.4	4.25	3.95	3.1	3.3	3.3	3.2
25	3.85	3.85	3.8	4.45	5.5	5.5	4.15	3.85	3.1	3.3	3.3	3.2
26	3.8	3.8	3.8	4.5	5.5	5.45	4.15	3.8	3.0	3.3	3.35	3.2
27	3.8	3.8	3.8	4.45	5.5	5.35	4.0	3.75	3.0	3.3	3.4	3.1
28	3.8	3.8	3.8	4.7	5.5	5.25	5.85	4.5	3.0	3.3	3.45	3.05
29	3.8	.....	3.7	4.6	5.4	5.15	4.55	3.55	3.0	3.3	3.3	3.0
30	3.8	.....	3.7	4.8	5.3	5.1	4.1	3.5	3.0	3.3	3.35	3.0
31	3.85	.....	3.7	.....	5.3	.....	4.25	3.45	.....	3.3	.....	3.0

Station rating table for Arkansas River near Canyon, Colo., from January 1 to June 10, 1905

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.40	150	4.30	730	5.20	1,620	6.20	3,130
3.50	190	4.40	810	5.30	1,740	6.40	3,540
3.60	240	4.50	900	5.40	1,870	6.60	3,980
3.70	300	4.60	990	5.50	2,000	6.80	4,440
3.80	360	4.70	1,080	5.60	2,140	7.00	4,930
3.90	430	4.80	1,180	5.70	2,290	7.20	5,450
4.00	500	4.90	1,280	5.80	2,440	7.40	5,990
4.10	570	5.00	1,390	5.90	2,600	7.60	6,550
4.20	650	5.10	1,500	6.00	2,760		

The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1904 and two during the early part of 1905. It is fairly well defined between gage heights 3.5 feet and 4.8 feet. Above gage height 4.8 feet the rating curve is very uncertain, being drawn to meet, at the highest gage height, the curve for the period following high water. It can be considered only a rough approximation.

Station rating table for Arkansas River near Canyon, Colo., from June 11 to December 31, 19

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.00	240	4.00	810	4.90	1,740	5.80	3,060
3.10	270	4.10	900	5.00	1,870	5.90	3,230
3.20	310	4.20	990	5.10	2,000	6.00	3,400
3.30	350	4.30	1,080	5.20	2,140	6.20	3,760
3.40	400	4.40	1,180	5.30	2,280	6.40	4,140
3.50	450	4.50	1,280	5.40	2,430	6.60	4,520
3.60	510	4.60	1,390	5.50	2,580	6.80	4,920
3.70	580	4.70	1,500	5.60	2,740	7.00	5,320
3.80	650	4.80	1,620	5.70	2,900	7.20	5,730
3.90	730						

The above table is applicable only for open-channel conditions. It is based on five dischs measurements made during the latter part of 1905. It is fairly well defined between gage heig 3.2 feet and 4.2 feet. The table has been extended beyond these limits, being based on two m urements near 6 feet. Above 6 feet it is uncertain.

Estimated monthly discharge of Arkansas River near Canyon, Colo., for 1905.

[Drainage area, 3,060 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dept inch
January	395	170	324	19,920	0.106	0
February	465	150	349	19,380	.114	
March	770	300	404	24,840	.132	
April	1,180	300	599	35,640	.196	
May	2,000	690	1,254	77,110	.410	
June	6,690	2,000	3,977	236,700	1.30	1
July	1,870	690	1,064	65,420	.348	
August	1,280	425	743	45,680	.243	
September	450	240	319	18,980	.104	
October	375	240	318	19,550	.104	
November	580	310	395	23,500	.129	
December	450	240	343	21,090	.112	
The year	6,690	150	841	607,800	.275	3

ARKANSAS RIVER AT PUEBLO, COLO.

The gaging station at Pueblo, Colo., was established in September, 1894, by A. P. Da at the Santa Fe Avenue Bridge. Since that time continuous records have been kept u various bridges for a period of eleven years. This station is an important one, being loca near the head of the principal irrigated portion of Arkansas Valley and above the h gates of the larger canals. For this reason water superintendents and commissioners dep on gagings made at this station for data by which distribution of the water is made to ca below.

The Arkansas River channel at Pueblo is the best confined stream in Colorado. A the Victoria Avenue Bridge slag levees and dry rubble walls confine the channel in a s what irregular course. From Victoria Avenue Bridge to Main Street Bridge, a distan 600 feet, the channel is straight, of uniform width, and with perpendicular masonry w At the lower side of the Main Street Bridge the masonry walls give way to hand-laid levees, which, though straight, bear at a slight angle to the left of the masonry walls.

of the stream is composed of cobblestones, merging into coarse gravel and sand. There ut one channel at all stages. During extreme cold weather gage readings are discon- ied, as the channel becomes obstructed with irregular masses and gorges of ice, which ide the stream into several channels. Gage heights range from 2 to 12 feet on the gage . During high water and its recession the channel is more or less shifting. During ıter the channel fills in slightly and is scoured out again in the spring. The flow of the eam is rapid, but not too swift for accurate measurements.

Discharge measurements have been made principally from the Main Street Bridge, though ne have been made at the Union Avenue Bridge. The Main Street Bridge consists of a gle 151-foot span. A stay line is located 40 feet upstream and is used for measurements ove gage height 4 feet. The initial point for soundings is the edge of the capstone of the ht masonry retaining wall.

Originally there were two gage rods. The main gage was a vertical staff fastened to the t-bank abutment of the Denver and Rio Grande railroad bridge at Santa Fe avenue. ıere was also a short vertical rod for extreme low water fastened to a pile about 20 feet out the stream. In June, 1895, an inclined staff gage was placed at the Victoria Avenue ridge in order to determine the slope of the water surface. These rods were read until ly 10, 1898, when, on account of the shifting of the bed of the river, they were abandoned, ıd a new gage was installed on the east side of the Main Street Bridge. Readings were ade at the Main Street Bridge until March 3, 1900, when, owing to the scouring of the chan- l, a staff gage was fastened vertically to the masonry wall about 60 feet below the south ıd of the Union Avenue Bridge.

June 13, 1900, this rod was connected with a bench mark on the coping at the north- est corner of the Union Avenue Bridge, which was found to be 19.79 feet above the zero of ıe rod. In March, 1902, another rod was fastened vertically to the masonry wall on the ght bank, about 30 feet above the south end of the Union Avenue Bridge. Gage heights om July 10, 1898, to July 14, 1902, were taken from the rod just below the Union Avenue ridge. From July 14, 1902, until July 7, 1905, the readings were taken from the rod above ıe bridge. When the upper gage was set the datum was 0.2 foot higher than the lower ıge. In all discharge measurements made in 1902 the gage height was taken from the rod ove the Union Avenue Bridge.

In June, 1905, the gage above Union Avenue Bridge was rendered useless by shifting of ıe channel, and July 7, 1905, a standard chain gage was fastened to the upstream side of ıe Main Street Bridge, about 300 feet below the staff gage. The length of the chain is 19.32 et. There are two markers, giving a range of 20 feet on a 10-foot scale. During 1905 the ıge was read twice each day by David J. Cox. The bench mark is a cross painted on the otway at the gage-chain box; elevation, 18.60 feet above the datum of the gage.

Information in regard to this station is contained in the following publications of the nited States Geological Survey (Ann=Annual Reports; Bull=Bulletin; WS=Water-Sup- ly Paper):

Description: Ann 11 ii, p 49; 18, iv, pp 227-228; Bull 140, p, 158; WS 16, p 120; 28, pp 107-108; 37, pp 9-260; 50, p 325; 66, pp 49-50; 84, pp 130-131; 99, pp 293-294; 131, pp 130-131.

Discharge: Ann 18, iv, p 228; Bull 131, p 90; 140, p 158; WS 16, p 120; 28, p 116; 37, p 260; 50, p 325; 66, p); 84, p 131; 99, p 295; 131, pp 132, 180.

Discharge, monthly: Ann 11, ii, pp 49, 98; 12, ii. p 360; 13, iii, p 94; 18, iv, p 230; 19, iv, p 357; 20, iv, pp 29, 336; 21, iv, p 232; 22, iv, p 342; WS 75, p 146; 84, p 133; 99, p 296; 131, p 133.

Discharge, yearly: Ann 13, iii, p 99; 20, iv, p 56.

Gage heights: Bull 140, p 159; WS 11, p 61; 16, p 120; 28, p 111; 37, p 260; 50, p 326; 66, p 50; 84, p 132; 99, p 295-296; 131, p 132.

Hydrographs: Ann 18, iv, p 231; 19, iv, p 357; 20, iv, p 337; 21, iv, p 232; 22, iv, p 342; WS 75, p 146.

Rainfall and run-off relation: Ann 20, iv, p 330.

Rating tables: Ann 18, iv, p 229; 19, iv, p 356; WS 28, p 117; 39, p 450; 52, p 518; 66, p 172; 84, p 132; 99, p 296; 131, p 133.

Discharge measurements of Arkansas River at Pueblo, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
March 4	R. I. Meeker	107	111	3.51	2.25	[illegible]
March 11	do	75	87	3.71	2.10	[illegible]
March 16	do	99	133	4.10	2.50	[illegible]
May 10	do	151	274	4.93	3.40	1,[illegible]
June 6	M. P. Beeson	150	835	8.15	6.75	6,[illegible]
June 7	R. I. Meeker	150	640	8.20	5.85	5,[illegible]
Do	do	150	655	8.03	5.90	5,[illegible]
June 20	do	150	410	6.80	4.25	2,[illegible]
June 24	do	150	396	6.70	4.15	2,[illegible]
July 7	do	149	196	4.06	2.72	[illegible]
August 9	do	151	230	4.35	3.02	1,[illegible]
September 23	do	80	102	2.65	2.15	[illegible]
November 4	do	89	119	2.97	2.30	[illegible]

Daily gage height, in feet, of Arkansas River at Pueblo, Colo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.1	1.95	2.4	4.05	4.05	4.3	3.35	3.3	2.4	2.05	2.35	2.55
2	2.1	1.95	2.4	2.9	3.9	4.75	3.15	3.35	2.4	2.08	2.33	2.55
3	2.05	1.95	2.4	2.8	3.75	5.1	3.0	3.05	2.35	2.05	2.33	2.52
4	2.05	1.95	2.3	2.6	3.6	6.3	2.95	2.95	2.4	2.38	2.35	2.45
5	2.0	1.95	2.3	2.55	3.5	6.55	2.85	2.85	2.35	2.32	2.42	2.45
6	2.0	2.0	2.3	2.55	3.45	6.6	2.75	2.85	2.55	2.3	2.6	2.48
7	2.0	2.0	2.7	2.8	3.35	6.05	2.55	3.25	2.7	2.2	2.62	2.48
8	2.0	2.0	2.75	2.9	3.35	6.25	2.65	3.15	2.55	2.12	2.58	2.48
9	2.0	2.0	2.65	2.85	3.55	6.55	2.8	2.95	2.4	2.05	2.5	2.5
10	1.95	2.0	2.45	2.9	3.45	6.6	2.75	2.95	2.35	1.95	2.38	2.5
11	1.95	2.0	2.2	2.75	3.35	6.0	3.0	2.85	2.45	1.97	2.4	2.5
12	1.95	2.0	2.1	2.75	3.3	5.7	3.0	3.0	2.3	2.03	2.35	2.48
13	1.9	2.0	2.1	2.75	3.25	5.7	2.85	2.75	2.25	1.97	2.3	2.52
14	1.9	2.0	2.2	2.75	3.25	5.6	2.85	2.55	2.3	2.0	2.25	2.52
15	1.9	2.0	2.35	2.75	3.2	5.45	2.8	2.55	2.3	2.0	2.28	2.52
16	1.9	2.0	2.4	2.7	3.2	5.25	2.9	2.85	2.25	2.07	2.28	2.52
17	1.9	2.0	2.6	2.75	3.2	5.15	2.85	2.9	2.2	2.05	2.3	2.52
18	1.9	2.0	2.6	2.6	3.45	4.8	2.7	2.85	2.2	2.2	2.28	2.52
19	1.9	2.0	2.5	2.65	3.55	4.65	2.5	2.75	2.2	2.23	2.28	2.5
20	1.9	2.05	2.5	2.65	4.1	4.2	2.7	3.1	2.2	2.17	2.22	2.5
21	1.9	2.1	2.4	2.55	4.2	4.0	3.0	2.75	2.2	2.2	2.22	2.48
22	1.9	2.15	2.4	2.45	4.35	3.85	3.2	2.55	2.2	2.2	2.2	2.42
23	1.9	2.2	2.3	2.7	4.45	3.9	3.0	2.35	2.15	2.27	2.25	2.38
24	1.9	2.25	2.3	3.4	4.6	3.85	2.8	2.55	2.15	2.25	2.3	2.4
25	1.9	2.3	2.25	3.5	4.6	3.8	2.75	2.7	2.12	2.25	2.25	2.4
26	1.9	2.35	2.25	3.95	4.45	3.7	2.8	2.65	2.1	2.23	2.22	2.42
27	1.9	2.4	2.35	3.75	4.45	3.7	3.05	2.65	2.08	2.2	2.3	2.4
28	1.9	2.4	2.4	3.75	4.4	3.65	2.65	2.4	2.05	2.2	2.3	2.4
29	1.9	.....	2.35	3.8	4.35	3.7	2.45	2.35	2.05	2.25	2.4	2.35
30	1.9	.....	2.3	3.85	4.15	3.45	3.05	2.5	2.05	2.27	2.48	2.3
31	1.9	.....	2.3	.....	4.1	.....	3.0	2.[illegible]	[illegible]	[illegible]	[illegible]	[illegible]

NOTE.—Gage heights during January and February have been [illegible]

tation rating table for Arkansas River at Pueblo, Colo., from January 1 to June 10, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.00	255	3.10	1,130	4.20	2,650	5.30	4,330
2.10	300	3.20	1,250	4.30	2,800	5.40	4,490
2.20	350	3.30	1,370	4.40	2,950	5.50	4,650
2.30	410	3.40	1,500	4.50	3,100	5.60	4,810
2.40	480	3.50	1,630	4.60	3,250	5.70	4,975
2.50	560	3.60	1,770	4.70	3,400	5.80	5,140
2.60	640	3.70	1,910	4.80	3,550	5.90	5,305
2.70	730	3.80	2,050	4.90	3,705	6.00	5,470
2.80	820	3.90	2,200	5.00	3,860	6.20	5,800
2.90	920	4.00	2,350	5.10	4,015	6.40	6,130
3.00	1,020	4.10	2,500	5.20	4,170	6.60	6,460

e above table is applicable only for open-channel conditions. It is based on six discharge measure-s made during 1904 and seven measurements during the first part of 1905. It is fairly well defined.

on rating table for Arkansas River at Pueblo, Colo., from June 11 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.00	200	2.40	420	2.80	770	3.20	1,230
2.10	240	2.50	500	2.90	870	3.30	1,360
2.20	290	2.60	580	3.00	980	3.40	1,490
2.30	350	2.70	670	3.10	1,100	3.50	1,630

above table is applicable only for open-channel conditions. It is based on three discharge meas-nts made during the latter part of 1905. It is well defined.
ve 3.5 feet the table is the same as the preceding one. Changes in conditions due to flood make ables necessary for 1905.

Estimated monthly discharge of Arkansas River at Pueblo, Colo., for 1905.

[Drainage area, 4,600 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ary	300	215	233	14,330	0.051	0.059
ary	480	235	293	16,270	.064	.067
h	775	300	475	29,210	.103	.119
	2,425	520	1,077	64,080	.234	.261
	3,250	1,250	2,085	128,200	.453	.522
	6,460	1,560	3,867	230,100	.841	.938
	1,425	460	845	51,960	.184	.212
st	1,425	385	790	48,580	.172	.198
mber	670	220	346	20,590	.075	.084
er	406	180	274	16,850	.060	.069
mber	598	290	385	22,910	.084	.094
ber	540	302	469	28,840	.102	.118
The year	6,460	180	928	671,900	.202	2.74

ARKANSAS RIVER NEAR SYRACUSE, KANS.

This station, established August 21, 1902, by W. G. Russell, is located on the highway bridge 1 mile south of Syracuse, Kans.

The channel above and below the station is straight and the water is sluggish. The right bank is low and liable to overflow; the left bank is high, and the bed of the stream is sandy and shifting.

Discharge measurements are made from the bridge. The initial point for soundings is on the left bank.

The gage is a staff fastened to the downstream pile of a bent, 158 feet from the initial point for soundings. During 1905 the gage was read once each day by Philip Botts. The bench mark is on the top of the east end of the first sill at the north end of the bridge. Elevation, 11.52 feet above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 84, p 123; 99, p 269; 131, p 134.
Discharge: 84, p 123; 99, p 269; 131, p 134.
Discharge, monthly: 84, p 125; 99, p 271.
Gage heights: 84, p 124; 99, p 270; 131, p 135.
Rating tables: 84, p 124; 99, pp 270-271.

Discharge measurements of Arkansas River, near Syracuse, Kans., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 19	W. G. Russell	262	328	2.39	2.70	785
June 7	do	420	1,341	3.85	4.75	5,162
June 8	do	532	1,656	3.84	5.15	6,362
June 8	do	562	1,833	3.77	5.40	6,909
June 9	do	527	1,595	3.57	5.20	5,704
July 30	do	380	966	2.55	4.00	2,468
August 19	do	208	140	1.51	2.30	211

Daily gage height, in feet, of Arkansas River near Syracuse, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	1.3	1.9	2.5	2.0	5.0	4.3	2.8	3.5	2.4	1.9	2.0
.....	1.5	1.9	2.5	3.0	4.9	4.3	2.7	6.3	2.2	1.9	2.0
.....	1.4	2.0	2.3	5.25	4.8	4.6	2.6	6.1	2.3	1.9	2.0
.....	1.7	2.5	2.3	5.0	4.7	4.0	2.5	4.7	2.0	1.9	2.0
.....	1.7	2.5	2.1	4.0	4.6	4.0	2.8	4.2	2.4	1.8	2.1
.....	1.8	2.5	2.1	3.5	4.5	4.3	2.8	3.7	2.4	1.8	2.1
.....	2.0	2.5	2.0	3.5	4.4	4.7	2.7	3.2	2.3	1.8	2.1
.....	2.0	2.5	2.0	3.1	4.3	5.4	2.6	3.7	2.3	1.8	2.0
.....	2.0	2.5	1.8	2.9	4.0	5.2	2.5	3.5	3.4	1.8	1.9
.....	1.8	2.5	1.8	3.1	3.9	5.4	2.4	3.2	3.2	1.7	1.9
.....	1.8	2.5	1.8	3.1	3.8	5.1	2.4	3.1	3.0	1.8	1.9
.....	1.7	2.5	1.8	3.1	4.4	5.1	2.0	3.1	2.7	1.8	2.0
.....	1.7	2.8	1.8	3.2	4.6	5.0	1.9	2.8	2.6	1.8	2.0
.....	1.5	2.8	1.8	3.4	4.4	5.0	1.8	2.7	2.6	1.8	2.0
.....	1.5	2.8	1.8	3.1	4.2	4.7	2.2	2.7	2.6	1.8	2.0
.....	1.7	2.8	1.8	3.1	4.2	4.7	1.9	2.6	2.4	1.8	2.1
.....	1.8	2.8	1.9	2.8	4.2	4.7	1.8	2.6	2.3	1.8	2.0
.....	1.9	2.8	1.9	2.8	4.2	4.5	1.8	2.6	2.4	1.8	2.0
.....	2.0	3.0	1.8	2.7	4.2	4.5	1.8	2.5	2.4	1.8	2.0
.....	2.4	3.0	1.8	2.7	4.8	4.3	1.8	2.2	2.4	1.8	2.0
.....	2.4	3.3	2.5	2.7	4.8	4.0	1.8	2.0	2.3	1.8	2.0
.....	2.0	3.4	2.4	2.6	4.5	4.5	1.8	2.1	2.3	1.8	2.0
.....	2.0	3.5	2.2	2.6	4.4	4.3	1.8	2.2	2.3	1.8	2.0
.....	1.8	3.5	2.0	3.5	4.2	3.7	2.3	2.0	2.0	1.8	2.1
.....	1.8	3.3	2.0	7.25	6.5	3.5	2.4	1.9	2.0	1.8	2.1
.....	1.5	3.0	1.8	6.5	4.7	3.5	2.5	1.8	2.1	1.8	2.1
.....	1.5	3.0	1.8	5.05	5.0	3.4	2.7	1.8	2.0	1.8	2.1
.....	1.5	2.8	1.9	6.25	5.0	3.3	2.5	3.3	2.0	1.8	2.2
.....	1.7	.....	1.8	5.0	4.8	3.0	4.8	2.9	2.0	1.8	2.2
.....	1.7	.....	1.7	5.0	4.7	2.9	4.3	2.6	1.9	1.8	2.3
.....	1.8	.....	1.7	.....	4.5	.....	3.4	2.5	.....	2.0	.....

n rating table for Arkansas River near Syracuse, Kans., from January 1 to November 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.30	3	2.60	535	3.80	2,100	5.00	5,800
1.40	5	2.70	625	3.90	2,300	5.20	6,750
1.50	10	2.80	725	4.00	2,500	5.40	7,900
1.60	20	2.90	835	4.10	2,720	5.60	9,100
1.70	40	3.00	950	4.20	2,950	5.80	10,500
1.80	65	3.10	1,070	4.30	3,200	6.00	12,000
1.90	95	3.20	1,200	4.40	3,500	6.20	13,600
2.00	130	3.30	1,335	4.50	3,800	6.40	15,400
2.10	175	3.40	1,480	4.60	4,150	6.60	17,200
2.20	230	3.50	1,625	4.70	4,500	6.80	19,300
2.30	295	3.60	1,775	4.80	4,900	7.00	21,500
2.40	370	3.70	1,930	4.90	5,350	7.20	24,100
2.50	450						

above table is applicable only for open-channel conditions. It is based on seven discharge measits made during 1905 and three high-water measurements of 1903. It is not very well defined.

Estimated monthly discharge of Arkansas River near Syracuse, Kans., for 1905.

[Drainage area, 24,960 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	370	3	78.0	4,796	0.0031	0.0036
February	1,625	95	737	40,930	.030	.031
March	450	40	149	9,162	.0060	.0069
April	24,800	130	3,613	215,000	.145	.162
May	16,300	2,160	4,311	265,100	.173	.199
June	7,900	835	3,783	225,100	.152	.170
July	4,900	65	612	37,630	.025	.029
August	14,500	65	1,765	108,500	.071	.082
September	1,480	95	393	23,380	.016	.018
October	130	40	70.2	4,316	.0028	.0032
November	295	95	151	8,985	.0060	.0067
The period				942,900		

ARKANSAS RIVER NEAR DODGE, KANS.

This station was established November 28, 1902, by W. G. Russell, and is located one-fourth mile south of Dodge, on the highway bridge.

The channel both above and below the station is straight for about 100 feet. Both banks are low and liable to overflow. The bed of the stream is sandy and shifting.

Discharge measurements are made from the bridge. The initial point for soundings is on the left bank.

The gage is a staff fastened to the upstream pile of a bent 337 feet from the north end of the bridge. During 1905 the gage was read once each day by Alexander Alter. Bench marks were established as follows: (1) The top of the east end of the cap at the north end of the bridge; elevation 9.83 feet. (2) The top of the east end of the cap at the abutment of the south end of the bridge; elevation, 10.10 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 84, p 123; 99, p 268; 131, p 135.
Discharge: 84, p 123; 99, p 268; 131, p 136.
Discharge, monthly: 131, p 138.
Gage heights: 84, p 128; 99, pp 268-269; 131, p 137.
Rating table: 131, p 138.

Discharge measurements of Arkansas River near Dodge, Kans., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 18	W. G. Russell	455	435	1.98	2.10	865
June 10	do	482	1,616	3.42	3.90	5,519
June 11	do	485	1,624	3.79	4.10	6,150
June 11	do	487	1,757	4.14	4.40	7,273
July 31	do	467	570	2.59	2.70	1,476
August 18	do	264	100	1.31	1.70	131
September 24	do	34	5.4	.83	1.10	4

Daily gage height, in feet, of Arkansas River near Dodge, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	1.4	2.05	2.4	1.4	4.8	3.55	2.0	2.4	1.1	1.0
.....	1.4	2.1	2.3	1.4	4.25	3.35	1.9	2.25	1.1	1.0
.....	1.4	2.1	2.2	1.4	4.0	3.0	1.9	2.85	1.1	1.0
.....	1.4	2.1	2.05	2.8	4.0	3.0	1.75	3.55	1.1	1.0
.....	1.4	2.1	2.0	3.5	4.0	3.0	1.6	3.1	1.1	1.0
.....	1.4	2.1	1.9	3.2	4.1	2.6	1.5	2.95	1.1	1.0
.....	1.4	2.1	1.85	2.8	4.0	2.65	1.45	2.7	1.1	1.0
.....	1.55	2.1	1.8	2.6	3.6	2.55	1.5	2.6	1.35	.9
.....	1.75	2.1	1.8	2.5	3.55	3.85	1.4	1.95	1.5	.9
.....	1.8	2.1	1.7	2.5	3.3	4.0	1.4	1.85	1.5	.9
.....	1.8	2.1	1.7	2.4	3.0	4.0	1.4	1.8	1.5	.9
.....	1.8	.9	1.7	2.3	2.6	4.0	1.35	1.7	1.45	.9
.....	1.8	.9	1.7	2.3	3.65	4.0	1.3	2.05	1.4	.9
.....	1.8	.9	1.6	2.3	3.65	4.0	1.2	1.95	1.5	.9
.....	1.7	.9	1.6	2.5	3.55	4.0	1.2	1.85	1.45	1.0
.....	1.7	.9	1.6	2.5	3.5	3.95	1.1	1.7	1.4	1.0
.....	1.7	.9	1.6	2.35	3.65	3.6	1.1	1.7	1.1	1.1
.....	1.7	.9	1.6	2.15	3.7	3.5	1.1	1.35	1.1	1.2
.....	1.7	.9	1.6	2.15	3.5	3.35	1.05	1.3	1.1	1.2
.....	1.8	.9	1.6	2.2	3.5	3.6	1.0	1.4	1.1	1.3
.....	1.8	.9	1.6	2.2	4.5	3.4	1.0	1.3	1.1	1.3
.....	1.85	.9	1.5	2.2	4.65	3.2	1.1	1.2	1.1	1.3
.....	1.95	1.0	1.4	2.3	4.35	3.2	1.1	1.2	1.1	1.3
.....	1.9	2.5	1.5	2.6	4.0	3.2	1.1	1.2	1.05	1.3
.....	1.9	2.6	1.5	3.0	4.75	2.9	1.1	1.1	1.0	1.3
.....	1.9	2.6	1.5	6.25	4.25	2.5	1.1	1.1	1.0	1.3
.....	2.0	2.8	1.5	5.25	3.5	2.4	1.0	1.1	1.0	1.3
.....	2.0	2.55	1.4	4.75	4.25	2.35	1.0	1.1	1.0	1.3
.....	2.0	.....	1.4	5.45	5.9	2.15	1.0	1.0	1.0	1.3
.....	2.0	.....	1.3	4.75	4.25	2.0	1.3	1.0	1.0	1.3
.....	2.0	.....	1.3	.....	4.0	.....	2.5	1.0	.....	1.4

NE.—River frozen January 1 to February 23, approximately.

on rating table for Arkansas River near Dodge, Kans., from January 1 to June 12, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.30	180	2.40	1,335	3.50	4,100	4.60	8,110
1.40	225	2.50	1,530	3.60	4,425	4.70	8,550
1.50	280	2.60	1,735	3.70	4,760	4.80	9,000
1.60	345	2.70	1,950	3.80	5,100	4.90	9,465
1.70	420	2.80	2,175	3.90	5,450	5.00	9,950
1.80	505	2.90	2,410	4.00	5,800	5.20	10,930
1.90	605	3.00	2,660	4.10	6,160	5.40	11,910
2.00	720	3.10	2,920	4.20	6,530	5.60	12,900
2.10	850	3.20	3,195	4.30	6,910	5.80	13,920
2.20	995	3.30	3,485	4.40	7,300	6.00	14,950
2.30	1,155	3.40	3,785	4.50	7,700		

he above table is applicable only for open-channel conditions. It is based on four discharge measurements made during April to June, 1905. Owing to the shifting character of the stream bed and insufficient measurements, the above table is very uncertain.

Station rating table for Arkansas River near Dodge, Kans., from June 13 to October 31, 1

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	2	1.80	200	2.60	1,255	3.40	3,425
1.10	4.5	1.90	275	2.70	1,460	3.50	3,770
1.20	10	2.00	370	2.80	1,685	3.60	4,125
1.30	20	2.10	480	2.90	1,930	3.70	4,490
1.40	35	2.20	605	3.00	2,195	3.80	4,880
1.50	60	2.30	745	3.10	2,480	3.90	5,235
1.60	95	2.40	900	3.20	2,780	4.00	5,620
1.70	140	2.50	1,070	3.30	3,095		

The above table is based on three discharge measurements made during July and August, 1905
See note to table above.

Estimated monthly discharge of Arkansas River near Dodge, Kans., for 1905.

Month.	Discharge in second-feet.			Total acre-f
	Maximum.	Minimum.	Mean.	
February 24-28	2,175	1,530	1,761	1
March	1,335	180	453	2
April	16,300	225	3,126	18
May	14,430	1,735	5,772	35
June	5,800	370	3,285	19
July	1,070	2	86.0	
August	3,948	2	545	3
September	60	2	17.1	
October	35	1	9.8	
The period				82

NOTE.—No estimate for ice period.

ARKANSAS RIVER AT HUTCHINSON, KANS.

This station was established May 13, 1895, and was discontinued October 31, 1905. located at the wagon bridge at the south end of Main street, Hutchinson, Kans.

The channel is straight for some distance above and below the bridge and has a widt 1,020 feet, broken by 11 steel piers. The bed is sandy and very shifting, necessitating quent discharge measurements and soundings. At low water the stream subdivides in number of small channels.

Discharge measurements are made from the bridge at high water; at low water they be made by wading.

The gage is a staff fastened to the downstream pier of the third bent from the north of the bridge. During 1905 the gage was read once each day by George E. Dixon. B marks were established as follows: (1) The upper crosspiece of the pier guard; elevat 8.35 feet. (2) The top of the iron doorsill of the first brick building next to the river; vation, 8.12 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following publications of United States Geological Survey (Ann=Annual Reports; Bull=Bulletin; WS = W Supply Paper):

Description: Ann 18, iv, pp 232-233; 20, iv, p 342-343; Bull 140, pp 1[illegible] p 265; 50, p 330; 66, p 56; 84, p 120; 99, p 266; 131, p 139.

Discharge: Ann 18, iv, p 233; Bull 140, p 161; WS 16, p 124; 28, p[illegible] 121; 99, p 266; 131, p 139.

Discharge, monthly: Ann 18, iv, p 234; 19, iv, p 361; 20, iv, p[illegible] *140, p 162; WS 75, p 147;* 84, p 122; 99, p 267; 131, p 141.

rge, yearly: Ann 20, iv, p 57.
eights: Bull 140, p 161; WS 11, p 62; 16, p 124; 28, p 114; 37, p 265; 50, p 330; 66, p 56; 84, p 121; 99, 7; 131, p 140.
graphs: Ann 18, iv, p 234; 19, iv, p 361; 20, iv, p 343; 21, iv, p 237; 22, iv, p 344; WS 75, p 148.
ll and run-off relation: Ann 20 iv, p 330.
; tables: Ann 18, iv, p 234; 19, iv, p 360; WS 28, p 117; 39, p 450; 52, p 518; 66, p 172; 84, p 122; 99, 1, p 140.

Discharge measurements of Arkansas River at Hutchinson, Kans., in 1905.

;e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis-charge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. G. Russell.....	398	554	2.58	2.80	1,432
.....	.....do.....	762	1,505	3.83	4.80	5,764
.....	.....do.....	532	1,250	3.19	4.20	3,985
.....	.....do.....	668	1,442	3.31	4.55	4,779
.....	.....do.....	568	1,164	3.18	4.15	3,697
3.....	.....do.....	408	469	2.26	2.60	1,059
20.....	.....do.....	312	228	1.96	1.85	446
ber 23..	.....do.....	131	87	1.85	1.40	161

Daily gage height, in feet, of Arkansas River at Hutchinson, Kans., for 1905.

)ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
....	1.95	2.25	3.48	2.05	5.57	5.0	3.2	2.6	1.4	1.3
.....	1.95	2.25	3.4	2.0	5.5	5.0	3.25	2.5	1.32	1.3
.....	1.95	2.25	3.4	2.05	5.15	4.75	3.2	2.5	1.22	1.3
.....	1.95	2.25	3.25	2.05	4.85	4.4	3.05	2.8	1.2	1.3
.....	1.95	2.25	3.05	2.05	4.7	4.2	3.0	2.9	1.2	1.3
.....	1.85	2.25	3.0	2.1	4.5	3.95	2.7	3.0	2.2	1.25
.....	1.75	2.25	2.9	3.82	4.5	3.6	2.45	3.4	2.15	1.2
.....	1.55	2.25	2.9	3.45	4.4	3.5	2.25	3.5	1.95	1.2
.....	1.5	2.25	2.8	3.3	4.6	3.35	2.2	3.4	1.9	1.2
.....	1.5	2.25	2.7	3.18	4.45	3.3	2.2	3.25	1.9	1.2
.....	1.5	2.25	2.6	3.05	4.25	4.3	2.22	3.05	1.9	1.2
.....	1.5	2.25	2.6	2.95	4.05	4.1	2.3	2.75	1.9	1.2
.....	1.5	2.25	2.52	2.9	3.85	4.4	2.2	2.4	1.85	1.15
.....	1.5	2.25	2.4	2.8	3.9	4.2	2.05	2.3	1.8	1.15
.....	1.5	2.2	2.4	2.7	3.8	4.3	1.92	2.3	1.75	1.15
.....	1.5	2.15	2.4	2.7	3.85	4.6	1.9	2.25	1.7	1.15
.....	1.6	2.05	2.4	2.75	3.85	4.35	1.9	2.2	1.65	1.15
.....	1.7	2.0	2.5	2.8	3.75	4.25	1.85	2.1	1.6	1.2
.....	1.7	2.0	2.5	2.75	3.8	4.15	1.8	1.95	1.55	1.2
.....	1.8	2.0	2.6	2.75	3.85	4.1	1.8	1.85	1.5	1.2
.....	1.95	2.25	2.5	2.7	4.05	4.0	1.7	1.9	1.45	1.2
.....	2.2	2.4	2.4	2.7	3.95	3.85	1.77	1.87	1.4	1.2
.....	2.2	2.5	2.3	2.6	4.8	4.2	1.8	1.8	1.4	1.2
.....	2.2	2.5	2.2	2.6	5.2	3.65	1.85	1.7	1.35	1.2
.....	2.2	2.78	2.2	2.7	4.8	3.5	1.7	1.67	1.35	1.2
.....	2.25	3.5	2.2	2.82	4.65	3.4	1.7	1.62	1.35	1.2
.....	2.25	2.9	2.15	4.1	4.95	3.15	1.7	1.6	1.35	1.2
.....	2.25	3.5	2.1	5.42	4.9	3.15	1.7	1.6	1.35	1.2
.....	2.25	.....	2.1	5.4	4.95	2.92	1.7	1.5	1.3	1.2
.....	2.25	.....	2.05	5.4	5.05	3.15	2.4	1.4	1.3	1.25
.....	2.25	.....	2.05	.....	5.58	.....	2.6	1.4	.....	1.3

Station rating table for Arkansas River at Hutchinson, Kans., from January 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.10	80	2.20	660	3.30	2,065	4.40	4,380
1.20	95	2.30	750	3.40	2,240	4.50	4,650
1.30	120	2.40	850	3.50	2,420	4.60	4,920
1.40	150	2.50	960	3.60	2,605	4.70	5,205
1.50	190	2.60	1,070	3.70	2,800	4.80	5,500
1.60	240	2.70	1,190	3.80	3,005	4.90	5,800
1.70	300	2.80	1,320	3.90	3,220	5.00	6,100
1.80	360	2.90	1,460	4.00	3,440	5.20	6,730
1.90	430	3.00	1,600	4.10	3,670	5.40	7,380
2.00	500	3.10	1,750	4.20	3,900	5.60	8,050
2.10	580	3.20	1,900	4.30	4,140		

The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during 1905, and is fairly well defined.

Estimated monthly discharge of Arkansas River at Hutchinson, Kans., for 1905.

[Drainage area, 34,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	705	190	430	26,440	0.013	0.015
February	2,420	500	866	48,100	.025	.026
March	2,384	540	1,112	68,370	.033	.038
April	7,446	500	1,965	116,900	.058	.065
May	7,982	2,902	4,838	297,500	.142	.164
June	6,100	1,488	3,470	206,500	.102	.114
July	1,982	300	743	45,680	.022	.025
August	2,420	150	882	54,230	.026	.030
September	660	95	257	15,290	.0076	.008
October	120	88	99.5	6,118	.0029	.003
The period				885,100		

ARKANSAS RIVER AT ARKANSAS CITY, KANS.

This station was established September 23, 1902, by W. G. Russell. It is located on the Chestnut Avenue Bridge, one-half mile west of Arkansas City, Kans.

The channel is straight for about 200 feet above and below the station and has a width of 550 feet, broken by 36 pile piers. Both banks are low and liable to overflow. The bed of the river is sandy and shifting. The current is moderately rapid.

Discharge measurements are made from the bridge. The initial point for soundings is on the left bank.

The gage is a staff fastened to the downstream pile of the second bent from the east end of the bridge. During 1905 the gage was read daily by T. C. White. Bench marks were established as follows: (1) the top of the cap on the pile which [illegible] 17.20 feet. (2) A nail driven into the south pile of the bent [illegible] 11.97 feet. Elevations refer to the datum of the gage.

nation in regard to this station is contained in the following Water-Supply Papers nited States Geological Survey.

tion: 84, p 119; 99, p 263; 131, p 141.
ge: 84, p 119; 99, p 264; 131, p 142.
ge, monthly: 99, p 265; 131, p 144.
ights: 84, p 120; 99, p 264; 131, p 142.
table: 99, p 265; 131, p 143.

Discharge measurements of Arkansas River at Arkansas City, Kans., in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. G. Russell.....	219	541	2.60	4.40	1,407
.....	.....do.....	366	1,767	3.79	7.70	6,693
.....	.....do.....	345	1,579	3.59	7.30	5,672
.....	.....do.....	325	1,459	3.10	6.90	4,529
.....	.....do.....	156	398	1.39	3.30	533
1.....	.....do.....	197	407	2.22	3.90	905
er 27..	.....do.....	170	432	1.30	3.55	564

Daily gage height, in feet, of Arkansas River at Arkansas City, Kans., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	3.1	4.1	5.4	4.3	8.7	9.0	5.0	7.6	2.5	3.2
.....	3.1	4.0	5.6	4.2	9.0	9.3	5.3	7.0	2.4	3.1
.....	3.0	3.8	5.7	4.1	9.2	9.2	5.6	6.0	3.2	2.9
.....	3.0	3.7	5.8	4.2	8.3	8.5	7.0	5.5	2.2	2.9
.....	2.9	3.8	5.8	4.1	7.7	8.1	8.1	5.4	2.2	2.8
.....	2.8	3.8	5.7	4.0	7.3	7.8	7.4	5.3	2.1	2.8
.....	2.8	3.9	5.7	4.3	7.1	7.6	7.1	5.2	2.5	2.7
.....	2.9	4.1	5.7	4.8	6.8	7.1	7.1	5.1	3.0	2.7
.....	3.0	4.2	5.6	4.9	7.1	6.4	6.7	5.4	3.2	2.7
.....	3.1	3.9	5.6	5.7	7.2	6.2	5.7	5.3	4.0	2.7
.....	3.0	3.8	5.5	5.9	7.3	6.3	5.5	5.2	4.7	2.6
.....	3.0	3.9	5.1	5.8	6.7	6.2	5.0	5.1	4.1	2.6
.....	2.9	3.8	4.5	4.9	6.6	5.4	4.8	5.1	5.0	2.6
.....	2.9	3.8	4.6	4.5	6.5	6.5	4.7	4.8	5.2	2.6
.....	2.9	3.8	4.5	4.3	6.0	6.9	4.6	4.6	5.1	2.6
.....	2.8	3.7	4.4	4.3	5.8	6.3	4.5	4.5	4.8	2.5
.....	2.9	3.7	4.4	4.2	5.8	6.6	4.4	4.4	4.4	2.4
.....	2.9	3.6	4.3	4.2	5.9	7.0	4.2	4.3	4.8	2.5
.....	3.1	3.7	4.5	4.1	5.7	7.1	4.0	4.2	6.8	2.5
.....	3.3	3.7	4.6	4.0	5.7	7.2	3.1	4.1	6.6	2.5
.....	3.5	3.8	4.7	4.4	5.9	7.1	3.8	3.9	5.5	2.5
.....	3.6	3.7	4.6	4.2	6.0	7.0	3.7	3.7	5.2	2.5
.....	3.6	3.8	4.5	4.3	6.2	6.1	3.6	3.7	4.8	2.5
.....	3.7	3.8	4.5	4.3	7.5	6.9	3.6	3.6	4.3	2.5
.....	3.8	3.7	4.1	4.5	7.1	6.8	3.5	3.1	3.8	2.5
.....	3.8	5.1	4.4	4.8	8.4	6.0	3.4	3.0	3.7	2.6
.....	4.1	5.3	4.5	4.9	7.7	5.8	3.3	2.1	3.6	2.6
.....	4.2	5.3	4.4	5.0	7.7	5.6	3.1	2.9	3.5	2.7
.....	4.3	.....	4.3	5.9	7.2	5.3	3.0	2.8	3.4	3.6
.....	4.3	.....	4.4	8.8	7.6	5.2	5.0	2.7	3.3	2.5
.....	4.2	.....	4.3	.....	9.3	.....	7.7	2.6	.....	3.4

-River frozen January 1 to February 25, approximately.

Station rating table for Arkansas River at Arkansas City, Kans., from January 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.10	75	3.60	670	5.10	2,190	7.20	5,440
2.20	82	3.70	750	5.20	2,310	7.40	5,800
2.30	90	3.80	840	5.30	2,440	7.60	6,160
2.40	100	3.90	930	5.40	2,570	7.80	6,540
2.50	112	4.00	1,020	5.50	2,700	8.00	6,920
2.60	128	4.10	1,110	5.60	2,840	8.20	7,330
2.70	150	4.20	1,210	5.70	2,980	8.40	7,750
2.80	180	4.30	1,310	5.80	3,120	8.60	8,170
2.90	220	4.40	1,410	5.90	3,270	8.80	8,595
3.00	270	4.50	1,510	6.00	3,420	9.00	9,025
3.10	320	4.60	1,620	6.20	3,730	9.20	9,460
3.20	380	4.70	1,730	6.40	4,050	9.40	9,900
3.30	440	4.80	1,840	6.60	4,380	9.60	10,360
3.40	510	4.90	1,950	6.80	4,720		
3.50	590	5.00	2,070	7.00	5,080		

The above table is applicable only for open-channel conditions. It is based on seven discharge measurements made during 1905. It is fairly well defined between gage heights 3.3 feet and 8 feet. Above 8 feet this table is the same as table for 1904.

Estimated monthly discharge of Arkansas River at Arkansas City, Kans., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March	3,120	1,110	1,996	122,70
April	3,270	1,020	1,702	101,30
May	9,680	2,980	5,422	333,40
June	9,680	2,310	5,000	297,50
July	7,125	270	2,333	143,4
August	6,160	75	1,710	105,1
September	4,720	75	1,272	75,6
October	670	100	173	10,6
The period				1,190,0

NOTE.—No estimate for ice period.

SALT FORK OF ARKANSAS RIVER NEAR ALVA, OKLA.

This station was established September 10, 1903, by W. G. Russell, and was discontinue December 31, 1905 It is located at the railway bridge about one-half mile northeast o Alva, Okla.

The channel is curved for about 200 feet above and below the station. The current sluggish at low and swift at high stages. The bed of the stream is composed of clean san and is shifting. There are one or more channels at low water and one at high water, divide by piers and piles.

Discharge measurements are made from the upper side of the deck railway bridge, or b wading at low stages. This bridge is composed of 146 feet of pile approach at the sou end, four 80-foot steel girders resting on stone piers, and 652 feet of pile approach at t north end. The initial point for soundings is at the south end.

A standard chain gage is fastened to the upstream guard rail of the bridge; length chain 23.00 feet. There is also a gage painted on the fourth pier from the south end of t bridge. The sinking of the river bed may cause minus readings at very low water. Duri

;age was read once each day by James P. Richmond. The bench mark is the bot-
: coping stone on the north face of the fourth pier from the south end of the bridge;
8.00 feet above the datum of the gage.
iption of this station and gage height and discharge data are contained in Water-
ıper No. 131, United States Geological Survey, pages 144–145.

harge measurements of Salt Fork of Arkansas River near Alva, Okla., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
....	W. G. Russell	82	25	1.16	0.35	29
.....	J. M. Giles	20	5	.88	.20	4.4
.....	Earl Patterson	328	190	1.93	1.10	368
.....	.....do	22	7	.85	.30	6
....	.....do	.....	37	1.22	.80	45
....	J. M. Giles	.....	7.6	1.71	.55	13
21 ..	Earl Patterson	40	20	1.29	.50	26
.....	J. M. Giles	16	5	.64	.25	3
.....	Earl Patterson	16	5	.52	.20	2
25 ..	.....do	.....	74	1.25	.80	92
18 ..	.....do	37	18	1.09	.45	20

gage height, in feet, of Salt Fork of Arkansas River near Alva, Okla., for 1905.

.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	0.0	0.3	0.4	1.0	1.1	0.4	0.3	0.3	0.4
.....	.....	.1	.2	.4	3.3	.8	.3	.3	.4	.4
.....	.....	.4	.1	.4	3.0	.5	4.8	.3	.4	.4
.....	.....	.3	.1	.3	2.0	.4	2.8	.3	.4	.4
.....	.....	.2	.1	.2	1.0	.2	1.6	.3	1.1	.4
.....	.....	.1	.1	.2	.5	.0	1.3	.3	.7	.4
.....	.....	.1	.1	.2	.3	.6	.8	.3	.5	.4
.....	.....	.1	.1	.2	.3	.3	.5	.3	.4	.4
.....	.....	.1	1.0	.2	1.0	.3	.3	.3	.4	.4
.....	.....	.1	.7	.2	1.5	.3	2.2	.3	.4	.4
.....	.....	.1	.4	.2	.8	.3	1.1	.3	.5	.4
.....	0.3	.1	.3	.2	.8	.3	.9	.3	.4	.4
.....	.3	.1	.2	.2	.5	3.8	.8	.3	.4	.4
.....	.3	.1	.1	.2	.3	2.0	.8	.3	.4	.4
.....	.3	.1	.1	.2	.3	1.7	.6	.3	.4	.4
.....	.4	.1	.1	.2	.1	1.3	.6	.3	.4	.4
.....	.5	.1	.1	.2	.0	.9	1.5	.3	.4	.4
.....	.9	.1	.1	.1	.0	.4	1.9	.3	.4	.4
.....	.5	.1	.1	2.0	.0	.3	1.0	.3	.4	.4
.....	.5	.2	.1	1.5	.3	4.8	.8	.3	.4	.4
.....	.3	.1	.1	1.5	.3	2.8	.7	.3	.4	.4
.....	.2	.1	.1	1.0	.3	1.6	.6	.3	.4	.4
.....	.2	.1	.6	.7	.3	1.3	.5	.3	1.7	.4
.....	.2	.1	.6	.7	.3	1.0	.4	.3	1.3	.4
.....	.2	.1	.6	.6	.3	.9	.4	.4	.8	.4
.....	.2	.1	.4	.5	.3	.7	.3	.4	.7	.4
.....	.2	.1	.4	.4	.3	.7	.3	.3	.6	.4
.....	.1	.4	.4	.3	1.6	.7	.3	.3	.5	.4
.....	.0	.3	.4	.2	1.0	.7	.3	.3	.4	.4
.....	.0	.35	.4	.2	1.8	.7	.3	.3	.4	.4
.....	.0	.....	.4	.....	1.5	.4	.....	.3	.....	.4

SALT FORK OF ARKANSAS RIVER NEAR TONKAWA, OKLA.

This station was established September 18, 1903, by W. G. Russell. It is located at the highway bridge one-half mile south of Tonkawa, Okla.

The channel is straight for about 200 feet above and below the station. The current is sluggish at low and swift at high stages. The right bank is low, wooded, and subject to overflow. The left bank is high, wooded, and does not overflow. The bed of the stream is composed of clean sand and is shifting. There is but one channel at low and high stages, broken only by the pile bents supporting the bridge.

Discharge measurements are made from the downstream side of the bridge to which the gage is attached. The initial point for soundings is at the north end of the bridge.

The gage is a staff fastened vertically to the downstream pile of a bent 198 feet from the north end of the bridge. During 1905 the gage was read by T. J. Bird. The bench mark is the top of a nail driven into a 6-inch cottonwood tree about 40 feet east of the north end of the bridge; elevation, 10.50 feet above the datum of the gage.

A description of this station and gage height and discharge data are contained in Water-Supply Paper No. 131, United States Geological Survey, pp. 145–147.

Discharge measurements of Salt Fork of Arkansas River near Tonkawa, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 29	W. G. Russell	208	148	0.68	1.35	101
July 28	do	319	546	1.34	2.50	735
August 18	Earl Patterson	48	37	1.22	.80	45
August 30	J. M. Giles	16	8	1.71	.55	13
September 26	W. G. Russell	163	164	.90	1.45	147

ıge height, in feet, of Salt Fork of Arkansas River near Tonkawa, Okla., for 1905.

ıay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	1.4	1.5	2.3	1.5	1.3	1.6	1.7	2.1	0.9	1.2
.....	1.4	1.5	2.0	2.4	1.2	2.4	2.4	3.2	.9	1.2
.....	1.3	1.5	1.9	3.5	1.2	2.4	3.1	2.5	1.0	1.2
.....	1.3	1.5	1.8	2.7	1.3	2.0	2.8	2.1	1.8	1.3
.....	1.4	.9	1.8	2.0	1.3	1.9	2.9	1.9	1.8	1.3
.....	1.4	.9	1.8	1.9	1.3	1.8	2.2	1.8	2.0	1.2
.....	1.5	.9	1.9	1.8	1.3	1.9	1.9	1.6	2.4	1.2
.....	1.5	.9	1.9	1.7	1.3	1.9	1.9	1.6	5.4	1.2
.....	1.5	.9	2.2	1.6	1.4	2.0	1.8	1.4	4.2	1.2
.....	1.5	.9	2.5	1.5	1.7	1.9	2.3	1.6	3.8	1.2
.....	1.5	.9	2.0	1.5	1.3	1.6	2.6	1.6	3.1	1.2
.....	1.5	.9	1.9	1.5	1.1	1.4	1.9	1.6	2.8	1.2
.....	1.5	.9	1.8	1.5	1.4	1.4	1.8	2.2	2.8	1.2
.....	1.5	.9	1.9	1.5	1.8	1.3	1.8	7.8	2.7	1.2
.....	1.5	.9	1.9	1.5	1.6	1.3	1.6	5.8	2.4	1.2
.....	1.5	.9	1.8	1.5	1.3	1.3	1.5	4.5	2.0	1.2
.....	1.5	.9	1.9	1.5	1.3	1.3	1.4	3.9	1.7	1.2
.....	1.5	.9	2.2	1.6	1.3	1.2	1.3	3.0	1.7	1.2
.....	1.5	.9	2.8	1.5	1.3	1.2	1.2	2.3	1.7	1.2
.....	1.5	1.2	1.8	1.5	1.3	1.2	1.2	2.6	1.5	1.2
.....	1.5	1.6	1.5	1.4	1.3	1.2	1.6	2.6	1.6	1.2
.....	1.5	2.1	1.7	1.3	1.3	3.9	1.3	2.6	1.5	1.3
.....	1.5	2.6	2.0	1.2	1.3	2.9	3.0	2.9	1.4	1.2
.....	1.5	2.8	1.9	1.2	1.3	2.8	4.0	3.0	1.2	1.2
.....	1.5	2.6	1.8	1.3	1.3	2.6	4.3	2.6	1.0	1.2
.....	1.5	2.6	1.6	1.3	1.3	1.2	3.0	2.0	1.0	1.2
.....	1.5	2.4	1.6	1.3	2.8	1.9	2.8	1.9	1.2	1.2
.....	1.5	2.3	1.6	1.2	2.6	1.6	2.5	1.8	1.2	1.3
.....	1.5	.....	1.5	1.2	2.6	1.5	2.0	1.6	1.2	1.2
.....	1.5	.....	1.5	1.3	2.6	1.7	1.9	1.0	1.2	1.3
.....	1.5	.....	1.5	.....	2.4	.....	1.9	1.0	.....	1.4

PURGATORY RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

ıtory River, a characteristic stream of eastern Colorado, is the principal tributary of ıs River in Colorado. It rises in the Culebra Mountains and flows northeastward he plains for a distance of 165 miles. In the spring the channel carries a moderate of water, but as summer approaches this is greatly diminished by irrigation and conditions until the channel is practically dry. The volume of water contributed Arkansas is so small that it has no appreciable effect on the discharge of that river times of excessive rainfall, when it may discharge a large volume for a short time. drainage basin of Purgatory River is long and narrow. The total area is 3,386 niles, of which 742 square miles, lying above Trinidad, are mountainous, the country ıade up of shales, sandstones, and igneous rocks. This area is much broken by us stream channels, which are normally dry. The lower basin is largely foothill , merging into rough plains farther east. Drainage lines are well defined through- area. For 60 miles of its length, commencing 25 miles below Trinidad, Purgatory ows in a deep canyon. There are numerous small tributary canyons at various o the main channel. The soil of this lower basin is largely detritus from decom- hales, sandstones, and similar soft sedimentary rocks. Erosion is still vigorous, r a storm the flood waters often contain in suspension as much as 10 per cent (by of silt.

In the mountainous portion the Weather Bureau records at Clearview for fifteen years give a mean annual rainfall of 23 inches; at Trinidad, ten years' record, 17 inches. The plains drainage has approximately a mean annual precipitation of 12 inches.

A characteristic feature of this stream is the occurrence of sudden and disastrous floods which take place irregularly and are the run-off of excessive precipitation. In the spring periodic floods occur from melting snow, which is often supplemented by spring rains. During these floods large areas of the stream bank are eroded. The most disastrous flood of record occurred October 1, 1904.

No storage is practiced on this stream, though investigations are being made by a corporation with the purpose of constructing a large storage reservoir for use in irrigation.

No power has been developed, and because of the abundance of coal in the vicinity of Trinidad it is doubtful if power development would be feasible, even under very favorable circumstances.

PURGATORY RIVER AT TRINIDAD, COLO.

This station was established May 1, 1896, at the Animas Street Bridge, the gage rod being attached to the cylindrical pier at the west end of the bridge. The station was, however, discontinued July 31, 1899, the greater portion of the water in the river being diverted above the gaging station; the channel was also shifting and results not satisfactory. July 25, 1905, the Trinidad station was reestablished, at the old location on the Animas Street Bridge, by R. I. Meeker. The reestablishment was for the purpose of collecting general hydrographic data, especially flood data.

The river channel is irregular in course at low water, but is generally straight above the bridge for a distance of a few hundred feet. Below, the channel is straight for a distance of 100 feet. The stream bed is composed of a loose deposit of cobblestones, graduating into coarse gravel and sand, and is more or less shifting. The left bank is a loose riprap stone above the bridge, with piling below. The right bank consists of the riprap embankments of the Colorado and Southern Railway, and will overflow at extreme high water. There is usually but one channel at all stages. Velocity at low stages is sluggish, increasing to swift velocities during high stages.

Discharge measurements are made from the downstream footway. A standard chain gage is attached to the upstream footway of the bridge; length of chain, 22.52 feet. The gage scale reads from 0 to 10 feet, the chain having two markers, giving a range of 20 feet in gage heights. During 1905 the gage was read twice each day by Perry Foote. The bench mark is a cross cut within a circle on the porch of the house at No. 312 Nevada Avenue, about 3 feet north of the Animas Street Bridge; elevation, 14.99 feet above the datum of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Reports; WS=Water-Supply Papers):

Description: Ann 18, iv, pp 231-232; WS 16, p 123; 28, p 108; 37, p. 263.
Discharge: Ann 18, iv, p 232; WS 16, p 123; 28, p 116; 37 p 263.
Discharge, monthly: Ann 19, iv, p 359; 20, iv, pp 329, 341; 21, iv, p 235.
Discharge, yearly: Ann 20, iv, p 57.
Gage heights: WS 11, p 61; 16, p 123; 28, p 113; 37, p 263.
Hydrograph: Ann 19, iv, p 360; 20, iv, p 341; 21, iv, p 236.
Rainfall and run-off relation: Ann 20, iv, p 330.
Rating tables: Ann 19, iv, p 358; WS 28, p 117; 39, p 450.

Discharge measurements of Purgatory River at Trinidad, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharg
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Secon feet.*
March 25	R. I. Meeker	45	62	2.29	.....	
August 25	.....do	43	126	2.83	5.65	
August 26	.....do	35	73	1.97	5.10	
November 4	.....do	25	18	1.22	4.67	

Daily gage height, in feet, of Purgatory River at Trinidad, Colo., for 1905.

Day.	Aug.	Sept.	Oct.	Nov.	Dec.	Day.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	5.05	4.52	4.65	5.0	17	.....	4.55	4.65	4.7	5.0
2	.....	4.75	4.58	4.75	5.0	18	.....	4.62	4.6	4.7	5.2
3	.....	4.7	4.6	4.72	5.0	19	.....	4.68	4.55	4.7	5.2
4	.....	5.35	4.55	4.7	4.9	20	.....	4.65	4.6	4.7	5.0
5	.....	4.7	4.58	4.7	4.9	21	.....	4.6	4.58	4.7	5.0
6	.....	5.0	4.6	4.7	4.9	22	.....	4.6	4.55	4.85	5.1
7	.....	5.1	4.52	4.65	4.9	23	.....	4.58	4.58	4.85	5.2
8	.....	4.88	4.5	4.52	4.95	24	.....	4.5	4.68	4.7	5.2
9	.....	4.95	4.6	4.72	5.0	25	.....	4.58	4.6	4.7	5.2
10	.....	4.92	4.52	4.7	5.0	26	5.05	4.6	4.62	4.7	5.2
11	.....	4.78	4.68	4.7	5.0	27	4.9	4.7	4.6	4.7	5.2
12	.....	4.72	4.6	4.7	5.0	28	4.95	4.7	4.65	4.9	5.2
13	.....	4.68	4.6	4.7	4.88	29	4.8	4.55	4.65	4.7	5.2
14	.....	4.62	4.6	4.7	4.88	30	4.85	4.58	4.65	4.7	5.2
15	.....	4.6	4.6	4.7	5.0	31	4.8	.....	4.65	.....	5.2
16	.....	4.58	4.58	4.7	5.3						

Station rating table for Purgatory River at Trinidad, Colo., from August 27 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.50	11	4.90	81	5.30	215	5.70	375
4.60	17	5.00	111	5.40	253	5.80	421
4.70	31	5.10	144	5.50	293	5.90	468
4.80	55	5.20	179	5.60	333		

The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during 1905. It is fairly well defined.

Estimated monthly discharge of Purgatory River at Trinidad, Colo., for 1905.

[Drainage area, 742 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
August 26-31	128	55	80.5	958	0.108	0.024
September	234	11	47.3	2,815	.064	.071
October	28	11	17.7	1,088	.024	.028
November	68	12	34.8	2,071	.047	.052
December	215	76	133	8,178	.179	.206
The period	.....	.....	.....	15,110	.....	.....

PURGATORY RIVER NEAR ALFALFA, COLO.

This station was established March 23, 1905, by R. I. Meeker. It is located one-eighth of a mile below the canyon entrance, 4 miles east of Alfalfa post-office, and about 25 miles east of Trinidad, in T. 33 S., R. 60 W.

The channel is straight for 200 feet above and below the cable, and is composed primarily of large fragments of sandstone; on top of these and along the sides of the channel is a

shifting bed of sand, which is deposited at low water and reaches a depth of at least 2 above gage height 7 feet this deposit is usually scoured out. The current of Purg River is very swift and beds of sand are rapidly deposited and scoured out during a y time. The right bank, which is the canyon side, is a talus slope composed largely of ments of sandstone from the vertical wall above, the interstices and intervening stre being filled by a deposit of sand. The left bank is of sand, about 8 feet high, gradually ing into the talus above. Above the talus slopes on either side the canyon walls are ve for 75 feet. Except at very low water there is more or less boiling of the current, w interferes during measurements. At high water the velocity is swift.

Discharge measurements are made by means of a cable, car, stay wire, and tagged The initial point for soundings is the zero mark of the tagged line at the right bank, the face of the large bowlder to which the cable is anchored. At low water, discharge r urements are often made by wading.

The permanent gage is an inclined staff bolted to a large sandstone bowlder on the bank of the stream, 15 feet below the cable. From 10 to 20 feet the gage consists of a tical staff bolted to an immense bowlder to which the righthand end of the cable i chored. After the high water of 1905 the channel filled in with sand so that the little that was in the river flowed along the left bank. August 7 a temporary rod was establ on the left bank at the same datum as the permanent gage. This rod is a staff driven cally into the river bed at left bank. During 1905 the gage was read once each day d ordinary and twice or more during varying stages, by Leigh Bull. The bench mar dash cut in the bowlder to which the vertical portion of the original rod is attached; e tion, 10.00 feet above the datum of the gage.

Discharge measurements of Purgatory River near Alfalfa, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D ch
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Sec f*
March 24	R. I. Meeker	83	90	2.51	4.85	
March 28	L. D. Bull	83	100	1.80	4.40	
April 17	do	83	130	2.46	5.20	
April 25	do	85	328	3.86	7.35	1,
May 4	do	95	194	3.78	6.35	
May 17	do	85	100	3.68	5.10	
May 21	do	90	140	4.04	6.05	
May 29	do	90	120	3.25	5.25	
June 11	do	90	110	3.65	5.50	
July 23	do	90	150	4.35	6.28	
August 3	do	96	110	4.34	5.80	
August 7	R. I. Meeker	37	53	2.74	4.00	
August 8	L. D. Bull	36	47	2.55	3.80	
August 12	do	43	56	2.62	4.00	
August 19	do	30	11.3	.85	2.65	
August 25	do	94	170	5.08	6.80	
September 2	do	75	52	1.86	3.88	
September 8	do	68	46	1.89	3.55	
September 21	do	28	8.7	.78	2.60	
October 11	do	28	7.2	.53	2.55	
November 26	do	22	6	.83	2.55	
December 3	do	26	15	1.07	2.80	
December 14	do	26	24	.88	3.20	

Daily gage height, in feet, of Purgatory River near Alfalfa, Colo., for 1905.

r.	Mar.	Apr.	May.	June.	July	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	7.2	7.5	5.5	2.75	4.0	3.95	2.65	2.45	2.8
.....	.....	5.66	7.3	5.4	2.6	5.0	3.9	2.65	2.45	2.8
.....	.....	5.45	6.8	5.3	2.5	6.1	3.7	2.6	2.45	2.8
.....	.....	6.24	6.4	5.3	2.4	3.8	3.35	2.6	2.45	2.8
.....	.....	5.9	5.85	5.75	2.3	3.9	3.5	2.6	2.45	2.8
.....	.....	6.6	5.4	5.6	2.2	3.9	5.1	2.6	2.45	2.75
.....	.....	6.6	5.25	5.5	2.1	3.9	4.2	2.55	2.4	2.75
.....	.....	6.45	5.3	6.0	2.15	3.8	3.8	2.55	2.45	3.1
.....	.....	6.55	5.1	5.8	2.0	3.7	3.35	2.55	2.45	3.2
.....	.....	6.3	5.6	5.4	1.9	3.65	3.15	2.55	2.45	3.0
.....	.....	6.0	5.2	5.5	1.95	3.5	3.05	2.55	2.45	3.0
.....	.....	5.8	4.85	5.4	1.9	4.0	2.9	2.55	2.45	3.0
.....	.....	5.55	4.8	5.3	1.8	3.85	2.7	2.55	2.45	3.2
.....	.....	5.55	5.1	5.1	1.7	3.55	2.7	2.55	2.45	3.2
.....	.....	5.6	5.1	4.9	1.6	3.4	2.65	2.55	2.45	3.2
.....	.....	5.5	5.1	4.7	1.5	3.3	2.65	2.55	2.45	3.1
.....	.....	5.2	5.2	4.6	1.55	3.0	2.6	2.55	2.45	3.15
.....	.....	5.2	5.25	4.25	1.6	2.8	3.75	2.55	2.45	3.1
.....	.....	5.35	5.2	4.1	1.65	2.65	2.75	2.55	2.45	3.1
.....	.....	5.5	5.8	4.0	1.65	2.55	2.65	2.55	2.45	3.1
.....	.....	5.0	6.1	3.9	1.7	2.5	2.65	2.55	2.4	3.05
.....	5.8	4.8	5.9	3.9	6.2	2.45	2.6	2.55	2.4	3.05
.....	5.25	4.9	9.0	3.85	4.8	2.4	2.6	2.55	3.4	3.1
.....	5.1	8.08	5.9	3.75	4.0	2.35	2.6	3.1	3.1	.....
.....	4.7	7.96	5.6	3.7	3.1	12.9	2.6	2.8	3.0	.....
.....	4.5	9.72	5.45	3.6	3.2	5.5	3.8	2.65	2.7	.....
.....	4.45	11.01	5.4	3.4	2.9	4.2	3.1	2.55	2.5	.....
.....	4.4	10.35	5.3	3.15	2.6	4.0	2.9	2.5	2.5	.....
.....	4.15	8.6	5.25	2.95	2.4	3.8	2.8	2.5	2.5	.....
.....	4.0	7.7	5.25	2.85	3.2	4.5	2.75	2.45	2.8	.....
.....	3.8	.....	5.3	.....	5.3	4.0	.....	2.45	.....	3.2

Station rating table for Purgatory River near Alfalfa, Colo., from March 22 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.50	0	3.10	37	4.70	228	7.60	1,250
1.60	1	3.20	45	4.80	244	7.80	1,360
1.70	1	3.30	53	4.90	261	8.00	1,480
1.80	1	3.40	62	5.00	280	8.20	1,600
1.90	2	3.50	72	5.20	322	8.40	1,730
2.00	2	3.60	82	5.40	369	8.60	1,860
2.10	3	3.70	93	5.60	421	8.80	2,000
2.20	4	3.80	105	5.80	479	9.00	2,140
2.30	5	3.90	117	6.00	545	9.50	2,505
2.40	6	4.00	130	6.20	618	10.00	2,900
2.50	8	4.10	143	6.40	695	10.50	3,330
2.60	11	4.20	156	6.60	778	11.00	3,780
2.70	15	4.30	170	6.80	865	11.50	4,250
2.80	19	4.40	184	7.00	955	12.00	4,730
2.90	24	4.50	198	7.20	1,045	12.50	5,220
3.00	30	4.60	213	7.40	1,145		

The above table is applicable only for open-channel conditions. It is based on 18 discharge measurements made during 1905. It is well defined between gage heights 2.5 feet and 7 feet. Below 2.5 feet the table is very uncertain.

Estimated monthly discharge of Purgatory River near Alfalfa, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March 22 to 31	479	105	230	4,[illegible]
April	3,780	244	911	54,[illegible]
May	2,140	244	502	30,[illegible]
June	545	22	248	14,[illegible]
July	618	0	50.9	3,[illegible]
August	5,630	6	29.3	18,[illegible]
September	300	11	54.6	3,[illegible]
October	37	7	11.3	[illegible]
November	62	6	11.3	672
December 1-23, 31	45	17	32.3	1,536
The period				131,700

CIMARRON RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Cimarron River rises in the Raton Mountain Range in Colfax County, N. Mex., at an elevation of nearly 7,000 feet, and flows eastward across Beaver County, in Oklahoma, then across the southwest corner of Kansas, entering Oklahoma again in Woodward County, and following a southeasterly course to its junction with Arkansas River at the Indian Territory line. The basin lies between those of Arkansas and North Canadian rivers, and is within the arid belt. From west to east it is 190 miles from the source to the [illegible] station at Arkalon, Kans., and 450 miles to its mouth; its extreme width is not mo[illegible] the basin is 5,200 square miles. The elevation at Arkalon [illegible] ence of elevation from the source of the river occurs in Ne[illegible]

The upper course of the Cimarron is entirely in a mountainous and hilly region, very precipitous, rocky, and impervious. In this portion there are no tributaries of any size, and the river seldom receives much water from melting snows. As it approaches Kansas the bottoms are sandy and porous, and, while the adjacent land is hilly, the soil is generally a black loam covered with buffalo grass. There is considerable timber along all the streams in New Mexico and northwestern Oklahoma, but very little in Kansas. The rainfall is very light, being about 12 inches in New Mexico and Oklahoma and increasing to 20 inches at Arkalon. Floods are rare and have no regular periods of occurrence. There are no lakes or marshes in this drainage basin, except small areas here and there along the river bottoms. The land is but little cultivated, forage being the principal product. There are few springs along Cimarron River below the Kansas line and underground water is at depths of from 50 to 150 feet. Some irrigation is practiced by private parties in New Mexico and Oklahoma, but none in Kansas. There is no water for power development in this basin.

CIMARRON RIVER NEAR KENTON, OKLA.

This station was established April 5, 1904, by W. G. Russell, and was discontinued July 31, 1905. It was located at the highway crossing on the main road, one-half mile north of Kenton, Okla.

The channel is very narrow and crooked, and the current is sluggish. Both banks are low, wooded, and subject to overflow. The bed of the stream is muddy, but too narrow to shift much. There is only one channel at low or medium stages, but there may be two at high stages.

Discharge measurements are made at low water by wading near the gage. At high stages discharges must be computed from the cross section and slope. The initial point for soundings is on the right bank of the stream.

There are two gages. The first is a staff driven vertically into the bed of the stream and fastened to posts driven into the ground. The second gage is in two sections, the first being the same as gage No. 1 and located 70 feet southwest of it. The second section is fastened to a cedar post 100 feet east of the first gage. During 1905 the gage was read by L. A. Wikoff. The bench mark is the top of three nails driven into the west side of an 18-inch willow tree standing 100 feet southwest of the first gage; elevation 8.15 feet above the datum of the gage.

A description of this station and gage height and discharge data are contained in Water-Supply Paper No. 131, United States Geological Survey, pp. 147–148, 181.

Discharge measurements of Cimarron River near Kenton, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
June 10	J. M. Giles	18	52	0.95	1.10	49
June 11	do	18	46	.59	.80	27
June 11	do	18	47	.65	.90	31
June 12	do	18	45	.53	.70	24

Daily gage height, in feet, of Cimarron River near Kenton, Okla., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	Ju
1	0.8	0.8	0.9	2.4	1.4	0.9	
2	.9	.8	.8	1.9	1.2	1.5	
3	.9	.8	.8	1.1	1.0	.9	
4	.9	.8	.8	1.0	.9	.7	
5	.9	.8	.8	.8	.8	.4	
6	.9	.8	.9	.8	.8	.4	
7	.9	.8	.9	.8	.8	.5	
8	.9	.8	.9	.8	.7	4.5	
9	.8	.8	.7	1.4	.7	1.1	
10	.8	.8	.7	1.6	.7	1.1	
11	.8	.8	.7	1.4	.7	.8	
12	.9	.8	.7	1.1	.7	.7	
13	.9	.8	.7	1.0	.7	.7	
14	.9	.8	.7	.9	.6	.7	
15	.9	.8	.7	.9	.6	.7	
16	.8	.8	.8	.8	.6	.6	
17	.9	.8	.8	.8	.5	.5	
18	.9	.5	.7	.8	.7	.5	
19	.9	.6	.7	.8	.5	.5	
20	1.0	.8	.7	.8	.5	.4	
21	.9	.8	.7	.8	2.1	.4	
22	.9	.8	.7	.8	.9	.3	
23	.8	.8	.7	1.6	4.8	.2	
23	.8	.8	.7	5.8	1.1	.2	
25	.8	.8	.7	4.8	1.1	.1	
26	.9	.7	.7	1.4	2.9	.1	
27	.9	.9	.7	3.4	4.3	.0	
28	.8	.9	.7	3.5	2.3	.0	
29	.8	.....	.7	2.3	1.4	.0	
30	.8	.....	.7	1.7	.....	.1	
31	.8	.....	.7	.....	.9	.....	

CIMARRON RIVER NEAR GARRETT, OKLA.

This station was established May 8, 1905. It is located at Strong's ranch, about 3 m west of Garrett, Okla., 20 miles east of Kenton, and 50 miles by stage from Clayton, N. M the nearest railroad station. The station is below the mouth of North Carriso and So Carriso creeks and 1 mile below the site of the proposed dam for a storage reservoir.

The channel is straight for 100 feet above and 300 feet below the gage. The curren swift. Both banks are about 6 feet high and subject to overflow. The bed of the strea composed of rocks and is permanent. There is but one channel at all stages.

Discharge measurements are made by wading near the gage at low water and from a ca one-half mile below the gage at high water. The initial point for soundings is the post s porting the cable on the right bank.

A vertical staff gage is fastened to a cottonwood tree on the left bank, about one-half m east of the ranch house. During 1905 the gage was read once each day by R. L. Stro Bench marks were established as follows: (1) A nail in a cross cut in a sandstone ledge the foot of the hill south of the river, about 50 feet upstream from the gage; elevati 16.30 feet. (2) A nail in the root of a cottonwood tree about 25 feet north of the ga elevation, 7.12 feet. Elevations refer to the datum of the gage.

Discharge measurements of Cimarron River near Garrett, Okla., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. W. Schlecht	24	41	1.00	1.30	41
.....	J. M. Giles	24	28	2.39	1.52	68
.....	....do	24	32	2.08	1.50	67
.....	....do	23	34	1.58	1.40	53
.....	....do	23	33	1.59	1.40	52
.....	....do	24	40	1.98	1.69	80
.....	....do	24	42	2.17	1.79	91
.....	....do	14	12.5	1.80	.90	22
.....	....do	14	12	1.38	.80	17
r 26..	E. Patterson	.....	8	1.46	.75	11.7
r 27..	....do	.....	8.5	1.15	.73	10.7
r 28..	....do	.....	8.1	1.20	.71	9.7
r 14..	....do	.....	11	1.47	.85	16
	J. M. Giles	.....	8.1	3.68	3.50	298
	....do	.....	19.7	5.49	6.50	1,082

[a] Computed from slope measurement, using Kutter's formula.

Daily gage height, in feet, of Cimarron River near Garrett, Okla., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	1.55	0.8	0.6	0.55	0.6	0.8	0.9
.....	.....	2.65	2.25	6.1	.55	.65	.8	.9
.....	.....	1.6	.95	4.3	.5	.65	.85	.9
.....	.....	1.45	.8	1.8	1.1	.65	.9	.85
.....	.....	1.25	.8	1.4	.75	.65	.8	.85
.....	.....	1.2	.75	.95	2.5	.65	.8	.85
.....	1.3	1.15	.75	6.5	1.55	.65	.8	.85
.....	1.3	9.3	1.95	4.55	3.95	.65	.85	.85
.....	1.2	2.8	1.0	1.55	4.6	.65	.85	.85
.....	1.15	2.1	.8	1.2	5.3	.65	.85	.85
.....	1.1	1.8	.7	.95	2.0	.65	.85	.65
.....	1.1	1.5	.65	1.0	1.3	.65	85	.65
.....	1.05	1.4	.65	3.3	1.0	.7	.85	.65
.....	1.05	1.5	.65	1.4	.9	.7	.85	.65
.....	1.1	1.35	.6	1.1	.9	.7	.85	.65
.....	1.1	1.15	.8	1.0	.85	.7	.85	.7
.....	1.1	1.2	.8	.9	.85	.7	.85	.85
.....	1.05	1.1	.6	.85	.85	.7	.85	.9
.....	1.0	1.05	.55	.8	.85	.7	.85	.9
.....	1.0	1.0	.5	.8	.8	.75	.85	.9
.....	1.05	1.0	.55	.95	.8	.75	.85	.9
.....	4.45	.9	.7	.75	.75	.75	.95	.85
.....	10.35	.9	2.0	.7	.75	.75	1.5	.85
.....	3.4	.85	1.0	.65	.75	.75	1.3	.8
.....	1.95	.85	.85	.6	.7	.8	1.0	.8
.....	2.55	.8	.8	.6	.8	.8	1.0	.85
.....	7.8	.8	.65	.6	.7	.8	.95	.9
.....	3.42	.8	1.0	.55	.7	.8	.9	.9
.....	2.55	.8	.9	.55	.65	.8	.9	.9
.....	1.75	1.1	.7	.55	.65	.8	.9	.85
.....	1.6	.....	.65	.55	.....	.8	.....	.85

Station rating table for Cimarron River near Garrett, Okla., from May 7 to December 31, 19

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.70	10	1.80	87	2.90	205	4.00	385
0.80	14	1.90	96	3.00	220	4.20	422
0.90	19	2.00	105	3.10	235	4.40	461
1.00	25	2.10	114	3.20	251	4.60	503
1.10	31	2.20	124	3.30	267	4.80	548
1.20	38	2.30	134	3.40	283	5.00	595
1.30	46	2.40	144	3.50	299	5.20	646
1.40	54	2.50	155	3.60	316	5.40	701
1.50	62	2.60	166	3.70	333	5.60	760
1.60	70	2.70	178	3.80	350	5.80	823
1.70	78	2.80	191	3.90	367	6.00	890

The above table is applicable only for open-channel conditions. It is based on fifteen discharge measurements made during 1905. It is well defined between gage heights 0.7 foot and 1.8 feet. Above 1.8 the table is based on computations from two slope measurements, using Kutter's formula. This extension can be considered only roughly approximate.

Estimated monthly discharge of Cimarron River near Garrett, Okla., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet
	Maximum.	Minimum.	Mean.	
May (23 days)	.....	25	91.0	4,1
June (29 days)	.....	14	49.6	2,9
July	129	5	22.2	1,3
August (30 days)	.....	6	90.5	5,5
September	673	5	74.4	4,4
October	14	7	10.4	6
November	62	14	19.5	1,1
December	19	8	15.4	9
The period	.....	.....	.....	20,9

NOTE.—On the days missing the discharge was above the limit of the rating table.

CIMARRON RIVER AT ARKALON, KANS.

This station was established August 15, 1903, by W. G. Russell, and was discontinued October 31, 1905. It is located at the Chicago, Rock Island and Pacific Railway bridge about one-half mile north of Arkalon, Kans.

The channel is straight for about 100 feet above and below the station. The current is sluggish at low and swift at high stages. Both banks are low and liable to overflow. The railroad embankment is high at each end of the bridge, forcing the water to pass beneath the bridge at all stages. There is but one channel, which is shallow except at high water. The piles of the bridge and drift may at times affect the measurements.

Discharge measurements are made from the bridge, but can be made at low water by wading. The initial point for soundings is the end of the bridge at the right bank of the river.

The original gage is a staff fastened to the fifth pile bent from the south end of the bridge on the downstream side. Sand having collected at the foot of the gage April 17, 1905, a section reading from zero to 2 feet was fastened to the fourth bent on the downstream side. During 1905 the gage was read once each day by Miss Ethel Singer. Bench marks were

ed as follows: (1) The top of the cap at the east end of the second bent from the d of the bridge; elevation, 15.76 feet. (2) The top of two nails in the top of a pile feet from the southwest corner of the bridge, 6.5 feet from the west side of the rail; n, 17.22 feet. Elevations refer to the datum of the gage.

nation in regard to this station is contained in the following publications of the States Geological Survey (Ann=Annual Reports; Bull=Bulletin; WS=Water-Papers):

tion: Ann 18, iv, p 243; Bull 140, p 167; WS 99, p 247; 131, pp 148–149.
rge: Ann 18, iv, p 243; Bull 140, p 167; WS 99, p 247; 131, p 149.
rge, monthly: Ann 18, iv, p 244; Bull 140, p 167.
eights: Bull 140, p 167; WS 11, p 64; 99, p 227; 131, p 149
table: Ann 18, iv, p 244.

Discharge measurements of Cimarron River at Arkalon, Kans., in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. G. Russell.....	39	25	1.40	1.60	35
.....	.....do.....	28	16	1.37	1.30	22

Daily gage height, in feet, of Cimarron River at Arkalon, Kans., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	1.3	1.6	1.3	1.7	1.9	4.0	1.4	1.5	1.3	1.3
.....	1.3	1.7	1.3	1.5	1.9	3.8	1.4	1.3	1.3	1.3
.....	1.3	1.8	1.3	1.9	1.9	3.0	1.4	1.3	1.3	1.3
.....	1.3	1.9	1.3	1.9	1.9	2.6	1.4	1.3	1.5	1.3
.....	1.3	1.9	1.4	1.9	1.9	2.0	1.4	1.3	1.4	1.3
.....	1.3	1.9	1.4	1.9	1.9	1.6	1.4	1.3	1.3	1.3
.....	1.3	1.9	1.4	1.8	1.9	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.9	1.4	1.8	1.9	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.9	1.4	1.8	1.8	1.4	1.4	2.5	1.3	1.3
.....	1.3	1.9	1.4	1.8	1.8	4.6	1.4	2.7	1.6	1.3
.....	1.3	1.9	1.4	2.0	1.8	2.9	1.4	2.3	1.4	1.3
.....	1.3	1.9	1.4	1.8	1.8	2.6	1.4	1.7	1.3	1.3
.....	1.3	1.9	1.4	1.8	1.8	2.3	1.4	1.3	1.7	1.3
.....	1.3	1.2	1.4	1.7	1.8	2.0	1.4	1.3	1.4	1.3
.....	1.3	1.2	1.4	1.6	1.7	1.9	1.4	1.3	1.3	1.3
.....	1.3	1.3	1.4	1.5	1.7	1.6	1.4	1.3	1.7	1.3
.....	1.3	1.3	1.4	1.6	1.5	1.4	1.4	1.3	1.4	1.3
.....	1.3	1.3	1.4	1.6	1.4	1.4	1.5	1.3	1.3	1.3
.....	1.3	1.3	1.4	1.5	1.4	1.4	1.5	1.3	1.3	1.3
.....	1.3	1.3	1.4	1.5	1.4	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.6	1.4	1.5	1.4	1.4	1.4	1.3	1.3	1.3
.....	1.3	2.1	1.4	1.4	1.4	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.9	1.4	1.8	1.4	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.7	1.4	2.5	3.7	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.4	1.4	2.8	3.8	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.4	1.4	3.4	3.5	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.3	1.4	4.6	3.4	1.4	1.4	1.3	1.3	1.3
.....	1.3	1.3	1.4	3.0	3.6	1.4	1.4	1.3	1.3	1.3
.....	1.3	.....	1.4	1.9	4.2	1.4	1.4	1.3	1.3	1.3
.....	1.4	.....	1.4	1.9	4.7	1.4	1.5	1.3	1.3	1.3
.....	1.5	.....	1.4	.....	4.5	.....	1.5	1.3	.....	1.3

CIMARRON RIVER NEAR WAYNOKA, OKLA.

This station was established September 11, 1903, by W. G. Russell, and was discontinued December 31, 1905. It is located at the railway bridge 2½ miles southwest of Waynoka, Okla.

The channel is straight for 1,000 feet above and below the station. Both banks are liable to overflow at very high water. The bed is shifting quicksand. At low water there may be several channels. At high water there is one channel, broken by the bridge supports.

Discharge measurements are made from the railway bridge, which is supported on piles and has a total span of 2,158 feet, and by wading at low water. The initial point for soundings is the east end of the bridge.

The gage is a staff fastened to the east side of the eighth pile bent from the east end of the bridge. During 1905 the gage was read by M. J. Sunden. Bench marks were established as follows: (1) The top of the cap of the bench to which the gage is spiked; elevation 10.98 feet. (2) The northeast corner of the cap of the bent at the fill at the east end of the bridge on the downstream side; elevation, 10.09 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 246; 131, p 150.
Discharge: 131, p 150.
Gage heights: 99, p 246; 131, p 151.

Discharge measurements of Cimarron River near Waynoka, Okla., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Second-feet.*
May 1	W. G. Russell	1.90	905
June 7	J. M. Giles	.90	68
June 20	Earl Patterson	.95	99
June 21	do	1.40	318
July 20	do	.40	.2
August 18	do	1.10	93
August 28	do	.30	2.6
September 20	do	.90	40
October 21	J. M. Giles	.30	.2
October 26	Earl Patterson	.41	.4
November 26	do	1.50	258
December 19	do	1.05	75

Daily gage height, in feet, of Cimarron River near Waynoka, Okla., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.1	1.3	1.5	1.0	1.9	1.6	0.8	1.6	0.3	0.5	0.5	1.0
.....	1.1	1.3	1.4	1.0	1.8	1.5	2.4	1.5	.3	.5	.5	1.0
.....	1.2	1.3	1.4	1.0	1.7	1.5	3.0	1.0	.3	.5	.5	1.0
.....	1.2	1.3	1.3	1.0	1.6	1.3	3.0	.8	.3	.5	.5	1.0
.....	1.2	1.3	1.3	1.5	1.5	1.0	2.0	.6	.3	.5	.6	1.0
.....	1.2	1.3	1.3	1.5	1.5	.9	1.8	.5	.3	.5	.6	1.0
.....	1.2	1.3	1.3	1.5	1.5	.8	1.6	.5	.3	.5	1.0	1.0
.....	1.1	1.3	1.3	1.5	1.5	.8	1.3	.5	.6	.4	1.0	1.0
.....	1.1	1.3	2.0	1.5	1.4	.7	2.0	.5	.6	.4	1.0	1.0
.....	1.1	1.3	2.0	1.5	1.3	.7	1.8	.5	4.5	.4	1.0	1.0
.....	1.0	1.3	2.0	1.4	1.2	.6	1.5	.5	2.5	.4	1.0	1.0
.....	1.0	1.3	2.0	1.4	1.1	.5	1.2	.5	2.0	.4	1.0	1.0
.....	1.0	1.3	2.0	1.3	1.0	.5	1.0	2.4	1.8	.4	1.0	1.0
.....	1.0	1.3	2.0	1.3	1.0	.6	.8	2.0	1.5	.4	1.0	1.0
.....	1.0	1.3	2.0	1.3	1.0	.7	.5	1.9	1.3	.4	.9	1.0
.....	1.0	1.3	2.0	1.3	1.0	1.0	.3	1.5	1.0	.4	.9	1.0
.....	1.0	1.3	2.0	1.3	1.0	1.0	.4	1.2	1.0	.4	.9	1.0
.....	1.0	1.3	2.0	1.3	1.0	1.0	.4	1.0	1.0	.3	.9	1.0
.....	1.1	1.3	2.0	1.6	1.0	1.0	.4	1.0	.9	.3	.9	1.0
.....	1.2	1.3	1.8	1.6	1.0	1.0	.4	1.5	.8	.3	1.0	1.0
.....	1.3	1.3	1.6	1.5	1.0	1.2	.4	1.3	.7	.3	1.0	1.0
.....	1.3	1.4	1.5	1.5	1.0	1.3	2.3	1.2	.6	.3	1.0	1.0
.....	1.3	1.5	1.5	1.5	1.0	1.4	2.0	1.0	.6	.3	1.0	1.0
.....	1.3	1.9	1.4	1.5	1.0	1.5	1.8	.8	.6	.4	2.0	1.0
.....	1.3	1.9	1.4	2.2	1.0	1.0	1.6	.6	.6	.4	1.2	1.0
.....	1.3	1.6	1.4	2.2	2.0	1.4	1.5	.5	.6	.4	1.2	1.0
.....	1.3	1.5	1.3	2.2	2.0	1.3	1.4	.5	.6	.4	1.2	1.0
.....	1.3	1.5	1.2	2.0	2.0	1.2	2.5	.5	.6	.4	1.2	1.0
.....	1.3	.....	1.1	2.0	2.0	1.0	2.0	.5	.6	.4	1.1	1.0
.....	1.3	.....	1.0	1.9	2.0	.9	2.0	.4	.6	.4	1.1	1.0
.....	1.3	.....	1.0	.....	1.8	.....	1.8	.4	.....	.4	.....	1.0

VERDIGRIS RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

s drainage basin lies between those of Grand and Arkansas rivers, being entirely ı the humid belt. It has no mountain tributaries, but depends for its water supply ɔ precipitation within its area. Its catchment area extends east and west in Kansas ndian Territory a distance of 70 miles, and north and south 170 miles, giving it an ɔf 7,920 square miles at the gaging station at Catoosa, Ind. T. The main stream is d by springs and small tributaries in Chase County, Kans., about 100 miles east of the r of the State, at an elevation of 1,075 feet, and flows nearly due south into Arkansas just above its junction with Grand River, about 6 miles northeast of Muscogee. Its tion at the mouth is 513 feet above sea level. Its principal tributaries are Fall, Elk, Caney rivers, all of which enter from the west. Fall and Elk rivers drain southern as, and Caney River drains southern Kansas and part of Indian Territory.

is basin lies within the Coal Measures and is composed of porous and broken sandstones imestones, which are covered with a black, porous loam. This, with a precipitation of d 40 inches, gives large quantities of underground water at a medium depth. There rge belts of timber along this river and all its tributaries, increasing in size to the south, ɔ the forest covers all the bottom lands and a large part of the upland. The culti- l area in Kansas is about 59 per cent of the drainage area; in Indian Territory it is

much less. The general slope of the basin is small and the streams are very crooked, with much débris in the channels, causing a very low velocity. Any heavy rainfall of long duration gives a flood which covers all the low bottom lands. The bottom lands in Kansas are generally cultivated and suffer damage, but those in Indian Territory are not generally under cultivation, and the damage is not great. The extreme flood height at the gaging station at Catoosa, Ind. T., was 48.8 feet and at Independence, Kans., 36 feet. These floods are liable to occur at any time during spring, summer, or fall. A few small lakes or ponds lie along the lower course of Verdigris River, but they are not of great extent. There are no irrigation works, and only a few water-power sites for mills, and most of these are abandoned. Along the middle course of the Verdigris are many large gas and oil wells, this portion of the basin being in the gas and oil belt of Kansas.

VERDIGRIS RIVER NEAR INDEPENDENCE, KANS.

This station was established April 20, 1904, by M. C. Hinderlider, for the purpose of making flood observations. It is located at the highway bridge three-fourths of a mile northwest of Independence, Kans.

The channel is straight for one-fourth mile above and below the station. The current is swift. Both banks are high rock cliffs covered with trees. The left bank overflows during floods. The bed of the stream is composed of gravel and bed rock, and is permanent. There is but one channel, divided at higher stages by one stone pier.

Discharge measurements are made from the downstream side of the two-span bridge. The initial point for soundings is the south face of the north abutment.

A standard chain is attached to the upstream guard rail near the south end of the bridge. There were no gage heights during 1905. Bench marks were established as follows: (1) The top of the capstone on the upstream side of the main pier in the stream, marked "+U. S. B. M. No. 1;" elevation, 44.11 feet. (2) The top stone of the north abutment at the end of the bridge on the upstream side, marked "U. S. B. M. No. 2;" elevation, 42.69 feet. (3) The top of the stone step in the upstream wing of the north abutment, marked "U.S.B. M.No.3;" elevation, 38.00 feet. (4) The top of the stone in the upstream wing wall of the south abutment, marked "+U. S. B. M. No. 4;" elevation, 45.17 feet. Elevations refer to the datum of the gage.

A description of this station and gage height and discharge data are contained in Water-Supply Paper No. 131, United States Geological Survey, pages 151–152.

Discharge measurements of Verdigris River near Independence, Kans., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
June 16	W. G. Russell	134	689	3.71	7.35	2,555
June 16	do	137	765	3.67	7.80	2,809
July 26	do	45	84	1.56	2.40	131
August 22	do	97	276	3.16	4.20	872
September 28	do	98	263	3.36	3.90	884

VERDIGRIS RIVER NEAR CATOOSA, IND. T.

This station was established September 25, 1903, by W. G. Russell. It is located at the Frisco Railway bridge, 2 miles northeast of Catoosa, Ind. T.

The channel is straight for 200 feet above and below the bridge. The current is sluggish. Both banks are low, wooded, and subject to overflow, but all water passes beneath the bridge and its approaches. At low water there is one channel, and at high water the channel is broken by the stone piers in the pile supports of the bridge, making five channels. The gaging section is obstructed by broken piles, on which drift collects. During high water it is

e to get any but surface velocities, and much of the current out of the main chan-
very low velocity.

rge measurements are made from the single-span steel railway bridge and its ap-
The initial point for soundings is at the west end of the bridge, 338 feet from
of the gage scale.

dard chain gage is attached to the guard rail of the railway bridge. During 1905
was read by John L. Calloway. The bench mark is the top of the second stone
the west and upstream side of the bridge; elevation, 50.21 feet above the datum
ge.

ation in regard to this station is contained in the following Water-Supply Papers of
ed States Geological Survey:

tion: 99, p 260; 131, p 153.
ge: 131, p 153.
ights: 99, p 261; 131, p 154.

Discharge measurements of Verdigris River near Catoosa, Ind. T., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. G. Russell.....	192	1,213	3.20	8.90	3,881
.....	.....do.....	182	871	3.06	7.05	2,670
2....	.....do.....	143	290	1.12	3.90	326

Daily gage height, in feet, of Verdigris River near Catoosa, Ind. T., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	3.7	4.4	12.0	7.7	7.4	37.65	10.2	9.25	9.8	10.6	21.4	6.9
.....	3.7	4.4	10.1	7.0	7.4	27.4	11.0	9.1	9.3	10.05	16.9	6.5
.....	3.6	4.4	9.8	6.9	7.3	24.4	18.7	9.1	9.15	10.0	11.7	6.2
.....	3.5	4.4	8.0	6.8	7.1	25.6	8.75	9.1	8.2	9.2	7.5	6.0
.....	3.5	4.4	7.9	6.7	7.0	25.4	6.05	8.4	8.7	9.1	5.4	5.1
.....	3.5	4.4	7.9	6.6	11.8	25.2	11.25	8.4	9.15	9.0	18.9	5.8
.....	3.5	4.3	9.8	6.6	12.1	25.8	26.25	8.2	8.1	8.2	21.8	5.5
.....	3.5	4.2	31.2	6.6	8.1	16.3	29.1	8.2	9.7	7.4	25.0	5.3
.....	3.5	4.0	28.05	6.6	9.0	12.0	27.2	7.3	10.7	6.6	20.4	5.1
.....	3.6	4.0	24.0	6.9	8.7	9.4	19.2	7.3	11.15	5.7	15.2	5.1
.....	3.6	4.0	22.1	6.9	8.9	9.5	16.7	7.2	10.6	4.8	9.3	5.0
.....	3.7	4.0	18.2	6.5	8.9	8.1	11.25	7.2	10.1	3.9	6.8	5.0
.....	3.7	4.0	14.3	6.5	10.7	7.2	8.2	8.7	10.6	3.8	6.4	5.0
.....	3.8	4.0	12.1	8.2	12.4	6.9	8.1	12.1	10.3	3.4	6.5	5.0
.....	3.8	4.0	9.1	7.0	10.4	7.2	8.25	12.4	10.2	3.0	6.8	4.1
.....	3.8	4.0	8.0	7.0	9.0	7.9	.....	9.75	10.7	2.8	6.5	4.1
.....	3.8	4.0	8.9	7.0	8.5	9.3	13.7	7.15	10.1	2.4	5.2	4.9
.....	3.8	3.9	9.4	7.4	8.7	9.8	19.45	7.0	10.65	18.8	4.1	4.8
.....	3.9	3.9	32.15	7.8	8.7	10.1	20.85	6.3	10.3	15.5	4.8	4.6
.....	3.9	4.0	36.0	7.9	13.85	12.5	21.5	10.35	11.15	14.8	5.8	4.2
.....	3.9	4.4	27.8	7.9	11.9	12.0	20.15	20.75	10.15	7.8	5.8	4.4
.....	4.0	4.5	15.1	7.9	11.9	9.0	18.65	26.7	10.1	6.4	5.4	4.4
.....	4.1	5.2	10.0	7.8	10.8	8.2	19.2	28.25	10.15	5.5	5.3	4.4
.....	4.1	8.3	6.5	7.9	10.7	7.9	17.6	22.35	11.15	4.1	5.2	4.3
.....	4.1	18.4	6.4	7.9	10.8	7.5	16.1	18.85	11.1	7.7	5.1	4.8
.....	4.1	29.3	6.3	7.9	10.8	7.4	16.0	16.8	10.1	25.5	3.5	4.8
.....	4.0	24.0	6.0	8.0	11.4	7.2	15.05	14.2	10.2	18.6	7.9	4.8
.....	4.0	14.0	6.3	7.9	20.25	7.0	27.25	14.2	10.1	15.2	8.9	4.8
.....	4.0	.....	8.6	7.8	22.9	6.8	10.5	14.2	11.45	10.3	7.6	4.8
.....	4.3	.....	9.6	7.6	42.5	6.7	9.4	14.2	10.6	8.1	7.2	4.8
.....	4.4	.....	9.7	.....	42.5	.....	9.4	12.2	.....	10.2	.....	5.3

FALL RIVER AT FALL RIVER, KANS.

This station was established as a flood station, April 22, 1904, by M. C. Hinderlider. It i located at the highway bridge one-eighth mile north of Fall River, Kans.

The channel is straight for about 300 feet above and 500 feet below the station, and th current is sluggish at low stages and swift at high stages. The right bank is of loam, slopir gradually out for about 100 feet to sandstone cliffs from 10 to 15 feet high. The left bar slopes at an angle of about 45° to the height of the bridge floor. Both banks are timber and do not overflow except at extreme stages. The low ground on the left bank extendi outward from the northwest end of the bridge is overflowed at very high stages of the riv The bed of the stream is composed of loam and mud and is probably unstable.

Discharge measurements are made from the three-span bridge to which the gage is a tached. The initial point for soundings is the surface of the ground at the north side of t right abutment.

A standard chain gage is fastened to the downstream railing near the left end of the brid During 1905 the gage was read once daily, and hourly during dangerous rises in the strea by Jesse McDaniel. Bench marks were established as follows: (1) The top of the sou masonry abutment on the downstream side; elevation, 41.768 feet. (2) On the sandsto ledge at the foot of the northeast corner of the south abutment; elevation, 33.777 feet. (The top of the first pier from the right bank, downstream side; elevation, 41.03 feet. (The top of the second pier from the right bank, downstream side; elevation, 40.08 feet. E vations refer to the datum of the gage.

A description of this station and gage height and discharge data are contained in Wa Supply Paper No. 131, United States Geological Survey, pages 154–155.

Discharge measurements of Fall River at Fall River, Kans., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di cha
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Sec fe*
May 31	W. G. Russell	95	229	0.71	3.20	
September 29	do	92	196	.46	2.90	

Daily gage height, in feet, of Fall River at Fall River, Kans., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.
.....	2.2	2.0	3.2	2.4	2.4	3.4	3.8	3.0	2.0
.....	2.1	2.0	3.0	2.4	2.4	3.6	4.0	3.0	2.0
.....	2.1	2.0	3.0	2.9	2.4	6.8	17.5	3.0	2.0
.....	2.0	2.0	2.8	2.6	2.4	4.0	7.5	2.9	2.0
.....	2.0	2.0	2.6	2.6	2.4	3.6	5.75	2.8	2.0
.....	2.0	2.0	2.4	2.4	2.4	3.6	5.4	2.7	2.0
.....	2.0	2.0	2.4	2.4	2.4	3.6	5.0	2.6	2.0
.....	2.0	2.0	2.3	2.4	2.4	3.5	4.7	2.5	2.0
.....	2.0	2.0	2.3	2.4	2.4	3.5	5.6	2.5	2.0
.....	2.0	2.0	2.3	2.4	2.4	3.2	5.0	2.5	2.0
.....	2.0	2.0	2.2	2.4	2.4	3.2	4.6	2.4	2.0
.....	2.0	2.0	2.1	2.4	2.4	3.2	4.1	2.4	2.0
.....	2.0	2.0	2.1	2.4	2.4	3.2	3.75	2.4	2.0
.....	2.0	2.0	2.1	2.4	2.4	3.0	3.6	2.3	2.4
.....	2.0	2.0	2.1	2.4	2.4	3.0	3.6	2.3	3.0
.....	2.0	2.0	2.1	2.4	2.4	11.3	3.6	2.3	3.0
.....	2.0	2.0	2.1	2.4	2.4	8.0	3.55	2.3	28.0
.....	2.0	2.0	2.8	2.3	2.4	6.0	3.6	2.3	16.0
.....	2.0	2.0	2.6	2.3	2.4	4.0	3.5	2.2	18.25
.....	2.0	2.0	2.4	2.3	2.4	3.6	3.5	2.2	7.1
.....	2.0	2.8	2.4	2.3	2.4	3.6	3.5	2.2	5.25
.....	2.0	3.6	2.8	2.3	2.4	3.6	3.5	2.2	4.25
.....	2.0	4.6	2.6	2.8	2.4	3.6	3.4	2.1	3.7
.....	2.0	4.0	2.4	2.8	2.4	3.6	3.3	2.1	3.4
.....	2.0	3.5	2.4	2.6	2.4	3.6	3.2	2.0	3.8
.....	2.0	3.5	2.4	2.4	2.4	3.6	3.2	2.0	3.1
.....	2.0	3.2	2.3	2.4	2.6	3.5	3.0	2.0	3.0
.....	2.0	3.0	2.2	2.4	2.8	3.5	2.9	2.0	3.0
.....	2.0	.....	2.2	2.4	4.0	3.6	2.8	2.0	3.0
.....	2.0	.....	2.4	2.4	6.0	3.6	3.0	2.0	3.0
.....	2.0	.....	2.4	.....	3.2	.....	3.0	2.0	.....

NEOSHO RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

ver rises in central Kansas, flows to the east and southeast, draining eastern ıtern Kansas, and then flows southward into Arkansas River just below Fort T. Its drainage basin lies between those of Kansas and Osage rivers on the st, and of Arkansas and Verdigris rivers on the south and west, being entirely ımid belt and east of the Great Plains. The drainage basin extends east and ntral Kansas to western Missouri, about 200 miles, and north and south into tory about the same distance, giving an area of 12,660 square miles. The many small tributaries, and flows through a rich agricultural country. It tain tributaries, but depends on the precipitation within its basin for its water

course of Neosho River lies in the Permian and upper Coal Measures, which ıys, and broken limestones, the overlying soil being a loose, porous loam. The r rolling and hilly, except along the streams, which have a large percentage of

The elevation at the headwaters is about 1,230 feet and at Wyandotte about ıe precipitation within this part of the basin is 30 to 35 inches per annum. The e lies in the upper Coal Measures, except for a short distance in the lower part, nds into the lower Coal Measures. In this stretch the formation is principally

a broken limestone, overlain by a porous loam. The lower course of the river lies in the lower Coal Measures, most of the rocks being limestones, somewhat broken, with an overlying soil of black porous loam, which permits the water to percolate through into the lower strata. This gives plenty of underground water, and many springs. The Neosho above the mouth of Spring River flows through the large oil and gas belts of Kansas. The precipitation in the middle and lower courses ranges from 35 to more than 40 inches per year. This part of Neosho River is very crooked and has a light slope, and the valley is subject to frequent and destructive floods. In many places dikes have been built to keep out the water, and the railroads have raised their tracks to get above it. There are a few dams on this part of the river for mills and power purposes, but the sites are on the lowlands and give a low fall. There are no power plants on Neosho River below Wyandotte, but one or more are under contemplation. The fall of the Neosho from Wyandotte to Fort Gibson is about 242 feet. In the upper part of this section of the basin the timber is in belts along the streams, while in the lower part it is in large bodies and the sections of prairie land are very scattering. The percentage of cultivated land along Neosho River in Kansas is 60 per cent; along Spring River and the Neosho below Wyandotte it is much less.

Spring River, the main tributary of Neosho River, rises in southwestern Missouri and flows through the lead and zinc regions in a southwest course into Kansas and then southward into Indian Territory. Its entire course is through rolling and broken country, except along the stream bottom. This is a grazing, agricultural, and mining region, the lead and zinc industry along the upper and middle courses of Spring River being very extensive. The soil is rocky, but in places there is considerable porous loam which allows the water to percolate into the lower strata, giving good underground water at a medium depth. The precipitation in the basin of Spring River is at least 40 inches per year; if this falls suddenly and in large quantities the channel of the river is not capable of carrying it off and destructive floods follow. The worst flood for many years occurred in July, 1905. There is a large electric power plant on Spring River at Lowell, Kans., with a fine concrete dam and powerhouse, which furnishes electricity for several cities along this river and in the vicinity. This dam and plant withstood the flood without any material damage.

NEOSHO RIVER AT FORT GIBSON, IND. T.[a]

This station was established September 22, 1903, by W. G. Russell. It is located at the Missouri Pacific Railway bridge, three-fourths of a mile northwest of Fort Gibson, Ind. T.

The channel is straight for about 500 feet above and below the station. The current is sluggish except at high water, when it is swift near the right bank. The right bank is high and wooded, and overflows only at very high stages. The left bank is high, rocky, and clean, and does not overflow. The bed of the stream is a smooth rock from the left bank to the middle; on the right it is sand and changes with every flood. There are four channels at low and five at high water. Drift at very high water makes it impossible to get other than surface velocities. October 11, 1905, the fall of the river from a point above the gaging station to a point about the same distance below, 620 feet distant, was 0.059 foot, which gives a slope of 0.00009516.

Discharge measurements are made from the downstream side of the three-span steel bridge. The bridge has a total length of 625 feet, with a pile approach of 157 feet at the west end. It is slightly oblique to the course of the current. The initial point for soundings is the edge of the abutment on the left bank of the river.

There are two sections of the gage. The first is a vertical staff fastened to the east face of the first stone pier from the left bank. The 9-foot mark is the top of the steel caisson and below this point gage heights are taken by means of a standard chain gage let down from a nail in the guard rail, along which the scale is marked. This gage is [illegible] only in very low or very high water and is kept in the pump house when not in u[illegible] was read once each day by W. L. Blackwell. Bench marks [illegible]

[a] Formerly known as Grand R[illegible]

ss, marked "B. M," on a hard limestone rock in the face of the wall 4 feet above eam side of the bridge on the left bank of the river; elevation, 24.90 feet above the the gage. (2) A United States Geological Survey standard bench mark, marked ı the top of the east bridge pier; elevation, 516 feet above sea level and 40.94 feet ɜ datum of the gage.

ation in regard to this station is contained in the following Water-Supply Papers ıited States Geological Survey:

ion: 37, p 268; 99, p 257; 131, pp 158–159.
ge: 37, p 268; 131, p 159.
ghts: 37, p 268; 99, p 257; 131, p 160.

Discharge measurements of Neosho River at Fort Gibson, Ind. T., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. G. Russell.....	495	4,227	2.01	11.40	8,484
.....	.....do.....	499	4,436	2.57	11.90	11,400
.....	.....do.....	493	3,871	1.41	11.00	5,457
.....	.....do.....	468	3,135	.83	9.90	2,588

Daily gage height, in feet, of Neosho River at Fort Gibson, Ind. T., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	9.0	9.8	15.1	12.5	10.6	20.0	12.0	17.0	11.5	14.2	13.0	11.0
.....	9.0	9.8	14.3	12.7	10.6	19.0	13.5	17.5	10.2	14.0	.....	10.8
.....	9.0	9.8	13.0	14.0	10.6	17.0	13.5	17.0	10.0	14.0	16.5	10.6
.....	9.0	.....	12.0	14.7	10.5	17.0	14.0	15.0	10.0	13.8	15.5	10.5
.....	9.0	.....	12.0	14.5	10.5	16.0	14.0	14.5	10.5	13.6	14.0	10.4
.....	9.0	.....	12.0	14.0	10.6	15.0	17.0	14.0	.....	13.5	12.5	10.4
.....	9.0	.....	12.4	13.5	11.3	14.0	16.5	13.5	10.8	13.4	12.8	10.4
.....	9.0	.....	12.8	13.0	11.8	19.0	16.0	13.0	11.0	13.3	13.8	10.4
.....	9.1	.....	13.8	12.5	11.9	16.0	15.5	12.8	10.8	13.2	14.8	10.4
.....	9.2	.....	17.0	12.0	12.0	14.0	16.0	12.6	10.6	13.2	13.0	10.4
.....	9.2	.....	17.5	12.0	11.6	13.8	15.5	12.8	11.6	13.0	12.5	10.3
.....	9.2	8.33	15.0	12.0	11.4	13.6	15.0	12.6	11.5	12.5	12.0	10.3
.....	9.2	8.33	14.0	12.0	11.4	13.4	14.5	12.0	12.5	12.0	11.6	10.3
.....	9.2	8.33	14.0	12.0	13.0	13.6	14.0	11.8	14.5	11.8	11.5	10.3
.....	9.2	8.33	13.5	11.7	12.5	13.4	13.5	11.6	12.5	11.6	11.4	10.2
.....	9.2	8.33	13.0	11.4	12.3	13.0	13.0	11.4	12.3	11.0	11.3	10.2
.....	9.2	8.33	12.9	11.2	13.3	12.9	12.8	12.0	12.2	10.5	11.0	10.2
.....	9.4	8.33	13.0	11.0	13.5	12.8	12.6	12.6	14.2	10.4	11.0	10.1
.....	9.4	9.0	15.5	11.0	13.7	13.0	12.4	12.8	15.2	13.4	10.9	10.0
.....	9.4	9.1	18.0	11.0	12.7	12.8	12.2	18.0	16.4	14.0	10.8	10.0
.....	9.5	9.1	18.7	11.0	18.0	12.4	12.0	23.5	16.4	14.0	10.7	9.8
.....	9.5	9.2	16.5	11.0	17.0	14.4	14.5	20.0	16.3	13.9	10.7	9.8
.....	9.5	9.5	15.0	10.9	17.0	14.4	16.5	18.0	15.8	13.6	10.6	9.8
.....	9.5	9.7	13.5	10.9	17.0	13.4	17.5	16.0	15.5	13.3	10.6	9.7
.....	9.5	9.8	12.5	10.9	16.5	13.2	15.5	15.0	15.3	13.4	10.5	9.7
.....	9.5	9.9	12.0	10.8	16.5	13.2	14.0	14.0	15.1	13.2	10.5	9.6
.....	9.5	15.1	12.0	10.8	16.0	13.0	13.8	12.5	15.0	17.2	10.5	10.0
.....	9.5	16.1	12.0	10.8	15.5	12.8	12.8	12.0	15.0	17.2	10.5	10.2
.....	9.7	.....	12.0	10.8	24.0	11.6	13.5	11.5	14.8	15.0	10.5	10.6
.....	9.7	.....	12.1	10.8	20.0	11.0	17.5	11.2	14.6	14.0	11.0	10.6
.....	9.8	.....	12.5	.....	19.0	.....	.....	11.0	.....	13.5	.....	10.5

River frozen over February 4-11, inclusive.

CANADIAN RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Canadian River rises in the mountains of Colfax County, N. Mex., flows southward across Mora and San Miguel counties, then turns to the east and flows across northern Texas, Oklahoma, and Indian Territory, uniting with Arkansas River about 80 miles above Fort Smith, Ark.

The drainage area is wooded in the upper portion and in Indian Territory, but consists of dry plains in Texas and Oklahoma. There are few tributaries, Ute Creek and Mora and Sapello rivers in New Mexico being the principal ones. The run-off is very uncertain, varying from extreme floods to practically nothing in a dry season.

CANADIAN RIVER AT CALVIN, IND. T.

This station was established in 1904 by the United States Weather Bureau. It is located at the railroad bridge about one-fourth mile west of Calvin, Ind. T.

The channel is straight for 2,000 feet above and below the station. The current is swift, and is oblique to the bridge at times. Neither bank will overflow beyond the limits of the bridge and trestle approach. The bed of the stream is composed of clean sand, and is shifting. There is but one channel, divided by the piers of the bridge and somewhat obstructed by old piles and drift caught on them.

Discharge measurements are made from the upstream side of the three-span bridge to which the gage is attached. The bridge has a total length of 835 feet, with a trestle approach of 30 feet at the left bank. The initial point for soundings is the face of the right abutment, upstream side.

A standard chain gage is fastened to the upstream side of the bridge near the middle of the stream; length of the chain, 28.00 feet. During 1905 the gage was read once each day by the United States Weather Bureau observer. Bench marks were established as follows: (1) A United States Geological Survey standard bench-mark post, marked "715," about 100 yards west of the Calvin depot; elevation, 28.72 feet. (2) On the right abutment, upstream side; elevation, 20.42 feet. (3) On the upstream end of the crossbeam, 353 feet from the initial point; elevation, 26.32 feet.

Discharge measurements of Canadian River at Calvin, Ind. T., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
July 28	J. M. Giles	622	1,578	5.38	4.37	8,4[illegible]
July 28	do	622	1,533	5.81	4.32	8,9[illegible]
July 29	do	496	1,590	4.44	4.15	7,0[illegible]
July 29	do	479	1,518	4.26	4.05	6,4[illegible]
September 24	E. R. Kerby	155	272	1.98	2.40	5[illegible]
September 27	J. M. Giles	114	168	1.48	2.22	2[illegible]
September 27	do	114	160	1.46	2.21	2[illegible]
October 10	E. R. Kerby	60	50	1.82	2.00	[illegible]
November 16	do		1,163	3.94	3.70	4,5[illegible]
November 18	do		869	2.90	3.20	2,5[illegible]
December 12	do		203	2.39	2.70	4[illegible]

Daily gage height, in feet, of Canadian River at Calvin, Ind. T., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov	Dec.
.....	0.4	0.1	2.1	1.5	4.1	6.0	2.4	5.2	2.1	2.1	1.9	4.7
.....	.3	.....	1.8	1.7	3.8	4.8	3.1	2.9	2.0	4.4	1.9	3.8
.....	.3	.....	1.5	3.2	3.3	4.1	3.1	2.8	2.2	2.9	1.9	3.8
.....	.3	.....	1.2	2.7	3.8	3.7	3.2	2.7	2.0	2.7	2.2	3.1
.....	.2	.....	1.1	2.3	4.0	3.4	3.1	2.4	2.2	2.3	2.6	3.0
.....	.2	.....	1.5	2.0	4.1	3.2	3.1	2.6	2.0	2.2	2.2	2.8
.....	.2	.....	2.0	4.0	3.9	3.0	3.0	2.9	1.9	2.1	2.1	2.4
.....	.2	.....	1.9	3.8	3.7	2.8	2.8	4.0	2.2	2.0	2.3	2.2
.....	.2	.....	2.2	3.4	3.5	2.8	2.7	3.7	2.7	2.0	2.6	2.0
.....	.6	.....	1.8	3.0	3.2	3.7	3.6	3.4	4.2	2.0	2.3	2.6
.....	.8	.....	1.2	3.0	3.2	3.2	3.2	3.1	4.0	2.0	2.6	2.6
.....	1.0	.....	1.7	2.6	3.4	3.8	3.0	3.0	4.7	1.9	2.5	2.6
.....	.....	.....	1.6	2.5	4.6	3.4	3.0	2.9	4.6	1.9	2.4	2.8
.....	.....	.....	1.7	2.8	4.5	2.9	3.0	3.1	4.3	2.0	2.3	3.0
.....	.....	.....	2.1	2.5	3.7	2.4	3.4	3.6	3.7	1.8	4.4	2.5
.....	.....	.....	2.0	2.5	3.7	2.7	3.2	4.2	3.6	1.9	3.9	2.5
.....	.....	.....	1.8	2.6	3.4	2.3	3.6	5.2	2.9	2.2	3.8	2.6
.....	.6	.....	2.4	2.4	3.1	2.6	3.6	4.0	2.8	2.3	3.2	2.7
.....	.5	.....	2.2	3.0	3.0	2.5	3.6	3.6	2.8	2.2	3.0	2.6
.....	.5	.....	2.5	3.0	7.0	2.8	4.1	3.8	2.5	2.0	3.0	3.8
.....	.5	.....	2.8	2.9	6.0	2.9	3.4	3.1	2.5	2.0	2.9	3.6
.....	.5	1.1	2.3	2.9	6.5	2.6	3.1	3.0	2.4	2.0	2.8	3.4
.....	.3	1.9	2.1	2.8	5.7	2.2	3.2	2.8	2.4	1.9	2.8	3.3
.....	.2	2.8	1.9	2.7	4.1	2.6	3.1	2.5	2.4	2.0	3.1	3.2
.....	.....	2.2	1.8	2.8	3.8	2.2	3.0	2.4	2.3	2.0	2.5	3.0
.....	.....	3.5	1.7	3.5	4.8	2.5	3.4	2.3	2.2	2.0	2.5	3.0
.....	.....	2.7	1.7	2.8	14.8	2.2	2.8	2.3	2.2	1.9	2.5	2.9
.....	.1	2.5	2.0	6.5	8.4	2.1	2.7	2.2	2.1	1.9	3.9	3.0
.....	.2	.....	2.0	5.4	10.0	2.8	4.2	2.2	2.2	1.9	5.4	3.0
.....	.1	.....	2.0	5.0	8.0	2.4	3.8	2.2	2.1	1.9	4.9	2.9
.....	.1	.....	1.6	.....	7.2	.....	3.7	2.1	.....	1.9	.....	3.0

River frozen January 13–17, 25–27, and February 2–21.

ating table for Canadian River at Calvin, Ind. T., from July 1 to November 30, 1905.

Gage eight.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.80	10	2.80	1,310	3.80	4,870	4.80	12,160
1.90	40	2.90	1,570	3.90	5,440	4.90	13,000
2.00	90	3.00	1,840	4.00	6,060	5.00	13,850
2.10	160	3.10	2,120	4.10	6,720	5.10	14,700
2.20	260	3.20	2,420	4.20	7,420	5.20	15,600
2.30	380	3.30	2,740	4.30	8,150	5.30	16,500
2.40	520	3.40	3,080	4.40	8,910	5.40	17,400
2.50	680	3.50	3,460	4.50	9,700		
2.60	860	3.60	3,880	4.60	10,510		
2.70	1,070	3.70	4,350	4.70	11,330		

ove table is applicable only for open-channel conditions. It is based on 10 discharge measure- ade during 1905. It is well defined between gage heights 2 feet and 4.5 feet. Owing to the shift- cter of the stream the table should not be applied prior to July 1, as there were no measure- fore that date. The only measurement in December indicates a decided change in conditions reason no estimate is made.

Estimated monthly discharge of Canadian River at Calvin, Ind. T., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
July	7,420	520	2,742	168,600
August	15,600	160	3,017	185,500
September	11,330	40	2,087	124,200
October	8,910	10	476	29,270
November	17,400	40	2,500	148,800
The period				656,400

CANADIAN RIVER NEAR LOGAN, N. MEX.

This station was established June 29, 1904, by W. G. Russell. It is located at the bridge of the Chicago, Rock Island and Pacific Railroad, 1 mile west of the depot at Logan, N. Mex. The station was discontinued February 26, 1905, though discharge measurements were made afterward.

A description of this station and gage height and discharge data are contained in Water-Supply Paper No. 131, United States Geological Survey, pages 160–162.

Discharge measurements of Canadian River near Logan, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Second-feet.*
October 10	Earl Patterson	30	22	0.61	14
November 20	do	43	43	1.70	73

Daily gage height, in feet, of Canadian River near Logan, N. Mex., for 1905.

Day.	Jan.	Feb.	Day.	Jan.	Feb.	Day.	Jan.	Feb.
1	2.0	2.1	12	2.0	2.0	23	2.0	2.6
2	2.0	2.1	13	2.0	2.0	24	2.0	2.6
3	2.0	2.1	14	2.0	2.0	25	2.0	2.55
4	2.0	2.1	15	2.0	2.0	26	2.0	2.4
5	2.0	2.2	16	2.0	2.0	27	2.0	.....
6	2.0	2.2	17	2.9	2.1	28	2.0	.....
7	2.0	2.2	18	2.9	2.1	29	2.2	.....
8	2.1	2.1	19	2.9	2.2	30	2.2	.....
9	2.1	2.1	20	2.9	2.85	31	2.2	.....
10	2.1	2.1	21	2.9	3.25			
11	2.1	2.0	22	2.9	2.65			

MORA RIVER AT LA CUEVA, N. MEX.

This station was established August 25, 1903, by M. C. Hinderlider. It is located at the wagon bridge at the village of La Cueva, N. Mex. La Cueva is situated in the Mora land grant, 26 miles directly north of Las Vegas. During the flood of September 29, 1904, the bridge to which the gage was attached was carried away and as a result records were discontinued for the remainder of the year. The station was reestablished April 29, 1905, at the old section, the bridge having been replaced.

is station is one-fourth mile below the dam site of the La Cueva reservoir, and was estab-
d to determine the amount of water available for storage in the reservoir for use on val-
unds below. The Mora canal diverts water from Mora River a short distance above this
ng station. At low water practically the entire flow of the river is diverted by this canal,
of it being at times used for power for a gristmill and returned to the river above the
ion. At other times the entire volume in the canal is carried through to a system of
age reservoirs, below which the water is used for irrigation. No data of value concern-
the canal have been secured during 1905.

he channel is straight for 50 feet above and 120 feet below the station. The bed of the
am is composed of solid rock which is partly covered with a loose deposit of shifting sand
l gravel. The left bank consists of sand and gravel, is low, and overflows at high water.
e right bank is a series of sandstone ledges. There is but one channel at all stages.

The bridge from which discharge measurements are made is not quite at a right angle to
e stream flow.

The original gage was a vertical rod fastened to the west end of the north abutment of the
dge. April 29, 1905, a staff gage was fastened vertically to the west side of the south
utment of the bridge, the datum being 1.32 feet above that of the original gage. During
05 the gage was read twice each day by Hugh Loudon, secretary of the La Cueva Land
d Cattle Company. The bench mark is a cross cut in the vertical face of the limestone
dge just above the south end of the bridge, marked "U. S. G. S., B. M.;" elevation, 4.51
et above the datum of the new gage.

Information in regard to this station is contained in the following Water-Supply Papers of
e United States Geological Survey.

Description: 99, p 249; 131, pp 162–163.
Gage heights: 99, p 249; 131, p 163.

Discharge measurements of Mora River at La Cueva, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
pril 29	R. I. Meeker	24	09	4.50	3.40	310
ily 2	do	18	15	1.60	.85	24
ugust 1	do	22	20	1.70	1.10	34

Daily gage height, in feet, of Mora River at La Cueva, N. Mex., for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	.....	0.55	1.0	3.2	2.2	0.85	1.1	[a]0.8	0.8	0.9
2	.....	[a].7	.75	3.4	2.2	.8	1.55	.85	.9	.9
3	.....	.85	.75	3.4	2.2	.8	1.4	.85	.9	.9
4	.....	.85	.7	3.0	2.7	.8	1.5	.9	.9	.9
5	.....	.85	.7	2.8	.....	.8	1.4	1.0	.9	.9
6	.....	1.5	.85	2.5	.....	.8	1.7	.9	.9	.9
7	.....	1.3	1.15	2.5	.....	.75	1.4	.85	.8	.9
8	.....	1.1	1.4	2.55	.....	.75	1.4	.9	.8	.9
9	.....	1.1	1.6	2.9	.....	.8	1.3	.95	.8	.95
10	.....	1.1	1.7	2.6	2.1	.75	1.2	.95	.8	.9
11	.....	1.05	1.7	2.4	2.0	.75	1.2	.9	.7	.9
12	.....	[a]1.05	1.55	2.4	2.0	.75	1.1	.9	.8	.9
13	.....	1.05	1.5	2.4	1.9	.7	1.1	.85	.8	.9
14	.....	1.05	1.45	2.3	1.8	.7	1.1	.85	.8	.9
15	.....	1.05	1.4	2.2	1.7	.7	1.0	.8	.8	.9
16	.....	[a]1.0	1.45	2.4	1.65	.7	1.0	.75	.6	.9
17	.....	1.0	1.4	2.5	1.6	.7	.95	.8	.8	.9
18	.....	.8	1.45	2.5	[a]1.5	.7	.9	.8	.8	.9
19	.....	.85	1.5	2.6	1.4	.7	.85	.8	.8	.9
20	.....	.9	[a]1.5	2.7	1.4	.7	.85	.6	.75	.9
21	.....	.85	1.5	2.5	1.3	.7	.75	.55	.95	.9
22	0.4	.8	1.55	2.4	1.3	.9	.7	.55	.9	1.05
23	.45	.8	2.1	2.5	1.2	.9	.8	.6	.9	1.0
24	.45	.75	2.0	2.5	1.2	.8	.8	.6	1.0	.9
25	.45	.8	2.1	2.3	1.2	.75	.8	.6	.95	.9
26	.5	.85	2.3	2.5	1.1	.7	.8	.65	.95	.9
27	.6	[a].8	2.9	2.3	1.05	[a].7	.8	.7	.9	1.1
28	.55	.75	3.0	2.4	1.0	.75	.8	.6	.95	1.0
29	.....	.65	3.3	2.2	.9	.75	.7	.7	.9	1.0
30	.....	.75	3.3	2.1	.9	.8	.7	.6	.9	1.0
31	.....	.7	.....	2.2	.....	.9	[a].75	.....	.9	.....

[a] Interpolated.

NOTE.—River frozen December 23-31.

Station rating table for Mora River at La Cueva, N. Mex., from February 22 to December 1905.

Gage height.	Discharge.	Gage height.	Discharge	Gage height.	Discharge.	Gage height.	Discharge
Feet.	*Second-feet.*	*Feet.*	*Second-feet*	*Feet.*	*Second-feet*	*Feet.*	*Second-feet*
0.20	12	1.10	31	2.00	105	2.90	224
0.30	13	1.20	39	2.10	115	3.00	240
0.40	14	1.30	45	2.20	126	3.10	257
0.50	16	1.40	52	2.30	138	3.20	274
0.60	18	1.50	60	2.40	151	3.30	292
0.70	21	1.60	68	2.50	164	3.40	310
0.80	24	1.70	77	2.60	178		
0.90	27	1.80	86	2.70	193		
1.00	30	1.90	95	2.80	208		

The above table is applicable only for open-channel conditions. It is based on three discharge urements made during 1905. On account of the small number of measurements, it should be cons as only approximate.

Estimated monthly discharge of Mora River at La Cueva, N. Mex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
February 22-28	18	14	15.7	218
March	60	17	28.2	1,734
April	292	21	87.1	5,183
May	310	115	175.	10,760
June (25 days)	193	27	72.6	3,600
July	27	21	22.8	1,402
August	77	21	35.0	2,152
September	30	17	23.2	1,380
October	30	18	25.4	1,562
November	34	27	27.8	1,654
December 1-22	32	26	27.5	1,200
The period				30,840

SAPELLO RIVER AT LOS ALAMOS, N. MEX.

This station was established August 22, 1903, by M. C. Hinderlider. It is located at a ford crossing Sapello River at a point about one-fourth mile due north from Los Alamos, N. Mex. Los Alamos is about 13 miles north of Las Vegas. The establishment of this station was for the purpose of determining the available amount of water for prospective diversion into the San Guijuela reservoir for the Las Vegas project. This basin lies about 6 miles northwest of Las Vegas.

The channel at the cable is about 125 feet wide and is straight above and below for 200 feet each way. The bed is composed of bowlders, cobblestones, sand, and gravel. The banks are of alluvial material, which erodes easily, and are about 10 feet high. There is but one channel at all stages. Gage heights range from 0 to 5 feet. The current is strong at all stages.

Discharge measurements were originally made by wading. In March, 1904, a cable, car, and tagged wire were installed for use during high water.

The original gage was an inclined staff 500 feet below the cable. September 29, 1904, the gage was destroyed by a disastrous flood which swept down this valley. Records were discontinued until April, 1905, when a standard chain gage was installed near the cable, about 400 feet above the location of the original gage. This gage is fastened to a cantilever arm on the right bank. The length of the chain is 15.44 feet. During 1905 the gage was read by W. N. Frank, jr. The bench mark is a nail driven into the post supporting the cable at the right bank; elevation, 11.50 feet above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 249-250; 131, pp 166-167.
Discharge: 99, p 250; 131, p 167.
Gage heights: 99, p 250; 131, p 168.

Discharge measurements of Sapello River at Los Alamos, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
February 3	R. I. Meeker	12	13	2.23	0.90	29
April 28	do	73	91	5.25	2.60	478
July 1	do	12	7.5	1.68	.40	13
August 2	do	12	11	1.73	.65	19

NOTE.—*Measurements made at different sections.*

Daily gage height, in feet, of Sapello River at Los Alamos, N. Mex., for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	1.5	1.5	2.25	1.4	0.4	0.7	0.1	0.1	0.1	0.8
2	.....	2.0	1.6	2.55	1.4	.4	.7	.15	.1	.1	.8
3	0.9	1.75	1.55	2.45	1.4	.3	.65	.4	.1	.1	.8
4	.9	1.7	1.65	2.0	1.35	.3	.65	.4	.1	.15	.8
5	.95	1.7	1.85	2.0	1.2	.25	1.15	.3	.1	.1	.8
6	1.0	2.75	1.9	1.85	1.15	.2	.8	.1	.1	.1	.8
7	.95	2.15	1.95	1.85	1.1	.0	.7	.15	.1	.1	.8
8	.9	1.75	1.85	1.85	1.45	.0	.7	.35	.1	.15	.8
9	1.7	1.65	1.85	1.9	1.35	.0	.6	.85	.1	.1	.8
10	1.05	1.6	1.85	1.75	1.25	.0	.5	.1	.1	.1	.8
11	.95	1.55	1.8	1.75	1.25	.0	1.3	.1	.1	.1	.8
12	.95	1.5	1.8	1.7	1.2	.0	1.2	.1	.1	.1	.8
13	.95	1.5	1.75	1.7	1.2	.0	.6	.2	.1	.1	.8
14	.95	1.4	1.6	1.65	.95	.1	.5	.1	.1	.1	.8
15	1.15	1.4	1.6	1.6	.9	.1	.45	.1	.1	.1	.8
16	1.25	1.4	1.6	1.55	.9	.1	.35	.1	.1	.1	.8
17	1.25	1.3	1.55	1.6	.75	.1	.35	.1	.1	.1	.8
18	1.15	1.25	1.55	1.7	.7	.15	.3	.1	.1	.1	.8
19	1.15	1.15	1.55	1.8	.65	.1	.2	.1	.1	.1	.8
20	1.1	1.15	1.5	1.8	.6	.1	.25	.2	.1	.1	.8
21	1.35	1.15	1.5	1.85	.5	.1	.2	.1	.1	.1	.8
22	1.25	1.2	1.6	1.75	.65	.1	.2	.1	.1	.9	.8
23	1.35	1.25	2.45	1.75	.45	.35	.2	.1	.1	.6	.8
24	1.35	1.25	3.45	1.7	.55	.45	.2	.1	.1	.6	.8
25	1.35	1.25	3.8	1.6	.55	.4	.2	.1	.1	.6	.8
26	1.4	1.25	3.35	1.6	.55	.25	.2	.15	.1	.6	.8
27	1.4	1.25	3.05	1.55	.45	.15	.1	.2	.1	1.9	.8
28	1.5	1.25	2.5	1.5	.35	.1	.15	.2	.1	.9	.8
29	.....	1.15	2.45	1.45	.35	.15	.15	.2	.1	.9	.8
30	.....	1.15	2.4	1.45	.4	.2	.2	.1	.1	.9	.8
31	.....	1.25	.....	1.4	.....	1.35	.15	.....	.1	.....	.8

UTE CREEK NEAR LOGAN, N. MEX.

This station was established August 12, 1904, by W. G. Russell. It is located about 7 miles northwest of Logan, N. Mex., and about 4 miles above the mouth of Ute Creek, near the old Martinez house.

The channel is straight for about 300 feet above the station. The current is sluggish at low and swift at high stages. The right bank is low, clean, and subject to overflow. The left bank is high, rocky, and wooded, and does not overflow. The bed of the stream is composed of clean sand and is shifting. There is but one channel at all stages.

Discharge measurements are made at low water by wading near the gage. Discharges for high stages must be computed from the slope and cross section. The initial point for soundings is at the gage on the left bank of the stream.

The original gage was washed out May 23, 1905. A new gage was established at the same datum June 30, 1905, the record being kept in the meantime by measuring down from a bench mark. The new gage is an inclined staff fastened to the rock on the left bank of the creek, about 100 feet above the site of the old gage. During 1905 the gage was read once each day by Manuel Martinez. Bench marks were established as follows: (1) A cross painted on the top of a rock on the left bank 200 feet below the gage; elevation, 5.51 feet. (2) The head of a bolt set in a rock 14 feet west of the gage; elevation, 3.46 feet. (3) A cross cut in a sandstone ledge directly over the gage; elevation, 11.89 feet. Elevations refer to the datum of the gage.

iption of this station and gage height and discharge data are contained in Water-aper No. 131, United States Geological Survey, pp. 170–171.

Discharge measurements of Ute Creek near Logan, N. Mex., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	J. M. Giles	6	4.3	0.90	0.50	3.9
.....	Earl Patterson	36	13.1	1.35	.80	17.7
.....	.....do	10	1.71	.73	.65	1.3
.....	.....do	68	58	3.31	1.50	194
.....	.....do	68	46	3.13	1.30	145
.....	.....do	70	67	3.98	1.60	266
.....	.....do	70	74	4.22	1.70	311
.....	.....do	54	32	2.50	1.15	80
.....	.....do	84	25	2.42	1.05	60
.....	.....do	7	2	.63	.75	1.4
.....	.....do	1	.13	.14	.70	.02
20...	.....do	.....	4.9	1.04	.90	5.1
15...	.....do	44	17	1.13	1.10	19

Daily gage height, in feet, of Ute Creek near Logan, N. Mex., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.3	0.3	0.8	0.6	0.8	1.2	1.8	4.9	0.8	0.8	.....	1.2
.....	.3	.3	.8	3.8	.6	.9	1.1	4.8	.8	.8	.....	1.1
.....	.2	.3	.8	2.9	.5	.6	1.1	4.5	.8	.8	.....	1.1
.....	.2	.3	.8	2.2	.4	.6	.9	2.9	.8	.8	.....	1.0
.....	.2	.3	.6	1.8	.3	.6	.8	1.1	2.5	.7	.....	.9
.....	.2	.3	.8	1.6	.3	.8	.7	1.3	1.9	.7	.....	.9
.....	.2	.3	.8	1.4	.3	.8	.6	1.9	2.9	.....	.....	.8
.....	.2	.3	.6	1.2	.3	.8	.6	3.3	2.4	.....	1.2	.7
.....	.2	.3	.6	1.1	.3	.8	.6	2.5	1.5	.....	2.1	.6
.....	.2	.3	.6	.9	.3	.9	.6	1.9	1.8	.....	1.9	.6
.....	.3	.3	.4	.9	.3	.9	.5	1.4	1.8	.....	1.5	.6
.....	.3	.3	.9	.9	.2	.8	.5	1.0	1.6	.....	1.8	.6
.....	.4	.3	.9	.9	.2	.6	.5	1.0	1.1	.....	1.8	1.4
.....	.4	.3	.9	.8	.2	.5	.4	.9	.9	.....	1.9	1.2
.....	.4	.4	.9	.8	.2	.3	.4	1.1	.8	.....	1.9	1.2
.....	.4	.4	.8	.4	.2	.2	.4	.9	1.3	.....	1.6	1.2
.....	.4	.4	.8	.4	.2	.2	.4	.8	1.1	.....	1.1	1.2
.....	.4	.3	.8	.4	.2	.2	.4	.6	1.1	.....	.9	1.2
.....	.5	.3	.4	.4	.2	.2	.4	.6	.9	.....	.9	1.2
.....	.5	.8	.4	.3	1.6	.2	.4	.6	.7	.....	.9	1.2
.....	.5	1.1	.5	.4	.9	.4	.9	.5	.7	.....	.9	1.2
.....	.5	.9	.5	.4	.8	.3	1.5	.5	.7	.....	1.0	1.1
.....	.5	.9	.6	3.5	8.8	.2	1.1	.5	.7	.....	2.8	1.0
.....	.5	1.6	.6	3.8	5.3	.2	.9	.5	.7	.....	1.6	1.0
.....	.5	1.4	.6	3.3	3.9	.2	.9	.5	.7	.....	1.3	1.0
.....	.4	1.1	.6	2.5	8.8	.2	.8	.5	.9	.....	1.3	1.0
.....	.4	.9	.5	2.1	3.9	.2	.8	.5	.9	.....	1.3	1.0
.....	.4	.9	.4	1.5	2.2	.2	.6	.8	.8	.....	1.3	1.0
.....	.4	.....	.3	1.0	1.9	.5	.5	.9	.8	.....	1.3	.9
.....	.3	.....	.3	.9	1.7	1.8	5.2	.9	.8	.....	1.2	.9
.....	.3	.....	.3	.....	1.5	.....	5.1	.8	.....	.....	.....	.9

Creek dry October 7 to November 7, inclusive.

BEAVER CREEK AT BEAVER, OKLA.

This station was established March 29, 1904, by W. G. Russell, and was discont December 31, 1905. It is located just below the ford about one-fourth mile nor Beaver, Okla.

The channel is straight for about 300 feet above and below the station and about 9 wide at ordinary stages. During the flood of July, 1904, the river was 2,547 feet wide a the highway and across the ford, and the stream bed was eroded. The current is slu at low water, but has a good current at high stages. Both banks are low, clean, and l to overflow. The bed of the stream is composed of clean sand and is shifting. There is one channel at all stages.

Discharge measurements are made at low water by wading. It is not possible to n high-water measurements in this vicinity, and the discharge during floods must be compu from the slope and cross section. The initial point for soundings is at the gage.

The original gage was destroyed July 9, 1904. A new inclined gage at the same da was fastened to posts driven into the bank of the river. June 18, 1905, a similar gage erected 440 feet downstream and was set to give the same reading at gage height 0.80 f the datum being 0.44 foot lower than that of the upper gage. By reading both gage flood stage the surface slope may be obtained. During 1905 the gage was read once a day by Logan Rock. The bench mark is the top of a pine stake about 0.5 foot above surface of the ground, 15 feet south of the gage; elevation, 5.00 feet above gage datum.

A description of this station and gage height and discharge data are contained in Wa Supply Paper No. 131, United States Geological Survey, pp. 171–172.

Discharge measurements of Beaver Creek at Beaver, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di cha
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Sec fe*
June 17	J. M. Giles	36	38	1.11	0.87	
June 18	do	48	32	1.26	.82	
June 19	do	48	26	1.24	.79	
August 25	do	40	32	1.33	.95	
November 23	E. Patterson		56	1.42	1.15	
November 23	do		61	1.55	1.30	
(a)	J. M. Giles		200	1.94	2.00	
(a)	do		345	2.45	3.00	
(a)	do		525	2.84	4.00	

(a) Computed from slope measurements, using Kutter's formula.

Daily gage height, in feet, of Beaver Creek at Beaver, Okla., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.1	1.2	1.3	1.05	1.6	1.8	0.7	0.4	0.45	0.3	0.8	1.25
2	1.05	1.25	1.25	1.25	1.5	1.8	.65	.45	.45	.3	.8	1.25
3	.9	1.25	1.25	1.2	1.4	1.7	.65	.35	.5	.25	.8	1.2
4	.9	1.3	1.2	1.5	1.3	1.7	.6	.3	.4	.6	.8	1.15
5	.9	1.3	1.15	1.4	1.2	1.65	.6	1.1	.45	.6	1.2	1.15
6	.85	1.3	1.1	1.3	1.2	1.4	.65	.9	.9	.55	1.1	1.15
7	.85	1.35	1.05	1.2	1.1	1.2	.7	.85	1.0	.45	1.0	1.1
8	.85	1.35	1.05	1.2	1.1	1.15	.75	.75	1.05	.55	1.0	1.1
9	.8	1.45	1.0	1.15	1.2	1.1	.65	.75	1.1	.55	1.2	1.1
10	.8	1.45	1.05	1.15	1.3	1.1	.65	.6	1.2	.45	1.15	1.0
11	.8	1.45	1.05	1.15	1.1	1.4	.65	.5	1.2	.55	1.1	.9
12	.85	1.5	1.05	1.1	1.05	1.4	.6	.5	1.25	.6	1.1	.9
13	.9	1.5	1.05	1.1	1.05	1.3	.55	.8	1.3	.6	1.1	.9
14	.9	1.5	1.05	1.05	1.0	1.2	.5	.75	1.4	.65	1.05	.95
15	.9	1.5	1.05	1.2	1.0	1.1	.5	.75	1.3	.65	1.05	.95
16	.9	1.6	1.0	1.1	1.0	.8	.75	.6	1.25	.65	1.05	.95
17	.9	1.4	1.0	1.05	.95	.9	.4	.5	1.1	.7	1.05	1.0
18	.9	1.4	1.05	1.05	.95	.85	.4	1.2	1.0	.7	1.0	1.0
19	.9	1.4	1.05	1.1	1.0	.85	.35	1.0	.9	.7	1.0	1.0
20	1.1	1.35	1.05	1.1	1.0	.8	.45	.5	.8	.75	.95	1.05
21	1.1	1.35	1.05	1.0	1.05	.8	.4	.5	.75	.75	.9	1.05
22	1.5	1.35	1.05	1.0	1.1	.8	.4	.45	.6	.8	.9	1.1
23	1.5	1.3	1.0	1.05	1.1	1.15	.35	1.05	.55	.8	1.5	1.1
24	1.4	1.2	.95	2.0	1.8	1.0	.85	1.0	.5	.8	1.5	1.1
25	1.2	1.15	.9	2.1	1.6	1.0	.75	1.0	.45	.85	1.4	1.15
26	1.3	1.15	.9	2.0	3.0	.85	1.6	.85	.45	.85	1.35	1.2
27	1.25	1.15	.85	3.0	2.6	.85	.85	.8	.4	.85	1.35	1.25
28	1.25	1.15	.85	2.7	2.7	.8	.85	.75	.35	.8	1.35	1.3
29	1.2	.....	.8	2.1	3.1	.75	.8	.7	.3	.8	1.3	1.4
30	1.25	.....	.8	1.7	2.6	.7	.75	.7	.3	.8	1.3	1.4
31	1.2	.....	.85	.....	2.5	.....	.4	.6	.....	.85	.....	1.45

NORTH FORK OF CANADIAN RIVER NEAR WOODWARD, OKLA.

This station was established September 13, 1903, by W. G. Russell. It is located 7 miles east of Woodward, at the railroad bridge.

The channel is straight for 200 feet above and below the station. The right bank is high and not liable to overflow. The left bank is low and liable to overflow under the bridge; there are scattering trees along the bank. The bed of the stream is sandy and shifting. There is but one channel, broken by two piers at low water and five piers at high water.

Discharge measurements are made from the six-span railroad bridge, which has a total length between abutments of 360 feet. The initial point for soundings is at the west end of the bridge.

The original gage is painted on the west face of the second pier from the west end of the bridge. A standard chain gage is fastened to the downstream guard rail of the bridge; length of chain, 18.44 feet. During 1905 the gage was read by Adolph Mueller. The bench mark is the bottom of the coping stone of the pier at the top of the gage; elevation, 7.00 feet above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 245; 131, pp 172-173.
Discharge: 131, p 173.
Gage heights: 99, p 246; 131, p 173.

Discharge measurements of North Fork of Canadian River near Woodward, Okla., in 1905

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis-charge
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second feet.*
March 30	W. W. Schlecht	54	104	1.54	2.50	
April 2	do	172	148	1.21	2.65	
April 6	do	204	224	1.34	2.96	
April 15	do	185	130	1.46	2.76	
May 2	W. G. Russell	169	488	1.77	3.40	
May 3	do	157	351	2.16	3.20	
June 8	J. M. Giles	106	123	1.57	2.65	
June 8	do	142	173	1.18	2.65	
June 19	Earl Patterson	66	63	1.79	2.40	
June 22	do	162	196	1.76	2.90	
July 21	do	81	48	1.46	2.30	
August 17	do	.....	282	1.77	3.50	
August 29	do	32	27	1.45	2.10	
September 19	do	40	37	1.40	2.30	
October 20	J. M. Giles	28	10	.90	1.85	
October 28	Earl Patterson	35	25	1.26	2.20	
November 27	do	.....	178	1.28	2.90	
December 17	do	161	101	1.31	2.80	

Daily gage height, in feet, of North Fork of Canadian River near Woodward, Okla., for 190

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.5	2.8	2.9	2.6	3.5	3.9	2.0	2.6	1.9	1.8	2.3	
2	2.5	2.8	2.8	2.6	3.4	3.8	2.2	2.6	1.8	1.8	2.3	
3	2.5	2.8	2.8	2.6	3.2	3.6	2.0	2.5	1.8	1.8	2.3	
4	2.5	2.8	2.7	2.8	3.0	2.9	1.8	2.3	1.8	1.7	2.4	
5	2.5	2.8	2.9	2.9	3.0	2.9	1.8	2.2	1.8	1.7	2.5	
6	2.5	2.8	3.3	2.9	3.0	2.9	1.8	2.2	2.0	1.7	2.5	
7	2.4	2.8	2.9	3.0	3.0	2.8	1.9	2.1	1.9	1.6	2.5	
8	2.4	2.8	2.9	3.0	3.0	2.7	1.9	2.1	2.1	1.6	2.4	
9	2.4	2.8	2.9	2.9	2.9	2.6	2.1	2.0	2.5	1.5	2.5	
10	2.4	2.8	2.9	2.8	2.9	2.6	2.2	1.9	2.4	1.5	2.5	
11	2.4	2.8	2.9	2.8	2.9	2.5	2.1	1.9	2.5	1.5	2.5	
12	2.4	2.8	2.9	2.8	2.8	2.5	2.1	1.9	2.5	1.5	2.6	
13	2.4	2.8	2.8	2.8	2.8	2.5	2.1	3.3	2.4	1.5	2.6	
14	2.4	2.8	2.8	2.8	2.7	2.4	2.1	3.1	2.4	1.5	2.6	
15	2.4	2.8	2.8	2.8	2.6	2.4	2.0	3.0	2.3	1.5	2.6	
16	2.4	2.8	2.8	2.8	2.6	2.4	1.9	3.0	2.2	1.5	2.6	
17	2.4	2.9	2.8	2.8	2.5	2.4	1.9	3.0	2.2	1.5	2.6	
18	2.4	2.9	2.9	2.8	2.5	2.4	1.9	3.6	2.2	1.6	2.6	
19	2.7	2.9	2.9	2.8	2.5	2.4	1.9	3.0	2.1	1.7	2.6	
20	2.7	2.9	3.0	2.7	2.5	2.4	1.8	2.8	2.1	1.8	2.5	
21	2.7	3.1	2.9	2.7	2.6	2.4	1.8	2.8	2.1	1.8	2.5	
22	2.7	3.1	2.8	2.6	2.8	3.4	1.9	2.6	2.1	1.9	2.6	
23	2.8	3.1	2.8	2.6	3.8	2.9	1.8	2.5	2.1	1.9	2.8	
24	2.9	3.0	2.8	2.8	3.6	2.8	2.8	2.3	2.1	1.9	2.8	
25	2.9	2.9	2.8	4.0	3.2	2.8	2.8	2.2	2.0	2.1	3.0	
26	2.9	2.9	2.8	3.8	3.1	2.6	2.6	2.2	1.9	2.1	2.9	
27	2.9	2.9	2.7	3.6	3.1	2.4	2.3	2.2	1.9	2.1	2.9	
28	2.9	2.9	2.6	3.6	3.1	2.0	2.3	2.2	1.9	2.1	2.9	
29	2.8	.....	2.6	3.5	3.9	2.0	2.3	2.2	1.8	2.2	2.9	
30	2.8	.....	2.6	4.5	3.5	2.0	2.9	2.0	1.8	2.2	2.8	
31	2.8	.....	2.5	.....	3.1	.....	2.7	1.9	.....	2.3	.....	

RTH FORK OF CANADIAN RIVER NEAR ELRENO, OKLA.

›n was established October 27, 1902, by W. G. Russell, and is located at the lge 2 miles north of Elreno, Okla.

el both above and below the station is straight for about 200 feet and has a feet at ordinary stage. The right bank is high and the left bank is low. Both ble to overflow. The bed of the stream is sandy and somewhat shifting.

measurements are made from the bridge. The initial point for soundings is e bridge on the right bank.

al gage was of the wire type. It was destroyed July 6, 1903, but was reestab-0, 1903. June 5, 1905, a standard chain gage was fastened to the downstream › bridge; length of chain, 17.46 feet. During 1905 the gage was read once each n Clift. The bench mark is the top of a steel cylinder pier on the north side of levation, 11.30 feet above the datum of the gage.

›n in regard to this station is contained in the following Water-Supply Papers d States Geological Survey:

84, p 114; 99, p 244; 131, p 174.
34, p 114; 99, p 244; 131, p 174.
nonthly: 131, p 177.
s: 84, p 114; 99, p 244; 131, p 175.
›: 131, p 176.

e measurements of North Fork of Canadian River near Elreno, Okla., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.	E. R. Kerby	106	194	2.18	3.80	423
.	Murphy and Kerby	105	200	1.97	3.50	395
.	J. M. Giles	105	187	1.64	3.55	307
..	do	110	325	2.02	5.13	658
..	E. R. Kerby	101	134	1.83	3.10	245
..	do	100	128	1.59	2.90	204
..	J. M. Giles	63	54	1.02	2.25	56
.	E. R. Kerby	104	171	1.63	3.30	278
..	do	104	171	1.58	3.25	270
..	do	47	26	.84	1.80	22
..	J. M. Giles	24	17	.71	1.70	12
..	E. R. Kerby	22	8	.50	1.50	4
..	do	.....	47	1.12	2.20	53
..	do	.....	97	1.32	2.70	128

Daily gage height, in feet, of North Fork of Canadian River near Elreno, Okla., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	3.0	.....	4.0	3.4	5.0	5.3	2.9	2.3	2.1	1.6	1.6	2.8
2	3.0	.....	4.0	4.1	4.9	5.3	3.0	2.3	1.9	1.6	1.6	2.8
3	2.9	.....	3.8	3.4	5.0	4.9	2.9	2.4	1.9	1.6	1.6	2.9
4	2.9	.....	3.6	3.4	5.4	4.4	2.9	2.3	1.8	1.6	1.7	2.8
5	2.8	.....	3.6	3.4	4.8	5.1	2.8	2.5	1.8	1.6	1.7	2.8
6	3.0	.....	3.6	3.6	4.7	4.8	2.6	2.7	1.8	1.6	1.8	2.8
7	3.2	.....	3.7	3.5	4.5	4.4	2.6	2.5	1.8	1.5	1.8	2.7
8	2.8	.....	3.7	3.5	4.0	4.2	2.6	2.7	2.0	1.5	1.8	2.8
9	.....	.....	3.9	3.6	4.0	4.0	2.9	2.3	2.2	1.5	2.0	2.8
10	.....	.....	4.2	4.0	3.9	3.7	2.9	2.2	2.4	1.5	2.0	2.8
11	.....	.....	4.1	3.8	3.7	3.7	2.8	2.1	2.2	1.5	2.1	2.7
12	.....	.....	4.0	3.9	3.7	3.5	2.6	2.2	2.2	1.5	2.1	2.7
13	.....	.....	3.9	4.1	3.6	3.4	2.6	2.3	2.0	1.4	2.1	2.7
14	.....	.....	3.9	4.0	3.8	3.3	2.6	2.2	2.0	1.4	2.1	2.8
15	.....	.....	4.0	3.6	3.9	3.2	2.4	2.2	2.0	1.4	2.1	2.8
16	.....	.....	3.9	3.6	3.6	3.1	2.4	2.3	2.2	1.4	2.2	2.7
17	.....	.....	3.8	3.5	3.4	3.1	2.3	3.2	2.2	1.5	2.2	2.8
18	.....	.....	4.1	3.5	3.2	3.0	2.3	3.0	2.2	1.5	2.2	2.7
19	.....	.....	4.1	3.5	3.2	2.9	2.3	3.1	2.0	1.5	2.3	2.8
20	.....	.....	4.1	3.5	3.4	2.0	2.3	3.2	2.0	1.5	2.3	2.8
21	.....	.....	4.2	3.5	3.4	2.0	2.2	3.3	1.9	1.5	2.4	2.8
22	.....	.....	4.5	3.5	3.4	3.3	2.3	3.4	1.8	1.5	2.4	2.8
23	.....	.....	4.1	3.4	3.5	3.1	2.2	3.4	1.8	1.5	2.4	2.8
24	.....	3.9	4.0	3.5	3.3	2.9	2.6	3.0	1.8	1.5	2.5	2.7
25	.....	8.6	3.9	3.5	3.2	2.9	2.5	2.8	1.8	1.5	2.4	2.7
26	.....	4.8	3.7	3.7	3.2	2.9	2.4	2.6	1.7	1.5	2.4	2.7
27	.....	4.0	3.6	3.6	3.3	3.6	2.2	2.5	1.7	1.5	2.7	2.6
28	.....	3.9	3.6	3.7	4.8	3.3	2.3	2.4	1.7	1.5	2.8	2.6
29	.....	.....	3.4	5.3	4.6	3.0	2.4	2.3	1.7	1.5	2.7	2.6
30	.....	.....	3.4	5.2	4.3	3.0	2.5	2.2	1.6	1.6	2.7	2.6
31	.....	.....	3.4	.....	4.2	.....	2.3	2.1	.....	1.6	.....	2.6

harge, in second-feet, of North Fork of Canadian River near Elreno, Okla., for 1905.

ay.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	515	370	650	710	187	67	43	11	11	164
.....	.....	515	535	625	710	210	67	26	11	11	164
.....	.....	464	370	650	615	187	82	26	11	11	187
.....	.....	415	370	740	490	187	67	20	11	15	164
.....	.....	415	370	600	650	164	99	20	11	15	164
.....	.....	415	415	575	580	119	141	20	11	20	164
.....	.....	440	395	530	490	119	99	20	8	20	141
.....	.....	440	395	410	450	119	141	34	8	20	164
.....	.....	490	415	410	410	187	67	54	8	34	164
.....	.....	560	515	385	340	187	54	82	8	34	164
.....	.....	535	464	330	345	164	43	54	8	43	141
.....	.....	515	490	330	300	119	54	54	8	43	141
.....	.....	490	535	310	280	119	67	34	6	43	141
.....	.....	490	515	360	270	119	54	34	6	43	164
.....	.....	515	415	390	255	82	54	34	6	43	164
.....	.....	490	415	305	240	82	67	54	6	54	141
.....	.....	464	395	260	245	67	256	54	8	54	164
.....	.....	535	395	220	210	67	210	54	8	54	141
.....	.....	535	395	220	187	67	233	34	8	67	164
.....	.....	535	395	260	34	67	256	34	8	67	164
.....	.....	560	395	260	34	54	279	26	8	82	164
.....	.....	630	395	260	279	67	302	20	8	82	164
.....	.....	535	370	280	233	54	302	20	8	82	164
.....	490	515	395	240	187	119	210	20	8	99	141
.....	.....	490	307	215	187	99	164	20	8	82	141
.....	720	440	340	215	187	82	119	15	8	82	141
.....	515	415	320	240	350	54	99	15	8	141	119
.....	490	415	340	590	279	67	82	15	8	164	119
.....	.....	370	720	540	210	82	67	15	8	141	119
.....	.....	370	700	470	210	99	54	11	11	141	119
.....	.....	370	.....	450	.....	67	43	.....	11	.....	119

From March 1 to June 17 the daily discharge was obtained by indirect method. For the of the year a rating table based on measurements subsequent to June 17 was used.

monthly discharge of North Fork of Canadian River near Elreno, Okla., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	630	370	480	29,510
.....	720	307	428	25,470
.....	740	215	397	24,410
.....	710	34	332	19,760
.....	210	54	112	6,887
.....	302	43	126	7,747
.....	82	11	32.1	1,910
.....	11	6	8.5	522
.....	164	11	59.9	3,564
.....	187	119	151	9,285
period	.....	.....	.....	129,100

RED RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

The headwaters of Red River include several forks, all of which have their sources in northern Texas. Red River takes a general easterly direction along the northern boundary of Texas, and then turns toward the southeast and flows through a low, swampy region in Louisiana into the Mississippi not far from the southern boundary of the State of Mississippi.

North Fork and Salt Fork rise in the Panhandle of Texas and flow in a general southeasterly course across the southwest corner of Oklahoma, uniting with Prairie Dog Fork a short distance above Vernon, Tex. Elm Fork, rising in the same locality, joins North Fork 50 or 75 miles above its mouth. The flow is very uncertain, most of the run-off being flood water after heavy rains. The flow ceases entirely in the late summer and fall in ordinary dry years. The drainage area consists of dry, semiarid plains varied by sandhills in some portions. The underlying rocks are sandstone, limestone, and gypsum in the upper portion and granite where the streams pass through the Wichita Mountains.

Washita River rises in northern Texas, crosses southern Oklahoma, and flows into Red River in the southern part of Indian Territory, about 10 miles from Denison, Tex.

Sulphur Fork of Red River has its headwaters in Hunt and Fannin counties, Tex., flows eastward, forming the boundary between Delta, Red River, and Bowie counties on the north, and Hopkins, Franklin, Titus, Morris, and Cass counties on the south, and empties into Red River in Arkansas about 7 miles north of the Louisiana boundary line. The flow of this river is very unreliable, changing with the rainfall. If the summer is at all dry it ceases altogether, but enough water always remains standing in pools to water stock. During or immediately after protracted or unusually heavy rains the river becomes very wide and deep, floods its bottoms, and often occasions considerable loss of stock and damage to planters and the railroads.

Big Cypress Creek has its headwaters in Franklin and Titus counties, Tex., flows in a general easterly direction, and empties into Red River. The flow of the river is unreliable, varying with the rainfall. In the summer it ceases and the river becomes dry except where the water stands in holes. After long or heavy rains the stream is liable to overflow its banks.

RED RIVER AT ARTHUR CITY, TEX.

This station was established January 1, 1905. The United States Weather Bureau has maintained a gaging station at this point since 1891.

The gage is a vertical staff fastened to one of the piers of the bridge. During 1905 the gage was read by Mrs. Mary Tunnell. Bench marks were established as follows: (1) The base of rail on the bridge above the second section of the Weather Bureau gage; elevation 411.10 feet above mean sea level, and 48.00 feet above the datum of the gage. (2) A rock with a 12-foot square surface, lying in the river about 300 feet southeast of the railway bridge; elevation, 363.40 feet above mean sea level and 0.30 foot above the datum of the gage.

Discharge measurements of Red River at Arthur City, Tex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge
		Feet.	*Square feet.*	*Feet per second*	*Feet*	*Second feet.*
March 17	H. H. Fox	290	1,995	2.10	7.6	4,1
March 18	do	506	3,830	3.67	11.0	13,(

Daily gage height, in feet, of Red River at Arthur City, Tex., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	4.3	4.5	8.0	9.2	12.4	23.3	9.2	13.7	6.7	6.0	6.7	9.3
.....	4.3	4.5	8.0	10.0	10.8	22.0	8.5	13.5	6.7	6.0	6.3	9.9
.....	4.2	4.5	8.0	14.5	10.0	21.0	8.0	13.0	6.0	14.5	6.0	9.3
.....	4.2	4.5	7.6	14.8	9.5	19.5	10.5	12.5	5.9	12.1	6.0	9.0
.....	4.2	4.5	6.3	14.6	9.5	18.0	10.8	9.2	5.7	11.0	5.8	8.8
.....	4.2	4.5	6.3	14.4	9.0	17.0	12.0	9.0	5.7	10.2	5.6	8.5
.....	4.2	4.5	6.3	14.0	9.0	15.0	12.5	8.8	5.7	9.8	9.5	8.3
.....	4.2	4.5	7.5	11.4	9.5	13.2	12.5	8.2	5.5	7.8	7.8	8.3
.....	4.2	4.5	8.9	10.4	9.2	12.0	19.5	8.0	5.5	7.1	7.2	7.7
.....	4.2	4.5	8.9	9.5	9.0	11.5	17.5	8.0	5.5	6.6	12.9	7.0
.....	4.8	4.5	8.9	9.0	9.0	10.4	14.5	7.4	5.6	6.6	12.7	6.8
.....	4.8	4.5	9.5	9.0	8.2	10.0	12.0	7.0	6.0	6.2	12.0	6.6
.....	4.8	4.5	9.0	8.0	8.2	9.8	11.0	8.0	11.6	6.2	11.4	6.5
.....	4.8	4.5	8.0	7.6	14.0	11.0	10.5	8.0	13.3	6.0	10.0	12.2
.....	5.3	4.5	9.4	7.6	14.4	10.5	10.5	8.0	11.5	6.0	11.7	17.2
.....	5.3	4.5	9.4	8.4	15.6	10.0	10.5	8.0	10.7	6.0	11.7	13.6
.....	5.3	4.5	7.6	8.4	15.0	9.6	10.2	9.8	10.4	6.0	11.2	12.0
.....	5.3	4.5	10.8	8.4	14.0	9.0	10.2	9.8	9.8	6.0	10.0	12.4
.....	5.6	4.6	13.0	10.0	12.5	8.8	10.7	9.5	9.5	10.0	8.7	11.4
.....	5.9	4.8	14.5	9.6	10.5	9.6	10.7	8.4	8.8	12.2	9.2	9.5
.....	5.9	4.8	15.5	9.6	16.0	12.0	11.0	9.0	8.2	8.5	8.0	15.0
.....	5.0	6.8	15.0	9.0	19.4	12.5	11.3	8.8	8.0	7.0	7.8	14.0
.....	4.5	6.8	11.7	9.3	21.2	12.5	13.2	8.6	7.8	7.0	7.8	13.4
.....	4.5	7.6	10.3	9.6	18.4	11.4	14.0	8.2	7.8	6.8	7.4	12.0
.....	4.5	9.0	9.6	14.8	21.6	11.4	14.2	8.0	7.6	9.9	9.0	11.6
.....	4.5	8.7	9.2	15.8	21.0	11.0	13.7	7.7	7.1	9.2	9.0	11.3
.....	4.5	8.4	8.7	15.8	18.0	9.5	13.7	7.6	7.0	8.0	9.0	9.0
.....	4.5	8.0	9.0	17.0	20.5	9.8	13.7	7.4	6.0	7.0	9.0	8.8
.....	4.5	.....	11.0	17.4	19.5	9.8	13.7	7.0	6.5	6.9	8.8	8.8
.....	4.5	.....	10.2	13.7	22.0	9.8	13.7	7.0	6.2	6.7	8.2	8.8
.....	4.5	.....	9.9	.....	25.0	.....	13.7	6.7	.....	6.7	.....	8.1

NORTH FORK OF RED RIVER NEAR GRANITE, OKLA.

station was established June 23, 1903, by Fred Bonstedt. It is located at the high-
idge 2 miles east and one-half mile north of Granite, Okla. The Chicago, Rock
nd Pacific Railway crosses the river near this point.

:hannel is straight for about 500 feet above the station and about 300 feet below.
anks are subject to overflow at flood stages. The bed of the stream is sandy and
:

iarge measurements are made from the bridge.

)riginal wire gage was replaced December 5, 1905, by a standard chain gage bolted
'encing on the upstream side of the bridge, 48 feet from the west end. Length of
21.16 feet. During 1905 the gage was read once each day by Elmer O. Tompkins.
ich mark is a United States Geological Survey standard iron post set 292 feet east
)ridge, near the south line of the highway; elevation, 10.64 feet above the datum of
'e and 1,539.8 feet above sea level.

'mation in regard to this station is contained in the following Water-Supply Papers
United States Geological Survey:

iption: 99, p 319; 131, pp 182-183.
arge: 99, p 319; 131, p 183.
heights: 99, p 320; 131, p 183.

Discharge measurements of North Fork of Red River near Granite, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
February 24	E. R. Kerby	192	391	3.23	6.50	1,265
April 12	do	32	34	.86	5.40	30
April 26	Murphy and Kerby	268	784	4.26	7.35	3,340
April 26	J. M. Giles	326	1,225	4.39	8.00	5,379
May 23	E. R. Kerby	101	134	1.99	6.10	266
May 24	J. M. Giles	87	76	1.90	5.80	144
June 9	E. R. Kerby	100	138	2.98	6.30	410
July 2	do	30	15	.82	5.50	12
July 11	do	12	11	.58	5.40	6.4
August 24	do	23	13	1.14	5.50	15
August 25	J. M. Giles	16	9.8	1.29	5.45	12.6
September 24	do	14	4.6	.59	5.20	2.7
September 27	E. R. Kerby	2.5	.5	1.00	5.10	.5
November 29	do	.....	86	1.62	6.10	139
December 5	do	.....	53	1.65	5.75	87
December 19	do	.....	45	1.59	6.05	72
(a)	J. M. Giles	.....	2,916	6.24	11.50	18,200
(a)	do	.....	2,100	5.11	9.50	10,730
(a)	do	.....	650	2.32	8.00	1,508
(a)	do	.....	240	1.58	7.00	380

[a] Computed from slope measurement, using Kutter's formula.

Daily gage height, in feet, of North Fork of Red River near Granite, Okla., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	.....	5.4	5.2	6.0	6.8	5.6	5.6	5.2	4.9	4.9	5.9
2	.....	.....	5.4	5.3	6.0	.....	5.5	5.5	5.1	5.0	4.9	5.9
3	.....	.....	5.3	5.3	5.9	.....	5.5	5.5	5.1	5.0	4.9	5.85
4	.....	.....	5.2	5.4	5.7	6.1	5.5	6.0	5.1	4.95	4.9	5.8
5	.....	.....	5.3	6.2	5.5	6.0	5.5	5.7	5.0	4.9	4.9	5.75
6	.....	.....	5.9	5.9	5.3	5.9	5.5	5.8	5.4	4.9	4.9	5.85
7	.....	.....	5.5	5.8	5.3	6.4	5.4	5.9	5.2	4.9	4.9	5.85
8	.....	.....	5.4	5.8	5.8	6.2	5.4	6.0	8.5	4.9	4.9	5.85
9	.....	.....	5.6	5.8	6.5	6.4	5.4	6.1	7.6	4.9	.....	5.8
10	.....	.....	5.9	6.3	6.1	6.2	5.4	6.2	7.5	4.9	6.0	5.8
11	.....	.....	5.7	6.1	5.9	6.2	5.3	5.8	6.4	4.9	6.8	5.85
12	.....	.....	5.6	5.8	5.7	6.1	5.3	6.0	6.0	4.9	6.1	5.85
13	.....	.....	5.6	5.6	5.6	6.0	5.3	7.8	6.0	4.9	6.05	6.0
14	.....	.....	5.6	5.4	5.5	6.1	5.3	7.0	6.05	4.9	6.0	6.05
15	.....	.....	5.7	5.4	5.4	6.0	5.3	6.8	5.9	4.9	6.0	6.4
16	.....	.....	5.9	5.4	5.7	5.9	5.4	6.5	5.65	4.9	5.95	6.15
17	.....	.....	7.7	5.3	5.4	5.9	5.4	6.2	5.5	4.9	5.85	6.1
18	.....	.....	6.5	5.3	5.3	5.8	5.4	.....	5.5	4.9	5.8	6.1
19	.....	.....	6.3	5.3	5.3	5.9	5.4	.....	5.45	4.9	.....	6.05
20	.....	.....	6.2	5.7	5.7	5.8	5.3	6.1	5.6	4.9	5.7	6.05
21	.....	.....	5.9	5.6	5.8	5.8	5.5	6.0	5.4	4.9	5.7	6.0
22	.....	.....	5.7	5.6	6.1	5.7	6.1	5.8	5.3	4.9	5.75	6.1
23	.....	8.1	5.6	5.8	6.0	5.6	5.9	5.6	5.2	4.9	5.8	6.15
24	5.0	6.5	5.4	6.2	5.8	5.6	5.6	5.5	5.2	4.9	8.85	.....
25	5.6	5.8	5.2	8.3	5.9	.....	5.5	5.5	5.2	4.9	7.5	.....
26	5.5	5.5	5.5	8.1	6.0	5.8	5.4	5.4	5.2	4.9	6.4	6.25
27	5.5	5.3	5.5	6.6	9.9	5.7	5.4	5.4	5.1	4.9	6.2	6.1
28	5.3	5.6	5.5	6.3	10.2	5.7	5.5	5.4	5.05	4.9	6.0	6.1
29	5.3	.....	5.3	6.0	7.4	5.6	5.6	5.4	5.0	4.9	5.9	6.1
30	5.5	.....	5.2	5.9	6.8	5.6	5.9	5.3	4.95	5.0	5.9	6.1
31	5.4	.....	5.1	.....	7.0	.....	5.7	5.3	.....	4.95	.....	.....

NORTH FORK OF RED RIVER NEAR SNYDER, OKLA.

This station was established April 14, 1905, and was discontinued July 31, 1905. It is located at the Frisco Railway bridge about 8 miles west of Snyder, Okla.

The channel is straight for 300 feet above and 1,000 feet below the station. The current is swift. The right bank is low and sandy, and overflows only under the railway trestle. The left bank is high and rocky and is not subject to overflow. The bed of the stream is composed of sand and is free from vegetation and shifting. There is but one channel, broken only by the pile bents, which are very close together, catching large quantities of drift during floods and making the current varying and uncertain.

Discharge measurements are made from the upstream side of the railroad bridge on trestle bents 14 feet apart. The initial point for soundings is the end of the upstream guard rail at the right bank.

A standard chain gage is attached to the downstream guard rail of the bridge; length of the chain, 18.65 feet. There are also two short sections of vertical gage fastened to the piles of the bridge. During 1905 the gage was read once each day by D. M. Deason. The bench mark is a cross on a rock on the left bank, 200 feet above the bridge; elevation, 7.04 feet above the datum of the gage.

Discharge measurements of North Fork of Red River near Snyder, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 14	E. R. Kerby	106	183	0.88	2.40	161
April 14	J. M. Giles	477	1,603	1.90	4.05	3,05
May 19	E. R. Kerby	182	224	.63	2.40	14
May 21	J. M. Giles	340	691	1.47	3.25	1,017
May 22	do	399	862	1.90	3.71	1,63
May 25	E. R. Kerby	162	330	1.78	2.90	58
May 30	do	357	2,203	3.43	4.15	7,56
June 1	J. M. Giles	480	1,978	1.58	4.35	3,12
June 13	E. R. Kerby	220	308	1.52	2.37	46
June 27	do	141	189	1.28	1.90	24
July 6	do	130	140	.81	1.50	11
July 7	do	131	146	.83	1.55	12
July 13	do	130	138	.94	1.65	13
July 14	do	130	136	.91	1.60	12
July 16	J. M. Giles	128	116	.69	1.50	8
July 20	do	125	99	.61	1.40	6
July 25	E. R. Kerby	145	200	1.48	2.00	29

Daily gage height, in feet, of North Fork of Red River near Snyder, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Day.	Apr.	May.	June.	July.
1	.....	2.8	4.2	1.9	17	2.3	.....	2.2	1.5
2	.....	2.7	3.9	1.9	18	2.4	.....	2.0	1.5
3	.....	.....	3.2	1.9	19	2.4	2.4	2.0	1.5
4	.....	.....	2.8	1.8	20	2.3	2.7	1.9	1.4
5	.....	.....	2.7	1.7	21	2.7	3.2	1.9	1.4
6	.....	.....	2.6	1.6	22	2.6	3.9	1.9	2.1
7	.....	.....	3.2	1.6	23	3.2	3.5	3.2	2.4
8	.....	.....	3.9	1.6	24	3.2	3.3	2.5	2.0
9	.....	.....	3.8	1.7	25	4.9	2.9	2.1	1.9
10	.....	.....	3.2	1.6	26	4.1	2.5	2.0	1.9
11	.....	.....	2.6	1.7	27	4.1	6.9	1.9	1.8
12	.....	4.3	2.5	1.6	28	3.5	6.6	1.9	1.7
13	.....	4.5	2.4	1.5	29	3.2	5.0	1.8	1.6
14	2.4	.....	2.4	1.5	30	3.1	4.2	1.9	1.5
15	2.3	.....	2.3	1.5	31	.....	4.5	.....	1.2
16	2.3	.....	2.2	1.5					

NORTH FORK OF RED RIVER NEAR HEADRICK, OKLA.

This station was established July 17, 1905. It is located at the Navajo dam site, about 4 miles northeast of Headrick and 8 miles west of Mountain Park, Okla.

The channel is straight for 200 feet above and 1,000 feet below the station. Both banks are high and clean and will not overflow. The bed of the stream is composed of sand and is shifting. There is but one channel at all except very low stages.

Discharge measurements are made by means of a cable and car about 100 yards above the gage. The initial point for soundings is a paint mark on the cable near the right end.

An inclined staff gage is fastened to the rock on the right bank. Above 6 feet the gage is painted on the rock. During 1905 the gage was read once each day by John Graves. The bench mark is a cross cut in the rock about 10 feet south of the gage; elevation, 8.40 feet above the datum of the gage.

harge measurements of North Fork of Red River near Headrick, Okla., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	J. M. Giles	49	67	1.00	2.00	67
.....	....do	74	108	.54	1.95	58
.....	E. R. Kerby	54	59	.92	1.95	54
.....	J. M. Giles	36	47	1.06	1.92	50
.....	E. R. Kerby	175	309	2.47	3.10	764
.....	....do	121	202	1.50	2.70	303
.....	....do	118	191	1.46	2.60	278
.....	....do	54	103	1.18	2.20	122
.....	....do	53	96	1.25	2.10	120
.....	....do	52	83	1.10	2.10	91
.....	....do	52	86	1.38	2.15	119
.....	....do	200	619	3.84	4.25	2,380
.....	....do	200	611	3.56	4.20	2,174
.....	....do	200	600	3.54	4.25	2,126
.....	....do	200	618	3.18	4.22	1,965
.....	....do	190	443	2.16	3.72	960
.....	....do	80	295	1.43	3.30	422
.....	....do	95	71	1.18	2.25	84
.....	....do	70	58	1.09	2.10	63
5	....do	27	41	.61	1.90	25
13	....do	86	318	1.16	3.10	368
13	....do	86	310	1.08	3.00	335
18	....do	83	259	.53	2.50	133
20	....do	83	274	.71	2.75	196
20	....do	83	266	.62	2.65	165
21	J. M. Giles	84	259	.48	2.60	125
29	E. R. Kerby	26	81	.55	2.20	44
.....	....do	26	82	.56	2.20	46
.....	....do	26	82	.59	2.20	48
.....	....do	29	16	1.32	2.10	21
.....	....do	30	20	1.25	2.10	25
.....	....do	20	20	1.10	2.10	22
11	....do	.....	389	2.78	3.80	1,082
13	....do	.....	241	1.13	3.00	272
24	....do	.....	222	1.30	2.80	288
27	....do	.....	373	1.38	3.20	514
8	J. M. Giles	.....	306	.40	2.60	121
16	E. R. Kerby	.....	314	.99	3.00	312
22	....do	.....	264	.86	2.85	226
27	....do	.....	255	.78	2.70	198

Daily gage height, in feet, of North Fork of Red River near Headrick, Okla., for 1905.

Day.	July.	Aug.	Sept.	Oct.	Nov	Dec.	Day.	July.	Aug.	Sept.	Oct.	Nov	Dec.
1		2.8	2.0	2.2	2.	2.6	17		3.2	2.6	2.1	2.7	2.7
2		2.5	2.0	2.2	2.	2.6	18	2.0	3.0	2.5	2.1	2.7	2.7
3		2.3	1.9	2.2	2.	2.6	19	2.0	3.5	2.4	2.1	2.5	2.6
4		2.	1.9	2.2	2.	2.6	20	1.9	3.0	2.6	2.1	2.4	2.6
5		2.	2.	2.2	3.0	2.6	21	1.8	2.	2.7	2.1	2.4	2.6
6		2.8	2.	2.	2.	2.6	22	2.5	2.	2.5	2.1	2.4	2.6
7		2.	2.2	2.	2.	2.6	23	3.0	2.5	2.5	2.1	2.4	2.6
8		2.8	2.	2.	2.	2.6	24	2.	2.4	2.5	2.1	2.8	2.6
9		2.3	3.	2.	3.0	2.6	25	2.5	2.3	2.3	2.1	3.8	2.6
10		2.1	4.45	2.	3.1	2.6	26	2.8	2.2	2.3	2.1	2.6	2.6
11		2.1	3.	2.	3.8	2.5	27	2.4	2.0	2.2	2.1	3.2	2.7
12		2.2	3.5	2.	3.1	2.5	28	2.3	2.0	2.2	2.1	2.2	2.7
13		2.6	3.	2.	3.1	2.7	29	2.3	2.0	2.2	2.1	2.6	2.6
14		4.6	2.9	2.	2.8	2.7	30	2.4	1.9	2.2	2.1	2.6	2.6
15		4.2	2.	2.	2.7	2.7	31	2.8	2.0		2.1		2.6
16		3.7	2.	2.	2.7	3.0							

Daily discharge, in second-feet, of North Fork of Red River near Headrick, Okla., for 1905.

Day.	July.	Aug.	Sept.	Oct.	Nov.	Dec.	Day.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1		425	50	46	25	190	17		430	150	24	240	230
2		220	50	46	26	180	18	67	300	130	24	240	230
3		140	30	46	26	170	19	67	720	110	24	160	200
4		80	25	46	26	160	20	50	300	150	24	125	200
5		80	60	43	340	150	21	35	190	175	24	125	200
6		425	75	40	125	140	22	220	155	130	24	125	200
7		180	75	37	75	130	23	630	115	130	24	125	200
8		425	90	31	125	120	24	275	100	130	24	290	190
9		140	840	31	340	120	25	220	85	75	24	1,080	180
10		95	3,300	27	150	120	26	425	75	75	24	200	180
11		95	975	24	1,080	100	27	180	65	50	24	515	190
12		110	720	21	360	100	28	140	65	45	24	75	190
13		275	370	21	360	170	29	140	65	45	24	200	170
14		4,900	270	21	290	170	30	180	62	45	24	200	170
15		2,050	220	24	240	170	31	425	65		24		170
16		970	175	24	240	320							

NOTE.—On account of shifting conditions, the daily discharge has been computed from several rating tables, each covering a short period of time.

Estimated monthly discharge of North Fork of Red River near Headrick, Okla., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
July 18–31	630	35	218	6,05[illegible]
August	4,900	62	432	26,5[illegible]
September	3,300	25	292	17,3[illegible]
October	46	21	28.6	1,7[illegible]
November	1,080	25	251	14,9[illegible]
December	320	100	175	10,7[illegible]
The period				77,[illegible]

ELM FORK OF RED RIVER NEAR MANGUM, OKLA.

on was established April 12, 1905. It is located on the highway bridge about 4 of Mangum, Okla.

nel is straight for about 500 feet above and 200 feet below the bridge. The wift. Both banks are low and liable to overflow. The bed of the stream is sand and is shifting. There is but one channel, broken by the pile bents of which catch and hold drift badly during high water.

measurements are made from the upstream side of the pile bent bridge. The for soundings is at the north end of the bridge.

d chain gage is fastened to the bridge; length of chain, 24.58 feet. During e was read once each day by E. R. Pierson. Bench marks were established as An iron pin driven flush with the surface 59 feet south and 7 feet west of the the bridge; elevation, 14.30 feet (2) A paint mark on the top of the bridge south of the gage; elevation, 18.46 feet. Elevations refer to the datum of the

rge measurements of Elm Fork of Red River near Mangum, Okla., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
E. R. Kerby	40	18	0.72	2.00	13
Murphy and Kerby	190	248	1.96	3.56	487
E. R. Kerby	130	105	1.46	2.90	153
J. M. Giles	242	589	2.28	4.70	1,346
do	143	145	1.26	2.90	183
do	151	167	1.55	3.30	259
do	226	321	1.84	3.88	592
do	310	1,404	4.74	8.35	6,648
do	312	1,722	5.38	9.30	9,271
E. R. Kerby	276	581	3.08	5.40	1,791
do	53	34	1.48	2.60	49
do	62	52	1.46	2.80	76
do	62	46	1.40	2.70	64
J. M. Giles	98	102	1.53	3.16	156
E. R. Kerby	53	21	1.15	2.40	24
J. M. Giles	42	16	.87	2.30	14
E. R. Kerby	32	14	1.14	2.30	16
do	32	14	1.17	2.30	16
do		33	1.33	2.40	44
do		35	1.20	2.30	43
do		24	1.09	2.40	26
J. M. Giles		893	2.43	5.40	2,175
do		3,000	480	11.50	14,400

[a] Computed from slope measurement, using Kutter's formula.

Daily gage height, in feet, of Elm Fork of Red River near Mangum, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1		2.4	3.7	2.6	2.5	2.3	2.2	2.4	2
2		2.3	3.2	2.6	2.5	2.3	2.2	2.3	2
3		2.2	3.2	2.6	2.5	2.3	2.2	2.3	2
4		2.2	3.0	2.6	3.0	2.3	2.2	2.3	2
5		2.2	3.0	2.6	2.6	2.3	2.3	3.0	2
6		2.2	2.9	2.5	2.5	2.4	2.3	2.6	2
7		2.3	5.9	2.5	2.7	2.4	2.3	2.7	2
8		2.3	4.5	2.5	3.1	2.4	2.3	2.6	2
9		2.3	3.5	2.5	2.6	3.0	2.3	4.2	2
10		2.5	3.0	2.7	2.5	3.4	2.3	4.4	2
11		2.3	3.0	2.7	2.5	2.8	2.3	2.9	2
12	2.0	2.3	2.9	2.6	2.4	2.5	2.3	2.7	2
13	2.0	3.5	2.8	2.5	3.9	2.5	2.2	2.5	
14	1.9	3.2	2.9	2.5	4.8	2.5	2.2	2.4	
15	1.8	2.5	2.8	2.5	3.2	2.4	2.2	2.4	
16	1.9	2.2	2.8	2.5	2.8	2.4	2.2	2.4	
17	2.0	2.1	2.7	2.4	2.7	2.3	2.3	2.4	
18	2.2	2.0	2.7	2.4	2.6	2.3	2.3	2.3	
19	2.9	2.2	2.7	2.6	2.5	3.2	2.2	2.3	
20	2.5	2.9	2.7	2.4	2.5	2.4	2.2	2.3	
21	2.3	3.9	2.6	2.4	2.4	2.4	2.2	2.4	
22	2.1	3.7	5.6	3.2	2.4	2.3	2.2	2.3	
23	2.1	3.0	3.7	2.7	2.4	2.3	2.2	2.5	
24	4.7	2.6	3.1	4.2	2.4	2.3	2.2	4.6	
25	5.4	4.0	2.9	3.4	2.3	2.3	2.2	3.2	
26	3.6	3.9	2.6	2.8	2.3	2.3	2.2	2.7	
27	2.9	11.6	2.6	2.7	2.3	2.3	2.2	2.5	
28	2.6	4.9	2.7	2.6	2.3	2.3	2.2	2.4	
29	2.4	3.7	2.6	3.0	2.3	2.2	2.2	2.4	
30	2.6	3.5	2.6	2.9	2.3	2.2	2.3	2.4	
31		5.1		2.6	2.3		2.3		

ischarge, in second feet, of Elm Fork of Red River near Mangum, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	65	550	50	37	14	9	25	41
.....	.....	50	260	50	37	14	9	16	41
.....	.....	37	260	50	37	14	9	16	41
.....	.....	37	195	50	120	14	9	16	41
.....	.....	37	195	50	50	14	16	120	41
.....	.....	37	165	37	37	25	16	50	41
.....	.....	50	2,500	37	65	25	16	65	41
.....	.....	50	1,150	37	140	25	16	50	41
.....	.....	300	400	37	50	120	16	900	41
.....	.....	80	195	65	37	225	16	1,100	41
.....	.....	50	195	65	37	80	16	100	41
.....	16	50	165	50	25	37	16	65	41
.....	16	400	140	37	680	37	9	37	120
.....	10	260	165	37	1,400	37	9	25	90
.....	7	80	140	37	165	25	9	25	23
.....	10	37	140	37	80	25	9	25	20
.....	16	26	120	25	65	14	16	25	20
.....	37	16	120	25	50	14	16	16	20
.....	165	37	120	50	37	165	9	16	20
.....	82	165	120	25	37	25	9	16	20
.....	50	680	100	25	25	25	9	25	20
.....	26	550	2,150	165	25	14	9	16	20
.....	26	195	550	65	25	14	9	37	23
.....	1,350	100	225	900	25	14	9	1,250	23
.....	1,850	750	165	350	14	14	9	200	20
.....	500	680	100	80	14	14	9	92	20
.....	165	14,600	100	65	14	14	9	58	20
.....	100	1,500	120	50	14	14	9	48	20
.....	65	550	100	120	14	7	9	44	20
.....	100	400	100	100	14	7	16	44	20
.....	.....	1,700	.....	50	14	.....	16	.....	20

On account of shifting conditions the low-water discharge was computed from several rating he high-water discharge was computed from current-meter and slope measurements.

ated monthly discharge of Elm Fork of Red River near Mangum, Okla., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
).....	1,850	7	242	9,120
.....	14,600	16	760	46,730
.....	2,500	100	367	21,840
.....	900	25	91.0	5,595
.....	1,400	14	109	6,702
.....	225	7	36.2	2,154
.....	16	9	11.7	719
.....	1,250	16	151.	8,985
.....	120	20	33.9	2,084
period.....				103,900

ELK CREEK NEAR HOBART, OKLA.

This station was established April 13, 1905. It is located at the highway bridge abo miles south of Hobart, Okla. The station 3 miles southwest of Hobart, estab lished Sept ber 22, 1904, was continued until this station was established. The 1905 gage heights at old station have been referred to the datum of the new one by adding 0.4 foot.

The channel is straight for 200 feet above and 100 feet below the station. The curre swift and is oblique to the bridge. Both banks are high and wooded. The right bank o flows during extreme high water. The bed of the stream is composed of sand and gr with very little vegetation and is slightly shifting. There is one channel at all stages u 20 feet, and two channels at higher stages.

Discharge measurements are made from the downstream side of the bridge. The ini point is at the east end of the bridge, marked with paint.

A standard chain gage is fastened to the bridge; length of chain, 33.45 feet. During l the gage was read once each day by G. W. Hines. Bench marks were established as follc (1) A standard bench-mark post three-fourths of a mile east of the bridge, 1,459.00 above mean sea level and 28.44 feet above the datum of the gage. (2) A paint mark on downstream end of a bridge beam near the center of the bridge, 1,459.14 feet above mean level and 28.58 feet above the datum of the gage.

Discharge measurements of Elk Creek near Hobart, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D cha
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Sec f*
January 29	E. R. Kerby	16	14	0.71	2.00	
February 24	Whittington and Kerby	16	33	1.02	2.90	
April 13	E. R. Kerby	20	9.5	2.43	2.30	
April 26	J. M. Giles	21	75	2.66	5.60	
April 27	Murphy and Kerby	19.5	30	2.22	3.76	
May 23	J. M. Giles	17	21	1.81	3.00	
May 31	do	33	148	2.60	8.57	
May 31	do	33	151	2.68	8.65	
July 7	E. R. Kerby	17	11	2.11	2.50	
July 12	do	16	11	2.00	2.50	
July 26	J. M. Giles	14	11	2.00	2.55	
July 26	do	16	10	1.99	2.52	
August 3	E. R. Kerby	14	8	1.50	2.25	
August 25	do	14	8	1.75	2.30	
September 14	do	17	14	1.80	2.65	
September 19	do	16	8	1.63	2.30	
September 23	J. M. Giles	18	13	.85	2.25	
September 28	E. R. Kerby	15	7	1.66	2.20	
October 14	do	11	4.2	1.48	2.10	
October 26	do	11	4.2	1.47	2.20	
November 28	do	.....	13	1.39	2.50	
December 28	do	.....	14	1.25	2.50	

Daily gage height, in feet, of Elk Creek near Hobart, Okla., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.3	2.3	2.2	2.2	3.1	10.9	2.7	2.2	2.2	2.2	2.2	2.3
2	2.3	2.3	2.2	2.2	2.5	5.3	2.7	2.3	2.2	2.2	2.2	2.3
3	2.3	2.3	2.2	2.4	2.3	4.2	2.7	2.3	2.3	2.2	2.2	2.3
4	2.3	2.3	2.2	2.4	2.3	4.3	2.6	2.2	2.2	2.2	2.7	2.3
5	2.3	2.3	2.3	2.4	2.2	4.1	2.6	2.2	2.2	2.2	2.4	2.3
6	2.3	2.3	6.4	2.4	2.1	4.2	2.5	2.2	2.2	2.2	2.4	2.3
7	2.3	2.3	4.4	2.3	2.1	4.1	2.5	2.3	2.2	2.2	2.8	2.3
8	2.3	2.3	3.1	2.2	2.2	8.5	2.6	2.3	2.6	2.2	2.5	2.3
9	2.3	2.3	2.8	2.2	2.2	4.6	2.7	2.3	10.1	2.2	2.5	2.4
10	2.3	2.3	2.6	7.9	3.2	4.2	3.9	2.2	7.0	2.2	2.4	2.4
11	2.5	2.3	2.4	3.4	2.2	3.9	3.2	2.2	3.9	2.2	2.3	2.4
12	2.5	2.3	2.3	2.8	2.4	3.4	2.9	2.2	3.0	2.1	2.3	2.4
13	2.5	2.3	2.3	2.3	2.2	3.5	2.8	2.2	2.8	2.1	2.3	2.5
14	2.5	2.3	2.3	2.3	3.0	3.4	2.7	8.2	2.7	2.1	2.3	2.5
15	2.5	2.3	2.2	2.2	2.5	3.4	2.5	13.5	2.6	2.1	2.3	2.5
16	2.5	2.3	2.5	2.1	3.0	3.3	2.4	5.4	2.5	2.1	2.3	2.6
17	2.5	2.4	2.9	2.0	2.1	3.3	2.4	3.4	2.5	2.2	2.3	2.6
18	2.5	2.4	7.1	2.2	2.1	3.1	2.3	3.3	2.5	2.2	2.3	2.6
19	2.5	2.4	5.9	2.2	2.0	3.1	2.3	2.9	2.3	2.2	2.3	2.5
20	2.5	2.4	4.4	2.1	2.0	3.0	2.3	2.8	2.3	2.2	2.3	2.5
21	2.5	2.4	3.5	2.0	4.2	3.0	2.2	2.6	2.3	2.1	2.3	2.5
22	2.5	2.4	3.0	2.0	3.9	3.0	4.3	2.5	2.3	2.1	2.3	2.5
23	2.4	4.4	2.6	2.1	2.6	2.9	4.0	2.4	2.2	2.1	3.4	2.5
24	2.4	3.4	2.4	6.2	2.3	2.9	3.4	2.4	2.2	2.2	3.4	2.5
25	2.4	3.0	2.3	13.2	2.3	2.8	2.9	2.3	2.2	2.2	3.3	2.5
26	2.4	2.4	2.3	8.1	7.0	2.8	2.5	2.3	2.2	2.2	3.3	2.5
27	2.4	2.4	2.3	3.6	16.5	2.8	2.4	2.3	2.2	2.2	2.5	2.5
28	2.4	2.2	2.2	3.0	24.2	2.7	2.3	2.2	2.2	2.3	2.5	2.6
29	2.4	.....	2.2	2.7	21.9	2.7	2.2	2.2	2.2	2.3	2.4	2.6
30	2.3	.....	2.1	3.3	6.4	2.7	2.2	2.2	2.2	2.3	2.4	2.6
31	2.3	.....	2.2	.....	9.2	.....	2.2	2.2	.....	2.3	.....	2.6

OTTER CREEK NEAR MOUNTAIN PARK, OKLA.

This station was established April 2, 1903, by G. H. Matthes. It is located on G. M. Dale's homestead, in the SE. ¼ sec. 21, T. 3 N., R. 17 W. of the Indian meridian. It is 2 miles west and 1 mile north of Mountain Park, Okla.

The channel is slightly curved both above and below the station. Both banks are about 20 feet high, of sandy loam, covered with vegetation, and subject to overflow. The bed of the stream is of sand and is liable to shift. The water flows in one channel at normal stages, but when about to overflow its banks part of the water is diverted through a slough into Horse Creek.

Discharge measurements are made by wading at low stage and from a cable about 100 yards below the gage at ordinary and flood stages.

The gage is a staff fastened to a cottonwood tree which stands at the water's edge. During 1905 the gage was read once each day by G. M. Dale. Bench marks were established as follows: (1) A 20-penny nail driven into the cottonwood tree to which the gage is attached; elevation, 10.00 feet. (2) A nail driven into a mesquite tree 150 feet southwest of G. M. Dale's house; elevation, 28.62 feet. (3) A nail driven into a hackberry tree 50 feet east of the creek and 20 feet north of the gage; elevation, 8.94 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 316–317; 131, p 185.
Discharge: 99, p 317; 131, p 185.
Discharge, monthly: 99, p 319; 131, p 187.
Gage heights: 99, 317–318; 131, p 186.
Rating table: 99, p, 318

Discharge measurements of Otter Creek near Mountain Park, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 30	E. R. Kerby	5	0.75	1.00	1.00	0.75
February 25	do	7	2.5	.80	1.20	2.0
April 19	do	9	4	1.35	1.20	5.4
May 13	do	61	746	2.37	13.30	1,772
May 14	do	29	71	1.86	3.30	133
May 17	do	19	18	1.38	1.70	25
May 20	Kerby and Osburne	54	448	2.97	11.00	1,332
May 22	J. M. Giles	53	364	1.53	6.50	556
May 24	E. R. Kerby	18	22	1.84	2.00	39
May 31	do	52	409	1.79	7.40	732
June 1	J. M. Giles	33	95	1.36	2.95	129
June 28	E. R. Kerby	19	7	1.20	1.20	8
July 6	do	15	5	.86	1.20	4.3
July 6	do	6	3.7	1.16	1.20	4.3
July 8	do	13	4.5	1.20	1.25	5.4
July 13	do	12	5.4	.91	1.20	5.0
July 15	do	12	5.4	1.00	1.25	5.4
July 15	J. M. Giles	12	4.0	.86	1.20	3.4
July 19	E. R. Kerby	12	4.0	.75	1.15	3.0
July 20	do	12	5	.76	1.20	3.8
July 21	J. M. Giles	5	2.9	.82	1.15	2.4
July 22	do	23	14	1.35	1.62	19
July 24	E. R. Kerby	18	13.5	1.41	1.50	19
July 26	do	12	5.1	1.08	1.20	5.6
July 27	do	12	5.2	1.12	1.20	5.8
August 3	do	10	2.9	1.08	1.15	3.1
August 8	do	7	3.9	.67	1.10	2.6
August 10	do	7	4.4	.70	1.10	3.1
August 20	do	5.5	1.7	1.05	1.10	1.8
August 27	do	5	1.4	.94	1.00	1.3
August 29	do	5	2.1	.28	1.0	.6
September 4	do	3	.6	1.00	.95	.6
September 12	do	5.5	1.5	.90	1.20	1.
September 15	do	5.5	1.5	.87	1.15	1.
September 18	do	3	.6	1.00	1.10	
September 21	J. M. Giles	1.6	.3	.65	1.00	
September 29	E. R. Kerby	3	.6	1.00	1.00	
October 3	do	3	.6	1.00	1.00	
October 5	do	3	.6	1.00	1.00	
October 12	do	3	.6	1.00	1.00	
October 15	do	3	.6	1.00	1.00	a
October 21	do	3	.6	1.00	1.00	a
November 11	do	27	16	.81	1.60	13
November 12	do	27	15	.80	1.50	12
November 24	do	10	6	1.00	1.40	6

a Float measurement.

Daily gage height, in feet, of Otter Creek near Mountain Park, Okla., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.9	1.1	1.1	5.2	1.6	3.0	1.4	1.1	1.0	1.0	1.1	1.2
.....	.9	1.1	1.1	3.8	1.5	2.4	1.3	1.1	1.0	1.1	1.1	1.2
.....	.9	1.1	1.1	2.0	1.5	2.0	1.2	1.2	1.0	1.1	1.1	1.2
.....	.9	1.1	1.1	1.6	1.5	1.8	1.2	1.3	1.0	1.1	1.2	1.1
.....	.9	1.1	1.1	1.5	1.4	1.7	1.2	1.2	1.0	1.1	1.9	1.1
.....	.9	1.1	1.1	1.7	1.4	1.5	1.2	1.2	1.1	1.1	1.5	1.1
.....	.9	1.1	1.3	1.5	1.4	1.5	1.2	1.2	1.1	1.1	1.3	1.1
.....	.9	1.1	1.3	1.3	1.4	1.5	1.2	1.2	1.1	1.1	1.3	1.1
.....	1.0	1.1	1.3	1.3	1.45	1.5	2.0	1.1	1.3	1.1	2.5	1.1
.....	1.0	1.2	1.2	1.2	1.5	1.5	1.5	1.1	1.2	1.1	2.5	1.1
.....	1.0	1.2	1.2	1.1	5.0	1.5	1.3	1.1	1.2	1.1	1.8	1.1
.....	1.0	1.2	1.2	1.1	12.0	1.5	1.3	1.1	1.2	1.1	1.4	1.1
.....	1.0	1.1	1.1	1.1	13.1	1.5	1.3	2.9	1.2	1.0	1.3	1.4
.....	1.0	1.1	1.1	1.0	4.1	1.4	1.2	1.8	1.2	1.0	1.3	1.3
.....	1.0	1.1	1.8	1.0	2.4	1.4	1.2	1.5	1.2	1.0	1.2	1.3
.....	1.0	1.1	2.15	1.0	1.9	1.4	1.2	1.3	1.2	1.0	1.2	1.3
.....	1.1	1.2	2.45	1.0	1.7	1.4	1.2	1.2	1.1	1.0	1.2	1.3
.....	1.2	1.3	2.6	1.2	1.6	1.4	1.2	1.2	1.1	1.0	1.2	1.2
.....	1.1	1.3	1.7	1.2	1.6	1.3	1.2	1.1	1.1	1.0	1.1	1.2
.....	1.1	1.3	1.4	1.2	8.4	1.3	1.2	1.1	1.1	1.0	1.2	1.2
.....	1.1	1.2	1.2	1.1	4.8	1.3	1.1	1.1	1.1	1.0	1.2	1.2
.....	1.1	1.2	1.2	1.1	5.9	1.3	2.4	1.1	1.0	1.0	1.2	1.2
.....	1.0	1.2	1.1	2.7	3.0	1.3	1.5	1.1	1.0	1.0	1.2	1.2
.....	1.0	1.3	1.1	7.8	2.3	1.3	1.5	1.1	1.0	1.1	1.3	1.2
.....	1.0	1.2	1.1	14.0	2.3	1.3	1.3	1.0	1.0	1.1	1.3	1.2
.....	1.0	1.2	1.1	5.0	2.6	1.3	1.3	1.0	1.0	1.1	1.2	1.2
.....	1.0	1.1	1.1	2.8	19.3	1.3	1.2	1.0	1.0	1.1	1.2	1.2
.....	1.0	1.1	1.1	2.1	6.0	1.2	1.2	1.0	1.0	1.1	1.2	1.2
.....	1.0	.....	1.2	1.8	3.2	1.2	1.1	1.0	1.0	1.1	1.2	1.2
.....	1.0	.....	1.1	1.7	8.3	1.2	1.1	1.0	1.0	1.1	1.2	1.2
.....	1.1	.....	1.1	.....	6.5	.....	1.1	1.0	.....	1.1	.....	1.2

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 316–317; 131, p 185.
Discharge: 99, p 317; 131, p 185.
Discharge, monthly: 99, p 319; 131, p 187.
Gage heights: 99, 317–318; 131, p 186.
Rating table: 99, p, 318

Discharge measurements of Otter Creek near Mountain Park, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 30	E. R. Kerby	5	0.75	1.00	1.00	0.75
February 25	do	7	2.5	.80	1.20	2.0
April 19	do	9	4	1.35	1.20	5.4
May 13	do	61	746	2.37	13.30	1,772
May 14	do	29	71	1.86	3.30	133
May 17	do	19	18	1.38	1.70	25
May 20	Kerby and Osburne	54	448	2.97	11.00	1,332
May 22	J. M. Giles	53	364	1.53	6.50	556
May 24	E. R. Kerby	18	22	1.84	2.00	39
May 31	do	52	409	1.79	7.40	732
June 1	J. M. Giles	33	95	1.36	2.95	129
June 28	E. R. Kerby	19	7	1.20	1.20	8
July 6	do	15	5	.86	1.20	4.3
July 6	do	6	3.7	1.16	1.20	4.3
July 8	do	13	4.5	1.20	1.25	5.4
July 13	do	12	5.4	.91	1.20	5.0
July 15	do	12	5.4	1.00	1.25	5.4
July 15	J. M. Giles	12	4.0	.86	1.20	3.4
July 19	E. R. Kerby	12	4.0	.75	1.15	3.0
July 20	do	12	5	.76	1.20	3.8
July 21	J. M. Giles	5	2.9	.82	1.15	2.4
July 22	do	23	14	1.35	1.62	19
July 24	E. R. Kerby	18	13.5	1.41	1.50	19
July 26	do	12	5.1	1.08	1.20	5.6
July 27	do	12	5.2	1.12	1.20	5.8
August 3	do	10	2.9	1.08	1.15	3.1
August 8	do	7	3.9	.67	1.10	2.6
August 10	do	7	4.4	.70	1.10	3.1
August 20	do	5.5	1.7	1.05	1.10	1.8
August 27	do	5	1.4	.94	1.00	1.3
August 29	do	5	2.1	.28	1.0	.6
September 4	do	3	.6	1.00	.95	.6
September 12	do	5.5	1.5	.90	1.20	1.4
September 15	do	5.5	1.5	.87	1.15	1.3
September 18	do	3	.6	1.00	1.10	[a].6
September 21	J. M. Giles	1.6	.3	.65	1.00	.2
September 29	E. R. Kerby	3	.6	1.00	1.00	[a].6
October 3	do	3	.6	1.00	1.00	[a].6
October 5	do	3	.6	1.00	1.00	[a].6
October 12	do	3	.6	1.00	1.00	
October 15	do	3	.6	1.00	1.00	[illegible]
October 21	do	3	.6	1.00	1.00	[illegible]
November 11	do	27	16	.81	1.60	13
November 12	do	27	15	.80	1.50	12
November 24	do	10	6	1.00	1.40	6

[a] Float measurement.

Daily gage height, in feet, of Otter Creek near Mountain Park, Okla., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.9	1.1	1.1	5.2	1.6	3.0	1.4	1.1	1.0	1.0	1.1	1.2
.....	.9	1.1	1.1	3.8	1.5	2.4	1.3	1.1	1.0	1.1	1.1	1.2
.....	.9	1.1	1.1	2.0	1.5	2.0	1.2	1.2	1.0	1.1	1.1	1.2
.....	.9	1.1	1.1	1.6	1.5	1.8	1.2	1.3	1.0	1.1	1.2	1.1
.....	.9	1.1	1.1	1.5	1.4	1.7	1.2	1.2	1.0	1.1	1.9	1.1
.....	.9	1.1	1.1	1.7	1.4	1.5	1.2	1.2	1.1	1.1	1.5	1.1
.....	.9	1.1	1.3	1.5	1.4	1.5	1.2	1.2	1.1	1.1	1.3	1.1
.....	.9	1.1	1.3	1.3	1.4	1.5	1.2	1.2	1.1	1.1	1.3	1.1
.....	1.0	1.1	1.3	1.3	1.45	1.5	2.0	1.1	1.3	1.1	2.5	1.1
.....	1.0	1.2	1.2	1.2	1.5	1.5	1.5	1.1	1.2	1.1	2.5	1.1
.....	1.0	1.2	1.2	1.1	5.0	1.5	1.3	1.1	1.2	1.1	1.8	1.1
.....	1.0	1.2	1.2	1.1	12.0	1.5	1.3	1.1	1.2	1.1	1.4	1.1
.....	1.0	1.1	1.1	1.1	13.1	1.5	1.3	2.9	1.2	1.0	1.3	1.4
.....	1.0	1.1	1.1	1.0	4.1	1.4	1.2	1.8	1.2	1.0	1.3	1.3
.....	1.0	1.1	1.8	1.0	2.4	1.4	1.2	1.5	1.2	1.0	1.2	1.3
.....	1.0	1.1	2.15	1.0	1.9	1.4	1.2	1.3	1.2	1.0	1.2	1.3
.....	1.1	1.2	2.45	1.0	1.7	1.4	1.2	1.2	1.1	1.0	1.2	1.3
.....	1.2	1.3	2.6	1.2	1.6	1.4	1.2	1.2	1.1	1.0	1.2	1.2
.....	1.1	1.3	1.7	1.2	1.6	1.3	1.2	1.1	1.1	1.0	1.1	1.2
.....	1.1	1.3	1.4	1.2	8.4	1.3	1.2	1.1	1.1	1.0	1.2	1.2
.....	1.1	1.2	1.2	1.1	4.8	1.3	1.1	1.1	1.1	1.0	1.2	1.2
.....	1.1	1.2	1.2	1.1	5.9	1.3	2.4	1.1	1.0	1.0	1.2	1.2
.....	1.0	1.2	1.1	2.7	3.0	1.3	1.5	1.1	1.0	1.0	1.2	1.2
.....	1.0	1.3	1.1	7.8	2.3	1.3	1.5	1.1	1.0	1.1	1.3	1.2
.....	1.0	1.2	1.1	14.0	2.3	1.3	1.3	1.0	1.0	1.1	1.3	1.2
.....	1.0	1.2	1.1	5.0	2.6	1.3	1.3	1.0	1.0	1.1	1.2	1.2
.....	1.0	1.1	1.1	2.8	19.3	1.3	1.2	1.0	1.0	1.1	1.2	1.2
.....	1.0	1.1	1.1	2.1	6.0	1.2	1.2	1.0	1.0	1.1	1.2	1.2
.....	1.0	.....	1.2	1.8	3.2	1.2	1.1	1.0	1.0	1.1	1.2	1.2
.....	1.0	.....	1.1	1.7	8.3	1.2	1.1	1.0	1.0	1.1	1.2	1.2
.....	1.1	.....	1.1	.....	6.5	.....	1.1	1.0	.....	1.1	.....	1.2

Daily discharge in second-feet, of Otter Creek near Mountain Park, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	384	24	120	14	3	0.6	0.6	1	
2	208	20	64	10	3	.6	1	1	
3	37	19	37	5	4	.6	1	1	
4	28	19	37	5	6	.6	1	3	
5	23	13	32	4	4	.6	1	30	
6	33	13	21	5	4′	1	1	10	
7	23	13	21	6	4	1	1	4	
8	13	13	21	4	4	1	1	4	
9	13	15	21	37	3	3	1	72	
10	9	17	21	15	3	2	1	72	
11	6	357	21	7	3	2	1	24	
12	6	1,525	21	7	3	1	1	8	
13	6	1,730	21	8	110	1	.6	5	
14	3	243	16	5	28	2	.6	5	
15	4	64	16	4	13	2	.6	3	
16	3	36	16	3	6	2	.6	3	
17	4	25	16	4	3	.6	.6	3	
18	9	20	16	3	3	.6	.6	3	
19	9	20	12	4	2	.6	.6	1	
20	9	880	12	4	2	.6	.6	3	
21	6	330	12	2	2	.6	.6	2	
22	6	480	12	64	2	.3	.6	2	
23	90	120	12	16	2	.4	.6	2	
24	775	56	12	19	2	.5	1	4	
25	1,900	56	12	9	1	.5	1	4	
26	357	80	12	9	1	.5	1	2	
27	100	2,910	12	7	1	.6	1	2	
28	43	495	8	6	.8	.6	1	2	
29	36	141	8	4	.6	.6	1	2	
30	30	860	7	3	.6	.6	1	2	
31	.....	570	.....	3	.6	.....	1	.....	

NOTE.—The daily discharge was obtained by indirect method. As no measurements were prior to April 1 no estimates were made for that period.

Estimated monthly discharge of Otter Creek near Mountain Park, Okla., for 1905.

[Drainage area, 126 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dep in
April	1,900	3	139	8,271	1.10	
May	2,910	13	360	22,140	2.86	
June	120	7	22.3	1,327	.177	
July	64	2	9.5	584	.075	
August	110	.6	7.2	443	.057	
September	3	.3	.95	57	.0075	
October	1	.6	.85	52	.0067	
November	72	1	9.3	553	.074	
December	6	1	2.1	129	.017	
The period	.....	.....	.....	33,560	.....	

HORSE CREEK NEAR MOUNTAIN PARK, OKLA.

This station was established April 17, 1905. It is located 5 miles north of Mountain Park, in the SE. ¼ sec. 1, T. 3 N., R. 17 W., of the Indian meridian.

The channel is straight for 50 feet above and 200 feet below the station. The current is sluggish. Both banks are low, covered with grass and weeds, and subject to overflow during high water. The bed of the stream is composed of firm earth, covered with vegetation, and is fairly permanent. There is but one channel.

Discharge measurements are made by wading near the gage. At high water measurements are made by means of a boat.

The gage is a staff with an auxiliary gage 600 feet downstream from the regular gage, for determining the slope of the stream. During 1905 the gage was read once each day by John S. Cundiff, when the stream was flowing. The bench mark is a nail driven into the elm tree to which the gage is fastened; elevation, 5.65 feet above the datum of the gage.

Discharge measurements of Horse Creek near Mountain Park, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 28	Murphy and Giles	3.3	1.33	0.54	0.71	0.72
May 14	E. R. Kerby	5	5.8	1.16	1.60	6.7
May 20	J. M. Giles	16	30	.86	2.95	26.3
July 6	E. R. Kerby				.40	0
November 24	do		.8	.67	.60	.54
(a)	J. M. Giles		90	2.30	5.00	207

a Computed from slope measurement using Kutter's formula.

Daily gage height, in feet, of Horse Creek near Mountain Park, Okla. for 1905.

Day.	Apr.	May.	June.	July.	Dec.	Day.	Apr.	May	June.	July	Dec.
1		0.5	1.3	0.7		17		0.			0.4
2		.5	1.0			18	0.9				.4
3		.5	.8			19	1.0	.6			.4
4		.4	.7			20	.8	5.			.4
5		.4	.7			21	.5	3.			.4
6		.4	.7			22	.5	3.			.4
7		.4	.7			23	6.0				.4
8			.7			24	2.4				.4
9			.6	1.5		25	3.0				.4
10		.6	.6			26	1.3				.4
11		2.9	.7			27	.8				.4
12		5.5	.7			28	.7	2.			.4
13		6.0	.5			29	.6	1.2			.4
14		1.6				30	.5	4.8			.4
15		1.0				31		2.7			
16		.8									

DRY FORK OF OTTER CREEK NEAR MOUNTAIN PARK, OKLA.

This station was established April 18, 1905. It is located about 4 miles north Mountain Park, Okla., in sec. 15, T. 3 N., R. 16 W., of the Indian meridian.

The channel is straight for 200 feet above and below the station. The current is The left bank is high; the right is low. Both are wooded and subject to overflow bed is sand and gravel, free from vegetation and slightly shifting. There is but one ch

Discharge measurements are made by wading near the gage.

The gage is a staff with an auxiliary gage 500 feet upstream from the regular g determining the slope. During 1905 the gage was read once each day by A. B. Slay The bench mark is a nail driven into a leaning cottonwood tree near a pump 35 f stream from the gage; elevation, 6.53 feet above the datum of the gage.

Discharge measurements of Dry Fork of Otter Creek near Mountain Park, Okla., in 1

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	c
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	S
April 18	E. R. Kerby	8	3	1.35	0.80	
April 28	Murphy and Giles	9	5	1.65	.90	
May 14	E. R. Kerby	14	14	2.04	1.50	
May 20	J. M. Giles	28	22	1.06	1.40	
June 12	E. R. Kerby	9	4	1.17	.70	
July 13	do	4	1.2	.83	.40	
July 15	J. M. Giles	6	2.2	.28	.45	
August 8	E. R. Kerby	1	.5	1.00	.40	
November 24	do		2.6	.96	.80	
December 15	do		1.8	1.33	.60	
December 29	do		1.5	1.20	.50	
(a)	J. M. Giles		104	3.43	4.00	
(a)	do		139	3.88	5.00	
(a)	do	75	268	5.05	8.00	

a Computed from slope measurements, using Kutter's formula.

Daily gage height, in feet, of Dry Fork of Otter Creek near Mountain Park, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	0.7	1.1	0.7	0.4	.....	.....	0.4	0.4
2	.....	.7	1.0	.6	.4	.....	.....	.4	.4
3	.....	.7	1.0	.5	.8	.....	0.3	.4	.4
4	.....	.6	.8	.5	.5	.....	.3	.5	.4
5	.....	.6	.8	.5	.4	.....	.3	.5	.4
6	.....	.6	.7	.5	.4	.....	.3	.6	.4
7	.....	.5	.7	.5	.4	.....	.3	.6	.4
8	.....	.5	.7	.5	.4	0.8	.3	.6	.4
9	.....	.5	.7	.7	.4	.5	.3	.7	.4
10	.....	2.8	.7	.6	.4	.5	.3	.6	.4
11	.....	2.2	.8	.5	.4	.5	.....	.6	.4
12	.....	5.5	.7	.5	.4	.4	.....	.5	.4
13	.....	8.4	.7	.4	.0	.4	.....	.5	.7
14	.....	1.7	.7	.4	.7	.3	.....	.5	.6
15	.....	1.4	.6	.5	.5	.3	.....	.4	.6
16	.....	1.0	.6	.5	.4	.3	.....	.4	.5
17	.....	.9	.6	.4	.4	.3	.....	.4	.5
18	.....	.9	.6	.4	.4	.3	.....	.4	.5
19	0.7	.8	.6	.4	.4	.3	.....	.4	.4
20	.6	2.5	.6	.4	.4	.3	.....	.4	.4
21	.6	2.3	.6	.5	.4	.3	.....	.4	.4
22	.5	1.9	.6	.5	.3	.3	.....	.4	.5
23	2.0	1.2	.6	.7	.....	.3	.3	.5	.4
24	1.4	1.1	.5	.5	.....	.3	.4	.8	.4
25	2.8	1.2	.5	.5	.....	.3	.4	.6	.4
26	1.4	3.0	.5	.5	.....	.3	.4	.5	.4
27	1.1	5.1	.5	.4	.....	.3	.3	.5	.4
28	.9	1.3	.5	.4	.....	.3	.3	.5	.4
29	.8	1.2	.5	.4	.....	.....	.3	.5	.3
30	.7	1.4	.5	.4	.....	.....	.3	.5	.4
31	.....	1.3	.....	.4	.....	.....	.4	.....	.4

NOTE.—Creek dry August 23 to September 7, September 29 to October 2, and October 11-22, inclusive.

Station rating table for Dry Fork of Otter Creek near Mountain Park, Okla., from April 19 to October 10, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.30	0.2	1.50	29	2.70	157	3.90	343
.40	.4	1.60	36	2.80	171	4.00	360
.50	1.0	1.70	44	2.90	185	4.20	394
.60	2.0	1.80	53	3.00	200	4.40	429
.70	3.5	1.90	63	3.10	215	4.60	465
.80	5.4	2.00	73	3.20	230	4.80	501
.90	7.8	2.10	84	3.30	245	5.00	539
1.00	10	2.20	95	3.40	261	5.20	577
1.10	13	2.30	106	3.50	277	5.40	616
1.20	16	2.40	118	3.60	293		
1.30	20	2.50	130	3.70	309		
1.40	24	2.60	143	3.80	326		

The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during the first part of 1905. It is well defined between gage heights 0.4 foot and 1.5 feet.

Above 1.5 feet the rating curve is based on computations from three slope measurements, using Kutter's formula. This extension should be considered only roughly approximate. Owing to shifting conditions a second table applies subsequent to October 10.

Station rating table for Dry Fork of Otter Creek near Mountain Park, Okla., from October 11 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.30	0.1	0.50	0.6	0.70	1.6
.40	.3	.60	1.0	.80	2.4

The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during the latter part of 1905. It is well defined.

Estimated monthly discharge of Dry Fork of Otter Creek near Mountain Park, Okla., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April 19–30	171	1.0	77.5	654
May	1,500	1.0	119	7,317
June	13	1.0	3.4	202
July	3.5	.4	1.1	68
August	7.8	.0	.82	50
September	5.4	.0	.41	24
October	.3	.0	.11	
November	2.4	.3	.66	4
December	1.6	.1	.42	2
The period				8,3

SALT FORK OF RED RIVER AT MANGUM, OKLA.

ion was established April 11, 1905. It is located at the highway bridge one-half of Mangum, Okla.

nel is straight for 1,000 feet above and 2,000 feet below the station. The current both banks are low, clean, and sandy, but do not overflow except under the ie bed of the stream is composed of sand and is shifting. There is but one chan- only by the pile supports of the bridge.

e measurements are made by wading during low water, and from the bridge dur- ıter. The bridge consists of ten 40-foot steel spans on piles, which catch drift l stages. The initial point for soundings is the north end of the bridge.

rd chain gage is fastened to the downstream railing of the bridge; length of chain,

During 1905 the gage was read once each day by C. O. Bowles. Bench marks ished as follows: (1) An iron post driven flush with the surface on the west side near a mesquite shrub just south of the cut for the highway and about 200 feet ·ft bank of the stream; elevation, 12.46 feet. (2) A paint mark on the cross- on the same side of the bridge as the gage; elevation, 14.30 feet. Elevations datum of the gage.

harge measurements of Salt Fork of Red River at Mangum, Okla., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
...	E. R. Kerby	43	20	.70	2.80	14
...	Murphy and Kerby	112	323	2.30	3.43	741
...	E. R. Kerby	138	133	1.67	3.00	222
...	J. M. Giles	202	174	1.62	3.18	281
...	....do	206	288	2.33	3.40	672
...	....do	110	79	1.32	2.90	104
...	....do	415	2,218	6.33	9.00	14,040
...	E. R. Kerby	83	78	1.71	1.90	134
...	....do	148	88	1.58	2.10	139
...	J. M. Giles	126	114	2.10	2.33	239
...	E. R. Kerby	.....	.....	.....	1.50	[a]1
4..	J. M. Giles	8	3	.60	1.30	2
7..	E R. Kerby	4	.5	1.00	1.30	.5
)..	....do	.....	62	1.29	2.20	80
...	....do	.....	63	1.29	2.20	81
...	....do	.....	56	1.16	2.50	66
	J. M. Giles	.....	1,276	6.78	7.50	8,590
	....do	.....	833	5.05	6.00	4,210

(a) Estimated.
(b) Computed from slope measurement using Kutter's formula.

Daily gage height, in feet, of Salt Fork of Red River at Mangum, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Nov.	D
1		2.5	2.4		2.0			
2			2.4		2.0			
3					2.35			
4					2.1		1.8	
5					2.0		1.9	
6					2.5	2.3	1.8	
7			3.2		1.9	2.0	1.7	
8			2.3		3.0	2.0	1.7	
9			2.2	2.5	2.0	1.9	1.7	
10			2.2	2.2	1.9	1.7	3.0	
11	2.8		2.6	2.0	1.8	1.7	2.6	
12	2.6		2.2	1.8	1.7	1.7	2.5	
13	2.5		2.2		3.8	1.7	2.4	
14	2.4		2.0		2.7	1.6	2.4	
15			2.0		2.3	1.6	2.4	
16			2.0		2.1	1.5	2.3	
17			1.9		2.0		2.2	
18	3.5		1.9		1.8		2.2	
19	3.55		1.8		1.6		2.2	
20		3.2	1.7				2.2	
21		3.3	1.6				2.1	
22		3.3	2.4				2.1	
23		2.9	2.1	2.5			2.4	
24	6.2		2.0	2.9			3.9	
25	3.3	3.2		2.5			3.0	
26	3.1	2.9		2.2			2.4	
27	2.8	7.5		2.5			2.4	
28	2.8			2.2			2.3	
29	2.6	3.0		2.2			2.2	
30	2.5	2.9		2.1			2.2	
31		2,7		2.0				

NOTE.—No flow for missing gage heights; water standing in pools.

y discharge, in second-feet, of Salt Fork of Red River at Mangum, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
		5	360	0	115	0	0	0	82
		0	360	0	115	0	0	0	84
		0	0	0	255	0	0	0	85
		0	0	0	150	0	0	5	85
		0	0	0	115	0	0	10	85
		0	0	0	325	180	0	5	85
		0	725	0	80	110	0	2	85
		0	315	0	620	110	0	2	85
		0	270	325	120	75	0	2	85
		0	270	185	80	30	0	475	85
	18	0	420	115	50	30	0	240	85
	10	0	270	50	30	30	0	200	85
	5	0	270	0	1,240	30	0	160	120
	2	0	175	0	440	10	0	160	110
	0	0	175	0	230	10	0	160	80
	0	0	175	0	150	1	0	120	75
	0	0	135	0	115	0	0	85	70
	825	0	135	0	50	0	0	85	40
	880	0	100	0	10	0	0	85	30
	0	450	70	0	0	0	0	85	20
	0	620	50	0	0	0	0	60	20
	0	620	270	0	0	0	0	60	70
	0	110	220	325	0	0	0	150	160
	4,900	100	175	555	0	0	0	1,250	260
	620	450	0	325	0	0	0	475	160
	330	110	0	185	0	0	0	160	70
	20	8,600	0	325	0	0	0	150	70
	20	600	0	185	0	0	0	110	70
	10	725	0	185	0	0	0	80	70
	5	670	0	150	0	0	0	80	70
		540		115	0		0		70

—On account of shifting conditions the low-water discharge was computed from several rating ach covering a short period. The high-water discharge was computed from one current-meter slope measurements.

timated monthly discharge of Salt Fork of Red River at Mangum, Okla., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
30	4,900	0	382	15,150
	8,600	0	439	26,990
	725	0	165	9,818
	555	0	97.6	6,001
	1,240	0	138	8,485
er	180	0	20.5	1,220
	0	0	0	0
er	1,250	0	149	8,866
r	260	20	85.5	5,257
e period				81,790

TURKEY CREEK NEAR OLUSTEE, OKLA.

This station was established April 20, 1905. It is located about 200 feet downstream from William Fullerton's irrigation dam, 6 miles northwest of Olustee, Okla.

The channel is straight for 200 feet above and below the station. The current is swift. Both banks are high and wooded, but subject to overflow during floods. The bed of the stream is sandy.

Low-water measurements are made by wading at the gage. High-water measurements are made from the highway bridge 1 mile east of the gage.

A staff gage in three sections is fastened to the right bank and trees on the same. An auxiliary gage is located 245 feet below the regular gage, for determinations of slope. During 1905 the gage was read once each day by James R. Craig. Bench marks were established as follows: (1) A group of three nails driven into the root of an elm tree on the right bank, 40 feet above the gage; elevation, 11.65 feet. (2) A point, marked with paint "U. S. R. S. B. M. 16.29," on a rock 20 feet from the gage; elevation 16.29 feet. Elevations refer to the datum of the gage.

Discharge measurements of Turkey Creek near Olustee, Okla., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 20	E. R. Kerby	15	9	1.67	2.40	15
June 5	do	15	10	1.92	2.70	20
July 18	do	11	9	1.29	2.50	11
July 22	do	10	7	1.64	2.47	11
July 22	do	10	7	1.58	2.47	10
July 30	do	16	13.5	.81	2.42	11
July 31	J. M. Giles	16	6	1.12	2.39	7
July 31	E. R. Kerby	16	13.5	.83	2.40	11
August 7	do	11	8	1.50	2.40	12
August 10	do		5.4	1.68	2.40	9
August 11	do	15	11	.75	2.30	8
August 11	do	11	9	1.21	2.30	11
August 18	do		8	1.80	2.50	15
August 21	do	11	10	1.12	2.40	11
August 22	do	11	10	1.15	2.40	12
September 9	do		37	1.89	3.70	71
September 9	do	27	39	1.90	3.70	74
September 20	J. M. Giles	16	9	1.14	2.32	10
September 20	do	16	9	1.14	2.33	10
October 7	do	7	10	2.00	2.50	21
November 2	do		14	1.43	2.50	20
December 9	do		4.4	3.13	2.30	14
December 30	do		4.8	2.90	2.30	14

Daily gage height, in feet, of Turkey Creek near Olustee, Okla., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Dec.
		2.2		2.5	2.4		2.2	2.3
		2.2		2.5	2.4		2.2	2.2
		2.2		2.5	2.5		2.1	2.3
		2.2		2.5	2.5		2.1	2.3
		2.2	2.7	2.6	2.4			2.3
		2.2	2.6	2.6	2.3			2.2
		2.1	12.2	2.6	2.4		2.5	2.2
		2.2	10.0	2.6	2.3		2.5	2.3
		2.2	2.9	2.6	2.3			2.3
		2.2	2.7	2.5	2.3	3.6	2.4	2.3
		2.4	2.7	2.5	2.3	4.7		2.3
		2.5	2.6	2.5	2.3	5.6		2.3
		6.2	2.7	2.5	2.4	2.7		2.3
		2.6	2.6	2.5	2.5	2.5		
		2.3	2.6	2.5	2.5	2.4		
		2.3	2.6	2.5	2.5	2.5		
		2.3	2.5	2.5	2.5	2.5		2.3
		2.2	2.6	2.5	2.5	2.5		2.6
		2.2	2.6	2.4	2.5	2.4		2.3
	2.4	7.1	2.6	2.4	2.5	2.5		2.3
	2.2	9.1	2.5	2.5	2.5	2.4		2.3
	2.2	13.6	2.5	2.5	2.5	2.3		2.3
	2.7	2.7	2.6	2.5	2.3	2.2		2.3
	6.6	2.5	2.5	2.5	2.4			2.2
	2.6	2.5	2.5	2.6	2.3	2.1		2.3
	2.6	3.1	2.5	2.5		2.3		2.3
	2.4		2.5	2.4		2.2		2.2
	2.3		2.5	2.4		3.5		2.2
	2.2		2.5	2.4		3.4		2.2
	2.2		2.5	2.4		2.2		2.2
				2.4				2.4

Gage out May 27 to June 4; creek dry September 24, and October 5–6 and 11–21. No readings to November 23, November 26–30, and December 14–16.

WASHITA RIVER AT ANADARKO, OKLA.

ation, established October 25, 1902, by W. G. Russell, is located at the highway ie-half mile north of the Anadarko railroad depc..

annel both above and below the station is straight for 200 feet. The right bank id the left bank is low. Both banks are liable to overflow. The bed of the stream and constant.

rge measurements are made from the bridge. The initial point for soundings is -bank end of the bridge, downstream side.

dard chain gage is fastened to the hand rail of the bridge; length of chain, 28.17 uring 1905 the gage was read once each day by James H. Dunlap. Bench marks ablished as follows: (1) A cross cut on the northeast corner of the capstone of the he right bank; elevation, 22.00 feet. (2) A nail in a large cottonwood tree at the d of the bridge, east of the road; elevation, 24.54 feet. Elevations refer to the f the gage.

Information in regard to this station is contained in the following Water-Supply Pape the United States Geological Survey:

Description: 84, p 139; 99, p 315; 131, p 187.
Discharge: 84, p 139; 99, p 315; 131, p 188.
Discharge, monthly, 131, p 189.
Gage heights: 84, p 140; 99, p 316; 131, p 188.

Discharge measurements of Washita River at Anadarko, Okla.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D cha
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Sec fe*
January 28	E. R. Kerby	60	94	1.47	2.8	
April 2	do	67	171	1.34	3.20	
April 24	J. M. Giles	66	150	1.47	3.30	
April 24	do	66	153	1.43	3.30	
April 25	Murphy and Kerby	70	219	1.85	4.11	
April 25	do	70	219	1.93	4.20	
May 22	E. R. Kerby	70	322	2.55	6.35	
June 5	J. M. Giles	70	360	2.25	6.50	
June 8	E. R. Kerby	70	279	2.77	6.30	
June 21	do	70	183	2.20	4.50	
July 3	do	69	132	1.54	3.70	
July 10	do	68	157	1.45	3.50	
July 24	J. M. Giles	70	286	1.70	4.90	
August 28	E. R. Kerby	67	128	1.63	3.30	
August 28	do	67	138	1.64	3.30	
September 6	do		119	1.39	2.90	
September 25	J. M. Giles		134	1.40	3.10	
September 26	do		128	1.33	3.00	
September 26	E. R. Kerby		130	1.44	3.00	
September 26	do		130	1.43	3.00	
October 1	do		94	1.43	2.60	
October 16	do		93	1.08	2.50	
October 24	do		92	1.16	2.50	
November 4	do		92	1.13	2.50	
November 17	do		137	1.28	2.80	
November 25	do		129	1.26	2.70	
November 30	do		222	1.66	3.80	
November 30	do		219	1.60	3.70	
December 4	do		185	1.44	3.20	
December 6	do		154	1.35	3.05	
December 18	do		142	1.20	2.90	
December 20	do		139	1.24	2.85	

Daily gage height, in feet, of Washita River at Anadarko, Okla., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	2.55	2.7	3.3	.....	4.3	18.7	3.9	3.1	3.0	2.6	2.5	3.6
.....	2.55	2.7	3.1	3.2	4.2	14.8	3.8	4.3	2.9	2.6	2.5	3.4
.....	2.55	2.8	3.1	3.3	4.0	12.7	3.7	3.6	2.8	2.6	2.5	3.3
.....	2.55	2.8	3.0	5.3	3.9	9.4	3.7	3.2	2.8	2.6	2.5	3.2
.....	2.55	2.8	3.0	4.4	3.8	6.6	3.5	3.1	2.7	2.6	2.7	3.1
.....	2.55	2.8	3.1	4.1	3.6	6.0	3.5	3.1	2.8	2.6	3.7	3.0
.....	2.55	2.8	3.3	3.8	3.5	5.8	3.4	3.0	3.0	2.6	3.9	3.0
.....	2.55	2.9	3.5	3.8	3.4	5.9	3.4	2.9	3.2	2.5	3.5	3.0
.....	2.55	2.9	3.8	3.7	3.3	6.8	3.5	2.8	4.7	2.5	3.4	2.9
.....	2.5	2.9	4.3	3.7	3.4	7.4	3.5	2.8	7.7	2.5	3.2	2.8
.....	2.5	2.9	3.8	7.3	3.6	9.6	3.4	2.7	8.4	2.4	3.0	2.8
.....	2.5	2.9	3.5	8.2	3.8	7.2	3.7	2.7	8.6	2.4	3.2	2.8
.....	2.5	2.9	3.3	6.3	5.2	5.8	3.4	2.9	5.9	2.5	3.5	2.9
.....	2.5	2.9	3.1	4.5	8.2	5.5	3.4	3.1	7.1	2.4	3.2	2.9
.....	2.5	2.8	3.1	3.7	10.1	5.1	3.4	4.2	4.8	2.5	2.9	2.9
.....	2.5	2.8	3.0	3.7	7.7	5.2	3.3	9.1	4.2	2.6	2.9	2.9
.....	2.65	2.8	3.5	3.7	6.2	5.3	3.2	9.4	3.9	2.5	2.9	2.9
.....	2.65	2.8	4.0	3.7	5.7	5.0	3.3	9.6	3.7	2.5	2.7	2.9
.....	2.65	2.9	4.3	3.4	4.3	4.8	3.4	6.4	3.6	2.4	2.7	2.8
.....	2.65	2.9	4.7	3.4	4.0	4.7	3.6	6.4	3 3	2.4	2.7	2.8
.....	2.65	3.0	5.1	3.3	5.8	4.5	3.3	6.1	3.2	2.5	2.6	2.8
.....	2.6	3.2	6.0	3.2	6.5	4.3	3.4	4.6	3.2	2.5	2.6	2.8
.....	2.6	3.5	5.0	3.2	6.4	4.3	5.2	4.1	3.4	2.5	2.6	2.8
.....	2.6	3.7	3.9	3.2	6.2	4.2	5.2	3.9	3.3	2.5	2.6	2.8
.....	2.6	4.0	3.6	4.1	5.4	4.1	4.5	3.7	3.2	2.5	2.6	2.8
.....	2.6	4.2	3.5	6.0	5.2	4.0	4.3	3.5	3.0	2.5	2.6	2.8
.....	2.6	3.7	3.5	10.8	12.6	4.0	4.1	3.4	2.9	3.5	2.6	2.8
.....	2.6	3.5	3.6	11.0	14.9	4.1	3.6	3.3	2.8	2.5	6.6	2.8
.....	2.7	.....	4.6	6.2	17.0	3.9	3.4	3.2	2.7	2.5	5.0	2.8
.....	2.7	.....	.....	5.1	18.3	3.8	3.3	3.2	2.7	2.5	4.2	2.8
.....	2.7	.....	.....	.....	18.8	.....	3.2	3.1	.....	2.5	.....	2.8

NOTE.—Ice conditions January 10-16 and February 3-14; gage heights to top of ice. Gage heights missing June 3-4 and December 31.

Daily discharge, in second-feet, of Washita River near Anadarko, Okla., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec
1	105	144	240	.....	455	.....	254	178	177	134	105	3
2	105	144	207	229	435	.....	227	382	162	134	105	3
3	105	.....	207	240	400	.....	203	262	148	134	104	2
4	105	.....	191	600	380	.....	218	194	148	134	104	2
5	105	.....	191	430	363	832	184	178	135	134	136	2
6	105	.....	207	378	327	715	198	183	150	134	300	1
7	105	.....	240	325	310	676	180	167	182	134	342	1
8	105	.....	273	325	290	656	197	152	213	105	273	1
9	105	.....	325	295	274	870	214	137	474	105	256	1
10	.....	.....	413	295	286	990	228	137	.....	105	224	1
11	.....	.....	325	990	320	.....	213	120	.....	90	196	1
12	.....	.....	273	.....	354	950	262	120	.....	90	230	1
13	.....	.....	240	775	513	677	213	152	693	100	285	1
14	.....	.....	207	440	.....	620	213	183	925	85	234	1
15	.....	160	207	295	.....	544	213	369	481	100	190	1
16	.....	160	191	295	.....	563	203	.....	373	115	190	1
17	136	160	273	284	795	581	186	.....	323	100	190	
18	136	160	360	284	608	525	203	.....	288	100	157	
19	136	175	413	234	436	489	220	790	272	85	157	
20	136	175	486	234	382	470	252	790	222	85	157	
21	136	191	560	220	718	432	203	790	206	107	142	
22	130	224	730	202	853	390	224	450	206	107	142	
23	130	273	542	202	835	383	544	357	237	107	142	
24	130	308	342	202	795	360	544	324	222	107	138	
25	130	360	290	405	641	334	412	289	206	107	138	
26	130	395	273	780	603	310	377	258	181	107	141	
27	130	308	273	.....	.....	300	341	242	175	106	148	
28	130	273	290	.....	.....	310	255	226	160	106	880	
29	144	.....	470	820	.....	268	227	208	144	106	580	
30	144	.....	.....	603	.....	250	210	208	144	105	436	
31	144	.....	.....	.....	.....	.....	196	194	.....	105	.....	

NOTE.—The daily discharge was obtained by indirect method. No estimates for ice conditions. estimate was made for gage heights above 7.5 feet owing to lack of measurements.

Estimated monthly discharge of Washita River at Anadarko, Okla., for 1905.

Month.	Discharge in second-feet.			Total in acre-fee
	Maximum	Minimum.	Mean.	
January 1-9, 17-31	144	105	124	5,1
February 1-2, 15-28	395	144	226	7,1
March 1-29	730	191	319	18,5
April (26 days)	(a)	202	399	20,5
May (23 days)	(a)	274	503	22,9
June (25 days)	(a)	250	541	26,8
July	544	180	252	15,5
August (28 days)	(a)	120	287	15,9
September (27 days)	(a)	135	268	14,3
October	134	85	109	6,7
November	880	104	227	13,5
December	333	158	187	11,5
The period				179,3

a Discharge beyond limits of rating table.

OUACHITA RIVER NEAR MALVERN, ARK.

This station was established March 3, 1903, at the Rockport Bridge, 1¾ miles northwest of Malvern, Ark., and was discontinued April 30, 1905. The gage was read by A. M. Baker.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 313-314; 131, p 190.
Discharge: 99, p 314; 131, p 190.
Discharge, monthly: 131, p 193.
Gage heights: 99, pp 314-315; 131, p 191.
Rating table: 131, p 192.

Daily gage height, in feet, of Ouachita River near Malvern, Ark., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	Day.	Jan.	Feb.	Mar.	Apr.
1	0.4	3.0	3.8	6.4	17	5.0	3 7	3.9	6.7
2	.3	3.9	3.7	5.4	18	3.5	3.5	4.0	5.6
3	1.3	3.2	3.2	6.1	19	3.8	4.0	4.0	5.4
4	1.3	2.8	3.0	12.0	20	3.8	3.7	4.0	6.5
5	1.2	2.6	2.9	7.9	21	3.6	3.7	3.9	7.7
6	1.2	2.4	2.7	6.1	22	3.2	4.2	3.7	7.4
7	1.2	2.4	2.7	5.2	23	3.0	5.0	3.5	6.0
8	1.0	3.0	4.6	4.7	24	2.9	5.6	3.5	5.3
9	1.3	3.7	12.5	4.2	25	2.7	5.7	3.1	7.5
10	2.0	4.5	15.8	3.8	26	2.5	5.4	3.0	8.3
11	1.9	4.9	11.2	7.5	27	2.1	4.9	3.0	7.1
12	11.2	5.8	8.1	7.9	28	2.0	4.2	2.9	6.0
13	10.9	6.0	6.5	6.3	29	2.4	.....	4.5	5.4
14	7.5	5.0	5.5	6.7	30	2.5	.....	8.4	4.6
15	5.2	4.7	4.8	8.6	31	2.7	.....	8.9	.....
16	5.1	4.0	4.2	8.5					

OUACHITA RIVER AT ARKADELPHIA, ARK.

This station was established August 1, 1905, by T. U. Taylor. It is located at the bridge of the St. Louis, Iron Mountain and Southern Railway at Arkadelphia, Ark.

The channel is straight for 500 feet above and 1,200 feet below the station. The current is sluggish at low water. During floods the water spreads out over both banks, but the railroad embankment on the west side forces it through the main channel unless the flood is high enough to flow over the railroad tracks near the passenger depot, one-fourth mile west of the bridge. On the east bank the flood water flows under 73 trestle bents of 12 feet clear space each. The highest water on record occurred in 1882, gage height 27.00 feet.

Discharge measurements are made from the three-span railway bridge. The initial points for soundings are the east faces of the east abutment and each pier, each span being treated as a separate channel.

A standard chain gage is located on the upstream side of the bridge near the middle of the first span from the right bank. During 1905 the gage was read once each day by J. W. Wilson. Bench marks were established as follows: (1) The top of the tie at the gage box; elevation, 35.27 feet. (2) The bridge seat on the north side of the west abutment; elevation, 31.22 feet. (3) A spike in the easternmost of three gum trees about one-eighth mile from the bridge directly across the track from the pumping station of the city waterworks; elevation, 27.00 feet. (4) United States Geological Survey bench mark in the northwest corner of the court-house, marked "246.00:" elevation, 124.57 feet. Elevations refer to the datum of the gage. Bench mark No. 4 is 246.00 feet above sea level.

Daily gage height, in feet, of Ouachita River at Arkadelphia, Ark., for 1905.

Day.	Aug.	Sept.	Oct.	Nov.	Dec.	Day.	Aug.	Sept.	Oct.	Nov.	Dec.
1	5.7	2.9	2.9	4.6	7.1	17	2.8	3.4	2.9	5.5	5.2
2	3.8	2.9	2.9	4.3	3.4	18	1.9	3.2	2.9	5.2	5.0
3	2.8	3.0	3.0	4.1	15.1	19	1.8	3.2	3.1	4.9	5.1
4	2.6	2.8	3.6	4.0	10.3	20	2.2	3.2	4.7	4.7	7.4
5	2.3	2.8	3.9	5.1	8.3	21	2.2	3.4	4.7	4.5	10.3
6	2.2	2.7	4.0	9.2	7.2	22	2.1	3.7	4.5	4.3	10.5
7	2.0	2.7	3.9	8.3	6.6	23	1.8	4.0	4.2	4.2	12.7
8	1.9	2.9	3.7	7.2	6.1	24	1.5	3.3	4.2	4.4	10.4
9	1.7	3.5	3.5	6.6	5.7	25	1.4	3.2	6.3	4.3	8.6
10	1.6	3.5	3.4	11.0	5.4	26	1.4	3.1	9.5	4.6	7.5
11	1.5	3.	3.3	11.7	5.1	27	2.4	3.0	8.7	4.9	6.8
12		4.	3.1	8.1	5.0	28	3.1	3.0	6.9	4.8	8.0
13	.3	4.6	3.0	8.2	4.9	29	3.0	3.0	5.8	10.7	7.7
14	.6	4.3	3.0	7.0	5.2	30	3.0	3.0	5.2	9.5	7.6
15	2.3	3.8	2.9	6.8	5.4	31	2.9		4.9		7.2
16	2.0	3.6	2.9	6.8	5.3						

INDEX.

	Page.
owledgments	12
foot, definition of	4
la., Colo.,	
urgatory River near:	
description	41-42
discharge	42
discharge, monthly	44
gage heights	43
rating table	44
, Okla.,	
alt Fork of Arkansas River near:	
description	36-37
discharge	37
gage heights	37
darko, Okla.,	
Washita River near:	
description	95-96
discharge	96
discharge, daily	98
discharge, monthly	98
gage heights	97
adelphia, Ark.,	
Ouachita River at:	
description	99
gage heights	100
alon, Kans.,	
Cimarron River near:	
description	48-49
discharge	49
gage heights	49
ansas, district hydrographer for	12
kansas City, Kans.,	
Arkansas River near:	
description	34-35
discharge	35
discharge, monthly	36
gage heights	35
rating table	36
rkansas River basin:	
description	19-21
rkansas River near—	
Arkansas City, Kans:	
description	34-35
discharge	35
discharge, monthly	36
gage heights	35
rating table	36
Canyon, Colo.:	
description	21-22
discharge	22
discharge, monthly	24
gage heights	23
rating tables	23,24
Arkansas River near—	Page.
Dodge, Kans.:	
description	30
discharge	30
discharge, monthly	32
gage heights	31
rating tables	31,32
Hutchinson, Kans.:	
description	32
discharge	33
discharge, monthly	34
gage heights	33
rating table	34
Pueblo, Colo.:	
description	24-25
discharge	26
discharge, monthly	27
gage heights	26
rating tables	27
Syracuse, Kans.:	
description	28
discharge	28
discharge, monthly	30
gage heights	29
rating table	29
Arkansas River, Salt Fork, near—	
Alva, Okla.:	
description	36-37
discharge	37
gage heights	37
Tonkawa, Okla.:	
description	38
discharge	38
gage heights	39
Arthur City, Tex.,	
Red River at:	
description	72
discharge	72
gage heights	73
Baer, J. J., acknowledgment to	12
Beaver Creek at—	
Beaver, Okla.:	
description	66
discharge	66
gage heights	67
Beeson, Melvin, aid by	12
Big Cypress Creek, Tex.:	
description	72
Brennan, M. S., aid by	12
Brick, Thomas E., aid by	12
Cable station, figure showing	7
Calvin, Ind. T.,	
Canadian River at:	
description	58

Daily gage height, in feet, of Ouachita River at Arkadelphia, Ark., for 1905.

Day.	Aug.	Sept.	Oct.	Nov.	Dec.	Day.	Aug.	Sept.	Oct.	N
1	5.	2.9	2.9	4.6	7.1	17	2.8	3.4	2.9	
2	3.	2.	2.9	4.3	3.4	18	1.9	3.2	2.9	
3	2.	3.0	3.0	4.1	15.1	19	1.8	3.2	3.1	
4	2.6	2.8	3.6	4.0	10.3	20	2.2	3.2	4.7	
5	2.3	2.8	3.9	5.1	8.3	21	2.2	3.4	4.7	
6	2.2	2.7	4.0	9.2	7.2	22	2.1	3.7	4.5	
7	2.0	2.7	3.9	8.3	6.6	23	1.8	4.0	4.2	
8	1.9	2.9	3.7	7.2	6.1	24	1.5	3.3	4.2	
9	1.7	3.5	3.5	6.6	5.7	25	1.4	3.2	6.3	
10	1.6	3.5	3.4	11.0	5.4	26	1.4	3.1	9.5	
11	1.5	3.3	3.3	11.7	5.1	27	2.4	3.0	8.7	
12	1.	4.	3.1	8.1	5.0	28	3.1	3.0	6.9	
13	1.	4.	3.0	8.2	4.9	29	3.0	3.0	5.8	
14	1.6	4.	3.0	7.0	5.2	30	3.0	3.0	5.2	
15	2.	3.8	2.9	6.8	5.4	31	2.9	.....	4.9	
16	2.	3.6	2.9	6.8	5.3					

INDEX.

	Page.
Acknowledgments	12
Acre-foot, definition of	4
Alma, Colo.,	
Purgatory River near:	
description	41-42
discharge	42
discharge, monthly	44
gage heights	43
rating table	44
Alva, Okla.,	
Salt Fork of Arkansas River near:	
description	36-37
discharge	37
gage heights	37
Amarko, Okla.,	
Washita River near:	
description	95-96
discharge	96
discharge, daily	98
discharge, monthly	98
gage heights	97
Ardelphia, Ark.,	
Ouachita River at:	
description	99
gage heights	100
Arlon, Kans.,	
Cimarron River near:	
description	48-49
discharge	49
gage heights	49
Arnsas, district hydrographer for	12
Arnsas City, Kans.,	
Arkansas River near:	
description	34-35
discharge	35
discharge, monthly	36
gage heights	35
rating table	36
Arnsas River basin:	
description	19-21
Arnsas River near—	
Arkansas City, Kans:	
description	34-35
discharge	35
discharge, monthly	36
gage heights	35
rating table	36
Canyon, Colo.:	
description	21-22
discharge	22
discharge, monthly	24
gage heights	23
rating tables	23,24
Arkansas River near—	Page.
Dodge, Kans.:	
description	30
discharge	30
discharge, monthly	32
gage heights	31
rating tables	31,32
Hutchinson, Kans.:	
description	32
discharge	33
discharge, monthly	34
gage heights	33
rating table	34
Pueblo, Colo.:	
description	24-25
discharge	26
discharge, monthly	27
gage heights	26
rating tables	27
Syracuse, Kans.:	
description	28
discharge	28
discharge, monthly	30
gage heights	29
rating table	29
Arkansas River, Salt Fork, near—	
Alva, Okla.:	
description	36-37
discharge	37
gage heights	37
Tonkawa, Okla.:	
description	38
discharge	38
gage heights	39
Arthur City, Tex.,	
Red River at:	
description	72
discharge	72
gage heights	73
Baer, J. J., acknowledgment to	12
Beaver Creek at—	
Beaver, Okla.:	
description	66
discharge	66
gage heights	67
Beeson, Melvin, aid by	12
Big Cypress Creek, Tex.:	
description	72
Brennan, M. S., aid by	12
Brick, Thomas E., aid by	12
Cable station, figure showing	7
Calvin, Ind. T.,	
Canadian River at:	
description	58

Calvin, Ind. T.—Continued. Page.
Canadian River at:
discharge 58
discharge, monthly 60
gage heights 59
rating table 59
Canadian River basin:
description 58
Canadian River at—
Calvin, Ind. T.:
description 58
discharge 58
discharge, monthly 60
gage heights 59
rating table 59
Logan, N. Mex.:
description 60
discharge 60
gage heights 60
Canadian River, North Fork, near—
El Reno, Okla.:
description 69
discharge 69
discharge, monthly 71
gage heights 70
rating table 71
Woodward, Okla.:
description 67
discharge 68
gage heights 68
Canyon, Colo.,
Arkansas River near:
description 21-22
discharge 22
discharge, monthly 24
gage heights 23
rating tables 23, 24
Catoosa, Ind. T.,
Verdigris River near:
description 52-53
discharge 53
gage heights 53
Cimarron River basin:
description 44-45
Cimarron River near—
Arkalon, Kans.:
description 48-49
discharge 49
gage heights 49
Garrett, Okla.
description 46
discharge 47
discharge, monthly 48
gage heights 47
rating table 48
Kenton, Okla.:
description 45
discharge 45
gage heights 46
Waynoka, Okla.:
description 50
discharge 50
gage heights 51
Computation, methods of 10-11
rules for —
Courtois Creek at—
Scotia, Mo.:
description 18
Courtois Creek at— Page.
Scotia, Mo.—Continued.
discharge 19
gage heights 19
Current meters, classes of 8
methods of using 8-10
Dodge, Kans.,
Arkansas River near:
description 30
discharge 30
discharge, monthly 32
gage heights 31
rating tables 31, 32
Drainage basins, list of 2-3
Elk Creek near—
Hobart, Okla.:
description 8
discharge 8
gage heights 8
Elm Fork of Red River:
description 7
near Mangum, Okla.:
description 7
discharge 7
discharge, daily 8
discharge, monthly 8
gage heights 8
El Reno, Okla.,
North Fork of Canadian River near:
description
discharge
discharge, monthly
gage heights
rating table
Equivalents, table of
Eureka, Mo.,
Meramec River near;
description 14
discharge
discharge, monthly
gage heights
rating table
Fall River at—
Fall River, Kans.:
description
discharge
gage heights
Floats, use of, in measuring discharge
Fort Gibson, Ind. T.,
Neosho River at:
description 36
discharge
gage heights
Gaging stations, equipment of
Garrett, Okla.,
Cimarron River near:
description
discharge
discharge, monthly
gage heights
rating table
Giles, J. M., field covered by
Graham, H. G., aid by
Granite, Okla.,
North Fork of Red River near:
description
discharge
gage heights

Page.

ına, F. W., field covered by..... 12
drick, Okla.,
North Fork of Red River near:
description..... 76
discharge..... 77
discharge, daily..... 78
discharge, monthly..... 78
gage heights..... 78
derlider, M. C., field covered by..... 12
art, Okla.,
Elk Creek near:
description..... 82
discharge..... 82
gage heights..... 83
se Creek near—
Mountain Park, Okla.:
description..... 87
discharge..... 87
gage heights..... 87
tchinson, Kans.,
Arkansas River at:
description..... 32
discharge..... 33
discharge, monthly..... 34
gage heights..... 33
rating table..... 34
drographers, list of..... 12
drographic surveys, annual appropriations for..... 1
organization and scope of..... 1–3
-covered streams, method of measuring ow of..... 10
lependence, Kans.,
Verdigris River near:
description..... 52
discharge..... 52
nton, Okla.,
Cimarron River near:
description..... 45
discharge..... 45
gage heights..... 46
Cueva, N. Mex.,
Mora River at:
description..... 60–61
discharge..... 61
discharge, monthly..... 63
gage heights..... 62
rating table..... 62
gan, N. Mex.,
Canadian River near:
description..... 60
discharge..... 60
gage heights..... 60
Ute Creek near:
description..... 64–65
discharge..... 65
gage heights..... 65
s Alamos, N. Mex.,
Sapello River at:
description..... 63
discharge..... 63
gage heights..... 64
lvern, Ark.,
Ouachita River near:
description..... 99
gage heights..... 99

Mangum, Okla., Page.
Elm Fork of Red River near:
description..... 79
discharge..... 79
discharge, daily..... 81
discharge, monthly..... 81
gage heights..... 80
Salt Fork of Red River near:
description..... 91
discharge..... 91
discharge, daily..... 93
discharge, monthly..... 93
gage heights..... 92
Meeker, F. L., aid by..... 12
Meeker, R. I., work in charge of..... 12
Meramec, Mo.,
Meramec River and Meramec Spring near:
See entries below.
Meramec River basin:
description..... 12
drainage areas..... 12
Meramec River near—
Eureka, Mo.:
description..... 14–15
discharge..... 15
discharge, monthly..... 16
gage heights..... 15
rating table..... 16
Meramec, Mo.:
description..... 13
discharge..... 13
gage heights..... 14
Meramec Spring near—
Meramec, Mo.:
description..... 17
discharge..... 17
gage heights..... 18
Methods of computing run-off..... 10–11
Methods of measuring stream flow..... 6–10
Miner's inch, definition of..... 3
Missouri, hydrographers in..... 12
Mora River at—
La Cueva, N. Mex.:
description..... 60–61
discharge..... 61
discharge, monthly..... 63
gage heights..... 62
rating table..... 62
Mountain Park, Okla.,
Horse Creek near:
description..... 87
discharge..... 87
gage heights..... 87
Dry Fork of Otter Creek near:
description..... 88
discharge..... 88
discharge, monthly..... 90
gage heights..... 89
rating tables..... 90
Otter Creek near:
description..... 83–84
discharge..... 84
discharge, daily..... 86
discharge, monthly..... 86
gage heights..... 85
Multiple-point method of measuring discharge, description of..... 9

Neosho River basin: description ..... Page. 55–56
Neosho River at—
Fort Gibson, Ind. T.:
description 56–57
discharge 57
gage heights 57
Olustree, Okla.,
Turkey Creek near:
description 94
discharge 94
gage heights 95
Otter Creek near—
Mountain Park, Okla.:
description 83–84
discharge 84
discharge, daily 86
discharge, monthly 86
gage heights 85
Otter Creek, Dry Fork, near—
Mountain Park, Okla.:
description 88
discharge 88
discharge, monthly 90
gage heights 89
rating tables 90
Ouachita River at—
Arkadelphia, Ark.:
description 99
gage heights 100
Malvern, Ark.:
description 99
gage heights 99
Pueblo, Colo.,
Arkansas River at:
description 24–25
discharge 26
discharge, monthly 27
gage heights 26
rating tables 27
Purgatory River basin:
description 39–40
Purgatory River near—
Alfalfa, Colo.:
description 41–42
discharge 42
discharge, monthly 44
gage heights 43
rating table 44
Trinidad, Colo.:
description 40
discharge 40
discharge, monthly 41
gage heights 41
rating table 41
Rating curves, methods of construction of 10–11
Rating tables, methods of construction of 10, 11
Red River basin:
description 72
Red River at—
Arthur City, Tex.:
description 72
discharge 72
gage heights 73
Red River, Elm Fork:
description 72
Red River, Elm Fork—Continued. Page.
near Mangum, Okla.:
description 70
discharge 70
discharge, daily 81
discharge, monthly 81
gage heights 80
Red River, North Fork
description 72
near Granite, Okla.:
description 73
discharge 74
gage heights 75
near Headrick, Okla.:
description 76
discharge 77
discharge, daily 78
discharge, monthly 78
gage heights 78
near Snyder, Okla.:
description 75
discharge 76
gage heights 76
Red River, Salt Fork:
description 72
near Mangum, Okla.:
description 91
discharge 91
discharge, daily 93
discharge, monthly 93
gage heights 92
Red River, Sulphur Fork:
description 72
Rules for computation, fundamental and special 4–5
Run-off in inches, definition of 4
Russell, W G field covered by 12
Salt Fork of Arkansas River near—
Alva, Okla.:
description 36–37
discharge 37
gage heights 37
Tonkawa, Okla.:
description 38
discharge 38
gage heights 39
Salt Fork of Red River:
description 72
near Mangum, Okla.:
description 91
discharge 91
discharge, daily 93
discharge, monthly 93
gage heights 92
Sapello River at—
Los Alamos, N. Mex.:
description 63
discharge 63
gage heights 64
Scotia, Mo.,
Courtois Creek at:
description 18
discharge 19
gage heights 19
Second-feet per squ
Second-foot, defini
Single-point meth
description of

Page.

: method of measuring discharge, use
l value of 6
ler, Okla.,
North Fork of Red River near:
description 75
discharge 76
gage heights 76
ing River, Mo.-Kans.-Ind. T.:
description 56
eam flow, field methods of measuring ... 6–10
office methods of computing 10–11
phur Fork of Red River:
description 72
racuse, Kans.,
Arkansas River near:
description 28
discharge 28
discharge, monthly 30
gage heights 29
rating table 29
ibles, explanation of 4
aylor, Thomas U., field covered by 12
exas, hydrographer in 12
immerman, O. H., work in charge of 12
onkawa, Okla.,
Salt Fork of Arkansas River near:
description 38
discharge 38
gage heights 39
rinidad, Colo.,
Purgatory River at:
description 40
discharge 40
discharge, monthly 41
gage heights 41
rating table 41
Turkey Creek near—
Olustree, Okla.:
description 94
discharge 94
gage heights 95

Ute Creek near— Page.
Logan, N. Mex.:
description 64–65
discharge 65
gage heights 65
Velocity methods of measuring discharge, description of 7–10
Verdigris River basin:
description 51–52
Verdigris River near—
Catoosa, Ind. T.:
description 52–53
discharge 53
gage heights 53
Independence, Kans.:
description 52
discharge 52
Vertical velocity-curve method of measuring discharge, description of 9
Washita River, Tex.-Okla.:
description 72
at Anadarko, Okla.:
description 95–96
discharge 96
discharge, daily 98
discharge, monthly 98
gage heights 97
Waynoka, Okla.,
Cimarron River near:
description 50
discharge 50
gage heights 51
Welland, A. A., aid by 12
Weir methods of measuring discharge, requirements of 6–7
Woodward, Okla.,
North Fork of Canadian River near:
description 67
discharge 68
gage heights 68

LASSIFICATION OF THE PUBLICATIONS OF THE UNITED STATES GEOLOGICAL SURVEY.

[Water-Supply Paper No. 173.]

The publications of the United States Geological Survey consist of (1) Annual Reports; (2) Monographs; (3) Professional Papers; (4) Bulletins; (5) Mineral Resources; (6) Water-Supply and Irrigation Papers; (7) Topographic Atlas of United States, folios and separate sheets thereof; (8) Geologic Atlas of United States, folios thereof. The classes numbered 2, 7, and 8 are sold at cost of publication; the others are distributed free. A circular giving complete lists may be had on application.

Most of the above publications may be obtained or consulted in the following ways:

1. A limited number are delivered to the Director of the Survey, from whom they may be obtained, free of charge (except classes 2, 7, and 8), on application.

2. A certain number are delivered to Senators and Representatives in Congress, for distribution.

3. Other copies are deposited with the Superintendent of Documents, Washington, D. C., from whom they may be had at practically cost.

4. Copies of all Government publications are furnished to the principal public libraries in the large cities throughout the United States, where they may be consulted by those interested.

The Professional Papers, Bulletins, and Water-Supply Papers treat of a variety of subjects, and the total number issued is large. They have therefore been classified into the following series: A, Economic geology; B, Descriptive geology; C, Systematic geology and paleontology; D, Petrography and mineralogy; E, Chemistry and physics; F, Geography; G, Miscellaneous; H, Forestry; I, Irrigation; J, Water storage; K, Pumping water; L, Quality of water; M, General hydrographic investigations; N, Water power; O, Underground waters; P, Hydrographic progress reports.

Series P.—The hydrographic progress reports contain the results of stream measurements. A report is issued for every calendar year, containing the results of data collected during that year. These reports were first published as a part of the Director's annual report or as a bulletin; they are now published as water-supply and irrigation papers. The following is a list, by years, of the publications containing the progress reports of stream measurements. A detailed index of these reports (1888-1903) is published as Water-Supply Paper No. 119.

1888. Tenth Annual Report, Part II.
1889. Eleventh Annual Report, Part II.
1890. Twelfth Annual Report, Part II.
1891. Thirteenth Annual Report, Part III.
1892. Fourteenth Annual Report, Part II.
1893. Bulletin No. 131.
1894. Bulletin No. 131; Sixteenth Annual Report, Part II.
1895. Bulletin No. 140.
1896. Water-Supply Paper No. 11; Eighteenth Annual Report, Part IV.
1897. Water-Supply Papers Nos. 15 and 16; Nineteenth Annual Report, Part IV.
1898. Water-Supply Papers Nos. 27 and 28; Twentieth Annual Report, Part IV.
1899. Water-Supply Papers Nos. 35, 36, 37, 38, and 39; Twenty-first Annual Report, Part IV.
1900. Water-Supply Papers Nos. 47, 48, 49, 50, 51, and 52; Twenty-second Annual Report, Part IV.
1901. East of Mississippi River, Water-Supply Papers Nos. 65 and 75.
West of Mississippi River, Water-Supply Papers Nos. 66 and 75.
1902. East of Mississippi River, Water-Supply Papers Nos. 82 and 83.
West of Mississippi River, Water-Supply Papers Nos. 84 and 85.

1903. East of Mississippi River, Water-Supply Papers Nos. 97 and 98.
West of Mississippi River, Water-Supply Papers Nos. 99 and 100.
1904. East of Mississippi River, Water-Supply Papers Nos. 124, 125, 126, 127, 128, and 129.
West of Mississippi River, Water-Supply Papers Nos. 130, 131, 132, 133, 134, and 135.
1905. East of Mississippi River, Nos. 165, 166, 167, 168, 169, 170, and 171.
West of Mississippi River, Nos. 171, 172, 173, 174, 175, 176, 177, and 178.

The Geological Survey and the Reclamation Service have suboffices in different parts of the United States, from which hydrographic and reclamation work in the respective localities is carried on and where data may be obtained on application. These offices are located as follows:

Boston, Mass., 6 Beacon street; Utica, N. Y., 75 Arcade; Atlanta, Ga., 409 Temple court; Austin, Tex., University of Texas; Chicago, Ill., 876 Federal Building; Belle Fourche, S. Dak.; Cody, Wyo.; Denver, Colo., Chamber of Commerce Building; Salt Lake, Utah; Los Angeles, Cal., 1106 Braly Building; San Francisco, Cal., 432 Merchants' Exchange Building; Phoenix, Ariz.; Carlsbad, N. Mex.; El Paso, Tex.; Billings, Mont.; Great Falls, Mont.; Hazen, Nev.; Boise, Idaho; Spokane, Wash., 424 Peyton Block; Pendleton, Oreg.

Correspondence should be addressed to

THE DIRECTOR,
UNITED STATES GEOLOGICAL SURVEY,
WASHINGTON, D. C.

JULY, 1906.

O

Water-Supply and Irrigation Paper No. 174 Series P, Hydrographic Progress Reports, 50

DEPARTMENT OF THE INTERIOR
UNITED STATES GEOLOGICAL SURVEY
CHARLES D. WALCOTT, DIRECTOR

REPORT

OF

PROGRESS OF STREAM MEASUREMENTS

FOR

THE CALENDAR YEAR 1905

PREPARED UNDER THE DIRECTION OF F. H. NEWELL

PART X.—Western Gulf of Mexico and Rio Grande Drainages

BY

T. U. TAYLOR and JOHN C. HOYT

WASHINGTON
GOVERNMENT PRINTING OFFICE
1906

CONTENTS.

	Page.
ıtroduction	1
Organization and scope of work	1
Definitions	3
Explanation of tables	4
Convenient equivalents	5
Field methods of measuring stream flow	6
Office methods of computing run-off	10
Cooperation and acknowledgments	12
ıbine River drainage basin	13
Description of basin	13
Sabine River near Longview, Tex	13
Neches River at Evadale, Tex	15
ïnity River drainage basin	17
Description of basin	17
Trinity River at Riverside, Tex	17
ıazos River drainage basin	19
Description of basin	19
Brazos River at Waco, Tex	19
Brazos River at Richmond, Tex	21
ılorado River (of Texas) drainage basin	24
Description of basin	24
Colorado River at Austin, Tex	24
Colorado River at Columbus, Tex	27
San Saba River near San Saba, Tex	29
Bartons Springs near Austin, Tex	30
uadalupe River drainage basin	31
Description of basin	31
Guadalupe River near Cuero, Tex	31
Comal River at New Braunfels, Tex	33
ian Antonio River drainage basin	34
Description of basin	34
San Antonio River at San Antonio, Tex	34
Nueces River drainage basin	35
Description of basin	35
Leona River at Uvalde, Tex	35
Rio Grande drainage basin	35
Description of basin	35
Rio Grande near Del Norte, Colo	36
Rio Grande near Lobatos, Colo	39
Rio Grande near San Ildefonso, N. Mex	4
Rio Grande near San Marcial, N. Mex	4
Rio Grande near El Paso, Tex	
Rio *Grande above Presidio, Tex*	

Rio Grande drainage basin—Continued. Page.
Rio Conchos near Ojinaga, Mexico 58
Rio Grande below Presidio, Tex 58
Rio Grande near Langtry, Tex 63
Rio Grande below mouth of Devils River, Tex 67
Rio Grande at Eagle Pass, Tex 71
Rio Grande near Laredo, Tex 76
Rio Grande near Roma, Tex 78
Rio Grande near Brownsville, Tex 81
Rio Salada near Guerrero, Tamaulipas, Mexico 84
Rio San Juan near Santa Rosalia ranch, Tamaulipas, Mexico 87
Conejos River near Mogote, Colo 90
Pecos River at Santa Rosa, N. Mex 93
Pecos River near Fort Sumner, N. Mex 95
Pecos River near Roswell, N. Mex 97
Pecos River near Dayton, N. Mex 99
Pecos River at Carlsbad, N. Mex 102
Pecos River and Margueretta flume near Pecos, Tex 105
Pecos River near Moorhead, Tex 110
Gallinas River near Las Vegas, N. Mex 115
Hondo River at Roswell, N. Mex 117
Hondo River at Hondo reservoir site, N. Mex 118
Taylor-Moore ditch near Roswell, N. Mex 120
Penasco River near Dayton, N. Mex 121
Devils River at Devils River, Tex 123
San Felipe Creek at Del Rio, Tex 127
Las Moras Creek near Brackettville, Tex 127

ILLUSTRATIONS.

Page.
PLATE I. Map showing location of principal gaging stations in the United States.
FIG. 1. Cable station, showing section of the river, car, gage, etc .....
2. Discharge, mean-velocity, and area curves for South Fork of Skykomish River near Index, Wash .....

PROGRESS REPORT OF STREAM MEASUREMENTS FOR THE CALENDAR YEAR 1905.

PART X.

By T. U. Taylor and John C. Hoyt.

INTRODUCTION.

ORGANIZATION AND SCOPE OF WORK.

The hydrographic work of the United States Geological Survey includes the collection of facts concerning and the study of conditions affecting the behavior of water from the time it reaches the earth as rain or snow until it joins the oceans or great navigable rivers. These investigations became a distinct feature of the work of the Survey in the fall of 1888, when an instruction camp was established at Embudo, N. Mex. The first specific appropriation for gaging streams was made by the act of August 18, 1894, which contained an item of $12,500 "for gauging the streams and determining the water supply of the United States, including the investigation of underground currents and artesian wells in the arid and semiarid sections." (28 Stat. L., p. 398.)

Since that time the appropriations have been gradually increased, as shown by the following table:

Annual appropriations for hydrographic surveys for the fiscal years ending June 30, 1895 to 1906.

1895	$12,500	1901	$100,000
1896	20,000	1902	100,000
1897	50,000	1903	200,000
1898	50,000	1904	200,000
1899	50,000	1905	200,000
1900	50,000	1906	200,000

As a result of the increased appropriations the work has been greatly extended, and at the same time it has been more thoroughly systemized by the adoption of standard methods and by grouping the States into districts, in each of which a district hydrographer and a corps of assistants carry on a comprehensive study of the hydrographic resources.

The chief features of the hydrographic work are the collection of data relating to the flow of the surface waters and the study of the conditions affecting this flow. Information is also collected concerning river profiles, duration and magnitude of floods, water power, etc., which may be of use in hydrographic studies. This work includes the study of the hydrography of every important river basin in the United States, and is of direct value in the commercial and agricultural development of the country.

In order to collect the material from which estimates of daily flow are made, gaging stations are established. The selection of a site for a gaging station and the length of time it is maintained depend largely on the physical features and the needs of each locality. If the water is to be used for power, special effort is made to obtain

EASTERN GULF OF MEXICO DRAINAGE BASINS.

Pearl.
Minor eastern Gulf of Mexico.

EASTERN MISSISSIPPI RIVER DRAINAGE BASINS.

Mississippi. Upper eastern Mississippi.

ST. LAWRENCE RIVER DRAINAGE BASINS.

Niagara River.
ı. Lake Ontario.
Lake Champlain (Richelieu River).
Minor St. Lawrence.

WESTERN MISSISSIPPI RIVER DRAINAGE BASINS.

Mississippi. Lower western Mississippi.
Arkansas.
Red.

WESTERN GULF OF MEXICO DRAINAGE BASINS.

Guadalupe.
San Antonio.
Nueces.
Rio Grande.
exas). Minor western Gulf of Mexico.

COLORADO RIVER DRAINAGE BASIN.

THE GREAT BASIN.

tains. Sierra Nevada.
Minor streams in Great Basin.

PACIFIC COAST DRAINAGE BASINS.

ic. Columbia.
Bay. Puget Sound.
ic.

HUDSON BAY DRAINAGE BASINS.

DEFINITIONS.

ne of water flowing in a stream—"the run-off" or "discharge"—is various terms, each of which has become associated with a certain class of se terms may be divided into two groups: (1) Those which represent a , as second-feet, gallons per minute, miner's inch, and run-off in second-are mile; and (2) those which represent the actual quantity of water, as pth in inches and acre-feet. They may be defined as follows:

oot" is an abbreviation for cubic foot per second, and is the rate of dis-ter flowing in a stream 1 foot wide and 1 foot deep, at a rate of 1 foot It is generally used as a fundamental unit from which others are

per minute" is generally used in connection with pumping and city r.

er's inch" is the rate of discharge of water passing through an orifice 1 under a head which varies locally. It has been commonly used by irrigators throughout the West, and is defined by statute in each State is used.

eet per square mile" is applied to the average number of cubic feet of g per second from each square mile of area drained, on the assumption -off is distributed uniformly both as regards time and area.

in inches" is the depth to which the drainage area would be covered if r flowing from it in a given period were conserved and uniformly dis-the surface. It is used for comparing run-off with rainfall, which essed in depth in inches.

"Acre-foot" is equivalent to 43,560 cubic feet, and is the quantity required to cover an acre to the depth of 1 foot. It is commonly used in connection with storage for irrigation work. There is a convenient relation between the second-foot and the acre-foot. One second-foot flowing for twenty-four hours will deliver 86,400 cubic feet or approximately 2 acre-feet.

EXPLANATION OF TABLES.

For each regular gaging station are given, as far as available, the following data:

1. Description of station.
2. List of discharge measurements.
3. Gage-height table.
4. Rating table.
5. Table of estimated monthly and yearly discharges and run-off, based on all the facts obtained to date.

The descriptions of stations give such general information about the locality and equipment as would enable the reader to find and use the station. They also give as far as possible, a complete history of all the changes since the establishment of the station that would be factors in using the data collected.

The discharge-measurement table gives the results of the discharge measurements made during the year, including the date, the name of the hydrographer, the gage height, the area of cross section, the mean velocity, and the discharge in second-feet.

The table of daily gage heights gives the daily fluctuations of the surface of the river as found from the mean of the gage readings taken each day. The gage height given in the table represents the elevation of the surface of the water above the zero of the gage. At most stations the gage is read in the morning and in the evening.

The rating table gives discharges in second-feet corresponding to each stage of the river as given by the gage heights.

In the table of estimated monthly discharge the column headed "Maximum" gives the mean flow for the day when the mean gage height was highest; this is the flow as given in the rating table for that mean gage height. As the gage height is the mean for the day there might have been short periods when the water was higher and the corresponding discharge larger than given in this column. Likewise in the column of "Minimum" the quantity given is the mean flow for the day when the mean gage height was lowest. The column headed "Mean" is the average flow for each second during the month. On this are based the computations for the three remaining columns, which are defined above.

In the computations for the tables of this report the following general and special rules have been used:

Fundamental rules for computation.

1. The highest degree of precision consistent with the rational use of time and money is imperative.
2. All items of computation should be expressed by at least two and not more than four significant figures.
3. Any measurement in a vertical velocity, mean velocity, or discharge curve whose per cent of error is five times the average per cent of error of all the other measurements should be rejected.
4. In reducing the number of significant figures, or the number of decimal places, by dropping the last figure, the following rules apply:

(a) When the figure in the place to be rejected is less than 5, drop it without changing the preceding figure. Example: 1,827.4 becomes 1,827.

(b) When the figure in the place to be rejected is greater than 5, drop it and increase the preceding figure by 1. Example: 1,827.6 becomes 1,828.

(c) When the figure in the place to be rejected is 5, and it is preceded by an even figure, drop the 5. Example. 1,828.5 becomes 1,828.

(d) When the figure in the place to be rejected is 5, and it is preceded by an odd figure, drop the 5 and increase the preceding figure by 1. Example: 1,827.5 becomes 1,828.

Special rules for computation.

1. Rating tables are to be constructed as close as the data upon which they are based will warrant. No decimals are to be used when the discharge is over 50 second-feet.

2. Daily discharges shall be applied directly to the gage heights as they are tabulated.

3. Monthly means are to be carried out to one decimal place when the quantities are below 100 second-feet. Between 100 and 10,000 second-feet, the last figure in the monthly mean shall be a significant figure. This also applies to the yearly mean.

4. Second-feet per square mile and depth in inches for the individual months shall be carried out to at least three significant figures, except in the case of decimals where the first significant figure is preceded by one or more naughts (0), when the quantity shall be carried out to two significant figures. Example: 1.25; .125; .012; .0012. The yearly means for these quantities are always to be expressed in three significant figures and at least two decimal places.

CONVENIENT EQUIVALENTS.

1 second-foot equals 50 California miner's inches.
1 second-foot equals 38.4 Colorado miner's inches.
1 second-foot equals 40 Arizona miner's inches.
1 second-foot equals 7.48 United States gallons per second; equals 448.8 gallons per minute; equals 646,272 gallons for one day.
1 second-foot equals 6.23 British imperial gallons per second.
1 second-foot for one year covers one square mile 1.131 feet deep, 13.572 inches deep.
1 second-foot for one year eqnals 0.000214 cubic mile; equals 31,536,000 cubic feet.
1 second-foot equals about 1 acre-inch per hour.
1 second-foot falling 10 feet equals 1.136 horsepower.
100 California miner's inches equal 15 United States gallons per second.
100 California miner's inches equal 77 Colorado miner's inches.
100 California miner's inches for one day equal 4 acre-feet.
100 Colorado miner's inches equal 2.60 second-feet.
100 Colorado miner's inches equal 19.5 United States gallons per second.
100 Colorado miner's inches equal 130 California miner's inches.
100 Colorado miner's inches for one day equal 5.2 acre-feet.
100 United States gallons per minute equal 0.223 second-foot.
100 United States gallons per minute for one day equal 0.44 acre-foot.
1,000,000 United States gallons per day equal 1.55 second-feet.
1,000,000 United States gallons equal 3.07 acre-feet.
1,000,000 cubic feet equal 22.95 acre-feet.
1 acre-foot equals 325,850 gallons.
1 inch deep on 1 square mile equals 2,323,200 cubic feet.
1 inch deep on 1 square mile equals 0.0737 second-foot per year.
1 inch equals 2.54 centimeters.
1 foot equals 0.3048 meter.
1 yard equals 0.9144 meter.
1 mile equals 1.60935 kilometers.
1 mile equals 1,760 yards; equals 5,280 feet; equals 63,360 inches.
1 square yard equals 0.836 square meter.
1 acre equals 0.4047 hectare.
1 acre equals 43,560 square feet; equals 4,840 square yards.
1 acre equals 209 feet square, nearly.
1 square mile equals 259 hectares.
1 square mile equals 2.59 square kilometers.
1 cubic foot equals 0.0283 cubic meter.
1 cubic foot equals 7.48 gallons; equals 0.804 bushel.
1 cubic foot of water weighs 62.5 pounds.
1 cubic yard equals 0.7646 cubic meter.
1 cubic mile equals 147,198,000,000 cubic feet.
1 cubic mile equals 4,667 second-feet for one year.
1 gallon equals 3.7854 liters.
1 gallon equals 8.36 pounds of water.
1 gallon equals 231 cubic inches (liquid measure).
1 pound equals 0.4536 kilogram.
1 avoirdupois pound equals 7,000 grains.
1 troy pound equals 5,760 grams.
1 meter equals 39.37 inches. Log. 1.5951654.
1 meter equals 3.280833 feet. Log. 0.5159842.
1 meter equals 1.093611 yards. Log. 0.0388629.
1 kilometer equals 3,281 feet; equals five-eights mile, nearly.
1 square meter equals 10.764 square feet; equals 1.196 square yards.
1 hectare equals 2.471 acres.
1 cubic meter equals 35.314 cubic feet; equals 1.308 cubic yards.
1 liter equals 1.0567 quarts.

"Acre-foot" is equivalent to 43,560 cubic feet, and is the quantity r cover an acre to the depth of 1 foot. It is commonly used in conne storage for irrigation work. There is a convenient relation between the s and the acre-foot. One second-foot flowing for twenty-four hours will del cubic feet or approximately 2 acre-feet.

EXPLANATION OF TABLES.

For each regular gaging station are given, as far as available, the follow

1. Description of station.
2. List of discharge measurements.
3. Gage-height table.
4. Rating table.
5. Table of estimated monthly and yearly discharges and run-off, base facts obtained to date.

The descriptions of stations give such general information about the l equipment as would enable the reader to find and use the station. The as far as possible, a complete history of all the changes since the establishr station that would be factors in using the data collected.

The discharge-measurement table gives the results of the discharge me made during the year, including the date, the name of the hydrographe height, the area of cross section, the mean velocity, and the discharge in s

The table of daily gage heights gives the daily fluctuations of the sur river as found from the mean of the gage readings taken each day. The given in the table represents the elevation of the surface of the water abo of the gage. At most stations the gage is read in the morning and in the

The rating table gives discharges in second-feet corresponding to each s river as given by the gage heights.

In the table of estimated monthly discharge the column headed "M gives the mean flow for the day when the mean gage height was highest; flow as given in the rating table for that mean gage height. As the gag the mean for the day there might have been short periods when the water and the corresponding discharge larger than given in this column. Like column of "Minimum" the quantity given is the mean flow for the da mean gage height was lowest. The column headed "Mean" is the aver each second during the month. On this are based the computations fc remaining columns, which are defined above.

In the computations for the tables of this report the following general rules have been used:

Fundamental rules for computation.

1. The highest degree of precision consistent with the rational use of time and money
2. All items of computation should be expressed by at least two and not more than fo

. Daily discharges shall be applied directly to the gage heights as they are tabulated.
. Monthly means are to be carried out to one decimal place when the quantities are below 100 ond-feet. Between 100 and 10,000 second-feet, the last figure in the monthly mean shall be a sig-icant figure. This also applies to the yearly mean.
i. Second-feet per square mile and depth in inches for the individual months shall be carried out at least three significant figures, except in the case of decimals where the first significant figure is eeded by one or more naughts (0), when the quantity shall be carried out to two significant figures. xample: 1.25; .125; .012; .0012. The yearly means for these quantities are always to be expressed in ree significant figures and at least two decimal places.

CONVENIENT EQUIVALENTS.

1 second-foot equals 50 California miner's inches.
1 second-foot equals 38.4 Colorado miner's inches.
1 second-foot equals 40 Arizona miner's inches.
1 second-foot equals 7.48 United States gallons per second; equals 448.8 gallons per minute; equals 646,272 gallons for one day.
1 second-foot equals 6.23 British imperial gallons per second.
1 second-foot for one year covers one square mile 1.131 feet deep, 13.572 inches deep.
1 second-foot for one year eqnals 0.000214 cubic mile; equals 31,536,000 cubic feet.
1 second-foot equals about 1 acre-inch per hour.
1 second-foot falling 10 feet equals 1.136 horsepower.
100 California miner's inches equal 15 United States gallons per second.
100 California miner's inches equal 77 Colorado miner's inches.
100 California miner's inches for one day equal 4 acre-feet.
100 Colorado miner's inches equal 2.60 second-feet.
100 Colorado miner's inches equal 19.5 United States gallons per second.
100 Colorado miner's inches equal 130 California miner's inches.
100 Colorado miner's inches for one day equal 5.2 acre-feet.
100 United States gallons per minute equal 0.223 second-foot.
100 United States gallons per minute for one day equal 0.44 acre-foot.
1,000,000 United States gallons per day equal 1.55 second-feet.
1,000,000 United States gallons equal 3.07 acre-feet.
1,000,000 cubic feet equal 22.95 acre-feet.
1 acre-foot equals 325,850 gallons.
1 inch deep on 1 square mile equals 2,323,200 cubic feet.
1 inch deep on 1 square mile equals 0.0737 second-foot per year.
1 inch equals 2.54 centimeters.
1 foot equals 0.3048 meter.
1 yard equals 0.9144 meter.
1 mile equals 1.60935 kilometers.
1 mile equals 1,760 yards; equals 5,280 feet; equals 63,360 inches.
1 square yard equals 0.836 square meter.
1 acre equals 0.4047 hectare.
1 acre equals 43,560 square feet; equals 4,840 square yards.
1 acre equals 209 feet square, nearly.
1 square mile equals 259 hectares.
1 square mile equals 2.59 square kilometers.
1 cubic foot equals 0.0283 cubic meter.
1 cubic foot equals 7.48 gallons; equals 0.804 bushel.
1 cubic foot of water weighs 62.5 pounds.
1 cubic yard equals 0.7646 cubic meter.
1 cubic mile equals 147,198,000,000 cubic feet.
1 cubic mile equals 4,667 second-feet for one year.
1 gallon equals 3.7854 liters.
1 gallon equals 8.36 pounds of water.
1 gallon equals 231 cubic inches (liquid measure).
1 pound equals 0.4536 kilogram.
1 avoirdupois pound equals 7,000 grains.
1 troy pound equals 5,760 grams.
1 meter equals 39.37 inches. Log. 1.5951654.
1 meter equals 3.280833 feet. Log. 0.5159842.
1 meter equals 1.093611 yards. Log, 0.0388629.
1 kilometer equals 3,281 feet; equals five-eighths mile, nearly.
1 square meter equals 10.764 square feet, equals 1.196 square yards.
1 hectare equals 2.471 acres.
1 cubic meter equals 35.314 cubic feet; equals 1.308 cubic yards.
1 liter equals 1.0567 quarts.

1 gram equals 15.43 grains.
1 kilogram equals 2.2046 pounds.
1 tonneau equals 2,204.6 pounds.
1 foot per second equals 1.097 kilometers per hour.
1 foot per second equals 0.68 mile per hour.
1 cubic meter per minute equals 0.5886 second-foot.
1 atmosph·re equals 15 pounds per square inch; equals 1 ton per square foot; equals 1 kilogram per square centimeter.
Acceleration of gravity equals 32.16 feet per second every second.
1 horsepower equals 550 foot-pounds per second.
1 horsepower equals 76 kilogram-meters per second.
1 horsepower equals 746 watts.
1 horsepower equals 1 second-foot falling 8.8 feet.
1½ horsepowers equal about 1 kilowatt.
To calculate waterpower quickly: $\frac{\text{Sec.-ft.} \times \text{fall in feet}}{11}$ = net horsepower on water wheel, realizing 80 per cent of the theoretical power.
Quick formula for computing discharge over weirs: Cubic feet per minute equals $0.4025l \times h^{\frac{3}{2}}$; l= length of weir in inches; h=head in inches flowing over weir, measured from surface of still water.
To change miles to inches on map:
Scale 1:125000, 1 mile=0.50688 inch.
Scale 1:90000, 1 mile=0.70400 inch.
Scale 1:62500, 1 mile=1.01376 inches.
Scale 1:45000, 1 mile=1.40800 inches.

FIELD METHODS OF MEASURING STREAM FLOW.

The methods used in collecting these data and in preparing them for publication are given in detail in Water-Supply Papers No. 94 (Hydrographic Manual, U. S. Geol. Survey) and No. 95 (Accuracy of Stream Measurements). In order that those who use this report may readily become acquainted with the general methods employed, the following brief description is given:

Streams may be divided, with respect to their physical conditions, into three classes—(1) those with permanent beds; (2) those with beds which change only during extreme low or high water; (3) those with constantly shifting beds. In estimating the daily flow, special methods are necessary for each class. The data on which these estimates are based and the methods of collecting them are, however, in general, the same.

There are three distinct methods of determining the flow of open-channel streams—(1) by measurements of slope and cross section and the use of Chezy's and Kutter's formulas; (2) by means of a weir; (3) by measurements of the velocity of the current and the area of the cross section. The method chosen for any case depends on the local physical conditions, the degree of accuracy desired, the funds available, and the length of time that the record is to be continued.

Slope method.—Much information has been collected relative to the coefficients to be used in the Chezy formula, $v=c\sqrt{Rs}$. This has been utilized by Kutter, both in developing his formula for c and in determining the values of the coefficient n which appears therein. The results obtained by the slope method are, in general, only roughly approximate, owing to the difficulty in obtaining accurate data and the uncertainty of the value for n to be used in Kutter's formula. The most common use of this method is in estimating the flood discharge of a stream when the only data available are the cross section, the slope as shown by marks along the bank, and a knowledge of the general conditions.

Weir method.—When funds are available and the conditions are such that sharp-crested weirs can be erected, these offer the best facilities for determining flow. If dams are suitably situated and constructed, they may be utilized for obtaining reliable estimates of flow. The conditions necessary to insu[illegible] divided into two classes—(1) those relating to the physical [illegible] itself, and (2) those relating to the diversion and use o[illegible] the dam.

The physical requirements are as follows: (*a*) Sufficient height of dam, so that ckwater will not interfere with free fall over it; (*b*) absence of leaks of appreciable gnitude; (*c*) topography or abutments which confine the flow over the dam at gh stages; (*d*) level crests, which are kept free from obstructions caused by floating s or ice; (*e*) crests of a type for which the coefficients to be used in $Q=c\,b\,h^{\frac{3}{2}}$, or ne similar standard weir formula, are known (see Water-Supply Paper No. 150); either no flashboards or exceptional care in reducing leaking through them and recording their condition.

Preferably there should be no diversion of water through or around the dam. nerally, however, the dam is built for purposes of power or navigation, and part all of the water flowing past it is diverted for such uses. This water is measured l added to that passing over the dam. To insure accuracy in such estimates the ount of water diverted should be reasonably constant. Furthermore, it should so diverted that it can be measured, either by a weir, a current meter, or a simple tem of water wheels which are of standard make, or which have been rated as ters under working conditions and so installed that the gate openings, the heads der which they work, and their angular velocities may be accurately observed.

The combination of physical conditions and uses of the water should be such that e estimates of flow will not involve, for a critical stage of considerable duration, e use of a head, on a broad-crested dam, of less than 6 inches. Moreover, when other conditions are good, the cooperation of the owners or operators of the plant still essential if reliable results are to be obtained.



FIG. 1.—Cable station, showing section of river, car, gage, etc.

A gaging station at a weir or dam has the general advantage of continuity of record through the periods of ice and floods and the disadvantages of uncertainty of coefficient to be used in the weir formula and of complications in the diversion and use of the water.

Velocity method.—The determination of the quantity of water flowing past a certain section of a stream at a given time is termed a discharge measurement. This quantity is the product of two factors—the mean velocity and the area of the cross section. The mean velocity is a function of surface slope, wetted perimeter, roughness of bed, and the channel conditions at, above, and below the gaging section. The area depends on the contour of the bed and the fluctuations of the surface. The two principal ways of measuring the velocity of a stream are by floats and current meters.

Great care is taken in the selection and equipment of gaging stations for determining discharge by velocity measurements in order that the data may have the required degree of accuracy. Their essential requirements are practically the same whether the velocity is determined by meters or floats. They are located, as far as possible, where the channel is straight both above and below the gaging section; where there are no cross currents, backwater, or boils; where the bed of the stream is reasonably

free from large projections of a permanent character, and where the banks are high and subject to overflow only at flood stages. The station must be so far removed from the effects of tributary streams and dams or other artificial obstructions that the gage height shall be an index of the discharge.

Certain permanent or semipermanent structures, usually referred to as "equipment," are generally pertinent to a gaging station. These are a gage for determining the fluctuations of the water surface, bench marks to which the datum of the gage is referred, permanent marks on a bridge or a tagged line indicating the points of measurement, and, where the current is swift, some appliance (generally a secondary cable) to hold the meter in position in the water. As a rule, the stations are located at bridges if the channel conditions are satisfactory, as from them the observations can more readily be made and the cost of the equipment is small.

The floats in common use are the surface, subsurface, and tube or rod floats. A corked bottle with a flag in the top and weighted at the bottom makes one of the most satisfactory surface floats, as it is affected but little by wind. In case of flood measurements, good results can be obtained by observing the velocity of floating cakes of ice or débris. In case of all surface float measurements, coefficients must be used to reduce the observed velocity to the mean velocity. The subsurface and tube or rod floats are intended to give directly the mean velocity in the vertical. Tubes give excellent results when the channel conditions are good, as in canals.

In measuring velocity by a float, observation is made of the time taken by the float to pass over the "run," a selected stretch of river from 50 to 200 feet long. In each discharge measurement a large number of velocity determinations are made at different points across the stream, and from these observations the mean velocity for the whole section is determined. This may be done by plotting the mean positions of the floats as indicated by the distances from the bank as ordinates and the corresponding times as abscissas. A curve through these points shows the mean time of run at any point across the stream, and the mean time for the whole stream is obtained by dividing the area bounded by this curve and its axis by the width. The length of the run divided by the mean time gives the mean velocity.

The area used in float measurements is the mean of the areas at the two ends of the run and at several intermediate sections.

The essential parts of the current meters in use are a wheel of some type, so constructed that the impact of flowing water causes it to revolve, and a device for recording or indicating the number of revolutions. The relation between the velocity of the moving water and the revolutions of the wheel is determined for each meter. This rating is done by drawing the meter through still water for a given distance at different speeds and noting the number of revolutions for each run. From these data a rating table is prepared, which gives the velocity per second for any number of revolutions.

Many kinds of current meters have been constructed. They may, however, be classed in two general types—those in which the wheel is made up of a series of cups, as the Price, and those having a screw-propeller wheel, as the Haskell. Each meter has been developed for use under some special condition. In the case of the small Price meter, which has been largely developed and extensively used by the United States Geological Survey, an attempt has been made to get an instrument which could be used under practically all conditions.

Current-meter measurements may be made from a bridge, cable, boat, or by wading, and gaging stations may be classified in accordance with such use. Fig. 1 shows a typical cable station.

In making the measurement an arbitrary number of points are laid off on a line perpendicular to the thread of the stream. The points at which the velocity and depth are observed are known as measuring points and are usually fixed at regular intervals, varying from 2 to 20 feet, depending on the size and condition of the

stream. Perpendiculars dropped from the measuring points divide the gaging section into strips. For each strip or pair of strips the mean velocity, area, and discharge are determined independently, so that conditions existing in one part of the stream may not be extended to parts where they do not apply.

Three classes of methods of measuring velocity with current meters are in general use—multiple point, single point, and integration.

The three principal multiple-point methods in general use are the vertical velocity curve, 0.2 and 0.8 depth, and top, bottom, and mid depth.

In the vertical velocity-curve method a series of velocity determinations are made in each vertical at regular intervals, usually from 0.5 to 1 foot apart. By plotting these velocities as abscissas and their depths as ordinates, and drawing a smooth curve among the resulting points, the vertical velocity curve is developed. This curve shows graphically the magnitude and changes in velocity from the surface to the bottom of the stream. The mean velocity in the vertical is then obtained by dividing the area bounded by this velocity curve and its axis by the depth. On account of the length of time required to make a complete measurement by this method, its use is limited to the determination of coefficients for purposes of comparison and to measurements under ice.

In the second multiple-point method the meter is held successively at 0.2 and 0.8 of the depth and the mean of the velocities at these two points is taken as the mean velocity for that vertical. On the assumption that the vertical velocity curve is a common parabola, with horizontal axis, the mean of the velocities at 0.22 and 0.79 of the depth will give (closely) the mean velocity in the vertical. Actual observations under a wide range of conditions show that this second multiple-point method gives the mean velocity very closely for open-water conditions where the depth is over 5 feet and the bed comparatively smooth, and moreover the indications are that it will hold nearly as well for ice-covered rivers.

In the third multiple-point method the meter is held at mid depth, at 0.5 foot below the surface, and at 0.5 foot above the bottom, and the mean velocity is determined by dividing by 6 the sum of the top velocity, four times the mid depth velocity, and the bottom velocity. This method may be modified by observing at 0.2, 0.6, and 0.8 depth.

The single-point method consists in holding the meter either at the depth of the thread of mean velocity or at an arbitrary depth for which the coefficient for reducing to mean velocity has been determined.

Extensive experiments by vertical velocity curves show that the thread of mean velocity generally occurs at from 0.5 to 0.7 of the total depth. In general practice the thread of mean velocity is considered to be at 0.6 depth, at which point the meter is held in a majority of the measurements. A large number of vertical velocity-curve measurements taken on many streams and under varying conditions show that the average coefficient for reducing the velocity obtained at 0.6 depth to mean velocity is practically unity.

In the other principal single-point method the meter is held near the surface, usually 1 foot below, or low enough to be out of the effect of the wind or other disturbing influences. This is known as the subsurface method. The coefficient for reducing the velocity taken at the subsurface to the mean has been found to be from 0.85 to 0.95, depending on the stage, velocity, and channel conditions. The higher the stage the larger the coefficient. This method is specially adapted for flood measurements, or when the velocity is so great that the meter can not be kept at 0.6 depth.

The vertical-integration method consists in moving the meter at a slow, uniform speed from the surface to the bottom and back again to the surface, and noting the number of revolutions and the time taken in the operation. This method has the advantage that *the velocity at each point of* the vertical is measured twice. It is *well adapted for measurements under ice* and as a check on the point methods.

The area, which is the other factor in the velocity method of determining the discharge of a stream, depends on the stage of the river, which is observed on the gage, and on the general contour of the bed of the stream, which is determined by soundings. The soundings are usually taken at each measuring point at the time of the discharge measurement, either by using the meter and cable or by a special sounding line or rod. For streams with permanent beds standard cross sections are usually taken during low water. These sections serve to check the soundings which are taken at the time of the measurements, and from them any change which may have taken place in the bed of the stream can be detected. They are also of value in obtaining the area for use in computations of high-water measurements, as accurate soundings are hard to obtain at high stages.

In computing the discharge measurements from the observed velocities and depths at various points of measurement, the measuring section is divided into elementary strips, as shown in fig. 1, and the mean velocity, area, and discharge are determined separately for either a single or a double strip. The total discharge and the area are the sums of those for the various strips, and the mean velocity is obtained by dividing the total discharge by the total area.

The determination of the flow of an ice-covered stream is difficult, owing to diversity and instability of conditions during the winter period, and also to lack of definite information in regard to the laws of flow of water under ice. The method now employed is to make frequent discharge measurements during the frozen periods by the vertical velocity-curve method and to keep an accurate record of the conditions such as the gage height to the surface of the water as it rises in a hole cut in the ice, the thickness and character of the ice, etc.

From these data an approximate estimate of the daily flow can be made by constructing a rating curve (really a series of curves) similar to that used for open channels, but considering in addition to gage heights and discharge, varying thickness of ice. Such data as are available in regard to this subject are published in Water Supply Paper No. 146, pp. 141–148.

OFFICE METHODS OF COMPUTING RUN-OFF.

There are two principal methods of estimating run-off, depending on whether or not the bed of the stream is permanent.

For stations on streams with permanent beds the first step in computing the run-off is the construction of the rating table, which shows the discharge corresponding to any stage of the stream. This rating table is applied to the record of stage to determine the amount of water flowing. The construction of the rating table depends on the method used in measuring flow.

For a station at a weir or dam the basis for the rating table is some standard weir formula. The coefficients to be used in its application depend on the type of dam and other conditions near its crest. After inserting in the weir formula the measured length of crest and assumed coefficient, the discharge is computed for various heads, and the rating table constructed.

The data necessary for the construction of a rating table for a velocity-area station are the results of the discharge measurements, which include the record of stage of the river at the time of measurement, the area of the cross section, the mean velocity of the current, and the quantity of water flowing. A thorough knowledge of the conditions at and in the vicinity of the station is also necessary.

The construction of the rating table depends on the following laws of flow for open permanent channels: (1) The discharge will remain constant so long as the conditions at or near the gaging station remain constant. (2) The discharge will be the same whenever the stream is at a given stage if the change of slope, due to the rise and fall of the stream, be neglected. (3) The discharge is a function of and increases *gradually* with the stage.

he plotting of results of the various discharge measurements, using gage heights rdinates and discharge, mean velocity, and area as abscissas, will define curves ch show the discharge, mean velocity, and area corresponding to any gage height. the development of these curves there should be, therefore, a sufficient number lischarge measurements to cover the range of the stage of the stream. Fig. 2 ws a typical rating curve with its corresponding mean velocity and area curves. s the discharge is the product of two factors, the area and the mean velocity, any nge in either factor will produce a corresponding change in the discharge. Their ves are therefore constructed in order to study each independently of the other. 'he area curve can be definitely determined from accurate soundings extending the limits of high water. It is always concave toward the horizontal axis or on a aight line, unless the banks of the stream are overhanging.

The form of the mean velocity-curve depends chiefly on the surface slope, the ughness of the bed, and the cross section of the stream. Of these, the slope is the incipal factor. In accordance with the relative changes of these factors the curve ay be either a straight line, convex, or concave toward either axis, or a combina- on of the three. From a careful study of the conditions at any gaging station the


MEAN VELOCITY, AREA AND RATING CURVES FOR SKYKOMISH RIVER (SO. FORK) NEAR INDEX, WASH.
MEASUREMENTS IN 1902 NO. 1 TO 7
" " 1903 8 " 12
RATING CURVE
AREA CURVE
MEAN VELOCITY CURVE
GAGE HEIGHT IN FEET
AREA IN SQUARE FEET
VELOCITY IN FEET PER SECOND
DISCHARGE IN SECOND-FEET

G. 2.—Discharge, mean-velocity, and area curves for South Fork of Skykomish River near Index, Wash.

rm which the vertical velocity-curve will take can be predicted, and it may be :tended with reasonable certainty to stages beyond the limits of actual measure- ents. Its principal use is in connection with the area curve in locating errors in scharge measurements and in constructing the rating table.

The discharge curve is defined primarily by the measurements of discharge, which e studied and weighted in accordance with the local conditions existing at the time each measurement. The curve may, however, best be located between and yond the measurements by means of curves of area and mean velocity. The dis- arge curve under normal conditions is concave toward the horizontal axis and is nerally parabolic in form.

In the preparation of the rating table the discharge for each tenth or half tenth on ie gage is taken from the curve. The differences between successive discharges are ien taken and adjusted according to the law that they shall either be constant or ıcreasing.

The determination of daily discharge of streams with changeable beds is a difficult roblem. *In case there is a weir or dam* available, a condition which seldom exists

on streams of this class, estimates can be obtained by its use. In case of velocity-area stations frequent discharge measurements must be made if the estimates are to be other than rough approximations. For stations with beds which shift slowly or are materially changed only during floods, rating tables can be prepared for periods between such changes and satisfactory results obtained with a limited number of measurements, provided that some of them are taken soon after the change occurs. For streams with continually shifting beds, such as the Colorado and Rio Grande, discharge measurements should be made every two or three days, and the discharges for intervening days obtained either by interpolation modified by gage height or by Professor Stout's method, which has been described in full in the Nineteenth Annual Report of the United States Geological Survey, Part IV, page 323, and in Engineering News of April 21, 1904. This method or a graphical application of it is also much used in estimating flow at stations where the bed shifts but slowly.

COOPERATION AND ACKNOWLEDGMENTS.

Most of the measurements presented in this paper have been obtained through local hydrographers. Acknowledgment is extended to other persons and corporations who have assisted these hydrographers or have cooperated in any way, either by furnishing records of the height of water or by assisting in transportation.

The following list, arranged alphabetically by States, gives the names of the hydrographers and others who have assisted in furnishing and preparing the data contained in this report:

Colorado.—District and resident hydrographer, M. C. Hinderlider,[a] assisted by R. I. Meeker, Wm A. Lamb, A. A. Weiland, Melvin Beeson, Thomas E. Brick, and F. L. Meeker. Acknowledgments are due the Colorado and Southern, Burlington and Missouri River, Union Pacific, and Chicago, Burlington and Quincy railroads for free transportation for hydrographers over their lines, also to the Denver Union Water Company for the free use of their reservoir for a rating station.

Louisiana.—District hydrographer, Thomas U. Taylor.[b]

New Mexico.[c]—The hydrographic work in the northern portion of this territory was carried under the direction of M. C. Hinderlider, district hydrographer, assisted as follows: The work in the north central portion was in charge of R. I. Meeker, while the work in the northwestern portion was in charge of O. H. Timmerman. For many favors and courtesies in the form of free accommodations to hydrographers and for assistance in securing records of flow on Mora River acknowledgments are due D. C. Duel, Hugh Loudon, and J. J. Baer, of La Cueva, N. Mex., also to James Hand, of Los Alamos, N. Mex., for similar favors. Transportation in the form of annual pass was furnished Mr. Meeker by the Denver and Rio Grande and Atchison, Topeka and Santa Fe railroads. The work in the southern and eastern portion was under the direction of J. M. Gile assisted by Earl Patterson. Acknowledgments are due the St. Louis and San Francisco, the Chicago Rock Island and Pacific, the Southern Kansas, the Fort Worth and Denver City, and the Texas and Pacific railroads for transportation furnished Mr. Giles, and the Pecos Valley lines for transportation furnished Mr. Patterson.

Texas.—District hydrographer, Thomas U. Taylor, assisted by H. H. Fox, E. C. H. Bantel, and B. Haberer. Acknowledgments are due the Missouri, Kansas and Texas, the International and Great Northern, the Houston and Texas Central, the Southern Pacific, the Texas and Pacific, the Fort Worth and Denver City, the Gulf, Colorado and Santa Fe, the St. Louis Southwestern (Cotton Belt) and the San Antonio and Aransas Pass railroads for transportation for the district hydrographer. Also to the Army engineers for gage heights at Riverside and for maps of Brazos River from the Gulf to Waco.

Special acknowledgment is due for the results of the data collected at certain stations in the Rio Grande drainage basin, to members of the International (Water) Boundary Commission as follows: Gen. Anson Mills, commissioner on the part of the United States; Señor Don Jacobo Blanco, commissioner on the part of Mexico, and W. W. Follett, consulting engineer on the part of the United States.

[a] Office of district hydrographer for Colorado, Kansas, Nebraska, northern New Mexico, Wyoming, Chamber of Commerce Building, Denver, Colo.

[b] Office of the district hydrographer for Texas, Arkansas, and Louisiana, Austin, Tex.

[c] District hydrographer for southern and eastern New Mexico, southern Oklahoma, and south Indian Territory, J. M. Giles, Carlsbad, N. Mex.

SABINE RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Sabine River has its headwaters in Collin and Hunt counties, Tex., flows in a outheasterly direction to the State line, then south, forming the boundary between Texas and Louisiana, and empties into Sabine Lake, an arm of the Gulf, near Orange, Tex. The small tributaries in eastern Texas support many small water mills, and he Sabine itself is navigable for several hundred miles. The drainage area of the Sabine in Texas above Orange is 7,500 square miles and its total drainage area above Orange in Louisiana and Texas is 10,400 square miles.

SABINE RIVER NEAR LONGVIEW, TEX.

This station was established January 1, 1904, by Thomas U. Taylor. It is located at the bridge of the International and Great Northern Railroad, about 3 miles southwest of Longview Junction, Tex.

The channel is straight for 150 feet above and 400 feet below the station. The current is sluggish. The right bank is low and cleared along the right of way of the railroad. The left bank is high and composed in its lower half of sandstone; it is cleared above and wooded below the station. The bed of the stream is rocky and fairly permanent. Old piles left from the false work used in erecting the bridge give trouble in making measurements at low water.

Discharge measurements are made from the bridge. The initial point for soundings is the east face of the west abutment.

A standard chain gage is attached to the guard rail of the bridge. During 1905 the gage was read twice each day by John Wadsack. Bench marks were established as follows: (1) The top of abutment, northeast corner, marked "U. S. G. S. 42.08 B. M."; elevation, 42.08 feet. (2) The top of an iron rod buried in a vertical position in the yard of the bridge watchman, 6 feet from the southeast corner of his house, 3 feet from the second post east of the gate, and 8 inches from the wire fence; elevation, 47.00 feet. (3) The top of tie at the gage; elevation, 45.00 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, p 322; 132, pp 19–20.
Discharge: 99, p 322; 132, p 20.
Discharge, monthly: 132, p 23.
Gage heights: 132, p 21.
Rating table: 132, p 22.

Discharge measurements of Sabine River near Longview, Tex., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
July 9	T. U. Taylor	3,660	3.08	30.1	11,270
July 10	do	4,150	3.67	32.6	15,240
July 11	do	4,316	3.85	33.4	16,630

Daily gage height, in feet, of Sabine River near Longview, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	8.0	7.65	16.15	17.65	28.9	32.4	24.9	25.95	7.1	7.4	12.3	9.8
2	7.5	7.65	15.3	18.5	30.2	31.7	23.35	26.15	7.1	7.4	11.2	10.8
3	7.25	7.7	13.75	23.85	31.85	31.15	21.75	26.4	7.1	7.3	10.3	10.8
4	7.15	7.8	11.65	24.7	32.6	30.55	22.15	26.5	7.0	7.3	9.4	10.7
5	7.1	7.8	10.1	24.35	32.55	29.55	24.15	26.35	6.95	7.3	9.0	11.5
6	7.0	7.8	9.4	23.35	32.2	28.5	25.2	25.65	6.9	7.2	9.3	12.6
7	7.0	8.25	9.05	22.55	32.15	26.75	26.6	23.65	6.9	7.2	9.5	13.0
8	6.9	10.05	9.35	21.05	32.55	24.1	28.1	19.45	6.9	7.1	9.8	13.3
9	6.95	11.75	10.8	21.65	33.0	20.6	29.95	15.0	7.0	7.0	10.2	13.3
10	7.0	12.55	13.95	21.65	33.9	15.85	32.8	11.4	7.0	6.9	10.9	12.9
11	7.45	12.55	14.4	22.1	34.05	11.6	33.4	10.3	6.9	6.9	11.7	12.0
12	9.3	12.1	14.2	22.95	34.3	9.8	33.15	9.9	6.8	6.8	12.9	11.0
13	11.4	11.4	15.15	23.95	33.25	9.6	32.7	9.25	6.8	6.8	14.2	12.5
14	11.15	10.8	15.6	24.6	34.1	9.45	32.2	8.95	6.9	6.8	15.3	15.0
15	10.8	10.6	16.2	24.85	33.45	9.3	31.7	8.55	6.9	6.8	16.4	16.4
16	10.25	10.75	17.15	24.7	33.1	9.4	31.25	8.35	6.9	6.7	17.1	17.8
17	9.4	11.05	17.4	23.45	33.6	9.25	31.1	8.15	6.9	6.9	17.7	19.4
18	9.0	11.3	20.45	21.65	34.9	9.05	31.1	7.95	6.8	7.1	18.2	21.3
19	8.85	13.95	27.8	21.95	35.05	9.7	31.15	7.8	6.9	7.2	18.7	25.6
20	9.35	17.15	27.45	23.2	34.9	10.5	30.7	7.7	7.05	7.9	18.9	28.2
21	9.3	17.75	27.15	24.15	34.45	10.2	30.25	7.55	7.55	9.1	18.6	28.4
22	8.95	17.05	27.05	24.15	34.05	11.15	29.65	7.4	8.05	10.6	17.0	29.4
23	8.45	16.35	26.25	23.85	33.55	16.0	29.4	7.4	7.95	11.9	14.0	30.0
24	8.05	16.0	25.0	24.0	33.4	13.85	28.35	7.3	7.7	12.1	11.1	33.6
25	7.8	16.9	23.45	27.15	33.6	13.7	27.15	7.25	7.95	11.7	9.7	33.8
26	7.7	16.05	21.6	27.65	34.25	15.05	26.1	7.25	7.95	10.2	9.3	33.6
27	7.55	16.35	19.4	27.5	34.7	21.6	25.5	7.1	7.8	9,5	9.1	33.2
28	7.5	16.45	16.1	27.5	34.65	27.15	25.05	7.1	7.7	10.1	9.0	32.8
29	7.4	.....	17.2	27.6	34.25	26.95	25.0	7.05	7.6	11.9	8.9	32.3
30	7.7	.....	18.65	28.15	33.65	26.15	25.25	7.0	7.45	13.2	8.9	31.8
31	7.65	.....	18.55	.....	33.05	.....	25.55	7.0	.....	13.4	.....	30.4

Station rating table for Sabine River near Longview, Tex., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
6.00	44	7.90	300	9.80	660	13.40	1,461
6.10	53	8.00	317	9.90	680	13.60	1,509
6.20	63	8.10	335	10.00	700	13.80	1,557
6.30	74	8.20	353	10.20	742	14.00	1,605
6.40	85	8.30	371	10.40	784	14.20	1,653
6.50	97	8.40	389	10.60	826	14.40	1,701
6.60	109	8.50	407	10.80	869	14.60	1,750
6.70	122	8.60	426	11.00	913	14.80	1,800
6.80	135	8.70	445	11.20	957	15.00	1,850
6.90	148	8.80	464	11.40	1,001	15.50	1,975
7.00	162	8.90	483	11.60	1,045	16.00	2,103
7.10	176	9.00	502	11.80	1,090	16.50	2,233
7.20	190	9.10	521	12.00	1,136	17.00	2,366
7.30	205	9.20	540	12.20	1,182	18.00	2,640
7.40	220	9.30	560	12.40	1,228	19.00	2,938
7.50	235	9.40	580	12.60	1,274	20.00	3,310
7.60	251	9.50	600	12.80	1,320	21.00	3,746
7.70	267	9.60	620	13.00	1,366	22.00	4,230
7.80	283	9.70	640	13.20	1,413		

The above table is based on 23 discharge measurements made during 1904 and 3 made during 1905. It is well defined between gage heights 6 feet and 22 feet. Above 22 feet the discharge is only approximate. Below 19 feet the table is the same as for 1904.

Estimated monthly discharge of Sabine River near Longview, Tex., for 1905.

[Drainage area, 2,900 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	1,001	148	385	23,670	0.133	0.153
February	2,570	259	1,251	69,480	.431	.449
March	8,490	512	3,134	192,700	1.08	1.24
April	8,865	2,542	5,511	327,900	1.90	2.12
May	19,480	9,735	16,640	1,023,000	5.74	6.62
June	14,980	512	4,470	266,000	1.54	1.72
July	16,680	4,106	9,777	601,200	3.37	3.88
August	7,316	162	1,934	118,900	.667	.769
September	326	135	195	11,600	.067	.075
October	1,461	122	461	28,350	.159	.183
November	2,907	483	1,382	81,900	.459	.512
December	17,360	660	6,388	392,800	2.20	2.54
The year	19,480	122	4,290	3,138,000	1.48	20.26

NECHES RIVER AT EVADALE, TEX.

A gaging station was established on Neches River at Evadale July 1, 1904, by Thomas U. Taylor. It is located at the bridge of the Gulf, Beaumont and Kansas City Railway.

The clear span or water way under each arm of the draw span is 50 feet, and the bridge continues each way on trestles. The left bank is high, whence the name of the railroad station, Fords Bluff, but the right or west bank is low and the trestle work continues about half a mile from the river channel.

Discharge measurements are made from the bridge at ordinary and high stages. At low water the current is very sluggish, and discharge measurements are made at shoals above or below the station.

Gage readings are made by reading down from the top of the tie to the water surface by means of a tape. The zero of the gage is 40.00 feet below the top of the tie in the west arm of the draw span of the bridge. During 1905 the gage was read by W. H. Whittemore.

A description of this station and gage height and discharge data are contained in Water-Supply Paper No. 132 of the United States Geological Survey, pages 23–24.

Discharge measurements of Neches River at Evadale, Tex., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-feet.*
March 27	H. H. Fox	21.6	13,730
March 29	do	22.1	14,240
June 24	T. U. Taylor	15.2	3,389
July 3	do	18.1	7,130

Daily gage height, in feet, of Neches River at Evadale, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	19.2	16.6	19.4	21.5	21.0	22.1	20.0	18.7	11.1	7.9	8.6	14.7
2	19.2	16.6	19.3	21.3	21.1	21.9	18.4	18.2	10.8	7.9	8.6	14.1
3	19.0	17.2	19.2	21.1	21.3	21.7	17.8	17.6	10.3	7.8	8.7	13.3
4	18.5	17.0	19.1	21.1	21.5	21.7	17.5	17.1	10.0	7.8	8.8	13.6
5	18.0	16.5	19.0	21.4	21.8	21.6	17.2	16.9	10.0	7.8	9.2	14.1
6	17.8	16.0	18.8	21.6	21.8	21.5	17.3	16.8	9.6	7.8	9.6	14.1
7	17.8	16.0	18.7	21.8	21.8	21.3	17.5	17.1	10.3	7.8	10.0	14.1
8	17.9	16.6	18.5	22.0	21.8	21.1	17.9	18.6	11.8	7.8	11.4	14.2
9	17.9	17.0	18.3	22.3	21.7	20.6	18.7	19.0	11.3	7.8	12.8	14.3
10	17.9	17.3	18.2	22.5	21.7	20.0	19.4	19.3	10.6	7.7	13.9	14.0
11	17.8	17.7	19.6	22.6	21.7	19.2	19.7	19.2	10.0	7.7	15.1	14.0
12	17.7	18.0	19.1	22.6	21.8	18.1	20.0	19.2	9.4	7.6	16.0	14.1
13	17.5	18.5	19.4	22.5	21.9	17.2	20.3	19.2	9.1	7.6	16.9	14.5
14	17.3	19.0	19.7	22.3	22.0	16.8	20.7	19.1	9.0	7.5	17.2	14.8
15	17.5	19.6	19.9	22.0	22.0	16.1	20.9	18.9	9.0	7.4	18.0	15.2
16	17.2	19.3	19.7	21.7	22.1	15.7	21.1	18.5	9.1	7.5	18.0	16.6
17	17.5	19.3	19.6	21.5	22.2	15.4	21.4	17.8	8.7	7.5	17.9	16.8
18	16.7	19.0	19.6	21.3	22.3	15.2	21.6	17.0	8.5	7.4	17.9	17.0
19	15.9	18.6	19.9	21.1	22.6	14.9	21.7	16.1	8.5	7.4	17.7	17.1
20	15.0	18.4	20.2	21.0	22.9	14.5	21.9	15.4	8.5	7.4	17.5	17.2
21	14.7	18.4	20.5	20.9	23.1	14.0	21.8	14.7	8.5	7.2	17.6	17.2
22	14.6	19.0	20.8	20.6	23.4	13.4	21.6	14.1	8.4	7.2	17.6	18.0
23	14.3	19.4	21.0	20.4	23.6	13.7	21.4	13.6	8.4	7.2	17.7	18.4
24	14.1	19.6	21.1	20.5	23.6	14.6	21.2	13.1	8.4	7.0	17.5	18.6
25	14.0	19.5	21.5	20.4	23.5	17.9	21.1	12.5	8.4	7.0	17.4	19.1
26	13.7	19.7	21.5	20.3	23.3	18.5	20.7	11.9	8.3	7.3	17.1	19.7
27	13.6	19.7	21.6	20.3	23.1	18.7	20.4	11.4	8.2	7.6	16.7	19.9
28	13.6	19.6	21.7	20.3	23.0	19.1	20.1	11.0	8.1	7.9	16.1	20.1
29	13.4	.....	21.8	20.4	22.7	19.3	19.9	10.6	8.0	8.0	15.7	19.3
30	13.1	.....	21.8	20.8	22.5	19.1	19.2	10.8	7.9	8.3	15.2	19.8
31	15.0	.....	21.6	.....	22.4	.....	19.5	11.4	.....	8.6	.....	20.0

Station rating table for Neches River at Evadale, Tex., from July 1, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
5.00	180	6.70	429	8.80	854	12.00	1,800
5.10	191	6.80	447	9.00	900	12.50	2,010
5.20	202	6.90	465	9.20	948	13.00	2,248
5.30	214	7.00	484	9.40	997	13.50	2,508
5.40	226	7.10	503	9.60	1,047	14.00	2,790
5.50	239	7.20	522	9.80	1,098	14.50	3,110
5.60	252	7.30	541	10.00	1,150	15.00	3,480
5.70	266	7.40	560	10.20	1,204	15.50	3,890
5.80	280	7.50	580	10.40	1,260	16.00	4,350
5.90	295	7.60	600	10.60	1,318	17.00	5,410
6.00	310	7.70	620	10.80	1,378	18.00	6,660
6.10	326	7.80	640	11.00	1,442	19.00	8,270
6.20	342	7.90	660	11.20	1,509	20.00	10,100
6.30	359	8.00	680	11.40	1,578	21.00	12,090
6.40	376	8.20	722	11.60	1,650	22.00	14,300
6.50	393	8.40	765	11.80	1,724	23.00	16,750
6.60	411	8.60	809				

The above table is based on seven discharge measurements made during 1904-5. It is fairly well defined between gage heights 5.6 feet and 22 feet. Above 22 feet the discharge is approximate.

Estimated monthly discharge of Neches River at Evadale, Tex., for 1904 and 1905.

[Drainage area, 8,200 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
1904.						
July	1,232	503	1,027	63,150	0.125	0.144
August	1,922	411	879	54,050	.107	.123
September	640	326	463	27,550	.056	.062
October	503	202	291	17,890	.035	.040
November	266	202	209	12,440	.025	.028
December	7,590	280	1,043	64,130	.127	.146
The period				239,200		
1905.						
January	8,620	2,298	5,090	313,000	.621	.716
February	9,530	4,350	7,171	398,300	.875	.911
March	13,840	6,960	10,210	627,800	1.25	1.44
April	15,750	10,670	12,870	765,800	1.57	1.75
May	18,300	12,090	15,070	926,600	1.84	2.12
June	14,540	2,454	7,865	468,000	.959	1.07
July	14,070	5,640	10,180	625,900	1.24	1.43
August	8,800	1,318	5,127	315,200	.625	.721
September	1,724	660	986	58,670	.120	.134
October	809	484	606	37,260	.074	.085
November	6,660	809	4,217	250,900	.514	.574
December	10,290	2,402	5,312	326,600	.648	.747
The year	18,300	484	7,059	5,114,000	.861	11.70

TRINITY RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Trinity River rises in a network of small streams in the counties of Montague, Jack, Wise, Denton, and Parker, Tex., but their combined flow above Dallas is not sufficient to keep the bottom or bed of the stream moist in dry times. Below Dallas the Trinity flows through a wooded country, and consequently it is not subject to sudden floods with their quick run-offs.

TRINITY RIVER AT RIVERSIDE, TEX.

A gaging station was established on Trinity River at Riverside, Tex., in December, 1902, by Thomas U. Taylor. It is located at the bridge of the International and Great Northern Railroad.

The channel is straight for 300 feet above and 1,000 feet below the bridge. The current is sluggish at low and swift at high stages. The right bank is high and rocky. The left bank is lower than the right, a trestle being used to measure the overflow at flood stages. The bed of the stream consists of tough mud or clay.

Discharge measurements are made from the railroad bridge. The initial point for soundings is the north face of the south abutment for the south channel. For the north channel the north face of the pier is the initial point.

During 1905 the gage was read by G. W. Higdon. The zero of the gage is 66.00 feet below the top of the ties (or base of rail) in the north arm of the draw span of the International and Great Northern Railroad bridge. The elevation of the top of the pivot pier above gage datum is 56.50 feet, and that of the top of the channel of the *lower chord of the arms of the* draw span of the bridge is 62.90 feet. According

to the survey of the United States Army engineers the elevation of the top of the tie with reference to mean low tide of the gulf is 148.70 feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 84, pp 142–143; 99, pp 322–323; 132, p 25.
Discharge: 84, p 143; 99, p 323; 132, p 26.
Discharge, monthly: 99, p 325; 132, p 28.
Gage heights: 99, pp 323–324; 132, p 26.
Rating table: 99, p 324; 132, p 27.

Discharge measurements of Trinity River at Riverside, Tex., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Second-feet.*
July 4	T. U. Taylor	37.6	24,6[illegible]
July 4	do	37.0	23,8[illegible]
July 5	do	35.8	21,4[illegible]
July 5	do	34.8	20,4[illegible]
July 6	H. H. Fox	32.7	18,9[illegible]
July 7	do	31.5	17,8[illegible]
July 8	do	30.2	17,3[illegible]

Daily gage height, in feet, of Trinity River at Riverside, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	10.4	9.2	17.9	28.5	42.5	49.1	45.7	34.4	10.4	8.5	11.5	11.2
2	9.5	9.5	15.4	25.6	43.1	48.6	44.0	34.4	10.1	8.4	11.2	12.0
3	9.1	9.5	12.7	29.2	42.9	48.0	41.6	34.3	9.8	8.3	10.5	12.2
4	8.9	9.4	11.4	29.2	41.4	47.4	38.5	33.7	9.1	8.3	10.3	11.9
5	8.8	9.4	10.7	29.0	39.4	46.9	35.8	33.7	8.9	8.2	10.2	11.5
6	8.6	9.4	10.2	28.6	37.7	46.4	33.5	32.2	8.9	8.1	10.3	11.1
7	8.5	9.7	10.0	27.5	36.3	46.1	31.8	31.9	8.9	8.1	11.1	12.5
8	8.4	10.7	10.0	26.6	35.8	45.9	30.3	31.4	8.8	8.0	12.3	12.7
9	8.4	13.2	22.8	26.2	36.4	45.9	32.4	30.9	8.7	8.0	12.6	12.4
10	8.4	13.6	15.4	26.2	38.0	45.9	34.3	29.9	8.7	10.0	17.5	11.7
11	8.3	13.3	16.4	26.2	38.6	45.8	35.2	28.5	8.6	13.0	17.6	11.0
12	9.5	14.0	23.3	26.7	39.0	45.6	35.7	26.3	8.5	13.5	17.9	10.5
13	11.7	14.3	20.1	27.2	39.6	45.0	35.5	18.7	8.5	12.9	17.7	10.5
14	11.4	15.0	18.8	27.7	40.6	44.2	34.5	14.0	8.4	11.9	17.3	12.8
15	10.6	15.1	19.4	27.8	43.3	43.6	33.7	11.9	8.4	10.7	17.9	17.2
16	9.9	14.5	20.0	27.8	46.6	41.8	32.7	11.4	8.4	10.0	17.7	18.6
17	10.0	13.6	20.0	27.8	48.5	38.0	31.9	11.2	8.3	9.4	19.4	20.0
18	11.9	12.5	22.6	27.4	49.8	29.7	31.0	11.2	8.3	9.0	19.5	20.5
19	12.7	15.7	27.0	27.2	50.0	19.7	31.0	11.0	8.2	8.9	19.7	22.5
20	12.7	19.7	27.3	26.7	52.4	15.7	29.5	10.5	8.7	9.2	19.6	26.7
21	11.9	19.4	28.1	25.4	48.9	14.0	32.1	10.3	9.0	13.5	19.4	29.8
22	10.9	19.9	29.2	22.1	48.0	16.4	29.0	10.0	9.0	14.1	18.7	31.9
23	10.2	18.9	27.5	18.3	47.1	18.8	29.2	10.0	9.2	13.8	17.1	32.5
24	9.7	18.0	26.7	17.4	46.2	18.8	30.0	10.0	9.2	14.0	15.7	32.3
25	8.7	18.0	27.2	32.9	46.5	18.1	30.1	9.7	9.7	14.7	15.7	31.8
26	9.1	18.5	26.4	36.4	46.6	18.8	30.5	9.7	9.8	14.2	14.7	31.5
27	9.0	18.8	28.2	37.7	47.7	37.7	30.5	9.5	9.5	13.2	14.1	31.5
28	8.9	18.6	29.0	36.3	48.9	44.8	31.0	8.4	9.3	12.2	13.6	32.0
29	8.8	.....	32.1	34.2	47.7	47.0	33.8	8.3	9.0	12.4	12.6	32.3
30	8.8	.....	31.1	40.6	49.9	46.8	34.1	8.3	8.7	12.2	11.8	32.7
31	8.8	.....	30.3	.....	48.7	.....	34.1	10.6	.....	12.5	.....	33.0

Estimated monthly discharge of Trinity River at Riverside, Tex., for 1905.

[Drainage area, 16,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
anuary	2,779	441	1,108	68,130	0.069	0.080
ebruary	8,081	761	4,064	225,700	.254	.264
arch	18,580	1,150	9,716	597,400	.607	.700
pril	26,730	6,138	15,310	911,000	.957	1.07
ay	38,500	22,020	30,260	1,861,000	1.89	2.18
ne	35,200	3,630	24,180	1,439,000	1.51	1.68
ly	31,800	15,780	20,070	1,234,000	1.25	1.44
ugust	20,680	441	8,136	500,300	.508	.586
eptember	1,375	413	682	40,580	.043	.048
ctober	4,127	360	1,848	113,600	.116	.134
ovember	7,923	1,261	4,613	274,500	.288	.321
ecember	19,950	1,433	9,270	570,000	.579	.668
The year	38,500	360	10,770	7,835,000	.673	9.17

NOTE.—Above estimates subject to large error for low and medium stages owing to the inconsistent ata on which the rating table was based.

BRAZOS RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

This river has its source in the Staked Plains region of western Texas and has a eneral southeasterly course, emptying into the Gulf of Mexico south of the mouth f Trinity River. Its drainage basin is entirely within the State of Texas.

BRAZOS RIVER AT WACO, TEX.

This station was established September 14, 1898, by Thomas U. Taylor. It is ocated at the suspension bridge on Bridge street, Waco, Tex.

The channel is straight for 1,000 feet above and 300 feet below the station. There s a good current at all stages. The right bank is composed of limestone and does ot overflow. The left bank is high, but overflows during floods. The bed of the tream is composed of sand, free from vegetation, and slightly shifting. A single-pan truss bridge crosses the river at an angle of 76° about 300 feet above the uspension bridge.

Discharge measurements are made from the suspension bridge. The initial point or soundings is the edge of the right abutment.

An inclined gage in three sections is located on the left bank under the bridge. During 1905 the gage was read twice each day by W. J. Cassaday. Bench marks were established as follows: (1) The top of the water table on the top of the south pier f the abutment of the suspension bridge, about 3 inches above the floor, marked "U. S. G. S. B. M."; elevation, 44.33 feet above the datum of the gage. (2) United tates Coast and Geodetic Survey bolt in the side of Patton's feed store; elevation, 5.60 feet above the datum of the gage and 413.18 feet above mean low tide. (3) he floor of the truss bridge above the suspension bridge, at the foot of the down-tream batter brace on the Waco side; elevation, 45.40 feet above the datum of the age.

Information in regard to this station is contained in the following Water-Supply apers of the United States Geological Survey:

Description: 28, p 118; 37, p 272; 50, p 333; 66, p 58–59; 84, pp 143–144; 99, pp 325–326; 132, pp 28–29.
Discharge: 28, p 129; 37, p 272; 50, p 334; 66, p 59; 84, pp 144–145; 99, p 327; 132, p 30.
Discharge, monthly: 75, pp 150–151; 84, p 146; 99, p 328; 132, p 31.
Gage heights: 28, p 121; 37, p 273; 50, p 334; 66, p 59; 84, p 145; 99, p 327; 132, p 30.
Rating tables: 66, p 173; 84, p 146; 99, p 328; 132, p 31.

Discharge measurements of Brazos River at Waco, Tex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
May 1[a]	W. J. Cassaday	450	11,350	7.75	29.0	88,000
May 2	H. H. Fox	460	4,055	4.02	12.5	16,320
May 2	do	450	3,540	3.78	11.4	13,400
May 2	do	450	4,660	4.22	13.9	19,680
May 3	do	440	2,800	3.40	9.7	9,520
May 3	do	445	3,100	3.51	10.4	10,880
May 4	do	440	2,390	3.26	8.8	7,780
May 8	do	480	10,420	7.11	26.7	74,110
May 9	do	460	6,820	5.59	18.8	38,090
May 9	do	450	5,210	4.44	15.3	23,140
August 10	T. U. Taylor	380	1,140	3.00	6.1	3,418
August 11	do	380	960	2.78	5.5	2,673
August 12	do	380	888	2.62	5.4	2,322
August 19	do	380	524	1.65	3.9	866
August 26	do	305	386	1.53	3.5	591

[a] Float measurement.

Daily gage height, in feet, of Brazos River at Waco, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.5	2.8	3.2	4.8	25.0	7.1	7.1	6.9	3.1	3.35	3.05	3.15
2	2.5	2.8	3.2	10.35	12.9	6.9	6.55	6.7	3.1	3.15	3.0	3.2
3	2.5	2.75	3.2	11.6	10.5	6.65	6.3	6.55	3.1	3.0	2.9	3.15
4	2.5	2.7	3.15	8.7	9.3	6.0	6.75	6.4	3.0	4.8	2.85	3.1
5	2.5	2.7	3.1	7.7	9.1	5.75	6.55	6.05	3.1	5.9	2.8	3.0
6	2.5	2.7	3.1	7.35	13.15	5.35	6.7	6.0	3.0	4.9	2.8	2.95
7	2.5	2.7	3.3	7.05	10.7	4.9	9.2	7.1	3.0	4.55	2.8	2.85
8	2.5	2.7	3.75	6.65	14.1	4.8	7.95	7.6	3.0	4.1	2.75	2.8
9	2.5	2.85	4.5	6.55	15.0	4.7	7.3	7.1	3.0	4.25	3.65	2.8
10	2.5	3.5	4.15	6.4	5.2	4.65	6.9	6.55	2.95	4.65	4.15	2.8
11	2.55	3.3	4.0	5.9	9.35	4.55	6.5	5.75	2.9	4.4	3.95	2.8
12	5.3	3.3	3.75	5.65	11.0	4.4	7.7	5.75	3.0	4.6	3.85	2.85
13	4.55	3.2	3.65	5.3	17.45	4.3	7.4	5.5	8.1	4.3	5.0	4.1
14	3.25	3.1	3.55	5.9	28.6	4.25	7.65	5.0	8.95	4.1	4.5	5.1
15	2.9	2.95	3.6	4.55	13.5	4.4	7.4	4.75	7.3	3.95	4.3	4.95
16	2.65	3.5	4.05	4.15	11.8	4.9	6.55	4.6	6.6	3.75	4.3	4.45
17	3.1	3.0	5.65	4.25	11.7	4.75	6.45	4.35	6.3	3.55	4.15	4.2
18	3.2	3.6	8.15	4.1	10.5	4.55	6.1	3.95	6.45	3.4	3.85	4.2
19	3.1	4.85	6.3	4.1	9.3	4.65	5.55	3.75	6.3	5.35	3.65	4.
20	3.0	4.95	6.1	4.1	8.6	4.8	4.9	5.15	6.05	7.55	3.5	5.
21	3.0	4.1	7.25	4.05	7.8	7.6	4.15	4.7	6.65	6.6	3.45	5.
22	2.95	3.75	5.5	4.0	13.8	8.8	4.2	4.35	5.05	5.75	3.35	4.
23	2.9	3.55	5.1	4.0	12.7	7.35	4.7	4.0	4.5	5.55	3.3	4.
24	2.9	3.4	4.95	14.2	16.15	8.25	4.5	3.9	4.3	5.1	3.4	4.
25	2.9	3.25	4.55	14.0	15.05	7.5	4.75	3.8	4.1	4.4	3.4	3.9
26	2.85	3.2	4.15	8.8	13.9	7.55	6.8	3.65	4.0	4.15	3.4	3.7
27	2.8	3.25	4.05	13.15	13.35	8.35	12.0	3.45	3.85	4.0	3.35	3.5
28	2.8	3.3	4.05	9.3	11.6	12.55	17.1	3.3	3.8	3.75	3.25	3.5
29	2.8	.....	5.1	10.1	9.0	8.65	12.9	3.25	3.65	3.55	3.2	3.45
30	2.8	.....	5.15	22.0	8.7	7.45	9.0	3.2	3.55	3.45	3.1	3.4
31	2.8	.....	4.7	.....	7.85	.....	7.55	3.1	.....	3.3	.....	3.5

n rating table for Brazos River at Waco, Tex., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.00	62	3.70	820	5.80	2,955	9.50	9,200
2.10	82	3.80	900	6.00	3,220	10.00	10,260
2.20	104	3.90	980	6.20	3,490	10.50	11,360
2.30	128	4.00	1,065	6.40	3,770	11.00	12,510
2.40	145	4.10	1,150	6.60	4,055	11.50	13,700
2.50	184	4.20	1,235	6.80	4,345	12.00	14,900
2.60	215	4.30	1,320	7.00	4,645	12.50	16,150
2.70	248	4.40	1,410	7.20	4,955	13.00	17,450
2.80	284	4.50	1,500	7.40	5,275	13.50	18,800
2.90	323	4.60	1,595	7.60	5,605	14.00	20,200
3.00	365	4.70	1,695	7.80	5,945	14.50	21,660
3.10	410	4.80	1,795	8.00	6,300	15.00	23,180
3.20	460	4.90	1,900	8.20	6,660	16.00	26,400
3.30	520	5.00	2,005	8.40	7,030	17.00	29,850
3.40	590	5.20	2,225	8.60	7,410	18.00	33,500
3.50	665	5.40	2,455	8.80	7,790		
3.60	740	5.60	2,700	9.00	8,190		

e above table is based on discharge measurements made during 1900 to 1905 and is well defined.

Estimated monthly discharge of Brazos River at Waco, Tex., for 1905.

[Drainage area, 30,750 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ıry	2,340	184	388	23,860	0.013	0.015
ıary	1,952	248	585	32,490	.019	.020
h	6,570	410	1,642	101,000	.053	.061
	50,400	1,065	7,347	437,200	.239	.267
	85,500	2,225	18,280	1,124,000	.594	.685
	16,280	1,277	3,898	231,900	.127	.142
	30,210	1,235	5,771	354,800	.188	.217
st	5,605	410	2,276	139,900	.074	.085
mber	8,090	323	1,906	113,400	.062	.069
er	5,522	365	1,561	95,980	.051	.059
mber	2,005	266	718	42,720	.023	.026
mber	2,515	284	931	57,240	.030	.035
The year	85,500	184	3,775	2,754,000	.123	1.68

BRAZOS RIVER AT RICHMOND, TEX.

his station was established January 1, 1903, by Thomas U. Taylor. It is located e bridge of the Southern Pacific Railroad.

he channel is straight for 200 feet above and 900 feet below the station, and has a th of about 175 feet at low water, without piers, and about 500 feet at ordinary h water, broken by three piers. During very high floods the left bank overflows the width of the stream is 900 feet. The bed of the stream is sandy except und the piers, where it is stony, and is slightly shifting. The current is obstructed ewhat by old piles. Above and at Waco the river rises rapidly, and when it s above gage height 30 feet overflows the bottom lands below the town. When

the floods spread out over the bottom lands, as they do from Waco to Richmond, the river stays up longer in its lower stretches than it does in the upper sections, as the bottoms and the lowlands serve as storage reservoirs for the backwater and are drained slowly as the river recedes. Above Waco the surface water rushes off into the stream more rapidly, and the river rises more suddenly and falls almost as suddenly. For this reason it is possible for the maximum discharge at Waco to be greater than it is at Richmond.

Discharge measurements are made from the bridge. The initial point for soundings is the east face of the pier under the west end of the middle span.

A standard chain gage is attached to the bridge; length of chain, 53.82 feet. During 1905 the gage was read once each day by J. E. Winston. Bench marks were established as follows: (1) The top of the tie at the downspout of the gage box in the central panel of the middle span on the downstream side of the bridge; elevation, 51.52 feet. (2) A point marked "R. F." on the southeast corner of the tie seat of west abutment; elevation, 51.11 feet. (3) The top of the north bolt in flange of hydrant at corner of Railroad and First streets, 6 inches below the top of the hydrant; elevation, 47.26 feet. (4) The top of the northeast corner of base stone of "Our Heroes" monument in the court-house square; elevation, 53.52 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 84, p 147; 99, p 329; 132, pp 32–33.
Discharge: 84, p 147; 99, p 330; 132, p 33.
Discharge, monthly: 99, p 332; 132, p 35.
Gage heights: 99, pp 330–331; 132, p 33.
Rating table: 99, p 331; 132, p 34.

Discharge measurements of Brazos River at Richmond, Tex., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Second-feet.*
July 25	T. U. Taylor	9.1	9,400
August 4	do	8.4	7,960

Daily gage height, in feet, of Brazos River at Richmond, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	2.5	6.1	5.6	10.1	28.1	18.1	19.5	13.6	3.4	3.1	3.4	3.1
.....	3.2	6.0	5.4	9.9	28.2	18.1	19.1	10.3	3.3	3.0	3.2	3.0
.....	4.1	5.8	4.8	9.2	28.3	15.1	18.9	9.3	3.4	3.0	3.3	3.0
.....	2.9	5.6	3.6	15.9	30.2	14.0	17.4	8.4	3.4	4.9	3.2	3.1
.....	2.7	5.1	6.0	18.1	31.9	13.8	17.1	7.8	3.6	2.5	3.2	3.2
.....	2.6	6.1	9.7	17.1	33.0	13.6	15.6	7.8	3.0	2.5	3.3	3.2
.....	2.3	5.9	10.1	15.0	32.9	13.5	15.2	6.2	2.6	2.5	3.4	3.3
.....	2.6	6.0	9.5	13.2	32.2	11.8	14.8	6.3	2.6	2.5	3.6	3.3
.....	3.1	6.1	8.8	12.0	31.2	11.5	14.5	6.35	2.6	2.6	3.7	3.5
.....	3.1	6.0	11.9	11.7	32.1	11.0	14.3	6.5	2.6	2.8	3.8	3.3
.....	3.1	6.1	11.4	11.1	31.1	11.0	14.3	6.7	2.6	3.2	4.0	3.2
.....	3.1	5.6	10.9	10.9	31.0	9.9	14.2	7.0	2.6	3.4	4.1	3.3
.....	3.1	6.1	10.6	10.8	31.3	8.6	14.1	7.1	4.3	3.2	4.2	3.3
.....	3.1	6.4	9.6	10.6	31.5	9.1	14.0	6.0	4.8	3.2	4.2	3.4
.....	3.1	6.3	7.7	10.1	31.5	8.6	14.0	5.1	5.7	3.2	4.3	3.5
.....	3.1	8.0	10.1	9.1	31.8	8.4	13.8	5.2	6.2	3.2	4.3	3.7
.....	3.6	10.6	8.3	8.1	32.1	8.2	13.0	5.4	6.5	3.2	4.5	4.6
.....	5.4	10.8	11.1	8.0	32.1	8.2	11.3	5.1	6.7	3.2	4.5	6.3
.....	3.9	9.8	16.1	7.8	31.6	8.2	11.1	4.9	7.0	3.2	4.3	8.0
.....	3.8	10.1	17.1	5.0	31.65	8.3	10.8	4.7	6.3	3.1	4.2	8.4
.....	3.5	9.1	17.1	2.8	28.6	8.2	9.7	4.0	4.3	3.1	4.0	8.4
.....	3.0	9.3	15.4	2.5	28.6	8.4	9.2	4.0	4.4	4.2	3.8	8.7
.....	2.8	10.1	13.9	2.1	29.0	9.9	9.1	4.0	4.6	5.7	3.5	8.8
.....	3.0	7.8	14.9	2.2	27.8	11.8	9.1	4.0	5.3	6.3	3.6	8.0
.....	3.0	7.1	13.3	20.1	25.7	11.8	9.1	4.0	5.3	7.1	3.4	7.1
.....	5.1	5.9	12.8	20.6	25.5	12.1	6.5	4.0	4.2	6.8	3.4	7.3
.....	6.1	5.0	10.8	21.7	25.0	22.0	8.0	3.9	4.4	5.3	3.3	7.5
.....	6.1	5.1	9.1	23.6	24.7	20.8	11.4	3.9	4.2	4.8	3.3	7.3
.....	6.0	.....	10.7	23.5	20.9	20.3	13.7	3.8	4.2	4.5	3.3	7.1
.....	5.9	.....	13.4	25.1	18.3	19.9	14.3	3.6	3.4	4.3	3.1	6.1
.....	6.1	.....	11.7	.....	18.1	.....	14.4	3.4	.....	4.0	.....	6.4

Station rating table for Brazos River at Richmond, Tex., from January 1, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.50	820	3.00	1,820	4.50	3,310	7.00	6,500
1.60	870	3.10	1,910	4.60	3,420	7.20	6,780
1.70	920	3.20	2,000	4.70	3,530	7.40	7,060
1.80	980	3.30	2,090	4.80	3,640	7.60	7,350
1.90	1,040	3.40	2,180	4.90	3,760	7.80	7,650
2.00	1,100	3.50	2,270	5.00	3,880	8.00	7,950
2.10	1,160	3.60	2,370	5.20	4,120	8.50	8,700
2.20	1,220	3.70	2,470	5.40	4,360	9.00	9,480
2.30	1,290	3.80	2,570	5.60	4,600	9.50	10,280
2.40	1,360	3.90	2,670	5.80	4,860	10.00	11,120
2.50	1,430	4.00	2,770	6.00	5,120	10.50	12,020
2.60	1,500	4.10	2,870	6.20	5,380	11.00	13,020
2.70	1,580	4.20	2,980	6.40	5,660	11.50	14,120
2.80	1,660	4.30	3,090	6.60	5,940	12.00	15,270
2.90	1,740	4.40	3,200	6.80	6,220	13.00	17,590

The above table is based on discharge measurements made during 1902–1905, and it is well defined. Above gage height 13 feet the rating curve is a tangent, the difference being 240 per tenth. Above 10 feet this table is the same as the 1903 table.

Estimated monthly discharge of Brazos River at Richmond, Tex., for 1905.

[Drainage area, 44,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	5,250	1,290	2,594	159,500	0.059	0.068
February	12,620	3,880	6,742	374,400	.153	.159
March	27,430	2,370	13,380	822,700	.304	.350
April	46,630	1,160	17,680	1,052,000	.402	.448
May	65,590	29,830	55,690	3,424,000	1.27	1.46
June	39,190	8,250	17,070	1,016,000	.388	.433
July	33,190	5,800	18,680	1,149,000	.425	.490
August	19,030	2,180	5,290	325,300	.120	.138
September	6,500	1,500	3,169	188,600	.072	.080
October	6,640	1,430	2,665	163,900	.061	.070
November	3,310	1,910	2,498	148,600	.057	.064
December	9,160	1,820	4,465	274,500	.101	.116
The year	65,590	1,160	12,490	9,098,000	.284	3.86

COLORADO RIVER (OF TEXAS) DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Colorado River rises in the extreme western portion of the State, within a few miles of the eastern boundary of New Mexico, and flows in a general southeasterly direction, emptying into the Gulf of Mexico in Matagorda County. The drainage area above Austin is 37,000 square miles and above Columbus 40,000 square miles, and it extends into the corner of New Mexico. Its main tributaries are the Concho, the San Saba, and the Llano. The Concho has a reliable flow and contributes a greater amount of water than the Colorado at their junction. The Concho furnishes water for irrigation and water power and supports in Irion and Tom Green counties some excellent irrigation systems, described in Water-Supply Paper No. 71. San Saba and Llano rivers are described in the same paper.

The Colorado at Austin emerges from a canyon. From Austin to the Gulf it traverses a rather flat country, and its waters are utilized for many power plants; 60,000 acres of rice were sowed during the season of 1902 in the counties of Colorado, Wharton, and Matagorda, under canals that obtained their water from the Colorado.

COLORADO RIVER AT AUSTIN, TEX.

This station was established December 21, 1897. It was originally located at the dam near Austin, Tex. On the failure of this dam the station was removed to the Congress Avenue Bridge, south of the city.

The channel is straight for 400 feet above and below the station. The velocity is moderately rapid. Neither bank has overflowed since the dam was washed away. The bed of the stream is composed of sand and is slightly shifting.

Discharge measurements are made by means of a cable and car 3 miles above Congress Avenue Bridge, about one-eighth mile above the ruins of the Austin dam and power house. The cable has a span of about 730 feet, but the width of the river at low water is less than half this distance.

Gage heights were first taken on the crest of the Austin dam August 13, 1895, and were continued from that date until the failure of the dam occurred in April, 1900. A staff gage consisting of upright posts driven into the bank of the river is located

ar the bath house about 150 feet above the bridge. For higher gage heights the st pier from the north has been marked up to 40.00 feet. A standard chain ge is attached to the bridge at the same datum. During 1905 the gage was read rice each day by W. Peterson. Bench marks were established as follows: (1) A nited States Coast and Geodetic Survey copper bolt on the top of the west end of e south pier of Congress Avenue Bridge, 475 feet above mean sea level and 48.00 feet ove the datum of the gage. (2) A similar bolt in the southwest wall of the post-fice at Austin, 508 feet above mean sea level; elevation, 81.00 feet above the datum f the gage. (3) On the first flange above the cribwork of the north pier of the ridge, marked "U. S. G. S. B. M. 4.78"; elevation, 4.78 feet above gage datum and 31.78 feet above mean sea level.

The low-water level at this point has been gradually falling for over a year. This as been caused by the erosion of the channel about 200 yards below the highway ridge. Under the highway bridge the water spreads out into a large pool, the utlet of which is through two contracted sections below, the main one of which eing the one in which the erosion has taken place. The lowest level that the water as reached yet has been 0.70 foot by gage, but the corresponding discharge was no ess than the minimum of 1902.

Information in regard to this station is contained in the following publications of he United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Bull 140, pp 82–83; WS 28, pp 118–119; 37, p 274; 50, pp 336–337; 66, p 64; 84, pp 149–150; 99, p 334; 132, p 36.
Discharge: Ann 18, iv, p 110; Bull 140, p 83; WS 28, p 129; 37, p 274; 50, p 337; 66, p 64; 84, p 150; 99, p 335; 132, p 37.
Discharge, monthly: WS 75, p 152; 84, p 152; 99, p 336; 132, p 39.
Gage heights: WS 28, pp 122–124; 37, p 275; 50, p 338; 66, p 64; 84, p 151; 99, p 335; 132, p 38.
Hydrograph: WS 75, p 152.
Rating tables: WS 66, p 173; 84, p 151; 99, p 336; 132, p 39.

Discharge measurements of Colorado River at Austin, Tex., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Second-feet.*
July 15	H. H. Fox	2.7	1,760
July 17	do	2.2	1,111
July 21	do	1.7	520
August 19	do	1.1	240
September 3	do	.8	176
September 16	T. U. Taylor	.8	171

Daily gage height, in feet, of Colorado River at Austin, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.3	1.2	1.3	1.8	7.9	2.75	2.25	4.2	0.8	1.25	1.0	1.0
2	1.25	1.2	1.3	1.85	6.75	3.7	2.05	3.2	.85	1.15	1.1	1.0
3	1.2	1.2	1.25	2.95	5.35	3.15	1.85	2.75	.8	1.1	1.1	1.0
4	1.2	1.2	1.2	5.5	4.55	2.9	2.0	2.6	.8	1.0	1.1	1.0
5	1.2	1.2	1.2	4.3	4.2	2.65	1.8	2.45	1.0	1.0	1.1	1.0
6	1.2	1.2	1.2	3.5	3.85	2.5	1.7	2.4	1.25	1.0	.95	1.0
7	1.2	1.2	1.25	5.1	3.55	2.5	2.6	2.3	1.0	1.3	1.0	1.0
8	1.2	1.2	1.65	3.75	3.35	2.35	3.3	2.15	.9	2.15	1.0	1.0
9	1.2	1.2	1.6	3.05	10.5	2.2	4.0	1.85	.8	2.95	1.25	1.0
10	1.2	1.2	1.5	2.75	7.85	2.1	4.65	1.55	.8	2.45	1.85	1.0
11	1.2	1.2	1.5	2.55	6.6	2.0	3.95	1.9	.85	2.2	2.4	1.0
12	1.2	1.2	1.6	2.5	4.95	1.9	3.6	1.8	.95	2.05	2.9	1.0
13	1.2	1.6	1.65	2.4	3.9	1.8	3.25	1.65	.9	1.95	2.7	1.25
14	1.3	1.15	1.6	2.4	3.6	1.8	3.05	1.5	.8	1.75	2.25	1.15
15	1.3	1.25	1.6	2.3	4.75	1.8	2.7	1.35	.8	1.55	1.95	1.0
16	1.25	1.15	1.75	2.15	7.6	2.2	2.4	1.3	.8	1.45	1.75	1.0
17	1.2	1.2	2.95	2.0	8.1	2.3	2.2	1.2	1.7	1.3	1.65	1.0
18	1.2	1.25	3.3	2.0	5.6	2.25	2.05	1.2	2.5	1.3	1.4	1.1
19	1.25	1.3	5.7	1.85	3.9	1.9	1.9	1.15	2.2	1.2	1.3	1.35
20	1.2	1.3	3.75	1.8	3.25	1.8	1.8	1.05	2.05	1.3	1.2	1.5
21	1.2	1.3	3.55	1.8	3.0	1.7	1.7	1.0	2.4	2.2	1.2	1.6
22	1.2	1.4	3.55	1.8	2.85	1.75	1.65	1.0	2.15	3.35	1.1	1.5
23	1.2	1.5	3.0	1.7	2.6	2.0	1.55	1.0	1.9	2.55	1.1	1.4
24	1.2	1.5	2.6	4.25	2.55	1.9	1.45	.9	1.8	2.05	1.1	1.6
25	1.2	1.4	2.5	9.2	4.75	3.2	1.4	.9	1.9	1.7	1.1	1.6
26	1.2	1.4	2.4	7.3	4.55	3.15	1.4	.82	1.8	1.45	1.1	1.4
27	1.2	1.4	2.25	6.25	4.45	2.85	1.3	.8	1.7	1.3	1.1	1.2
28	1.15	1.3	2.15	5.75	3.7	2.7	1.3	.8	1.57	1.25	1.1	1.15
29	1.1	.....	2.05	7.65	3.5	2.7	1.8	.9	1.5	1.2	1.05	1.0
30	1.1	.....	1.9	15.05	3.9	2.5	3.6	.9	1.4	1.2	1.0	1.3
31	1.1	.....	1.9	.....	3.35	.....	5.95	.9	.....	1.15	.....	1.2

Station rating table for Colorado River at Austin, Tex., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.80	175	1.90	790	3.00	2,260	4.20	5,170
.90	195	2.00	885	3.10	2,450	4.40	5,810
1.00	220	2.10	990	3.20	2,650	4.60	6,510
1.10	250	2.20	1,105	3.30	2,860	4.80	7,270
1.20	290	2.30	1,225	3.40	3,070	5.00	8,080
1.30	340	2.40	1,345	3.50	3,290	5.20	8,920
1.40	400	2.50	1,470	3.60	3,530	5.40	9,760
1.50	470	2.60	1,605	3.70	3,780	5.60	10,600
1.60	540	2.70	1,750	3.80	4,040	5.80	11,440
1.70	620	2.80	1,910	3.90	4,310	6.00	12,280
1.80	700	2.90	2,080	4.00	4,580	6.20	13,130

The above table is based on discharge measurements made during 1904–5. It is well defined between gage heights 0.8 foot and 6 feet. Above gage height 6.1 feet the rating curve is a tangent the difference being 430 per tenth.

mated monthly discharge of Colorado River at Austin, Tex., for 1905.

[Drainage area, 37,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	340	250	293	18,020	0.0079	0.0091
.....	540	270	335	18,600	.0091	.0095
.....	11,020	290	1,461	89,830	.039	.045
.....	51,190	620	6,557	390,200	.177	.198
.....	31,620	1,537	8,267	508,300	.223	.257
.....	3,780	620	1,404	83,540	.038	.042
.....	12,070	340	1,949	119,800	.053	.061
.....	5,170	175	775	47,650	.021	.024
.....	1,470	175	488	29,040	.013	.014
.....	2,965	220	689	42,360	.019	.022
.....	2,080	207	505	30,050	.014	.016
.....	540	220	299	18,380	.0081	.0093
r	51,190	175	1,918	1,396,000	.052	.707

COLORADO RIVER AT COLUMBUS, TEX.

ion was established in December, 1902, by Thomas U. Taylor. It is he highway bridge east of Columbus.

nel is straight for 200 feet above and 600 feet below the bridge, and has 140 feet at low water, unobstructed by piers, and a width of 450 feet at gh water, broken by two piers. At very high stages the left bank over- veral hundred feet, but the water passes under the iron trestle approach ge. The bed is composed of gravel and sand and is fairly permanent.

e measurements are made from the three-span highway bridge at which located.

marked on the downstream side of the pier on the west side of the river. n is taken at 50 feet below the top of this pier, and the observer, W. E. asures down from this point with a tagged chain and lead weight. Bench established as follows: (1) The top of pier at the west end of the middle bridge; elevation, 50.00 feet. (2) The east end of the top of the top at the south door of the Columbus jail; elevation, 53.22 feet. (3) The of the top stone step at the east door of the Columbus court-house; eleva- feet. (4) The top of the rail over the extreme west pier of the Southern idge crossing the river above the gaging station; elevation, 51.13 feet. refer to the datum of the gage.

rement made at this station August 5, 1905, by T. U. Taylor gave the esults: Gage height, 10.8 feet; discharge, 3,820 second-feet.

ion in regard to this station is contained in the following Water-Supply ne United States Geological Survey:

: 84, p 149; 99, pp 332–333; 132, p 40.
84, p 149; 99, p 333; 132, p 40.
monthly; 132, p 42.
ts: 99, pp 333–334; 132, p 41.
e: 132, p 42.

Daily gage height, in feet, of Colorado River at Columbus, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
1	6.45	5.8	6.4	7.9	30.75	12.25	10.5	7.5	6.8	7.3	7.7	7.
2	6.4	5.8	6.3	8.9	33.0	12.1	10.05	14.15	6.8	7.2	7.7	6.
3	6.4	6.0	6.2	14.1	30.7	11.3	9.6	13.5	7.2	7.15	6.9	6.
4	6.4	6.0	6.2	11.4	21.15	11.15	10.05	11.85	7.1	7.1	6.9	6.
5	6.2	5.8	6.0	9.1	17.4	11.85	10.25	10.6	6.9	7.05	6.9	6.
6	6.2	5.8	6.0	13.55	15.6	11.05	9.65	9.75	6.8	7.0	6.9	6.
7	6.2	5.8	6.0	13.2	14.3	10.4	8.9	9.05	6.8	6.9	7.15	6.
8	6.2	5.8	10.5	11.95	13.25	9.9	8.55	8.55	6.8	6.9	7.0	6.
9	6.0	6.0	12.45	14.0	12.6	9.6	11.75	8.35	6.8	6.75	8.5	6.
10	6.0	6.1	11.4	12.35	16.6	9.55	14.8	8.5	6.9	6.7	9.05	6.
11	6.0	6.2	9.55	11.0	24.5	9.4	15.0	8.5	6.9	6.6	8.4	6.
12	6.0	6.2	8.4	10.25	21.75	9.1	14.0	8.2	6.8	9.05	7.8	6.
13	6.0	6.4	7.85	9.7	17.95	8.65	12.85	8.1	6.7	8.7	7.5	7.
14	7.2	6.4	7.35	8.7	16.8	8.65	12.2	8.1	6.65	8.15	8.0	7.
15	7.05	6.2	9.5	9.05	21.1	8.5	11.3	8.0	6.6	8.05	8.0	7.
16	6.4	6.2	14.45	8.75	18.25	8.5	10.95	7.75	6.6	7.7	8.45	7.
17	6.4	6.0	10.1	8.65	17.0	8.45	10.4	7.55	6.6	7.6	8.35	7.
18	6.2	5.9	13.9	8.5	22.75	8.95	9.7	7.5	6.6	7.6	7.9	7.
19	6.2	15.5	18.5	8.35	20.2	9.35	9.2	7.5	6.6	7.3	7.6	8.
20	6.2	12.0	16.0	8.1	16.05	9.25	8.6	7.25	6.6	7.3	7.45	8.
21	6.0	9.75	15.6	8.0	13.8	8.9	8.6	7.4	7.25	7.2	7.4	8.
22	6.0	8.25	18.75	7.85	12.1	9.5	8.5	7.2	8.1	7.2	7.35	7.
23	6.1	7.5	14.9	7.7	11.8	11.75	8.3	7.05	8.05	7.15	7.2	7.
24	6.1	6.85	16.6	22.25	14.75	9.4	8.15	7.0	8.15	7.45	7.1	7.
25	6.0	6.65	11.05	24.45	13.25	8.5	8.1	6.95	8.35	9.85	7.1	8.
26	6.0	6.55	10.25	24.25	12.3	10.8	8.05	6.9	7.9	9.2	7.15	7.
27	5.95	6.4	9.65	21.65	12.35	24.75	8.0	6.95	7.65	7.9	7.45	7.
28	5.85	6.4	9.15	19.0	14.25	17.0	8.0	6.85	7.45	7.7	7.1	6.
29	5.8	.....	11.4	18.35	13.6	13.25	7.7	6.8	7.5	7.5	7.1	6.
30	5.85	.....	9.2	26.25	12.7	11.5	7.6	6.8	7.5	7.3	7.0	7.
31	5.8	.....	8.25	.....	12.45	.....	7.6	6.8	.....	7.2	.....	7.

Station rating table for Colorado River at Columbus, Tex., from January 1, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
5.40	510	7.30	1,460	9.40	2,850	13.50	6,160
5.50	550	7.40	1,520	9.60	2,990	14.00	6,610
5.60	590	7.50	1,580	9.80	3,130	14.50	7,090
5.70	630	7.60	1,640	10.00	3,270	15.00	7,590
5.80	680	7.70	1,700	10.20	3,410	16.00	8,660
5.90	730	7.80	1,760	10.40	3,570	17.00	9,860
6.00	780	7.90	1,820	10.60	3,730	18.00	11,140
6.10	830	8.00	1,880	10.80	3,890	19.00	12,520
6.20	880	8.10	1,940	11.00	4,050	20.00	13,970
6.30	930	8.20	2,010	11.20	4,210	21.00	15,470
6.40	980	8.30	2,080	11.40	4,370	22.00	17,080
6.50	1,030	8.40	2,150	11.60	4,530	23.00	18,700
6.60	1,080	8.50	2,220	11.80	4,690	24.00	20,420
6.70	1,130	8.60	2,290	12.00	4,850	25.00	22,200
6.80	1,180	8.70	2,360	12.20	5,010	26.00	24,070
6.90	1,230	8.80	2,430	12.40	5,170	27.00	25,980
7.00	1,280	8.90	2,500	12.60	5,350	28.00	27,920
7.10	1,340	9.00	2,570	12.80	5,530		
7.20	1,400	9.20	2,710	13.00	5,710		

The above table is based on discharge measurements made during 1902-1905. It is well defined.

Estimated monthly discharge of Colorado River at Columbus, Tex., for 1905.

[Drainage area, 40,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	1,400	680	895	55,030	0.022	0.025
February	8,110	680	1,044	57,980	.026	.027
March	12,180	780	4,115	253,000	.103	.119
April	24,550	1,700	6,775	403,100	.169	.189
May	37,900	4,690	11,830	727,400	.296	.341
June	21,750	2,185	4,194	249,600	.105	.117
July	7,590	1,640	3,303	203,100	.083	.096
August	6,745	1,180	2,166	133,200	.054	.062
September	2,115	1,080	1,366	81,290	.034	.038
October	3,165	1,080	1,622	99,730	.041	.047
November	2,605	1,230	1,611	95,860	.040	.045
December	2,150	1,030	1,377	84,670	.034	.039
The year	37,900	680	3,358	2,444,000	.084	1.14

SAN SABA RIVER NEAR SAN SABA, TEX.

San Saba River rises in two springs near Fort McKavett, in the western part of Menard County, Tex., and flows in an easterly direction for over 100 miles to its junction with Colorado River (of Texas). It is fed by many springs between Fort McKavett and Menardville, the largest of which is the one that feeds or is the source of Clear Creek.

A gaging station was established on San Saba River at the suspension bridge, 1 mile northwest of the town of San Saba, Tex., December 30, 1904, by E. C. H. Bantel. The drainage area above the town of San Saba is 3,000 square miles.

Sixteen miles above the gaging station the river issues from the canyon section of the river and emerges into a very rich valley that offers exceptional advantages for irrigation. There are about 40,000 acres that could be brought under a supplemental irrigation system, and the water supply of the San Saba River at this point becomes of the utmost importance. The low-water flow at the "Narrows," 17 miles above the town of San Saba, is about 25 second-feet, and any irrigation on an extensive scale will have to be done by means of an impounding dam, which can be constructed across the river near the ranch of Hilliard Doran, forming the reservoir in the canyon section of the river. Four miles above the town of Menardville the Noyes ditch takes out the larger supply of water from the river and diverts it into an irrigation system that extends through Menardville and to a point 5 miles below. Two other smaller ditches below San Saba, the Maimee and the Kitchen, divert practically all the remainder of the low flow into irrigation systems. In addition to the gravity systems there are several pumping plants along the stream from Fort McKavett to the head of the canyons, about 12 miles below Menardville. Thus in dry times about the only water that could be relied on for a big irrigation system in the San Saba Valley would be the water that could be stored by an impounding reservoir. The topography, the flood discharges, the excellent site for a dam, the nearness of stone, the absence of alkali in the water, and the richness of the soil all point to the fact that this valley offers one of the best and most feasible irrigation problems in the State of Texas.

The channel is straight for 150 feet above and 1,000 feet below the station. The current is swift at high and sluggish at low stages. Both banks are high, but liable to overflow at high stages. The bed of the stream is composed of sand and gravel. *There is but one channel at all stages.*

Discharge measurements are made from the suspension bridge. The initial po for soundings is the north face of the south pier.

The elevations of the water surface are determined by measuring down by mea of a tape from a certain casting on the upstream face in the flooring of the bridg the zero elevation being 40.00 feet below the same. Bench marks were establishe as follows: (1) A large wire nail driven into a tree 50 feet from the south end of th bridge; elevation, 37.63 feet. (2) A wire nail driven into a water elm 70 feet from the north end of the bridge, on the east side of the road; elevation, 37.16 feet. (3) A wire nail driven into a live oak tree 200 feet from the south end of the bridge and 50 feet from the edge of the stream; elevation, 37.16 feet. Elevations refer to the datum of the gage.

A measurement made at this station August 18, 1905, by T. U. Taylor, gave the following results: Gage height, 7.2 feet; discharge, 27 second-feet.

A description of this station and gage height and discharge data are contained in Water-Supply Paper No. 132, United States Geological Survey, pp. 43–44.

Daily gage height, in feet, of San Saba River near San Saba, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	7.9	7.9	7.9	7.8	9.8	7.8	7.4	7.3	7.2	7.2	7.6	7.7
2	7.9	7.9	7.9	9.4	8.3	7.8	7.4	7.2	7.2	7.2	7.6	7.7
3	7.9	7.8	7.9	8.4	8.1	7.7	7.4	8.1	7.5	7.2	7.6	7.7
4	7.9	7.8	7.8	8.2	8.1	7.7	7.3	7.6	7.3	7.2	7.6	7.5
5	7.9	7.8	7.8	8.0	8.4	7.6	7.3	7.4	7.2	7.2	7.6	7.5
6	7.9	7.8	7.8	8.0	8.0	7.6	8.2	7.4	7.2	7.2	7.6	7.5
7	7.9	7.8	7.8	7.9	7.8	7.6	8.4	7.4	7.2	7.7	7.7	7.5
8	7.9	8.0	7.8	7.8	13.7	7.5	8.1	7.3	7.2	7.6	7.7	7.5
9	7.9	7.9	7.8	7.8	11.15	7.5	9.7	7.3	7.2	7.6	7.7	7.5
10	7.9	7.9	7.8	7.8	8.9	7.5	8.2	7.2	7.2	7.6	7.9	7.5
11	7.9	7.8	7.9	7.8	8.2	7.5	8.0	7.2	7.2	7.6	7.8	7.5
12	7.8	7.8	7.7	7.8	8.0	7.4	7.8	7.3	7.2	7.6	7.7	7.5
13	7.9	7.9	7.7	7.8	8.0	8.0	7.7	7.3	7.2	7.6	7.6	
14	7.8	7.8	7.8	7.8	7.9	7.6	7.6	7.3	7.2	7.6	7.6	
15	7.8	8.0	7.8	7.8	7.8	7.6	7.5	7.3	7.2	7.6	7.6	
16	7.9	7.9	8.3	7.8	7.9	7.5	7.5	7.3	7.2	7.6	7.6	
17	7.9	7.9	8.0	7.8	8.05	7.4	7.5	7.2	7.2	7.4	7.6	
18	7.9	7.9	7.9	7.7	8.0	7.4	7.5	7.2	7.2	7.4	7.6	
19	7.9	10.0	8.1	7.6	7.9	7.4	7.5	7.2	7.3	19.6	7.6	
20	7.9	10.9	7.9	7.6	7.9	7.4	7.5	7.2	7.4	8.2	7.6	
21	7.9	8.9	7.9	7.6	7.9	7.4	7.6	7.2	7.3	7.7	7.6	
22	7.9	7.9	7.9	7.6	7.9	7.4	7.6	7.2	7.2	7.8	7.6	
23	7.9	8.0	7.8	7.8	7.8	7.5	7.6	7.2	7.2	7.7	7.6	
24	7.9	7.9	7.8	9.4	13.4	7.5	7.5	7.2	7.2	7.7	7.7	
25	7.9	7.9	7.8	8.4	9.2	7.4	7.5	7.2	7.2	7.7	7.7	
26	7.9	7.9	7.9	8.1	8.25	7.5	7.4	7.2	7.2	7.7	7.7	
27	7.8	7.9	7.8	8.1	8.1	8.7	7.3	7.2	7.2	7.7	7.7	
28	7.9	7.9	7.8	8.0	8.0	7.7	7.2	7.2	7.2	7.6	7.7	
29	7.9	.....	7.8	7.8	7.8	7.5	7.3	7.2	7.2	7.6	7.7	
30	7.9	.....	7.8	13.0	7.8	7.4	7.3	7.2	7.2	7.6	7.7	
31	7.9	.....	7.8	.....	7.8	.....	7.4	7.2	.....	7.6	.....	

BARTONS SPRINGS NEAR AUSTIN, TEX.

These springs are located about 2 miles from Austin and are similar in beha and in flow to the Comal, San Felipe, and San Marcos. They respond in incre flow to the rainfall in the Edwards Plateau, but this response is always delayed

some months. About a quarter of a mile from the head of the springs the Walsh spring was formerly active and operated a small mill, but it ceased flowing several years ago. In the wet season of 1900 it revived and continued flowing till the early part of 1901, when it again ceased, continuing dry till the early part of 1903. June 6, 1903, the flow of the Walsh spring was 8.5 second-feet, but it stopped flowing in the latter part of 1903 and has since remained dry.

Discharge measurements of Bartons Springs near Austin, Tex., 1894–1905.

Date.	Hydrographer.	Discharge.
		Second-feet.
1894	C. C. Babb	17
1895	do	25
March, 1898	T. U. Taylor	20
May, 1898	do	30
August, 1900	do	69
December, 1900	do	33
June, 1902	do	19
August, 1902	do	19
June, 1903	A. A. Cother	69
June, 1904	T. U. Taylor	43
July, 1905	H. H. Fox	65

GUADALUPE RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Guadalupe River rises in the southern-central part of Texas, flows southeastward, and empties into San Antonio Bay. During the summer of 1902 its discharge was the least in its observed history, causing much loss above New Braunfels, where half a dozen power plants were forced to shut down or to run on short time. The flow at this time was so low that special efforts were made to obtain measurements at several points along its course.

GUADALUPE RIVER NEAR CUERO, TEX.

The Guadalupe, while the best water-power stream in Texas, has a drainage area above Cuero of only 5,100 square miles. Its efficiency is due almost entirely to the canal at New Braunfels. Below New Braunfels the largest tributary is San Marcos River.

This station was established by Thomas U. Taylor December 26, 1902. The original location was at the dam at Carl Buchel's power house, 3 miles north of Cuero, Tex. As it proved impossible to measure flood discharges at this point, a new station was established in July, 1903, at the bridge of the San Antonio and Aransas Pass Railroad 3 miles west of Cuero.

The channel is straight and has a width of 125 feet at low stages. The right bank is low and overflows for several hundred feet at high stages. The section is deep and the flow is sluggish. The bed is composed of soft material and may change somewhat.

Discharge measurements are made from the highway bridge, 200 feet below the railway bridge, when the gage is above 8 feet, but at lower stages the discharge is measured on the crest of the Buchel dam, 3 miles upstream, where the owners cooperate by shutting off the turbines and forcing the water over the crest of the dam. The crest of this dam is 140 feet long and 4 feet wide, and the depth of the water at the upper edge of the crest of the dam is about 1 foot. The discharge at this stage

was found to be 407 second-feet. In the usual weir formula, where $Q=c\,b\,h^{\frac{3}{2}}$, this would give a value of 2.9 for C. The initial point for soundings at the bridge is the east face of the tubular pier under the west end of the highway bridge.

A standard chain gage is attached to the bridge; length of chain, 46.20 feet. During 1905 the gage was read twice each day by Robert Miller, jr. Bench marks were established as follows: (1) The top of the tie in the third panel from the east end of the bridge; elevation, 50.00 feet. (2) The seat of the valve, about 100 feet from the pump house, on the line of pipe that leads from the pump to the water tank; elevation, 44.85 feet. (3) The top of a vertical iron rod buried in the ground 4 feet east of a mulberry tree near the left end of the bridge; elevation, 42.18 feet. Elevations refer to the datum of the gage.

A measurement made at this station August 5, 1905, by T. U. Taylor, gave the following results: Gage height, 6.3 feet; discharge, 754 second-feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 84, p 156; 99, p 337; 132, pp 45–46.
Discharge: 66, p 62; 99, p 338; 132, p 46.
Discharge, monthly: 99, p 340; 132, p 49.
Gage heights: 99, pp 338–339; 132, p 47.
Rating table: 99, p 339; 132, p 48.

Daily gage height, in feet, of Guadalupe River near Cuero, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	10.3	6.3	6.48	7.05	15.4	8.42	8.17	6.3	6.4	6.15	6.1	6.2
2	7.4	6.3	6.43	7.0	20.1	8.65	7.45	6.27	6.45	6.05	6.15	6.15
3	6.85	6.35	6.35	7.1	21.65	8.8	7.3	6.25	6.5	6.5	6.15	6.1
4	6.55	6.35	6.3	7.52	22.75	8.75	7.27	6.3	6.6	6.35	6.25	6.13
5	6.45	6.4	6.3	9.85	18.35	7.95	7.35	6.25	6.65	6.5	6.22	6.17
6	6.5	6.4	6.3	11.25	12.85	7.85	8.15	6.17	6.4	6.3	6.15	6.23
7	6.5	6.4	6.35	9.52	11.95	7.75	8.0	6.37	6.25	6.2	6.17	6.25
8	6.5	6.38	6.5	8.92	11.35	7.7	7.9	6.42	6.2	6.27	6.25	6.3
9	6.5	6.38	7.8	8.58	10.98	7.62	7.72	6.45	6.17	6.15	6.6	6.28
10	6.5	6.4	8.13	8.38	10.45	7.6	11.7	6.42	6.2	6.27	11.8	6.3
11	6.6	6.55	7.9	8.4	9.9	7.5	15.8	6.45	6.27	6.1	10.9	6.28
12	6.72	6.6	6.75	8.85	9.55	7.4	13.15	6.42	6.3	6.17	8.65	6.25
13	7.45	6.55	6.55	8.93	9.58	7.27	9.9	6.4	6.3	5.95	7.4	6.2
14	7.95	6.4	6.65	8.35	10.55	7.25	8.56	6.4	6.27	6.0	7.22	6.23
15	7.5	6.45	9.45	7.95	17.93	7.25	7.45	6.42	6.15	5.9	7.0	6.5
16	7.0	6.4	15.8	7.88	18.45	7.27	7.0	6.45	6.0	6.0	6.85	6.5
17	6.55	6.4	14.6	7.83	20.9	7.17	7.05	6.45	5.9	6.1	6.55	6.53
18	6.5	6.35	12.25	7.73	15.52	7.2	6.85	6.42	6.05	6.2	6.55	6.55
19	6.5	14.95	10.85	7.55	9.98	7.05	6.85	6.42	6.0	6.15	6.5	6.6
20	6.5	13.85	11.85	7.45	9.1	7.05	6.77	6.45	6.1	6.05	6.5	6.55
21	6.5	13.0	10.55	7.3	8.85	6.9	6.57	6.72	6.2	6.15	6.4	6.48
22	6.5	9.95	11.65	7.38	8.67	7.67	6.47	6.45	6.25	6.06	6.47	6.4
23	6.45	7.95	14.2	7.42	8.55	8.15	6.4	6.30	6.15	6.15	6.65	6.
24	6.4	7.35	10.25	23.25	8.47	8.1	6.52	6.55	6.2	6.1	6.85	6.
25	6.37	6.7	7.4	21.9	8.3	7.4	6.52	6.35	6.25	6.15	6.3	6.
26	6.3	6.6	7.5	23.25	8.37	7.75	6.52	6.15	6.25	6.05	6.2	6.
27	6.3	6.6	7.5	24.3	8.17	9.35	6.17	6.3	6.27	6.1	6.25	6.
28	6.25	6.6	7.62	23.45	8.25	12.65	6.12	6.27	6.3	6.17	6.3	6.
29	6.2	.....	7.92	24.9	8.37	14.87	6.4	6.25	6.25	6.1	6.35	6.
30	6.2	.....	7.9	24.05	8.3	11.9	6.3	6.22	6.1	6.25	6.3	6.1
31	6.25	.....	7.5	.....	8.37	.....	6.27	6.27	.....	6.15	.....	6.1

rating table for Guadalupe River near Cuero, Tex., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
6.00	580	8.00	1,280	10.00	1,980	14.00	3,400
6.10	615	8.10	1,315	10.20	2,050	14.20	3,480
6.20	650	8.20	1,350	10.40	2,120	14.40	3,560
6.30	685	8.30	1,385	10.60	2,190	14.60	3,640
6.40	720	8.40	1,420	10.80	2,260	14.80	3,720
6.50	755	8.50	1,455	11.00	2,330	15.00	3,800
6.60	790	8.60	1,490	11.20	2,400	15.50	4,000
6.70	825	8.70	1,525	11.40	2,470	16.00	4,200
6.80	860	8.80	1,560	11.60	2,540	16.50	4,400
6.90	895	8.90	1,595	11.80	2,610	17.00	4,650
7.00	930	9.00	1,630	12.00	2,680	17.50	4,900
7.10	965	9.10	1,665	12.20	2,750	18.00	5,150
7.20	1,000	9.20	1,700	12.40	2,820	18.50	5,440
7.30	1,035	9.30	1,735	12.60	2,890	19.00	5,740
7.40	1,070	9.40	1,770	12.80	2,960	20.00	6,340
7.50	1,105	9.50	1,805	13.00	3,030	21.00	7,040
7.60	1,140	9.60	1,840	13.20	3,100	22.00	7,840
7.70	1,175	9.70	1,875	13.40	3,170	23.00	8,680
7.80	1,210	9.80	1,910	13.60	3,240	24.00	9,680
7.90	1,245	9.90	1,945	13.80	3,320	25.00	10,690

above table is based on one discharge measurement made during 1905 and measurements prior t. It is well defined. The above table was used for 1903.

Estimated monthly discharge of Guadalupe River near Cuero, Tex., for 1905.

[Drainage area, 5,100 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ry	2,085	650	840	51,650	0.165	0.190
ary	3,780	685	1,094	60,780	.215	.224
	4,120	685	1,530	94,080	.300	.346
	10,580	930	3,192	189,900	.626	.698
	8,455	1,340	2,997	184,300	.588	.678
	3,748	895	1,378	82,000	.270	.301
	4,120	674	1,207	74,220	.237	.273
t	832	632	708	43,530	.139	.160
ıber	808	545	666	39,630	.131	.146
er	755	545	634	38,980	.124	.143
ıber	2,610	615	881	52,600	.173	.193
ber	790	615	684	42,060	.134	.154
The year	10,580	545	1,318	953,700	.258	3.51

COMAL RIVER AT NEW BRAUNFELS, TEX.

nal River has been fully described in Water-Supply Papers, Nos. 71 and 105. ɔurce is in the numerous big springs that issue from the foothills west of New ıfels, Tex. The joint discharge of these forms Comal River at the junction of l Springs Creek and Comal Creek. The water from the head springs naturally down Comal Springs Creek, but a gravel dam deflects part of this flow into the

Landa mill race. These waters again join about 4 miles above the highway bri north of the court-house, forming Comal River. The following table shows the re of current-meter measurements on Comal River at various times:

Discharge measurements of Comal River at New Braunfels, Tex., 1895–1905.

Date.	Hydrographer.	Discharge.	Remarks.
		Second-feet.	
1895	C. C. Babb	328	At highway bridge.
1898	T. U. Taylor	320	Do.
1899	....do	310	In park.
1900	....do	374	Do.
1901	....do	343	Do.
1902	....do	333	Do.
1903	....do	412	In park (recent rains).
1904	....do	375	In park.
1905	....do	390	Do.

SAN ANTONIO RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

San Antonio River rises about 3 miles north of the mission of San Fernando, t geographic center of the city of San Antonio. The underground source of Sa Antonio River and of the artesian wells in the vicinity is the same. The flow of t headwaters is extremely variable, as is seen from the record at San Antonio.

SAN ANTONIO RIVER AT SAN ANTONIO, TEX.

About 1885 San Antonio River at San Antonio began to fail, and by the latter pa of 1897 the flow above the city had entirely ceased. San Pedro Creek rises in Sa Pedro Park and has maintained a flow of 9 second-feet for several years. This joi San Antonio River just below the city and above the Hot Wells, where many of t measurements are made. This river has gone through the same experience as ma of the big springs. There is no doubt that the river and the artesian wells have t same underground source, but the river regained its former efficiency in 1900 short after the celebrated flood (Water Supply Paper No. 105); in two years, however, t discharge has dropped to a third of the discharge in 1900. The following tab shows the discharge measurements that have been made on this stream:

Discharge measurements of San Antonio River at San Antonio, Tex., 1895–1905.

Date.	Hydrographer.	Discharge.	Remarks.
		Second-feet.	
December, 1895	C. C. Babb	40	Upper canal.
November, 1896	....do	41	Do.
December, 1897	T. U. Taylor	0	Lower canal.
December, 1897	....do	11	Hot Wells.
March, 1898	....do	0	Lower canal.
March, 1898	....do	9	Hot Wells.
June, 1899	....do	0	Lower canal.
June, 1899	....do	10	Hot Wells.
September, 1900	....do	103	Lower canal.
September, 1900	....do	125	Hot Wells.
October, 1901	....do	41	Do.
March, 1904	....do	65	Do.
June, 1904	....do	61	Do.
September, 1905	....do	117	Do.

NUECES RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

The two main forks of Nueces River rise in Edwards County, Tex., and flows southward through the rugged mountains of the Edwards Plateau, uniting about 14 miles from Uvalde and about 6 miles above the crossing of the Southern Pacific Railroad. On their way through the mountains both branches are fed by springs and carry perpetually running water from their sources, about 12 miles south of Rock Springs to their junction at the foot of the Edwards Plateau. At about the junction of the branches the usual flow sinks into gravel beds, occasionally reappearing in big, clear pools at points where the gravel has been washed off from the solid bed-rock bottom. Four or five miles below the Southern Pacific Railroad bridge flowing water again appears, the stream along its low land course being fed by numerous springs.

LEONA RIVER AT UVALDE, TEX.

The flow of Leona River at Uvalde is variable and the river has often stopped flowing altogether near Uvalde. It was dry in 1885, but soon revived and continued flowing till 1893, when it again ceased for a time. Its history at the brickyard crossing, 1½ miles below the town on the road to Pearsall, is given in the following table:

Discharge measurements of Leona River at Uvalde, Tex., 1885–1905.

Date.	Hydrographer.	Discharge.	Remarks.
		Second-feet.	
1885			Flowed.
1893			Did not flow.
December, 1895	C. C. Babb	11	
June, 1899	T. U. Taylor		Do.
September, 1900	do	5	
March, 1904	do	22	
August, 1905	do	13	

RIO GRANDE DRAINAGE BASIN.

DESCRIPTION OF BASIN.

The source of the Rio Grande is in the snow masses of the high peaks of the continental divide in Hinsdale and Mineral counties in southwestern Colorado. The main stream flows in an easterly direction for about 75 miles, receiving numerous tributaries from the mountainous region through which it passes. At Del Norte the stream channel leaves a narrow canyon-like valley and enters the San Luis Valley. From Del Norte the general course is southeasterly for about 75 miles to a point 20 miles east of Antonito, where it crosses the Colorado-New Mexico State line. Four miles above the State line the Rio Grande enters a canyon, locally known as the Rio Grande Canyon, and continues through it to a short distance below Embudo, N. Mex., where the canyon walls retreat rapidly, especially on the west side, giving room for a border of irregular hills between the higher mesa walls and the flood plain adjacent to the river. This is the beginning of Espanola Valley, about 3 or 4 miles in width, which extends to White Rock Canyon, about 25 miles below, and through which the Rio Grande flows for 30 miles. Again the canyon walls recede, and the river enters Albuquerque Valley, which averages from 1 to 3 miles in width and continues down to about Socorro, N. Mex. Throughout its course in New Mexico the general direction of the Rio Grande is southward to El Paso; thence it is southeasterly to the Gulf of Mexico.

From the high mountains which surround this basin come a large number of smal streams, some of which unite into creeks of considerable size, while others sink an gradually disappear into the coarse soil of the valley bottom. Below Del Norte fe streams of importance enter the river with the exception of the Chama in Ne Mexico and the Pecos in Texas, as nearly all those which issue from the mountain lose their water, except in flood periods, in the sandy plains before they reach the main channel. Rio Conchos is the principal tributary from the Mexican side.

The limited data on precipitation collected by the United States Weather Bureau show the mean annual rainfall to be 25 inches in the mountainous portion of the drainage. This diminishes to 10 inches in the foothills and lower portions of the drainage.

The determination of the amount of water in the Rio Grande is of importance, both on account of its use in irrigation and from its bearing upon interstate and international distribution of water. Most of the New Mexico and Texas stations down to Eagle Pass are maintained by the United States section of the International (Water) Boundary Commission. The data are collected by W. W. Follett, consulting engineer for the Commission, and have been furnished through the courtesy of Gen. Anson Mills, Commissioner. On account of the shifting character of the river beds at the International (Water) Boundary stations, no rating tables have been prepared. The estimated monthly discharges are from daily discharges computed by Mr. Follett directly from the discharge measurements.

The five stations from Laredo down (Laredo, Roma, Brownsville, Salado near Guerrero, and San Juan at Santa Rosalie Ranch) are maintained by the Mexican section of the Commission.

RIO GRANDE NEAR DEL NORTE, COLO.

Measurements and observations were first begun in the vicinity of Del Norte in 1889 by George T. Quinby. The object of the measurements was to obtain the flow of the river before water was diverted for the agricultural region of San Luis Valley, and by a comparison of this with the figures obtained at Embudo to acquire data as to the effect of the numerous ditches taking out water between the two points. The river 25 miles above Del Norte flows out of the canyon at Wagon Wheel Gap Little water, however, is diverted until the edge of the San Luis Valley is reached the largest canal heading near the town of Del Norte. During freshets the river divides into a number of channels, making it difficult to obtain measurements near town. In order to avoid the expense of establishing a station during time of high water the first measurements—those about June 1—were made from several bridges crossing the numerous branches. The results were not wholly satisfactory, and June 25 a station was established above the branches. Later a locality about 2 miles farther up was chosen. Records are continuous for a period of sixteen years.

The station is about 2 miles west of Del Norte, above the main canal taking water from the Rio Grande, and is above all the irrigating ditches of importance.

The stream course, which is of uniform section, is straight for 100 yards both above and below the cable. The bed is composed of small bowlders and cobblestones and hitherto has been considered permanent. However, the high water of June 1905, altered the section considerably along the right side. The present section will probably be permanent for a long period of years and can change only during extreme high water. The left bank is low and of gradual slope, and is composed of cobble stones and gravel with a fringe of small cottonwood trees, and overflows at high water. The right bank is 6 feet above low water, of about 45° slope, and is composed of bowlders, cobblestones, and gravel. The extreme high water of 1905 overflowed this bank and extended over the entire bottom land to the right for a distance of half a mile. There is but one channel at all stages, and it is about 75 feet wide and of very regular section. Gage heights range from 1 to 5 feet save at extreme high water. The current is swift at low water, and exceptionally so during high water. Very accurate results may be secured at this station.

Discharge measurements were first made from a flatboat controlled by a cable across the river. They are now made by means of a cable, car, tagged wire, and stay wire. The initial point for soundings is on the right bank of river, and is indicated by a tag on the tagged wire, 22 feet from the tree to which the cable is anchored.

Several inclined gages have been used from time to time. The datum of each has been the same, and the location practically so. The lower part of the present gage is an inclined rod at the cable, and the upper part a vertical post, on the right bank. During 1905 the gage was read once each day by Richard D. Adams. The bench mark is a United States Geological Survey iron bench mark post set in the ground 25 feet south of the gage; elevation, 8.25 feet above the datum of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 14, ii, pp 110–111; 18, iv, p 246; Bull 131, pp 41–42; 140, p 170; WS 16, p 127; 28, p 120; 37, pp 277–278; 50, p 347; 66, p 65; 84, pp 194–195; 99, pp 400–401; 132, p 52.

Discharge: Ann 18, iv, p 246; Bull 131, p 91; 140, p 170; WS 16, p 127; 28, p 129; 37, p 278; 50, p 347; 66, p 65; 84, p 195; 99, p 401; 132, p 53.

Discharge, monthly: Ann 11, ii, p 98; 12, ii, pp 349, 360; 13, iii, p 94; 14, ii, p 11; 18, iv, p 247–248; 19, iv, p 383; 20, iv, pp 358, 360–364; 21 iv, p 256; 22, iv, p 347; WS 75, p 153; 84, p 196; 99, p 402; 132, p 54.

Discharge, yearly: Ann 18, iii, p 99; 20, iv, p 57.

Gage heights: Bull 131, pp 42–43; 140, p 170; WS 11, p 64; 16, p 127; 28, p 126; 37, p 278; 50, p 347; 66, p 65; 84, pp 195–196; 99, p 401; 132, p 53.

Hydrographs: Ann 12, ii, p 250; 18, iv, p 249; 19, iv, p 384; 20, iv, p 365; 21, iv, p 256; 22, iv, p 348.

Rainfall and run-off relation: Ann 20, iv, p 359.

Rating tables: Ann 18, iv, p 247; 19, iv, p 383; WS 28, p 130; 39, p 450; 52, p 519; 66, p 173; 84, p 196; 99, p 402; 132, p 54.

Discharge measurements of Rio Grande near Del Norte, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 20	R. I. Meeker	132	184	3.46	2.08	638
June 28	do	156	550	6.23	3.90	3,428
July 25	do	137	224	3.32	1.70	744
September 18	do	122	130	2.15	1.00	280

Daily gage height, in feet, of Rio Grande near Del Norte, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.5	3.8	6.25	3.2	1.95	1.2	1.9	1.1	1.0
2	1.45	3.9	6.7	3.05	1.9	1.2	1.6	1.1	1.0
3	1.5	3.2	6.9	2.9	1.9	1.2	1.5	1.1	1.0
4	1.45	2.9	7.0	2.75	1.8	1.25	1.5	1.1	1.0
5	1.45	2.8	7.05	2.55	1.85	1.25	1.4	1.1	1.0
6	1.75	2.6	6.1	2.35	1.9	1.3	1.4	1.1	1.0
7	1.7	2.7	6.2	2.3	1.9	1.25	1.35	1.1	1.0
8	1.8	2.9	6.45	2.25	1.85	1.2	1.3	1.1	1.0
9	2.5	3.4	6.4	2.2	1.75	1.2	1.25	1.1	1.0
10	2.5	3.25	6.3	2.15	1.6	1.25	1.25	1.1	1.0
11	2.1	2.8	6.0	2.1	1.7	1.2	1.2	1.1	1.0
12	2.0	2.9	5.9	2.0	1.75	1.15	1.2	1.0	1.0
13	1.95	3.1	5.7	2.0	1.6	1.1	1.2	1.0	1.0
14	2.0	3.1	5.7	1.95	1.55	1.1	1.2	1.0	1.0
15	2.1	3.7	5.65	1.95	1.45	1.1	1.2	1.0	1.0
16	2.15	4.2	5.65	1.8	1.4	1.05	1.2	1.0	1.0
17	2.15	4.9	5.2	1.85	1.35	1.0	1.2	1.0	1.0
18	2.1	5.1	5.0	1.85	1.3	1.0	1.25	1.0	1.0

Daily gage height, in feet, of Rio Grande, near Del Norte, Colo., for 1905—Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
19	2.3	5.6	4.8	1.9	1.25	1.0	1.25	1.0	1.0
20	2.1	5.7	4.7	1.9	1.25	1.0	1.2	1.0	1.0
21	2.5	5.5	4.6	1.95	1.2	1.0	1.2	1.0	1.0
22	2.15	5.8	4.2	2.0	1.15	1.0	1.2	1.0	1.0
23	2.2	6.2	4.1	1.9	1.15	1.0	1.2	1.0	1.0
24	2.1	6.0	4.0	1.8	1.2	1.0	1.2	1.0	1.0
25	2.1	6.5	3.85	1.7	1.3	1.1	1.2	.8	1.0
26	2.1	6.0	3.75	1.65	1.25	1.2	1.2	.8	1.0
27	2.4	5.9	3.45	1.6	1.25	1.15	1.2	.8	1.0
28	2.6	6.0	3.9	1.7	1.2	1.1	1.2	.9	1.0
29	3.0	4.5	3.65	1.8	1.25	1.05	1.2	1.0	1.0
30	3.25	4.9	3.5	2.15	1.3	2.27	1.15	1.0	1.0
31	.....	5.6	.....	2.0	1.25	.....	1.15	.....	1.0

Station rating table for Rio Grande near Del Norte, Colo., from April 1 to June 5, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.40	290	2.60	1,135	3.80	2,400	5.00	4,010
1.50	345	2.70	1,225	3.90	2,520	5.20	4,330
1.60	405	2.80	1,315	4.00	2,640	5.40	4,650
1.70	465	2.90	1,410	4.10	2,760	5.60	4,990
1.80	535	3.00	1,510	4.20	2,890	5.80	5,410
1.90	605	3.10	1,610	4.30	3,030	6.00	5,890
2.00	675	3.20	1,710	4.40	3,170	6.20	6,450
2.10	745	3.30	1,810	4.50	3,310	6.40	7,100
2.20	815	3.40	1,920	4.60	3,450	6.60	7,850
2.30	890	3.50	2,040	4.70	3,590	6.80	8,730
2.40	970	3.60	2,160	4.80	3,730	7.00	9,760
2.50	1,050	3.70	2,280	4.90	3,870		

The above table is applicable only for open-channel conditions. It is based on discharge measurements made previous to the high water of June, 1905. It is not well defined. Below gage height 5.5 feet it is the same as the 1904 table.

Station rating table for Rio Grande near Del Norte, Colo., from June 6 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
[a]1.00	290	2.20	1,150	3.40	2,670	4.60	4,630
1.10	330	2.30	1,260	3.50	2,820	4.70	4,820
1.20	380	2.40	1,370	3.60	2,970	4.80	5,010
1.30	440	2.50	1,480	3.70	3,120	4.90	5,200
1.40	500	2.60	1,600	3.80	3,280	5.00	5,400
1.50	560	2.70	1,720	3.90	3,440	5.20	5,810
1.60	630	2.80	1,850	4.00	3,600	5.40	6,230
1.70	700	2.90	1,980	4.10	3,760	5.60	6,670
1.80	780	3.00	2,110	4.20	3,930	5.80	7,110
1.90	860	3.10	2,250	4.30	4,100	6.00	7,550
2.00	950	3.20	2,390	4.40	4,270	6.20	8,030
2.10	1,050	3.30	2,530	4.50	4,450	6.40	8,510

[a] 0.8 = 220; 0.9 = 255.

The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during the latter part of 1905. Estimates based on this table are only approximate.

Estimated monthly discharge of Rio Grande near Del Norte, Colo., for 1905.

[Drainage area, 1,400 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
l	1,760	318	760	45,220	0.543	0.606
	7,460	1,135	3,411	209,700	2.44	2.81
	10,080	2,745	6,090	362,400	4.35	4.85
	2,390	630	1,091	67,080	.779	.898
ust	905	355	578	35,540	.413	.476
ember	1,227	290	376	22,370	.269	.300
ber	860	355	430	26,440	.307	.354
ember	330	220	296	17,610	.211	.235
ember	290	290	290	17,830	.207	.239
The period				804,200		

RIO GRANDE NEAR LOBATOS, COLO.

'his station was established June 28, 1899, by A. L. Fellows, and is 13 miles east Antonio, the nearest railroad station. It is located at the State highway bridge i point near the Colorado-New Mexico State line, about 10 miles east of Lobatos t-office and in T. 33 N., R. 11 E. The record of flow at this station is of impor-ce to the proposed Government irrigation project near Engle, N. Mex., and also n the fact that it gives the discharge of the river at the Colorado State line, so that ncludes practically all of the Colorado drainage.

'he cross section above and below the station is fairly uniform and the channel ular, being straight above and below for a considerable distance. The stream nnel is a gash cut through the solid lava to a general depth of 40 feet at the dge. The stream floor is fairly smooth, but is littered with angular fragments lava that catch and hold a loose, shallow deposit of sand during low water, which vails during the greater portion of the year. The right bank is a perpendicuar a cliff. The left bank, composed of loose fragments of lava at the water's edge, pes gradually up to the lava cliff. The channel can not overflow either bank at is section. At low stages there are usually two channels; during high water there but one. Gage heights range from 1 to 10 feet. At low water the current is very ggish; at high water very swift. The center pier obstructs the current very little ring high water.

Discharge measurements at high water are made from the downstream side of the idge, a double span steel structure with cylinder piers at the center of the stream d 300 feet in length.

The initial point for soundings is at the right end of the bridge, downstream side. t low water discharge measurements are made by wading either above or below ie bridge.

The gage is a scale on the right side of the downstream pier of the bridge. During 905 the gage was read twice each day by Román Mondragón. The bench mark is chiseled point marked "B. M." on the face of the lava bluff at the west end of the ridge; elevation, 7.42 feet above the datum of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 37, p 279; 50, pp 348–349; 66, p 65; 84, pp 192–193; 99, p 395; 132, p 55.
Discharge: WS 37, p 279; 50, p 349; 66, p 65; 84, p 193; 99, p 395; 132, p 55.
Discharge, monthly: Ann 21, iv, p 257; 22 iv, p 349; WS 75, p 153; 84, p 194; 99, p 397; 132, p 57.
Gage heights: WS 37, p 280; 50, p 349; 66, p 66; 84, p 193; 99, p 396; 132, p 56..
Hydrographs: Ann 21, iv, p 257; 22, iv, p 349.
Rating tables: WS 39, p 450; 52, p 519; 66, p 173; 84, p 193; 99, p 396; 132, p 56.

Discharge measurements of Rio Grande near Lobatos, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. feet.*	*Feet per second.*	*Feet.*	*Sec.-feet.*
April 21	R. I. Meeker	234	433	1.85	2.45	801
June 23	do	249	1,029	3.23	4.25	3,343
July 26[a]	do	207	188	.36	1.12	67
September 22	do	200	166	.28	1.00	46

[a] Made by wading.

Daily gage height, in feet, of Rio Grande near Lobatos, Colo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.6	2.75	3.00	2.0	3.6	6.25	2.9	1.25	1.2	1.0	1.3	1.9
2	2.6	2.8	3.15	2.0	4.4	6.5	2.7	1.35	1.1	1.0	1.3	1.9
3	2.6	2.8	3.2	2.0	4.65	7.05	2.55	1.7	1.15	1.0	1.3	1.9
4	2.6	2.8	3.2	2.0	4.55	7.85	2.2	1.7	1.2	1.5	1.4	1.9
5	2.6	2.8	3.2	1.95	4.25	8.25	2.1	1.7	1.2	1.5	1.4	1.9
6	2.6	2.8	3.15	1.9	3.65	8.75	2.0	1.7	1.2	1.4	1.4	1.9
7	2.6	2.8	2.1	1.9	3.45	8.85	1.85	1.6	1.2	1.5	1.4	1.9
8	2.6	2.8	2.3	1.9	3.3	9.05	1.7	1.6	1.2	1.5	1.5	1.9
9	2.6	2.8	2.5	1.95	3.4	8.85	1.6	1.65	1.2	1.4	1.5	1.9
10	2.6	2.8	2.5	2.05	3.55	8.6	1.5	1.6	1.2	1.4	1.5	2.0
11	2.6	2.8	2.5	2.1	3.7	8.45	1.4	1.6	1.2	1.3	1.6	2.0
12	2.6	2.8	2.6	2.4	3.5	8.1	1.4	1.6	1.2	1.3	1.6	2.0
13	2.6	2.8	2.6	2.4	3.4	7.6	1.4	1.6	1.1	1.2	1.6	2.05
14	2.6	2.8	2.5	2.4	3.6	6.8	1.3	1.45	1.1	1.2	1.6	2.2
15	2.6	2.8	2.4	2.3	3.6	6.7	1.3	1.4	1.1	1.2	1.6	2.2
16	2.6	2.8	2.45	2.2	4.1	6.4	1.3	1.35	1.1	1.1	1.6	2.2
17	2.6	2.8	2.45	2.25	4.7	6.3	1.3	1.3	1.0	1.1	1.6	2.2
18	2.6	2.8	2.45	2.3	5.1	6.05	1.3	1.3	1.0	1.1	1.6	2.2
19	2.6	2.8	2.4	2.4	5.9	5.8	1.3	1.3	1.0	1.1	1.6	2.2
20	2.6	2.8	2.4	2.5	6.6	5.15	1.2	1.2	1.0	1.1	1.6	2.2
21	2.6	2.8	2.4	2.5	7.0	4.9	1.2	1.2	1.0	1.1	1.6	2.2
22	2.6	2.8	2.3	2.55	7.2	4.5	1.2	1.2	1.0	1.1	1.6	2.2
23	2.6	2.8	2.2	2.6	7.7	4.0	1.2	1.2	1.0	1.1	1.6	2.2
24	2.6	2.8	2.1	2.6	7.95	3.65	1.2	1.2	1.0	1.1	1.7	2.2
25	2.6	2.8	2.0	2.6	8.0	3.55	1.2	1.2	1.0	1.1	1.7	2.2
26	2.6	2.8	2.0	2.6	8.4	3.5	1.2	1.3	1.0	1.1	1.7	2.2
27	2.6	2.8	2.0	2.6	8.15	3.5	1.2	1.2	1.0	1.2	1.7	2.2
28	2.6	2.85	2.1	2.7	8.0	3.3	1.2	1.2	1.0	1.3	1.9	2.2
29	2.6	.....	2.0	3.0	7.7	3.2	1.2	1.2	1.0	1.3	1.6	2.2
30	2.6	.....	2.0	3.3	7.1	3.0	1.2	1.2	1.0	1.3	1.85	2.2
31	2.6	.....	2.0	.....	6.7	.....	1.2	1.2	.....	1.3	.....	2.2

RIO GRANDE NEAR SAN ILDEFONSO, N. M.

tation was established February 3, 1895, by A. P. Davis, and is located at
ver and Rio Grande Railroad bridge, 9 miles below Espanola and 2 miles
Ildefonso. The station has been called by the following names: Rio Grande,
n, and Water Tank. The data at this station are of especial interest in con-
with irrigation projects, owing to the fact that Mexican settlers of this valley
considerable volume of water for their cultivated lands. The method of
on of water to land by these people is very wasteful. In recent years a num-
nportant modern irrigation systems have been planned and built in the val-
e vicinity of Albuquerque, 40 miles below.

nannel is straight for 150 feet above and 500 feet below the cable. The bed
ream at the cable is about 200 feet in width, and is composed of lava bowl-
h a shifting deposit of sand and silt, which scours out and changes during
h water and accumulates immediately on its recession. At low water ordi-
e channel finds a narrow passage through this deposit. The right bank is
composed of lava bowlders with a silt deposit. It overflows at high water.
bank is scattered with lava bowlders and is the steep side of a mountain
vered with scattered cedars. There is but one channel at all stages. Gage
ange from 1.5 to 12 feet. During high water it is difficult to secure accurate
nents from the bridge on account of the high velocity of the current and
h surface. In addition to this, the Denver and Rio Grande Railroad bridge
cross the river at a right angle to the direction of the current.

cable section the water boils considerably at low water. At high water at
ions the velocity is close to 20 feet per second.

rge measurements are made from a cable with car and tag line 150 feet above
ge, to which the gage is attached. At very high water measurements must
from the railroad bridge. The initial point for soundings at the cable is at
of the cable on the left side of the stream, where the cable is fastened to two
lar trees.

iginal gage at this station was located on the left bank, 180 feet above the
The inclined portion read from 1 to 10 feet and the vertical portion from 10
. It was found that this gage was not well located, and March 30, 1904, a
od was established on the downstream side of the north pier of the bridge,
n being 2.019 feet higher than that of the original gage. During the flood
nber, 1904, this rod was cut off from the water by the filling in of the chan-
tober 29, 1904, a standard chain gage was established on the downstream
board of the bridge, at the same datum as the new rod gage; length of chain,
t. During 1905 the gage was read twice each day by Joseph Gomez. The
ark is a United States Geological Survey tablet, set in the top of a granite
5 feet square and 2 feet high, located in a clump of cedars on the right bank
ver, about 75 feet from the west end of the north pier of the railroad bridge;
, 11.37 feet above the datum of the new gage.

nation in regard to this station is contained in the following publications of
ed States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=
pply Paper):

ion: Ann 18, iv, pp 252-253; Bull 140, pp 175-176; WS 16, p 130; 28, p 120; 37, pp 281-282; 50 pp
, p 67; 84, pp 186-187; 99, p 387, 132, pp 57-58.
ge: Ann 11, ii, p 107; Ann 18, iv, p 253; Bull 140, p 176; WS 16, p 130; 28, p 129; 37, p 282; 50, p
7; 84, pp 187-188; 99, pp 387-389; 132, p 59.
ge, monthly: Ann 18, iv, p 254; 19, iv, p 386; 20, iv, pp 358, 370; 21, iv, p 259; 22, iv, p 351; Bull
WS 75, p 154; 84, p 189; 99, p 390; 132, p 62.
ge, yearly: Ann 20, iv, p 58.
ights: Bull 140, p 176; WS 11, p 66; 16, p 130; 28, p 127; 37, p 282; 50, p 351; 66, p 68; 84, p 188;
390; 132, p 60.
aphs: Ann 18, iv, p 255; 19, iv, p 387; 21, iv, p 260; 22, iv, p 351.
and run-off relation: Ann 20, iv, p 359.
ables: Ann 18, iv, p 253; 19, iv, p 386; Bull 140, p 176; WS 28, p 130; 39, p 451; 66, p 178; 132,

Discharge measurements of Rio Grande near San Ildefonso, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis-charg
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Secon feet*
April 26	R. I. Meeker	130	709	5.82	5.45	4.
June 9	do	132	484	6.0	4.45	2.
June 30	do	132	434	5.72	4.25	2.
July 28	do	115	171	3.77	2.15	
July 29	do	115	162	3.16	2.0	
September 21	do	80	102	2.25	1.62	

Daily gage height, in feet, of Rio Grande near San Ildefonso, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	2.31	2.4	3.88	3.62	7.85	9.3	4.05	3.25	1.6	2.1	1.9	
2	2.36	2.45	4.38	3.72	8.45	9.1	3.85	2.65	1.6	1.9	1.9	
3	2.36	2.55	4.33	3.77	8.95	9.2	3.65	3.1	1.6	1.9	1.9	
4	2.26	2.8	4.48	3.72	8.75	9.5	3.5	2.8	1.6	1.8	2.0	
5	2.26	2.55	4.98	3.57	7.6	10.2	3.25	2.7	1.9	1.8	2.0	
6	2.26	2.55	4.78	3.62	7.4	10.5	3.05	2.8	2.0	1.8	2.0	
7	2.26	2.4	4.88	3.77	7.3	10.45	2.85	3.0	1.9	1.8	2.2	
8	2.36	2.45	4.93	4.22	6.65	10.7	2.65	2.9	1.8	1.8	2.0	
9	2.36	2.45	4.58	4.42	7.6	11.1	2.5	2.6	1.8	1.8	1.9	
10	2.46	2.4	4.38	4.87	7.45	10.4	2.45	2.4	1.8	1.8	1.9	
11	2.36	2.49	4.38	4.96	6.8	10.05	2.25	2.6	1.8	1.8	1.9	
12	2.46	2.49	4.43	4.96	7.05	9.65	2.2	2.5	1.7	1.8	2.2	
13	2.36	2.24	4.08	5.16	7.2	9.4	2.05	2.4	1.7	1.8	2.2	
14	2.16	2.19	4.18	5.06	7.4	9.05	2.0	2.3	1.7	1.8	2.2	
15	2.06	2.24	4.73	4.91	8.2	8.45	2.0	2.2	1.7	1.7	2.2	
16	2.31	2.54	4.63	4.86	8.8	8.15	1.9	2.0	1.7	1.7	2.2	
17	2.31	2.49	4.58	4.96	9.65	7.7	1.85	1.9	1.7	1.7	2.2	
18	2.46	2.44	4.48	5.06	10.5	7.5	1.8	1.8	1.6	1.7	2.2	
19	2.36	2.44	4.08	5.36	11.1	7.15	1.8	1.6	1.6	1.7	2.2	
20	2.36	2.49	4.03	5.46	11.6	6.85	1.85	1.5	1.6	1.7	2.2	
21	2.35	2.54	4.17	5.31	11.5	6.45	2.1	1.3	1.6	1.7	2.2	
22	2.4	2.54	4.17	6.01	11.45	6.3	2.2	1.0	1.6	1.7	3.0	
23	2.35	2.59	4.02	6.01	11.5	5.95	2.2	.6	1.6	1.9	3.0	
24	2.35	2.79	3.92	6.31	11.75	5.7	2.1	.6	1.6	1.9	2.5	
25	2.4	3.04	3.82	5.36	11.8	5.45	2.2	2.0	1.8	1.9	2.4	
26	2.35	3.49	3.87	5.41	11.5	5.15	2.2	1.8	2.0	1.9	2.4	
27	2.3	3.61	4.12	5.61	11.25	4.9	2.05	1.8	2.1	1.9	2.3	
28	2.3	3.69	4.17	6.26	10.9	4.75	2.2	1.7	1.9	1.9	2.3	
29	2.35	.....	3.77	6.81	10.6	4.45	2.1	1.6	1.8	1.9	2.4	
30	2.4	.....	3.67	7.31	10.5	4.25	2.75	1.6	1.8	1.9	2.3	
31	2.4	.....	3.57	.....	9.4	.....	3.45	1.6	.....	1.9	.....	

Station rating table for Rio Grande near San Ildefonso, N. Mex., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.60	40	2.10	560	3.60	1,790	6.20	5,480
0.70	50	2.20	620	3.70	1,900	6.40	5,850
0.80	70	2.30	680	3.80	2,010	6.60	6,230
0.90	90	2.40	750	3.90	2,120	6.80	6,630
1.00	120	2.50	820	4.00	2,230	7.00	7,030
1.10	150	2.60	890	4.20	2,470	7.50	8,100
1.20	180	2.70	960	4.40	2,710	8.00	9,230
1.30	210	2.80	1,040	4.60	2,960	8.50	10,440
1.40	250	2.90	1,120	4.80	3,220	9.00	11,690
1.50	290	3.00	1,200	5.00	3,500	9.50	12,990
1.60	330	3.10	1,290	5.20	3,800	10.00	14,310
1.70	370	3.20	1,380	5.40	4,110	10.50	15,670
1.80	410	3.30	1,480	5.60	4,430	11.00	17,100
1.90	460	3.40	1,580	5.80	4,770	11.50	18,600
2.00	510	3.50	1,680	6.00	5,120		

The above table is based on six discharge measurements made during 1905 and three high-water measurements made in 1903. It is not well defined.

Estimated monthly discharge of Rio Grande near San Ildefonso, N. Mex., for 1905.

[Drainage area, 14,050 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	792	540	707	43,470	0.050	0.058
February	1,889	614	929	51,590	.066	.069
March	3,472	1,757	2,571	158,100	.183	.211
April	7,682	1,757	3,679	218,900	.262	.292
May	19,500	6,330	12,770	785,200	.909	1.05
June	17,400	2,530	9,625	572,700	.685	.764
July	2,290	410	874	53,740	.062	.072
August	1,430	40	629	38,680	.045	.052
September	560	330	389	23,150	.028	.031
October	560	370	422	25,950	.030	.035
November	1,200	460	638	37,960	.045	.050
December	680	460	617	37,940	.044	.051
The year	19,500	40	2,821	2,047,000	.201	2.74

RIO GRANDE NEAR SAN MARCIAL, N. MEX.

August 8, 1889, a station was established near San Marcial and a measurement was made which gave a discharge of 19 second-feet. Soon after this date, however, the river gage was destroyed and the locality was abandoned until January 29, 1895, when the station was reestablished by A. P. Davis at the bridge of the Atchison, Topeka and Santa Fe Railway, 1 mile south of San Marcial, N. Mex.

The channel is sandy and shifting. A number of bridge piers interfere with the current to a certain extent, but not with the observed gage heights. They sometimes affect the

discharge measurements. There is no overflow channel beyond the bridge. The section gives gravity flow.

Discharge measurements are made from the downstream side of the bridge. The initial point for soundings is the face of the bridge abutment on the left bank of the stream.

The inclined gage established January 29, 1895, was carried away in 1896 and a wire gage was put in its place. This gage has since been abandoned, and the gage heights are now measured with a graduated rod from the deck of the bridge, but using the old gage datum. The top of the ties on the bridge is at elevation 19.00 feet on the gage. The range between high and low water is about 8 feet. Bench marks were established as follows: (1) The top of the capstone on which the bridge truss rests; elevation, 15.00 feet. (2) The top of the extension of the pier to which the old vertical gage was fastened; elevation, 13.00 feet. Elevations refer to the datum of the gage.

The observations during 1905 have been made under the direction of the United States section of the International (Water) Boundary Commission. The various hydrographers at this station have also acted as gage readers.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Cross section: Ann 18, iv, p 257.
Description: Ann 18, iv, pp 254-255; Bull 131, p 46; 140, p 177; WS 16, p 131; 28, p 120; 37, p 282; 50, pp 351-352; 66, p 68; 84, pp 183-184; 99, pp 382-383; 132, pp 62-63.
Discharge: Ann 11, ii, p 107; 18, iv, p 256; Bull 131, p 46; 140, p 177; WS 16, p 131; 28, p 129; 37, p 283; 50, p 352; 66, pp 68-69; 84, pp 184-185; 99, pp 383-385; 132, pp 63-64, 127.
Discharge, mean daily: WS 132, p 66.
Discharge, monthly: Ann 18, iv, p 257; 19, iv, p 388; 20, iv, pp 358, 371; 21, iv, p 261; 22, iv, 352; WS 75, p 155; 84, p 186; 99, p 386; 132, p 67.
Discharge, yearly: Ann 20, iv, p 58.
Gage heights: Bull 140, p 178; WS 11, p 66; 16, p 131; 28, p 128; 37, p 283; 50, p 352; 66, p 69; 84, p 185; 99, p 386; 132, p 65.
Hydrographs: Ann 19, iv, p 389; 20, iv, p 371; 21, iv, p 261; 22, iv, p 352.
Rainfall and run-off relation: Ann 20, iv, p 359.
Rating tables: Ann 18, iv, p 256; 19, iv, p 387-388; WS 28, p 131.

Discharge measurements of Rio Grande near San Marcial, N. Mex., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second*	*Feet.*	*Second-feet.*
January 3	L. W. Broyles	259	2.04	7.8	528
January 6	do	325	2.10	8.0	684
January 9	do	238	2.39	7.9	568
January 12	do	207	3.10	8.1	922
January 15	do	203	3.38	8.0	686
January 18	do	184	2.95	7.9	543
January 21	do	193	3.37	8.0	651
January 24	do	176	3.05	7.9	536
January 27	do	211	2.80	7.9	590
January 31	do	197	3.43	8.0	675
February 3	do	237	3.50	7.9	830
February 6[a]	do	184	3.59	7.9	661
February 9	do	309	3.30	8.1	1,019
February 12	do	258	2.98	8.0	768
February 15	do	237	2.83	8.1	671
February 18	do	284	2.93	8.0	831
February 21	do	243	3.28	8.1	796
February 24	do	246	3.01	8.0	740
February 28	do	660	3.47	8.5	2,287
March 3	do	720	4.01	8.6	2,886

[a] Ice in river.

easurements of Rio Grande near San Marcial, N. Mex., in 1905—Continued.

Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
L. W. Broyles	929	5.46	9.0	5,073
do	979	4.70	8.9	4,598
do	697	6.88	9.2	4,795
do	664	5.04	8.6	3,344
do	554	5.64	8.4	3,125
do	833	4.57	9.3	3,806
do	717	3.79	8.8	2,721
do	731	4.07	9.0	2,972
do	630	3.49	8.6	2,198
do	652	4.18	8.7	2,724
do	852	3.91	9.2	3,331
do	589	3.07	8.5	1,808
do	584	3.34	8.7	1,950
do	972	4.02	9.6	3,911
do	1,026	3.90	9.6	4,006
do	954	4.03	9.1	3,840
do	997	4.30	9.4	4,288
do	1,769	5.50	10.2	9,726
do	1,571	4.68	10.2	7,356
do	1,558	5.03	10.7	7,829
do	2,318	5.03	11.4	11,650
do	1,833	5.98	10.7	10,955
do	1,868	5.92	10.0	11,058
do	1,597	5.44	10.3	8,694
do	1,656	6.37	10.2	10,543
do	1,684	6.15	10.3	10,361
do	2,063	6.18	10.9	12,758
do	2,474	6.51	11.6	16,097
do	2,621	6.72	12.5	17,607
do	4,093	6.55	12.8	26 810
do	4,294	5.62	12.7	24,142
do	4,642	5.51	13.2	25,577
do	2,847	7.12	13.1	20,264
do	3,154	6.33	11.9	19,973
do	3,208	5.09	11.6	16,780
do	2,821	5.34	12.7	15,071
do	3,341	5.74	12.5	19,162
do	2,660	4.40	10.9	11,702
do	2,744	5.00	9.7	13,726
do	1,976	4.55	9.4	9,000
do	1,340	4.74	8.7	6,345
do	983	4.34	8.4	4,271
do	882	3.97	8.2	3,505
do	722	3.66	8.0	2,641
do	527	3.03	7.6	1,598
do	359	3.18	7.4	1,143
do	385	2.04	7.2	784
do	209	2.23	6.8	466
do	176	1.56	6.6	274
do	141	1.33	6.4	188
do	117	1.51	6.2	177
do	108	1.46	6.3	158
do	97	0.84	6.3	81
do	35	1.91	5.9	67

Discharge measurements of Rio Grande near San Marcial, N. Mex., in 1905—Conti

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	I ch
		Square feet.	*Feet per second.*	*Feet.*	*Sec fe*
August 3	L. W. Broyles	334	2.56	7.4	
August 6	do	339	1.78	7.1	
August 9	do	334	1.91	7.3	
August 12	do	298	2.29	6.9	
August 15	do	207	2.15	6.5	
August 18	do	131	1.10	6.3	
August 21	do	80	1.20	6.0	
August 24	do	13	0.46	5.6	
September 7	do	117	2.74	7.3	
September 9	do	79	1.90	6.7	
September 11	do	61	1.52	6.5	
September 25	do	47	1.11	5.6	
September 27	do	144	1.60	6.7	
September 29	do	90	1.81	6.3	
October 5	D. H. West	92	1.71	5.9	
October 6	do	97	1.56	5.9	
October 8	do	74	1.69	5.8	
October 11	do	63	1.32	5.6	
October 14	do	70	1.39	5.7	
October 17	do	65	1.23	5.7	
October 20	do	68	1.24	5.7	
October 23	do	73	1.30	5.8	
October 26	do	84	1.50	5.9	
October 28	do	88	1.67	5.9	
October 31	do	101	1.71	6.2	
November 3	do	94	1.86	6.2	
November 9	do	255	2.90	7.1	
November 11	do	204	3.27	7.05	
November 14	do	232	2.51	7.0	
November 17	do	210	2.28	6.8	
November 20	do	196	2.45	6.8	
November 23	do	241	2.52	7.0	
November 25	do	548	2.96	7.6	
November 28	do	201	2.68	6.9	
November 30	do	446	3.42	7.7	
December 3	Geo. W. King	317	2.57	7.3	
December 6	do	249	2.14	7.2	
December 9	do	228	2.60	7.2	
December 12	do	220	2.74	7.2	
December 15	do	347	2.22	7.5	
December 18	do	275	2.26	7.3	
December 21	do	315	2.05	7.4	
December 24	do	127	1.81	6.9	
December 27	do	93	1.90	6.5	
December 30	do	105	1.77	6.5	

Daily gage height, in feet, of Rio Grande near San Marcial, N. Mex., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	7.7	8.0	8.8	8.85	10.35	12.6	8.05	6.75	.....	6.4	6.1	7.7
.....	7.7	7.9	8.75	8.9	10.5	12.2	7.75	6.9	.....	6.15	6.1	7.4
.....	7.8	7.9	8.65	9.1	10.65	11.95	7.6	7.15	.....	6.1	6.2	7.3
.....	7.95	8.0	9.1	8.85	11.25	11.5	7.5	7.15	.....	6.0	6.35	7.2
.....	8.0	8.0	9.05	8.65	11.5	11.45	7.45	7.0	.....	5.95	6.45	7.2
.....	7.95	8.05	•8.95	8.5	11.45	11.55	7.4	7.15	6.8	5.95	6.5	7.15
.....	7.8	8.65	8.9	8.4	10.7	11.9	7.35	7.0	7.3	5.9	6.65	7.25
.....	7.9	8.45	8.95	8.5	10.15	12.3	7.3	7.05	6.7	5.8	6.9	7.25
.....	7.9	8.15	9.25	8.75	9.9	12.7	7.2	7.4	6.7	5.7	7.05	7.15
.....	8.05	7.95	9.25	9.05	10.1	12.55	7.05	7.2	6.85	5.6	6.75	7.3
.....	8.15	7.9	8.85	9.45	10.3	12.5	6.9	7.0	6.5	5.6	7.05	7.3
.....	8.1	8.0	8.6	9.65	10.45	12.35	6.8	6.95	6.1	5.7	7.0	7.2
.....	8.1	7.8	8.8	9.95	10.1	11.9	6.8	6.8	5.4	5.7	6.9	7.3
.....	8.05	7.65	8.75	9.65	10.3	11.3	6.7	6.75	5.3	5.7	6.95	7.3
.....	8.0	8.0	8.6	9.55	10.25	11.0	6.6	6.55	.....	5.75	6.9	7.45
.....	8.0	7.9	8.65	9.7	10.65	10.4	6.6	6.45	.....	5.7	6.8	7.5
.....	8.05	8.0	8.95	9.2	10.85	10.05	6.5	6.4	.....	5.7	6.8	7.4
.....	7.9	8.0	9.2	9.1	11.1	9.7	6.4	6.3	.....	5.7	6.8	7.3
.....	7.9	8.1	9.15	9.15	11.45	9.3	6.3	6.2	.....	5.7	6.8	7.4
.....	7.8	8.25	9.15	9.3	11.85	9.4	6.2	6.1	.....	5.7	6.8	7.4
.....	8.0	8.15	8.8	9.4	12.35	9.35	6.2	6.0	.....	5.7	6.8	7.4
.....	8.0	8.05	8.7	9.5	12.75	9.0	6.1	5.85	.....	5.8	6.9	7.25
.....	7.95	7.95	8.75	9.7	12.95	8.8	6.2	5.7	.....	5.8	7.0	7.2
.....	7.9	8.0	9.0	10.3	13.05	8.7	6.35	5.6	.....	5.75	8.65	6.9
.....	7.9	8.8	8.9	11.0	12.65	8.55	6.2	.....	5.6	5.8	7.75	6.5
.....	7.9	8.6	8.75	10.45	13.15	8.35	6.4	.....	7.55	5.9	7.6	6.4
.....	7.9	8.45	8.6	10.15	13.2	8.2	6.25	.....	7.3	5.9	7.3	6.5
.....	7.9	8.55	8.6	9.95	13.2	8.2	6.1	.....	6.2	5.95	6.95	6.5
.....	7.95	.....	8.7	10.0	13.15	8.1	6.1	.....	6.7	6.05	6.95	6.5
.....	8.0	.....	8.8	10.2	13.0	8.0	6.0	.....	6.55	6.05	7.7	6.5
.....	8.0	.....	8.7	.....	13.0	.....	5.9	.....	.....	6.15	.....	6.5

:.—No flow August 25 to September 5 and September 15–24

Daily discharge in second-feet of Rio Grande near San Marcial, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	370	730	4,090	2,910	7,500	19,360	2,770	405	0	180	160	1,530
2	400	780	3,790	2,970	7,630	19,660	1,990	495	0	170	160	990
3	a 530	a 830	a3,190	a 3,210	a 7,790	a19,970	a1,600	a 645	0	165	a 175	a 815
4	650	930	5,620	2,360	10,830	17,110	1,375	645	0	160	220	690
5	685	930	a5,350	2,120	a12,200	16,350	1,260	570	0	a 160	260	610
6	a 625	a 970	4,840	a 1,810	12,120	a16,480	a1,145	a 645	180	a 155	265	a 595
7	470	2,700	4,600	1,730	a10,950	15,810	1,045	570	a 320	150	375	585
8	570	2,130	a4,630	1,810	10,010	15,440	965	580	150	a 125	550	605
9	a 570	a1,180	4,830	a 2,050	a10,560	a15,070	a 785	a 700	a 150	105	a 600	a 565
10	820	720	a4,920	2,720	9,630	15,930	665	670	195	85	450	655
11	1,005	670	3,950	3,600	a 8,690	17,390	545	645	a 95	a 85	a 665	655
12	a 920	a 770	a3,340	a 4,070	10,620	a18,460	a 465	a 710	50	95	580	a 605
13	920	500	3,560	4,690	a10,040	16,370	465	620	10	95	510	660
14	800	290	3,500	4,090	10,700	13,570	370	590	5	a 95	a 550	660
15	a 690	a 570	a3,340	a 3,900	a10,160	a12,170	a 275	a 470	0	95	530	a 740
16	600	560	3,370	4,200	11,760	11,880	275	350	0	85	480	770
17	760	740	3,540	3,900	a12,560	12,800	230	255	0	a 80	a 480	695
18	a 545	a 830	a3,600	a 3,840	13,710	a13,730	a 190	a 145	0	80	480	a 630
19	545	880	3,490	3,910	a15,380	10,950	185	125	0	85	480	645
20	440	980	3,490	4,140	16,550	10,170	180	110	0	a 85	a 480	645
21	a 650	a 840	a2,720	a 4,290	a17,350	a 8,810	a 175	a 95	0	85	480	a 645
22	650	770	2,600	4,840	23,400	7,480	170	60	0	a 95	540	515
23	590	710	2,660	5,950	a28,600	6,720	165	25	0	95	a 605	445
24	a 535	a 740	a2,970	a10,280	29,070	a 6,340	a 160	a 5	0	90	3,720	a 230
25	550	3,220	2,780	14,160	a23,540	5,300	120	0	a 50	105	a1,920	175
26	570	2,600	2,490	9,210	28,000	a 4,080	120	0	470	a 125	1,620	180
27	a 590	2,130	a2,200	7,210	27,100	3,500	a 80	0	a 400	135	1,160	a 175
28	590	a2,440	2,280	6,610	a25,580	a 3,500	70	0	145	a 150	a 620	180
29	630	.....	2,560	6,760	23,600	3,070	70	0	a 230	160	620	195
30	675	.....	2,840	a 7,300	20,430	a 2,640	65	0	210	160	a1,530	a 185
31	a 675	.....	a2,720	.....	a19,060	.....	a 65	0	.....	a 170	.....	185

a Meter measurements.

Estimated monthly discharge of Rio Grande near San Marcial, N. Mex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	1,005	370	636	39,11
February	3,220	290	1,150	63,8
March	5,620	2,200	3,544	217,9
April	14,160	1,730	4,695	279,3
May	29,070	7,500	15,649	962,2
June	19,970	2,640	12,004	714,2
July	2,770	65	582	35,7
August	710	0	327	20,0
September	470	0	89	5,2
October	180	80	120	7,3
November	3,720	160	713	42,3
December	1,530	160	559	34,3
The year	29,070	0	3,339	2,422,0

RIO GRANDE NEAR EL PASO, TEX.

This station was located at the pumping house of the smelter company, 3 miles north of Paso, Tex. The bed of the stream here is composed of mud, constantly shifting and anging. May 1, 1897, the station was placed under the charge of W. W. Follett, conting engineer, International (Water) Boundary Commission, and by him removed 1 mile ther up the river to Courchesne's limekiln.

The left bank of the river is formed by the loose rock fill of the Atchison, Topeka and Santa Railway embankment and will not overflow. The right bank is not so good, being made ound and subject to overflow. The bottom of the river here has also proved unstable, scour- g on a rise and filling on a fall of the river. During the spring flood of 1905 the right ank began to erode and receded about 60 or 80 feet. This has left a bad low-water section. here is a large shifting bar about mid stream. It is still the best site for a station in the cinity of El Paso, however, as the entire bed is constantly shifting for many miles above d below. On account of the shifting bed the only accurate method of estimating the ily discharge is by taking a large number of measurements. In extreme high water the ottom overflows slightly for a width of 200 feet beyond the right cable support.

Discharge measurements are made by means of a cable of 410 feet span, car, tagged wire, nd guy wire. The initial point for soundings is the cable support on the left bank.

River heights were measured at the masonry pump-foundation pier. The pier was torn own in October, 1902, so an inclined wooden gage was established some 60 feet upstream. his is a timber bolted to steel bars set with cement in holes drilled in solid rock. The nge between high and low water is about 11 feet. The bench mark is a one-half inch iron olt set in solid rock at the head of the gage; elevation, 13.00 feet above the datum of the age.

The observations at this station during 1905 have been made under the direction of the Jnited States section of the International (Water) Boundary Commission. The hydrog- apher is W. L. Follett and the gage reader is Valmore Courchesne.

Information in regard to this station is contained in the following publications of the Jnited States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Cross section: Ann 18, iv, p 258.

Description: Ann 14, iv, p 114; 18, iv, pp 257-259; Bull 131, p 46; 140, p 178; WS 16, p 132; 28, p 120; 37, pp 283-284; 50, p 352; 66, p 70; 84, p 181; 99, pp 378-379; 132, pp 67-68.

Discharge: Ann 18, iv, p 259; Bull 140, p 179; WS 16, pp 132-133; 28, p 120; 37, p 284; 50, p 353; 66, p 70; 84, pp 181-182; 99, pp 379-381; 132, pp 68-69.

Discharge, mean daily: WS 132, p 70.

Discharge, monthly: Ann 11, ii, p 99; 12, ii, pp 350, 360; 13, iii, p 94; 14, iv, pp 114-115; 19, iv, p 390; 20 iv, pp 358, 372; 21, iv, p 262; 22, iv, p 353; WS 75, p 155; 84, p 183; 99, p 382; 132, p 71.

Discharge, yearly: Ann 11, ii, p 54; 13, iii, p 99; 20, iv, p 58.

Gage heights: Bull 131, p 47; 140, p 179; WS 11, p 67; 16, p 133; 28, p 128; 37, p 284; 50, p 353; 66, p 70; 84, p 182; 99, pp 381-382; 132, p 69.

Hydrographs: Ann 12, ii, p 280; 14, ii, p 114; 19, iv, p 390; 21, iv, p 263; 22, iv, p 353; WS 75, p 156.

Rating tables: Ann 19, iv, p 389; Bull 131, p 47.

Sediment observations: Ann 11, ii, p 57.

Discharge measurements of Rio Grande near El Paso, Tex., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Dis charg
		Square feet.	*Feet per second.*	*Feet.*	*Secon fee*
January 3	Valmore Courchesne	224	1.64	6.4	
January 8	do	228	1.68	6.3	
January 11	do	316	2.42	7.2	
January 14	do	395	2.57	7.6	1.
January 18	do	314	2.45	7.2	
January 21	do	267	2.34	7.0	
January 24	do	225	2.05	6.4	
January 28	do	226	2.38	6.7	
January 31	do	210	2.18	6.5	
February 3	do	222	2.20	6.6	
February 7	do	223	2.20	6.6	
February 10	do	268	2.49	7.0	
February 12	do	404	2.52	7.6	1
February 15	do	274	2.14	6.8	
February 19	do	293	2.46	7.2	
February 21	do	464	2.71	8.0	1
February 25	do	360	2.45	7.4	
February 28	do	438	3.11	8.15	1
March 3	do	588	4.36	9.2	2
March 8	do	861	4.21	9.9	3
March 12	do	1,126	4.36	10.8	4
March 15	do	670	5.14	9.8	3
March 18	do	582	4.78	9.8	3
March 21	do	801	3.96	10.3	
March 24	do	690	3.34	9.7	
March 31	do	629	2.69	9.3	
April 3	do	808	2.55	9.9	
April 6	do	737	3.01	9.9	
April 9	do	516	2.76	8.9	
April 14	do	798	3.67	10.35	
April 17	do	804	4.23	10.6	
April 20	do	757	3.92	10.3	
April 24	do	820	4.39	10.9	
April 29	do	1,295	5.42	12.75	
May 2	do	912	5.67	11.4	
May 6	do	1,253	5.18	12.5	
May 9	do	1,633	5.97	13.5	
May 12	do	1,063	5.50	11.5	
May 16	do	1,385	4.40	12.0	
May 20	do	1,201	5.05	12.3	
May 23	do	1,715	5.67	13.9	
May 25	do	1,870	5.27	14.6	
May 28[a]	do	3,722	4.51	15.6	
May 30[a]	do	4,094	4.62	15.9	
June 2[a]	do	3,806	5.44	16.1	
June 6	do	2,930	5.46	14.35	
June 9	do	2,738	6.43	14.8	
June 12	do	3,549	6.67	14.9	
June 15	do	3,607	6.54	14.9	
June 18	do	2,517	6.73	13.85	
June 21	do	1,162	6.29	12.4	
June 25	do	1,151	4.97	11.1	
June 27	do	1,080	4.23	10.5	

[a] Includes overflow sections.

ge measurements of Rio Grande near El Paso, Tex., in 1905—Continued.

Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
Valmore Courchesne	1,031	3.30	9.5	3,398
do	937	2.55	8.9	2,388
do	669	2.07	8.1	1,383
do	502	2.04	7.6	1,024
do	363	1.91	7.4	694
do	299	1.58	7.1	471
do	239	1.74	6.8	415
do	216	1.79	6.7	386
do	263	1.65	6.8	435
do	223	1.84	6.8	410
do	174	1.50	6.5	261
do	149	1.33	6.3	198
do	369	1.97	7.3	726
do	307	1.86	7.0	572
W. L. Follett	481	2.04	7.7	979
W. W. Follett	270	1.81	6.8	488
do	197	1.52	6.4	300
do	156	1.28	6.2	199
do	123	1.19	6.0	146
do	97	1.02	5.8	99
W. L. Follett	75	0.75	5.6	56
do	52	0.67	5.4	35
do	34	0.91	5.4	31
do	35	0.91	5.4	32
do	33	0.82	5.3	27
do	113	1.24	6.2	140
do	88	1.27	5.9	112
do	68	1.13	5.7	77
do	32	1.47	5.5	47
do	20	0.95	5.25	19
do	16	1.00	5.2	16
do	92	1.66	6.2	153
do	113	1.76	6.45	199
do	85	1.53	6.0	130
do	72	1.25	5.8	90
do	45	1.31	5.6	59
do	38	1.16	5.5	44
do	28	0.86	5.4	24
do	23	1.00	5.3	23
do	27	1.15	5.35	31
do	30	1.30	5.4	39
do	34	1.15	5.4	39
do	35	1.03	5.5	36
do	58	1.26	5.65	73
do	83	1.37	5.85	114
do	148	1.36	6.2	202
do	216	1.83	6.75	395
do	217	1.58	6.7	342
do	208	1.49	6.6	309
do	222	1.51	6.6	335
do	569	2.51	8.05	1,426
do	772	2.06	8.35	1,588
do	659	2.05	8.2	1,349

Discharge measurements of Rio Grande near El Paso, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
December 6	W. L. Follett	426	1.62	7.25	691
December 9	do	374	1.45	6.9	541
December 12	do	375	1.59	7.0	595
December 15	do	352	1.63	7.0	572
December 18	do	335	1.73	7.0	581
December 21	do	334	1.65	6.95	550
December 24	do	304	1.49	6.9	454
December 27	do	300	1.62	6.9	486
December 30	do	201	1.38	6.3	278

Daily gage height, in feet, of Rio Grande near El Paso, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	6.4	6.5	9.05	9.6	11.55	16.05	9.35	6.5	5.45	6.65	5.5	7.75
2	6.4	6.55	9.2	9.9	11.4	16.1	9.15	6.4	5.4	6.4	5.6	7.65
3	6.4	6.55	9.15	9.85	11.6	15.95	8.9	6.35	5.4	6.25	5.6	8.2
4	6.3	6.5	9.4	9.65	11.7	15.4	8.7	6.3	5.4	6.1	5.65	7.9
5	6.25	6.5	9.7	9.7	12.15	14.95	8.6	6.3	5.4	6.0	5.7	7.55
6	6.25	6.5	9.6	9.9	12.45	14.25	8.45	6.4	5.4	6.0	5.7	7.25
7	6.3	6.6	9.95	9.6	12.9	13.85	8.2	7.3	5.4	5.9	5.85	7.1
8	6.3	6.6	9.95	9.25	13.3	13.85	8.05	7.15	5.4	5.8	6.0	7.0
9	6.3	6.7	10.1	8.9	13.5	14.75	7.85	6.95	5.4	5.8	6.05	6.9
10	6.85	7.25	10.8	8.85	12.9	14.5	7.65	7.05	5.3	5.65	6.2	6.8
11	7.2	8.05	10.8	9.0	11.75	14.5	7.6	7.0	5.3	5.6	6.3	6.85
12	7.2	7.65	10.8	9.2	11.5	14.9	7.6	7.65	5.9	5.6	6.35	7.0
13	8.05	7.3	10.4	9.75	11.65	14.75	7.45	7.4	5.95	5.55	6.65	7.05
14	7.7	7.0	10.05	10.35	12.05	14.9	7.3	6.95	5.9	5.5	6.7	7.05
15	7.5	6.8	9.9	10.8	12.2	14.85	7.2	6.8	5.9	5.45	6.7	7.0
16	7.4	6.8	9.9	10.85	12.05	14.85	7.1	6.65	5.8	5.4	6.7	7.0
17	7.3	6.7	9.9	10.6	11.9	14.35	7.0	6.5	5.7	5.4	6.7	7.1
18	7.2	6.45	9.7	10.6	12.05	13.9	6.9	6.4	5.6	5.4	6.7	7.0
19	7.0	7.2	9.7	10.55	12.2	13.35	6.8	6.3	5.55	5.4	6.6	7.15
20	7.0	8.05	10.1	10.35	12.35	12.8	6.75	6.2	5.5	5.3	6.6	7.05
21	6.95	7.95	10.3	10.3	12.7	12.4	6.7	6.2	5.4	5.3	6.6	7.0
22	6.7	7.6	10.3	10.3	13.3	12.0	6.7	6.05	5.35	5.3	6.55	6.95
23	6.6	7.75	10.05	10.7	13.9	11.85	6.9	6.0	5.25	5.3	6.55	6.85
24	6.4	7.65	9.75	11.0	14.3	11.4	6.95	6.0	5.2	5.4	6.6	6.9
25	6.4	7.45	9.55	11.35	14.65	11.1	6.8	5.95	5.2	5.4	6.8	6.95
26	6.55	7.5	9.55	12.15	15.0	10.7	6.65	5.8	5.2	5.4	6.9	6.9
27	6.75	7.65	9.75	13.0	15.3	10.5	6.6	5.8	5.2	5.4	7.8	6.8
28	6.7	8.05	9.6	13.1	15.55	10.15	6.7	5.75	5.8	5.4	8.25	6.55
29	6.6	.....	9.45	12.9	15.75	9.9	6.8	5.6	6.25	5.4	8.75	6.3
30	6.5	.....	9.3	12.15	15.9	9.6	6.55	5.55	6.05	5.45	8.3	6.3
31	6.5	.....	9.3	.....	15.9	.....	6.5	5.5	.....	5.5	.....	6.2

Daily discharge, in second-feet, of Rio Grande near El Paso, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	405	460	2,390	1,890	5,380	20,270	3,150	260	40	230	a35	1,035
.....	385	475	2,560	2,060	a5,170	a20,720	2,810	230	a35	a195	60	965
.....	a365	a475	a2,500	a2,030	5,410	20,320	a2,390	a215	35	170	60	a1,350
.....	340	460	2,860	1,960	5,530	18,840	2,130	200	30	145	a75	1,140
.....	330	460	3,320	2,040	6,070	17,620	2,000	200	a30	a130	85	895
.....	340	460	3,170	a2,220	a6,430	a15,630	1,820	250	30	130	85	a690
.....	370	a490	3,700	1,980	7,800	14,190	a1,510	a725	30	110	a115	625
.....	a385	490	a3,700	1,700	9,100	14,190	1,350	645	a35	a90	150	585
.....	385	550	3,910	a1,420	a9,760	a17,410	1,200	545	30	90	165	a540
.....	620	a820	4,910	1,370	8,590	18,300	a1,060	a595	30	65	a200	500
.....	a765	1,290	4,910	1,530	6,350	20,190	970	570	a25	a60	235	525
.....	765	a1,050	a4,910	1,740	a5,850	a23,680	910	a950	a110	60	255	a595
.....	1,290	860	4,330	2,310	5,960	23,050	a735	810	115	50	360	620
.....	a1,075	695	3,810	a2,930	6,570	23,620	620	565	a110	a45	380	620
.....	950	a585	a3,500	3,760	6,680	a23,270	545	a490	110	35	a380	a570
.....	890	585	3,370	3,850	a6,200	23,270	a470	415	90	25	370	575
.....	830	550	3,150	a3,400	5,740	20,100	450	345	a75	a25	355	630
.....	a770	460	a2,700	3,400	5,890	a17,250	430	a300	60	25	a340	a580
.....	630	a720	2,700	3,330	6,020	13,620	a415	250	50	25	310	655
.....	625	1,290	3,020	a3,040	a6,180	9,970	400	200	a45	a25	310	605
.....	a605	a1,220	a3,170	2,970	6,980	a7,310	385	a200	35	25	a310	a580
.....	540	1,000	3,170	2,970	8,360	6,820	a385	160	30	25	305	530
.....	515	1,100	2,810	3,380	a9,720	6,640	485	145	a20	a30	315	455
.....	a460	1,035	a2,380	a3,780	9,800	6,090	510	a145	15	40	a335	a455
.....	460	a910	2,080	4,430	a10,210	a5,720	a435	130	15	40	485	480
.....	500	975	2,080	5,900	12,640	4,950	385	100	a15	a40	560	475
.....	555	1,070	2,380	7,500	14,720	a4,560	360	a100	15	40	a1,240	a450
.....	a540	a1,300	2,150	7,700	a16,450	4,150	a380	85	110	40	1,530	365
.....	500	.....	1,920	a7,300	17,860	3,860	410	55	a165	a40	1,870	280
.....	460	.....	1,690	5,900	18,920	a3,510	285	a50	140	40	a1,560	a280
.....	a460	.....	a1,690	.....	a18,920	.....	a260	45	.....	40	.....	245

a Meter measurements.

Estimated monthly discharge of Rio Grande near El Paso, Tex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
nuary	1,290	330	584	35,920
bruary	1,300	460	780	43,309
arch	4,910	1,690	3,065	188,489
ril	7,700	1,370	3,326	197,911
ay	18,920	5,170	8,879	545,950
ne	23,680	3,510	14,304	851,147
ly	3,150	260	956	58,800
ugust	950	45	322	19,785
ptember	165	15	56	3,322
tober	230	25	69	4,225
ovember	1,870	35	428	25,458
ecember	1,350	245	610	37,478
The year	23,680	15	2,782	2,011,794

RIO GRANDE ABOVE PRESIDIO, TEX.

This station was established April 4, 1900, by the International (Water) Boundary mission. It was 9 miles above Presidio and above the mouth of Rio Conchos, one principal tributaries of the Rio Grande, and about 200 miles below El Paso. The was in a straight stretch of the river, but in the bight of a long bend. In 1903 th began to erode a cut-off across this bend and the spring flood of 1905 deepened this c to such an extent that more water passed through it than through the station, and came necessary to abandon its location. In September, 1905, the station was m miles farther upstream and rebuilt. Its location is far enough above the mouth Conchos to be free from the effects of backwater from that stream.

The river is nearly straight for one-fourth mile above and below the new location. banks overflow slightly in extreme flood, but no large amount of water passes outs measured section. The bed is shifting sand. The banks are fairly solid, but woul if a heavy current should strike them.

Discharge measurements are made by means of a cable, car, tagged wire, and gu The initial point for soundings is the cable support on the left bank.

The gage is an inclined scantling fastened to posts sunk in the ground. The lo the river was gage height 1.5 feet September 21, 1905, and marks showed high wat 9.5 feet. The bench mark is the top of a mesquite post level with the ground back left guy-cable deadman; elevation, 9.35 feet above the datum of the gage.

The observations during 1905 were made under the direction of the United Sta tion of the International (Water) Boundary Commission. The hydrographer was Hague, and the gage reader was Preciliano Spencer.

Information in regard to this station is contained in the following publications United States Geological Survey (Ann=Annual Report; WS=Water-Supply Pap

Description: WS 50, p 356; 66, p 72; 84, p 177; 99, p 373; 132, p 71.
Discharge: WS 50, p 355; 66, pp 72-73; 84, p 178; 99, pp 373-375; 132, p 72.
Discharge, mean daily: WS 132, p 74.
Discharge, monthly: Ann 22, iv, p 354; WS 75, p 157; 84, p 179; 99, p 376; 132, p 75.
Gage heights: WS 50, p 355; 66, p 73; 84, p 178; 99, pp 375-376; 132, p 73.

Discharge measurements of Rio Grande above Presidio, Tex., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.
		Square feet.	*Feet per second.*	*Feet.*
January 3	Jas. P. Hague	158	2.04	3.55
January 6	do	145	2.03	3.4
January 9	do	143	1.96	3.4
January 12	do	140	1.91	3.3
January 15	do	167	2.07	3.6
January 18	do	213	2.98	4.2
January 21	do	205	2.70	3.95
January 24	do	186	2.52	3.8
January 27	do	171	2.29	3.7
January 30	do	163	2.28	3.55
February 2	do	169	2.09	3.55
February 5	do	171	2.35	3.7
February 8	do	155	2.06	3.5
February 11	do	159	2.13	3.5+
February 14	do	163	2.12	3.55
February 17	do	200	2.71	3.9
February 20	do	161	2.37	3.6
June 17[a]	do	1,489	4.10	8.8
June 21[a]	do	1,353	3.61	8.6

[a] Channel only. Bottoms overflowed. The channel was carrying less than 50 per cent of the t charge at the station. The actual discharge was computed from daily gage heights, the flow Presido station, and of Conchos River.

scharge measurements of Rio Grande above Presidio, Tex., in 1905—Continued.

te.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
a	Jas. P. Hague	1,322	3.34	8.5	4,411
a	do	1,301	3.33	8.5	4,331
	do	1,260	2.97	8.2	3,771
	do	1,097	2.43	7.0	2,668
	do	917	1.93	6.2	1,774
	do	671	2.13	5.0	1,432
	do	422	2.91	4.2	1,226
	do	526	3.48	5.6	1,830
b	do	633	3.61	6.05	2,285
	do	507	3.58	5.5	1,814
	do	456	3.37	5.2	1,537
	do	295	3.16	3.65	932
	do	290	3.14	3.6	912
2	do	338	2.67	3.7	903
5	do	333	2.79	3.7	929
8	do	232	2.02	2.6	469
10	do	235	2.36	2.7	555
13	do	223	1.87	2.6	416
16	do	259	2.12	3.0	549
19	do	265	2.13	3.0	565
22	do	260	2.03	2.8	528
25	do	225	1.89	2.4	426
27	do	201	1.61	2.15	323
30	do	213	1.59	2.2	339
ber 2	do	127	1.57	1.8	200
ber 5	do	171	1.77	2.3	302
ber 7	do	419	4.09	5.4	1,712
ber 10	do	282	2.20	3.15	620
ber 13	do	277	2.13	3.0	590
ber 16	do	70	1.51	1.5	106
ber 18	do	80	1.69	1.5	135
ber 21	do	71	1.56	1.5	111
ber 26c	do	75	1.57	3.0	118
ber 29	do	65	1.66	2.9	108
2	do	63	1.52	2.75	96
5	do	54	1.44	2.7	78
8	do	63	1.41	2.7	89
11	do	66	1.39	2.7	92
14	do	53	1.38	2.7	73
17	do	56	1.30	2.7	73
20	do	62	1.29	2.7	80
23	do	58	1.31	2.7	76
29	do	45	1.16	2.6	52
ber 1	do	46	1.11	2.6	51
ber 5	do	33	1.09	2.5	36
ber 8	do	48	1.23	2.65	59
ber 11	do	136	1.66	3.4	226
ber 14	do	164	1.59	3.5	260

nel only. Bottoms overflowed. The channel was carrying less than 50 per cent of the total dis-t the station. The actual discharge was computed from daily gage heights, the flow of lower station, and of Conchos River.

nel only. Bottom overflowed. Overflow ceased at 5.5 feet on gage.

on moved 8 miles farther up Rio Grande and new gage established 16 miles above mouth of The new gage heights are not comparable with old.

—No measurements were made during March, April, and May.

Discharge measurements of the Rio Grande above Presidio, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
November 17	Jas. P. Hague	135	1.72	3.4	2
November 20	do	109	1.31	3.1	1
November 23	do	101	1.29	3.0	1
November 26	do	98	1.31	3.0	1
November 29	do	90	1.29	2.9	1
December 3	do	213	2.07	3.8	4
December 6	do	320	2.54	4.4	8
December 9	do	291	2.50	4.3	7
December 12	do	328	2.67	4.4	8
December 16	do	227	2.52	4.0	5
December 19	do	204	2.34	3.8	4
December 22	do	251	2.31	4.2	5
December 24	do	228	2.49	4.15	5
December 28	do	216	2.55	4.15	5
December 31	do	192	2.57	4.0	4

Daily gage height, in feet, of Rio Grande above Presidio, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec
1	3.7	3.45	4.05	6.25	7.8	7.85	8.15	3.3	1.7	2.8	2.6	3.
2	3.7	3.55	4.35	6.0	7.85	8.0	7.9	3.95	1.65	2.75	2.6	3.
3	3.55	3.5	4.75	5.75	8.0	8.1	7.6	2.85	2.0	2.7	2.6	3.
4	3.5	3.5	4.5	5.95	8.0	8.2	7.3	3.25	2.1	2.7	2.5	4.
5	3.4	3.65	5.8	6.3	7.9	8.25	6.8	3.6	2.45	2.7	2.55	4.
6	3.4	3.7	6.3	6.45	8.1	8.5	6.6	2.9	1.7	2.7	2.6	4.
7	3.4	3.65	6.6	6.25	8.1	8.6	6.45	2.85	5.95	2.7	2.6	4.
8	3.4	3.55	7.45	6.2	8.1	8.75	6.15	2.7	4.15	2.7	2.65	4.
9	3.4	3.5	7.25	6.1	7.9	8.8	5.75	2.85	5.6	2.7	3.55	4.
10	3.4	3.55	7.4	6.25	7.75	8.85	5.3	2.65	3.15	2.7	3.5	4.
11	3.4	3.55	7.8	5.85	7.65	8.9	4.95	2.55	2.8	2.7	3.4	4.
12	3.3	3.4	7.9	5.5	7.7	8.85	4.7	2.6	3.05	2.7	3.6	4.
13	3.3	3.5	8.0	5.3	8.0	9.05	4.5	2.9	2.95	2.7	3.55	4.
14	3.3	3.6	8.15	5.0	8.0	9.05	4.15	2.6	2.25	2.7	3.45	4.
15	3.45	3.55	8.2	4.9	8.1	8.8	7.65	2.6	1.7	2.7	3.75	4.
16	3.6	3.8	8.0	5.15	8.05	8.75	5.8	2.9	1.55	2.7	3.65	3.
17	3.95	3.9	8.2	5.6	8.2	8.8	6.7	3.9	1.65	2.7	3.45	3.
18	4.25	4.0	7.95	6.15	8.15	8.5	4.75	3.35	1.5	2.7	3.5	3.
19	4.15	3.75	7.85	6.9	8.2	8.75	6.45	2.95	2.15	2.7	3.4	3
20	4.0	3.6	7.8	7.65	8.25	8.7	8.05	3.1	1.65	2.7	3.15	4
21	3.95	3.7	7.55	7.6	7.65	8.65	5.2	2.8	1.5	2.7	3.1	4
22	3.9	3.6	7.3	7.75	7.8	8.8	4.0	2.7	1.4	2.7	3.1	4
23	3.8	3.55	7.45	7.7	7.65	8.65	4.85	2.6	1.2	2.7	3.0	4
24	3.8	3.4	7.65	7.45	7.5	8.55	5.5	2.35	1.2	2.7	3.0	4
25	3.75	4.25	7.65	7.4	7.5	8.5	6.55	2.25	1.2	2.6	3.0	4
26	3.7	4.25	7.55	7.4	7.5	8.45	4.45	2.0	[a]3.0	2.6	3.0	4
27	3.75	4.15	7.2	7.75	7.55	7.95	3.65	2.15	3.0	2.6	3.0	4
28	3.6	4.1	6.7	7.85	7.6	7.7	3.65	1.8	2.9	2.6	3.0	4
29	3.6	.....	6.4	8.0	7.5	7.55	3.6	1.9	2.9	2.6	2.95	4
30	3.55	.....	6.35	7.85	7.6	7.8	3.6	2.35	2.8	2.6	2.9	4
31	3.5	.....	6.3	.....	7.75	.....	3.6	1.85	.....	2.6	.....	4

[a] September 26 this station was moved 8 miles farther up the Rio Grande and a new gage was established. The new gage heights are not comparable with the old.

Daily discharge, in second-feet, of Rio Grande above Presidio, Tex., for 1905.

Day.	Jan.	Feb.	Mar.[a]	Apr.[b]	May.[c]	June.[d]	July.[e]	Aug.	Sept.	Oct.	Nov.	Dec.
1	355	330	580	1,580	2,750	5,850	/6,400	740	180	100	/50	225
2	355	/355	650	1,470	2,850	6,200	5,400	/1,000	/170	/95	50	295
3	/325	340	800	1,370	3,100	6,500	4,200	575	240	85	50	/440
4	315	340	700	1,510	3,200	6,900	3,600	745	260	80	35	755
5	295	/385	1,310	1,730	3,200	7,480	/2,970	/890	/330	/80	/40	815
6	/295	400	1,580	1,850	3,500	8,860	2,730	595	180	80	50	/815
7	290	380	1,760	1,730	3,600	9,640	2,580	575	/2,260	85	50	855
8	285	/340	2,310	1,700	3,700	10,620	/2,280	/510	1,070	/90	/60	730
9	/280	325	2,180	1,640	3,600	11,200	1,880	595	1,910	90	270	/730
10	280	345	2,270	1,730	3,550	11,780	1,610	/535	/620	90	255	670
11	280	/350	2,810	1,510	3,550	12,360	/1,420	460	550	/90	/225	735
12	/265	315	2,960	1,340	3,700	12,540	1,350	445	600	85	295	/835
13	265	335	3,110	1,240	4,100	13,700	1,300	/515	/575	80	280	645
14	265	/360	3,330	1,090	4,200	13,700	/1,210	415	350	/75	/245	570
15	/305	345	3,430	1,040	4,400	12,600	4,200	415	170	75	335	610
16	345	480	3,110	1,160	4,450	12,400	2,030	/515	120	75	305	/535
17	515	/540	3,430	1,390	4,700	/12,600	/3,150	915	165	/75	/245	480
18	/660	590	3,030	1,670	4,750	11,400	1,370	700	/135	75	260	505
19	615	460	2,880	2,120	4,900	12,300	/2,850	/545	320	75	230	/480
20	570	/380	2,810	2,640	5,050	12,100	5,000	600	160	/80	/160	570
21	/555	430	2,430	2,610	4,550	/11,900	/1,540	530	/110	80	145	595
22	525	390	2,220	2,710	4,800	12,500	1,070	/500	110	75	145	/580
23	470	355	2,320	2,680	4,750	11,900	1,410	475	100	/75	/130	580
24	/470	315	2,580	2,500	4,700	/11,500	/1,810	410	110	75	130	/565
25	430	680	2,580	2,470	4,800	10,800	3,000	/365	120	60	130	560
26	390	680	2,430	2,470	4,900	10,100	1,250	245	/120	55	/130	585
27	/430	640	2,150	2,710	5,050	/7,600	/930	/325	120	55	130	610
28	375	620	1,820	2,780	5,200	6,100	930	210	110	50	130	/550
29	375	.....	1,640	2,890	5,200	5,500	910	245	/110	/50	/120	530
30	/370	.....	1,610	2,780	5,400	6,000	/910	/390	100	50	115	510
31	355	.....	1,580	.....	5,650	.....	910	230	.....	50	.....	/495

[a] Discharge computed from former measurements and checked by discharge of the lower Presidio station.

[b] Discharge computed from measurements of June and July, 1903.

[c] Water flowing across bottoms during the whole month. Discharge computed from those of the lower Presidio station, due allowance being made for flow of Rio Conchos.

[d] Over 50 per cent of the water passing this station during June was outside of channel. Discharges obtained by combining gage heights with flow at the lower Presidio station and of the Conchos.

[e] Discharge for gage heights above 5.5 feet when water leaves main channel above station and flows across bottom was obtained by combining gage height with flow at the lower Presidio station and of the Conchos.

/ Meter measurements.

Estimated monthly discharge of Rio Grande above Presidio, Tex., for 1905.

Month.	Discharge in second-feet.		
	Maximum.	Minimum.	Mean.
January	660	265	384
February	680	315	421
March	3,430	580	2,206
April	2,890	1,040	1,937
May	5,650	2,750	4,253
June	13,700	5,500	10,154
July	6,400	910	2,329
August	1,000	210	523
September	2,260	100	382
October	100	50	75
November	335	35	160
December	855	225	505
The year	13,700	35	1,952

RIO CONCHOS NEAR OJINAGA, MEXICO.

Discharge measurements of Rio Conchas 2 miles above mouth, near Ojinaga, M

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.
1905.		*Square feet.*	*Feet per second.*	*Feet.*
June 18	Jas. P. Hague	527	1.77	2.5
June 22	....do	472	1.26	2.2
July 4	....do	294	.97	1.5

NOTE.—Above measurements made to determine the inflow between the upper and lowe stations.

RIO GRANDE BELOW PRESIDIO, TEX.

This station was established April 8, 1900, by the International (Water) Bound mission. It is 6 miles below Presidio; also below the mouth of Rio Conchos and a miles below El Paso. It is at the west end of the canyon section of the Rio Gran discharge at this station minus the discharge at the station above Presidio, Te discharge of Rio Conchos, except at rare intervals, when some rain water enters Grande from the north.

The river is fairly straight at the station and for one-fourth mile above and bel right bank is a rocky bluff. The left bank is an alluvial deposit and overflow feet back from the river, where gravel hills are found. The bed is shifting sa affected by a drainage line called Alamos Creek, which reaches the river one-fo below the station. This is subject to torrential floods, which bring large quantities ders and gravel into the Rio Grande, forming a temporary dam. This remains, backwater onto the gage, until a flood in the river scours it out.

Discharge measurements are made by means of a cable, car, tagged wire, and g The tagged wire is extended across the bottom on the Texas side to the foot of t hills. The initial point for soundings is the tagged-wire support at the hills on bank. A boat is provided for measuring flood flow across the bottom.

The gage is an inclined scantling bolted to posts sunk into the ground. Th overflow gage at the gravel hills. This consists of a vertical staff nailed to a tr range between low and high water is about 23 feet. The highest recorded gage 26.35 feet, September 11, 1904. The extreme floods come from the Conchos. Th

at 13 feet on the gage. The bench mark is the top of a pine post sunk in the
t the foot of the gravel hills at the left end of the tagged wire; elevation, 13.55
e the datum of the gage.
servations during 1905 were made under the direction of the United States section
ernational (Water) Boundary Commission. The hydrographer is James P. Hague,
age reader, Felicitas Gonzales.
ation in regard to this station is contained in the following publications of the
tates Geological Survey (Ann = Annual Report; WS = Water-Supply Papers):

ion: WS 50, p 355; 66, p 74; 84, p 175; 99, p 368; 132, p 75.
e: WS 50, p 356; 66, p 74; 84, pp 175-176; 99, pp 369-372; 132, pp 75-78.
e, mean daily: WS 132, p 79.
e, monthly: Ann 22, iv, p 355; WS 75, p 158; WS 84, p 177; 99, p 373; 132, p 79.
ghts: WS 50, p 356; 66, p 75; 84, pp 176-177; 99, p 372; 132, p 78.
aph: WS 75, p 159.

Discharge measurements of Rio Grande below Presidio, Tex., in 1905.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
	Jas. P. Hague	851	1.62	6.9	1,376
	do	772	1.40	6.7	1,078
	do	766	1.43	6.65	1,096
1	do	756	1.42	6.55	1,071
4	do	730	1.33	6.5	971
7	do	741	1.34	6.55	995
0	do	878	1.71	7.05	1,502
3	do	859	1.64	6.9	1,407
6	do	751	1.57	6.8	1,176
9	do	656	1.49	6.6	978
1	do	690	1.34	6.45	925
3	do	656	1.37	6.4	899
6	do	638	1.33	6.4	848
9	do	611	1.30	6.35	795
12	do	595	1.30	6.25	774
15	do	580	1.25	6.1	724
18	do	838	1.63	6.9	1,366
21	do	976	1.99	7.5	1,945
	do	2,582	4.86	11.25	12,541
	do	2,568	4.86	11.2	12,473
	do	2,320	4.58	10.45	10,622
	do	1,867	3.46	9.3	6,456
	do	1,680	2.37	8.3	3,980
	do	1,582	2.03	7.9	3,219
	do	1,321	1.57	7.5	2,073
	do	1,224	1.37	7.2	1,677
	do	1,346	1.64	7.65	2,202
	do	1,752	3.57	8.85	6,249
	do	2,294	4.41	10.2	10,128
	do	2,229	4.45	10.1	9,910
	do	2,652	5.55	11.2	14,715
	do	2,705	6.05	11.65	16,355
	do	2,259	4.62	10.5	10,432
	do	1,548	2.78	8.6	4,303
	do	1,540	2.80	8.6	4,305
	do	1,468	2.61	8.4	3,836
	do	1,467	2.70	8.5	3,966
	do	1,857	5.02	10.0	9,319

Discharge measurements of Rio Grande below Presidio, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di cha
		Square feet.	*Feet per second.*	*Feet.*	*Sec fe*
August 18	Jas. P. Hague	2,767	5.89	11.7	1
August 21	do	1,888	4.72	10.0	
August 24	do	1,783	4.52	9.7	
August 26	do	1,722	4.74	9.75	
August 28	do	1,568	3.82	8.9	
August 31	do	1,300	2.51	8.1	
September 3	do	914	2.68	7.6	
September 6	do	944	2.78	7.6	
September 11	do	2,313	4.82	10.65	
September 14	do	2,303	4.70	10.55	
September 17	do	1,780	4.59	9.8	
September 20	do	1,085	3.81	8.55	
September 23	do	2,933	7.06	12.3	
September 27	do	2,407	5.20	10.95	
September 30	do	2,430	5.34	11.05	
October 3	do	2,718	5.72	11.45	
October 6	do	2,553	5.38	11.1	
October 9	do	1,641	4.05	8.95	
October 12	do	1,588	3.59	8.6	
October 15	do	1,056	2.88	7.9	
October 18	do	1,126	2.48	7.7	
October 21	do	1,164	2.06	7.5	
October 24	do	1,002	1.85	7.2	
October 28	do	972	1.54	7.0	
October 31	do	954	1.41	7.0	
November 3	do	866	1.50	6.75	
November 7	do	1,489	3.69	8.75	
November 10	do	2,265	4.83	10.75	
November 13	do	1,547	4.73	9.4	
November 16	do	1,420	4.63	9.15	
November 19	do	1,489	4.80	9.3	
November 22	do	1,377	3.72	8.65	
November 25	do	1,131	2.66	7.9	
November 28	do	1,076	2.59	7.65	
December 2	do	1,548	4.45	9.2	
December 5	do	1,312	4.04	8.6	
December 8	do	1,140	3.49	8.2	
December 10	do	1,016	3.17	7.9	
December 14	do	908	2.82	7.6	
December 17	do	1,438	4.39	9.1	
December 20	do	1,491	4.68	9.2	
December 23	do	1,610	4.82	9.45	
December 27	do	1,317	4.12	8.6	
December 30	do	1,262	2.91	8.1	

Daily gage height, in feet, of Rio Grande below Presidio, Tex., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	6.9	6.4	7.35	7.75	8.15	9.3	9.45	10.3	7.95	10.5	6.9	7.7
.....	6.85	6.4	7.3	7.6	8.3	9.35	8.8	9.75	7.85	11.4	6.8	9.3
.....	6.8	6.4	7.35	7.6	8.45	9.4	8.4	9.1	7.6	11.2	6.75	9.4
.....	6.8	6.4	7.15	7.5	8.3	9.6	8.3	8.8	7.6	10.6	6.7	8.7
.....	6.75	6.4	7.4	7.45	8.35	9.85	8.2	8.75	7.75	10.75	6.95	8.55
.....	6.7	6.4	7.85	7.65	8.45	10.05	8.15	8.6	7.75	11.3	7.7	8.45
.....	6.7	6.5	7.95	7.7	8.5	10.35	7.9	8.55	9.4	11.0	8.8	8.25
.....	6.65	6.45	8.1	7.65	8.55	10.5	7.6	8.5	9.55	9.75	9.8	8.15
.....	6.6	6.35	8.15	7.65	8.5	10.75	7.65	8.35	11.35	9.05	10.3	8.0
.....	6.6	6.3	8.1	7.65	8.65	11.15	7.55	8.5	11.3	8.85	10.7	7.85
.....	6.55	6.3	8.15	7.6	8.6	11.55	7.5	8.6	10.75	8.65	11.6	7.8
.....	6.5	6.25	8.25	7.45	8.55	11.7	7.3	8.55	10.7	8.6	10.75	7.75
.....	6.5	6.1	8.2	7.4	8.6	12.15	7.2	9.05	10.45	8.3	9.3	7.7
.....	6.5	6.1	8.25	7.4	8.7	12.6	7.2	9.6	10.45	8.1	9.3	7.6
.....	6.5	6.1	8.4	7.4	8.8	12.35	8.8	10.2	10.45	7.9	9.55	8.05
.....	6.5	6.3	8.3	7.35	8.8	12.0	7.8	10.0	10.05	7.75	9.2	8.85
.....	6.55	6.95	8.6	7.4	8.9	11.35	10.35	10.45	9.75	7.7	9.4	9.15
.....	6.7	6.85	8.6	7.7	8.95	11.15	8.45	11.7	9.05	7.7	9.6	9.5
.....	6.85	7.45	8.45	7.8	8.95	11.25	9.4	10.9	8.85	7.65	9.2	10.0
.....	7.05	7.45	8.45	7.9	9.0	11.3	10.65	10.5	8.55	7.6	9.1	9.5
.....	6.9	7.5	8.35	8.1	8.95	11.35	10.2	10.0	8.7	7.5	8.9	9.75
.....	6.9	7.4	8.15	8.1	9.0	11.45	9.85	9.65	9.65	7.45	8.55	10.0
.....	6.9	7.5	8.1	7.85	9.25	11.25	10.6	9.75	11.95	7.35	8.25	9.4
.....	6.9	7.2	8.05	7.8	9.05	11.05	10.6	9.8	13.35	7.25	8.2	9.0
.....	6.8	7.2	8.2	7.8	8.9	10.8	11.25	10.2	14.45	7.2	8.05	8.75
.....	6.8	7.4	8.15	7.95	8.9	10.5	11.4	9.75	13.25	7.15	7.8	8.65
.....	6.75	7.5	8.15	8.0	9.05	9.85	11.55	9.5	10.9	7.1	7.75	8.6
.....	6.7	7.45	8.1	8.15	9.2	9.4	11.75	9.0	10.3	7.0	7.65	8.45
.....	6.6	.....	7.9	8.1	9.1	9.3	11.05	8.75	10.35	7.0	7.55	8.35
.....	6.5	.....	7.8	8.15	9.0	9.3	10.55	8.35	11.3	7.0	7.7	8.15
.....	6.45	.....	7.7	.....	9.15	.....	10.3	8.15	.....	7.0	.....	8.0

Daily discharge, in second-feet, of Rio Grande below Presidio, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.[a]	May.[a]	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1,360	900	2,050	2,630	2,970	6,400	6,830	[b]10,430	3,000	11,750	1,320	2,880
2	[b]1,330	900	1,980	2,410	3,270	6,580	5,220	8,440	2,850	15,200	1,300	[b]7,160
3	1,250	[b]900	2,050	2,380	3,650	6,770	[b]4,230	6,160	[b]2,450	[b]14,130	[b]1,290	7,420
4	1,220	880	1,750	2,230	3,270	7,510	3,980	[b]5,020	2,510	12,080	1,270	5,560
5	[b]1,130	860	2,130	2,140	3,390	8,450	3,790	4,840	2,810	12,570	1,710	[b]5,130
6	1,100	[b]850	2,840	2,350	3,650	9,210	3,690	4,300	[b]2,870	[b]14,530	3,300	4,810
7	1,120	950	3,000	2,390	3,800	10,330	[b]3,220	[b]4,190	7,680	13,400	[b]5,640	4,140
8	[b]1,100	900	3,250	2,290	3,940	10,800	2,360	4,070	8,100	9,280	8,360	[b]3,850
9	1,090	[b]800	3,330	2,260	3,800	11,400	2,500	[b]3,670	13,140	[b]6,970	9,720	3,490
10	1,080	790	3,250	2,200	4,230	12,360	[b]2,210	4,070	13,000	6,370	[b]10,810	[b]3,110
11	[b]1,070	790	3,330	2,200	4,090	13,410	2,070	4,300	[b]11,440	5,830	13,500	3,000
12	1,010	[b]770	3,500	2,020	3,940	13,880	1,810	[b]4,140	11,300	[b]5,700	10,940	2,810
13	990	720	3,420	1,960	4,090	15,410	[b]1,680	5,930	10,500	4,610	[b]7,020	2,700
14	[b]970	720	3,500	1,960	4,380	16,940	1,680	7,900	[b]10,500	3,820	7,020	[b]2,810
15	970	[b]720	3,760	1,960	4,670	16,090	6,080	[b]10,100	10,500	[b]3,040	7,770	3,000
16	970	880	3,590	1,900	4,670	14,900	[b]2,650	9,320	9,080	2,860	[b]6,720	5,690
17	[b]1,000	1,400	4,110	1,960	4,980	12,850	10,730	11,100	[b]8,010	2,790	7,440	[b]6,010
18	1,150	1,320	4,110	2,330	5,140	12,340	[b]4,910	[b]16,300	5,750	[b]2,790	8,040	7,000
19	1,300	1,900	3,840	2,460	5,140	12,590	7,830	12,600	5,100	2,690	[b]6,840	8,810
20	[b]1,500	1,900	3,840	2,600	5,310	[b]12,660	[b]11,930	10,900	[b]4,130	2,590	6,530	[b]7,730
21	1,410	[b]1,950	3,670	2,890	5,140	12,810	10,130	[b]8,910	4,610	[b]2,400	5,900	8,400
22	1,410	1,870	3,330	2,890	5,310	13,100	[b]9,160	7,920	8,790	2,310	[b]4,840	9,080
23	[b]1,410	1,990	3,250	2,530	6,210	[b]12,600	12,080	8,200	[b]19,140	2,130	4,000	[b]7,610
24	1,360	1,710	3,160	2,460	5,490	12,120	12,080	[b]8,340	23,870	[b]1,950	3,850	6,530
25	1,220	1,730	3,420	2,460	4,980	11,510	[b]14,900	9,700	27,170	1,860	[b]3,430	5,810
26	[b]1,180	1,950	3,330	2,670	4,980	[b]10,770	15,440	[b]8,160	22,130	1,770	2,920	5,340
27	1,130	2,070	3,330	2,740	5,490	8,470	15,990	7,520	[b]12,300	1,680	2,880	[b]5,410
28	1,080	2,040	3,250	2,970	6,030	6,810	[b]16,750	[b]6,250	9,540	[b]1,500	[b]2,790	4,900
29	[b]980	.....	2,920	2,890	5,670	[b]6,460	13,960	4,800	9,770	1,450	2,690	4,530
30	950	.....	2,760	2,970	5,310	6,460	11,960	4,120	14,130	[b]1,400	2,880	[b]3,850
31	[b]930	.....	2,600	.....	5,850	.....	10,960	[b]3,430	.....	1,350	.....	3,530

[a] Daily discharges computed from measurements of November, 1904, and June, 1905.
[b] Meter measurements.

Estimated monthly discharge of Rio Grande below Presidio, Tex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	1,500	930	1,154	70,949
February	2,070	720	1,256	69,739
March	4,110	1,750	3,150	193,686
April	2,970	1,900	2,405	143,127
May	6,210	2,970	4,608	283,319
June	16,940	6,400	11,065	658,433
July	16,750	1,680	7,510	461,772
August	16,300	3,430	7,260	446,420
September	27,170	2,450	9,872	587,445
October	15,200	1,350	5,574	342,744
November	13,500	1,270	5,424	322,750
December	9,080	2,560	5,286	325,031
The year	27,170	720	5,380	3,905,415

RIO GRANDE NEAR LANGTRY, TEX.

ion was established in April, 1900, by the International (Water) Boundary Com-
t is located one-half mile south of Langtry station, on the southern Pacific Rail-
s about 440 miles below El Paso, Tex., at the east end of the canyon section of
ande, and a short distance to the west of the mouth of Pecos River, one of the
ibutaries of the Rio Grande.

r is nearly straight for 1 mile above and one-half mile below the station. The
can) bank is a rock bluff. The left bank is alluvial deposit for 200 feet back to
. The bed of the river is shifting sand, as is also the left bank.

e measurements are made by means of a cable of 490 feet span, car, tagged wire,
re. The initial point for soundings is the pole supporting the cable on the left

is a vertical staff, bolted to the bluff on the right bank. It is read from the left
the aid of field glasses. The range between high and low water is about 36 feet.
t recorded gage is 36.5 feet, September 13, 1904. The bottom begins to over-
e height 29.5 feet and the overflow extends 110 feet back from the cable pole.
n is densely wooded. The bench mark is a cross cut on a large bowlder at the
Texas side, in line with the cable; elevation, 40.56 feet above the datum of the

ions during 1905 were made under the direction of the United States section of
tional (Water) Boundary Commission. The hydrographer was E. E. Winter
ge reader was W. H. Dodd.

ion in regard to this station is contained in the following publications of the
tes Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

WS 50, p 357; 66, p 75; 84, p 172; 99, p 365; 132, p 80.
WS 50, p 357; 66, pp 75–76; 84, pp 172–173; 99, pp 365–367; 132, pp 80–81.
ean daily: WS 132, p 83.
onthly: Ann 22, iv, p 355; WS 75, p 160; 84, p 174; 99, p 368; 132, p 83.
s: WS 50, p 358; 66, p 76; 84, p 174; 99, pp 367–368; 132, p 82.

Discharge measurements of Rio Grande near Langtry, Tex., in 1905.

Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
E. E. Winter	658	2.36	1.6	1,552
do	642	2.30	1.55	1,474
do	618	2.02	1.4	1,248
do	625	1.93	1.3	1,207
do	585	1.88	1.1	1,097
do	628	2.06	1.4	1,296
do	587	2.10	1.5	1,234
do	607	1.72	1.3	1,045
do	568	1.62	1.2	922
do	571	1.59	1.2	909
do	531	2.02	1.1	1,070
do	520	1.95	1.0	1,012
do	713	2.71	1.9	1,932
do	840	2.49	2.2	2,091
do	1,162	3.28	3.1	3,810
do	1,187	3.21	3.3	3,810
do	944	3.00	3.0	2,831
do	968	3.07	3.0	2,976
do	883	2.83	2.7	2,496
do	732	2.46	2.3	1,800

Discharge measurements of Rio Grande near Langtry, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di char
		Square feet.	*Feet per second.*	*Feet.*	*Seco fe*
April 7	E. E. Winter	789	2.62	2.0	
April 11	do	774	2.84	1.9	
April 15	do	777	2.94	1.9	
April 20	do	791	2.99	1.7	
April 24	do	956	2.99	2.4	
April 27	do	889	2.97	2.4	
May 2	do	957	3.14	2.6	
May 6	do	1,037	3.59	2.7	
May 10[a]	do	868	2.86	3.4	
May 15	do	1,087	3.57	3.3	
May 19	do	1,158	4.11	3.4	
May 24	do	1,184	3.81	3.5	
May 29	do	1,175	3.55	3.4	
June 2	do	1,120	4.25	3.8	
June 8	do	1,532	5.01	5.2	
June 12	do	2,344	5.66	6.8	1
June 16	do	3,167	5.96	8.5	1
June 20	do	2,538	5.09	7.1	1
June 24	do	2,481	5.28	7.3	1
June 28	do	1,718	4.38	5.9	
July 3	do	1,129	4.06	4.1	
July 8	do	984	3.58	2.8	
July 14	do	760	3.25	2.0	
July 19	do	1,056	3.36	3.2	
July 24	do	1,403	4.65	4.8	
July 29	do	1,659	5.16	6.1	
August 4	do	1,350	4.45	3.9	
August 10	do	1,126	3.55	3.2	
August 14	do	1,658	4.67	5.2	
August 19	do	1,724	4.92	5.55	
August 24	do	1,433	4.74	4.4	
August 28	do	1,444	4.75	4.5	
September 2	do	997	3.61	2.7	
September 7	do	848	3.47	2.15	
September 10	do	1,643	4.52	5.65	
September 16	do	1,355	3.95	4.4	
September 22	do	1,017	3.72	3.0	
September 25	do	1,672	4.78	5.65	
September 28	do	3,324	7.13	10.85	
October 2	do	1,693	5.16	6.35	
October 6	do	1,355	4.88	5.0	
October 10	do	1,310	4.71	4.65	
October 14	do	1,035	3.71	3.25	
October 19	do	980	3.52	2.5	
October 23	do	818	3.34	2.0	
October 28	do	766	2.98	1.7	
November 2	do	769	2.62	1.6	
November 6	do	751	1.87	1.3	
November 9	do	733	1.80	1.3	
November 13	do	1,004	3.13	2.7	
November 17	do	1,302	3.52	4.0	
November 21	do	1,342	3.64	4.1	

[a] Channel filled with mud washed in by local rains.

Discharge measurements of Rio Grande near Langtry, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
November 28	E. E. Winter	942	3.74	2.4	3,523
November 30	do	784	3.70	2.0	2,902
December 3	H. F. Collins	839	3.87	2.1	3,248
December 9	do	1,047	3.83	2.85	4,008
December 12	do	931	3.75	2.2	3,493
December 17	do	817	3.59	2.0	2,937
December 20	do	1,500	5.62	4.2	8,434
December 25	do	1,589	5.85	4.6	9,299
December 31	do	990	4.19	2.7	4,144

Daily gage height, in feet, of Rio Grande near Langtry, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.7	1.4	1.9	5.4	2.45	3.5	10.2	5.2	2.95	5.5	1.6	1.9
2	1.7	1.25	1.9	2.6	2.6	3.85	5.35	4.8	2.65	6.75	1.6	1.9
3	1.6	1.2	1.9	2.4	2.6	3.8	4.2	4.1	2.55	7.3	1.55	2.05
4	1.6	1.15	1.95	2.25	2.6	3.9	3.7	3.9	2.5	6.4	1.5	3.2
5	1.6	1.05	2.3	2.15	2.65	3.9	3.65	3.75	2.55	5.4	1.45	3.85
6	1.55	1.15	2.3	2.0	2.7	4.05	3.55	3.5	2.15	4.9	1.3	3.55
7	1.5	1.05	2.3	2.0	2.7	4.55	2.8	3.45	2.15	5.7	1.3	3.4
8	1.5	1.1	2.5	2.0	2.8	5.25	2.8	3.35	2.7	6.65	1.3	3.15
9	1.5	1.2	4.35	2.05	5.1	5.7	2.65	3.2	2.9	5.55	1.3	2.85
10	1.45	1.15	3.05	2.05	3.45	5.65	2.4	3.2	6.25	4.6	1.3	2.55
11	1.4	1.1	2.8	1.95	3.2	5.8	2.25	3.1	9.5	4.15	1.3	2.4
12	1.4	1.1	2.8	1.9	3.7	6.95	2.2	2.9	5.4	3.75	1.3	2.25
13	1.3	1.1	2.9	1.9	4.0	7.0	2.1	5.95	5.1	3.6	2.0	2.2
14	1.3	1.1	2.9	1.9	3.95	7.7	2.0	5.1	4.5	3.15	4.3	2.1
15	1.3	1.1	3.35	1.9	3.35	8.15	1.95	5.35	4.4	2.95	7.0	2.1
16	1.25	1.0	3.1	1.9	3.25	8.65	1.9	5.75	4.4	2.85	4.55	2.0
17	1.2	1.0	3.0	1.8	3.3	8.3	2.15	6.3	4.95	2.8	4.0	2.0
18	1.2	1.0	3.0	1.7	3.3	7.1	3.25	5.55	4.8	2.5	4.5	2.55
19	1.1	1.0	3.0	1.7	3.35	7.35	3.25	6.25	3.95	2.45	4.6	4.0
20	1.1	1.0	3.05	1.7	3.4	7.15	3.75	6.7	3.5	2.25	4.15	4.25
21	1.1	1.2	3.25	1.7	3.5	7.3	3.9	7.05	3.05	2.1	4.05	4.2
22	1.1	1.4	3.1	1.7	3.5	7.2	4.65	5.95	2.9	2.0	3.7	4.0
23	1.25	2.0	3.0	2.35	3.5	7.25	5.35	4.65	2.7	1.95	3.2	4.5
24	1.7	1.9	2.9	2.4	4.15	7.25	4.85	4.35	2.7	1.9	2.8	5.25
25	1.65	1.85	2.75	2.4	3.7	7.1	7.55	5.65	5.6	1.8	2.55	4.6
26	1.6	1.8	2.7	2.4	3.5	7.0	5.4	5.15	8.4	1.8	2.4	3.9
27	1.6	1.8	2.7	2.4	3.5	6.3	5.3	4.95	10.4	1.75	2.4	3.6
28	1.5	1.8	2.7	2.75	3.4	5.65	5.5	4.5	10.3	1.7	2.35	3.25
29	1.5	.....	2.7	2.55	3.6	7.5	6.15	4.05	6.6	1.6	2.2	3.05
30	1.45	.....	2.7	2.4	3.45	11.1	6.4	3.65	5.65	1.6	1.95	2.85
31	1.4	.....	2.5	.....	3.5	.....	6.15	3.3	.....	1.6	.....	2.7

Daily discharge, in second-feet, of Rio Grande near Langtry, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	1,350	1,130	1,930	7,700	2,700	4,370	25,700	7,520	4,000	7,830	2,100	
2	a1,550	a990	1,930	2,100	3,000	a 4,860	6,420	7,050	a 3,540	a9,930	a2,010	
3	1,550	930	1,930	a1,900	3,130	4,760	a4,690	6,230	3,420	11,580	1,910	a
4	1,550	870	1,960	1,890	3,260	4,960	4,260	a6,000	3,360	8,880	1,810	
5	1,550	760	2,190	1,930	3,490	4,960	4,220	5,600	3,420	7,240	1,710	
6	a1,470	a 880	a2,190	1,920	a3,730	5,270	4,140	5,000	2,940	a6,480	a1,410	
7	1,400	820	2,280	a2,070	3,730	6,310	3,520	4,800	a 2,940	7,800	1,380	
8	1,400	850	2,660	2,130	3,930	a 7,770	a3,520	4,500	3,600	9,630	1,350	
9	1,400	910	6,690	2,220	6,530	9,420	3,320	4,100	3,850	7,580	a1,320	
10	1,320	a 880	a3,710	2,280	a2,590	9,250	3,000	a4,000	a 9,530	a6,090	1,300	
11	1,250	910	3,130	a2,240	2,410	9,770	2,800	3,800	22,500	5,330	1,280	
12	a1,250	960	3,050	2,220	3,730	a13,770	2,730	3,400	8,150	4,670	1,260	a
13	1,210	1,020	3,170	2,240	4,650	13,940	2,600	9,240	7,320	4,420	a2,240	
14	a1,210	a1,070	3,090	2,260	4,870	16,250	a2,470	a7,540	5,640	a3,780	5,480	
15	1,210	1,070	a3,910	a2,280	a3,980	17,730	2,420	8,050	5,360	3,680	13,880	
16	1,180	1,010	3,310	2,340	3,950	a19,380	2,380	8,870	a 5,360	3,630	6,230	
17	1,150	1,010	3,020	2,300	4,220	18,040	2,600	9,980	6,900	3,600	a4,580	a
18	1,150	a1,010	2,930	2,250	4,390	12,930	3,620	8,480	6,480	3,450	6,080	
19	a1,100	1,010	a2,830	2,300	a4,660	14,000	a3,640	a9,880	5,200	a3,380	6,380	
20	1,100	1,010	2,960	a2,360	4,670	a12,970	4,570	10,780	4,530	3,090	5,040	a
21	1,100	1,210	3,400	2,360	4,780	13,100	4,850	11,480	3,850	2,870	a4,850	
22	1,100	1,420	3,140	2,370	4,690	13,010	6,240	9,530	a 3,670	2,730	4,570	
23	a1,200	2,030	a2,980	2,820	4,660	13,050	7,540	7,230	3,450	a2,650	4,170	
24	1,500	1,930	2,820	a2,860	a5,810	a13,050	a6,600	a6,700	3,450	2,580	3,850	
25	1,430	a1,880	2,580	2,780	4,880	12,300	14,700	9,300	a 7,900	2,430	3,640	a
26	1,370	1,830	2,500	2,710	4,450	11,910	7,460	8,230	16 280	2,430	3,520	
27	1,370	1,830	2,500	a2,640	4,420	9,120	7,300	7,800	22,340	2,350	3,520	
28	a1,230	1,830	a2,500	2,990	4,190	a 7,020	7,620	a6,860	a22,030	a2,280	a3,440	
29	1,230	.....	2,500	2,790	a4,570	14,600	a8,650	5,960	10,830	2,200	3,210	
30	1,180	.....	2,500	2,640	4,270	29,300	9,170	5,160	7,980	2,200	a2,830	
31	1,130	.....	2,180	.....	4,370	.....	8,670	4,460	.....	2,200	.....	a

a Meter measurements.

Estimated monthly discharge of Rio Grande near Langtry, Tex., for 1905.

Month.	Discharge in second-feet.			Total acre-fe
	Maximum.	Minimum.	Mean.	
January	1,550	1,100	1,296	7
February	2,030	760	1,181	6
March	6,690	1,930	2,854	17
April	7,700	1,890	2,530	15
May	6,530	2,410	4,150	25
June	29,300	4,370	11,572	68
July	25,700	2,380	5,852	35
August	11,480	3,400	7,017	43
September	22,500	2,940	7,327	43
October	11,580	2,200	4,806	29
November	13,880	1,260	3,545	21
December	10,700	2,760	5,227	32
The year	29,300	760	4,780	3,47

IO GRANDE BELOW MOUTH OF DEVILS RIVER, TEXAS.

ıtion was established in April, 1900, by the International (Water) Boundary Com-
It is alongside the Southern Pacific Railroad track, about a mile below the mouth
River and about 480 miles below El Paso.

er is nearly straight for 1 mile above and the same distance below the station.
bank is alluvial deposit, overflowing in extreme high water for a distance of some
ack from the river. The left bank is a loose rock fill along which runs the South-
c Railroad. The bed is rock for a short distance from the left bank; the rest is
ınd and gravel.

ge measurements are made by means of a cable, car, tagged wire, and guy wire.
ge is an inclined scantling spiked to posts set in the ground. The highest flood
showed watermarks of 36.5 feet on gage; it occurred April 6, 1900, about two
ore this gage was established. The range between high and low water is about
The bench mark is a cross cut on top of the coping stone of a culvert near the
vation, 36.98 feet above the datum of the gage.

servations during 1905 have been made under the direction of the United States
the International (Water) Boundary Commission. The hydrographer is E. E.
ıd the gage reader is John Harrison.

ation in regard to this station is contained in the following publications of the
tates Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

n: WS 50, pp 364–365; 66, p 80; 84, p 162; 99, p 345; 132, p 84.
WS 50, p 365; 66, p 80; 84, p 162; 99, pp 345–347; 132, pp 84–85.
mean daily: WS 132, p 87.
monthly: Ann 22, iv, p 357; WS 75, p 161; 84, p 163; 99, p 348; 132, p 88.
ıts: WS 50, p 365; 66, p 81; 84, p 163; 99, pp 347–348; 132, p 86.

arge measurements of Rio Grande below mouth of Devils River, Texas, in 1905.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
.....	E. E. Winter	1,267	1.99	3.9	2,524
)	.....do	1,225	1.99	3.8	2,439
3	.....do	1,185	1.91	3.7	2,264
3	.....do	1,171	1.87	3.6	2,187
	.....do	1,155	1.82	3.6	2,104
5	.....do	1,218	1.98	3.9	2,411
	.....do	1,175	1.89	3.7	2,225
1	.....do	1,160	1.78	3.6	2,060
)	.....do	1,190	1.78	3.7	2,123
13	.....do	1,150	1.74	3.6	2,005
17	.....do	1,342	1.64	3.6	2,197
22	.....do	1,392	1.72	3.85	2,401
28	.....do	1,566	2.23	4.4	3,485
.....	.....do	1,607	2.17	4.6	3,487
.....	.....do	1,746	2.51	5.3	4,378
.....	.....do	1,887	3.56	6.0	6,715
.....	.....do	1,926	3.73	6.2	7,193
.....	.....do	1,703	2.64	5.6	4,494
.....	.....do	1,602	2.29	5.1	3,671
.....	.....do	1,570	2.58	4.7	4,050
.....	.....do	1,531	2.87	4.5	4,400
.....	.....do	1,468	2.84	4.4	4,167
.....	.....do	1,385	2.28	4.0	3,152
.....	.....do	1,402	2.41	4.25	3,382
.....	.....do	1,790	2.84	5.5	5,078

Discharge measurements of Rio Grande below mouth of Devils River, etc.—Continued

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di cha
		Square feet.	*Feet per second.*	*Feet.*	*Sec fe*
April 30	E. E. Winter	2,170	3.24	6.7	
May 5	do	1,741	3.03	5.7	
May 9	do	1,930	3.15	5.9	
May 13	do	1,774	3.04	5.7	
May 18	do	1,977	3.38	6.0	
May 22	do	2,122	3.11	5.9	
May 26	do	2,203	3.27	6.2	
May 31	do	2,280	3.68	6.4	
June 6	do	2,386	3.44	6.6	
June 10	do	2,717	4.59	7.5	
June 15	do	3,101	5.08	9.4	
June 19	do	3,410	6.12	9.5	
June 23	do	3,336	6.16	9.0	
June 27	do	3,034	5.15	8.4	
June 29	do	10,582	8.05	21.9	
July 6	do	2,321	3.94	6.7	
July 12	do	2,062	3.08	5.9	
July 17	do	1,575	2.44	4.7	
July 22	do	2,223	3.68	6.5	
July 26	do	2,285	4.09	7.05	
July 31	do	3,088	5.12	8.6	
August 8	do	2,610	4.03	6.9	
August 12	do	2,550	4.40	7.0	
August 17	do	3,063	5.14	8.6	
August 23	do	2,700	4.69	7.5	
August 26	do	2,697	4.60	7.3	
August 31	do	2,279	4.08	6.2	
September 5	do	1,736	3.03	5.2	
September 12	do	2,930	4.46	8.15	
September 18	do	2,373	3.91	6.9	
September 24	do	1,769	3.40	5.4	
September 27	do	3,423	5.84	9.95	
September 30	do	2,682	5.08	7.95	
October 5	do	2,568	4.59	7.55	
October 9	do	2,502	4.41	7.25	
October 13	do	2,178	4.04	6.5	
October 18	do	1,715	3.36	5.1	
October 21	do	1,388	3.19	4.8	
October 26	do	1,268	3.06	4.4	
October 31	do	1,169	2.88	4.1	
November 5	do	1,258	2.35	4.0	
November 8	do	1,214	2.19	3.95	
November 12	do	1,256	2.40	4.0	
November 15	do	2,826	5.54	8.45	
November 20	do	2,181	4.77	6.8	
November 24	do	1,905	4.34	5.8	
November 29	do	1,442	3.81	4.9	
December 6	H. F. Collins	1,879	5.18	6.3	
December 11	do	1,578	4.04	6.1	
December 15	do	1,449	3.83	5.2	
December 19	do	1,426	3.77	5.3	
December 24	do	2,360	5.70	7.45	
December 27	do	1,884	4.79	6.2	

y gage height, in feet, of Rio Grande below mouth of Devils River, Tex., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	4.2	3.7	4.25	8.0	6.25	6.35	10.7	7.85	5.65	7.2	4.1	4.65
.....	4.0	3.65	4.35	7.1	5.85	6.7	10.7	7.6	5.5	7.75	4.1	4.6
.....	3.95	3.6	4.4	5.5	5.75	6.5	10.1	7.6	5.5	9.0	4.15	4.5
.....	3.9	3.55	4.4	5.05	5.7	6.55	7.25	7.35	5.4	8.45	4.1	4.5
.....	3.9	3.5	4.45	4.85	5.7	6.6	7.15	7.0	5.3	7.65	4.0	5.95
.....	3.9	3.55	4.75	4.65	5.8	6.65	6.75	6.95	5.1	6.95	4.05	6.4
.....	3.85	3.65	4.7	4.55	5.85	6.85	6.35	6.9	5.0	7.0	3.9	6.65
.....	3.85	3.65	5.35	4.5	5.9	7.1	6.3	7.0	5.2	7.7	3.95	6.6
.....	3.8	3.7	5.65	4.5	5.9	7.55	6.2	7.1	5.6	7.25	3.95	6.15
.....	3.8	3.7	5.95	4.5	7.15	7.5	5.8	7.3	7.0	7.05	4.0	6.15
.....	3.75	3.7	5.0	4.5	5.8	7.55	5.3	7.5	9.7	7.0	4.05	6.05
.....	3.75	3.7	4.9	4.5	5.7	8.1	5.5	6.85	8.35	6.8	4.0	5.55
.....	3.7	3.7	5.3	4.5	5.7	8.65	4.95	8.95	7.6	6.4	4.1	5.65
.....	3.7	3.65	5.35	4.4	5.95	9.0	4.9	8.65	7.95	6.0	5.55	5.35
.....	3.7	3.65	6.3	4.3	6.1	9.45	4.75	7.55	7.4	5.9	8.3	5.25
.....	3.65	3.65	6.2	4.3	6.05	9.7	4.65	7.75	7.2	5.3	7.1	5.45
.....	3.6	3.6	5.9	4.25	5.95	9.5	4.7	8.55	6.9	5.1	6.6	5.9
.....	3.6	3.6	5.95	4.15	5.95	9.6	5.4	8.25	6.9	5.05	6.7	5.6
.....	3.6	3.6	5.9	4.0	5.9	9.55	5.25	8.3	6.95	4.95	6.75	5.8
.....	3.6	3.6	5.9	4.0	5.9	9.7	6.5	8.75	6.75	4.95	6.75	7.35
.....	3.6	3.65	6.0	4.0	5.9	9.7	6.2	9.1	5.85	4.85	6.65	7.25
.....	3.6	4.0	6.15	4.25	5.9	9.2	6.5	8.45	5.5	4.75	6.55	7.0
.....	3.75	4.4	6.05	4.45	5.95	8.8	6.9	7.3	5.5	4.7	6.1	6.65
.....	3.85	4.4	5.85	7.7	6.15	8.6	7.0	6.95	5.35	4.6	5.65	7.1
.....	3.9	4.4	5.65	5.95	7.25	8.6	7.9	7.1	6.65	4.5	5.35	7.15
.....	3.9	4.4	5.55	5.3	6.3	8.55	7.1	7.45	8.75	4.45	5.25	6.6
.....	3.9	4.4	5.45	4.95	6.1	8.4	7.5	7.7	10.2	4.35	5.15	6.15
.....	3.85	4.4	5.4	4.9	6.05	10.3	7.8	7.35	10.7	4.25	5.0	5.95
.....	3.8	.....	5.35	5.0	6.1	21.1	8.5	6.9	8.7	4.2	4.95	5.75
.....	3.75	.....	5.15	6.7	6.1	9.65	8.7	6.35	7.8	4.15	4.8	5.55
.....	3.7	.....	5.05	.....	6.3	.....	8.5	6.1	.....	4.1	.....	5.4

Daily discharge, in second-feet, of Rio Grande below mouth of Devils River, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2,730	2,220	3,240	10,900	6,230	8,040	29,140	13,470	7,060	10,300	3,320	4,700
2	2,590	2,140	3,340	8,200	5,530	8,070	29,140	12,700	6,460	12,700	3,280	4,580
3	2,550	2,060	3,370	5,400	5,360	8,250	26,140	12,700	6,460	18,450	3,330	4,280
4	a2,520	a2,030	3,330	4,630	5,270	8,280	11,890	11,920	6,050	15,920	3,190	4,200
5	2,520	2,000	3,360	4,290	a5,270	8,310	11,390	10,840	a5,650	a12,180	a2,950	8,670
6	2,520	2,030	3,740	a3,950	5,600	a8,430	a9,390	10,680	4,950	10,280	2,980	a10,080
7	2,480	2,030	a3,630	3,940	5,800	9,380	7,910	10,530	4,750	10,400	2,630	10,280
8	2,480	2,090	4,700	4,030	6,010	10,570	7,740	a10,830	5,150	12,380	a2,660	9,530
9	2,440	a2,120	5,300	4,220	a6,090	12,710	7,390	11,130	5,950	a11,030	2,720	7,630
10	a2,440	2,120	5,900	a4,400	9,010	a12,470	6,130	11,730	9,450	10,440	2,880	7,090
11	2,350	2,120	4,000	4,400	5,640	12,550	5,080	12,330	20,600	10,290	3,040	a6,290
12	2,350	2,120	3,870	4,400	5,380	13,500	a5,500	a10,790	a13,860	9,700	a3,010	5,190
13	a2,260	a2,120	4,380	4,400	a5,390	14,460	4,350	17,150	11,400	a8,590	3,210	5,960
14	2,260	2,110	a4,500	a4,170	6,120	15,060	4,250	15,950	12,450	7,720	6,960	5,530
15	2,260	2,100	6,940	3,920	6,610	a15,960	3,940	12,770	10,800	7,510	a15,210	a5,690
16	2,220	2,210	6,870	3,920	6,600	18,140	3,730	13,330	10,200	6,200	11,340	6,170
17	2,190	a2,200	6,310	3,790	6,460	19,720	a3,840	a15,600	9,280	5,770	9,960	7,470
18	a2,190	2,200	a6,600	3,540	a6,570	20,100	5,530	14,770	a9,280	a5,670	10,180	6,320
19	2,160	2,200	6,480	a3,150	6,600	a21,080	5,170	14,910	9,430	5,230	10,290	7,250
20	2,130	2,200	6,480	3,150	6,600	22,100	8,180	16,350	8,960	4,980	a10,290	13,050
21	a2,100	2,240	6,720	3,150	a6,600	22,520	7,460	17,750	7,000	a4,530	10,070	12,620
22	2,100	a2,690	a7,090	a3,380	6,600	20,940	a8,180	15,330	6,240	4,360	9,860	11,750
23	2,250	3,490	6,520	3,650	6,700	a19,760	9,030	a12,100	6,240	4,290	8,900	10,470
24	2,350	3,490	5,720	16,000	7,110	18,330	9,240	11,420	a5,920	4,150	a7,800	a12,170
25	2,410	3,490	4,930	5,980	9,860	17,700	12,740	11,850	9,870	4,010	6,870	12,350
26	a2,410	3,490	a4,410	a4,800	a7,460	16,860	a9,550	a12,850	16,340	a3,940	6,560	10,440
27	2,410	3,490	4,240	4,310	6,960	a15,630	11,220	13,560	a21,000	3,790	6,250	a8,860
28	2,360	a3,490	4,160	4,240	6,840	25,100	12,460	12,560	23,500	3,620	5,790	8,150
29	2,310	.....	4,080	4,380	6,960	a80,350	15,380	11,280	16,020	3,540	a5,640	7,520
30	2,260	.....	3,750	a7,020	6,960	21,900	16,210	9,720	a13,140	3,450	5,290	6,870
31	a2,220	.....	a3,590	.....	a7,760	.....	a15,390	a9,000	.....	a3,370	.....	6,350

a Meter measurements.

Estimated monthly discharge of Rio Grande below mouth of Devils River, Tex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	2,730	2,100	2,349	144,436
February	3,490	2,000	2,443	135,669
March	7,080	3,240	4,888	300,575
April	10,900	3,150	4,790	285,045
May	9,860	5,270	6,515	400,582
June	80,350	8,040	17,572	1,045,636
July	29,140	3,730	10,409	640,046
August	17,750	9,000	12,835	789,223
September	23,500	4,750	10,115	601,904
October	18,450	3,370	7,722	474,823
November	15,210	2,630	6,216	369,858
December	13,060	4,280	7,984	490,888
The year	80,350	2,000	7,820	5,678,690

RIO GRANDE AT EAGLE PASS, TEX.

on was established in April, 1900, by the International (Water) Boundary Com-
is a half mile above the highway bridge between Eagle Pass, Tex., and Ciudad
z, Mexico, and about 540 miles below El Paso.
is practically straight for 1 mile above the station. Below it curves slowly to
about half a mile and then swings as slowly to the left. The right bank is
osit with a bottom back of it about 1,500 feet wide, which begins to overflow
ht 22 feet. The left bank is shale rock rising abruptly from the river. The
ream is shifting sand. At low water the depth is considerable and the velocity

measurements are made by means of a cable, car, tagged wire, and guy wire.
oint for soundings is the pole supporting the cable on the left bank.
up to 10.5 feet is a vertical staff bolted to a shale cliff. Above 10.5 feet, it is
l spiked to posts set in the shale. The highest recorded flood reached gage
feet, and occurred at midnight, June 29, 1905. The range between high and
33 feet. The bench mark is the top of a nail driven into the shale at the gage;
0.40 feet above the datum of the gage.
vations during 1905 were made under the direction of the United States section
national (Water) Boundary Commission. The hydrographer is J. K. Wilson,
reader Robert Boubel.
on in regard to this station is contained in the following publications of the
es Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

: WS 50, pp 365-366; 66, p 81; 84, p 158; 99, p 341; 132, p 88.
WS 50, p 366; 66, pp 81-82; 84, pp 158-159; 99, pp 341-344; 132, pp 88-91.
nean daily: WS 132, p 93.
nonthly: Ann 22, IV, p 357; WS 75, p 162; 84, p 160; 99, p 345; 132, p 94.
s: WS 50, p 366; 66, p 82; 99, p 344; 132, p 92.
1: WS 75, p 163.

Discharge measurements of Rio Grande at Eagle Pass, Tex., in 1905.

Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
J. K. Wilson	2,609	1.68	3.3	4,373
do	2,557	1.58	3.1	4,048
do	2,464	1.31	3.1	3,221
do	2,498	1.26	3.1	3,158
do	2,464	1.37	3.0	3,370
do	2,479	1.38	2.8	3,416
do	2,467	1.32	2.8	3,259
do	2,473	1.40	2.95	3,462
do	2,512	1.33	3.1	3,390
do	2,530	1.28	3.0	3,229
do	2,472	1.27	2.7	3,131
do	2,444	1.41	2.9	3,452
do	2,499	1.30	2.8	3,254
do	2,450	1.32	2.8	3,239
do	2,484	1.29	2.8	3,213
do	2,529	1.59	3.25	4,024
do	2,551	1.62	3.2	4,126
do	2,548	1.63	3.2	4,143
do	2,657	1.69	3.4	4,498
do	2,947	2.42	4.1	7,126
do	3,729	4.25	5.4	15,851
do	2,931	2.53	4.0	7,406

Discharge measurements of Rio Grande at Eagle Pass, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	D cha
		Square feet.	*Feet per second.*	*Feet.*	*Sec fe*
March 16	J. K. Wilson	3,600	4.15	5.1	1
March 19	do	2,965	3.00	4.6	
March 23	do	2,982	3.09	4.7	
March 27	do	2,893	2.37	4.15	
March 31	do	2,823	2.38	4.0	
April 1	do	3,695	3.66	5.5	
April 2	do	4,270	6.34	6.75	
April 6	do	2,955	1.96	3.8	
April 10	do	2,611	1.99	3.6	
April 13	do	2,576	2.04	3.7	
April 17	do	2,535	1.98	3.5	
April 20	do	2,483	1.80	3.35	
April 24	do	3,817	4.82	6.4	
April 27	do	2,622	2.43	4.0	
April 30	do	2,974	2.79	4.25	
May 4	do	2,827	2.99	4.4	
May 8	do	2,791	2.93	4.5	
May 11	do	2,767	2.85	4.5	
May 15	do	3,119	3.20	4.9	
May 18	do	2,758	3.02	4.4	
May 21	do	3,038	3.26	4.5	
May 25	do	3,109	3.66	5.05	
May 28	do	3,062	3.97	5.25	
May 31	do	3,093	3.74	4.8	
June 3	do	3,116	3.40	5.1	
June 7	do	3,389	3.36	5.05	
June 10	do	3,573	4.48	5.95	
June 13	do	3,727	4.95	6.35	
June 17	do	4,326	5.54	7.4	
June 20	do	4,255	5.13	7.2	
June 23	do	4,206	5.01	7.1	
June 27	do	4,269	4.58	6.9	
July 10	do	4,533	2.76	4.8	
July 14	do	3,918	1.89	4.0	
July 17	do	3,837	1.88	4.0	
July 21	do	4,183	2.65	5.0	
July 25	do	3,977	2.08	4.3	
July 28	do	4,061	2.91	5.25	
July 31	do	4,401	3.99	6.7	
August 4	do	3,874	3.73	6.0	
August 7	do	4,052	3.52	5.4	
August 10	do	3,816	3.53	5.6	
August 16	do	3,773	3.95	5.7	
August 19	do	4,011	3.99	6.0	
August 23	do	4,052	4.20	6.0	
August 26	do	3,723	3.63	5.5	
August 29	do	3,665	3.71	5.4	
August 31	do	3,607	2.99	4.8	
September 4	do	3,371	2.47	4.4	
September 7	do	3,099	2.14	3.8	
September 11	Pedro Rosales	3,916	3.89	5.9	
September 14	do	3,663	3.92	5.7	
September 19	do	3,671	3.45	5.55	

rge measurements of Rio Grande at Eagle Pass, Tex., in 1905—Continued.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
	Pedro Rosales	3,251	2.77	4.55	9,008
	do	2,904	2.75	4.0	7,991
	do	4,610	6.69	7.85	30,834
	do	4,980	6.97	8.3	34,695
	do	3,490	4.16	5.9	14,515
	do	4,009	4.53	6.35	18,172
	J. K. Wilson	3,939	4.75	6.3	18,728
	do	2,733	2.55	3.9	6,973
	do	2,458	2.17	3.5	5,344
	do	2,377	2.00	3.3	4,752
	do	2,275	1.97	3.2	4,484
	do	2,252	1.99	3.0	4,472
	do	2,436	2.27	3.3	5,526
	do	2,310	2.00	2.9	4,622
	do	2,226	1.85	2.7	4,127
	do	3,254	3.70	5.0	12,039
	do	2,940	4.10	4.85	12,041
	do	3,954	3.73	4.9	14,756
	do	2,548	2.66	4.2	6,768
	do	2,420	2.57	3.7	6,216
	do	2,321	2.33	3.6	5,419
	do	2,510	2.17	3.3	5,438
	do	2,609	2.87	4.3	7,498
	do	2,629	2.39	3.8	6,273
	do	2,371	2.44	3.7	5,785
	do	2,367	2.36	3.6	5,584
	do	3,152	4.07	4.8	12,817
	do	4,011	4.05	4.95	16,242
	do	2,492	3.10	4.4	7,718
	do	2,631	2.40	3.85	6,327

Daily gage height, in feet, of Rio Grande at Eagle Pass, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	3.3	3.0	3.2	5.8	4.65	5.0	14.0	6.45	4.45	5.8	3.0	3.5
2	3.3	3.0	3.2	7.1	4.5	5.05	13.0	6.05	4.25	5.9	3.0	3.4
3	3.3	3.0	3.1	4.65	4.4	5.1	11.0	6.0	4.4	6.3	3.35	3.3
4	3.2	2.8	3.2	4.0	4.35	5.0	10.2	5.95	4.35	6.8	3.3	3.35
5	3.2	2.8	3.4	3.8	4.5	4.9	6.9	5.6	4.0	6.2	3.15	3.5
6	3.1	2.75	3.4	3.8	4.6	4.95	6.3	5.45	3.9	5.5	2.95	4.6
7	3.1	2.7	3.5	3.8	4.45	5.1	6.2	5.35	3.75	5.3	2.85	4.45
8	3.1	2.7	3.95	3.8	4.5	5.3	6.15	5.4	3.75	5.85	2.85	4.3
9	3.1	2.9	4.05	3.7	4.6	5.8	5.95	5.45	4.15	6.3	2.8	4.2
10	3.1	2.9	5.45	3.6	5.4	6.0	4.85	5.65	4.45	5.7	2.7	3.85
11	3.1	2.9	4.8	3.8	4.6	5.85	4.55	5.55	5.9	5.1	2.7	3.8
12	3.1	2.9	4.2	3.85	4.4	5.95	4.4	5.4	7.2	4.8	2.85	3.75
13	3.1	2.9	4.0	3.7	4.3	6.35	4.15	5.7	5.65	4.55	2.9	3.8
14	3.1	2.8	4.0	3.7	4.4	6.7	3.95	6.5	5.8	4.45	3.75	3.7
15	3.0	2.8	4.2	3.6	4.9	6.95	3.75	6.25	5.95	4.25	4.55	3.6
16	3.0	2.8	5.5	3.55	4.7	7.2	3.55	5.7	5.45	4.1	5.4	3.6
17	3.0	2.8	4.6	3.5	4.4	7.4	4.0	5.9	5.25	3.85	4.95	3.6
18	2.9	2.8	4.6	3.4	4.4	7.4	4.0	6.25	5.3	3.65	4.75	3.55
19	2.9	2.8	4.6	3.3	4.3	7.4	3.95	6.0	5.65	3.6	4.95	3.45
20	2.8	2.8	4.5	3.3	4.55	7.2	4.8	6.15	5.4	3.55	4.95	4.6
21	2.8	2.8	4.65	3.35	4.5	7.45	5.0	6.65	4.85	3.7	4.85	4.85
22	2.8	2.8	4.7	3.55	4.7	7.2	4.7	7.0	4.55	3.5	4.9	4.8
23	2.8	3.0	4.65	3.5	4.65	7.1	5.3	5.95	4.3	3.4	4.65	4.7
24	2.8	3.15	4.5	5.35	5.15	7.0	4.5	5.5	4.2	3.35	4.35	4.65
25	2.75	3.4	4.4	4.8	5.65	7.0	4.9	5.35	4.0	3.3	4.15	5.3
26	2.7	3.4	4.3	4.55	6.9	6.95	6.7	5.55	5.95	3.2	4.0	4.95
27	2.7	3.3	4.15	4.0	5.35	6.9	5.85	5.8	7.15	3.2	3.75	4.65
28	2.95	3.2	4.2	4.4	5.6	6.45	5.25	5.75	7.8	3.15	3.7	4.35
29	3.2	.....	4.1	4.05	5.0	16.8	5.65	5.3	8.1	3.1	3.6	4.2
30	3.1	.....	4.05	4.65	4.8	25.4	6.3	4.95	6.3	3.0	3.55	4.3
31	3.05	.....	4.0	.....	4.85	.....	6.7	4.75	.....	3.05	.....	3.85

Daily discharge, in second-feet, of Rio Grande at Eagle Pass, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	4,290	3,230	4,130	a15,200	9,450	11,650	75,500	16,460	8,640	14,010	4,470	5,350
2	4,330	3,230	4,130	a29,100	8,850	11,120	66,500	14,680	7,880	a14,510	4,470	5,280
3	a4,370	a3,230	3,950	9,000	8,450	a10,590	50,500	14,460	8,330	16,980	5,700	5,210
4	4,210	3,160	a4,140	6,390	a8,250	10,440	44,900	a14,210	a8,190	19,950	a5,530	a5,540
5	4,210	3,160	4,500	5,790	8,690	10,290	25,100	13,390	7,210	a17,420	5,190	5,850
6	4,050	3,140	a4,500	a5,790	8,970	10,740	21,500	13,570	6,930	14,120	4,740	8,120
7	a4,050	a3,130	4,750	5,790	8,160	a11,650	20,900	a14,000	a6,510	13,320	a4,500	7,810
8	3,840	3,130	6,530	5,790	a8,190	12,680	20,600	13,660	6,510	16,270	4,500	a7,500
9	3,630	3,450	a6,930	5,500	8,490	15,240	19,400	13,330	8,080	a18,730	4,370	7,260
0	3,420	3,450	a16,050	a5,210	12,500	a16,320	a12,830	a13,740	9,310	15,790	4,130	6,390
1	a3,220	a3,450	10,400	5,600	a8,300	15,410	10,930	13,390	a15,230	12,850	a4,130	a6,270
2	3,200	3,450	8,000	5,700	7,500	16,010	9,970	12,800	21,700	11,380	4,500	6,080
3	3,180	3,450	7,400	a5,250	7,100	a18,450	8,370	14,450	14,120	10,160	4,620	6,080
4	a3,160	a3,250	a7,400	5,250	7,500	20,300	a7,170	18,610	a14,840	9,670	7,170	a5,790
5	3,160	3,250	8,000	5,130	a9,990	21,620	6,480	17,510	15,400	8,690	a10,240	5,590
6	3,260	3,240	a16,550	5,070	9,330	22,930	5,710	a14,910	12,720	7,950	13,840	5,590
7	a3,370	a3,240	8,900	a5,010	8,340	a23,980	a7,210	15,640	11,540	a6,770	12,240	5,580
8	3,330	3,240	8,900	4,650	a8,340	23,980	7,210	17,250	11,610	5,960	a11,640	a5,480
9	3,390	3,230	a8,900	4,300	8,330	23,980	7,020	a16,000	a12,180	5,750	13,070	5,280
0	3,350	3,220	8,580	a4,300	9,720	a21,830	10,300	17,000	12,130	a5,550	13,700	11,610
1	a3,420	a3,210	9,070	4,480	a9,900	23,690	a11,080	19,750	10,110	6,140	13,930	a13,020
2	3,360	3,210	9,230	5,280	10,440	21,830	9,870	21,750	a9,010	5,340	a14,760	12,820
3	3,310	3,570	a9,010	5,080	10,310	a21,090	12,280	a16,660	8,550	5,050	12,130	12,420
4	a3,260	a3,840	8,360	a12,100	11,770	20,320	9,060	13,510	8,370	a4,900	9,100	12,220
5	3,210	4,320	7,930	9,570	a14,500	20,320	a10,500	12,760	a7,990	4,750	a6,720	17,300
6	3,160	4,320	7,500	8,570	20,900	19,940	17,600	a13,760	15,500	4,480	6,550	a16,240
7	3,160	4,220	a6,850	a6,370	12,900	a19,590	14,200	15,210	25,100	a4,480	6,280	11,590
8	a3,460	a4,130	6,970	7,970	a14,000	17,300	a11,810	15,160	a30,400	4,480	a6,220	a7,600
9	3,460	.....	6,840	6,570	11,830	166,600	13,400	a13,380	a33,000	4,480	5,670	7,220
0	3,470	.....	6,780	a9,900	11,580	238,300	15,980	11,480	17,200	4,350	a5,270	7,470
1	a3,340	.....	a6,720	.....	a11,780	.....	a17,580	a10,540	.....	a4,600	.....	a6,330

a Meter measurements.

Estimated monthly discharge of Rio Grande at Eagle Pass, Tex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
nuary	4,370	3,160	3,542	217,805
bruary	4,320	3,130	3,434	190,711
rch	16,550	3,950	7,674	471,868
ril	29,100	4,300	7,324	435,788
y	20,900	7,100	10,139	623,445
ne	238,300	10,290	29,939	1,781,474
ly	75,500	5,710	18,757	1,153,309
gust	21,750	10,540	14,936	918,387
ptember	33,000	6,510	12,810	762,228
tober	19,950	4,350	9,641	592,820
vember	14,760	4,130	7,646	454,968
cember	17,300	5,210	8,125	499,597
The year	238,300	3,130	11,164	8,102,400

RIO GRANDE NEAR LAREDO, TEX.

This station was established in April, 1900, by the International (Water) Boundary C mission. It was intended to measure the river from the highway bridge connecting Lar with Nuevo Laredo, Tamaulipas, and the gage was established on the right bank just ab the bridge. Measurements were kept up by the Mexican section of the Commission for months, but the results were so conflicting that the station was abandoned. In July, 1 a cable station was established by the Commission some 2 miles above Nuevo Laredo, cr ing to the United States military reservation of Fort McIntosh, the cable landing just be the pump house. The station is about 670 miles below El Paso.

The river at the new section is nearly straight for one-half mile above and below cable. The right bank is alluvial deposit, but is above high water. The left bank is talus of a shale bluff going well above high water. The bed is shifting sand.

Discharge measurements are made by means of a cable, car, and guy wire. The ini point for soundings is the cable support on the right bank.

The gage is an inclined scantling fastened to posts and trees. Low water is about 1 on the gage. The highest flood recorded is 32.2 feet, on the night of June 30, 1905.

The observations during 1905 were made under the direction of the Mexican sectio the International (Water) Boundary Commission.

Discharge measurements of Rio Grande near Laredo, Tex., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di char
		Square feet.	*Feet per second.*	*Feet.*	*Seco fe*
January 1	Luis Varela	2,183	1.84	2.3	
January 5	do	2,015	1.71	2.2	
January 10	do	1,978	1.69	2.2	
January 17	do	1,940	1.60	1.8	
January 21	do	1,942	1.56	1.7	
January 24	do	1,977	1.59	1.65	
January 28	do	1,946	1.52	1.6	
February 5	do	1,958	1.56	1.6	
February 11	do	1,831	1.53	1.5	
February 15	do	1,826	1.56	1.5	
February 18	do	1,840	1.60	1.5	
February 23	do	1,827	1.57	1.5	
February 27	do	1,857	1.58	1.5	
March 1	do	1,815	1.58	1.5	
March 6	do	2,010	1.69	2.2	
March 10	do	2,231	2.32	3.1	
March 15	do	2,250	2.18	3.2	
March 17	do	3,054	3.81	4.95	1
March 24	do	3,550	3.72	3.9	
March 28	do	2,190	2.23	3.0	
May 1[a]	do	2,288	2.33	3.2	
May 7	do	2,343	2.16	3.3	
May 13	do	2,472	2.25	3.5	
May 19	do	2,330	2.24	3.6	
May 21	do	2,461	1.79	3.0	
May 24	do	2,420	2.28	3.3	
May 25[b]	do	2,521	2.40	4.2	
May 27	do	3,800	4.54	7.55	1
June 10	do	2,806	4.86	5.8	1
June 12	do	2,785	3.85	5.0	1
June 14	do	2,677	5.18	6.0	1

[a] The record of measurements made during April was lost in a cyclone which occurred April 2
[b] Gage height uncertain.

scharge measurements of Rio Grande near Laredo, Tex., in 1905—Continued.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
.....	Luis Varela	2,852	5.18	7.0	14,760
.....	....do	3,229	5.39	7.75	17,407
.....	....do	2,701	5.19	6.6	14,005
.....	....do	5,370	5.73	12.2	30,749
.....	....do	4,944	5.67	11.9	28,044
.....	....do	2,622	3.19	6.3	8,369
.....	....do	2,554	2.59	5.8	6,603
.....	....do	2,358	2.56	5.5	6,025
.....	....do	2,322	2.48	5.4	5,751
.....	....do	2,664	3.70	7.2	9,854
.....	....do	2,538	2.53	5.0	6,426
.....	....do	3,787	5.70	8.2	21,602
.....	....do	3,809	3.23	6.45	12,318
.....	....do	3,648	3.86	6.6	14,091
.....	....do	3,647	3.29	5.4	11,993
.....	....do	3,179	3.74	6.2	11,893
.....	....do	3,490	3.66	6.5	12,777
r 2...	....do	3,017	2.94	5.1	8,867
r 7...	....do	3,212	2.69	4.2	8,627
r 13...	....do	4,723	4.96	8.35	23,416
r 16...	....do	4,314	3.76	7.0	16,227
r 22...	....do	3,102	3.31	5.8	10,256
r 27...	....do	3,315	3.61	6.55	11,981
r 29...	....do	4,634	5.02	9.9	23,270
.....	....do	3,321	4.82	7.0	15,998
).....	....do	3,410	5.14	7.25	17,534
7.....	....do	2,514	2.97	4.85	7,456
3.....	....do	2,456	2.89	4.8	7,101
3.....	....do	2,302	2.42	4.3	5,574
).....	....do	2,247	2.06	3.9	4,627
·3.....	....do	2,104	2.11	3.8	4,438
·12...	....do	2,028	1.81	3.1	3,671
·15...	....do	2,135	2.23	3.9	4,760
·17...	....do	3,012	4.60	6.65	13,855
·24...	....do	2,620	3.75	5.5	9,823
·30...	....do	2,247	2.32	4.4	5,221
3.....	....do	2,145	2.42	4.3	5,201
8.....	....do	2,709	2.51	5.3	6,807
14....	....do	2,439	2.80	4.7	6,823
16....	....do	2,239	2.48	4.5	5,549
22....	....do	2,941	3.34	5.8	9,812
26....	....do	2,816	4.19	6.2	11,793

Daily gage height, in feet, of Rio Grande near Laredo, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	2.3	1.6	1.5	2.9	3.55	4.5	18.6	7.25	5.6	7.2	3.9	
2	2.3	1.6	1.6	4.25	3.6	4.15	11.2	7.05	5.15	6.65	3.95	
3	2.25	1.6	1.7	6.65	3.75	4.2	10.5	7.05	4.8	6.5	3.7	
4	2.2	1.6	1.75	3.2	3.55	4.2	9.8	7.15	4.4	7.4	4.2	
5	2.15	1.65	1.9	3.2	3.5	4.45	9.3	6.85	4.65	8.2	4.05	
6	2.0	1.7	2.2	3.0	3.35	4.5	8.1	6.45	4.8	6.8	3.9	
7	2.0	1.7	2.3	2.9	3.3	4.45	7.75	5.65	4.55	6.35	3.85	
8	2.05	1.7	2.45	2.9	3.65	3.75	7.5	5.1	4.6	6.15	3.6	
9	2.2	1.7	2.5	2.8	3.55	4.25	7.25	7.05	4.7	6.55	3.35	
10	2.2	1.6	2.8	2.6	3.7	5.2	7.05	7.0	4.55	7.15	3.55	
11	2.15	1.5	4.1	3.15	3.85	5.0	6.8	8.25	5.1	6.9	3.5	
12	2.0	1.5	3.3	2.9	3.85	5.0	6.3	7.5	6.9	5.95	3.05	
13	1.9	1.5	3.3	2.8	3.55	5.05	6.25	6.85	7.9	5.55	3.25	
14	1.9	1.5	3.25	2.6	4.1	6.0	6.05	6.7	7.25	5.35	4.0	
15	1.9	1.5	3.2	2.6	5.1	6.1	5.95	7.15	7.25	5.2	3.95	
16	1.85	1.5	4.45	2.5	4.1	6.7	5.75	6.8	7.0	5.0	5.15	
17	1.8	1.5	4.65	2.45	3.65	7.3	5.6	6.8	6.65	4.9	6.8	
18	1.8	1.5	3.65	2.4	3.7	7.0	5.55	7.2	6.2	4.75	6.2	
19	1.8	1.5	3.0	2.3	3.45	7.45	5.6	7.15	6.1	4.55	6.35	
20	1.7	1.5	3.5	2.25	3.05	7.45	5.4	6.25	6.65	4.55	5.9	
21	1.7	1.5	3.7	2.25	3.15	6.95	5.0	5.6	6.35	4.6	6.0	
22	1.7	1.5	3.7	2.45	5.0	7.7	5.3	6.1	5.6	4.4	5.85	
23	1.6	1.5	3.85	2.95	3.75	7.25	5.55	5.55	5.1	4.4	5.45	
24	1.6	1.5	3.85	2.9	3.85	7.4	5.85	5.25	5.0	4.5	5.45	
25	1.6	1.5	3.5	4.25	4.5	6.55	5.95	5.2	4.75	4.45	5.1	
26	1.6	1.5	3.5	4.1	5.6	6.55	6.1	5.1	4.85	4.25	4.9	
27	1.6	1.5	3.35	3.55	7.1	6.7	7.2	6.1	6.6	4.1	4.7	
28	1.6	1.5	3.1	3.2	6.1	6.55	7.4	6.15	9.2	3.9	4.65	
29	1.6	.....	3.0	3.05	5.65	6.35	7.55	6.45	9.55	3.95	4.55	
30	1.6	.....	3.0	3.35	4.3	23.0	7.55	5.45	8.75	3.85	4.45	
31	1.6	.....	2.95	.....	4.0	.....	7.8	5.3	.....	3.95	.....	

RIO GRANDE NEAR ROMA, TEX.

This station was established in 1900 by the International (Water) Boundary Comm sion. It is near Roma, Tex., 775 miles by river below El Paso.

The river is straight for 1 mile above and one-half mile below the station. The r bank is alluvial deposit and overflows in high water for a width of 250 feet. The over section is thickly covered with mesquite brush. The left bank is of hard material and not overflow. The bottom is shifting sand.

Discharge measurements are made by means of a cable, car, and guy wire. The in point for soundings is the cable support on the left bank.

The gage is an inclined scantling spiked to posts and trees. Low water is 1 foot on g and the highest recorded flood, September 16, 1904, marked 26.0 feet on gage.

The observations during 1905 were made under the direction of the Mexican sectio the International (Water) Boundary Commission.

ischarge measurements of Rio Grande near Roma, Tex., in 1905.

Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
H. P. Guerra	3,026	2.13	3.8	6,452
....do	2,811	2.01	3.5	5,644
....do	2,042	2.05	3.1	4,193
....do	1,815	2.06	2.9	3,740
....do	1,854	2.14	3.0	3,959
....do	1,704	2.07	2.8	3,532
....do	1,693	1.93	2.7	3,262
....do	1,644	1.88	2.5	3,080
....do	1,684	1.90	2.6	3,205
....do	1,653	2.12	2.6	3,512
....do	1,690	1.83	2.5	3,100
....do	1,758	2.07	2.7	3,642
....do	1,590	2.05	2.5	3,257
....do	1,912	2.23	3.2	4,263
....do	2,332	2.44	4.0	5,689
....do	3,683	4.24	7.05	15,600
....do	2,277	3.39	4.5	7,716
....do	2,748	4.49	5.4	12,331
....do	2,324	3.47	4.6	8,066
....do	3,251	4.40	6.7	14,303
....do	2,040	3.34	4.1	6,811
....do	1,929	2.73	3.8	5,260
....do	2,009	2.87	3.9	5,760
....do	2,242	3.07	4.4	6,876
....do	2,801	4.43	5.6	12,422
....do	2,487	3.62	4.8	8,991
....do	2,467	3.05	4.6	7,528
....do	2,575	3.05	5.0	7,858
....do	3,097	4.11	6.1	12,740
....do	2,786	3.87	5.6	10,770
....do	2,736	3.88	5.55	10,628
....do	3,606	4.80	7.4	17,312
....do	3,385	4.56	6.9	15,450
....do	3,584	4.64	7.3	16,624
....do	2,836	3.72	5.6	10,546
....do	3,290	3.74	6.2	12,308
....do	3,645	4.25	6.9	15,481
....do	4,033	4.66	7.8	18,803
....do	4,252	4.93	8.3	20,966
....do	4,557	5.26	9.0	23,973
....do	8,374	5.14	17.0	43,041
....do	5,682	5.22	11.5	29,642
....do	4,368	5.17	8.7	22,568
....do	3,923	3.67	7.3	14,387
....do	4,004	2.82	6.1	11,289
....do	3,850	2.74	5.7	10,531
....do	3,685	2.61	5.3	9,633
....do	3,155	3.94	6.2	12,437
....do	3,299	4.13	6.6	13,641
....do	4,058	4.38	7.7	17,767
....do	3,796	3.76	7.2	14,267
....do	3,433	4.05	6.9	13,912
....do	4,143	4.61	7.9	19,116

Discharge measurements of Rio Grande near Roma, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di char
		Square feet.	*Feet per second.*	*Feet.*	*Seco fe*
September 5	H. F. Guerra	2,902	3.11	5.2	9
September 8	do	2,751	3.01	4.9	8
September 13	do	4,083	4.60	7.8	1
September 19	do	6,224	5.38	12.7	3
September 21	do	4,933	4.82	9.7	2
September 23	do	3,763	4.42	7.1	1
September 29	do	4,246	4.59	8.1	1
October 5	do	4,482	4.74	8.5	2
October 7	do	3,816	4.42	7.2	1
October 9	do	3,425	4.11	6.8	1
October 13	do	3,294	3.63	6.1	1
October 17	do	2,981	3.37	5.5	1
October 20	do	2,836	2.60	5.1	
October 24	do	2,530	2.64	4.5	
November 7	do	2,334	2.52	4.4	
November 10	do	2,138	2.05	4.0	
November 17	do	3,031	4.07	6.0	1
November 20	do	3,294	4.01	6.6	1
November 25	do	2,814	3.51	5.5	
November 28	do	2,618	3.29	5.0	
December 9	do	2,706	3.47	5.3	
December 11	do	2,557	3.08	4.9	
December 14	do	2,358	3.19	4.7	
December 20	do	2,244	3.13	4.4	
December 23	do	2,938	3.53	5.8	1
December 28	do	2,891	3.29	5.5	

Daily gage height, in feet, of Rio Grande near Roma, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	3.8	3.0	2.7	4.1	5.3	6.35	17.7	7.65	5.8	8.2	4.75	4.75
2	3.8	3.0	3.05	4.35	4.6	7.0	22.3	7.75	5.55	6.9	4.65	4.7
3	3.8	2.85	3.15	4.8	4.7	6.35	16.55	7.35	5.35	6.6	4.55	4.65
4	3.7	2.8	2.9	6.75	4.75	6.3	13.75	7.1	5.05	7.15	4.45	4.6
5	3.65	2.7	3.2	4.75	4.7	5.85	10.9	6.9	5.2	8.5	4.6	4.55
6	3.55	2.7	3.85	4.2	4.7	5.6	9.15	6.75	5.4	7.85	4.55	4.7
7	3.45	2.6	6.35	4.05	4.75	5.65	8.55	6.65	5.0	7.05	4.45	4.95
8	3.4	2.55	4.7	3.9	4.8	5.55	7.9	6.35	4.9	6.5	4.15	5.45
9	3.4	2.5	3.65	4.0	5.1	5.6	7.35	6.1	4.8	6.55	4.3	5.35
10	3.3	2.6	3.45	3.9	5.0	5.7	7.15	6.4	4.8	7.1	4.05	5.25
11	3.3	2.6	3.75	3.85	5.05	6.15	6.95	6.5	5.1	7.2	4.0	5.05
12	3.25	2.6	4.5	3.9	6.0	6.2	6.7	6.6	5.45	6.6	4.0	4.9
13	3.2	2.6	4.4	3.9	5.15	6.15	6.45	6.5	7.35	6.2	4.05	4.8
14	3.15	2.6	3.95	4.1	4.8	6.4	6.2	6.35	7.45	5.85	4.0	4.75
15	3.05	2.5	3.9	4.25	5.5	6.75	5.95	7.7	6.4	5.65	4.3	4.65
16	3.0	2.5	3.9	4.0	5.7	6.95	5.75	7.35	6.5	5.55	4.25	4.6
17	2.9	2.5	4.85	3.9	5.05	7.4	5.8	7.05	6.55	5.5	5.55	4.5
18	2.9	2.55	5.25	3.95	4.75	7.55	6.4	6.7	6.1	5.3	6.15	4.5
19	2.95	2.95	4.45	4.0	4.55	7.75	5.65	7.2	11.3	5.3	5.6	4.5
20	3.0	2.75	4.35	3.95	4.45	7.7	5.45	6.9	10.1	5.55	6.45	4.45
21	2.9	2.6	4.4	3.9	4.5	7.75	5.6	6.9	9.3	5.6	5.9	4.4
22	2.9	2.6	4.55	3.9	4.5	8.15	6.9	6.95	8.7	5.8	5.9	5.1
23	2.8	2.6	4.6	3.95	5.15	8.15	7.2	7.55	7.5	5.1	5.8	5.7
24	2.8	2.45	4.5	4.5	4.65	7.95	6.95	7.7	5.9	4.5	5.75	5.55
25	2.8	2.4	4.5	4.35	4.8	7.85	6.85	6.7	5.65	4.35	5.55	5.6
26	2.8	2.35	4.4	4.85	6.75	7.65	7.15	6.4	5.55	4.5	5.35	5.75
27	2.7	2.3	4.4	4.95	6.4	8.8	7.2	6.4	5.45	4.4	5.05	5.7
28	2.85	2.15	4.4	4.65	6.8	8.35	7.65	6.25	6.4	4.45	4.95	5.55
29	2.9	.....	4.3	5.1	6.55	8.0	6.9	6.75	8.3	4.3	4.85	5.4
30	3.0	.....	4.2	5.8	7.3	8.25	6.85	6.45	8.9	4.2	4.8	5.15
31	3.0	.....	4.2	.....	6.5	.....	6.95	6.2	.....	4.3	.....	5.0

RIO GRANDE NEAR BROWNSVILLE, TEX.

This station was established in 1900 by the International (Water) Boundary Commission. It is about 1 mile above Brownsville, Tex., and in front of Matamoros, Tamaulipas, and 960 miles by river below El Paso.

Between Roma and Brownsville there are many lagoons (old river beds) and lakes which take river water during moderate floods, and a large area overflows quite deeply in larger floods. Much of this water returns slowly to the river as the flood subsides, so that the flow passes Brownsville more uniformly than it does Roma. Large quantities of water also leave the river entirely, reaching the Gulf of Mexico through channels remote from the Rio Grande Local run-off, however, keeps the total water at Brownsville well up toward the combined flow of the San Juan and the Rio Grande at Roma. The river is nearly straight for one-half mile above and below the station. Both banks are alluvial and are just about level with high water. The right bank is protected by piling. The bed of the stream is shifting sand.

Discharge measurements are made by means of a cable, car, and guy wire. The cable is so constructed that it can be lowered and raised. The initial point for soundings is the cable support on the right bank.

The gage is a vertical scantling fastened to one of the protection piles. High water is 13 feet on the gage, and low water is −1.0.

The observations during 1905 were made under the direction of the Mexican sectio the International (Water) Boundary Commission.

Discharge measurements of Rio Grande near Brownsville, Tex., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di cha
		Square feet.	*Feet per second.*	*Feet.*	*Sec fe*
January 2	P. Guerra	2,886	2.60	5.3	
January 6	do	2,712	2.59	4.7	
January 10	do	2,588	2.41	4.3	
January 14	do	2,531	2.34	4.1	
January 18	do	2,381	2.33	3.8	
January 22	do	2,318	2.32	3.5	
January 26	do	2,301	2.30	3.4	
January 30	do	2,247	2.16	3.2	
February 3	do	2,252	2.24	3.4	
February 7	do	2,276	2.29	3.5	
February 11	do	2,138	2.20	3.0	
February 16	do	2,112	2.17	2.9	
February 24	do	2,230	2.22	3.1	
February 27	do	2,122	2.17	2.8	
March 3	do	2,172	2.21	2.9	
March 7	do	2,283	2.30	3.5	
March 13	do	2,321	3.30	5.2	
March 17	do	2,468	3.41	5.7	
March 20	do	3,141	3.36	7.6	1
March 25	do	2,926	3.44	6.5	1
March 29	do	2,964	3.43	6.5	1
April 2	do	2,734	3.31	5.8	
April 6	do	4,010	4.55	9.25	1
April 11	do	2,835	2.19	5.1	
April 16	do	2,735	2.19	4.9	
April 24	do	2,535	2.03	4.0	
April 28	do	3,528	3.22	6.8	1
May 2	do	3,117	3.49	7.65	1
May 6	do	2,635	3.33	6.3	
May 10	do	2,524	3.18	6.0	
May 14	do	3,086	3.44	7.5	
May 18	do	4,015	3.27	7.9	
May 22	do	2,566	3.35	6.1	
May 26	do	3,575	3.12	6.8	
May 30	do	4,980	4.67	10.5	
June 3	do	5,282	4.60	11.2	
June 6	do	5,136	4.03	10.8	
June 11	do	4,268	3.65	8.4	
June 15	do	4,508	3.72	9.0	
June 20	do	5,516	4.42	11.7	
June 24	do	5,967	4.78	12.7	
June 28	do	5,716	4.63	12.2	
July 2	do	6,103	4.60	13.1	
July 6	do	6,274	4.65	13.5	
July 10	do	6,105	4.11	13.3	
July 12	do	5,148	3.64	11.0	
July 18	do	4,290	2.79		
July 22	do	4,521			
July 26	do	4,071			

arge measurements of Rio Grande near Brownsville, Tex., in 1905—Continued.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
	P. Guerra	4,899	3.73	11.65	18,275
	do	4,806	4.42	11.3	21,236
	do	4,561	4.03	10.5	18,382
	do	4,038	3.64	9.4	14,697
	do	4,118	3.68	9.6	15,135
	do	4,621	3.99	10.6	18,435
	do	4,723	4.11	10.8	19,390
	do	4,008	3.59	9.25	14,399
1	do	4,756	3.32	9.6	15,773
6	do	4,169	2.39	7.5	9,946
10	do	4,039	2.21	7.1	8,937
14	do	4,091	2.27	7.3	9,301
18	do	4,899	3.32	9.8	16,287
21	do	6,069	4.77	12.8	28,944
25	do	6,202	5.00	13.1	31,029
29	do	3,448	2.97	8.1	10,259
	do	5,260	4.39	12.8	23,081
	do	5,407	4.95	13.1	26,749
	do	4,714	3.55	11.3	16,714
	do	5,127	3.14	10.7	16,121
	do	4,416	2.30	8.1	10,171
	do	4,582	2.50	8.5	11,476
	do	3,627	1.88	6.5	6,802
2	do	3,622	2.03	6.1	7,338
6	do	3,407	3.22	7.9	10,956
8	do	3,462	3.38	8.1	11,697
14	do	3,827	2.15	6.7	8,237
18	do	3,630	2.16	6.5	7,833
22	do	4,972	4.02	10.1	20,002
26	do	3,607	3.74	8.7	13,500
29	do	3,272	3.37	7.9	11,011
3	do	3,724	2.41	6.6	8,970
8	do	3,453	2.21	6.3	7,638
12	do	3,216	3.27	7.8	10,506
17	do	3,813	2.46	6.9	9,394
21	do	3,596	2.16	6.3	7,767
25	do	3,460	3.32	8.0	11,487
29	do	4,025	3.56	8.6	14,349

Daily gage height, in feet, of Rio Grande near Brownsville, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	5.45	3.2	2.7	6.1	7.4	11.05	12.7	10.7	9.5	12.75	6.2	7.05
2	5.35	3.4	2.7	5.75	7.5	10.35	13.0	10.9	8.9	13.1	6.1	6.85
3	5.15	3.4	2.9	5.55	6.3	11.8	13.1	11.3	8.4	12.95	6.65	6.65
4	4.95	3.4	3.15	5.65	6.05	12.5	13.15	11.55	8.0	11.45	11.55	6.55
5	4.85	3.45	3.35	9.0	6.15	11.7	13.4	11.1	7.7	10.85	10.1	6.45
6	4.65	3.6	3.4	9.25	6.3	11.05	13.5	10.65	7.45	12.65	8.05	6.3
7	4.6	3.45	3.45	6.75	6.3	9.7	13.5	10.45	7.2	13.1	7.4	6.3
8	4.5	3.25	5.85	5.6	6.2	8.8	13.5	10.25	7.35	13.05	8.1	6.3
9	4.35	3.1	7.7	5.3	6.05	8.55	13.5	9.9	7.35	13.0	8.35	6.9
10	4.25	3.05	7.7	5.2	6.1	8.45	12.95	9.6	7.15	12.25	7.9	7.
11	4.25	2.95	6.0	5.15	6.45	8.4	11.65	9.4	6.95	11.25	7.45	8.
12	4.15	2.9	5.05	5.1	6.6	8.55	10.9	9.55	6.75	11.65	7.25	7.
13	4.25	2.9	5.1	5.0	6.5	8.9	10.6	9.65	6.75	11.55	6.95	7.
14	4.1	2.9	6.1	5.0	7.35	9.0	10.3	9.75	7.5	11.1	6.75	7
15	4.0	2.9	6.1	4.95	7.5	9.05	9.7	9.5	11.0	10.5	6.55	7
16	3.95	2.9	5.85	4.9	6.85	9.35	9.15	9.15	10.95	9.7	6.4	7
17	3.9	2.9	5.7	4.8	7.7	10.15	8.95	9.9	9.8	9.0	6.4	6.
18	3.8	2.9	5.7	4.75	7.75	10.7	8.75	10.95	9.75	8.65	6.5	6
19	3.8	2.9	6.95	4.65	6.6	11.35	10.45	10.5	9.55	8.4	8.95	6.
20	3.7	2.9	7.55	4.45	6.1	11.75	12.4	10.4	9.75	8.15	9.7	6
21	3.6	2.9	6.6	4.4	6.1	12.0	10.8	10.75	12.85	8.15	9.3	6.
22	3.5	3.0	6.15	4.25	6.1	12.05	9.05	10.5	13.05	8.95	10.15	6.
23	3.5	3.1	6.1	4.1	6.1	12.5	8.3	10.3	13.25	8.5	10.15	6.
24	3.5	3.1	6.35	4.05	6.1	12.7	9.2	10.7	13.4	8.5	9.4	7.
25	3.5	2.9	6.5	3.85	6.75	12.65	9.6	11.5	12.25	8.35	9.1	8.
26	3.4	2.9	6.65	3.8	6.8	12.3	9.3	11.65	9.75	7.6	8.8	7.
27	3.3	2.8	6.7	4.6	6.05	12.05	9.8	9.65	8.75	6.9	8.45	7.
28	3.2	2.8	6.65	6.55	9.4	12.3	10.4	9.15	8.35	6.65	8.05	8.
29	3.2	.....	6.5	6.55	9.75	12.75	11.7	8.6	8.1	6.45	7.75	8.
30	3.2	.....	6.35	6.1	10.4	12.8	11.4	9.2	8.0	6.35	7.3	8.
31	3.2	.....	6.15	.....	10.6	.....	10.9	9.7	.....	6.25	.....	7.

RIO SALADO NEAR GUERRERO, TAMAULIPAS, MEXICO.

This station was established in 1900 by the International (Water) Boundary Commissio The Salado is a torrential stream entering the Rio Grande from the Mexican side about miles below Laredo, or 730 miles by river below El Paso. The town of Guerrero is locat on the Salado some 4 miles above its mouth, and the gaging station is 2 miles above t town.

The river is a series of pools and rapids. The best pool available was chosen for the s tion. The river curves to the left both above and below the cable. The banks are sa clay, not subject to erosion. The bottom is mud. In low water the river is measured wading among rocks below the station.

Discharge measurements are made by means of a cable, car, and guy wire. The ini point for soundings is the cable support on the left bank.

The gage is an inclined scantling fastened to posts sunk in the bank. Low water flow) is −1 on the gage. The highest recorded flood, on June 16, 1903, gave 17.7 on gage

The observations during 1905 were made under the direction of the Mexican section of International (Water) Boundary Commission.

Discharge measurements of Rio Salado near Guerrero, Tamaulipas, Mexico, in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
January 3	D. de Lassaulx	1,789	0.51	3.6	916
January 7	do	1,766	.49	3.5	871
January 11	do	1,747	.46	3.4	795
January 15	do	1,726	.42	3.3	727
January 19	do	1,481	.43	3.2	638
January 23	do	1,687	.36	3.1	609
January 28	do	1,665	.34	3.0	560
February 1	do	1,650	.29	2.9	485
February 5	do	1,628	.26	2.8	431
February 9	do	1,610	.25	2.7	404
February 13	do	1,615	.25	2.6	405
February 17	do	1,586	.25	2.5	397
February 21	do	1,585	.25	2.5	395
February 25	do	1,565	.24	2.4	369
March 1	do	1,556	.23	2.3	352
March 5	do	1,631	.26	2.7	419
March 7	do	2,050	1.01	4.8	2,067
March 11	do	1,890	.76	4.0	1,441
March 18	do	1,729	.40	3.3	683
March 24	do	1,685	.32	3.0	539
March 28	do	1,624	.27	2.8	435
April 1	do	1,601	.27	2.7	428
April 5	do	1,583	.26	2.6	415
April 10	do	1,560	.26	2.4	401
April 14	do	1,531	.24	2.3	366
April 18	do	1,510	.23	2.2	350
April 22	do	1,492	.18	2.1	265
April 26	do	1,489	.17	2.0	249
May 2	do	1,632	.32	2.9	518
May 6	do	1,471	.18	2.1	268
May 10	do	1,411	.16	1.7	219
May 12	do	1,707	.38	3.3	656
May 17	do	1,482	.18	2.1	266
May 21	do	1,452	.16	1.9	239
May 26	do	2,421	2.26	6.75	5,479
May 30	do	2,520	2.46	7.2	6,194
June 3	do	1,698	.89	4.0	1,506
June 7	do	1,580	.49	3.4	773
June 11	do	1,475	.42	3.0	624
June 15	do	1,446	.29	2.7	423
June 20	do	1,366	.25	2.3	337
June 24	do	1,416	.31	2.8	436
June 28	do	2,076	1.86	6.0	3,861
July 3	do	2,384	3.03	8.2	7,218
July 7	do	1,762	1.43	5.2	2,523
July 12	do	1,774	1.29	4.9	2,282
July 16	do	1,708	1.23	4.7	2,095
July 20	do	1,695	1.34	5.0	2,275
July 23	do	1,784	1.67	5.5	2,984
July 27	do	1,716	1.41	5.1	2,423
August 1	do	1,681	1.19	4.9	1,992
August 5	do	1,599	1.07	4.6	1,718
August 9	do	1,559	.98	4.4	1,530

Discharge measurements of Rio Salado near Guerrero, Tamaulipas, Mexico, in 1905—Con

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di cha
		Square feet.	*Feet per second.*	*Feet.*	*Sec f*
August 13	D. de Lassaulx	1,535	0.90	4.3	
August 18	do	1,488	.83	4.0	
August 23	do	1,469	.74	3.8	
August 28	do	1,427	.71	3.7	
September 2	do	1,405	.66	3.6	
September 7	do	1,405	.62	3.5	
September 15	do	1,371	.57	3.4	
September 20	do	1,973	2.43	6.4	
September 22	do	2,618	3.82	9.3	
September 25	do	1,427	.83	3.8	
September 29	do	1,368	.65	3.5	
October 4	do	2,031	2.61	7.0	
October 8	do	1,389	.77	3.8	
October 12	do	1,354	.69	3.6	
October 16	do	1,296	.61	3.3	
October 21	do	1,907	2.23	6.4	
October 26	do	1,260	.52	3.1	
October 29	do	1,243	.50	3.0	
November 2	do	1,460	.93	4.0	
November 6	do	1,246	.45	3.0	
November 10	do	1,225	.42	2.9	
November 14	do	1,202	.40	2.8	
November 18	do	1,207	.39	2.8	
November 22	do	1,280	.48	3.2	
November 27	do	1,208	.38	2.8	
December 1	do	1,172	.38	2.7	
December 6	do	1,223	.41	2.9	
December 10	do	1,152	.37	2.6	
December 15	do	1,152	.37	2.6	
December 19	do	1,220	.41	2.9	
December 23	do	1,193	.36	2.7	
December 28	do	1,164	.36	2.6	

ıage height, in feet, of Rio Salado near Guerrero, Tamaulipas, Mexico, for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	3.6	2.9	2.3	2.7	2.7	4.8	3.95	4.85	3.55	3.5	4.05	2.7
.....	3.6	2.9	2.3	2.7	2.85	4.7	6.9	4.8	3.55	3.4	4.0	2.7
.....	3.6	2.9	2.3	2.6	2.45	5.2	8.35	4.75	3.5	3.4	3.6	2.7
.....	3.5	2.8	2.45	2.6	2.25	5.4	9.4	4.7	3.5	7.1	3.2	2.7
.....	3.5	2.8	2.7	2.6	2.15	4.1	5.9	4.6	3.55	5.9	3.0	2.6
.....	3.5	2.8	4.55	2.6	2.05	3.7	5.45	4.6	3.6	4.65	3.0	2.85
.....	3.5	2.7	4.75	2.5	2.0	4.0	5.2	4.5	3.5	4.0	3.0	2.75
.....	3.5	2.7	4.1	2.5	2.1	4.0	5.15	4.5	3.5	3.8	2.9	2.7
.....	3.5	2.7	3.2	2.5	1.8	3.4	5.15	4.5	3.5	3.75	2.9	2.65
.....	3.5	2.7	3.8	2.4	2.5	3.25	5.05	4.4	3.4	3.65	2.9	2.6
.....	3.4	2.7	3.85	2.4	3.4	3.0	5.0	4.45	3.4	3.5	2.8	2.6
.....	3.4	2.7	4.25	2.4	3.15	3.0	4.9	4.3	3.4	3.8	2.85	2.65
.....	3.4	2.6	3.0	2.4	2.8	2.9	4.9	4.3	3.4	3.55	2.85	2.7
.....	3.3	2.6	3.0	2.3	3.0	2.8	4.8	4.2	3.4	3.4	2.8	2.7
.....	3.3	2.6	2.9	2.3	2.55	2.7	4.8	4.15	3.4	3.3	2.8	2.6
.....	3.3	2.5	2.9	2.3	2.4	2.6	4.7	4.1	3.4	3.3	2.8	2.6
.....	3.3	2.5	3.15	2.2	2.1	2.5	5.9	4.1	3.3	3.3	2.8	2.6
.....	3.3	2.5	3.3	2.2	2.2	2.4	4.85	4.0	3.3	3.2	2.8	2.65
.....	3.2	2.75	3.25	2.2	2.2	2.35	5.4	4.0	4.7	3.2	4.3	2.85
.....	3.2	2.55	3.15	2.2	1.9	2.3	4.9	3.95	6.7	3.6	4.6	2.85
.....	3.2	2.5	3.5	2.1	1.85	3.05	5.7	3.9	7.75	6.2	3.15	2.85
.....	3.2	2.5	3.85	2.1	1.8	3.2	5.75	3.9	9.3	6.2	3.3	2.95
.....	3.2	2.5	3.3	2.1	1.7	2.95	5.45	3.8	4.95	4.05	3.05	2.85
.....	3.1	2.5	3.05	2.1	1.7	2.7	5.35	3.8	4.25	3.45	2.95	2.7
.....	3.1	2.4	3.0	2.1	3.9	2.5	5.25	3.8	3.85	3.3	2.9	2.7
.....	3.1	2.4	3.0	2.0	7.1	2.35	5.2	3.7	3.75	3.1	2.85	2.6
.....	3.0	2.4	2.9	2.0	4.3	3.6	5.1	3.7	3.65	3.1	2.8	2.6
.....	3.0	2.4	2.8	2.2	4.7	5.9	5.05	3.7	3.55	3.0	2.8	2.6
.....	3.0	.....	2.8	2.3	5.7	4.8	5.0	3.65	3.5	3.0	2.8	2.6
.....	3.0	.....	2.8	2.0	7.3	4.0	4.9	3.6	3.5	3.0	2.7	2.6
.....	2.9	.....	2.8	.....	5.6	.....	4.9	3.6	.....	3.0	.....	2.5

N JUAN NEAR SANTA ROSALIA RANCH, TAMAULIPAS, MEXICO.

ation was established in 1900 by the International (Water) Boundary Commis-
: San Juan is a long torrential stream entering the Rio Grande 15 miles below Roma
miles by river below El Paso. Six miles above its mouth is the town of Camargo.
on was first placed 12 miles above Camargo, but in time of heavy flood in the Rio
ackwater reached the station, and on July 14, 1902, it was moved 6 miles farther
to its present location. It is now above backwater.

anks are sandy clay which are above high water and do not erode. The bottom is
ich erodes slightly in flood.

rge measurements are made by means of a cable, car, and guy wire. The initial
soundings is the cable support at the right bank.

ge is an inclined scantling spiked to posts and a tree. Low water (no flow) is 0 on the
he highest recorded flood, on September 16, 1904, reached 27 feet on the gage.

servations during 1905 were made under the direction of the Mexican section of the
onal (Water) Boundary Commission.

Discharge measurements of Rio San Juan near Santa Rosalia ranch, Tamaulipas, Me in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	D cha
		Square feet.	*Feet per second.*	*Feet.*	*Sec f*
January 4	S. Jaso	966	0.31	2.5	
January 9	do	659	.25	2.5	
January 14	do	626	.26	2.3	
January 18	do	621	.19	2.2	
January 21	do	618	.18	2.2	
January 26	do	600	.12	2.0	
January 30	do	614	.13	2.0	
February 4	do	591	.13	2.0	
February 8	do	601	.14	1.95	
February 12	do	543	.11	1.7	
February 16	do	545	.10	1.7	
February 20	do	583	.12	2.0	
February 24	do	636	.17	2.3	
February 28	do	587	.11	2.0	
March 4	do	567	.10	1.9	
March 6	do	817	.72	3.4	
March 8	do	1,839	1.82	7.2	
March 13	do	609	.29	2.2	
March 17	do	658	.40	2.6	
March 21	do	630	.36	2.5	
March 25	do	596	.33	2.2	
March 29	do	552	.20	1.9	
April 3	do	614	.32	2.4	
April 7	do	453	.12	1.4	
April 12	do	486	.15	1.6	
April 20	do	434	.12	1.25	
April 24	do	748	.58	3.35	
April 28	do	493	.10	1.4	
May 3	do	414	.12	1.3	
May 8	do	1,466	1.51	6.45	
May 9	do	877	.89	3.95	
May 12	do	448	.16	1.7	
May 17	do	344	.09	1.1	
May 22	do	308	.08	.9	
May 26	do	310	.08	1.0	
May 31	do	2,431	2.53	10.25	
June 2	do	3,736	3.92	15.65	
June 3	do	2,794	2.41	11.7	
June 5	do	1,283	1.98	5.65	
June 9	do	541	.66	3.2	
June 13	do	389	.34	2.3	
June 17	do	307	.21	1.75	
June 22	do	970	1.34	4.1	
June 27	do	359	.44	2.55	
July 3	do	312	.22	1.8	
July 7	do	256	.10	1.3	
July 11	do	219	.07	1.0	
July 15	do	202	.07	.9	
July 16	do	491	.74	3.0	
July 18	do	3,883	4.04	16.35	
July 19	do	1,748	2.58	10.1	
July 25	do	288	.44	2.3	

measurements of Rio San Juan near Santa Rosalia ranch, Tamaulipas, Mexico, in 1905—Continued.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
	S. Jaso	190	0.14	1.5	27
	do	167	.12	1.3	20
	do	151	.08	1.1	12
	do	371	.91	2.9	338
	do	229	.29	1.8	66
	do	153	.15	1.2	23
	do	135	.08	.9	11
	do	118	.08	.8	10
	do	108	.06	.7	7
1	do	101	.06	.5	6
17	do	382	.90	2.8	345
19	do	626	2.16	4.85	1,354
20	do	3,955	4.57	16.5	18,071
21	do	2,521	3.35	13.15	8,444
25	do	653	1.77	5.05	1,155
29	do	231	.56	2.2	129
	do	180	.30	1.7	54
	do	1,485	2.68	6.55	3,973
	do	2,620	3.52	13.65	9,230
	do	1,761	3.28	10.2	5,781
	do	1,386	2.35	8.0	3,262
	do	605	1.45	4.7	875
	do	1,481	2.63	8.6	3,899
	do	580	1.30	4.5	756
	do	470	.82	3.3	387
	do	462	.82	3.2	378
	do	2,170	3.77	14.7	8,179
	do	1,661	3.39	11.2	5,625
	do	1,614	2.54	8.75	4,102
3	do	1,083	1.92	6.6	2,077
8	do	954	1.87	5.9	1,786
1	do	1,844	2.41	10.75	4,445
7	do	917	1.42	4.9	1,305
	do	960	1.15	4.4	1,104
	do	1,050	1.72	5.45	1,801
1	do	709	1.40	4.3	990
3	do	712	1.23	4.2	875
2	do	638	1.14	3.9	727
7	do	600	.98	3.7	585
0	do	636	.76	3.6	485

Daily gage height, in feet, of Rio San Juan near Santa Rosalia Ranch, Tamaulipas, Mexico, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.6	2.0	2.0	1.7	1.4	7.4	2.05	1.5	0.6	1.95	4.75	4.6
2	2.6	3.25	2.0	1.7	1.35	14.1	1.95	1.4	.6	1.75	19.3	4.55
3	2.6	2.3	1.9	2.2	1.3	10.4	1.75	1.4	.6	3.5	14.45	4.4
4	2.5	2.0	1.9	1.7	1.3	10.55	1.6	1.3	.5	6.6	9.95	4.3
5	2.5	1.9	2.6	1.6	1.3	6.0	1.5	1.3	.5	5.4	8.25	4.3
6	2.5	1.9	3.8	1.5	1.3	5.2	1.4	1.3	.5	4.55	10.35	4.35
7	2.5	1.9	4.1	1.4	1.25	4.35	1.25	1.2	.....	11.9	11.7	4.5
8	2.5	1.9	6.6	1.4	4.6	3.45	1.1	1.3	.....	11.3	10.95	4.7
9	2.5	2.0	4.2	1.45	3.5	3.05	1.1	1.1	.....	7.35	8.7	5.45
10	2.4	1.95	3.2	1.5	2.45	2.65	1.0	1.1	.....	5.45	9.35	5.3
11	2.4	1.85	2.45	1.6	1.95	2.55	1.0	2.95	.....	4.55	8.0	4.15
12	2.35	1.75	2.3	1.55	1.8	2.4	1.0	2.7	.....	6.9	6.9	4.5
13	2.3	1.7	2.2	1.5	1.65	2.25	.95	1.95	.....	8.5	6.6	4.4
14	2.3	1.8	2.2	1.5	1.45	2.15	.9	1.75	.....	5.65	6.6	4.3
15	2.2	1.8	2.65	1.4	1.3	1.95	.9	1.55	.....	4.9	6.65	4.3
16	2.2	1.7	2.5	1.4	1.2	1.85	2.9	1.45	.....	4.45	6.5	4.25
17	2.2	1.7	2.8	1.4	1.1	1.7	6.2	1.35	2.35	4.1	5.85	4.2
18	2.2	1.7	2.85	1.3	1.1	1.6	15.2	1.15	2.5	3.85	5.75	4.2
19	2.2	2.15	2.7	1.3	1.05	1.55	11.45	1.1	4.0	3.65	5.65	4.1
20	2.2	2.0	2.6	1.25	1.0	1.5	6.15	1.0	14.5	3.55	5.55	4.1
21	2.2	1.95	2.5	1.2	.9	1.7	5.1	.95	11.75	3.25	9.1	3.9
22	2.15	2.1	2.4	1.2	.9	5.65	3.25	.9	6.15	3.35	6.75	3.9
23	2.1	2.2	2.35	1.2	.9	4.85	2.75	.9	4.3	3.45	5.95	3.9
24	2.1	2.3	2.3	2.25	.9	3.6	2.45	.85	3.25	3.35	5.55	3.9
25	2.0	2.25	2.2	2.6	.95	3.3	2.25	.8	3.9	3.3	5.3	3.8
26	2.0	2.2	2.05	2.1	1.0	3.35	2.05	.8	3.85	3.2	5.2	3.7
27	2.0	2.1	2.0	1.4	1.0	3.35	1.9	.7	2.75	3.1	4.9	3.7
28	2.0	2.0	1.95	1.35	1.0	3.15	1.8	.7	2.35	3.1	4.8	3.7
29	2.0	.....	1.9	1.3	1.0	2.35	1.7	.7	2.15	3.0	4.7	3.6
30	2.0	.....	1.85	1.25	1.0	1.95	1.6	.7	2.0	3.0	4.6	3.6
31	2.0	.....	1.7	.....	8.5	.....	1.5	.7	.....	3.0	.....	3.6

NOTE.—No flow September 7-16.

CONEJOS RIVER NEAR MOGOTE, COLO.

Conejos River is the largest tributary of the Rio Grande in Colorado. Its source is the slopes of Conejos Peak and adjoining mountains, which have a general altitude of 12,000 feet. The general course is very irregular. Half of this course is in canyon, while the lower half is through the broad, almost level San Luis Valley. The lower basin is composed of gravelly mesas which merge into the level valley lands below. Rainfall data collected at Conejos by the United States Weather Bureau for a few months give the mean annual rainfall as 10 inches. The precipitation increases with the altitude to approximately 20 inches in the head waters. Irrigation as heretofore practiced has been very crude, and almost the entire normal flow of the river at low water is required for the numerous small ditches which render cultivation possible.

This station was established August 25, 1899, by A. L. Fellows, and is located 500 feet below the highway bridge 4 miles above Mogote, Colo., in T. 33 N., R. 7 W., New Mexico principal meridian. The nearest railroad station is Antonito, Colo., 12 miles east. This station was discontinued in the fall of 1900 and reestablished in the spri[redacted] fact that Conejos River is the chief tributary of the Rio Grande in Colorad[redacted] of importance, as it is above all diversions, of which there are a great m[redacted] A number of storage reservoirs are proposed for this basin.

hannel at the gage has a very gentle curve, and the bed is composed of small bowlders
›blestones. The banks are low, of alluvial material, and will overflow during very
ıter. At extremely high stages, water passes through low depressions around
les of the channel and is not registered on the gage. Such was the case during the
high water of June, 1905. The velocity is moderate at low water at this section.
ighway bridge above the gage the channel is 90 feet in width, with a 9-foot crib pier
g the current at the center of stream. The section is not uniform, and is composed
lers and cobblestones. During the high water of June a considerable volume of water
ıround the right end, running over the bridge to a depth of about 6 inches. This high
lso eroded the channel greatly and changed its alignment for 1 mile above and many
low. During August and the remaining portion of the year this section was partially
ted by a temporary rock and log dam extending at a slight angle upstream and under
span of the bridge. This dam was for the purpose of diverting water for irrigation
l probably go out with high water. At low water the velocity is moderate at the
and at high stages it is very swift.

ıarge measurements are made at the gage rod during low water, and from the down-
side of the highway bridge during high water. The initial point for soundings is
of the right abutment.

gage is an inclined staff fastened to a large stump on the left bank of the river at
ıg's ranch. Gage heights range from 1 to 6 feet on the gage. During 1905 the gage
d twice each day by Miss Nellie King. The bench mark is the center of three 20-
ıails driven into the base of a large cottonwood tree, 300 feet south of gage; elevation,
t above the datum of the gage.

mation in regard to this station is contained in the following publications of the States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

ion: WS 37, pp 278-279; 50, p 348; 99, p 397; 132, p 94.
ge: WS 37, p 279; 50, p 348; 99, p 398; 132, p 95.
e, monthly: Ann 22, iv, p 348; 99, p 399; 132, p 96.
ghts: WS 37, p 279; 50, p 348; 99, p 398; 132, p 95.
ables: WS 52, p 519; 99, p 399; 132 p 96.
computations: WS 50, p 306.

Discharge measurements of Conejos River near Mogote, Colo., in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	R. I. Meeker.....	76	162	2.01	2.20	328
.....	.....do.....	81	289	4.69	3.65	1,356
.....	.....do.....	66	151	1.64	2.00	246
er 19[a].	.....do.....	65	61	1.02	1.30	62

[a] Wading at gage rod.

Daily gage height, in feet, of Conejos River near Mogote, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	1.65	3.4	4.8	3.2	1.7	1.7	1.6
2	1.4	3.4	5.1	3.0	2.2	1.6	1.55
3	1.5	3.0	5.15	3.0	2.25	1.5	1.5
4	1.55	2.8	5.55	3.35	2.4	1.5	1.4
5	1.6	2.7	5.65	3.6	2.1	1.55	1.4
6	1.6	2.55	4.4	3.65	2.2	1.55	1.4
7	1.75	2.7	5.05	2.35	2.2	1.6	1.35
8	1.85	2.85	5.35	2.65	2.15	1.5	1.3
9	2.0	3.0	5.05	2.4	2.05	1.5	1.3
10	2.1	2.85	4.9	2.55	1.9	1.5	1.3
11	2.0	2.75	4.85	2.55	2.25	1.5	1.2
12	2.0	2.75	4.7	2.45	2.1	1.4	1.2
13	2.05	3.0	4.7	2.4	1.9	1.4	1.2
14	2.0	3.1	4.6	2.4	1.9	1.4	1.2
15	2.1	3.55	4.7	2.5	1.8	1.4	1.2
16	2.05	3.9	4.55	2.5	1.7	1.4	1.2
17	2.15	4.15	4.3	2.3	1.7	1.3	1.3
18	2.2	4.3	4.2	2.2	1.65	1.35	1.3
19	2.35	4.35	4.1	2.25	1.6	1.3	1.3
20	2.2	4.45	3.95	2.4	1.65	1.3	1.3
21	2.25	4.45	3.8	2.45	1.6	1.3	1.3
22	2.35	4.5	3.7	2.45	1.6	1.3	1.3
23	2.3	4.6	3.8	2.4	1.6	1.3	1.4
24	2.2	4.75	3.7	2.2	1.6	1.25	1.5
25	2.2	4.75	3.6	2.1	1.8	1.25	1.5
26	2.3	4.85	3.55	2.0	1.7	1.4	1.4
27	2.5	4.8	3.55	2.05	1.7	1.4	1.4
28	2.7	4.6	3.5	2.2	1.65	1.4	1.4
29	2.9	4.05	3.4	2.4	1.75	1.4	1.4
30	3.05	4.25	3.3	2.3	1.7	1.65	1.4
31	.....	4.5	.....	2.15	1.7	.....	1.4

Station rating table for Conejos River near Mogote, Colo., from April 1 to June 5, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.40	25	2.40	425	3.40	1,120	4.40	2,180
1.50	55	2.50	480	3.50	1,210	4.50	2,300
1.60	85	2.60	540	3.60	1,310	4.60	2,430
1.70	120	2.70	600	3.70	1,410	4.70	2,560
1.80	155	2.80	660	3.80	1,510	4.80	2,690
1.90	190	2.90	725	3.90	1,610	4.90	2,820
2.00	230	3.00	795	4.00	1,720	5.00	2,950
2.10	275	3.10	870	4.10	1,830	5.20	3,230
2.20	320	3.20	950	4.20	1,940	5.40	3,510
2.30	370	3.30	1,030	4.30	2,060	5.60	3,800

The above table is applicable only for open channel conditions. It is based on one discharge measurement made during 1905 and on 1904 measurements. It is not well defined.

Station rating table for Conejos River near Mogote, Colo., from June 6 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.20	45	2.30	375	3.40	1,120	4.50	2,300
1.30	60	2.40	425	3.50	1,210	4.60	2,430
1.40	80	2.50	480	3.60	1,310	4.70	2,560
1.50	100	2.60	540	3.70	1,410	4.80	2,690
1.60	125	2.70	600	3.80	1,510	4.90	2,820
1.70	155	2.80	660	3.90	1,610	5.00	2,950
1.80	185	2.90	725	4.00	1,720	5.10	3,090
1.90	215	3.00	795	4.10	1,830	5.20	3,230
2.00	250	3.10	870	4.20	1,940	5.30	3,370
2.10	290	3.20	950	4.30	2,060	5.40	3,510
2.20	330	3.30	1,030	4.40	2,180		

The above table is applicable only for open channel conditions. It is based on three discharge measurements made during 1905. It is not well defined.

Estimated monthly discharge of Conejos River near Mogote, Colo., for 1905.

[Drainage area, 282 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	832	25	297	17,670	1.05	1.17
May	2,755	510	1,544	94,940	5.48	6.32
June	3,875	1,030	2,226	132,500	7.89	8.80
July	1,360	250	528	32,460	1.87	2.16
August	425	125	213	13,100	.755	.870
September	155	52	87.4	5,201	.310	.346
October	125	45	71.5	4,396	.254	.293
The period				300,300		

PECOS RIVER AT SANTA ROSA, N. MEX.

This station was established May 5, 1903, by H. C. Hurd. It was originally located at the bridge of the Chicago, Rock Island and Pacific Railway, but was moved later in the year to a point 335 feet above the railway bridge.

The bed of the river is solid rock, overlaid by quicksand to the depth of 2 or 3 feet in the long dry season. The current is never sluggish and becomes very swift during the time of floods. The channel is straight for one-fourth mile above and below the station. Both banks are high and can not overflow.

Discharge measurements are made by means of a cable. The initial point for soundings is the left end of the cable.

The original gage was a staff bolted to the masonry footing of the east tower. During the great flood of September 29 and 30, 1904, the upper portion of the gage rod was torn away, but the lower portion was left intact. A new gage was installed on the east side of the second pier to replace the one which was torn out. This new portion of the gage is bolted to the east face of the second pier from the north end of the bridge. The same flood cut away the earth from the face of the north abutment, leaving the bench mark about 25 feet above the ground and inaccessible, so in establishing the new gage reference was made to the old gage which had not been moved by the flood. During 1905 the gage was read once each day by L. M. Shely. Bench marks were established as follows: (1) A shelf cut in the east abutment; elevation, 29.70 feet. (2) A chiseled surface on the east side of the first pier from the north end of the bridge, near the top of the second stone from

the downstream end of the pier, in the second tier of stones from the bed rock, marked "B. M."; elevation, 6.41 feet. (3) The top of the downstream end of retaining wall on the east side of the river; elevation, 14.60 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 363–364; 132, p 97.
Discharge: 99, p 364; 132, p 97.
Gage heights: 99, pp 364–365; 132, p 98.

Discharge measurements of Pecos River at Santa Rosa, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage Height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second feet.*
May 2	J. M. Giles	96	236	5.61	2.50	1,321
June 2	E. Patterson	93	196	5.28	2.10	1,035
June 5	do	93	195	5.88	2.30	1,145
July 3	do	78	37	1.49	1.10	55
July 7	do	26	14	1.03	.80	14.5
August 21	Giles and Patterson	25	12	1.19	.72	14.8
August 23	E. Patterson	24	12	1.16	.71	13.9
October 8	do	24	11	1.09	.81	12
October 24	J. M. Giles	26	13	1.16	.80	15
November 17	E. Patterson	18	10	1.19	.87	12

Daily gage height, in feet, of Pecos River at Santa Rosa, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	0.5	0.5	1.5	1.0	1.5	2.6	1.5	1.2	0.7	0.7	0.8	1.5
2	.5	.5	1.6	1.0	2.5	2.1	1.5	3.0	.7	.7	.8	1.0
3	.5	.5	2.0	1.0	2.5	2.0	1.5	2.5	.7	.7	.8	1.0
4	.5	.5	2.0	1.0	2.5	3.05	1.0	2.5	1.5	.7	.8	1.0
5	.5	.5	2.5	1.0	2.5	2.2	.9	2.0	1.5	.7	.8	.8
6	.5	.5	3.0	1.0	2.5	2.1	.8	2.0	1.0	.7	.8	.8
7	.5	.5	3.0	1.0	3.0	1.9	.8	1.5	.9	.7	.9	.8
8	.5	.6	2.0	1.5	2.5	2.0	.8	1.5	.9	.7	.8	.8
9	.5	.6	2.0	1.5	2.5	3.0	.8	1.5	.9	.8	1.0	.8
10	.5	.6	2.0	1.5	2.5	2.3	.8	1.5	.9	.8	1.1	.8
11	.5	.6	2.0	2.5	2.5	2.0	.7	1.5	.9	.8	.9	.8
12	.5	.6	1.5	2.5	2.5	2.5	.7	2.5	1.3	.8	.9	.8
13	.5	.6	1.5	1.5	2.5	2.5	.7	2.0	1.0	.8	.9	.8
14	.5	.6	1.5	1.5	3.0	2.0	.7	1.5	1.0	.8	.9	.9
15	.4	.6	1.4	1.5	2.5	1.7	.7	1.5	1.0	.8	.9	.8
16	.4	.6	1.4	1.5	2.5	1.7	.7	1.5	1.0	.8	.9	.6
17	.4	.6	1.4	1.5	2.5	1.0	.7	1.0	.8	.8	.9	.6
18	.4	.6	1.4	1.5	2.5	1.0	.7	.9	.8	.8	.9	.6
19	.4	.6	1.4	1.5	2.5	1.0	.7	.8	.8	.8	.9	.5
20	.4	.8	1.4	1.5	2.5	1.0	.7	.7	.7	.8	.9	.5
21	.4	.8	1.4	1.5	2.5	1.0	.9	.7	.7	.8	.9	.5
22	.4	1.0	1.4	1.5	2.5	1.0	2.5	.7	.7	.8	.9	.5
23	.4	1.5	1.4	3.5	2.5	1.0	1.5	.7	.7	.8	4.0	.5
24	.4	1.5	1.4	3.0	2.8	1.0	1.5	.7	.7	.8	2.5	.5
25	.4	3.0	1.4	3.0	3.0	1.0	1.5	.7	.7	.8	1.5	.6
26	.4	1.5	1.4	2.5	2.5	1.5	1.0	.7	.7	.8	1.5	.6
27	.4	1.5	1.4	2.5	2.5	1.5	1.0	.7	.7	.8	3.0	.6
28	.4	1.5	1.4	2.5	2.5	1.5	1.0	.7	.7	.8	1.0	.6
29	.5	.....	1.4	2.5	2.5	1.5	1.0	.7	.7	.8	2.0	.6
30	.5	.....	1.4	3.0	2.5	1.5	1.0	.7	.7	.8	1.6	.5
31	.5	.....	1.4	.....	2.0	.....	1.0	.7	.....	.8	.....	.6

PECOS RIVER NEAR FORT SUMNER, N. MEX.

This station was established June 12, 1904, by Earl Patterson. It is located about 12 iles northwest of Fort Sumner, N. Mex., and 45 miles south of Santa Rosa, N. Mex., the earest railway station. It was originally located 1 mile upstream from the spring, trees, nd houses known as Arinosa, but was relocated July 5, 1905, near the spring.

Both banks are high and will not overflow except in extreme high water. The bed of he river is clean, shifting sand.

Discharge measurements are made by wading at or near the gage.

The gage is an inclined staff bolted to a ledge of sandstone on the right bank. During 905 the gage was read twice each day by J. C. Pacheco. Bench marks were established as llows: (1) The head of a bolt set in the rock 14 feet upstream from gage; elevation, 7.48 et. (2) A cross cut in the sandstone ledge 5 feet downstream from gage; elevation, 7.11 et. Elevations refer to the datum of the gage.

A description of this station and gage height and discharge data are contained in Water-upply Paper No. 132 of the United States Geological Survey, pp. 98101.

Discharge measurements of Pecos River near Fort Sumner, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second feet.*
y 4	E. Patterson	84	68	1.56	1.40	107
y 6	do	91	55	1.55	1.30	86
;ust 22	Giles and Patterson	46	52	1.64	1.40	85
ober 9	E. Patterson	75	62	1.48	1.45	92
ember 18	do	80	59	1.60	1.50	95
(a)	J. M. Giles	.....	200	1.76	2.00	352
(a)	do	.....	405	2.70	3.00	1,093
(a)	do	.....	615	3.36	4.00	2,066

[a] Computed from slope measurement, using Kutter's formula.

Daily gage height, in feet, of Pecos River near Fort Sumner, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
1	0.4	0.3	2.95	1.3	2.3	2.3	1.4	1.8	1.4	1.4	1.55	1
2	.4	.3	2.6	1.35	2.4	2.2	1.7	1.5	1.4	1.4	1.5	1
3	.4	.3	2.25	1.3	2.45	2.25	1.55	2.0	1.4	1.4	1.55	
4	.4	.8	2.0	1.3	2.4	1.95	1.45	1.72	1.4	1.4	1.65	
5	.4	.8	.85	1.2	2.2	2.8	1.4	2.22	3.2	1.4	1.55	
6	.4	.8	.75	1.3	2.15	2.3	1.3	1.87	1.6	1.4	1.6	
7	.4	.8	.7	1.3	1.95	2.25	1.4	1.87	1.5	1.4	1.6	
8	.4	.9	1.1	1.2	2.05	2.1	1.35	2.15	1.6	1.4	1.6	
9	.4	.7	1.0	1.2	2.25	2.4	1.4	1.85	1.6	1.45	1.7	
10	.4	.6	1.25	1.2	2.3	2.45	1.4	1.77	1.5	1.5	1.7	
11	.4	.6	1.3	1.35	2.3	2.6	1.4	1.7	1.7	1.5	1.7	
12	.4	.6	1.2	1.6	2.2	2.35	1.4	1.9	1.5	1.45	1.65	
13	.4	.6	1.2	1.7	2.0	2.3	1.4	2.3	1.5	1.45	1.6	
14	.4	.6	1.2	1.4	2.05	2.35	1.4	1.77	1.45	1.45	1.6	
15	.4	.6	1.2	1.4	2.15	2.2	1.4	1.52	1.45	1.45	1.55	
16	.4	.6	1.2	1.5	2.2	2.1	1.35	1.5	1.4	1.4	1.6	
17	.4	.6	1.15	1.5	2.35	1.9	1.35	1.47	1.35	1.45	1.55	
18	.3	.6	1.1	1.45	2.4	1.8	1.35	1.42	1.3	1.45	1.5	
19	.3	.6	1.0	1.75	2.55	1.9	1.35	1.42	1.35	1.4	1.5	
20	.3	.5	.9	1.6	3.1	1.8	1.35	1.4	1.35	1.4	1.55	
21	.3	.6	.8	1.7	2.95	1.8	1.4	1.4	1.3	1.4	1.6	
22	.3	.7	1.1	1.7	2.5	1.9	2.1	1.4	1.3	1.4	1.65	
23	.3	1.3	1.0	2.7	3.3	1.75	2.0	1.4	1.35	1.45	2.2	
24	.4	1.55	.9	2.95	2.75	1.7	1.7	1.45	1.35	1.45	2.7	
25	.4	1.2	.8	2.95	2.9	1.7	1.6	1.45	1.35	1.5	2.1	
26	.4	1.05	.8	2.4	2.25	1.7	1.6	1.4	1.35	1.5	1.75	
27	.4	.9	.9	2.2	2.25	1.6	1.6	1.4	1.35	1.5	1.6	
28	.4	.9	.95	2.45	2.5	1.6	1.5	1.4	1.45	1.5	1.7	
29	.4	.....	1.0	2.45	2.4	1.6	1.5	1.4	1.4	1.5	1.85	
30	.3	.....	1.1	2.35	2.4	1.5	1.52	1.4	1.5	1.6	2.1	
31	.3	.....	1.0	.....	2.3	.....	1.45	1.4	.....	1.55	.....	

discharge, in second-feet, of Pecos River near Fort Sumner, N. Mex., for 1905.

Day.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
	.....	260	85	90	120	225
	.....	120	85	90	110	260
	.....	360	85	90	115	225
	.....	220	85	90	135	180
	105	490	1,250	90	110	180
	85	295	170	90	120	180
	105	295	130	90	115	225
	95	450	170	90	110	200
	105	285	170	95	130	180
	105	245	130	105	130	140
	105	210	215	105	130	210
	105	310	130	95	120	240
	105	550	130	95	110	325
	105	245	117	95	110	200
	105	128	117	95	100	210
	95	120	105	90	105	200
	95	110	95	95	100	200
	95	90	85	95	95	200
	95	90	85	90	95	210
	95	85	95	90	100	210
	105	85	85	90	105	190
	420	85	85	90	115	140
	360	85	95	95	480	95
	215	102	95	95	825	500
	170	102	95	105	420	325
	170	85	95	105	230	265
	170	85	97	105	157	265
	130	85	117	105	210	240
	130	85	105	105	280	240
	130	85	130	160	420	210
	117	85	.....	130	.....	600

Daily discharge determined by indirect method as applied to shifting channels. As no measwere made prior to July 4, no estimates have been made for that period.

mated monthly discharge of Pecos River near Fort Sumner, N. Mex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
	420	85	138	7,391
	550	85	191	11,740
	1,250	85	151	8,985
	160	90	98.4	6,050
	825	95	183	10,890
	600	95	235	14,450
period	.....	.....	.....	59,510

PECOS RIVER NEAR ROSWELL, N. MEX.

ation was established April 24, 1903, by W. M. Reed. It is located at the highway miles southeast of Roswell, N. Mex., and about 200 feet below the mouth of Hondo

annel is straight for one-half mile above and below the station and has a width at r of about 50 feet and at ordinary high water of 430 feet. The channel is broken by

two iron piers. The current is rapid except near the mouth of Hondo River, where it b comes sluggish. At high water the Pecos and the Hondo join above the bridge. The ga heights on the Pecos may be affected by back water at periods when the Pecos is low and t Hondo is high. Both banks are high and free from timber, but they overflow at extre flood stages. The bed is sandy and shifting, and the cross section changes during each flo

Discharge measurements are made from the highway bridge. The initial point for soun ings is a zero marked on the guard rail at the west end and north side of the bridge.

The original gage is painted on the right side of the right pier of the bridge. Septemb 15, 1905, a standard chain was bolted to the upstream fencing of the bridge 325 feet fro the initial point for soundings; length of chain, 26.45 feet. During 1905 the gage was re twice each day by Miss Dovie Goldsmith. Bench marks were established as follows: (1 The top of the pier upon which the original gage is painted; elevation, 20.10 feet. (2) T top of angle bar connecting fencing with first upright east of pier on which the gage is painte elevation, 25.17 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers the United States Geological Survey:

Description: 99, p 360; 132, p 101.
Discharge: 99, p 360; 132, p 102.
Gage heights: 99, p 361; 132, p 102.

Discharge measurements of Pecos River near Roswell, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di cha
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Sec fe*
February 28	E. Patterson	290	433	2.10	2.90	
March 28	F. S. Dobson	164	260	1.65	2.00	
April 12	Giles and Mitchell	176	274	2.21	2.55	
April 26	E. Patterson	317	729	4.53	4.50	
April 28	do	304	415	3.13	3.40	
May 23	do	364	682	4.48	4.50	
June 14	do	362	535	2.92	3.70	
July 10	do	106	74	.85	2.30	
July 18	do	36	39	.81	1.90	
July 24	do	370	765	4.74	5.80	
July 25	do	371	1,300	5.25	6.80	
July 27	do	223	618	4.47	4.50	
August 2	J. M. Giles	210	377	1.90	3.40	
August 9	E. Patterson	379	498	3.26	3.80	
August 26	do	112	133	.80	1.80	
August 28	do	120	108	.71	1.70	
September 4	do	104	96	.76	1.70	
September 6	do	219	1,063	5.88	5.90	
September 7	do	204	541	2.45	3.50	
September 8	do	214	430	3.10	3.60	
September 9	do	150	198	2.38	2.80	
September 11	do	137	187	2.19	2.75	
October 4	do	102	113	1.35	2.45	
October 13	do	101	85	1.04	2.25	
October 13	J. M. Giles	90	92	1.14	2.25	
October 23	E. Patterson	101	89	1.07	2.30	
October 30	do	100	93	1.04	2.30	
November 5	do	.....	270	1.23	3.00	
November 10	do	.....	328	1.93	3.00	
November 24	J. M. Giles	.....	710	3.20	4.10	
November 25	do	.....	686	2.81	4.00	
December 11	E. Patterson	180	308	1.28	2.60	

Daily gage height, in feet, of Pecos River near Roswell, N. Mex., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.2	1.2	2.5	2.3	3.3	3.5	2.5	3.3	1.8	2.1	2.5	3.5
.....	1.2	1.2	2.5	3.0	3.35	3.4	2.5	3.0	1.8	2.1	2.5	3.2
.....	1.2	1.2	2.3	2.45	3.2	3.4	2.5	4.0	1.8	2.2	2.6	3.2
.....	1.2	1.2	2.3	2.3	3.2	3.4	2.5	3.3	1.8	2.4	3.0	3.0
.....	1.0	1.3	2.9	2.3	3.2	3.4	2.5	3.2	1.8	2.4	3.0	2.8
.....	1.0	1.3	2.3	2.35	3.2	4.5	2.5	3.2	7.5	2.3	3.0	2.6
.....	1.0	2.0	2.5	2.45	3.45	5.0	2.4	3.2	3.7	2.3	3.0	2.6
.....	1.0	2.0	4.0	2.45	3.35	4.0	2.4	3.0	3.6	2.3	3.0	2.6
.....	1.0	2.2	3.0	2.4	3.35	3.5	2.3	3.8	2.9	2.2	3.3	2.6
.....	1.6	2.2	3.0	2.4	3.2	3.5	2.3	3.4	3.7	2.2	3.0	2.6
.....	2.0	2.0	3.9	2.45	3.1	4.0	2.3	3.4	3.0	2.2	3.0	2.7
.....	2.0	2.0	3.0	2.5	3.5	4.0	2.3	3.3	2.5	2.2	3.0	2.7
.....	2.6	2.4	3.0	2.5	3.45	4.4	2.2	3.2	2.45	2.2	3.0	2.7
.....	2.0	2.4	2.9	2.45	3.35	3.7	2.2	3.2	2.45	2.1	2.8	2.7
.....	1.1	2.0	2.9	2.45	3.25	3.5	2.2	3.2	2.45	2.1	2.8	2.7
.....	1.6	2.6	2.8	2.45	3.25	3.5	2.0	2.8	2.4	2.1	2.8	2.7
.....	1.4	2.8	2.6	2.45	3.3	3.5	2.0	2.6	2.4	2.1	2.8	2.7
.....	1.0	2.7	2.6	2.45	3.45	3.5	2.0	2.5	2.4	2.1	2.8	2.5
.....	1.0	2.5	2.3	2.45	3.45	3.5	6.2	2.3	2.3	2.1	2.6	2.5
.....	1.6	2.3	2.2	2.45	3.5	3.5	3.3	2.3	2.2	2.1	2.6	2.5
.....	2.0	2.6	2.0	2.45	3.8	3.5	3.0	2.0	2.2	2.1	2.6	2.5
.....	2.4	2.6	2.0	2.45	4.45	3.5	3.0	2.0	2.2	2.1	2.6	2.5
.....	2.4	2.0	2.0	5.35	4.45	3.5	10.0	2.0	2.2	2.1	2.6	2.5
.....	2.4	2.0	2.0	5.0	4.45	3.3	6.0	2.0	2.2	2.1	4.75	2.5
.....	2.0	2.6	2.0	4.0	4.45	3.3	6.7	1.8	2.1	2.1	3.85	2.5
.....	2.0	3.6	2.6	4.45	4.45	3.3	5.6	1.8	2.1	2.3	3.5	2.5
.....	1.1	3.0	2.4	3.75	4.45	3.3	4.3	1.8	2.1	2.3	3.3	2.5
.....	1.8	2.5	2.0	3.3	4.0	3.3	3.8	1.8	2.1	2.4	3.0	2.5
.....	1.3	.....	2.0	3.3	3.7	3.3	3.4	1.8	2.1	2.4	2.8	2.4
.....	1.2	.....	2.0	3.3	3.7	3.0	3.4	1.8	2.1	2.45	3.5	2.4
.....	1.2	.....	2.0	.....	3.5	.....	3.4	1.8	.....	2.45	.....	2.4

PECOS RIVER NEAR DAYTON, N. MEX.

station was established March 24, 1905. It was located about 3 miles east of Dayton, :., 100 feet below the mouth of Penasco River and about 6 miles above McMillan dam ewood, N. Mex. The gage was washed out September 6, 1905, and the station was ed September 7, 1905, about one-half mile upstream.

channel is straight for 200 feet above and 500 feet below the station. The right bank and the cable will be accessible until the river rises above 10 feet on the gage. The ık is about the same height. The bed is clean shifting sand and the current good.

harge measurements were made by means of a cable at the original location until the ge was established, when the cable was reerected about 100 yards below the new gage. present gage is a staff fastened to posts driven into the right bank. During 1905 the as read once each day by Eugene Lattion. The bench mark is a nail in the upstream the post under the cable on the right bank; elevation, 13.90 feet above the datum of ge..

Discharge measurements of Pecos River near Dayton, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 18	J. M. Giles	145	327	1.71	2.52	559
May 8	E. Patterson	188	516	3.04	4.60	1,572
May 15	J. M. Giles	149	409	2.80	4.18	1,145
May 28	E. Patterson	192	510	3.83	5.20	1,956
June 13	do	193	644	3.60	5.30	2,319
July 1	J. M. Giles	109	145	1.33	2.60	193
July 1	do	109	145	1.29	2.60	187
July 11	E. Patterson	72	96	1.05	1.95	101
July 15	do	71	84	1.07	1.90	91
July 23	do	196	744	3.25	5.60	2,422
July 23	do	196	789	3.32	5.80	2,623
July 23	do	196	823	3.64	6.00	3,004
September 1 [a]	do	140	170	.80	1.50	137
September 6 [a]	J. M. Giles	94	126	1.55	1.72	196
September 9	do	171	552	1.82	3.40	1,006
September 9	do	170	491	1.84	3.15	905
September 12	do	96	161	2.61	1.95	419
September 12	do	96	163	2.80	2.05	456
September 15	E. Patterson	96	108	2.14	1.50	236
October 4	J. M. Giles	109	142	1.62	1.65	230
October 4	do	109	143	1.68	1.67	240
October 15	E. Patterson	112	142	1.60	1.70	228
October 21	do	111	139	1.46	1.67	204
November 7	do	.....	204	1.71	2.26	359
November 23	J. M. Giles	.....	241	1.76	2.40	425
November 23	do	.....	238	1.79	2.40	427
November 26	do	.....	759	2.20	4.30	1,668
November 28 [b]	do	.....	380	1.55	3.00	588
November 28 [b]	do	.....	378	1.62	3.05	612
December 8	E. Patterson	.....	280	2.08	2.60	583
December 28	do	.....	202	1.63	2.30	329

[a] Measurement by wading. [b] Backwater from McMillan reservoir.

NOTE.—Measurements April 18 to September 1 made below the mouth of the Penasco; after September 1 made above mouth of Penasco.

Daily gage height, in feet, of Pecos River near Dayton, N. Mex., for 1905.

y.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	1.85	5.1	4.6	2.5	3.4	1.5	1.4	1.6	3.5
.....	.....	1.85	4.95	4.5	2.5	3.8	1.7	1.5	1.9	3.5
.....	.....	2.5	4.9	4.3	2.4	3.9	2.2	1.6	1.5	3.5
.....	.....	2.1	4.9	4.5	2.3	4.0	2.5	1.7	2.0	3.4
.....	.....	2.65	5.1	4.2	2.3	3.6	2.3	1.7	2.2	3.4
.....	.....	2.3	5.2	4.3	2.2	3.6	1.7	1.7	2.2	3.0
.....	.....	2.3	5.2	5.6	2.1	3.4	4.5	1.7	2.2	2.9
.....	.....	2.25	5.0	4.5	2.1	5.0	3.4	1.7	2.3	2.9
.....	.....	2.25	5.4	4.4	2.2	4.8	3.3	1.6	2.4	2.7
.....	.....	2.15	4.9	4.4	2.1	4.5	2.8	1.6	3.0	2.7
.....	.....	2.15	4.7	4.6	2.1	3.8	2.5	1.6	2.9	2.7
.....	.....	2.1	4.3	6.0	2.0	3.5	2.0	1.7	2.9	2.7
.....	.....	3.0	4.3	5.4	2.0	3.3	2.2	1.8	2.7	2.7
.....	.....	3.3	4.4	4.6	2.0	3.4	2.0	1.5	2.6	3.1
.....	.....	3.0	4.2	4.7	2.0	4.0	1.5	1.7	2.5	3.0
.....	.....	3.5	4.0	4.5	2.0	3.9	1.7	1.7	2.5	3.0
.....	.....	3.55	4.2	4.6	1.9	3.0	1.8	1.7	2.6	2.9
.....	.....	3.3	4.2	4.3	1.8	2.8	1.5	1.7	2.9	2.9
.....	.....	3.5	4.0	4.2	1.8	2.9	1.3	1.7	2.3	2.9
.....	.....	3.3	4.2	4.0	3.8	2.5	3.0	1.7	2.3	2.7
.....	.....	3.25	6.5	3.7	3.0	2.3	2.0	1.7	2.3	2.7
.....	.....	3.3	4.9	3.7	2.8	2.0	1.5	1.7	2.5	2.7
.....	.....	4.1	5.2	3.6	10.9	2.2	1.4	1.7	2.4	2.7
.....	2.5	5.6	4.5	3.4	.....	1.8	1.5	1.7	4.5	2.8
.....	2.3	6.45	6.2	3.9	.....	1.7	1.5	1.6	5.4	3.2
.....	2.25	5.7	5.4	3.2	.....	1.7	1.5	1.7	4.2	2.55
.....	1.85	5.85	5.0	3.1	5.9	1.6	1.5	1.7	3.6	2.5
.....	1.85	5.2	5.0	3.0	5.5	1.6	1.4	1.6	3.2	2.5
.....	2.0	4.95	5.7	3.0	4.9	1.5	1.5	1.6	2.9	2.6
.....	2.0	4.7	4.7	2.6	4.2	1.2	1.5	1.6	3.4	2.4
.....	1.85	.....	4.7	.....	3.7	1.2	.....	1.6	.....	3.0

NOTE.—Water above gage July 24–26.

PECOS RIVER AT CARLSBAD, N. MEX.

This station was established May 20, 1903, by V. L. Sullivan. It is located at the Green Street Bridge, Carlsbad, N. Mex., and is about 500 feet below the station of the Pecos Valley and Northeastern Railway and 2,000 feet below the Hagerman power dam.

Both banks are high and not subject to overflow. The bed of the river is solid rock, much corrugated, which makes low-water measurements subject to considerable inaccuracy. The The channel is straight for some distance above and below the station. The current is swift at the station, but sluggish, both above and below.

Discharge measurements are made by wading when the stage of the river will permit, and from the lower side of the bridge during floods. The initial point for soundings is on the south side of the bridge at the west abutment.

The bridge and original gage were carried away by the flood of October, 1904. The new gage is in three sections: The first is a vertical section, reading from 0 to 6 feet, spiked to the abutment on the right bank. The second section, reading from 6 to 10 feet, is spiked to a post on the right bank. The third section, reading from 9 to 19 feet, is nailed to a pile in the railroad trestle over a ravine about 100 feet south of Green street and 100 feet from the river bank. The datum is the same as that of the original gage. During 1905 the gage was read twice a day by V. L. Sullivan, a civil engineer in the employ of the Pecos Valley Irrigation Company. The bench mark is the northeast corner of the stone threshold at the door of the men's waiting room of the Pecos Valley and Northeastern Railway depot; elevation, 25.63 feet above the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 99, pp 358-359; 132, p 103.
Discharge: 99, p 359; 132, p 103.
Gage heights: 99, pp 359-360; 132, p 104.

Discharge measurements of Pecos River at Carlsbad, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
February 24	F. S. Dobson	190	671	2.10	2.39	1,413
March 13	V. L. Sullivan	190	1,236	2.42	4.05	3,001
May 8	Murphy and Giles	212	765	3.84	4.10	2,941
May 9	do	202	608	4.51	3.95	2,740
May 13	J. M. Giles	165	169	1.98	1.25	334
July 5	do	103	113	2.30	1.13	261
July 10	do	120	185	3.66	1.76	678
July 25[a]	V. L. Sullivan	310	4,110	13.36	15.85	54,930
July 26[a]	do	290	3,151	12.29	12.60	38,730
July 27[a]	do	260	2,266	10.76	9.85	24,380
July 28	do	245	1,403	8.05	7.00	11,300
August 5	J. M. Giles	189	870	2.39	3.43	2,082
August 7	do	182	708	2.04	2.70	1,441
October 10	do	.....	86	2.36	1.07	203
October 11	do	78	87	2.36	1.07	207
November 27	do	.....	407	4.72	3.05	1,923

[a] Made by floats.

Daily gage height, in feet, of Pecos River at Carlsbad, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.23	1.89	2.81	1.3	3.87	1.85	1.2	3.9	1.19	1.28	1.42	2.19
2	1.23	1.88	2.8	1.29	3.77	1.4	1.18	4.15	1.2	1.58	1.44	2.21
3	1.23	1.88	2.79	1.27	1.65	1.1	1.18	4.77	1.55	1.61	1.44	2.26
4	1.23	1.88	2.4	1.26	1.4	1.12	1.18	3.57	1.24	1.58	1.48	2.31
5	1.23	1.88	1.4	1.28	1.4	1.7	1.19	3.45	1.48	1.55	1.44	2.16
6	1.23	1.88	2.12	1.3	1.67	2.9	1.19	3.25	1.49	1.15	1.44	2.09
7	1.23	1.88	2.5	1.28	4.35	4.05	1.18	2.9	1.84	1.11	1.27	2.02
8	1.23	1.87	2.8	1.29	4.2	4.2	1.18	2.57	3.0	1.08	1.2	1.92
9	1.23	1.87	3.13	1.29	3.95	4.05	1.91	2.4	3.0	1.08	1.45	1.86
10	1.23	1.87	3.18	1.3	1.55	3.78	1.77	2.15	2.58	1.08	1.47	1.84
11	1.23	1.87	3.2	1.3	1.65	3.47	1.68	2.51	2.09	1.08	1.77	1.82
12	1.23	1.87	4.19	1.31	2.35	1.69	1.55	2.62	1.9	1.09	1.98	1.81
13	1.23	1.87	4.06	1.32	1.35	2.68	1.36	2.72	1.62	1.1	1.98	1.87
14	1.23	1.85	3.96	1.32	1.29	3.57	1.2	2.27	1.55	1.11	1.96	1.89
15	1.23	1.85	3.78	1.32	1.26	3.82	1.17	2.13	1.04	1.12	1.75	1.88
16	1.23	1.85	3.55	1.62	1.26	3.7	1.15	2.07	1.03	1.12	1.75	1.88
17	1.23	1.85	3.29	1.64	1.27	3.41	1.14	2.12	1.01	1.13	1.75	1.86
18	1.24	1.84	2.93	1.9	1.28	3.12	1.1	1.9	.99	1.13	1.75	1.82
19	1.24	1.84	2.65	1.91	1.29	2.75	1.0	1.7	.99	1.13	1.74	1.8
20	1.24	1.83	2.35	1.96	2.05	2.35	.99	1.65	1.0	1.14	1.73	1.75
21	1.24	1.83	1.2	2.0	3.6	2.1	1.48	1.52	1.0	1.14	1.72	1.68
22	1.24	1.83	1.18	2.1	3.52	1.23	1.54	1.47	1.04	1.14	1.71	1.62
23	1.24	1.83	1.19	2.05	3.6	1.23	2.77	1.45	1.06	1.14	1.7	1.6
24	1.24	2.39	1.22	2.5	2.4	1.23	8.67	1.43	1.06	1.15	1.69	1.64
25	1.24	2.38	1.23	4.3	3.8	1.22	14.39	1.37	1.08	1.15	1.69	1.68
26	1.3	2.36	1.25	4.38	4.2	1.22	12.42	1.31	1.1	1.15	2.61	1.61
27	1.6	2.35	1.28	4.28	3.91	1.21	10.0	1.25	1.18	1.16	3.11	1.6
28	1.9	2.6	1.3	4.15	3.77	1.2	7.0	1.28	1.22	1.16	2.95	1.58
29	1.9	.....	1.28	4.1	3.6	1.2	5.35	1.25	1.12	1.17	2.67	1.56
30	1.9	.....	1.28	4.02	3.6	1.2	4.5	1.22	1.12	1.17	2.45	1.55
31	1.89	.....	1.28	.....	3.6	.....	4.15	1.2	.....	1.17	.....	1.54

Station rating table[a] for Pecos River at Carlsbad, N. Mex., from May 29, 1903, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
.30	22	2.00	870	3.70	2,470	6.80	10,520
.40	35	2.10	950	3.80	2,610	7.00	11,300
.50	50	2.20	1,030	3.90	2,750	7.20	12,080
.60	70	2.30	1,110	4.00	2,900	7.40	12,870
.70	95	2.40	1,190	4.20	3,220	7.60	13,670
.80	125	2.50	1,275	4.40	3,570	7.80	14,500
.90	165	2.60	1,360	4.60	3,940	8.00	15,400
1.00	210	2.70	1,445	4.80	4,350	8.20	16,360
1.10	255	2.80	1,530	5.00	4,800	8.40	17,320
1.20	305	2.90	1,615	5.20	5,290	8.60	18,280
1.30	360	3.00	1,700	5.40	5,820	8.80	19,240
1.40	420	3.10	1,790	5.60	6,380	9.00	20,200
1.50	490	3.20	1,890	5.80	6,970	9.20	21,160
1.60	560	3.30	1,990	6.00	7,600	9.40	22,120
1.70	635	3.40	2,100	6.20	8,290	9.60	23,080
1.80	710	3.50	2,220	6.40	9,020	9.80	24,040
1.90	790	3.60	2,340	6.60	9,760	10.00	25,000

[a] The above table is not strictly applicable June 13 to 22, 1903, owing to a considerable change in the high-water section during the flood of October, 1904.

The above table is based on two discharge measurements made during 1903, three made during 1904, and 16 made during 1905. It is fairly well defined between gage heights 1 foot and 16 feet. Below 1 foot it is subject to error as high as 20 per cent.

Estimated monthly discharge of Pecos River at Carlsbad, N. Mex., for 1903.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
June[a]	15,640	119	1,959	116,600
July	390	110	164	10,080
August	110	82	92.7	5,700
September	85	82	82.8	4,927
October	82	80	81.5	5,011
November	82	80	81.7	4,862
December	82	80	80.3	4,938
The period	.....	.....	.....	152,100

[a] See rating table footnote.

Estimated monthly discharge of Pecos River at Carlsbad, N. Mex., for 1904.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	161	80	99.4	6,112
February	141	90	94.0	5,407
March	137	22	85.0	5,226
April	90	88	88.1	5,242
May	110	0	84.3	5,183
June	122	75	91.4	5,439
July	107	95	96.5	5,934
August	420	104	132	8,116
September	224	107	152	9,045
October 1-2; 11-31	30,200	1,190	4,269	194,800
November	1,530	255	695	41,360
December 1-24	766	295	521	24,800
The period				316,700

Estimated monthly discharge of Pecos River at Carlsbad, N. Mex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	790	322	392	24,100
February	1,360	734	838	46,540
March	3,204	295	1,266	77,840
April	3,534	338	1,079	64,210
May	3,480	338	1,574	96,780
June	3,220	255	1,256	74,740
July	47,600	206	5,236	321,900
August	4,287	305	1,164	71,570
September	1,700	206	486	28,920
October	568	246	308	18,940
November	1,800	305	739	43,970
December	1,118	518	742	45,620
The year	47,600	206	1,257	915,100

PECOS RIVER AND MARGUERETTA FLUME NEAR PECOS, TEX.

This station was established January 1, 1898, by Thomas U. Taylor, and is located about 6 miles above Pecos, Tex., at the flume of the Barstow Irrigation Company (old Margueretta Canal Company). The canal diverts the water from Pecos River 3 miles above the flume from the west side of the river. The water, except about 10 second-feet taken by the West Valley ditch, is carried across to the east side by a timber flume supported on pile bents.

The channel is straight for 300 feet above and 100 feet below the measuring section. The river bed is sandy and shifting. In floods such as those of October, 1904, and July, 1905, a large volume of water passes down the West Valley, west of the canal. This water spreads over the country from the flume to Pecos and can not be measured with any accuracy.

Discharge measurements are made from a cable about 200 yards below the flume. The initial point for soundings is the post supporting the cable on the west bank. Measurements taken in the flume at the east end show the amount of water used for irrigation on the east side of the river.

The gage is a staff which is nailed to one of the piles under the upstream side of the flume. The gage in the flume is at the east end and has its zero at the bottom of the flume. During 1905 both gages were read by Lawrence Vauter, gate keeper for the irrigation company. Bench marks were established as follows: (1) The top of the west abutment on the north side of the flume, marked "U. S. G. S. B. M. 21.70;" elevation, 21.70 feet. (2) On the stone wall on the south side of the canal, under the window of the gate keeper's house, marked "U. S. G. S. B. M. 20.95;" elevation, 20.95 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann = Annual Report; WS = Water-Supply Paper):

Pecos River near Pecos, Tex.

Description: WS 28, p 119; 37, p 285; 50, p 358; 66, p 76; 84, pp 168–169; 99, p 355; 132, pp 104–105.
Discharge: WS 28, p 130; 37, p 385; 50, p 359; 66, p 77; 84, p 169; 99, p 356; 132, p 105.
Discharge, monthly: WS 84, p 172; 99, p 358; 132, p 109.
Discharge, yearly: Ann 20, iv, p 57.
Gage heights: WS 28, p 125; 37, p 286; 50, pp 360–361; 66, p 77; 84, p 170; 99, p 356; 132, p 106.
Rating tables: WS 84, p 171; 99, p 357; 132, p 108.

Marguerette flume near Pecos, Tex.

Description: WS 84, pp 168–169; 99, p 355; 132, pp 104–105.
Discharge: WS 50, p 360; 66, p 77; 84, p 169; 132, p 105.
Gage heights: WS 50, p 361; 84, p 171; 99, p 357; 132, p 107.
Rating table: WS 132, p 108.

Discharge measurements of Pecos River near Pecos, Tex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
May 10	Murphy and Giles	144	695	3.55	6.10	2,470
July 11	J. M. Giles	81	105	1.81	1.27	189
July 11	.....do	81	103	1.72	1.25	177
July 14	E. Patterson	99	150	2.50	2.20	376
August 11	J. M. Giles	172	496	2.66	3.25	1,318
August 12	.....do	170	463	2.82	3.20	1,304
August 31	E. Patterson	96	205	2.10	1.20	432
September 13	.....do	90	359	2.49	2.50	895
September 14	.....do	89	326	2.39	2.20	779
October 6	J. M. Giles	138	254	1.81	1.40	459
October 7	.....do	138	263	1.95	1.50	51[illegible]
October 16	E. Patterson	82	92	1.45	0.20	[illegible]
October 20	.....do	80	88	1.30	0.10	[illegible]
November 8	.....do	.....	184	1.87	1.00	[illegible]
November 16	Grover and Giles	.....	413	2.12	2.22	[illegible]
November 17	J. M. Giles	.....	398	2.24	2.20	[illegible]
December 6	E. Patterson	169	444	2.37	2.80	1,[illegible]
(a)	J. M. Giles	.....	1,304	4.92	8.00	6,[illegible]
(a)	.....do	.....	2,024	6.32	12.00	12,7[illegible]
(a)	.....do	.....	3,140	7.91	18.00	24,8[illegible]

[a] Computed from slope measurement, using Kutter's formula.

Daily gage height, in feet, of Pecos River, near Pecos, Tex., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	2.0	2.5	4.3	2.1	5.0	5.5	2.5	7.6	1.4	.....	0.2	2.8
.....	2.0	2.5	4.3	2.0	4.3	5.0	1.5	6.2	.....	.....	.2	2.6
.....	2.1	2.5	4.3	1.9	3.0	3.9	1.5	5.65	.....	.....	.2	2.4
.....	2.1	2.5	4.3	1.9	3.0	2.9	1.5	6.15	.....	.....	.4	2.3
.....	2.1	2.5	4.1	1.9	3.0	2.0	1.5	5.85	.....	.....	.9	2.0
.....	2.1	2.5	4.1	1.9	2.8	1.9	1.5	4.9	.....	1.4	.9	1.9
.....	2.1	2.9	4.1	1.6	2.6	3.1	1.4	4.5	.....	1.5	1.0	2.0
.....	2.1	3.0	4.1	1.6	2.6	4.0	1.4	4.0	.....	1.4	1.1	2.3
.....	2.1	3.1	4.1	1.5	6.0	6.0	1.4	3.7	1.4	.9	1.0	2.4
.....	2.1	3.2	4.1	1.4	6.1	6.2	1.2	3.6	4.5	.3	1.0	2.4
.....	2.1	3.2	4.6	1.4	6.0	6.0	2.5	3.5	3.5	.3	1.0	2.4
.....	2.1	3.1	4.6	1.4	3.0	5.8	2.3	3.2	3.2	.2	1.1	2.4
.....	2.1	3.1	5.9	1.3	2.6	5.9	2.2	3.4	2.6	.2	1.4	2.1
.....	2.1	3.1	6.6	1.1	3.6	4.9	1.9	3.6	2.2	.2	2.4	2.0
.....	2.1	3.1	6.6	1.1	3.2	3.2	1.5	3.5	2.1	.2	2.3	2.0
.....	2.1	3.1	6.5	1.1	2.5	5.0	1.4	3.0	2.1	.2	2.2	2.0
.....	2.1	3.1	6.2	1.1	2.0	5.9	1.4	3.0	.....	.2	2.2	2.0
.....	2.1	3.1	6.1	1.6	1.9	6.0	1.0	2.9	.....	.2	1.8	2.1
.....	2.1	3.1	6.0	1.7	1.5	5.6	.9	2.9	.....	.2	1.8	2.1
.....	2.1	3.0	5.0	1.8	1.0	4.9	.9	2.8	.....	.1	1.8	2.0
.....	2.1	3.0	5.1	2.0	1.0	4.0	.9	2.8	.....	.1	1.8	2.0
.....	2.0	3.0	5.1	2.1	2.0	3.8	.9	2.8	.....	.1	1.8	1.9
.....	2.0	3.0	4.2	2.1	4.9	2.9	1.0	2.6	.....	.2	1.8	1.8
.....	2.0	3.0	3.9	3.0	5.0	2.8	4.9	2.0	.....	.3	1.7	1.8
.....	2.0	3.0	2.1	3.1	5.1	1.8	7.2	1.6	.....	.3	1.6	1.8
.....	2.0	4.2	2.1	4.0	4.0	1.6	9.4	1.2	.....	.3	1.6	1.8
.....	2.0	4.5	2.1	5.5	5.6	1.5	13.7	1.2	.....	.3	1.6	1.8
.....	2.0	4.4	2.1	6.5	6.0	1.5	18.3	1.2	.....	.2	3.1	1.8
.....	2.0	.....	2.1	6.6	5.6	1.5	17.2	1.2	.....	.2	3.5	1.8
.....	2.0	.....	2.1	6.0	5.5	4.5	13.2	1.2	.....	.2	3.4	1.7
.....	2.0	.....	2.0	.....	5.5	.....	10.2	1.2	.....	.2	.....	1.7

ion rating table for Pecos River, near Pecos, Tex., from January 1 to July 24, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.90	140	2.20	375	3.50	835	4.80	1,535
1.00	150	2.30	400	3.60	880	4.90	1,600
1.10	160	2.40	430	3.70	925	5.00	1,665
1.20	170	2.50	460	3.80	975	5.20	1,795
1.30	185	2.60	490	3.90	1,025	5.40	1,935
1.40	200	2.70	525	4.00	1,080	5.60	2,075
1.50	220	2.80	560	4.10	1,135	5.80	2,220
1.60	240	2.90	595	4.20	1,190	6.00	2,370
1.70	260	3.00	630	4.30	1,245	6.20	2,530
1.80	280	3.10	670	4.40	1,300	6.40	2,690
1.90	300	3.20	710	4.50	1,355	6.60	2,850
2.00	325	3.30	750	4.60	1,415		
2.10	350	3.40	790	4.70	1,475		

ove table is based on four discharge measurements made during 1905. It is no twell defined.

Station rating table for Pecos River, near Pecos, Tex., from July 25 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.10	115	1.30	465	2.50	955	3.70	1,640
.20	135	1.40	500	2.60	1,000	3.80	1,715
.30	155	1.50	535	2.70	1,050	3.90	1,790
.40	180	1.60	570	2.80	1,100	4.00	1,865
.50	205	1.70	610	2.90	1,150	4.20	2,030
.60	235	1.80	650	3.00	1,200	4.40	2,210
.70	265	1.90	690	3.10	1,250	4.60	2,390
.80	295	2.00	730	3.20	1,305	4.80	2,580
.90	325	2.10	775	3.30	1,365	5.00	2,780
1.00	360	2.20	820	3.40	1,430		
1.10	395	2.30	865	3.50	1,500		
1.20	430	2.40	910	3.60	1,570		

The above table is based on 13 discharge measurements made during 1905. It is well defined betwe gage heights 0.1 foot and 3.2 feet. Above gage height 3.2 feet it is based on three slope measurement

Estimated monthly discharge of Pecos River, near Pecos, Tex., for 1905.

Month.	Discharge in second-feet.			Total i acre-fe
	Maximum.	Minimum.	Mean.	
January	350	325	340	20
February	1,355	465	682	37
March	2,850	325	1,372	84
April	2,850	160	596	3
May	2,470	150	1,091	6
June	2,530	220	1,243	7
July	25,500	140	3,548	21
August	5,800	430	1,664	10
September[a]				
October 6–31	530	115	189	
November	1,500	130	592	3
December	1,100	615	764	4
The period				7

[a] No estimate.

NOTE.—For discharge of flume of Barstow Irrigation Company see following pages.

measurements of flume of Barstow Irrigation Company near Pecos, Tex., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	Murphy and Giles	20.5	33	7.83	1.70	257
.....	J. M. Giles	20.5	17.4	5.86	1.10	102
.....	do	20.5	17.4	5.91	1.10	103
.....	E. Patterson	20.5	18.5	6.21	1.15	115
r 14	do	20.5	26.6	7.07	1.40	188
.....	J. M. Giles	20.5	29	7.62	1.60	219
.....	do	20.5	27	7.57	1.50	202
6.....	E. Patterson	20.5	24	7.11	1.30	168
0.....	do	20.5	23	7.01	1.25	158
r 8	do	20.5	27	7.30	1.40	194
r 8[a]	do	20.5	35	4.25	1.70	148
r 16	J. M. Giles	20.5	26.6	4.97	1.30	132
r 16[a]	do	20.5	14	2.29	.80	32
6....	E. Patterson	20.5	13.3	1.57	.65	21

[a] At lower end of flume.

ge height, in feet, of flume of Barstow Irrigation Company near Pecos, Tex., for 1905.

ay.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	1.0	1.8	1.8	1.6	.....	.....	.....	1.3	0.8
.....	.....	1.0	1.8	1.8	1.0	.....	.....	.....	1.3	.8
.....	.....	1.0	1.8	1.6	1.0	.....	.....	.....	1.3	.8
.....	.....	1.0	1.8	1.6	1.0	.....	.....	.....	1.3	.8
.....	.....	1.0	1.8	1.8	1.0	.....	.....	.....	1.5	.8
.....	.....	1.0	1.8	1.8	1.0	.....	.....	1.6	1.5	.8
.....	.....	.9	1.8	1.9	1.0	.....	.....	1.5	1.5	.7
.....	.....	1.0	1.8	1.9	1.0	.....	.....	1.4	1.5	.7
.....	.....	1.1	1.8	1.9	1.0	.....	.....	1.4	1.5	.7
.....	.....	1.3	1.8	1.9	1.1	.....	1.5	1.4	1.5	.7
.....	.....	1.4	1.8	1.9	1.3	.....	1.5	1.3	1.5	.7
.....	1.1	1.6	1.9	1.9	1.3	.....	1.5	1.3	1.5	.7
.....	1.1	1.8	1.9	1.6	1.05	.....	1.5	1.3	1.5	.7
.....	1.1	1.8	1.8	1.6	1.5	.....	1.4	1.3	1.5	.6
.....	1.1	1.8	1.8	1.6	1.6	.....	1.4	1.3	1.3	.6
.....	1.1	1.9	1.8	1.6	1.6	.....	1.4	1.3	1.3	.6
.....	1.1	1.9	1.8	1.6	1.6	.....	.....	1.3	.8	.6
.....	1.1	1.8	1.8	1.6	1.6	.....	.....	1.3	.8	.6
.....	1.1	1.8	1.8	1.6	1.4	.....	.....	1.3	.8	.6
.....	1.2	1.8	1.8	1.8	1.3	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.8	1.8	1.3	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.9	1.7	1.3	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.8	1.7	1.5	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.8	1.7	1.6	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.8	1.7	1.8	.....	.....	1.4	.8	.6
.....	1.3	1.8	1.8	1.7	1.6	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.9	1.7	2.4	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.8	1.7	2.65	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.8	1.7	2.35	.....	.....	1.3	.8	.6
.....	1.3	1.8	1.8	2.0	1.25	.....	.....	1.3	.8	.6
.....	1.3	.....	1.8	.....	.6	.....	.....	1.3	.....	.6

November 1-16 water was being wasted from flume into river; hence gage heights at upper
ne did *not represent flow accurately.*

Station rating table for flume of the Barstow Irrigation Company near Pecos, Tex., from March 12 to November 16, 1905.[a]

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.60	10	1.00	80	1.40	179	1.80	285
0.70	22	1.10	103	1.50	205	1.90	312
0.80	38	1.20	128	1.60	231	2.00	340
0.90	57	1.30	153	1.70	258		

[a] Not strictly applicable November 1–16, during which time water was being wasted from flume into river; hence gage heights at upper end of flume did not represent flow accurately.

The above table is based on 13 discharge measurements made during 1905. It is fairly well defined between gage heights 1.1 feet and 1.7 feet.

Estimated monthly discharge of flume of Barstow Irrigation Company near Pecos, Tex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March 12–31	153	103	132	5,237
April	312	57	216	12,850
May	312	285	288	17,710
June	340	231	269	16,010
July	522	10	182	11,190
September 10–16	205	179	194	2,694
October 6–31	231	153	162	8,355
The period				74,050

PECOS RIVER NEAR MOORHEAD, TEX.

This station was established by the International (Water) Boundary Commission in April, 1900. It is near Moorhead, immediately above the high bridge of the Southern Pacific Railroad.

The station is in the bottom of a canyon about 300 feet deep. The river is straight for a mile or more both above and below the station. Both banks are of rock, but the bottom of the stream is mud. The river here consists of a series of pools connected by rapids. The best pool was chosen for the station.

Discharge measurements are made by means of a cable, car, and tagged wire. The initial point for soundings is the cable support on the left bank.

The gage is a scantling bolted to one of the piers of the bridge. Its painted face is read from the top of the cliff with the aid of field glasses. The highest known flood occurred April 6, 1900, about two weeks before this gage was established. The water marks showed that it reached 35.75 feet on the gage. The range between high and low water is 35 feet. The bench mark is a cross cut on solid rock above a spring about 600 feet above the bridge; elevation, 27.08 above the datum of the gage.

The observations during 1905 have been made under the direction of the United States section of the International (Water) Boundary Commission. The hydrographer is E. E. Winter and the gage reader is the section foreman for the railroad.

ontained in the following Water-Supply Papers

l; 132, p 109.
p 352–353; 132, pp 109–111.

; 132, p 114.
54; 132, p 112.

River near Moorhead, Tex., in 1905.

	Area of section.	Mean velocity.	Gage height.	Discharge.
	Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
.....	773	0.98	1.75	758
.....	774	.95	1.75	735
.....	762	.80	1.65	611
.....	756	.80	1.6	604
.....	755	.74	1.5	557
.....	724	.73	1.5	531
.....	726	.73	1.5	532
.....	762	.91	1.7	694
.....	760	.93	1.75	710
.....	775	1.02	2.0	787
.....	790	1.03	2.0	811
.....	807	1.07	2.2	861
.....	782	1.01	2.1	791
.....	795	1.01	2.05	806
.....	924	1.97	3.4	1,817
.....	849	1.39	2.7	1,180
.....	893	1.72	3.2	1,532
.....	1,004	2.20	3.7	2,212
.....	824	1.26	2.4	1,041
.....	770	1.03	2.1	795
.....	861	1.18	2.5	1,018
.....	821	.98	2.0	805
.....	827	.93	1.9	772
.....	790	.90	1.7	709
.....	785	.89	1.6	702
.....	921	1.47	3.0	1,356
.....	845	1.01	2.2	854
.....	1,023	2.24	3.5	2,288
.....	1,000	2.16	3.4	2,155
.....	981	1.62	3.1	1,594
.....	1,010	2.02	3.4	2,040
.....	883	1.12	2.2	991
.....	950	1.72	2.8	1,633
.....	883	1.13	2.2	999
.....	1,011	1.61	3.2	1,623
.....	948	1.23	2.6	1,166
.....	857	.84	1.9	720
.....	1,037	2.24	3.5	2,324
.....	1,004	2.07	3.4	2,078
.....	1,010	2.00	3.3	2,025
.....	898	1.17	2.2	1,050
.....	1,015	1.44	3.1	1,459
.....	907	1.04	2.1	942
.....	867	.85	2.0	734
.....	874	.85	2.0	739

Discharge measurements of Pecos River near Moorhead, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Dis-charg
		Square feet.	*Feet per second.*	*Feet.*	*Secon feet*
July 28	E. E. Winter	768	0.83	1.65	
August 6	do	1,104	3.20	4.3	
August 10	do	1,208	3.92	5.2	
August 15	do	956	2.57	3.35	
August 20	do	899	1.69	2.8	
August 24	do	906	1.51	2.6	
August 30	do	894	1.33	2.4	
September 6	do	782	.96	1.9	
September 11	do	775	.89	1.8	
September 14	do	785	.93	2.0	
September 22	do	803	1.08	2.2	
September 25	do	774	.96	2.0	
September 28	do	791	.97	1.9	
October 3	do	774	.81	1.7	
October 7	do	793	.91	1.9	
October 10	do	803	.94	1.9	
October 15	do	780	.84	1.75	
October 20	do	774	.78	1.6	
October 24	do	729	.73	1.5	
October 29	do	724	.71	1.5	
November 3	do	704	.72	1.4	
November 7	do	707	.71	1.4	
November 10	do	711	.71	1.4	
November 14	do	743	.86	1.7	
November 18	do	716	.75	1.6	
November 22	do	792	1.12	2.2	
November 25	do	783	1.12	2.2	
December 2	H. F. Collins	772	1.15	2.0	
December 8	do	827	1.53	2.4	
December 13	do	831	1.51	2.4	
December 22	do	805	1.52	2.3	
December 25	do	788	1.44	2.3	
December 29	do	783	1.45	2.2	

Daily gage height, in feet, of Pecos River near Moorhead, Tex., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.75	1.6	2.05	6.7	2.6	3.0	2.2	3.5	2.4	1.8	1.4	2.0
.....	1.75	1.65	2.1	3.75	2.6	3.15	2.2	3.55	2.35	1.7	1.4	2.0
.....	1.75	1.7	2.15	3.0	3.45	3.2	2.3	3.8	2.45	1.7	1.4	2.2
.....	1.75	1.7	2.2	2.5	3.5	3.2	2.65	3.9	2.45	1.8	1.4	2.65
.....	1.75	1.7	2.25	2.3	3.55	3.2	2.35	4.1	2.25	1.8	1.35	2.7
.....	1.75	1.75	2.3	2.2	3.6	3.2	2.3	4.15	1.95	1.85	1.35	2.6
.....	1.75	1.75	2.4	2.1	3.55	3.2	3.1	4.55	1.9	1.9	1.4	2.55
.....	1.7	1.8	3.45	2.0	3.4	3.05	4.1	4.85	1.95	1.9	1.4	2.4
.....	1.7	1.85	2.75	2.0	3.35	2.65	4.4	4.9	1.9	2.0	1.4	2.4
.....	1.7	1.9	2.6	2.0	3.2	2.05	3.55	5.1	1.9	1.95	1.4	2.45
.....	1.65	2.0	2.65	2.0	3.15	2.0	2.7	5.5	2.0	1.8	1.6	2.5
.....	1.65	2.0	2.6	1.9	3.1	1.9	2.35	5.6	1.8	1.8	1.7	2.45
.....	1.65	2.0	2.6	1.9	3.1	1.75	2.1	5.4	1.9	1.75	1.7	2.4
.....	1.6	2.0	2.6	1.85	3.2	1.7	2.0	4.9	2.05	1.75	1.8	2.4
.....	1.55	2.0	5.2	1.8	3.2	2.15	2.0	3.6	2.65	1.75	1.8	2.4
.....	1.5	2.0	3.25	1.7	3.4	3.0	2.0	3.5	2.9	1.75	1.8	2.3
.....	1.5	2.1	3.2	1.7	3.3	3.45	2.0	3.25	2.75	1.7	1.8	2.3
.....	1.5	2.15	3.35	1.7	3.15	3.5	2.0	3.0	2.4	1.65	1.7	2.3
.....	1.45	2.2	3.55	1.7	2.8	3.5	2.0	2.8	2.3	1.65	2.0	2.3
.....	1.45	2.2	3.7	1.6	2.25	3.5	2.0	2.8	2.3	1.6	2.1	2.3
.....	1.45	2.2	3.2	1.6	2.35	3.4	2.1	2.8	2.2	1.55	2.2	2.3
.....	1.45	2.1	2.85	1.6	2.75	3.4	2.0	2.7	2.2	1.5	2.2	2.3
.....	1.45	2.1	2.65	8.95	2.7	3.4	1.95	2.6	2.2	1.5	2.2	2.3
.....	1.5	2.1	2.45	3.05	2.8	3.2	1.7	2.6	2.2	1.5	2.2	2.3
.....	1.5	2.05	2.25	2.95	2.85	3.05	1.7	2.6	2.05	1.5	2.2	2.3
.....	1.5	2.05	2.7	2.7	2.55	2.9	1.6	2.5	2.0	1.5	2.1	2.3
.....	1.5	2.05	2.7	2.25	2.4	2.65	1.65	2.5	2.0	1.45	2.1	2.3
.....	1.5	2.0	2.5	2.2	2.4	2.95	1.65	2.5	1.95	1.45	2.1	2.2
.....	1.55	.....	2.25	3.2	2.25	6.05	1.75	2.45	1.95	1.5	2.1	2.2
.....	1.55	.....	2.05	2.65	2.6	2.25	3.1	2.4	1.9	1.45	2.0	2.1
.....	1.45	.....	2.0	.....	2.9	.....	3.2	2.4	.....	1.45	.....	2.1

Daily discharge, in second-feet, of Pecos River near Moorhead, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	I
1	700	625	805	8,950	1,100	1,700	1,050	2,090	1,190	700	470	
2	730	660	845	2,070	1,100	1,660	a1,050	2,180	1,140	630	490	
3	a 760	a 695	880	1,320	a2,220	a1,620	1,095	2,630	1,230	a 630	a 510	
4	750	695	920	a1,020	2,290	1,620	1,250	2,810	1,230	675	510	
5	745	695	955	935	2,360	1,620	1,115	3,170	1,060	675	490	
6	740	710	990	890	2,430	1,620	1,095	a3,260	a 800	695	490	
7	a 735	a 710	1,065	845	2,360	1,620	a1,460	3,860	750	a 720	a 505	
8	670	725	a1,855	a 805	a2,150	1,500	2,460	4,270	780	730	505	a
9	670	740	1,225	805	2,060	a1,200	2,760	4,330	750	805	505	
10	670	755	1,090	805	1,780	810	1,910	a4,600	750	a 785	a 505	
11	610	a 785	a1,135	805	a1,680	780	1,250	5,330	a 790	685	590	
12	a 610	790	1,110	a 770	1,590	a 720	1,070	5,530	690	685	635	
13	610	795	1,110	770	1,590	640	a 940	5,260	710	650	635	a
14	605	800	1,110	755	1,740	620	850	4,580	a 760	650	a 680	
15	580	a 810	5,220	740	1,740	800	820	a2,810	1,320	a 650	660	
16	a 560	810	a1,560	710	a2,040	1,740	790	2,710	1,570	650	645	
17	560	835	1,530	a 710	1,950	a2,260	760	2,390	1,420	625	630	
18	560	850	1,735	715	1,820	2,280	a 735	1,860	1,070	600	a 575	
19	540	860	2,005	720	1,510	2,240	735	1,520	970	600	760	
20	a 530	a 860	a2,210	700	a1,040	2,210	740	a1,520	970	a 575	820	
21	520	860	1,760	a 700	1,150	a2,080	800	1,520	870	550	880	
22	515	790	1,445	700	1,580	2,080	740	1,440	a 870	530	a 885	a
23	510	a 790	1,265	14,570	1,520	2,060	a 725	1,370	870	530	880	
24	a 530	805	a1,085	1,390	a1,630	a1,930	650	a1,370	870	a 530	880	
25	530	790	915	a1,320	1,690	1,780	650	1,370	a 770	530	a 875	a
26	530	a 805	1,310	1,170	1,370	1,630	625	1,280	770	525	825	
27	530	805	1,310	885	1,210	1,380	640	1,280	800	500	825	
28	530	775	1,130	a 855	1,210	a1,680	a 640	1,280	a 800	495	825	
29	a 550	.....	a 915	1,480	a1,050	7,300	670	1,230	800	a 515	825	a
30	550	.....	755	1,140	1,420	1,040	1,460	a1,190	765	490	775	
31	510	.....	715	.....	1,740	.....	1,560	1,190	.....	490	.....	

a Meter measurements.

Estimated monthly discharge of Pecos River, near Moorhead, Tex., for 1905.

Month.	Discharge in second-feet.			Total acre-f
	Maximum.	Minimum.	Mean.	
January	760	510	605	3
February	860	625	772	4
March	5,220	715	1,354	8
April	14,570	700	1,668	9
May	2,430	1,040	1,681	10
June	7,300	620	1,745	10
July	2,760	625	1,068	6
August	5,530	1,190	2,617	16
September	1,570	690	938	5
October	805	490	616	3
November	885	470	670	3
December	1,550	830	1,220	7
The year	14,570	470	1,246	90

GALLINAS RIVER NEAR LAS VEGAS, N. MEX.

This station was established August 13, 1903, by E. G. Marsh. It is located at Las gas Hot Springs, 6 miles above Las Vegas, N. Mex. The establishment of this station s primarily for the purpose of determining the amount of water available for diversion l storage in the San Guyjuella basin about 6 miles northwest of Las Vegas.

The channel is straight for 50 feet above and 100 feet below the station. The bed is mposed of bowlders with a loose deposit of sand and gravel during low water. The right nk is a vertical wall protecting the power house. The left bank is a vertical wall com-sed of bowlders embedded in binding material. There is but one channel at all stages. e velocity is moderate at low water and very swift during high water.

Discharge measurements are made from a single-span wooden bridge at the power house ring high water; at low water discharge measurements are made at the same section by ding.

The original gage was bolted to the masonry wall on the right bank which protects Hot rings Nos. 16 and 17. These springs are located about 300 feet above the power house d bridge from which discharge measurements are made. The gage was washed out by e flood of September 29, 1904, and was replaced by a similar rod October 19, 1904. The ro of the new rod is 0.71 foot lower than the zero of the old rod. During 1905 the gage is read twice each day by William Prager, except when rapid fluctuations make more quent observations necessary. The bench mark is a leaded bolt in a granite outcropping the right (south) bank of the river 200 feet above the gage rod; elevation, 19.17 feet ove the datum of the new gage. The 7-foot mark on this gage is identical with the upper rface of the masonry wall to which it is attached.

Information in regard to this station is contained in the following Water-Supply Papers the United States Geological Survey:

escription: 99, p 253; 132, pp 116–117.
ischarge: 99, p 254; 132, p 117.
age heights: 99, p 254; 132, p 118.

Discharge measurements of Gallinas River near Las Vegas, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
February 5 [a]	R. I. Meeker	17	20	0.45	1.80	9
April 27 [b]	do	50	78	4.19	3.10	327
May 27 [b]	Meeker and Murphy	42	54	3.02	2.65	163
July 1 [a]	R. I. Meeker	24	23	1.04	1.90	24
August 2 [a]	do	24	25	1.20	2.00	30

[a] Made by wading under foot bridge. [b] Made from Hot Springs bridge.

Daily gage height, in feet, of Gallinas River near Las Vegas, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.8	1.8	2.2	2.3	3.1	2.5	1.9	2.05	1.8	1.8	1.6	2.0
2	1.8	1.8	2.8	2.3	3.2	2.45	1.9	2.1	1.8	1.8	1.6	1.8
3	1.8	1.8	2.6	2.4	3.1	2.4	1.9	1.95	1.8	1.8	1.6	1.8
4	1.8	1.8	2.45	2.5	2.95	2.45	1.8	1.9	1.85	1.8	1.6	2.0
5	1.8	1.8	2.5	2.5	2.85	2.4	1.8	2.13	1.8	1.7	1.6	2.0
6	1.8	1.8	2.6	2.5	2.8	2.3	1.8	2.1	1.8	1.6	1.6	1.8
7	1.8	1.8	2.6	2.5	2.75	2.3	1.8	2.3	1.85	1.6	1.6	1.8
8	1.8	1.8	2.5	2.6	2.8	2.65	1.8	2.2	1.8	1.6	1.6	1.8
9	1.8	1.8	2.5	2.6	2.95	2.5	1.8	2.1	1.85	1.65	1.6	1.8
10	1.8	1.8	2.5	2.6	2.85	2.45	1.8	2.1	1.9	1.6	1.6	1.8
11	1.8	1.8	2.4	2.6	2.8	2.4	1.8	2.1	1.8	1.6	1.6	1.8
12	1.8	1.8	2.3	2.6	2.75	2.3	1.8	2.1	1.8	1.6	1.6	2.0
13	1.8	1.8	2.3	2.55	2.75	2.3	1.8	2.05	1.8	1.6	1.6	2.0
14	1.8	1.8	2.3	2.5	2.7	2.25	1.8	2.0	1.8	1.6	1.6	1.8
15	1.8	1.85	2.4	2.5	2.7	2.2	1.8	1.9	1.8	1.6	1.6	1.8
16	1.8	1.8	2.4	2.5	2.75	2.15	1.8	1.9	1.8	1.6	1.8	1.8
17	1.8	1.8	2.4	2.5	2.8	2.1	1.8	1.9	1.8	1.6	1.75	1.8
18	1.8	1.8	2.3	2.5	2.9	2.1	1.8	1.9	1.8	1.6	1.6	1.8
19	1.8	1.85	2.3	2.5	2.8	2.1	1.8	1.9	1.8	1.6	1.8	1.8
20	1.8	1.8	2.3	2.5	2.8	2.0	1.8	1.9	1.8	1.6	1.8	1.8
21	1.8	1.85	2.2	2.5	2.8	2.05	1.8	1.8	1.7	1.6	1.8	1.8
22	1.8	2.0	2.2	2.5	2.8	2.0	2.0	1.8	1.7	1.6	2.0	1.8
23	1.8	2.3	2.2	2.9	2.7	2.0	2.01	1.8	1.7	1.6	2.35	1.8
24	1.8	2.7	2.2	3.2	2.65	2.0	2.0	1.8	1.7	1.6	2.05	1.8
25	1.8	2.65	2.2	3.15	2.6	1.95	1.9	1.8	1.8	1.6	2.0	1.8
26	1.8	2.7	2.25	3.05	2.6	1.9	1.9	1.8	2.2	1.6	2.0	1
27	1.8	2.7	2.35	3.1	2.6	1.9	1.8	1.8	1.9	1.6	3.05	1
28	1.8	2.2	2.4	3.2	2.55	1.9	1.8	1.8	1.9	1.6	2.8	1
29	1.8	.....	2.3	3.1	2.5	1.9	1.8	1.8	1.85	1.6	2.35	1
30	1.8	.....	2.25	3.0	2.5	1.9	1.8	1.8	1.8	1.6	2.2	1
31	1.8	.....	2.25	.....	2.5	.....	2.3	1.8	.....	1.6	.....	1

Station rating table for Gallinas River near Las Vegas, N. Mex., from October 8, 1904, December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.60	2	2.10	42	2.60	148	3.10	330
1.70	6	2.20	57	2.70	178	3.20	380
1.80	12	2.30	75	2.80	210		
1.90	20	2.40	97	2.90	245		
2.00	30	2.50	121	3.00	285		

The above table is based on five discharge measurements made during 1905. It is well defined.

Estimated monthly discharge of Gallinas River near Las Vegas, N. Mex., for 1904–1905.

[Drainage area, 90 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
1904.						
October 8–31	210	2	32.6	1,551	0.362	0.323
November	57	4	13.7	815	.152	.170
December	20	2	10.2	627	.113	.130
1905.						
January	12	12	12.0	738	.133	.153
February	178	12	40.1	2,227	.446	.464
March	210	57	93.3	5,737	1.04	.120
April	380	75	177	10,530	1.97	2.20
May	380	121	206	12,670	2.29	2.64
June	163	20	63.4	3,773	.704	.786
July	75	12	17.1	1,051	.190	.219
August	75	12	26.7	1,642	.297	.342
September	57	6	14.0	833	.156	.174
October	12	2	3.5	215	.039	.045
November	308	2	32.1	1,910	.357	.398
December	30	12	18.7	1,150	.208	.240
The year	380	2	57.8	42,480	.652	7.78

NOTE.—From January 1 to September 27, 1904, the discharge was practically nothing, the water not being sufficient for current meter measurements. Discharge from September 29 to October 7, 1904, inclusive, was 16,570 acre-feet. Taken from G. B. Monk's report of floods in northern New Mexico in 1904. See also Water-Supply Paper No 147, Destructive Floods in United States in 1904, by E. C. Murphy.

HONDO RIVER AT ROSWELL, N. MEX.

This station was established April 25, 1903, by W. M. Reed. It is located at the bridge at the intersection of Main and Vegas streets, Roswell, N. Mex.

The channel is nearly straight for 50 feet above and 450 feet below the bridge and has a width at ordinary high stages of 40 feet. The current has a moderate velocity. Both banks are low and overgrown with weeds, but are not liable to overflow. The bed of the stream is sandy loam, fairly permanent, and free from vegetation. There is but one channel at all stages.

Discharge measurements are made from the highway bridge. The initial point for soundings is a zero marked on the east stringer at the north end of the bridge.

In July, 1905, the channel of the river was widened at the street crossing and the original gage was torn out by the workman. August 8, 1905, a new inclined gage was placed on the left bank at the upstream side of bridge. It consists of a timber spiked to stakes driven in the bank, and the upper end is bolted to a sill of the bridge. During 1905 the gage was read by members of the Geological Survey office force at Roswell. Bench marks were established as follows: (1) The top of eyebar on west side of bridge; elevation, 7.45 feet. (2) The southeast corner of the cement sidewalk 25 feet northwest of bridge; elevation, 7.82 feet. (3) The top step near stone column at the entrance to the office of the Pecos Valley Lumber Company; elevation, 3.10 feet. Elevations refer to the datum of the gage.

Information in regard to this station is contained in the following Water-Supply Papers the United States Geological Survey:

Description: 99, pp 361–362; 132, pp 118–119.
Discharge: 99, p 362; 132, p 119.
Gage heights: 99, p 362; 132, p 119.

Discharge measurements of Hondo River at Roswell, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 13	J. M. Giles	11	6	1.07	0.10	6
April 25	E. Patterson	26	93	3.71	5.20	345
April 25	do	27	102	3.74	5.60	383
April 25	W. A. Wilson		98	4.36	6.00	429
April 26	E. Patterson	26	84	3.62	4.80	306
April 26	do	24	77	3.53	4.50	271
April 26	do	26	88	4.03	4.95	356
April 27	do	24	69	3.00	4.20	206
May 13	do	14	27	2.92	1.75	78
May 17	J. M. Giles	14	15	2.51	1.10	38
July 24	E. Patterson	30	131	4.20	5.00	551
July 24	do	24	82	3.79	3.20	311
July 25	do	30	134	4.09	5.00	550
July 26	do	32	159	4.27	5.90	682
July 26	do	32	156	4.15	5.60	648
July 27	do	30	125	3.95	4.75	495
July 28	do	27	110	3.72	4.00	409
July 31	do	22	49	3.41	2.00	166
August 2	J. M. Giles	24	65	3.59	2.50	234
August 2	do	20	54	3.10	1.85	169
August 8	E. Patterson	21	50	3.83	2.10	192
August 15	do	19	32	3.61	1.50	116
August 26	do	13	10	2.18	− .10	22
August 28	do	4	2	.64	−1.10	1.
September 8	do	8	3	.93	− .90	3
September 11	do	14	23	2.94	.75	68
October 4	do	8	1.6	.71	−1.00	1.
November 10	do		22	2.42	.80	52
November 29	do		103	3.82	3.95	394
December 3	do		36	3.50	1.35	124
December 9	do	21	20	2.58	.40	51
December 23	do	20	15	2.47	.20	36

HONDO RIVER AT HONDO RESERVOIR SITE, NEW MEXICO.

This station was established March 9, 1903, by W. A. Wilson. It is located at the fir New Mexico reservoir dam site, 12 miles southwest of Roswell, N. Mex.

The channel is straight for 200 feet above and below the station. The current is swift high water and sluggish at low water. Both banks are high, without trees, and liable overflow. There is but one channel at all stages. The bed is composed of shifting sar and the cross section changes during each flood.

A footbridge has been constructed 75 feet below the dam, for the purpose of making di charge measurements. The initial point for soundings is 1 foot south of the north end of tl west stringer of the bridge.

The gage is a vertical timber located 10 feet north of the footbridge. During 1905 tl gage was read twice each day by Lee Hall. The bench-mark is on a ledge of rock whi

45° W., and is 650 feet distant from the gage; elevation, 19.10 feet above the f the gage.

ıation in regard to this station is contained in the following Water-Supply Papers nited States Geological Survey:

ɔn: 99, p 362; 132, pp 119–120.
': 99, p 363; 132, p 120.
;hts: 99, p 363; 132, p 121.

ɯge measurements of Hondo River at Hondo reservoir site, New Mexico, in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
24...	H. C. Hurd	23	26	3.77	3.25	96
26...	H. L. Eames	23	48	3.84	4.35	184
.....	.....do	24	58	6.95	5.70	400
.....	.....do	24	74	7.26	6.58	536
.....	.....do	24	62	7.07	6.00	436
.....	.....do	23	37	4.45	4.85	166
.....	.....do	24	34	2.33	3.38	78
.....	.....do	24	28	2.34	3.20	66
.....	.....do	24	31	2.04	3.10	63
.....	.....do	24	32	2.39	3.20	77
.....	.....do	24	29	2.17	2.90	62
.....	.....do	18	18	1.88	2.30	33
.....	.....do	15	9.5	1.31	1.77	12
.....	Giles and Eames	24	32	2.20	2.90	71
.....	H. L. Eames	30	205	7.05	9.80	1,446
.....	.....do	25	170	6.83	8.40	1,158
.....	J. M. Giles	.....	45	2.32	3.22	105
.....	E. Patterson	31	177	4.28	9.70	758
.....	.....do	25	125	5.73	7.80	714
.....	.....do	23	33	4.01	3.60	132
.....	.....do	23	39	4.80	3.80	188
).....	.....do	23	51	5.60	5.40	285
).....	.....do	23	14	1.91	3.30	26
r 10..	.....do	.....	13	2.54	3.40	33
r 16..	J. M. Giles	.....	11	1.72	3.20	19
.....	E. Patterson	20	9	1.96	3.12	18
4.....	.....do	12	6	1.09	2.95	7
4.....	J. M. Giles	11	7.2	1.47	2.97	10.6
4.....	E. Patterson	14	7	1.65	3.10	11.6
r 29..	.....do	.....	106	5.23	8.00	556
1.....	.....do	.....	44	5.27	5.35	232
26...	.....do	.....	.....	.....	5.00	a 20

a Estimated through ice and snow.

Daily gage height, in feet, of Hondo River at Hondo reservoir site, New Mexico, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	0.95	.....	4.6	2.9	7.5	1.45	.....	6.55	2.9	3.1	3.1	5.3
2	.9	.....	5.0	2.8	7.95	2.05	4.3	3.75	2.9	3.2	3.05	4.9
3	.9	.....	5.7	2.65	8.0	1.75	4.0	7.9	2.8	3.25	3.0	4.5
4	.9	.....	6.65	2.6	7.3	1.75	3.9	4.5	3.15	3.25	3.0	4.
5	.9	.....	6.6	2.4	6.85	2.0	3.8	3.95	3.25	3.1	3.0	4.
6	.85	.....	6.2	2.3	6.35	1.8	.....	3.85	3.7	3.1	3.15	3.
7	.9	.....	6.05	2.1	5.85	1.85	.....	4.1	3.4	3.05	3.35	3.
8	.95	.....	5.9	1.95	5.45	1.7	.....	4.3	3.45	3.0	3.3	3.
9	.85	.....	5.55	1.8	4.95	7.8	.....	6.75	3.35	3.0	3.45	3.
10	.85	.....	5.25	1.9	5.0	7.95	.....	5.6	3.6	3.0	3.8	3.
11	.9	.....	5.1	2.25	4.55	7.45	.....	5.85	3.95	3.0	3.85	3.
12	2.3	.....	4.95	2.95	4.05	10.5	.....	7.05	3.5	3.0	3.8	3.
13	1.9	.....	4.9	2.95	3.75	5.95	.....	4.7	3.3	3.0	3.65	3.
14	1.65	.....	4.75	2.75	3.6	5.25	.....	5.4	3.2	3.0	3.65	3.
15	1.55	.....	4.8	2.55	3.55	5.15	.....	5.05	3.2	2.9	3.5	3.
16	1.55	.....	4.6	2.35	3.25	5.15	.....	5.3	3.15	2.9	3.45	3.
17	1.5	.....	4.6	2.4	3.0	5.1	.....	4.65	3.05	3.0	3.4	3.
18	1.4	.....	4.5	2.3	3.05	5.1	.....	4.4	3.05	2.9	3.3	3.
19	1.3	.....	4.35	2.5	3.05	4.9	.....	4.15	2.95	2.95	3.35	3.
20	1.3	2.65	4.1	2.85	3.15	4.9	.....	4.0	2.9	2.95	3.35	2.
21	1.7	2.75	3.9	3.05	4.1	4.8	.....	3.95	2.95	3.0	3.35	2.
22	1.2	2.95	3.75	2.75	3.55	4.7	.....	3.85	2.55	3.0	3.35	3.
23	1.2	3.05	3.55	3.1	3.1	4.7	6.3	4.2	2.85	3.05	3.45	3.
24	.....	3.25	3.3	3.2	2.9	4.55	8.05	4.2	2.9	3.05	3.3	4.
25	.....	4.25	3.2	9.1	2.65	4.4	11.4	3.9	2.75	3.15	3.3	4.
26	.....	4.25	3.1	7.4	2.55	4.35	9.2	3.6	3.65	3.1	3.3	4.
27	.....	4.4	3.1	7.95	2.4	4.15	8.55	3.2	3.4	3.1	3.25	4.
28	.....	4.6	3.15	8.8	2.25	3.9	7.0	3.2	3.6	3.05	6.7	4.
29	.....	.....	3.2	8.45	2.15	3.75	6.5	3.15	3.45	3.1	8.7	4.
30	.....	.....	3.2	8.25	2.05	.....	4.15	3.15	3.2	3.0	6.0	4
31	.....	.....	2.6	.....	1.75	.....	4.35	3.15	.....	3.05	.....	4

NOTE.—River dry on days of no gage height.

TAYLOR-MOORE DITCH NEAR ROSWELL, N. MEX.

This station was established March 23, 1905, and discontinued June 8, 1905. It is loca between the diversion dam and reservoir site, 12 miles southwest of Roswell. The di takes water from Hondo River 2 miles above the Hondo River gaging station.

The channel is straight for 1,000 feet above and below the station and the current is sw Discharge measurements are made by wading or from a plank thrown across the ditch at gage. A staff gage is driven into the bank of the ditch. During 1905 the gage was read d by H. L. Eames.

Discharge measurements of Taylor-Moore ditch near Roswell, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis chan
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Secon feet*
April 3	H. L. Eames	7	5.4	3.02	1.45	
April 6	do	7	4.0	2.23	1.20	
April 10	do	7	6.4	3.29	1.62	
April 14	J. M. Giles	7	7.0	3.73	1.72	

Daily gage height, in feet, of Taylor-Moore ditch near Roswell, N. Mex., for 1905.

Day.	Apr.	May.	June.	Day.	Apr.	May.	June.	Day.	Apr.	May.	June.
1	.....	.....	1.6	12	1.71	1.9	.....	23	1.88	1.5	.....
2	.....	.....	1.7	13	1.72	1.9	.....	24	1.9	1.5	.....
3	1.45	.....	1.8	14	1.72	1.9	.....	25	.....	1.4	.....
4	1.47	.....	1.9	15	1.75	1.9	.....	26	.....	1.3	.....
5	1.35	.....	1.9	16	1.72	1.8	.....	27	.....	1.2	.....
6	1.2	.....	1.9	17	1.72	1.81	.....	28	.....	1.15	.....
7	1.0	.....	1.9	18	1.75	1.82	.....	29	.....	1.1	.....
8	1.28	.....	1.9	19	1.78	1.92	.....	30	.....	.7	.....
9	1.6	1.5	.....	20	1.78	1.83	.....	31	.....	1.2	.....
10	1.63	1.92	.....	21	1.82	1.92	.....				
11	1.69	1.91	.....	22	1.84	1.6	.....				

NOTE.—Dam broke April 25; rebuilt May 8. Ditch dry April 25 to May 8. Dam washed out June 9; ditch dry.

Station rating table for Taylor-Moore ditch near Roswell, N. Mex., from March 23 to June 8, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.70	0.3	1.10	6.7	1.50	17.6	1.90	33
.80	1.7	1.20	8.9	1.60	21.2	2.00	37
.90	3.2	1.30	11.4	1.70	25		
1.00	4.8	1.40	14.4	1.80	29		

The above table is based on four discharge measurements made during 1905. It is well defined between gage heights 1.2 feet and 1.7 feet.

Estimated monthly discharge of Taylor-Moore ditch near Roswell, N. Mex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March 23–31	16	6	12.1	216
April	33	0	17.9	1,065
May	34	0	16.7	1,027
June 1–8	33	21	30.0	476

NOTE.—March 23 to April 2 discharge estimated. Ditch dry April 25 to May 8 and after June 8.

PENASCO RIVER NEAR DAYTON, N. MEX.

This station was established September 12, 1905. It is located about 2 miles east and 1 mile north of Dayton and about 1 mile above the mouth of the river. Both banks are high, but are subject to overflow. The bed of the stream is composed of gravel and is slightly shifting. The current has a good velocity. Discharge measurements are made by wading near the gage.

The gage is in two sections: An inclined scale fastened to stakes driven into the left bank reads from 0 to 5.5 feet. A vertical section nailed to a post at the end of the inclined scale reads from 5.5 to 7.5 feet. During 1905 the gage was read once each day by Eugene Lattion. Bench marks were established as follows: (1) The top of post to which gage is fastened; elevation, 7.38 feet. (2) A nail in post at corner of fence on right bank opposite the gage; elevation, 9.82 feet. Elevations refer to the datum of the gage.

Discharge measurements of Penasco River near Dayton, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
September 12	J. M. Giles	16	7.8	0.95	1.00	7.4
September 15	E. Patterson	8	4.4	1.00	.90	4.4
October 4	J. M. Giles	12	6.8	.68	.95	4.6
October 15	E. Patterson	13	7.7	.70	.95	5.4
November 23	J. M. Giles	52	2.93	1.80	1.51	151
November 23	do	34	2.08	1.47	1.41	71
November 23	do	21	2.56	1.37	1.37	53
November 28	do	22	1.67	1.15	1.15	29

Daily gage height, in feet, of Penasco River near Dayton, N. Mex., for 1905.

Day.	Sept.	Oct.	Nov.	Dec.	Day.	Sept.	Oct.	Nov.	Dec.	Day.	Sept.	Oct.	Nov.	Dec.
1		0.9	1.0	1.6	12	1.0	1.0	1.0	1.4	23	.8	1.0	1.55	1.5
2		.9	1.0	1.9	13	.8	1.0	1.0	1.4	24	.9	1.0	1.3	1.5
3		1.0	1.0	1.5	14	.6	1.0	1.0	1.5	25	1.0	1.0	1.2	1.3
4		1.0	1.3	1.6	15	.95	1.0	1.0	1.5	26	.9	1.0	1.2	1.2
5		1.0	1.5	1.6	16	1.0	1.0	1.0	1.5	27	1.0	1.0	1.1	1.4
6		1.0	1.0	1.6	17	1.0	1.0	1.0	1.5	28	.9	1.0	1.8	1.4
7		.9	1.0	1.5	18	1.0	1.0	1.0	1.5	29	.9	1.0	1.7	1.3
8		1.0	1.0	1.5	19	1.0	1.0	1.0	1.5	30	.9	1.0	1.7	1.2
9		1.0	1.0	1.4	20	1.0	1.0	1.0	1.5	31		1.0		1.8
10		1.0	1.0	1.4	21	1.5	1.0	1.0	1.5					
11		1.0	1.0	1.4	22	.9	1.0	1.0	1.5					

Station rating table for Penasco River near Dayton, N. Mex., from September 12, 1905, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.60	1	1.00	7	1.40	57	1.80	150
.70	2	1.10	15	1.50	77	1.90	180
.80	3	1.20	26	1.60	99		
.90	5	1.30	40	1.70	123		

The above table is based on eight discharge measurements made during 1905. It is well defined between gage heights 0.9 foot and 1.8 feet.

Estimated monthly discharge of Penasco River near Dayton, N. Mex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
September 12-30	77	1	9.3	351
October	7	5	6.8	418
November	150	7	28.3	1,684
December	180	26	75.3	4,630

DEVILS RIVER AT DEVILS RIVER, TEX.

This station was established in April, 1900, by the International (Water) Boundary Commission. It is opposite the Southern Pacific Railroad station at Devils River.

The river is about 50 miles in length, has a perennial flow, and during flood periods is subject to great fluctuations. No good location for a gaging station exists on this stream where it would be accessible from the railroad station. At the site chosen, the river is straight for one-fourth mile both above and below the station. The right bank is the talus of a cliff, the left bank is a bottom heavily timbered. The bed of the stream is nearly all a rock ledge, but seamed and faulted so as to be rough. The currents change in such a way at so give materially different discharges for the same gage height.

Discharge measurements are made by means of a cable, car, and tagged wire. The initial point for soundings is the cable support on the left bank.

The gage is a scantling spiked vertically to a tree. The highest water on record occurred April 6, 1900, about two weeks before this gage was established. It reached a height of 25.4 feet on the gage, but this is 8 feet higher than any other known flood. Low water is 2 feet on the gage. The bench mark is a nail in the side of the gate post near the railroad station; elevation, 31.26 feet above the datum of the gage.

The observations during 1905 have been made under the direction of the United States section of the International (Water) Boundary Commission. The hydrographer is E. E. Winter, and the gage reader is John Harrison.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 50, pp 363–364; 66, p 79; 84, p 164; 99, p 348; 132, p 122.
Discharge: WS 28, p 130; 50, p 364; 66, p 79; 84, p 164; 99, pp 349–350; 132, pp 123–124.
Discharge, mean daily: WS 132, p 125.
Discharge, monthly: Ann 22, iv, p 356; WS 75, p 161; 84, p 165; 99, p 351; 132, p 125.
Gage heights: WS 50, p 364; 66, p 79; 84, p 165; 99, pp 350–351; 132, p 124.

Discharge measurements of Devils River at Devils River, Tex., in 1905.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
January 9	E. E. Winter	347	1.30	2.3	452
January 17	do	347	1.29	2.3	448
January 25	do	347	1.28	2.3	444
January 30	do	347	1.22	2.25	424
February 8	do	348	1.23	2.3	429
February 16	do	348	1.24	2.3	432
February 27	do	351	1.24	2.3	437
March 13	do	351	1.35	2.35	475
March 17	do	444	1.71	2.6	761
March 21	do	407	1.67	2.5	680
March 25	do	376	1.45	2.4	544
March 30	do	375	1.44	2.4	540
April 5	do	433	1.58	2.65	682
April 13	do	404	1.49	2.5	600
April 18	do	378	1.41	2.4	533
April 25	do	1,079	2.94	4.9	3,168
April 30	do	724	2.18	3.5	1,580
May 4	do	491	1.62	2.8	795
May 12	do	468	1.48	2.7	691
May 17	do	468	1.51	2.7	706
May 25	do	461	1.77	2.7	816
May 30	do	465	2.00	2.7	928
June 5	do	490	1.90	2.8	929

Discharge measurements of Devils River at Devils River, Tex., in 1905—Continued.

Date.	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Di char
		Square feet.	*Feet per second.*	*Feet.*	*Sec fe*
June 14	E. E. Winter	461	1.78	2.7	
June 22	do	462	1.78	2.7	
June 26	do	459	1.74	2.7	
June 30	do	518	2.02	2.9	
July 6	do	457	1.82	2.7	
July 11	do	446	1.65	2.65	
July 16	do	403	1.50	2.55	
July 21	do	411	1.42	2.55	
July 27	do	404	1.39	2.5	
July 30	do	401	1.38	2.5	
August 7	do	406	1.40	2.5	
August 11	do	407	1.39	2.5	
August 16	do	402	1.35	2.5	
August 22	do	401	1.39	2.5	
August 25	do	402	1.43	2.5	
August 30	do	403	1.38	2.5	
September 4	do	552	1.80	3.0	
September 18	do	405	1.67	2.5	
September 23	do	403	1.66	2.5	
September 26	do	403	1.63	2.5	
September 29	do	405	1.62	2.5	
October 4	do	403	1.54	2.5	
October 12	do	403	1.45	2.5	
October 17	do	402	1.41	2.5	
October 25	do	396	1.23	2.45	
October 30	do	401	1.27	2.5	
November 4	do	396	1.28	2.5	
November 11	do	396	1.27	2.5	
November 16	do	401	1.26	2.5	
November 24	do	396	1.23	2.5	
November 30	do	396	1.60	2.5	
December 5	H. F. Collins	372	1.54	2.45	
December 10	do	372	1.59	2.45	
December 18	do	365	1.62	2.45	
December 26	do	365	1.62	2.45	

Daily gage height, in feet, of Devils River at Devils River, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.3	2.3	2.3	6.0	4.1	2.85	2.95	2.5	2.5	2.7	2.5	2.45
2	2.3	2.3	2.3	3.65	3.5	2.8	2.8	2.5	2.5	3.1	2.5	2.45
3	2.3	2.3	2.3	2.9	3.0	2.85	2.8	2.5	3.2	2.85	2.5	2.45
4	2.3	2.3	2.3	2.8	2.85	2.95	2.7	2.5	3.1	2.55	2.5	2.45
5	2.3	2.3	2.3	2.7	2.8	2.8	2.7	2.5	2.7	2.5	2.5	2.45
6	2.3	2.3	2.3	2.7	2.8	2.8	2.7	2.5	2.6	2.5	2.5	2.45
7	2.3	2.3	2.35	2.6	2.7	2.7	2.7	2.5	2.5	2.5	2.5	2.45
8	2.3	2.3	2.35	2.6	2.7	2.65	2.7	2.5	2.5	2.5	2.5	2.45
9	2.3	2.3	2.35	2.55	2.7	2.6	2.6	2.5	2.5	2.5	2.5	2.45
10	2.3	2.3	2.35	2.55	2.7	2.6	2.6	2.5	2.5	2.5	2.5	2.45
11	2.3	2.3	2.35	2.55	2.7	2.6	2.65	2.5	2.5	2.5	2.5	2.45
12	2.3	2.3	2.35	2.5	2.7	2.6	2.6	2.5	2.5	2.5	2.5	2.45
13	2.3	2.3	2.35	2.45	2.7	2.65	2.6	2.5	2.5	2.5	2.5	2.45
14	2.3	2.3	2.35	2.5	2.85	2.7	2.55	2.5	2.5	2.5	2.5	2.45
15	2.3	2.3	2.35	2.5	2.75	2.7	2.5	2.5	2.5	2.5	2.5	2.45
16	2.3	2.3	2.7	2.5	2.7	2.7	2.55	2.5	2.5	2.5	2.5	2.45
17	2.3	2.3	2.6	2.45	2.65	2.7	2.55	2.5	2.5	2.5	2.5	2.45
18	2.3	2.3	2.6	2.4	2.5	2.7	2.55	2.5	2.55	2.5	2.5	2.45
19	2.3	2.3	2.6	2.4	2.5	2.7	2.55	2.5	3.8	2.5	2.5	2.45
20	2.3	2.3	2.6	2.4	2.5	2.7	2.55	2.5	2.75	2.8	2.5	2.45
21	2.3	2.3	2.5	2.4	2.5	2.9	2.55	2.5	2.5	2.5	2.5	2.45
22	2.3	2.3	2.5	2.4	2.5	2.7	2.55	2.5	2.5	2.45	2.5	2.45
23	2.3	2.3	2.5	2.55	2.5	2.7	2.55	2.5	2.5	2.45	2.5	2.45
24	2.3	2.3	2.5	3.1	2.75	2.7	2.55	2.5	2.5	2.45	2.5	2.45
25	2.3	2.3	2.4	4.9	2.7	2.7	2.55	2.5	2.5	2.45	2.5	2.45
26	2.3	2.3	2.4	4.9	2.8	2.7	2.55	2.5	2.5	2.45	2.5	2.45
27	2.3	2.3	2.4	2.9	2.9	2.7	2.5	2.5	2.5	2.45	2.5	2.45
28	2.3	2.3	2.4	2.7	2.85	2.8	2.5	2.5	2.5	2.45	2.5	2.45
29	2.3	.....	2.4	2.6	2.7	5.0	2.5	2.5	2.5	2.45	2.5	2.45
30	2.25	.....	2.4	4.2	2.7	3.25	2.5	2.5	2.5	2.5	2.5	2.4
31	2.25	.....	2.4	.....	3.25	.....	2.5	2.5	.....	2.5	.....	2.4

Daily discharge, in second-feet, of Devils River at Devils River, Tex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	445	440	435	6,470	2,260	990	1,090	555	570	770	510	575
2	445	440	440	1,750	1,590	930	940	560	580	1,100	510	575
3	445	435	440	840	1,020	990	930	560	1,200	870	510	575
4	450	435	440	770	a 850	1,110	830	560	a 1,100	a 650	a 510	575
5	450	435	445	a 710	795	a 930	a 830	565	750	615	510	a 575
6	450	430	445	710	795	930	825	565	680	610	510	580
7	450	430	470	655	690	820	820	a 565	620	605	505	585
8	450	a 430	470	655	690	770	810	565	620	600	505	585
9	a 450	430	470	630	690	720	705	565	630	595	505	590
10	450	430	470	630	690	720	700	565	630	590	500	a 590
11	450	430	475	630	690	720	a 735	a 565	640	585	a 500	590
12	450	430	475	600	a 690	720	680	565	640	a 585	500	590
13	450	430	a 475	a 565	690	770	675	560	650	580	500	590
14	450	430	475	600	850	a 820	620	555	650	575	505	590
15	450	430	475	600	750	820	570	550	660	570	505	590
16	450	a 430	840	600	700	820	a 605	a 540	660	565	a 505	590
17	a 450	430	a 760	565	a 655	820	600	545	670	a 565	505	590
18	450	430	760	a 535	510	820	595	550	a 720	555	505	a 590
19	450	430	760	535	525	820	590	555	1,920	550	505	590
20	445	435	760	535	540	820	585	555	890	820	500	590
21	445	435	a 680	535	555	1,040	a 580	560	670	530	500	590
22	445	435	665	535	570	a 820	580	a 560	670	505	495	590
23	445	435	650	630	585	820	580	565	a 670	500	495	590
24	445	435	635	1,010	850	810	580	570	660	490	a 490	590
25	a 445	435	a 545	a 3,170	a 815	810	580	a 575	660	a 485	500	590
26	445	435	545	3,170	940	a 800	580	575	a 655	485	520	a 595
27	445	a 435	545	840	1,060	800	a 560	570	655	485	540	590
28	445	435	540	710	1,030	920	560	565	655	485	570	585
29	445	.....	540	650	910	3,280	555	560	a 660	485	600	580
30	a 425	.....	a 540	a 2,370	a 930	a 1,400	a 555	a 560	660	a 510	a 630	515
31	425	.....	540	.....	1,480	.....	555	560	.....	510	.....	510

a Meter measurement.

Estimated monthly discharge of Devils River at Devils River, Tex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	450	425	446	27,441
February	440	430	433	24,040
March	840	435	555	34,126
April	6,470	535	1,107	65,861
May	2,260	510	851	52,354
June	3,280	720	945	56,251
July	1,090	555	677	41,653
August	575	540	561	34,483
September	1,920	570	736	43,825
October	1,100	485	594	36,545
November	630	490	515	30,635
December	595	510	582	35,763
The year	6,470	425	667	482,977

SAN FELIPE CREEK AT DEL RIO, TEX.

San Felipe Creek rises in four large springs northeast of Del Rio, and flows southward into e Rio Grande. The waters of these springs are used in two large irrigation systems, the ie on the west side of the creek having been in use for many years, while the one on the east s only recently been constructed by G. Bedell Moore. The following table shows the dis-arge measurements that have been taken on the combined flow of the Madre ditch and the eek just south of the bridge of the Southern Pacific Railroad.

Discharge measurements of San Felipe Creek at Del Rio, Tex., 1895–1905.

Date.	Hydrographer.	Discharge.	Remarks.
		Second-feet.	
cember, 1895	C. C. Babb	99	
arch, 1899	T. U. Taylor	113	
ptember, 1900	do	149	Rainy season.
cember, 1901	C. N. Campbell	150	After Brackett flood.
ptember, 1902	T. U. Taylor	115	
arch, 1904	do	118	Includes 38 second-feet in ditch.
igust, 1905	do	103	

LAS MORAS CREEK NEAR BRACKETTVILLE, TEX.

Las Moras Creek, like its sister springs of the Edwards Plateau, rises very suddenly. It is ated near the twin towns of Brackettville and Fort Clark, and threads its way between e two. It flows south, supporting many irrigation systems, and finally empties into the o Grande 25 miles above Eagle Pass. Its flow is extremely variable, being a reflex barom-er of the season preceding, and like the Leona at Uvalde, it gives a safe index of the rain-ll of the Edwards Plateau for months before. The following table shows the discharge easurements that have been taken:

Discharge measurements of Las Moras Creek near Brackettville, Tex., 1895–1905.

Date.	Hydrographer.	Discharge.	Remarks.
		Second-feet.	
cember, 1895	C. C. Babb	21	At footbridge, Brackettville.
ne, 1899	T. U. Taylor	60	At Mulligans Bend.
ptember, 1900	do	51	Do.
ptember, 1902	do	11	Do.
ptember, 1902	do	11	Do.
rch, 1904	do	28	Do.
gust, 1905	do	14	Do.

INDEX.

A. Page.

e-foot, definition of 4
a of waterway, method of determining.. 10
stin, Tex.,
Barton Springs near:
description 30-31
discharge 31
Colorado River at:
description 24-25
discharge 25
discharge, monthly 27
gage heights 26
rating table 26

B.

ton Springs near—
Austin, Tex..
description 30-31
discharge 31
stow Irrigation Co., flume near—
Pecos, Tex.:
discharge 109
discharge, monthly 110
gage heights 109
rating table 110
ckettville, Tex.,
Las Moras Creek near—
description 127
discharge 127
zos River at—
Richmond, Tex.:
description 21-22
discharge 22
discharge, monthly 24
gage heights 23
rating table 23
Waco, Tex.:
description 19
discharge 20
discharge, monthly 21
gage heights 20
rating table 21
zos River basin:
description 19
wnsville, Tex.:
Rio Grande near—
description 81-82
discharge 82-83
gage heights 84

C.

lsbad, N. Mex.,
Pecos River at:
description 102
discharge 102
discharge, monthly 104-105
gage heights 103
rating table 104
Colorado River at— Page.
Austin, Tex.:
description 24-25
discharge 25
discharge, monthly 27
gage heights 26
rating table 26
Columbus, Tex.:
description 27
discharge, monthly 29
gage heights 28
rating table 28
Colorado River (of Texas) basin:
description 24
Columbus, Tex.,
Colorado River at:
description 27
discharge, monthly 29
gage heights 28
rating table 28
Comal River at—
New Braunfels, Tex.:
description 33-34
discharge 34
Computation, rules for 4-5
Conejos River near—
Mojote, Colo.:
description 90-91
discharge 91
discharge, monthly 93
gage heights 92
rating table 92-93
Cooperation and acknowledgments 12
Cuero, Tex.,
Guadeloupe River near:
description 31-32
discharge, monthly 33
gage heights 32
rating table 33
Current meters, types of 8
Current-meter measurements, method of making 8-9

D.

Dam station, construction of rating table for 10
Dayton, N. Mex.,
Pecos River near:
description 99
discharge 100
gage heights 101
Penasco River near:
description 121
discharge 122
discharge, monthly 122
gage heights 122
rating table 123

Page.

Del Norte, Colo.,
  Rio Grande near:
    description ... 36–37
    discharge ... 37
    discharge, monthly ... 39
    gage heights ... 37–38
    rating table ... 38
Delrio, Tex.,
  San Felipe Creek at:
    description ... 127
    discharge ... 127
Devils River, Tex.,
  Devils River at:
    description ... 123
    discharge ... 123–124
    discharge, daily ... 126
    discharge, monthly ... 126
    gage heights ... 125
  Rio Grande near:
    description ... 67
    discharge ... 67–68
    discharge, daily ... 70
    discharge, monthly ... 70
    gage heights ... 69
Devils River at—
  Devils River, Tex.:
    description ... 123
    discharge ... 123–124
    discharge, daily ... 126
    discharge, monthly ... 126
    gage heights ... 125
"Discharge," definition of ... 3
Discharge, daily, determination of ... 11–12
Drainage basins, list of ... 2–3

E.

Eagle Pass, Tex.,
  Rio Grande at:
    description ... 71
    discharge ... 71–73
    discharge, daily ... 75
    discharge, monthly ... 75
    gage heights ... 74
El Paso, Tex.,
  Rio Grande near:
    description ... 49
    discharge ... 50–52
    discharge, daily ... 53
    discharge, monthly ... 53
    gage heights ... 52
Equivalents, table of ... 5
Evadale, Tex.,
  Naches River at:
    description ... 15
    discharge ... 15
    discharge, monthly ... 17
    gage heights ... 16
    rating table ... 16

F.

Field methods of measuring stream flow ... 6–10
Float method of measuring velocity, description of ... 8
Fort Sumner, N. Mex.,
  Pecos River near:
    description ... 95
    discharge ... 95
    discharge, daily ... 97
    discharge, monthly ... 97
    gage height ... 96

G.

Page.

Gage-height table, explanation of ... 4
Gaging station, equipment of ... 8
Gallinas River near—
  Las Vegas, N. Mex.:
    description ... 115
    discharge ... 115
    discharge, monthly ... 117
    gage heights ... 116
    rating table ... 116
Guadaloupe River near—
  Cuero, Tex.:
    description ... 31–32
    discharge, monthly ... 33
    gage heights ... 32
    rating table ... 33
Guadaloupe River basin:
  description ... 31
Guerrero, Tamaulipas, Mexico,
  Rio Salado near:
    description ... 84
    discharge ... 85–86
    gage heights ... 87

H.

Hondo Reservoir site, N. Mex.,
  Hondo River at:
    description ... 118–119
    discharge ... 119
    gage heights ... 120
Hondo River at—
  Hondo Reservoir site, N. Mex.:
    description ... 118–119
    discharge ... 119
    gage heights ... 120
  Roswell, N. Mex.:
    description ... 117–118
    discharge ... 118
Hydrographic surveys, appropriations for ... 1
  organization of ... 2

I.

Ice measurements, methods of making ... 9–10
Integration, method of measuring discharge, description of ... 9

L.

Langtry, Tex.,
  Rio Grande near:
    description ... 63
    discharge ... 63–65
    discharge, daily ... 66
    discharge, monthly ... 66
    gage heights ... 65
Laredo, Tex.,
  Rio Grande near:
    description ... 76
    discharge ... 76–77
    gage heights ... 78
Las Moras Creek near—
  Bracketville, Tex.:
    description ... 127
    discharge ... 127
Las Vegas, N. Mex.,
  Gallinas River near:
    description ...
    discharge ...
    discharge, monthly ...
    gage heights
    rating table

	Page.
na River at—	
Uvalde, Tex.:	
description	35
discharge	35
atos, Colo.,	
Rio Grande near:	
description	39–40
discharge	40
gage heights	40
gview, Tex.,	
Sabine River near:	
description	13
discharge	13
discharge, monthly	15
gage heights	14
rating table	14
M.	
iner's inch," definition of	3
gote, Colo.,	
Conejos River near:	
description	90–91
discharge	91
discharge, monthly	93
gage heights	92
rating table	92–93
orhead, Tex.,	
Pecos River near:	
description	110–111
discharge	111–112
discharge, daily	114
discharge, monthly	114
gage heights	113
ltiple-point method of measuring discharge, description of	9
N.	
hes River at—	
Evadale, Tex.:	
description	15
discharge	15
discharge, monthly	17
gage heights	16
rating table	16
v Braunfels, Tex.,	
Comal River at:	
description	33–34
discharge	34
ces River basin:	
description	35
P.	
os, Tex.,	
Barstow Irrigation Co. flume near:	
discharge	109
discharge, monthly	110
gage heights	109
rating table	110
Pecos River near:	
discharge	106
discharge, monthly	108
gage heights	107
rating table	107
Pecos River and Margueretta flume near:	
description	105–106
Pecos River at or near—	
Carlsbad, N. Mex.:	
description	102
discharge	102
discharge, monthly	104–105
gage heights	103
rating table	104
Dayton, N. Mex.:	
description	99
discharge	100
gage heights	101
Fort Sumner, N. Mex.:	
description	95
discharge	95
discharge, daily	97
discharge, monthly	97
gage heights	96
Moorhead, Tex.:	
description	110–111
discharge	111–112
discharge, daily	114
discharge, monthly	114
gage heights	113
Pecos, Tex.:	
discharge	106
discharge, monthly	108
gage heights	107
rating table	107
Roswell, N. Mex.:	
description	97–98
discharge	98
gage heights	99
Santa Rosa, N. Mex.:	
description	93–94
discharge	94
gage heights	94
Pecos River and Margueretta flume near—	
Pecos, Tex.:	
description	105–106
Penasco River near—	
Dayton, N. Mex.:	
description	121
discharge	122
discharge, monthly	122
gage heights	122
rating table	122
Presidio, Tex.,	
Rio Grande near:	
description	54 58–59
discharge	54–56, 59–60
discharge, daily	57, 62
discharge, monthly	57, 62
gage heights	56, 61
Presidio del Norte, Mexico,	
Rio Conchas near:	
discharge	58
R.	
Rating table, construction of	10
Rating table, explanation of	4
Richmond, Tex.,	
Brazos River at:	
description	21–22
discharge	22
discharge, monthly	24
gage heights	23
rating table	23

Rio Conchas near-- Page.
Presidio del Norte, Mexico:
discharge ... 58
Rio Grande near--
Brownsville, Tex.:
description ... 81-82
discharge ... 82-83
gage heights ... 84
Del Norte, Colo.:
description ... 36-37
discharge ... 37
discharge, monthly ... 39
gage heights ... 37-38
rating table ... 38
Devils River, Tex.:
description ... 67
discharge ... 67-68
discharge, daily ... 70
discharge, monthly ... 70
gage heights ... 69
Eagle Pass, Tex.:
description ... 71
discharge ... 71-73
discharge, daily ... 75
discharge, monthly ... 75
gage heights ... 74
El Paso, Tex.:
description ... 49
discharge ... 50-52
discharge, daily ... 53
discharge, monthly ... 53
gage heights ... 52
Langtry, Tex.:
description ... 63
discharge ... 63-65
discharge, daily ... 66
discharge, monthly ... 66
gage heights ... 65
Laredo, Tex.:
description ... 76
discharge ... 76-77
gage heights ... 78
Lobatos, Colo.:
description ... 39-40
discharge ... 40
gage heights ... 40
Presidio, Tex.:
description ... 54, 58-59
discharge ... 54-56, 59-60
discharge, daily ... 57, 62
discharge, monthly ... 57, 62
gage heights ... 56, 61
Roma, Tex.:
description ... 78
discharge ... 79-80
gage heights ... 81
San Ildefonso, N. Mex.:
description ... 41
discharge ... 42
discharge, monthly ... 43
gage heights ... 42
rating table ... 43
San Marcial, N. Mex.:
description ... 43-44
discharge ... 44-46
discharge, daily ... 48
discharge, monthly ... 48
gage heights ... 47
Rio Grande basin: Page.
description ... 35-36
Rio Salado near—
Guerrero, Tamaulipas, Mexico:
description ... 84
discharge ... 85-86
gage heights ... 87
Rio San Juan near—
Santa Rosalie Ranch, Tamaulipas, Mexico:
description ... 87
discharge ... 88-90
gage heights ... 90
Riverside, Tex.,
Trinity River at:
description ... 17-18
discharge ... 18
discharge, monthly ... 19
gage heights ... 18
Roma, Tex.,
Rio Grande near:
description ... 78
discharge ... 79-80
gage heights ... 81
Roswell, N. Mex.,
Hondo River at:
description ... 117-118
discharge ... 118
Pecos River near:
description ... 97-98
discharge ... 98
gage heights ... 99
Taylor Moore ditch near:
description ... 120
discharge ... 120
discharge, monthly ... 121
gage heights ... 121
rating table ... 121
"Run-off," definition of ... 3
Run-off, office methods of computing ... 10-12
"Run-off in inches" definition of ... 3

S.

Sabine River near -
Longview, Tex.:
description ... 13
discharge ... 13
discharge, monthly ... 15
gage heights ... 14
rating table ... 14
Sabine River basin:
description ... 1
San Antonio River at -
San Antonio, Tex.:
description ... 3
discharge ... 34
San Antonio, Tex.,
San Antonio River at:
description ... 34
discharge ... 34
San Antonio River basin:
description ... 34
San Felipe Creek at
Del Rio, Tex.:
description ... 127
discharge ... 127
San Ildefonso, N. Mex.,
Rio Grande near:
description ... 41

	Page.
San Ildefonzo, N. Mex.—Continued.	
Rio Grande near—Continued.	
discharge	42
discharge, monthly	43
gage heights	42
rating table	43
San Marcial, N. Mex.,	
Rio Grande near:	
description	43–44
discharge	44–46
discharge, daily	48
discharge, monthly	48
gage heights	47
San Saba, Tex.,	
on San Saba River at:	
description	29–30
gage heights	30
San Saba River at—	
San Saba, Tex.:	
description	29–30
gage heights	30
Santa Rosa, N. Mex.,	
Pecos River at:	
description	93–94
discharge	94
gage heights	94
Santa Rosalie Ranch, Tamaulipas, Mexico,	
Rio San Juan near:	
description	87
discharge	88–89
gage heights	90
"second-feet per square mile," definition of	3
"second-foot," definition of	3
single point method of measuring discharge, description of	9
slope method of measuring stream flow, description of	6
stream flow, field methods of measuring	6–10
surface measurements, method of making	9

T.	Page.
Tables, explanation of	4
Taylor-Moore ditch near—	
Roswell, N. Mex.:	
description	120
discharge	120
discharge, monthly	121
gage heights	121
rating table	121
Trinity River at—	
Riverside, Tex.:	
description	17–18
discharge	18
discharge, monthly	19
gage heights	18
Trinity River basin:	
description	17
U.	
Uvalde, Tex.,	
Leona River at:	
description	35
discharge	35
V.	
Velocity method of measuring stream flow, description of	7–10
Vertical integration method of measuring discharge, description of	9
Vertical velocity curve method of measuring discharge, description of	9
W.	
Waco, Tex.,	
Brazos River at:	
description	19
discharge	20
discharge, monthly	21
gage heights	20
rating table	21
Weir method of measuring stream flow, description of	6–7
Weir station, construction of rating table for	10

ASSIFICATION OF THE PUBLICATIONS OF THE UNITED STATES GEOLOGICAL SURVEY.

[Water-Supply Paper No. 174.]

The publications of the United States Geological Survey consist of (1) Annual eports; (2) Monographs; (3) Professional Papers; (4) Bulletins; (5) Mineral esources; (6) Water-Supply and Irrigation Papers; (7) Topographic Atlas of nited States, folios and separate sheets thereof; (8) Geologic Atlas of United tates, folios thereof. The classes numbered 2, 7, and 8 are sold at cost of publica-on; the others are distributed free. A circular giving complete lists may be had n application.

Most of the above publications may be obtained or consulted in the following ways:

1. A limited number are delivered to the Director of the Survey, from whom they ay be obtained, free of charge (except classes 2, 7, and 8), on application.

2. A certain number are delivered to Senators and Representatives in Congress, or distribution.

3. Other copies are deposited with the Superintendent of Documents, Washington,). C., from whom they may be had at practically cost.

4. Copies of all Government publications are furnished to the principal public libraries in the large cities throughout the United States, where they may be consulted by those interested.

The Professional Papers, Bulletins, and Water-Supply Papers treat of a variety of subjects, and the total number issued is large. They have therefore been classified into the following series: A, Economic geology; B, Descriptive geology; C, Systematic geology and paleontology; D, Petrography and mineralogy; E, Chemistry and physics; F, Geography; G, Miscellaneous; H, Forestry; I, Irrigation;. J, Water storage; K, Pumping water; L, Quality of water; M, General hydrographic investigations; N, Water power; O, Underground waters; P, Hydrographic progress reports.

Series P.—The hydrographic progress reports contain the results of stream measurements. A report is issued for every calendar year, containing the results of data collected during that year. These reports were first published as a part of the Director's annual report or as a bulletin; they are now published as water-supply and irrigation papers. The following is a list, by years, of the publications containing the progress reports of stream measurements. A detailed index of these reports (1888-1903) is published as Water-Supply Paper No. 119.

1888. Tenth Annual Report, Part II.
1889. Eleventh Annual Report, Part II.
1890. Twelfth Annual Report, Part II.
1891. Thirteenth Annual Report, Part III.
1892. Fourteenth Annual Report, Part II.
1893. Bulletin No. 131.
1894. Bulletin No. 131; Sixteenth Annual Report, Part II.
1895. Bulletin No. 140.
1896. Water-Supply Paper No. 11; Eighteenth Annual Report, Part IV.
1897. Water-Supply Papers Nos. 15 and 16; Nineteenth Annual Report, Part IV.
1898. Water-Supply Papers Nos. 27 and 28; Twentieth Annual Report, Part IV.
1899. Water-Supply Papers Nos. 35, 36, 37, 38, and 39; Twenty-first Annual Report, Part IV.
1900. Water-Supply Papers Nos. 47, 48, 49, 50, 51, and 52; Twenty-second Annual Report, Part IV.
1901. East of Mississippi River, Water-Supply Papers Nos. 65 and 75.
West of Mississippi River, Water-Supply Papers Nos. 66 and 75.
1902. East of Mississippi River, Water-Supply Papers Nos. 82 and 83.
West of Mississippi River, Water-Supply Papers Nos. 84 and 85.

1903. East of Mississippi River, Water-Supply Papers Nos. 97 and 98.
West of Mississippi River, Water-Supply Papers Nos. 99 and 100.
1904. East of Mississippi River, Water-Supply Papers Nos. 124, 125, 126, 127, 128, and 129.
West of Mississippi River, Water-Supply Papers Nos. 130, 131, 132, 133, 134, and 135.
1905. East of Mississippi River, Nos. 165, 166, 167, 168, 169, 170, and 171.
West of Mississippi River, Nos. 171, 172, 173, 174, 175, 176, 177, and 178.

The Geological Survey and the Reclamation Service have suboffices in different parts of the United States, from which hydrographic and reclamation work in the respective localities is carried on and where data may be obtained on application. These offices are located as follows:

Boston, Mass., 6 Beacon street; Utica, N. Y., 75 Arcade; Atlanta, Ga., 409 Temple court; Austin, Tex., University of Texas; Chicago, Ill., 876 Federal Building; Belle Fourche, S. Dak.; Cody, Wyo.; Denver, Colo., Chamber of Commerce Building; Salt Lake, Utah; Los Angeles, Cal., 1108 Braly Building; San Francisco, Cal., 432 Merchants' Exchange Building; Phoenix, Ariz.; Carlsbad, N. Mex.; El Paso, Tex.; Billings, Mont.; Great Falls, Mont.; Hazen, Nev.; Boise, Idaho; Spokane, Wash., 424 Peyton Block; Pendleton, Oreg.

Correspondence should be addressed to

THE DIRECTOR,
UNITED STATES GEOLOGICAL SURVEY,
WASHINGTON, D. C.

AUGUST, 1906.

O

ater-Supply and Irrigation Paper No. 175 Series P, Hydrographic Progress Reports, 51

DEPARTMENT OF THE INTERIOR
UNITED STATES GEOLOGICAL SURVEY
CHARLES D. WALCOTT, DIRECTOR

REPORT

OF

ROGRESS OF STREAM MEASUREMENTS

FOR

THE CALENDAR YEAR 1905

PREPARED UNDER THE DIRECTION OF F. H. NEWELL

PART XI.—Colorado River Drainage above Yuma

BY

M. C. HINDERLIDER and G. L. SWENDSEN

WASHINGTON
GOVERNMENT PRINTING OFFICE
1906

CONTENTS.

	Page.
luction	1
rganization and scope of work	1
efinitions	3
xplanation of tables	4
onvenient equivalents	5
ield methods of measuring stream flow	6
ffice methods of computing run-off	10
ooperation and acknowledgments	11
al description of Colorado River drainage basin	12
River drainage basin	13
rea and extent	13
reen River	13
Description of basin	13
Green River at Greenriver, Wyo	14
Green River at Jensen, Utah	17
Green River at Ouray, Utah	18
Green River at Greenriver, Utah	19
lewfork River drainage basin	21
Description of basin	21
Newfork River near Cora, Wyo	22
Pine Creek near Pinedale, Wyo	23
Pole Creek at Fayette, Wyo	25
Fall Creek near Fayette, Wyo	28
Boulder Creek near Boulder, Wyo	30
Eastfork River at Newfork, Wyo	32
ampa River drainage basin	34
Description of basin	34
Yampa River at Steamboat Springs, Colo	35
Yampa River near Craig, Colo	37
Yampa River near Maybell, Colo	39
Elk River near Trull, Colo	41
Fortification Creek at Craig, Colo	43
Williams River at Hamilton, Colo	44
Milk Creek near Axial, Colo	47
Miscellaneous measurements	49
White River drainage basin	49
Description of basin	49
North Fork of White River near Buford, Colo	50
South Fork of White River near Buford, Colo	52
White River at Meeker, Colo	54
White River near Rangely, Colo	56
Marvine Creek near Buford, Colo	58
uchesne River drainage basin	60
Description of basin	60

:OGRESS REPORT OF STREAM MEASUREMENTS FOR THE CALENDAR YEAR 1905.

PART XI.

By M. C. HINDERLIDER and G. L. SWENDSEN.

INTRODUCTION.

ORGANIZATION AND SCOPE OF WORK.

he hydrographic work of the United States Geological Survey includes the collecton of s concerning and the study of conditions affecting the behavior of water from the time it ches the earth as rain or snow until it joins the oceans or great navigable rivers. These estigations became a distinct feature of the work of the Survey in the fall of 1888, when instruction camp was established at Embudo, N. Mex. The first specific appropriation gaging streams was made by the act of August 18, 1894, which contained an item of $12,500 r gaging the streams and determining the water supply of the United States, including investigation of underground currents and artesian wells in the arid and semiarid sec-ıs." (28 Stat. L., p. 398.)

since that time the appropriations have been gradually increased, as shown by the follow-table:

nnual appropriations for hydrographic surveys, fiscal years ending June 30, 1895 to 1906.

.....	$12,500	1901	$100,000
.....	20,000	1902	100,000
.....	50,000	1903	200,000
.....	50,000	1904	200,000
.....	50,000	1905	200,000
.....	50,000	1906	200,000

As a result of the increased appropriations the work has been greatly extended, and at the ıe time it has been more thoroughly systemized by the adoption of standard methods and grouping the States into districts, in each of which a district hydrographer and a corps of istants carry on a comprehensive study of the hydrographic resources.

The chief features of the hydrographic work are the collection of data relating to the flow surface waters and the study of the conditions affecting this flow. Information is also col-ted concerning river profiles, duration and magnitude of floods, water power, etc., which y be of use in hydrographic studies. This work includes the study of the hydrography of ry important river basin in the United States and is of direct value in the commercial and icultural development of the country.

n order to collect the material from which estimates of daily flow are made gaging sta-ıs are established. The selection of a site for a gaging station and the length of time it is intained depend largely on the physical features and the needs of each locality. If the er is to be used for power special effort is made to obtain information concerning the

minimum flow; if water is to be stored the maximum flow receives special attention. In all sections of the country permanent gaging stations are maintained for general statistical purposes, to show the conditions existing through long periods. They are also used as primary stations and their records in connection with short series of measurements serve as bases for estimating the flow at other points in the drainage basin.

During the calendar year 1905 the division of hydrography has continued measuring the flow of streams on the same general lines as in previous years. Many new and improved methods have been introduced, by which the accuracy and value of the results have been increased. Approximately 800 regular gaging stations were maintained during the year and an exceptionally large number of miscellaneous measurements and special investigations were made. The "Report of Progress of Stream Measurements," which contains the results of this work, is published in a series of fourteen Water-Supply and Irrigation Papers, Nos. 165 to 178, as follows:

No. 165. Atlantic coast of New England drainage.
No. 166. Hudson, Passaic, Raritan, and Delaware River drainages.
No. 167. Susquehanna, Gunpowder, Patapsco, Potomac, James, Roanoke, and Yadkin river drainages.
No. 168. Santee, Savannah, Ogeechee, and Altamaha rivers and eastern Gulf of Mexico drainages.
No. 169. Ohio and lower eastern Mississippi river drainages.
No. 170. Great Lakes and St. Lawrence River drainages.
No. 171. Hudson Bay and upper eastern and western Mississippi River drainages.
No. 172. Missouri River drainage.
No. 173. Meramec, Arkansas, Red, and lower western Mississippi river drainages.
No. 174. Western Gulf of Mexico and Rio Grande drainages.
No. 175. Colorado River drainage above Yuma.
No. 176. The Great Basin drainage.
No. 177. The Great Basin and Pacific Ocean drainages in California and Colorado River drainage below Gila River.
No. 178. Columbia River and Puget Sound drainages.

These papers embody the data collected at the regular gaging stations, the results of the computations based on the observations, and such other information as may have a direct bearing on the study of the subject, and include, as far as practicable, descriptions of the basins and the streams draining them.

For the purpose of introducing uniformity into the reports for the various years the drainages of the United States have been divided into eleven grand divisions, which have been again divided into secondary divisions, as shown in the following list. The Progress Report has been made to conform to this arrangement, each part containing the data for one or more of the secondary divisions. The secondary divisions have in most cases been redivided, and the facts have been arranged, as far as practicable, geographically.

List of drainage basins in the United States.

NORTHERN ATLANTIC DRAINAGE BASINS.

St. John.	Thames.
St. Croix.	Housatonic.
Penobscot.	Hudson.
Kennebec.	Passaic.
Androscoggin.	Raritan.
Presumpscot.	Delaware.
Saco.	Susquehanna.
Merrimac.	Potomac.
Connecticut.	Minor Chesapeake Bay.
Blackstone.	Minor northern Atlantic.

SOUTHERN ATLANTIC DRAINAGE BASINS.

James.	Great Pedee (Yadkin).
Chowan.	Santee.
Roanoke.	Savannah.
Tar.	Ogeechee.
Neuse.	Altamaha.
Cape Fear.	Minor southern Atlantic.


127°
125°
123°
79°
77°
75°
73°
71°
69°
67°
A
WASHINGTON
OREGON
MAINE
VT.
N.H.
MASS.
CONN.
R.I.
NEW YORK
PENNSYLVANIA
NEW JERSEY
MD.
DEL.
WEST VIRGINIA
VIRGINIA
KENTUCKY
NORTH CAROLINA
SOUTH CAROLINA
GEORGIA
ALABAMA
LOUISIANA
FLORIDA
500 miles
49°
47°
45°
43°
41°
39°
37°
35°
33°
31°
29°
27°
25°
85°
83°
81°
79°
77°

DURING 1905.

EASTERN GULF OF MEXICO DRAINAGE BASINS.

vanee.	Pearl.
plachicola.	Minor eastern Gulf of Mexico.
bile.	

EASTERN MISSISSIPPI RIVER DRAINAGE BASINS.

wer eastern Mississippi.	Upper eastern Mississippi.
io.	

ST. LAWRENCE DRAINAGE BASINS.

ke Superior.	Niagara River.
ke Michigan.	Lake Ontario.
ke Huron.	Lake Champlain (Richelieu River).
ke St. Clair.	Minor St. Lawrence.
ke Erie.	

WESTERN MISSISSIPPI RIVER DRAINAGE BASINS.

›per western Mississipppi.	Lower western Mississippi.
ssouri.	Arkansas.
›ramec	Red.

WESTERN GULF OF MEXICO DRAINAGE BASINS.

bine.	Guadalupe.
ches.	San Antonio.
inity.	Nueces.
razos.	Rio Grande.
lorado (of Texas).	Minor western Gulf of Mexico.

COLORADO RIVER DRAINAGE BASIN.

THE GREAT BASIN.

asatch Mountains.	Sierra Nevada.
umboldt.	Minor streams in Great Basin.

PACIFIC COAST DRAINAGE BASINS.

uthern Pacific.	Columbia.
n Francisco Bay.	Puget Sound.
rthern Pacific.	

HUDSON BAY DRAINAGE BASINS

DEFINITIONS.

The volume of water flowing in a stream, the "run-off" or "discharge," is expressed in rious terms, each of which has become associated with a certain class of work. These rms may be divided into two groups—(1) those which represent a rate of flow, as second-feet, llons per minute, miner's inch, and run-off in second-feet per square mile; and (2) those ich represent the actual quantity of water, as run-off in depth in inches and acre-feet. ey may be defined as follows:

"Second-foot" is an abbreviation for cubic foot per second, and is the rate of discharge water flowing in a stream 1 foot wide, 1 foot deep, at a rate of 1 foot per second. It is nerally used as a fundamental unit from which others are computed.

"Gallons per minute" is generally used in connection with pumping and city water pply.

The "miner's inch" is the rate of discharge of water that passes through an orifice 1 inch quare under a head which varies locally. It has been commonly used by miners and irri- tors throughout the West, and is defined by statute in each State in which it is used. In ost States the California miner's inch is used, which is the fiftieth part of a second-foot.

"Second-feet per square mile" is applied to the average number of cubic feet of water owing per second from each square mile of area drained, on the assumption that the run-off distributed uniformly both as regards time and area.

EASTERN GULF OF MEXICO DRAINAGE BASINS.

wanee.	Pearl.
plachicola.	Minor eastern Gulf of Mexico.
bile.	

EASTERN MISSISSIPPI RIVER DRAINAGE BASINS.

wer eastern Mississippi.	Upper eastern Mississippi.
io.	

ST. LAWRENCE DRAINAGE BASINS.

ke Superior.	Niagara River.
ke Michigan.	Lake Ontario.
ke Huron.	Lake Champlain (Richelieu River).
ke St. Clair.	Minor St. Lawrence.
ke Erie.	

WESTERN MISSISSIPPI RIVER DRAINAGE BASINS.

per western Mississippi.	Lower western Mississippi.
issouri.	Arkansas.
ramee	Red.

WESTERN GULF OF MEXICO DRAINAGE BASINS.

bine.	Guadalupe.
eches.	San Antonio.
inity.	Nueces.
razos.	Rio Grande.
lorado (of Texas).	Minor western Gulf of Mexico.

COLORADO RIVER DRAINAGE BASIN.

THE GREAT BASIN.

asatch Mountains.	Sierra Nevada.
umboldt.	Minor streams in Great Basin.

PACIFIC COAST DRAINAGE BASINS.

uthern Pacific.	Columbia.
n Francisco Bay.	Puget Sound.
rthern Pacific.	

HUDSON BAY DRAINAGE BASINS

DEFINITIONS.

The volume of water flowing in a stream, the "run-off" or "discharge," is expressed in rious terms, each of which has become associated with a certain class of work. These rms may be divided into two groups—(1) those which represent a rate of flow, as second-feet, llons per minute, miner's inch, and run-off in second-feet per square mile; and (2) those ich represent the actual quantity of water, as run-off in depth in inches and acre-feet. ey may be defined as follows:

"Second-foot" is an abbreviation for cubic foot per second, and is the rate of discharge water flowing in a stream 1 foot wide, 1 foot deep, at a rate of 1 foot per second. It is nerally used as a fundamental unit from which others are computed.

"Gallons per minute" is generally used in connection with pumping and city water pply.

The "miner's inch" is the rate of discharge of water that passes through an orifice 1 inch quare under a head which varies locally. It has been commonly used by miners and irri- tors throughout the West, and is defined by statute in each State in which it is used. In ost States the California miner's inch is used, which is the fiftieth part of a second-foot.

"Second-feet per square mile" is applied to the average number of cubic feet of water owing per second from each square mile of area drained, on the assumption that the run-off distributed uniformly both as regards time and area.

"Run-off in inches" is the depth to which the drainage area would be covered if al water flowing from it in a given period were conserved and uniformly distributed on the face. It is used for comparing run-off with rain fall, which is usually expressed in dep inches.

"Acre-foot" is equivalent to 43,560 cubic feet, and is the quantity required to c an acre to the depth of 1 foot. It is commonly used in connection with storage for irr tion work. There is a convenient relation between the second-foot and the acre-foot. second-foot flowing for twenty-four hours will deliver 86,400 cubic feet, or approxima 2 acre-feet.

EXPLANATION OF TABLES.

For each regular gaging station are given, as far as available, the following data:

1. Description of station.
2. List of discharge measurements.
3. Gage-height table.
4. Rating table.
5. Table of estimated monthly and yearly discharges and run-off, based on all the fa obtained to date.

The descriptions of stations give such general information about the locality and equi ment as would enable the reader to find and use the station. They also give, as far as pos ble, a complete history of all the changes since the establishment of the station that wou be factors in using the data collected.

The discharge-measurement table gives the results of the discharge measurements ma during the year, including the date, the name of the hydrographer, the area of cross se tion, the mean velocity, the gage height, and the discharge in second-feet.

The table of daily gage heights gives the daily fluctuations of the surface of the river found from the mean of the gage readings taken each day. The gage height given in the t ble represents the elevation of the surface of the water above the zero of the gage. At mo stations the gage is read in the morning and in the evening.

The rating table gives discharges in second-feet corresponding to each stage of the river given by the gage heights.

In the table of estimated monthly discharge, the column headed "Maximum" gives t mean flow for the day when the mean gage height was highest, and it is the flow as given the rating table for that mean gage height As the gage height is the mean for the da there might have been short periods when the water was higher and the corresponding d charge larger than given in this column. Likewise, in the column of "Minimum," the qu tity given is the mean flow for the day when the mean gage height was lowest The colu headed "Mean" is the average flow for each second during the month. On this are ba the computations for the three remaining columns, which are defined above.

In the computations for the tables of this report the following general and special ru have been used:

Fundamental rules for computation.

1. The highest degree of precision consistent with the rational use of time and money is imperativ
2. All items of computation should be expressed by at least two and not more than four signific figures.
3. Any measurement in a vertical velocity, mean velocity, or discharge curve whose per cent of er is five times the average per cent of error of all the other measurements should be rejected.
4. In reducing the number of significant figures, or the number of decimal places, by dropping the figure, the following rules apply:

(*a*) When the figure in the place to be rejected is less than 5, drop it without changing the prece figure. Example: 1,827.4 becomes 1,827.

(*b*) When the figure in the place to be rejected is greater than 5, drop it and increase the [redacted] ure by 1. Example: 1,827.6 becomes 1,828.

(*c*) When the figure in the place to be rejected is 5, and it is preceded by an e[redacted] Example: 1,828.5 becomes 1,828.

(*d*) When the figure in the place to be rejected is 5, and it is preceded [redacted] *and increase the* preceding figure by 1. Example: 1,827.5 becomes 1,82[redacted]

Special rules for computation.

1. Rating tables are to be constructed as closely as the data on which they are based will warrant. No decimals are to be used when the discharge is over 50 second-feet.

2. Daily discharges shall be applied directly to the gage heights as they are tabulated.

3. Monthly means are to be carried out to one decimal place when the quantities are below 100 second-feet. Between 100 and 10,000 second-feet the last figure in the monthly mean shall be a significant figure. This also applies to the yearly mean.

4. Second-feet per square mile and depth in inches for the individual months shall be carried out to at least three significant figures, except in the case of decimals where the first significant figure is preceded by one or more naughts (0), when the quantity shall be carried out to two significant figures. Example: 1.25; 0.125; 0.012; 0.0012. The yearly means for these quantities are always to be expressed in three significant figures and at least two decimal places.

CONVENIENT EQUIVALENTS.

1 second-foot equals 50 California miner's inches.
1 second-foot equals 38.4 Colorado miner's inches.
1 second-foot equals 40 Arizona miner's inches.
1 second-foot equals 7.48 United States gallons per second; equals 448.8 gallons per minute; equals 646,272 gallons for one day.
1 second-foot equals 6.23 British imperial gallons per second.
1 second-foot for one year covers 1 square mile 1.131 feet deep, 13.572 inches deep.
1 second-foot for one year equals 0.000214 cubic mile; equals 31,536,000 cubic feet.
1 second-foot equals about 1 acre-inch per hour.
1 second-foot falling 10 feet equals 1.136 horsepower.
100 California miner's inches equal 15 United States gallons per second.
100 California miner's inches equal 77 Colorado miner's inches.
100 California miner's inches for one day equal 4 acre-feet.
100 Colorado miner's inches equal 2.60 second-feet.
100 Colorado miner's inches equal 19.5 United States gallons per second, nearly.
100 Colorado miner's inches equal 130 California miner's inches.
100 Colorado miner's inches for one day equal 5.2 acre-feet.
100 United States gallons per minute equal 0.223 second-foot.
100 United States gallons per minute for one day equal 0.44 acre-foot.
1,000,000 United States gallons per day equal 1.55 second-feet.
1,000,000 United States gallons equal 3.07 acre-feet.
1,000,000 cubic feet equal 22.95 acre-feet.
1 acre-foot equals 325,850 gallons.
1 inch deep on 1 square mile equals 2,323,200 cubic feet.
1 inch deep on 1 square mile equals 0.0737 second-foot per year.
1 inch equals 2.54 centimeters.
1 foot equals 0.3048 meter.
1 yard equals 0.9144 meter.
1 mile equals 1.60935 kilometers.
1 mile equals 1,760 yards; equals 5,280 feet; equals 63,360 inches.
1 square yard equals 0.836 square meter.
1 acre equals 0.4047 hectare.
1 acre equals 43,560 square feet; equals 4,840 square yards.
1 acre equals 209 feet square, nearly.
1 square mile equals 259 hectares.
1 square mile equals 2.59 square kilometers.
1 cubic foot equals 0.0283 cubic meter.
1 cubic foot equals 7.48 gallons; equals 0.804 bushel.
1 cubic foot of water weighs 62.5 pounds.
1 cubic yard equals 0.7646 cubic meter.
1 cubic mile equals 147,198,000,000 cubic feet.
1 cubic mile equals 4,667 second-feet for one year.
1 gallon equals 3.7854 liters.
1 gallon equals 8.36 pounds of water.
1 gallon equals 231 cubic inches (liquid measure).
1 pound equals 0.4536 kilogram.
1 avoirdupois pound equals 7,000 grains.
1 troy pound equals 5,760 grams.
1 meter equals 39.37 inches. Log. 1.5951654.
1 meter equals 3.280833 feet. Log. 0.5159842.
1 meter equals 1.093611 yards. Log. 0.0388629.
1 kilometer equals 3,281 feet; equals five-eighths mile, nearly.

1 square meter equals 10.764 square feet; equals 1.196 square yards.
1 hectare equals 2.471 acres.
1 cubic meter equals 35.314 cubic feet; equals 1.308 cubic yards.
1 liter equals 1.0567 quarts.
1 gram equals 15.43 grains.
1 kilogram equals 2.2046 pounds.
1 tonneau equals 2,204.6 pounds.
1 foot per second equals 1.097 kilometers per hour.
1 foot per second equals 0.68 mile per hour.
1 cubic meter per minute equals 0.5886 second-foot.
1 atmosphere equals 15 pounds per square inch; equals 1 ton per square foot; equals 1 kilogram per square centimeter.
Acceleration of gravity equals 32.16 feet per second every second.
1 horsepower equals 550 foot-pounds per second.
1 horsepower equals 76 kilogram-meters per second.
1 horsepower equals 746 watts.
1 horsepower equals 1 second-foot falling 8.8 feet.
1½ horsepowers equal about 1 kilowatt.

To calculate water power quickly: $\frac{\text{Sec. ft.} \times \text{fall in feet}}{11}$ = net horsepower on water wheel, realizing 80 per cent of the theoretical power.

Quick formula for computing discharge over weirs: Cubic feet per minute equals $0.4025\, l\sqrt{h^3}$; l=length of weir in inches; h=head in inches flowing over weir, measured from surface of still water.

To change miles to inches on map:
Scale 1 : 125000, 1 mile=0.50688 inch.
Scale 1 : 90000, 1 mile=0.70400 inch.
Scale 1 : 62500, 1 mile=1.01376 inches.
Scale 1 : 45000, 1 mile=1.40800 inches.

FIELD METHODS OF MEASURING STREAM FLOW.

The methods used in collecting these data and in preparing them for publication are given in detail in Water-Supply Papers No. 94 (Hydrographic Manual U. S. Geological Survey) and No. 95 (Accuracy of Stream Measurements). In order that those who use this report may readily become acquainted with the general methods employed, the following brief description is given:

Streams may be devided with respect to their physical conditions into three classes—(1) those with permanent beds; (2) those with beds which change only during extreme low or high water; (3) those with constantly shifting beds. In estimating the daily flow special methods are necessary for each class. The data on which these estimates are based and the methods of collecting them are, however, in general the same.

There are three distinct methods of determining the flow of open-channel streams—(1) by measurements of slope and cross section and the use of Chezy's and Kutter's formulas; (2) by means of a weir; (3) by measurements of the velocity of the current and of the area of the cross section. The method chosen for any case depends on the local physical conditions, the degree of accuracy desired, the funds available, and the length of time the record is to be continued.

Slope method.—Much information has been collected relative to the coefficients to be used in the Chezy formula $v=c\sqrt{rs}$. This has been utilized by Kutter, both in developing his formula for c and in determining the values of the coefficient n which appears therein. The results obtained by the slope method are in general only roughly approximate, owing to the difficulty in obtaining accurate data and the uncertainty of the value for n to be used in Kutter's formula. The most common use of this method is in estimating the flood discharge of a stream when the only data available are the cross section, the slope as shown by marks along the bank, and a knowledge of the general conditions.

Weir method.—When funds are available and the conditions are such that sharp-crested weirs can be erected, these offer the best facilities for determining flow. If dams are suitably situated and constructed, they may be utilized for obtaining reliable estimates of flow. The conditions necessary to insure good results may be divided into two classes—(1) those relating to the physical characteristics of the dam itself, and (2) those relating to the diversion and use of the water around and through the dam.

ıe physical requirements are as follows: (a) Sufficient height of dam, so that backwater not interfere with free fall over it; (b) absence of leaks of appreciable magnitude; (c) graphy or abutments which confine the flow over the dam at high stages; (d) level ts, which are kept free from obstructions caused by floating logs or ice; (e) crests of a for which the coefficients to be used in $Q=c\,b\,h^{\frac{3}{2}}$, or some similar standard weir formula, known (see Water-Supply Paper No. 150); (f) either no flash boards or exceptional in reducing leakage through them and in recording their condition.

referably there should be no diversion of water through or around the dam. Generally, ever, a dam is built for purposes of power or navigation, and part or all of the water ng past it is diverted for such uses. This water is measured and added to that passing the dam. To insure accuracy in such estimates, the amount of water diverted should easonably constant. Furthermore, it should be so diverted that it can be measured, r by a weir, a current meter, or a simple system of water wheels which are of standard s or which have been rated as meters under working conditions and so installed that gate openings, the heads under which they work, and their angular velocities may be rately observed.

ıe combination of physical conditions and uses of the water should be such that the ıates of flow will not involve for a critical stage of considerable duration the use of a on a broad-crested dam of less than 6 inches. Moreover, when all other conditions good, the cooperation of the owners or operators of the plant is still essential if reliable lts are to be obtained.



FIG. 1.—Cable station, showing section of river, car, gage, etc.

gaging station at a weir or dam has the general advantage of continuity of record ugh the period of ice and floods and the disadvantages of uncertainty of coefficient to sed in the weir formula and of complications in the diversion and use of the water.

locity method.—The determination of the quantity of water flowing past a certain sec- of a stream at a given time is termed a discharge measurement. This quantity is the uct of two factors—the mean velocity and the area of the cross section. The mean city is a function of surface slope, wetted perimeter, roughness of bed, and the channel itions at, above, and below the gaging section. The area depends on the contour of bed and the fluctuations of the surface. The two principal ways of measuring the city of a stream are by floats and current meters.

reat care is taken in the selection and equipment of gaging stations for determining dis- ge by velocity measurements in order that the data may have the required degree of racy. Their essential requirements are practically the same whether the velocity is mined by meters or floats. They are located as far as possible where the channel is ght both above and below the gaging section; where there are no cross currents, back- r, or boils; where the bed of the stream is reasonably free from large projections of a ıanent character, and where the banks are high and subject to overflow only at flood s. The station must be so far removed from the effects of tributary streams and dams ther artificial obstructions that the gage height shall be an index of the discharge.

Certain permanent or semipermanent structures usually referred to as "equipment" are generally appurtenant to a gaging station. These are a gage for determining the fluctuations of the water surface, bench marks to which the datum of the gage is referred, permanent marks on a bridge or a tagged line indicating the points of measurement, and, where the current is swift, some appliance (generally a secondary cable) to hold the meter in position in the water. As a rule the stations are located at bridges if the channel conditions are satisfactory, as from them the observations can more readily be made and the cost of the equipment is small.

The floats in common use are the surface, subsurface, and tube or rod floats. A corked bottle with a flag in the top and weighted at the bottom makes one of the most satisfactory surface floats, as it is affected but little by wind. In case of flood measurements, good results can be obtained by observing the velocity of floating cakes of ice or débris. In case of all surface-float measurements, coefficients must be used to reduce the observed velocity to the mean velocity. The subsurface and tube or rod floats are intended to give directly the mean velocity in the vertical. Tubes give excellent results when the channel conditions are good, as in canals.

In measuring velocity by a float, observation is made of the time taken by the float to pass over the "run," a selected stretch of river from 50 to 200 feet long. In each discharge measurement a large number of velocity determinations are made at different points across the stream, and from these observations the mean velocity for the whole section is determined. This may be done by plotting the mean positions of the floats as indicated by the distances from the bank as ordinates and the corresponding times as abscissas. A curve through these points shows the mean time of run at any point across the stream, and the mean time for the whole stream is obtained by dividing the area bounded by this curve and its axis by the width. The length of the run divided by the mean time gives the mean velocity.

The area used in float measurements is the mean of the areas at the two ends of the run and at several intermediate sections.

The essential parts of the current meters in use are a wheel of some type, so constructed that the impact of flowing water causes it to revolve, and a device for recording or indicating the number of revolutions. The relation between the velocity of the moving water and the revolutions of the wheel is determined for each meter. This rating is done by drawing the meter through still water for a given distance at different speeds and noting the number of revolutions for each run. From these data a rating table is prepared which gives the velocity per second for any number of revolutions.

Many kinds of current meters have been constructed. They may, however, be classed in two general types—those in which the wheel is made up of a series of cups, as the Price, and those having a screw-propeller wheel, as the Haskell. Each meter has been developed for use under some special condition. In the case of the small Price meter, which has been largely developed and extensively used by the United States Geological Survey, an attempt has been made to get an instrument which could be used under practically all conditions.

Current-meter measurements may be made from a bridge, cable, boat, or by wading, and gaging stations may be classified in accordance with such use. Fig. 1 shows a typical cable station.

In making the measurement an arbitrary number of points are laid off on a line perpendicular to the thread of the stream. The points at which the velocity and depth are observed are known as measuring points, and are usually fixed at regular intervals, varying from 2 to 20 feet, depending on the size and conditions of the stream. Perpendiculars dropped from the measuring points divide the gaging section into strips. For each strip or pair of strips the mean velocity, area, and discharge are determined independently, so that conditions existing in one part of the stream may not be extended to parts where they do not apply.

Three classes of methods of measuring velocity with current meters are in general use—multiple-point, single-point, and integration.

The three principal multiple-point methods in general use are the vertical velocity curve, 0.2 and 0.8 depth, and top, bottom, and mid-depth.

In the vertical velocity-curve method a series of velocity determinations are made in each ertical at regular intervals, usually from 0.5 to 1 foot apart. By plotting these velocities s abscissas and their depths as ordinates, and drawing a smooth curve among the resulting oints, the vertical velocity curve is developed. This curve shows graphically the magnitude nd changes in velocity from the surface to the bottom of the stream. The mean velocity in he vertical is then obtained by dividing the area bounded by this velocity curve and its axis y the depth. On account of the length of time required to make a complete measurement y this method, its use is limited to the determination of coefficients for purposes of comarison and to measurements under ice.

In the second multiple-point method the meter is held successively at 0.2 and 0.8 of the epth, and the mean of the velocities at these two points is taken as the mean velocity for hat vertical. Assuming that the vertical velocity-curve is a common parabola with horiontal axis, the mean of the velocities at 0.22 and 0.79 of the depth will give (closely) the ean velocity in the vertical. Actual observations under a wide range of conditions show at this second multiple-point method gives the mean velocity very closely for open-water onditions where the depth is over 5 feet and the bed comparatively smooth, and moreover e indications are that it will hold nearly as well for ice-covered rivers.

In the third multiple-point method the meter is held at mid-depth, at 0.5 foot below the rface, and at 0.5 foot above the bottom, and the mean velocity is determined by dividing y 6 the sum of the top velocity, four times the mid-depth velocity, and the bottom velocity. his method may be modified by observing at 0.2, 0.6, and 0.8 depth.

The single-point method consists in holding the meter either at the depth of the thread of ean velocity or at an arbitrary depth for which the coefficient for reducing to mean velocity s been determined.

Extensive experiments by vertical velocity-curves show that the thread of mean velocity nerally occurs at from 0.5 to 0.7 of the total depth. In general practice the thread of mean locity is considered to be at 0.6 depth, at which point the meter is held in the majority of easurements. A large number of vertical velocity-curve measurements taken on many reams under and varying conditions show that the average coefficient for reducing the locity obtained at 0.6 depth to mean velocity is practically unity.

In the other principal single-point method the meter is held near the surface, usually 1 foot low, or low enough to be out of the effect of wind or other disturbing influences. This is own as the subsurface method. The coefficient for reducing the velocity taken at the bsurface to the mean has been found to be from 0.85 to 0.95 depending on the stage, locity, and channel conditions. The higher the stage the larger the coefficient. This ethod is especially adapted for flood measurements or when the velocity is so great that e meter can not be kept at 0.6 depth.

The vertical-integration method consists in moving the meter at a slow, uniform speed om the surface to the bottom and back again to the surface, and noting the number of volutions and the time taken in the operation. This method has the advantage that the locity at each point in the vertical is measured twice. It is well adapted for measurements der ice and as a check on the point methods.

The area, which is the other factor in the velocity method of determining the discharge of a ream, depends on the stage of the river, which is observed on the gage, and on the general ntour of the bed of the stream, which is determined by soundings. The soundings are ually taken at each measuring point at the time of the discharge measurement, either by ing the meter and cable, or by a special sounding line or rod. For streams with permaent beds standard cross sections are usually taken during low water. These sections rve to check the soundings which are taken at the time of the measurements, and from em any change which may have taken place in the bed of the stream can be detected. hey are also of value in obtaining the area for use in computations of high-water measureents, as accurate soundings are hard to obtain at high stages.

In computing the discharge measurements from the observed velocities and depths at arious points of measurement, the measuring section is divided into elementary strips, as

shown in fig. 1, and the mean velocity, area, and discharge are determined separately for either a single or a double strip. The total discharge and the area are the sums of those for the various strips, and the mean velocity is obtained by dividing the total discharge by the total area.

The determination of the flow of an ice-covered stream is difficult, owing to diversity and instability of conditions during the winter period, and also to lack of definite information in regard to the laws of flow of water under ice. The method now employed is to make frequent discharge measurements during the frozen periods by the vertical velocity-curve method and to keep an accurate record of the conditions, such as the gage height to the surface of the water as it rises in a hole cut in the ice, the thickness and character of the ice, etc. From these data an approximate estimate of the daily flow can be made by constructing a rating curve (really a series of curves) similar to that used for open channels, but considering in addition to gage heights and discharge varying thickness of ice. Such data as are available in regard to this subject are published in Water-Supply Paper No. 146, pp. 141–148.

OFFICE METHODS OF COMPUTING RUN-OFF.

There are two principal methods of estimating run-off, depending on whether or not the bed of the stream is permanent.

For stations on streams with permanent beds the first step in computing the run-off is the construction of the rating table, which shows the discharge corresponding to any stage


MEAN VELOCITY, AREA AND RATING CURVES FOR SKYKOMISH RIVER (SO. FORK) NEAR INDEX, WASH.
MEASUREMENTS IN 1902 NO. 1 TO 7
1903 8 " 12
RATING CURVE
AREA CURVE
MEAN VELOCITY CURVE
GAGE HEIGHT IN FEET
AREA IN SQUARE FEET
VELOCITY IN FEET PER SECOND
DISCHARGE IN SECOND-FEET

FIG. 2.—Rating, area, and mean-velocity curves for South Fork of Skykomish River near Index, Wash.

of the stream. This rating table is applied to the record of stage to determine the amount of water flowing. The construction of the rating table depends on the method used in measuring flow.

For a station at a weir or dam the basis for the rating table is some standard weir formula. The coefficients to be used in its application depend on the type of dam and other conditions near its crest. After inserting in the weir formula the measured length of crest and assumed coefficient the discharge is computed for various heads and the rating table constructed.

The data necessary for the construction of a rating table for a velocity-area station are the results of the discharge measurements, which include the record of stage of the river at the time of measurement, the area of the cross section, the mean velocity of the current, and the quantity of water flowing. A thorough knowledge of the conditions at and in the vicinity of the station is also necessary.

The construction of the rating table depends on the following laws of flow for open permanent channels: (1) The discharge will remain constant so long as the conditions at or near the gaging station remains constant. (2) The discharge will be the same whenever the stream is at a given stage if the change of slope due to the rise and fall of the stream be neglected. (3) The discharge is a function of and increases gradually with the stage.

The platting of results of the various discharge measurements, using gage heights as ordinates and discharge, mean velocity, and area as abscissas, will define curves which show the discharge, mean velocity, and area corresponding to any gage height. For the development of these curves there should be, therefore, a sufficient number of discharge measurements to cover the range of the stage of the stream. Fig. 2 shows a typical rating curve with its corresponding mean velocity and area curves.

As the discharge is the product of two factors, the area and the mean velocity, any change in either factor will produce a corresponding change in the discharge. Their curves are therefore constructed in order to study each independently of the other.

The area curve can be definitely determined from accurate soundings extending to the limits of high water. It is always concave toward the horizontal axis or on a straight line, unless the banks of the stream are overhanging.

The form of the mean-velocity curve depends chiefly on the surface slope, the roughness of the bed, and the cross section of the stream. Of these, the slope is the principal factor. In accordance with the relative change of these factors the curve may be either a straight line, convex, or concave toward either axis, or a combination of the three. From a careful study of the conditions at any gaging station the form which the vertical velocity-curve will take can be predicted, and it may be extended with reasonable certainty to stages beyond the limits of actual measurements. Its principal use is in connection with the area curve in locating errors in discharge measurements and in constructing the rating table.

The discharge curve is defined primarily by the measurements of discharge which are studied and weighted in accordance with the local conditions existing at the time of each measurement. The curve may however, best be located between and beyond the measurements by means of curves of area and mean velocity. The discharge curve under normal conditions is concave toward the horizontal axis and is generally parabolic in form.

In the preparation of the rating table the discharge for each tenth or half tenth on the gage is taken from the curve. The differences between successive discharges are then taken and adjusted according to the law that they shall either be constant or increasing.

The determination of daily discharge of streams with changeable beds is a difficult problem. In case there is a weir or dam available, a condition which seldom exists on streams of this class, estimates can be obtained by its use. In case of velocity-area stations frequent discharge measurements must be made if the estimates are to be other than rough approximations. For stations with beds which shift slowly or are materially changed only during floods rating tables can be prepared for periods between such changes and satisfactory results obtained with a limited number of measurements, provided that some of them are taken soon after the change occurs. For streams with continually shifting beds, such as the Colorado and Rio Grande, discharge measurements should be made every two or three days and the discharges for intervening days obtained either by interpolation modified by gage heights or by Professor Stout's method, which has been described in full in the Nineteenth Annual Report of the United States Geological Survey, Part IV, page 323, and in the Engineering News of April 21, 1904. This method or a graphical application of it is also much used in estimating flow at stations where the bed shifts but slowly.

COOPERATION AND ACKNOWLEDGMENTS.

Most of the measurements presented in this paper have been obtained through local hydrographers. Acknowledgment is extended to other persons and corporations who have assisted local hydrographers or have cooperated in any way, either by furnishing records of the height of water or by assisting in transportation.

The following list, arranged alphabetically by States, gives the names of the district hydrographers and others who have assisted in furnishing and preparing the data contained in this report:

Arizona.—District hydrographer, W. A. Farish,[a] assisted by H. S. Reed, W. Richins, O. Richins, R. H. Ross, H. R. Fry, F. Asplind, Prof. G. E. P. Smith, R. L. Newman, and E. O. Blades.

California.—The hydrographic work of the United States Geological Survey in the Colorado River drainage in California has been carried on in cooperation with the State under the direction of Supervising Engineer J. B. Lippincott,[b] assisted by Engineer W. B. Clapp.

Colorado.—District and resident engineer, M. C. Hinderlider,[c] assisted by R. I. Meeker, William A. Lamb, H. G. Graham, A. A. Weiland, O. H. Timmerman, Melvin Beeson, Thomas E. Brick, and F. L. Meeker. Acknowledgments are due the Denver and Rio Grande, Colorado and Southern, Burlington and Missouri River, and Union Pacific railroads for transportation furnished to the district hydrographer and assistants. Acknowledgments are also due the Denver Union Water Company for the use of their reservoir as a rating station for current meters.

Nevada.—The hydrographic work in this section has been carried on in cooperation with the State by Henry Thurtell,[d] State engineer, assisted by W. A. Wolf, J. T. Shaw, R. A. Craig, O. F. Heizer, H. H. Church, and L. A. Woolley. Acknowledgment is due to the Southern Pacific Company for transportation furnished to the district hydrographer and assistants, and also to the San Pedro Los Angeles, and Salt Lake Railroad for transportation furnished to the State engineer.

New Mexico.—The hydrographic work in the northern portion of this Territory was carried on under the direction of the district hydrographer, M. C. Hinderlider, assisted by R. I. Meeker and O. H. Timmerman. Acknowledgments are due the Denver and Rio Grande Railroad for transportation for R. I. Meeker.

Utah.—Engineer George L. Swendsen,[e] assisted by W. G. Swendsen, acting hydrographer, and A. B. Larson. Acknowledgments are due to the Oregon Short Line, Denver and Rio Grande, and San Pedro, Los Angeles and Salt Lake railroads for transportation; to the Telluride Power Company, the Spanish Fork and Payson canal companies, the Sevier River water users, and State Engineer C. Tanner; also to Doctor Hyatt, of the United States Weather Bureau, for material assistance in field observations. The Salt Lake daily papers have continued their interest by following conditions very closely. The hydrographic work in the Uinta Indian Reserve and on upper Green River in Utah has been carried on under the direction of the district hydrographer, M. C. Hinderlider, by the resident hydrographer, Howard S. Reed, with headquarters at Fort Duchesne.

Wyoming.—The hydrographic work in this State has been carried on under the direction of the district hydroprapher, M. C. Hinderlider, and by the resident hydrographer, A. J. Parshall. Acknowledgments are due the Union Pacific Railroad for annual passes over its lines in Wyoming for the resident hydrographer.

GENERAL DESCRIPTION OF COLORADO RIVER DRAINAGE BASIN.

Colorado River is formed in the southeastern part of Utah by the junction of Grand and Green rivers. Green River is larger than the Grand and is the upward continuation of the Colorado. Including the Green the entire length of the Colorado is about 2,000 miles. The region drained is about 800 miles long, varies in width from 300 to 500 miles, and contains about 300,000 square miles. It comprises the southwestern part of Wyoming, the western part of Colorado, the eastern half of Utah, practically all of Arizona, and small portions of California, Nevada, New Mexico, and old Mexico. Most of this area is arid, the mean annual rainfall being about 8½ inches. The streams receive their supply from the melting snows on the high mountains of Wyoming, Utah, and Colorado.

There are two distinct portions of the basin of the Colorado. The lower third is but little above the level of the sea, though here and there ranges of mountains rise to elevations of 2,000 to 6,000 feet. This part of the valley is bounded on the north by a line of cliffs which present a bold, often vertical, step hundreds or thousands of feet, to the table-land above. The upper two-thirds of the basin stands from 4,000 to 8,000 feet above sea level, and is bordered on the east, west, and north by ranges of snow-clad mountains which attain altitudes varying from 8,000 to 14,000 feet above sea level. Through this plateau the Colorado and its tributaries have cut narrow gorges or canyons in which they

[a] Office, Phoenix, Ariz.
[b] Office, 1108 Union Trust Building, Los Angeles, Cal.
[c] Office of district engineer for Colorado, Kansas, eastern Utah, northern New Mexico, and southern Wyoming, Chamber of Commerce Building, Denver, Colo.
[d] Office, Carson, Nev.
[e] Office, Salt Lake City, Utah.

t almost inaccessible depths. At points where lateral streams enter, the canyons are n by narrow, transverse valleys, diversified by bordering willows, clumps of box elder, mall groves of cottonwood. The whole upper basin of the Colorado is traversed by a inth of these canyons, most of which are dry during the greater portion of the year, and water only during the melting of the snow and the brief period of the autumnal and g rains.

w mesas, dry and treeless, stretch back from the brink of the canyons, and beyond are lines of brilliantly colored cliffs, scores or hundreds of miles in length and hundreds or sands of feet in altitude, presenting steep or even vertical faces of rock. These cliffs a series of terraces, and each marks the boundary "of some geological series of strata dges of which are exposed, like courses of masonry, in the scarp walls of the palisades." [a] lateral extension of such a line of cliffs is very irregular, sharp salients being projected he plains below and deep recesses cut into the terraces above.

he region is further diversified by short ranges of eruptive mountains. A vast system ssures extends across the country, and huge cinder cones, red, brown, and black, stand g the fissures and form conspicuous landmarks, set, as they are, in contrast to the ht varigated rocks of sedimentary origin.[b]

s a matter of convenience the drainage area has been divided into three basins: (1) en River basin, (2) Grand River basin, and (3) Colorado River below the junction of nd and Green rivers, and each of these basins is subdivided to allow the separate descrip- n of branches of the main river.

GREEN RIVER DRAINAGE BASIN.

AREA AND EXTENT.

reen River and its tributaries drain an area rudely triangular in outline, bounded on the th and east by the Wind River Mountains and the ranges forming the Continental Divide, the south and east by the White River Plateau and the Roan or Book Cliffs, and on the th and west by the Gros Ventre and Wyoming mountains and the great Wasatch Range. greatest length of the basin, north and south, is about 370 miles. In an east-west direc- n it measures at its widest point about 240 miles. The total drainage area is approxi- tely 41,000 square miles.

he area includes a large part of western Wyoming, northwestern Colorado, and eastern h. The Uinta and Uncompahgre Indian reservations are located in this basin in north- tern Utah.

n the following account of the work of the United States Geological Survey in this region ing 1905 the basin has been subdivided, as a matter of convenience, the main river being cribed first and the tributary streams, beginning at the headwaters, afterwards.

GREEN RIVER.

DESCRIPTION OF BASIN.

reen River heads on the west slope of the Wind River Mountains in western Wyoming, ultimate source being a number of small lakes fed by the glaciers and immense snow osits always to be found on Fremont and neighboring peaks. For perhaps 25 miles the er flows northwestward through the mountains. It then turns abruptly and runs in a eral southerly direction across western Wyoming into Utah. A few miles below the oming-Utah boundary another sharp turn carries the river eastward along the Uinta untains, through which it breaks near the east end of the range. It then flows south- d in Colorado for about 25 miles, turns back into Utah, and continues to flow in a south- terly and southerly direction until it unites with the Grand to form the Colorado. Its gth, measured roughly along the course, is approximately 425 miles.

---

[a] Dutton, C. E., Physical geology of the Grand Canyon district: Second Ann. Rept. U. S. Geol. Sur- , 1882, p. 51.

[b] Powell, J. W., Exploration of the Colorado River of the West, Washington, 1875, p. 6.

The topography of the headwater region is rugged in the extreme. The Wind River Range on the east and the Gros Ventre and Wyoming ranges on the northwest and west gradually close in as they extend southward, forming a basin comprising approximately 7,450 square miles in extent above the gaging station at Green River, Wyo. The upper part of this basin is very narrow, but southward the valley opens out and near Fontanelle, Wyo., is several miles wide, with benches and rolling table-lands extending westward to the foothills of the Wyoming Range and eastward to the bluffs which hug the east bank of the river. At Green River the valley is again narrow—only a few hundred yards in width—and for some distance southward the river runs between bluffs standing so close together that no flood plain is seen. Throughout much of its course in Utah the Green flows through a succession of long, deep, narrow canyons, with walls ranging in height from a few hundred to as many thousand feet, separated by short valleys containing small tracts of arable lands.

In its upper course the Green receives as tributaries numerous streams heading in the Wind River, Gros Ventre, and Wyoming ranges of mountains, some of them extending so far back into the abrupt, ragged canyons that they dovetail with streams flowing in opposite directions. The most important of these tributaries are Newfork River, Big Sandy Creek, La Barge Creek, Fontanelle Creek, Black Fork, and Henry Fork. South of the Uinta Mountains the first large stream flowing into the Green is the Yampa, which comes in from the east at the point where the Green turns westward to reenter Utah after its southward journey in Colorado. Farther south Ashley Creek and Uinta and White rivers discharge their waters to the Green, Ashley Creek and the Uinta from the west and the White from the east. Below this point the only tributaries of importance are Minnie Maud Creek and San Rafael River, which enter from the west, the latter at a point about 32 miles above the junction of the Green and the Grand.

In the foothills and in close proximity to the main ranges of the upper portion of the basin the soil is sand mixed with disintegrated granite, changing into a light, sandy loam on the rolling uplands, and a rich alluvial deposit in the valleys adjacent to the waterways. Very little land is under cultivation, and except in a few favored localities the only product is hay, which is consumed by the stock grazed on the surrounding hills. Directly south of the Uinta Mountains, in the region drained by Ashley Creek and Uinta, Whiterocks, and Duchesne rivers, large tracts of excellent agricultural land are found, much of it being comprised in the Uinta Indian Reservation.

The geology of this basin is described in the Eleventh Annual Report of the United States Geological and Geographical Survey of the Territories for 1877, F. V. Hayden in charge, pages 509-646. Information in regard to the hydrography is contained in the first to fourth annual reports of the Reclamation Service and in other United States Geological Survey reports.

GREEN RIVER AT GREENRIVER, WYO.

This station was established May 2, 1895, near the pump house at a point about 40 feet below the bridge of the Union Pacific Railroad, at Greenriver, Wyo. Since that date it has been maintained continuously, except for a few months during the winter and during the year 1900.

The channel is straight for about 500 feet above and 300 feet below the measuring section, and the banks are sufficiently high to prevent overflow. The bed of the stream is composed of sand. During low-water periods the entire right half of the channel is a bed of clean sand, shifting more or less each year, and the stream runs in a single channel on the left; but as the water rises it extends across the two channels and under the approaches of the bridge. At the gage there are at ordinary stages two channels and at times of flood four channels, interrupted, to some extent, by open cribs four feet wide, made by spiking heavy planks to piles driven into the bed of the stream, which here is sandy but stable.

Discharge measurements are made from the iron highway bridge about one-half mile below the railway bridge, as the section under the latter is unsatisfactory for the purpose. The initial point for soundings is a deep notch cut in the railing near the end of the bridge on the left bank.

The gage, which was observed during 1905 by William Slater, is a staff securely fastened to heavy submerged cribbing on the east bank of the river. The bench mark is a cross on the third step from the bottom of the south end of the east abutment of the railroad bridge; elevation 12.48 feet above the zero of the gage. It has not changed perceptibly since so placed.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 18, iv, pp 272-273; Bull 140, p 200; WS 16, p 135; 28, p 131; 37, pp 286-287; 50, pp 366-367; 66, p 82; 85, p 75; 100, p 124; 133, p 53.

Discharge: Ann 18, iv, p 274; Bull 140, p 200; WS 16, p 135; 28, p 142; 37, p 287; 66, p 82; 85, p. 75; 133, p 54.

Discharge, monthly: Ann 18, iv, p 275; 19, iv, p 395; 20, iv, pp 378-380; 21, iv, p 302; Bull 140, p 201; WS 75, p 164; 85, p 77; 133, p 56.

Discharge, yearly: Ann 20, iv, p 58.

Gage heights: Bull 140, p 201; WS 11, p 70; 16, p 135; 28, p 134; 37, p 287; 50, p 367; 66, p 83; 85, p 76; 100, p 125; 133, p 54.

Hydrographs: Ann 18, iv, p 275; 19, iv, p 396; 20, iv, p 381; 21, iv, p 303.

Rainfall and run-off relation: Ann 20, iv, p 379.

Rating tables: Ann 18, iv, p 274; 19, iv, p 395; Bull 140, p 201; 28, p 144; 39, p 451; 66, p 173; 85, p 76; 133, p 55.

Discharge measurements of Green River at Greenriver, Wyo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 26	A. J. Parshall	164	470	1.53	0.88	718
April 6	do	163	470	1.22	.85	573
April 16	do	164	535	1.67	1.15	894
April 28	do	170	644	2.13	1.70	1,374
May 18	do	166	540	1.58	1.15	854
May 28	do	234	907	2.81	2.35	2,546
June 12	do	289	1,702	4.46	4.00	7,590
June 25	do	284	1,258	3.71	3.05	4,666
June 29	do	284	1,353	3.78	3.25	5,116
July 25	do	240	919	2.60	2.30	2,392
August 6	do	170	683	2.03	1.70	1,389
August 16	do	166	621	1.77	1.40	1,103
September 8	do	164	562	1.35	1.00	759
September 23	do	159	495	.90	.55	445
October 20	do	160	509	.93	.65	476

Daily gage height, in feet, of Green River at Greenriver, Wyo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	0.8	1.42	2.65	3.4	1.95	1.2	0.7
2	.85	1.45	2.68	3.3	1.9	1.2	.75
3	.8	1.55	2.85	3.32	1.82	1.2	.8
4	.82	1.72	3.12	3.22	1.8	1.2	.78
5	.85	1.8	3.48	3.08	1.75	1.25	.75
6	.88	1.78	3.7	3.02	1.7	1.28	.72
7	.95	1.7	3.95	2.95	1.65	1.22	.7
8	.92	1.68	3.78	2.88	1.65	1.2	.7
9	.95	1.58	3.7	2.82	1.6	1.15	.68
10	1.05	1.55	3.95	2.8	1.58	1.1	.66
11	1.22	1.5	4.08	2.72	1.55	1.02	.65
12	1.25	1.45	3.95	2.65	1.5	.92	.6
13	1.2	1.35	3.72	2.62	1.45	.82	.6
14	1.15	1.3	3.48	2.7	1.45	.75	.6
15	1.15	1.22	3.65	2.72	1.45	.72	.6
16	1.15	1.18	3.9	2.75	1.38	.7	.6
17	1.2	1.1	4.0	2.75	1.32	.65	.6
18	1.2	1.15	4.0	2.78	1.28	.65	.6
19	1.2	1.3	4.28	2.72	1.2	.65	.58
20	1.25	1.5	3.95	2.68	1.15	.6	.55
21	1.28	1.68	3.6	2.6	1.2	.6	.55
22	1.3	1.72	3.25	2.55	1.2	.55	.55
23	1.28	1.88	3.05	2.45	1.2	.55	.55
24	1.28	1.98	3.0	2.42	1.2	.55	.55
25	1.35	2.2	3.02	2.32	1.25	.5	.55
26	1.42	2.3	3.1	2.22	1.2	.5	.52
27	1.52	2.3	3.15	2.2	1.2	.5	.5
28	1.58	2.42	3.22	2.15	1.15	.55	.5
29	1.6	2.58	3.32	2.12	1.2	.58	.5
30	1.55	2.72	3.4	2.08	1.2	.62	.55
31	.....	2.75	.....	2.0	1.2	.....	.55

Station rating table for Green River at Greenriver, Wyo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.50	420	1.50	1,160	2.50	2,910	3.50	5,920
.60	475	1.60	1,265	2.60	3,180	3.60	6,250
.70	535	1.70	1,380	2.70	3,460	3.70	6,585
.80	600	1.80	1,510	2.80	3,745	3.80	6,920
.90	670	1.90	1,655	2.90	4,035	3.90	7,255
1.00	745	2.00	1,815	3.00	4,330	4.00	7,590
1.10	820	2.10	1,995	3.10	4,635	4.10	7,930
1.20	900	2.20	2,195	3.20	4,945	4.20	8,270
1.30	980	2.30	2,415	3.30	5,265	4.30	8,610
1.40	1,065	2.40	2,655	3.40	5,590		

NOTE.—The above table is applicable only for open-channel conditions. It is based on 15 discharge measurements made during 1905 and is well defined.

Estimated monthly discharge of Green River at Greenriver, Wyo., for 1905.

[Drainage area, 7,450 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ril	1,265	600	883	52,540	0.119	0.133
y	3,602	820	1,582	97,270	.212	.244
ne	8,542	3,320	5,947	353,900	.798	.890
y	5,590	1,815	3,459	212,700	.464	.535
gust	1,735	860	1,122	68,990	.151	.174
tember	964	420	639	38,020	.086	.096
tober	600	420	486	29,880	.065	.075
The period				853,300		

GREEN RIVER AT JENSEN, UTAH.

This station was established November 7, 1903. It is located at Jensen post-office, about 0 feet below what is known as Billings Ferry, 15 miles from Vernal. The nearest railroad ation, Dragon, Utah, is about 40 miles distant. Brush Creek enters the river 1½ miles ove the station and Ashley Creek 3 miles below.

The channel is straight for about 1,000 feet above and below the station. The right bank high, is composed of gravel, and will not overflow; the left bank is low and sandy and overed with underbrush. The bed of the stream is sandy and shifting. There is but one hannel at all stages.

The first discharge measurements were made from the ferryboat, but the station was quipped with a cable and car during 1904. The initial point for soundings is the first hite mark on the cable on the right bank.

The gage is a vertical timber 10 feet long, braced to a cottonwood tree about 10 feet from he edge of the river. The gage is referred to bench marks as follows: (1) A 40-penny spike riven into the cottonwood tree to which the gage is attached; elevation, 10.66 feet above he zero of the gage. (2) A 40-penny spike driven into the southwest corner of Mr. Billings's rain house about 3 feet above the ground; elevation, 25.64 feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of he United States Geological Survey:

Description: 100, pp 123–124; 133, p 56.
Discharge: 100, p 124; 133, p 57.
Discharge, monthly: 133, p 58.
Gage heights: 100, p 124; 133, p 57.
Rating table: 133, p 58.

Daily gage height, in feet, of Green River at Jensen, Utah, for 1905.

Day.	June.	July.	Aug.	Day.	June.	July.	Aug.	Day.	June.	July.	Aug.
.....	8.9	6.96	3.86	12.....	11.1	5.28	.....	22.....	8.28	4.7	.....
2.....	9.18	6.79	3.82	13.....	10.88	5.2	.....	23.....	7.52	4.52	.....
3.....	9.59	6.73	3.68	14.....	10.36	5.09	.....	24.....	7.71	4.48	.....
4.....	9.81	6.64	3.6	15.....	9.98	4.97	.....	25.....	7.66	4.4	.....
5.....	10.15	6.68	3.48	16.....	9.75	4.92	.....	26.....	7.59	4.25	.....
6.....	10.4	6.49	.....	17.....	9.52	4.87	.....	27.....	7.4	4.1	.....
7.....	11.09	6.11	.....	18.....	9.49	4.82	.....	28.....	7.23	3.99	.....
8.....	11.16	5.88	.....	19.....	9.46	4.86	.....	29.....	7.09	3.93	.....
9.....	10.92	5.69	.....	20.....	9.34	4.86	.....	30.....	6.96	4.0	.....
0.....	10.82	5.47	.....	21.....	8.86	4.82	.....	31.....	.....	3.76	.....
1.....	10.05	5.39	.....								

GREEN RIVER AT OURAY, UTAH.

This station was established March 23, 1904. It is located about 500 feet below the ferry maintained by the Government at Ouray, Utah. The nearest town is Vernal, Utah, 35 miles distant, and the nearest railroad station is Dragon, about 35 miles distant.

The channel is slightly curved for about 2,000 feet above and is straight for 1,200 feet below the station. Both banks are fairly high and timbered. The right bank overflows for a short distance at high stages. The bed is composed of clean sand and is shifting. The stream is usually confined to one channel, which changes as sand bars are formed during high water. The velocity is fairly good.

Discharge measurements are made from the Government ferry cable, which is suspended across the river about 500 feet above the gage. The initial point for soundings is the first white mark on the cable on the right bank of the river.

The gage is a staff securely driven into the river bottom and spiked to a large cottonwood tree that overhangs the right bank. The gage is referred to bench marks as follows: (1) A large nail driven into the inside face of the tree that supports the gage rod; elevation, 13.80 feet above the zero of the gage. (2) A large nail driven into a blaze on a root of one of a group of large cottonwood trees 150 feet northeast of the gage; elevation, 13.51 feet above the zero of the gage.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 133 of the United States Geological Survey, pages 59–60.

Daily gage height, in feet, of Green River at Ouray, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.
1	0.5	0.8	1.45	1.15	4.32	8.45	5.75
2	.5	.8	1.55	1.1	4.75	8.75	5.55
3	.5	.82	1.72	1.1	5.0	9.25	5.46
4	.5	.88	1.92	1.0	5.6	9.72	5.32
5	.5	.95	2.0	1.0	5.95	10.1	5.22
6	.5	1.0	1.9	1.02	5.4	10.28	5.05
7	.5	1.0	1.75	1.1	4.82	10.72	4.85
8	.5	1.0	1.5	1.02	4.45	11.12	4.42
9	.5	1.0	1.25	.92	4.25	11.28	.....
10	.5	1.0	1.1	1.0	4.1	10.95	.....
11	.55	1.0	1.0	1.5	4.22	10.4	.....
12	.65	1.0	1.0	1.82	4.4	10.55	.....
13	.7	1.0	1.0	2.1	4.7	10.75	.....
14	.7	1.02	.95	2.3	4.6	10.22	.....
15	.7	1.08	.9	2.3	4.28	9.72	.....
16	.7	1.1	1.0	2.3	4.0	9.35	.....
17	.7	1.12	1.05	2.3	3.95	8.92	.....
18	.7	1.18	1.2	3.05	4.05	8.88	.....
19	.7	1.2	1.32	3.05	4.45	8.7	.....
20	.7	1.22	1.38	3.3	5.65	8.38	.....
21	.7	1.25	1.4	2.65	6.55	8.25	.....
22	.7	1.25	1.42	2.7	7.22	8.0	.....
23	.7	1.25	1.48	2.9	7.72	7.7	.....
24	.7	1.28	1.5	2.75	8.3	7.32	.....
25	.7	1.3	1.5	2.65	8.78	6.9	.....
26	.7	1.3	1.48	2.75	8.95	6.58	.....
27	.7	1.3	1.38	3.05	9.1	6.5	.....
28	.7	1.3	1.28	3.2	8.9	6.28	.....
29	.7	.....	1.18	3.3	8.9	6.1	.....
30	.72	.....	1.1	3.5	8.72	5.9	.....
31	.78	.....	1.2	.....	8.52	.....	.....

GREEN RIVER AT GREENRIVER, UTAH.

This station was established October 21, 1894, discontinued in November, 1896, and reestablished February 16, 1905. It is located at the Rio Grande Western Railway bridge at Greenriver (formerly Blake), Utah, in latitude 39° north, longitude 110° 9′ west, in the San Rafael quadrangle.

The channel is straight for about 2,000 feet above and 1,000 feet below the station. Both banks are barren and are sufficiently high to prevent overflow. At the ferry cable the bed is of clay and shale and is apparently permanent except for a thin layer of silt or sand, which is deposited near the center at low stages and sluices out at high stages. The bed at the railroad bridge is in the main solid rock and is probably permanent, but is rather rough in profile. Conditions for high-water measurements are unfavorable owing to the large masonry piers of the bridge and the high velocity of the current. The velocity at the low-water section is low. Information in regard to winter conditions is incomplete.

At low and ordinary stages discharge measurements are made from a ferryboat at a point 400 to 500 feet above the bridge. The cable to which the ferryboat is attached is graduated at 20-foot intervals with white paint. The initial point for soundings is the south face of a blazed tree, to which the cable is attached, on the west side of the stream. High-water measurements are made from the lower chord on the upstream side of the steel-truss railroad bridge. The initial point for soundings is a white zero mark across the rail on the east end of the bridge.

The gage, which was read during 1905 by Frank Jacobs, is of the chain type, and is attached to the upper guard rail of the bridge at a point near the second pier from the west end. The length of the chain is 28.45 feet. The distance from the outside edge of the pulley to the 3-foot mark on the gage rod is 1.85 feet. The old bench mark established in 1894 was on a pier, but a new bridge has since been constructed and the pier changed. It was therefore impossible to get a definite tie to the original datum. A rough tie was, however, obtained from the old inclined gage on the shore near the pump house, and this showed the present datum to be 1.68 feet below the original. In view of the fact that the cross section at the gage has been changed to some extent by the relocation of the bridge piers, it is probably impossible to establish a satisfactory relation between the original records and those now being taken. The present bench mark is the top of a 1¼-inch iron drift bolt set in the west abutment of the railroad bridge on the north side. The bolt projects about 8 inches above the surface of the stone and is on one of the footing courses of the abutment about 3 feet from the top; elevation of bench mark above the zero of the gage, 25.64 feet.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 18, iv, pp 275–276; Bull 131, p 48; 140, pp 202–203; WS 16, p 136; 28, p 131; 37, pp 292–293.
Discharge: Ann 18, iv, p 276; 19, iv, p 396; Bull 131, pp 48, 92; 140, p 202; WS 16, p 136; 37, p 293.
Discharge, monthly: Ann 18, iv, p 278; 19, iv, p 398; 20, iv, p 378, 387; 21, iv, p 304.
Discharge, yearly: Ann 20, iv, p 58.
Gage heights: Bull 140, p 203; WS 11, p 70; 16, p 136; 28, p 134; 37, p 293.
Hydrographs: Ann 18, iv, p 279; 19, iv, p 398; 20, iv, p 388; 21, iv, p 305.
Rainfall and run-off relation: Ann 20, iv, p 379.
Rating tables: Ann 18, iv, p 277; 19, iv, p 397; WS 28, p 144; 39, p 451.

Discharge measurements of Green River at Greenriver, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 16[a]	W. G Swendsen	450	1,605	1.95	4.70	3,120
April 25[a]	do	452	2,292	2.33	5.65	5,338
April 25[a]	do	452	2,292	2.34	5.65	5,380
May 12[b]	do	448	2,800	3.46	6.40	9,688
June 2[b]	do	474	3,864	5.76	8.80	22,270
June 20[b]	do	482	3,983	6.35	9.05	25,310
August 23[a]	A. B. Larson	438	1,659	1.31	4.14	2,175
August 23[a]	do	438	1,659	1.30	4.14	2,160

[a] Measurement made from ferryboat. [b] Measurement made from railroad bridge.

Daily gage height, in feet, of Green River at Greenriver, Utah, for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	3.8	4.6	5.95	8.95	7.5	5.05	3.9	5.9	4.0	3.9
2	.....	3.9	4.75	6.1	8.8	7.4	5.0	3.9	5.2	4.05	3.8
3	.....	3.9	4.8	6.6	9.0	7.3	5.0	3.9	4.9	3.95	3.6
4	.....	4.05	4.6	6.85	9.25	7.25	5.0	3.9	4.85	3.85	3.4
5	.....	4.1	4.5	7.15	9.6	7.2	5.0	4.05	4.65	4.05	3.4
6	.....	4.1	4.5	7.3	9.8	7.1	5.0	4.05	4.6	4.15	3.3
7	.....	4.25	4.5	7.25	9.85	7.0	4.9	4.7	4.45	4.1	3.3
8	.....	4.5	4.5	7.0	10.05	6.9	4.8	4.45	4.4	4.1	3.2
9	.....	4.6	4.6	6.7	10.3	6.8	4.7	4.35	4.25	4.2	3.2
10	.....	4.9	4.5	6.6	10.55	6.7	4.7	4.45	4.3	4.1	3.2
11	.....	5.05	4.5	6.4	10.5	6.6	4.6	4.55	4.4	4.0	3.3
12	.....	5.0	4.55	6.4	10.05	6.45	4.55	4.55	4.3	3.95	3.35
13	.....	4.85	4.75	6.6	10.2	6.3	4.5	4.35	4.2	3.9	3.4
14	.....	4.75	5.0	6.95	10.2	6.25	4.5	4.25	4.25	3.85	3.4
15	.....	4.7	5.15	6.75	9.95	6.05	4.5	4.05	4.1	4.0	3.4
16	3.8	4.7	5.4	6.55	9.85	6.0	4.5	4.0	4.1	4.0	3.3
17	3.6	4.7	5.3	6.4	9.35	5.95	4.45	3.9	4.1	4.0	3.4
18	3.45	4.7	5.3	6.4	9.25	5.85	4.35	4.0	4.1	4.0	3.4
19	3.45	4.7	5.65	6.4	9.15	5.8	4.2	4.1	4.0	3.9	3.4
20	3.5	4.8	5.65	6.6	9.05	5.75	4.2	4.0	3.9	3.9	3.4
21	3.5	4.75	5.45	7.0	8.85	5.7	4.2	4.15	3.9	4.0	3.4
22	3.5	4.95	5.4	7.55	8.65	5.7	4.2	4.2	4.0	4.4	3.4
23	3.6	5.0	5.5	7.95	8.55	5.6	4.2	4.3	4.05	4.25	3.5
24	3.6	4.9	5.55	8.3	8.4	5.6	4.0	4.2	4.0	4.2	3.6
25	3.6	4.8	5.65	8.6	8.35	5.5	4.0	4.4	4.0	4.1	3.6
26	3.7	4.8	5.65	8.85	8.15	5.45	4.15	4.45	4.0	4.0	3.6
27	3.7	4.8	5.5	9.05	8.05	5.4	4.15	4.6	4.0	4.05	3.6
28	3.8	4.8	5.55	9.2	7.85	5.3	4.0	4.65	4.0	4.15	3.6
29	.....	4.8	5.75	9.05	7.75	5.25	4.0	5.15	4.0	4.1	3.6
30	.....	4.7	5.95	9.05	7.6	5.2	3.95	5.85	4.0	4.0	3.6
31	.....	4.7	.....	9.0	.....	5.2	3.9	.....	4.0	.....	3.6

NOTE. Ice conditions December 24-31.

rating table for Green River at Greenriver, Utah, from February 16, 1905, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.20	1,220	4.60	2,900	6.00	7,110	7.80	16,110
3.30	1,290	4.70	3,100	6.10	7,510	8.00	17,360
3.40	1,370	4.80	3,320	6.20	7,920	8.20	18,670
3.50	1,460	4.90	3,560	6.30	8,340	8.40	20,020
3.60	1,550	5.00	3,820	6.40	8,770	8.60	21,410
3.70	1,650	5.10	4,090	6.50	9,210	8.80	22,870
3.80	1,760	5.20	4,370	6.60	9,660	9.00	24,400
3.90	1,870	5.30	4,660	6.70	10,120	9.20	25,970
4.00	1,990	5.40	4,960	6.80	10,600	9.40	27,590
4.10	2,120	5.50	5,280	6.90	11,090	9.60	29,260
4.20	2,260	5.60	5,620	7.00	11,590	9.80	30,970
4.30	2,410	5.70	5,970	7.20	12,640	10.00	32,720
4.40	2,560	5.80	6,340	7.40	13,750	10.50	37,230
4.50	2,720	5.90	6,720	7.60	14,900		

E.—The above table is applicable only for open-channel conditions. It is based on eight dis- measurements made during 1905. It is fairly well defined between gage heights 4.1 feet and 9.1

Estimated monthly discharge of Green River at Greenriver, Utah, for 1905.

[Drainage area, 38,200 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ary 16–28	1,760	1,415	1,556	40,120	0.041	0.020
	3,955	1,760	3,020	185,700	.079	.091
	6,915	2,720	4,256	253,200	.111	.124
	25,970	6,915	13,910	855,300	.364	.420
	37,700	14,900	26,380	1,570,000	.691	.771
	14,320	4,370	8,202	504,300	.215	.248
t	3,955	1,870	2,751	169,200	.072	.083
nber	6,530	1,870	2,530	150,600	.066	.074
er	6,720	1,870	2,506	154,100	.066	.076
ıber	2,560	1,815	2,052	122,100	.054	.060
ber 1–22	1,870	1,220	1,382	60,300	.036	.029
The period				4,065,000		

NEWFORK RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

wfork River and its tributaries drain a portion of the western slopes of the Wind River e, extending from Fremont Peak southeastward to Mount Bonneville, Mount Geikie, Twin Buttes. The main stream flows in a general southerly course to a point near Wyo., where it turns sharply to the southwest, joining Green River about 40 miles

The entire length of the Newfork does not exceed 50 miles. The basin as a whole is triangular in shape and comprises approximately 1,100 square miles. Forests, in some places dense, cover about 300 square miles. Pines predominate, but aspens and firs are also found.

Pine, Pole, and Boulder creeks and Eastfork River are the chief tributaries of the Newfork. These are all small streams, heading far back among the high peaks of the range and fed by the numerous springs and small mountain lakes with which the region is dotted. Fremont, Boulder, Fayette, Half Moon, Burnt, and Meadow lakes are the largest and most important of these. Fremont Lake, through which Pine Creek flows, has an area of approximately 2,500 acres. The outlet is narrow and a dam at this point might be made to raise the water surface about 30 feet. Such a dam would probably store all the surplus waters of the creek. Boulder Creek flows through Boulder Lake. The outlet of this lake also is narrow, and a dam to raise the surface of the lake about 5 feet is in process of construction. In the drainage area of Pole Creek there are said to be no less than 40 small settling basins.

The upper portion of all these streams is forested and the valleys and rolling bench lands are covered with sagebrush and a sparse growth of nutritious grasses. The soil of the foothill region is sandy and gravelly in character, gradually becoming a rich loam at the lower levels. Several ditches are taken out of Pine and Pole creeks and Eastfork River, and small areas of land are irrigated in a primitive way. The valley of Boulder Creek contains from 15,000 to 20,000 acres of the best agricultural land in the northern Green River basin. This could easily be watered from the creek, and diversion projects which contemplate the reclamation of the greater part of it are well under way.

NEWFORK RIVER NEAR CORA, WYO.

A temporary gaging station was established May 23, 1905, for the purpose of obtaining data in regard to the relative run-off of the stream and its tributaries. It is located at the "Pinedale Crossing," about 3 miles below Cora, in sec. 19, T. 34 N., R. 104 W.

The channel, though generally very winding, is straight for 150 feet above and 100 feet below the gage. The banks are not subject to overflow. The bed of the stream is composed of cobblestones and is permanent.

Discharge measurements are made by wading at a point 100 feet above or from a foot bridge 50 feet above the gage.

The gage was read at 5 p. m. six days each week (the Sunday reading being estimated) by J. J. Hansen, the mail carrier between Cora and Pinedale. The gage consists of a board nailed to a hewn timber, firmly braced by long poles to the left bank of the stream. The bench mark is the top of a stake driven into the ground 10 feet northeast of the gage, opposite the 3.50-foot mark on the gage.

The station was discontinued August 31.

Discharge measurements of Newfork River near Cora, Wyo., in 1905.

Date.	Hydrographer	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 23	A. J. Parshall	25	19	1.32	2.10	25
May 25	do	25	19	.95	2.05	18
June 18	do	35	48	3.37	2.50	162
June 22	do	30	26	1.80	2.15	47
September 20	do	12	3.2	.62	1.90	2

Daily gage height, in feet, of Newfork River near Cora, Wyo., for 1905.

Day.	June.	July.	Aug.	Day.	June.	July.	Aug.	Day.	June.	July.	Aug.
.....	2.5	2.3	2.1	12.....	2.25	2.15	2.1	23.....	2.1	2.1	2.0
.....	2.5	2.28	2.1	13.....	2.2	2.15	2.1	24.....	2.1	2.1	2.0
.....	2.5	2.25	2.1	14.....	2.25	2.2	2.1	25.....	2.1	2.1	2.0
.....	2.3	2.2	2.1	15.....	2.3	2.2	2.1	26.....	2.1	2.15	2.0
.....	2.1	2.2	2.2	16.....	2.3	2.18	2.05	27.....	2.15	2.15	2.0
.....	2.1	2.2	2.1	17.....	2.7	2.15	2.05	28.....	2.2	2.1	2.0
.....	2.1	2.2	2.1	18.....	2.5	2.1	2.05	29.....	2.2	2.1	2.0
.....	2.15	2.2	2.1	19.....	2.3	2.1	2.05	30.....	2.25	2.1	2.0
.....	2.25	2.2	2.1	20.....	2.2	2.1	2.0	31.....	.....	2.1	2.0
.....	2.3	2.2	2.1	21.....	2.2	2.1	2.0				
.....	2.28	2.2	2.1	22.....	2.15	2.1	2.0				

OTE.—Sunday gage heights estimated.

PINE CREEK NEAR PINEDALE, WYO.

ine Creek, designated on the eariler maps as Fremont Creek, rises on the southern face remont Peak, near the top, and flows southwestward to its point of junction with New- r River. Its length is about 25 miles. From its source to a point about 2 miles beyond mont Lake, through which it flows, it is a winding stream having a series of falls and ids, almost impassable even at low water. Its drainage area comprises 130 square es, about 60 square miles being covered with forest, more or less dense. Two diversion hes are taken from the stream, and together these irrigate about 2,000 acres of grass d. Another canal of larger dimensions is contemplated to provide water for an addi- al 6,000 acres.

A gaging station was established on the stream April 25, 1904. It was located about -fourth mile west of Pinedale, but this location not proving entirely satisfactory, it was ndoned at the close of the season, and April 2, 1905, it was reestablished near the Hansen ch, 1 mile above Pinedale, in sec. 28, T. 34 N., R. 109 W.

The channel is comparatively straight for several hundred feet above and below the e. The stream runs high in its banks, but does not overflow. The bed is rocky and manent. There is but one channel, and this is unobstructed except during the winter nths, when ice forms. The range of gage heights seldom exceeds 2 feet.

High-water measurements are made by means of a boat, a strong wire being stretched m bank to bank for use as an anchor. During low-water periods measurements are de by wading at a point 300 yards below the gage, where the bed of the channel is gen- lly smoother.

The gage, which during 1905 was read daily by J. J. Hansen, is a vertical 10-inch round ber, set 1 foot deep into the rocky bottom of the channel and braced firmly to a large e tree on the right bank. The bench mark is a spike driven into the tree opposite the oot mark on the gage.

A description of this station, with gage-height and discharge data, is contained in Water- pply Paper No. 133, of the United States Geological Survey, pages 60–62.

Discharge measurements of Pine Creek near Pinedale, Wyo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 29	A. J. Parshall	26	25	1.04	1.00	26
April 2	do	25	25	1.04	1.00	26
April 21	do	35	28	1.29	1.10	36
April 24	do	28	32	1.09	1.10	35
May 23	do	77	80	1.50	1.40	120
May 23[a]	do	35	52	2.04	1.40	106
May 25	do	77	87	1.58	1.45	137
May 30	G. N. Stadin	78	118	2.07	1.65	244
June 18[b]	A. J. Parshall	80	204	6.19	2.85	1,262
June 22[b]	do	80	180	4.88	2.50	878
August 11	do	80	116	2.31	1.70	268
September 16	do	30	34	2.26	1.30	77
September 20	do	30	31	2.16	1.25	67

[a] Measured at a point 300 yards below station, below a diversion ditch.
[b] Measurements made from boat.

Daily gage height, in feet, of Pine Creek near Pinedale, Wyo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	1.0	1.15	1.7	2.8	2.0	1.45	1.2
2	1.0	1.15	1.8	2.8	1.9	1.45	1.2
3	1.0	1.2	1 9	2.8	1.9	1.45	1.2
4	1.0	1.2	2.0	2.8	1.85	1.45	1.25
5	1.0	1.2	2.2	2.75	1.8	1.4	1.2
6	1.0	1.2	2.35	2.75	1.8	1.4	1.2
7	1.0	1.2	2.4	2.7	1.8	1.4	1.2
8	1.0	1.2	2.5	2.7	1.8	1.4	1.2
9	1.0	1.2	2.6	2.7	1.75	1.4	1.2
10	1.0	1.2	2.7	2.7	1.75	1.4	1.2
11	1.0	1.2	2.7	2.7	1.7	1.4	1.2
12	1.0	1.2	2.6	2.7	1.7	1.4	1.2
13	1.0	1.25	2.7	2.65	1.65	1.4	1.15
14	1.0	1.25	2.8	2.6	1.6	1.35	1.15
15	1.0	1.2	2.8	2.6	1.6	1.35	1.15
16	1.0	1.2	2.8	2.6	1.6	1.35	1.15
17	1.0	1.2	2.9	2.6	1.6	1.35	1.15
18	1.1	1.25	2.9	2.6	1.6	1.3	1.15
19	1.05	1.25	2.8	2.6	1.55	1.3	1.15
20	1.05	1.3	2.7	2.4	1.55	1.3	1.15
21	1.1	1.3	2.6	2.35	1.55	1.25	1.15
22	1.1	1.3	2.5	2.35	1.5	1.25	1.1
23	1.1	1.4	2.5	2.3	1.5	1.25	1.1
24	1.1	1.4	2.5	2.3	1.5	1.25	1.1
25	1.1	1.5	2.5	2.2	1.5	1.25	1.1
26	1.1	1.5	2.5	2.15	1.5	1.25	1.1
27	1.1	1.55	2.6	2.15	1.5	1.25	1.1
28	1.1	1.6	2.7	2.1	1.5	1.25	1.1
29	1.1	1.6	2.7	2.1	1.5	1.2	1.1
30	1.1	1.7	2.8	2.1	1.5	1.2	1.1
31	.....	1.7	.....	2.0	1.5	.....	1.1

ı rating table for Pine Creek near Pinedale, Wyo., from March 29 to September 20, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	26	1.60	206	2.20	607	2.80	1,200
1.10	35	1.70	258	2.30	694	2.90	1,313
1.20	54	1.80	316	2.40	786	3.00	1,430
1.30	83	1.90	380	2.50	885		
1.40	118	2.00	451	2.60	986		
1.50	159	2.10	526	2.70	1,091		

ε.—The above table is applicable only for open-channel conditions. It is based on 12 discharge rements made from March 29 to September 20, 1905, and is well defined.

Estimated monthly discharge of Pine Creek near Pinedale, Wyo.

[Drainage area, 130 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	35	26	29.6	1,761	0.228	0.254
.....	258	43	95.8	5,890	.737	.850
.....	1,313	258	932	55,460	7.17	8.00
.....	1,200	451	904	55,580	6.95	8.01
ıt.....	451	159	236	14,510	1.82	2.10
nber.....	138	54	96.9	5,766	.745	.831
er.....	67	35	45.1	2,773	.347	.400
The period.....	.....	.....	.....	141,700	.....	.....

POLE CREEK AT FAYETTE, WYO.

le Creek rises on the southern and western slopes of Newfork Peak, flows southwest- , and unites with Newfork River about midway between the points where Pine Creek Eastfork River join that stream. Like the other tributaries of the Newfork, it is a ıtain stream, its source of supply being the direct drainage at its head and numerous lakes and ponds, of which Fayette and Halfmoon lakes are the largest. The creek is t 25 miles in length. For the last 10 miles of its course it flows through a level or ly undulating valley, varying from 1 mile to 3 miles in width, with a rich alluvial soil. diversion ditches, which provide water for the irrigation of about 3,700 acres of land, aken from the creek.

e gaging station was established April 22, 1904. It is located at a point opposite and t 300 yards distant from Fayette post-office, in sec. 9, T. 33 N., R. 108 W.

e channel is straight for about 50 feet above and 100 feet below the station. The bank is low, is covered with brush, and is liable to overflow. The left bank is high clean and does not overflow. The bed is composed of cobblestones and sand and is e. There is but one channel at low water; at high water there is one main channel a small slough on each side. The slope of the channel is toward the left bank, and the nt is swift. Gage heights have a range of nearly 3 feet. The creek seldom freezes ely over owing to the velocity of the current and the numerous adjacent springs. e are no natural obstructions except such as are formed by the accumulations of ice ıg the willows that fringe the banks and extend back for a considerable distance.

At ordinary stages discharge measurements are made by wading at a point about 5 yards below the gage. High-water measurements are made by means of a boat swung from a wire stretched taut directly across the channel from bank to bank.

The gage, which was read during 1905 by G. N. Stadin, is a vertical timber set 1 f deep into the cobblestone bed of the stream and firmly braced to the left bank. For during high-water stages a wire gage has been attached to the vertical gage in such a v as to extend about 3 feet out over the stream. The gage is referred to bench marks follows: (1) The top of a 3-inch stake driven firmly into the ground about 10 feet from gage and marked with a copper number "0;" elevation above the zero of the gage, 4.47 f (2) The top of a similar stake about 10 feet from the gage, marked with a copper num "7;" elevation, 5.02 feet above the zero of the gage.

A description of this station, with gage-height and discharge data, is contained in Wa Supply Paper No. 133 of the United States Geological Survey, pages 62–65.

Discharge measurements of Pole Creek at Fayette, Wyo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di char
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.*
March 30	A. J. Parshall	31	24	0.79	1.00	
April 21	do	35	29	.97	1.10	
April 25	do	37	33	1.03	1.15	
May 19	G. N. Studin	42	47	2.00	1.55	
May 21	A. J. Parshall	65	50	2.05	1.65	
May 23	do	70	71	2.72	2.00	
May 24	do	70	86	2.93	2.15	
May 25	do	70	94	3.01	2.25	
May 30	G. N. Studin	70	101	3.43	2.50	
June 15[a]	A. J Parshall	70	155	5.13	3.00	
June 16[a]	do	70	156	5.29	3.05	
June 17[a]	do	70	163	5.58	3.15	
June 20[a]	do	70	131	4.50	2.80	
June 21[a]	do	70	122	4.18	2.70	
June 22[a]	do	70	114	3.98	2.65	
August 9	do	44	49	1.88	1.60	
August 13	do	43	47	1.79	1.55	
September 17	do	35	29	.96	1.12	
September 19	do	35	28	.93	1.10	

[a] Discharge measurement made from boat.

Daily gage height, in feet, of Pole Creek at Fayette, Wyo., for 1905.

Day	Apr.	May	June.	July.	Aug.	Sept.	
1	1.0	1.25	2.45	2.85	1.85	1.3	
2	1.0	1.30	2.55	2.85	1.85	1.3	
3	1.0	1.4	2.55	2.7	1.85	1.3	
4	1.0	1.4	2.7	2.7	1.85	1.3	
5	1.0	1.4	2.9	2.6	1.85	1.3	
6	1.0	1.4	2.1	2.6	1.8	1.3	
7	1.0	1.4	3.1	2.55	1.75	1.25	
8	1.0	1.4	3.2	2.55	1.7	1.25	
9	1.0	1.4	3.15	2.45	1.7	[illegible]	
10	1.0	1.45	3.2	2.4	1.[illegible]		
11	1.0	1.45	3.3	2.4	[illegible]		
12	1.0	1.45	3.2	2.4	[illegible]		
13	1.0	1.45	3.0	[illegible]			

Daily gage height, in feet, of Pole Creek at Fayette, Wyo., for 1905—Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
	1.05	1.45	2.85	2.4	1.6	1.2	1.0
	1.05	1.45	3.0	2.4	1.6	1.15	1.0
	1.05	1.45	3.0	2.4	1.5	1.15	.95
	1.05	1.45	3.05	2.35	1.5	1.15	.95
	1.1	1.45	3.1	2.3	1.5	1.1	.95
	1.1	1.5	3.0	2.25	1.5	1.05	.95
	1.1	1.55	2.85	2.25	1.5	1.05	.95
	1.1	1.5	2.7	2.15	1.5	1.05	.95
	1.05	1.8	2.65	2.1	1.4	1.05	.95
	.95	2.0	2.65	2.05	1.4	1.05	.95
	1.15	2.15	2.65	2.0	1.4	1.05	.95
	1.15	2.25	2.65	2.0	1.4	1.05	.95
	1.15	2.25	2.75	2.0	1.35	1.05	.95
	1.15	2.35	2.85	1.95	1.35	1.0	.95
	1.15	2.35	2.9	1.9	1.35	1.0	.95
	1.15	2.35	2.85	1.9	1.35	1.0	.95
	1.20	2.4	2.9	1.85	1.35	1.0	.95
	.....	2.45	.....	1.8	1.35	.....	.95

Station rating table for Pole Creek at Fayette, Wyo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	19	1.60	94	2.20	255	2.80	590
1.10	27	1.70	114	2.30	293	2.90	680
1.20	36	1.80	137	2.40	335	3.00	775
1.30	47	1.90	162	2.50	383	3.10	875
1.40	60	2.00	190	2.60	440	3.20	980
1.50	76	2.10	221	2.70	510	3.30	1,085

NOTE.—The above table is applicable only for open-channel conditions. It is based on 19 discharge measurements made during 1905. It is well defined between gage heights 1 foot and 3.2 feet.

Estimated monthly discharge of Pole Creek at Fayette, Wyo., for 1905.

[Drainage area, 126 square miles.]

Month.	Discharge in second-feet.				Run-off.	
	Maximum.	Minimum.	Mean.	Total in acre-feet.	Second-feet per square mile.	Depth in inches.
April	36	16	23.8	1,416	0.189	0.211
May	359	42	132	8,116	1.05	1.21
June	1,085	221	669	39,810	5.31	5.92
July	635	137	319	19,620	2.53	2.92
August	150	54	91.5	5,626	.726	.837
September	47	19	32.8	1,952	.260	.290
October	19	16	17.3	1,064	.137	.158
The period				77,600		

FALL CREEK NEAR FAYETTE, WYO.

Fall Creek, a small tributary of Pole Creek, joins the latter less than 2 miles from the point where it emerges from the foothills. It is fed by numerous springs and small mountain lakes and flows through Burnt Lake, which covers an area of 700 or 800 acres. The creek is about 15 miles long and drains an area of 60 square miles, of which almost one-third is forested. The entire basin is very rough. One small ditch is taken from it, conveying water upon the Pole Creek flats.

A gaging station was established April 22, 1904. It is located about 1 mile southeast of Fayette post-office, at the crossing of the Upper Boulder road, in sec. 10, T. 33 N., R. 108 W.

The channel is straight for about 40 feet above and 50 feet below the station. The banks are high and are not liable to overflow. The bed of the stream is composed of cobblestones and gravel and is smooth. The current is swift except at very low water, when it becomes sluggish. There is but one channel at all stages. Early in 1905 some large cobblestones, which at low water protruded from the riffles below the gage, were removed, and the rating curve for 1905 is therefore slightly different from that for 1904. Gage heights have a range of almost 2 feet. The stream is frozen solid during the winter months.

Discharge measurements are made at low and ordinary stages by wading, and at high water by means of a boat, the initial point for soundings being the left bank at the gage. At extreme low water a section 200 yards below the gage is chosen.

The gage, which was read during 1905 by G. N. Stadin, is a vertical timber set in the bed of the stream and firmly braced to the left bank. The bench mark is a cross on the highest point of a stone about 1 foot in diameter planted firmly in the ground 10 feet from the gage and surrounded by smaller stones. Elevation above the zero of the gage, 4.63 feet.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 133 of the United States Geological Survey, pages 65–67.

Discharge measurements of Fall Creek near Fayette, Wyo., in 1905.

Date.	Hydrographer	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft*
April 21	A. J. Parshall	31	19	0.74	1.35	14
April 25	do	30	22	.64	1.35	14
May 21	do	34	27	1.30	1.55	35
May 23	do	35	38	1.90	1.73	72
May 24	do	35	39	2.05	1.80	80
May 30	G. N. Stadin	37	47	2.83	2.00	133
June 16	A. J. Parshall	37	72	4.53	2.70	326
June 19	do	37	62	3.61	2.35	224
Do	do	55	60	3.50	2.35	210
June 20	do	37	55	3.27	2.15	180
August 9	do	33	26	1.04	1.48	27
August 13	do	33	24	.87	1.42	21
September 17	do	12	4.2	.86	1.18	3.6
September 19	do	12	4.8	.69	1.15	3.3

Daily gage height, in feet, of Fall Creek near Fayette, Wyo., for 1905.

y.	May.	June.	July.	Aug.	Sept.	Oct.	Day.	May.	June.	July	Aug.	Sept.	Oct.
.....	1.4	2.1	2.85	1.6	1.3	1.15	17.....	1.4	2.7	1.95	1.4	1.2	1.15
.....	1.4	2.2	2.85	1.6	1.3	1.15	18.....	1.45	2.65	1.9	1.4	1.15	1.15
.....	1.4	2.4	2.7	1.6	1.3	1.15	19.....	1.45	2.3	1.9	1.4	1.15	1.15
.....	1.4	2.6	2.4	1.6	1.3	1.15	20.....	1.5	2.2	1.9	1.4	1.15	1.15
.....	1.4	2.7	2.25	1.6	1.3	1.15	21.....	1.5	2.25	1.85	1.35	1.15	1.15
.....	1.4	2.8	2.15	1.6	1.25	1.15	22.....	1.65	2.15	1.8	1.35	1.15	1.15
.....	1.4	2.75	2.1	1.55	1.25	1.15	23.....	1.75	2.2	1.7	1.35	1.15	1.15
.....	1.4	2.7	2.0	1.55	1.25	1.1	24.....	1.8	2.2	1.7	1.35	1.15	1.15
.....	1.4	2.85	1.9	1.5	1.25	1.1	25.....	1.8	2.2	1.7	1.3	1.15	1.15
.....	1.4	2.9	1.95	1.5	1.25	1.1	26.....	1.9	2.4	1.6	1.3	1.1	1.15
.....	1.4	2.5	1.95	1.45	1.25	1.1	27.....	2.0	2.45	1.6	1.3	1.1	1.15
.....	1.4	2.5	1.95	1.45	1.25	1.1	28.....	2.0	2.3	1.6	1.3	1.1	1.15
.....	1.4	2.4	1.95	1.4	1.25	1.1	29.....	2.1	2.3	1.65	1.3	1.1	1.15
.....	1.4	2.4	1.95	1.4	1.2	1.1	30.....	2.1	2.3	1.65	1.3	1.1	1.15
.....	1.4	2.5	1.95	1.4	1.2	1.15	31.....	2.1	.....	1.65	1.3	.....	1.15
.....	1.4	2.65	1.95	1.4	1.2	1.15							

ion rating table for Fall Creek near Fayette, Wyo., from May 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.10	2	1.60	46	2.10	157	2.60	293
1.20	5	1.70	65	2.20	183	2.70	321
1.30	10	1.80	86	2.30	209	2.80	350
1.40	18	1.90	108	2.40	237	2.90	380
1.50	31	2.00	132	2.50	265	3.00	410

E.—The above table is applicable only for open-channel conditions. It is based on 14 discharge rements made from April 21 to September 19, 1905.

Estimated monthly discharge of Fall Creek near Fayette, Wyo., for 1905.

[Drainage area, 60 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	157	18	50.4	3,099	0.840	0.968
.....	380	157	252	15,000	4.20	4.69
.....	365	46	130	7,993	2.17	2.50
it.....	46	10	23.5	1,445	.392	.452
nber.....	10	2	5.33	317	.089	.099
er.....	3	2	2.77	170	.046	.053
The period.....	.....	.....	.....	28,020	.....	.....

BOULDER CREEK NEAR BOULDER, WYO.

Boulder Creek rises in the vicinity of Mounts Bonneville and Geikie, in the Wind Ri Mountains, flows westward through Boulder Lake, then turns to the southwest and un with Newfork River 3 miles above the point where the latter stream is joined by the E fork. Numerous small mountain lakes, scattered over an area 5 or 6 miles square, c tribute their drainage to the creek near its head. Boulder Lake, the largest of these, at an elevation of 7,200 feet and its water surface is estimated to cover 1,500 acres. total area of the basin is 160 square miles and approximately one-third of this is timbe The upper two-thirds of the basin is very rough; but the lower third is a gently sloping which contains 15,000 to 20,000 acres of excellent agricultural land.

The gaging station was established April 23, 1904. It is located at the Coolidge ra about 1½ miles northeast of Boulder post-office, in sec. 4, T. 32 N., R. 108 W., and is be all diversion ditches. In the 1904 Progress Report this station was given as Boulder C near Newfork, Wyo.

The channel is nearly straight for about 300 feet above and below the station. right bank is low and is covered with brush and small trees, but is liable to overflow f short distance only; the left bank is high and can not overflow. The bed of the strea composed of cobblestones and sand and is stable. There is but one channel at all sta and this slopes toward the left bank. The current is swift at high water, but beco sluggish at low stages. Gage heights have a range of about 4 feet. The stream fre solid during the winter months. Early in 1905 the larger rocks and some sunken drifts opposite the gage were removed, slightly changing the cross section and the value of gage heights on the discharge curve. .

Discharge measurements are made by wading at the station until the water rise about the 2-foot mark on the gage, when the wooden highway bridge, 2 miles below, is u The initial point for soundings is at the gage.

The gage, which was read during 1905 by T. J. Coolidge, is a timber firmly set in bed of the stream and braced to a tree and stump on the left bank. The bench mark spike driven in a stump opposite the 4-foot mark on the gage and 3 feet distant.

A description of this station, with gage-height and discharge data, is contained in Wa Supply Paper No. 133, of the United States Geological Survey, pages 67–69.

Discharge measurements of Boulder Creek near Boulder, Wyo.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D cha
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Se*
April 22[a]	A. J. Parshall	25	25	1.56	0.50	
May 22	do	64	122	1.76	1.10	
May 24	do	67	155	2.51	1.60	
May 24[b]	do	57	161	2.45	1.60	
May 28[b]	G. N. Stadin	60	191	2.79	1.90	
June 16[b]	A. J. Parshall	81	331	5.33	3.90	
June 19[b]	do	81	300	3.37	2.80	
June 21[b]	do	80	268	2.99	2.40	
June 24[b]	G. N. Stadin	81	301	3.89	3.00	
August 10	A. J. Parshall	60	94	.98	.75	
August 12	do	60	86	.86	.70	
September 18	do	55	46	.39	.30	

[a] Measured at point 100 yards above station. [b] Measured at bridge 2 miles bel

Daily gage height, in feet, of Boulder Creek near Boulder, Wyo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
		0.5	2.15	3.0	0.92	0.45	0.2
		.5	2.6	3.0	.9	.45	.2
		.6	2.98	2.78	.88	.45	.2
		.6	3.42	2.4	.82	.45	.2
		.6	3.92	2.4	.8	.45	.2
		.6	3.72	2.4	.8	.45	.2
		.6	3.55	2.38	.8	.42	.2
		.6	3.85	2.3	.78	.42	.2
		.6	4.15	2.3	.72	.4	.2
		.6	3.95	2.18	.7	.4	.2
		.6	3.35	2.12	.7	.4	.2
		.6	3.08	2.05	.7	.4	.2
		.6	3.25	2.02	.7	.4	.2
		.6	3.72	1.95	.65	.4	.2
	0.5	.6	3.95	1.95	.6	.4	.2
	.5	.6	3.88	1.95	.6	.4	.2
	.5	.65	3.65	1.98	.6	.38	.2
	.5	.72	3.25	1.85	.58	.3	.2
	.5	.82	2.85	1.65	.55	.3	.2
	.5	.92	2.45	1.5	.5	.3	.2
	.5	1.0	2.40	1.5	.5	.28	.2
	.5	1.1	2.55	1.45	.48	.25	.2
	.5	1.3	2.8	1.38	.45	.25	.2
	.5	1.6	3.08	1.3	.45	.25	.2
	.5	1.68	3.2	1.25	.45	.25	.2
	.5	1.75	3.22	1.2	.45	.25	.2
	.5	1.8	3.35	1.2	.45	.25	.2
	.5	1.9	3.42	1.18	.45	.22	.2
	.5	1.9	3.4	1.12	.5	.2	.2
	.5	1.9	3.15	1.02	.5	.2	.2
		1.85		1.0	.5		.2

ing table for Boulder Creek near Boulder, Wyo., from April 15, to October 31, 1905.

ge ht.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
et.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
20	9	1.10	189	2.00	594	2.90	1,097
30	18	1.20	224	2.10	644	3.00	1,160
40	29	1.30	263	2.20	695	3.20	1,289
50	42	1.40	304	2.30	747	3.40	1,421
60	58	1.50	349	2.40	800	3.60	1,557
70	77	1.60	396	2.50	855	3.80	1,695
80	100	1.70	444	2.60	913	4.00	1,835
90	127	1.80	494	2.70	973	4.20	1,975
00	157	1.90	544	2.80	1,035		

he above table is applicable only for open-channel conditions. It is based on 12 discharge its made during 1905. It is well defined between gage heights 0.5 foot and 3 feet.

Estimated monthly discharge of Boulder Creek near Boulder, Wyo., for 1905.

[Drainage area, 155 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April 15–31	42	42	42	1,333	0.271	0.1
May	544	42	188	11,560	1.21	1.4
June	1,940	913	1,350	80,330	8.71	9.7
July	1,160	157	543	33,390	3.50	4.0
August	133	35	64.5	3,966	.416	.5
September	35	9	23.6	1,404	.152	.2
October	9	9	9.0	553	.058	.1
The period				132,500		

EASTFORK RIVER AT NEWFORK, WYO.

Eastfork River, the southernmost as well as the largest of the tributaries of the Newfork, is formed by the three small creeks which drain its upper basin. Two of these, Silver and Willow creeks, head among the small mountain lakes about Twin Butte and on the southern slopes of Mount Geikie, at an elevation of about 9,000 feet; the third, Muddy Creek, is a spring stream and heads at a somewhat lower elevation farther to the south. The total area of the Eastfork basin is about 320 square miles, and perhaps 2 per cent of this is forested. The upper portion of the basin is the broken, rugged country of the mountains; farther down the valley opens out into broad, level stretches, with a gradual slope to the west. The soil is a sandy loam, well covered in its natural condition with a heavy growth of sagebrush and a smaller quantity of nutritious grasses. Irrigation is practiced in a primitive way, a few small diversion ditches taking water out upon lowland meadows.

A gaging station was established April 1, 1905. It is located at a point about one-third mile southeast of Newfork post-office, in sec. 34, T. 32 N., R. 108 W., and about one-fourth mile above the county highway bridge across Eastfork, near the Noble ranch house.

There is but one channel and the banks are not liable to overflow. The bed of the stream is sandy and shifting, and the section is less satisfactory than was supposed when the gage was installed. Gage heights have a range of about 4 feet. The bed at the highway bridge is less changeable and furnishes a better section than that first selected, though it is divided into three channels by the piling. The river freezes solid during the later months of the winter.

During the lower stages discharge measurements are made by wading at the station, the initial point for soundings being the bench mark. At high water, when the gage reads above 2.5 feet, measurements are made from the highway bridge, which is a three-span wooden structure, resting upon piling protected by rock at the bottom.

The gage, which during 1905 was read daily by Mrs. Cora Noble, is a vertical timber, firmly braced to the right bank. The bench mark is a copper "O" on the top of a post set in the ground 10 feet west of the gage; elevation, 5.68 feet above the zero of the gage.

Discharge measurements of Eastfork River at Newfork, Wyo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft*
.....	A. J. Parshall	81	64	0.69	0.30	44
.....	.....do	95	228	2.18	1.92	498
.....	.....do	95	246	2.35	2.13	577
.....	.....do	75	238	2.84	2.40	675
.....	G. N. Stadin	75	274	3.31	2.65	907
.....	A. J. Parshall	75	324	4.26	3.35	1,381
.....	.....do	75	259	2.97	2.50	769
.....	.....do	75	215	2.40	2.00	516
.....	G. N. Stadin	75	272	2.84	2.45	772
.....	A. J. Parshall	85	80	.67	.40	54
.....	.....do	83	71	.68	.35	48
18[b].	.....do	64	54	.63	.20	34

[a] Discharge measurement made at bridge below station.
[b] Discharge measurement made 100 yards below station.

Daily gage height, in feet, of Eastfork River at Newfork, Wyo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept	Oct.
.....	1.6	0.5	3.1	1.65	0.4	0.3	0.2
.....	1.6	.5	3.8	1.6	.4	.3	.2
.....	1.6	.5	4.0	1.3	.4	.3	.2
.....	1.6	.5	4.55	1.2	.4	.3	.2
.....	1.8	.4	4.9	1.1	.4	.3	.2
.....	1.2	.4	3.7	1.1	.4	.3	.2
.....	.9	.4	3.5	1.0	.4	.3	.2
.....	.9	.4	4.2	1.0	.4	.3	.2
.....	.9	.5	4.4	1.0	.4	.2	.2
.....	.8	.5	3.7	.9	.4	.2	.2
.....	.5	.5	2.85	.9	.3	.2	.2
.....	.4	.5	2.95	.8	.3	.2	.2
.....	.4	.5	3.25	.8	.3	.2	.2
.....	.4	.4	3.75	.8	.3	.2	.2
.....	.4	.4	3.5	.8	.3	.2	.2
.....	.4	.5	3.35	1.0	.3	.2	.2
.....	.4	.6	3.3	1.0	.3	.2	.2
.....	.3	1.0	2.95	.8	.3	.2	.2
.....	.3	1.0	2.35	.6	.3	.2	.2
.....	.3	1.4	2.1	.5	.3	.2	.2
.....	.3	1.7	2.05	.5	.3	.2	.2
.....	.3	2.0	2.4	.5	.3	.2	.2
.....	.3	2.3	2.55	.6	.3	.2	.2
.....	.3	2.3	2.55	.6	.3	.2	.2
.....	.3	2.2	2.45	.5	.3	.2	.2
.....	.4	2.2	2.6	.5	.3	.2	.2
.....	.4	2.55	2.35	.5	.3	.2	.2
.....	.4	2.55	2.3	.5	.3	.2	.2
.....	.4	2.3	2.0	.4	.3	.2	.6
.....	.4	2.05	1.6	.4	.3	.2	.8
.....	.....	2.2	.....	.5	.3	.....	.3

Station rating table for Eastfork River at Newfork, Wyo., from May 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.20	30	1.00	181	1.80	445	2.60	851
.30	43	1.10	208	1.90	485	2.70	914
.40	58	1.20	236	2.00	527	2.80	979
.50	75	1.30	267	2.10	572	2.90	1,046
.60	93	1.40	300	2.20	621	3.00	1,115
.70	112	1.50	334	2.30	674	3.10	1,262
.80	133	1.60	370	2.40	731		
.90	156	1.70	407	2.50	790		

NOTE.—The above table is applicable only for open-channel conditions. It is based on 12 discharge measurements made during 1905. It is fairly well defined between gage heights 0.2 foot and 2.6 feet. The table has been extended beyond these limits. Above gage height 3.20 feet the rating curve is a tangent, the difference being 76 per tenth.

Estimated monthly discharge of Eastfork River at Newfork, Wyo., for 1905.

[Drainage area, 320 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	445	43	127	7,557	0.397	0.443
May	820	58	286	17,580	.894	1.03
June	2,554	370	1,234	73,430	3.86	4.31
July	388	58	147	9,039	.459	.529
August	58	43	47.8	2,939	.149	.172
September	43	30	33.5	1,993	.105	.117
October	133	30	35.8	2,201	.112	.129
The period	.....	.....	.....	114,700	.....	.....

YAMPA RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Yampa River rises in Egeria Park, in the southeastern part of Routt County, Colo., runs in a general northerly direction to Steamboat Springs, and thence westward to its point of junction with Green River, just east of the Colorado-Utah State boundary. Throughout almost its entire course it flows in a succession of open valleys alternating with deep, narrow canyons, the longest and deepest of the canyons being that through which it enters the Green.

The drainage basin of the river lies for the most part within the boundaries of Routt County, which is a little larger than the State of Massachusetts and comprises about 6,000 square miles. Its eastern limit is formed by the Park Mountains, and the melting of the snows on their high peaks is the source of numerous small streams whose waters augment the volume of the river and form its chief perennial supply. Westward from the mountains the basin is largely the eroded and dissected Yampa Plateau, whose wide terraces, abrupt cliffs, and deep-cut gulches and arroyos are the striking features of the region. The general level is over 6,000 feet above sea.

The rocks of the basin are largely of sedimentary origin and embrace chiefly formations of tiary and Cretaceous periods. The soils derived from these rocks are friable and soft, h considerable alkali, and large tracts are covered with sagebrush. The forests in the untainous portion of the basin are composed of coniferous trees, and scattered clumps of on and cedars are found in the plateau country. Weather Bureau records show the mean ual precipitation at the town of Lay to be 12.35 inches.

Elk River, Fortification Creek, Elk Head Creek, William River, and Little Snake River are most important tributaries of the Yampa. The upper basins of these streams are within forested region, but along their lower courses are many cultivated areas.

Irrigation in the Yampa basin is confined to low bottom lands and scattered first-bench ds, but a number of systems are now under consideration.

YAMPA RIVER AT STEAMBOAT SPRINGS, COLO.

This station was established May 3, 1904, at the highway bridge at the east end of Steam- at Springs. May 8, 1905, it was reestablished at the new steel highway bridge, about one- rth mile below the old bridge, in sec. 17, T. 6 N., R. 84 W.

The channel is straight for about 400 feet above and below the station. The left bank is , but a roadway about 8 feet high leading to the bridge prevents any overflow. The left nk is high and practically clean. The stream does not overflow even at extremely high ges. The bed is composed of rock and gravel, with some sand, and is clean and perma- nt. There is but one channel at all stages, obstructed to some extent by several large wlders. The current is swift at high and medium at low stages. Gage heights have a nge of about 4.5 feet. Ice conditions during the winter months render gage readings practicable.

Discharge measurements are made from the upstream side of the single-span bridge, to hich the gage is attached. A stay line is used to keep the meter in position during measure- nts of high stages. The initial point for soundings is the upstream side of the left abut- ent, marked zero.

A standard chain gage, which was read twice each day during 1905 by Elmer Brightman, attached to the downstream side of the bridge, 35 feet from the left abutment. The length the chain is 13.43 feet. The gage is referred to bench marks as follows: (1) The top of the est side of the left abutment of the bridge; elevation 11.50 feet above the zero of the gage. 2) A standard United States Geological Survey iron post, located 100 feet south of the ft end of the old wooden bridge, one-fourth mile up the river; elevation, 15.65 feet above e zero of the gage.

A description of this station, with gage-height and discharge data, is contained in Water- upply Paper No. 133 of the United States Geological Survey, pages 70–72.

Discharge measurements of Yampa River at Steamboat Springs, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis- charge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 8	H. G. Graham	98	334	2.05	4.50	684
May 9	do	92	220	3.71	5.60	816
June 10	Hinderlider and Graham	97	447	7.36	8.15	3,290
Do	do	97	421	7.65	7.90	3,220
July 26	H. G. Graham	81	88	1.45	4.25	128
August 26	do	81	63	.75	4.00	47

Daily gage height, in feet, of Yampa River, at Steamboat Springs, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	3.65	4.95	7.5	5.15	4.38	4.0	4.18
2	3.65	5.0	7.7	5.65	4.3	4.0	4.18
3	3.65	4.9	7.85	5.4	4.3	4.0	4.1
4	3.7	4.65	8.4	5.15	4.25	4.0	4.1
5	3.75	4.55	8.7	5.05	4.18	4.02	4.1
6	3.75	4.15	8.25	4.9	4.2	4.15	4.1
7	3.75	4.45	8.6	4.8	4.22	4.18	4.08
8	3.75	4.55	8.68	4.72	4.18	4.18	4.08
9	3.8	4.75	8.68	4.68	4.15	4.12	4.08
10	4.05	5.65	8.15	4.65	4.2	4.1	4.08
11	4.05	5.62	8.65	4.52	4.25	4.1	4.08
12	4.0	5.6	7.75	4.52	4.38	4.02	4.08
13	4.05	5.48	7.75	4.42	4.32	4.1	4.08
14	4.05	5.38	7.5	4.42	4.25	4.1	4.08
15	4.0	5.32	7.65	4.42	4.18	4.08	4.08
16	4.15	5.55	7.3	4.32	4.15	4.02	4.08
17	4.15	5.75	7.08	4.32	4.12	4.02	4.08
18	4.25	6.05	7.02	4.3	4.02	4.02	4.08
19	4.25	6.22	6.85	4.3	4.0	4.02	4.05
20	4.25	6.45	6.8	4.32	4.0	4.08	4.12
21	4.15	6.75	6.72	4.3	4.0	4.08	4.18
22	4.15	6.85	6.72	4.28	4.0	4.08	4.18
23	4.15	7.1	6.35	4.25	4.0	4.02	4.18
24	4.15	7.25	6.2	4.18	4.0	4.02	4.18
25	4.15	6.95	6.0	4.15	4.0	4.08	4.18
26	4.15	7.02	5.88	4.12	4.0	4.08	4.18
27	4.25	6.95	5 65	4.18	4.0	4.08	4.18
28	4.3	6.95	5.5	4.32	4.0	4.08	4.18
29	4.35	6.8	5.4	4.35	4.0	4.1	4.18
30	4.75	6.82	5.2	4.35	3.98	4.18	4.18
31	.....	6.95	.....	4.38	4.0	.....	4.18

Station rating table for Yampa River at Steamboat Springs, Colo., from April 1 to May 18, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.20	130	4.10	440	5.00	935	5.90	1,640
3.30	146	4.20	485	5.10	,000	6.00	1,740
3.40	170	4.30	530	5.20	1,070	6.20	1,940
3.50	200	4.40	580	5.30	1,145	6.40	2,150
3.60	232	4.50	630	5.40	1.220	6.60	2,370
3.70	268	4.60	685	5.50	1,300	6.80	2,610
3.80	307	4.70	745	5.60	1,380	7.00	2,850
3.90	350	4.80	805	5.70	1,465	7.20	3,110
4.00	395	4.90	870	5.80	1,550	7.40	3,400

NOTE.—The above table is applicable only for open-channel conditions. It is based on seven discharge measurements made during 1904, and is fairly well defined.

on rating table for Yampa River at Steamboat Springs, Colo., from May 19 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.90	35	4.90	395	5.90	1,025	6.90	1,920
4.00	55	5.00	445	6.00	1,105	7.00	2,030
4.10	80	5.10	495	6.10	1,185	7.20	2,260
4.20	110	5.20	550	6.20	1,270	7.40	2,500
4.30	145	5.30	610	6.30	1,355	7.60	2,750
4.40	180	5.40	675	6.40	1,445	7.80	3,010
4.50	220	5.50	740	6.50	1,535	8.00	3,270
4.60	260	5.60	805	6.60	1,625	8.20	3,540
4.70	305	5.70	875	6.70	1,720	8.40	3,820
4.80	350	5.80	950	6.80	1,820	8.60	4,100

TE.—The above table is applicable only for open-channel conditions. It is based on five discharge urements made during 1905, and is fairly well defined.

Estimated monthly discharge of Yampa River at Steamboat Springs, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
l	775	250	418	24,870
	2,320	462	1,405	86,390
	4,240	550	2,435	144,900
	840	86	254	15,620
ıst	173	51	92.5	5,688
ember	104	55	73.1	4,350
ber	104	75	88.2	5,423
The period				287,200

YAMPA RIVER NEAR CRAIG, COLO.

is station was established April 30, 1904. It is located on the wagon bridge 1 mile ı of Craig, on the road to Meeker, Colo., in sec. 6, T. 6 N., R. 90 W., just below the h of Fortification Creek and about 7 miles above the mouth of Williams River.

e channel is straight for 250 feet above and 300 feet below the station. Both banks ow and overflow at extremely high stages. The bed of the stream is composed of sand, el, and cobblestones, and is permanent. There is but one channel at all ordinary stages, en by the piers of the bridge; at high stages the stream flows through the culverts at end of the bridge, and the current is materially broken by the driftwood which inva- y collects at the upper side of the piers. The current is swift at high, but very sluggish w water. Gage heights have a range of about 6 feet during an ordinary season. Ice in hannel renders gage readings impracticable during the winter months.

scharge measurements are made from the downstream side of the three-span tubular pier bridge. The initial point for soundings is the vertical wall of the old log abut- on the left bank, to which the gage is attached.

e gage, which was read twice each day during 1905 by Lawson Thompson, is a vertical er 12 feet long, fastened to a pile on the old log abutment at the left end of the bridge. gage is referred to bench marks as follows: (1) The top of a bolt marked with a cross on op of the tubular steel and concrete pier on the downstream side of the left abutment

of the bridge; elevation, 14.34 feet above the zero of the gage. (2) The top of a bolt marked with a cross on the top of the corresponding pier on the upstream side of the bridge; elevation, 14.37 feet above the zero of the gage.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 133, of the United States Geological Survey, pages 72–74.

Discharge measurements of Yampa River near Craig, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 5	H. G. Graham	181	913	2.83	4.75	2,58
June 8	Hinderlider, Graham, and Hoyt	204	1,474	4.91	7.72	7,24
July 24	H. G. Graham	123	545	.82	2.70	45
August 25	do	122	447	.33	1.95	15
August 27	do	122	441	.32	1.95	13

Daily gage height, in feet, of Yampa River near Craig, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	2.8	5.6	6.75	4.55	2.6	1.8	2.0
2	3.05	5.85	7.15	4.45	2.65	1.8	2.0
3	2.9	5.55	7.15	4.7	2.6	1.8	2.0
4	2.85	5.05	7.45	4.55	2.65	1.8	2.0
5	2.75	4.65	8.05	4.35	2.6	1.8	2.0
6	2.85	4.5	8.0	4.1	2.85	1.8	2.0
7	3.35	4.35	7.45	3.8	2.85	1.8	2.0
8	3.7	4.5	7.6	3.8	2.85	1.95	2.0
9	4.15	5.15	7.8	3.7	2.85	2.2	2.0
10	4.35	5.25	8.1	3.65	2.85	2.2	2.0
11	4.05	4.8	7.55	3.6	2.65	2.2	2.0
12	3.8	4.65	7.35	3.55	2.55	1.9	1.9
13	3.8	4.6	7.0	3.5	2.5	1.9	1.9
14	4.25	4.7	7.2	3.4	2.4	1.9	1.9
15	3.8	4.55	6.9	3.4	2.35	1.8	2.0
16	3.8	4.8	6.9	3.25	2.4	1.8	2.0
17	3.95	4.75	6.7	3.15	2.4	1.8	2.0
18	4.15	5.7	6.4	2.95	2.4	1.8	2.1
19	4.4	6.3	6.25	2.9	2.45	1.8	2.0
20	4.4	6.65	6.0	2.95	2.4	1.8	2.0
21	4.25	6.8	5.8	2.9	2.25	1.85	2.0
22	4.15	7.15	5.75	2.9	2.25	1.9	2.0
23	4.2	7.4	5.9	2.75	2.3	1.9	2.0
24	4.4	7.7	5.75	2.7	2.15	1.8	2.1
25	4.35	7.45	5.55	2.55	1.95	1.9	2.1
26	4.35	7.0	5.45	2.6	1.9	1.9	2.0
27	4.65	6.95	5.3	2.6	1.9	1.9	2.1
28	5.1	6.9	5.0	2.55	1.9	1.9	2.1
29	5.25	6.75	4.9	2.5	1.9	1.9	2.1
30	5.4	6.35	4.75	2.5	1.9	1.9	2.15
31	.....	6.25	.....	2.5	1.8	.....	2.2

ation rating table for Yampa River near Craig, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.80	100	3.00	670	4.20	1,750	5.80	4,040
1.90	125	3.10	740	4.30	1,860	6.00	4,390
2.00	155	3.20	810	4.40	1,980	6.20	4,750
2.10	190	3.30	890	4.50	2,100	6.40	5,130
2.20	230	3.40	970	4.60	2,230	6.60	5,520
2.30	270	3.50	1,060	4.70	2,360	6.80	5,930
2.40	320	3.60	1,150	4.80	2,490	7.00	6,360
2.50	370	3.70	1,240	4.90	2,630	7.50	7,520
2.60	420	3.80	1,330	5.00	2,770	8.00	8,750
2.70	480	3.90	1,430	5.20	3,070		
2.80	540	4.00	1,530	5.40	3,380		
2.90	600	4.10	1,640	5.60	3,700		

RE.—The above table is applicable only for open-channel conditions. It is based on discharge measents made during 1904–1905. It is well defined between gage heights 1.9 feet and 4.8 feet.

Estimated monthly discharge of Yampa River near Craig, Colo., for 1905.

[Drainage area, 1,730 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
l	3,380	510	1,579	93,960	0.913	1.02
	8,000	1,920	4,177	256,800	2.41	2.78
	9,000	2,425	5,713	339,900	3.30	3.68
	2,360	370	1,002	61,610	.579	.668
ust	570	100	333	20,480	.192	.221
ember	230	100	124	7,379	.072	.080
ber	230	125	163	10,020	0.94	.108
The period				790,100		

YAMPA RIVER NEAR MAYBELL, COLO.

his station was established April 17, 1904. It is located at the Thornburg bridge, 10 s west of Maybell and 75 miles from Meeker, Colo., in sec. 19, T. 7 N., R. 96 W.

he channel is straight for about 300 feet above and 600 feet below the station. The left k is low and clean and overflows to a considerable extent during high water. The right k is high and clean and is not subject to overflow. The bed of the stream is composed ravel and sand and is shifting. Ice conditions render gage readings impracticable dur- the winter months. The ordinary range of gage heights is about 6 feet.

ischarge measurements are made from the downstream side of the two-span bridge to ch the gage is fastened. The initial point for soundings is the edge of the left abutment.

he gage, which was read twice each day during 1905 by Peter Farrell, is a staff fastened he left downstream edge of the middle pier of the bridge. The bench mark is a United es Geological Survey standard bronze tablet set in the top stone of the right abut- nt on the downstream side; elevation above the zero of the gage, 10.79 feet.

. description of this station, with gage-height and discharge data, is contained in Water- pply Paper No. 133, of the United States Geological Survey, pages 75–77.

Discharge measurements of Yampa River near Maybell, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 24	H. G. Graham	210	1,623	5.64	6.20	9,154
May 25	do	210	1,645	5.53	6.25	9,097
May 27	do	210	1,496	5.23	5.60	7,824
June 25	do	207	1,165	4.03	4.20	4,699
June 26	do	206	1,099	3.72	3.90	4,088
Aug. 18	do	172	409	.56	.45	229

Daily gage height, in feet, of Yampa River near Maybell, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	1.3	3.9	5.8	2.4	1.55	0.1	0.1
2	1.35	4.2	6.0	2.25	1.2	.15	.25
3	1.5	4.3	5.85	2.65	1.2	.15	.1
4	1.45	4.1	5.9	2.4	1.25	.2	.25
5	1.25	4.1	6.0	2.4	1.15	.18	.1
6	1.35	3.5	6.1	2.4	.95	.4	.25
7	1.5	4.05	6.2	2.3	.95	.3	.2
8	1.65	4.1	6.75	2.2	.8	.35	.25
9	2.05	3.9	5.85	1.95	.7	.3	.2
10	2.65	3.75	5.5	1.75	.5	.45	.2
11	2.5	3.4	5.95	1.7	.55	.35	.3
12	2.4	3.4	6.5	1.5	.4	.4	.3
13	2.75	3.3	6.6	1.5	.45	.25	.2
14	2.75	3.55	6.65	1.4	.4	.28	.25
15	2.65	3.3	6.4	1.35	.2	.35	.3
16	2.55	3.4	5.55	1.45	.3	.3	.4
17	2.65	3.6	4.75	1.3	.25	.22	.3
18	2.6	4.1	4.55	1.25	.35	.2	.3
19	2.75	4.95	4.45	1.25	.4	.22	.2
20	2.8	5.55	4.35	1.15	.35	.2	.3
21	2.55	5.8	4.4	1.1	.35	.2	.55
22	2.6	5.85	4.2	1.35	.3	.25	.4
23	2.75	6.25	4.25	1.1	.15	.35	.3
24	2.8	6.25	4.45	1.05	.3	.28	.3
25	2.65	6.25	4.05	.9	.25	.25	.15
26	3.05	5.75	3.9	1.2	.15	.3	.2
27	3.1	5.65	3.75	1.15	.2	.4	.25
28	3.4	5.7	3.4	1.05	.25	.35	.35
29	3.35	5.9	3.3	1.15	.2	.25	.4
30	3.75	5.9	3.15	1.3	.2	.25	.3
31		5.7		1.5	.2		.25

rating table for Yampa River near Maybell, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.00	100	1.30	690	2.60	1,950	3.90	3,920
.10	130	1.40	760	2.70	2,080	4.00	4,100
.20	160	1.50	840	2.80	2,210	4.20	4,470
.30	190	1.60	920	2.90	2,340	4.40	4,860
.40	230	1.70	1,000	3.00	2,480	4.60	5,270
.50	270	1.80	1,090	3.10	2,620	4.80	5,710
.60	310	1.90	1,180	3.20	2,770	5.00	6,170
.70	350	2.00	1,280	3.30	2,920	5.20	6,640
.80	400	2.10	1,380	3.40	3,080	5.40	7,120
.90	450	2.20	1,490	3.50	3,240	5.60	7,610
1.00	500	2.30	1,600	3.60	3,400	5.80	8,110
1.10	560	2.40	1,710	3.70	3,570	6.00	8,630
1.20	620	2.50	1,830	3.80	3,740	6.50	10,070

t.—The above table is applicable only for open-channel conditions. It is based on discharge ·ements made during 1904-1905, and it is well defined.

Estimated monthly discharge of Yampa River near Maybell, Colo., for 1905.

[Drainage area, 3,670 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	3,655	655	1,825	108,600	0.497	0.554
.....	9,325	2,920	5,581	343,200	1.52	.75
.....	10,850	2,695	6,768	402,700	1.84	05
.....	2,015	450	968	59,520	.264	304
t.....	880	145	303	18,630	.083	096
nber.....	250	130	185	11,010	.050	056
er.....	290	145	188	11,560	.051	.059
ie period.....	.....	.....	.....	955,200	.....	.....

ELK RIVER NEAR TRULL, COLO.

; River rises in the northeastern part of Routt County, Colo., flows southward, and Yampa River 6 miles below Steamboat Springs. The drainage basin comprises the rn slope of the Park Range and the greater part of it is mountainous, but there is some prairie land along the river and its larger tributaries. Much of this prairie land is under 'ation, being irrigated by numerous ditches from the streams. Hay is the principal but in the lower portion of the valley cereals are raised to some extent. The higher ons of the basin are covered by heavy forests of pine and spruce. Precipitation con- principally of snow during the winter months.

e gaging station was established May 2, 1904. It is located about 2 miles southeast of post-office, on the stage road between Steamboat Springs and Hayden, Colo., in sec. ·7 N., R. 85 W., and is below all tributaries.

e channel is straight for 100 feet above and for 300 feet below the station. Both s are low but are not liable to overflow except at very high stages. The bed of the m is composed of rock and is permanent. There is but one channel at all stages. The

current is swift at all times and exceedingly so at high water. Ice conditions render gage readings impracticable during the winter months. Gage heights have an ordinary range of about 4 feet.

Discharge measurements are made from the downstream side of the single-span bridge to which the gage is attached. The initial point for soundings is the vertical wall of the masonry abutment at the left end of the bridge on the downstream side. There is also a stay-wire about 50 feet above the bridge for holding the meter at high stages.

The gage was read twice each day during 1905 by H. W. Hitchins. The original gage was timber, placed vertically near the right end of the bridge. This was replaced June 22, 1904, by a standard chain gage, referred to the same datum. The chain hangs from a point 25 feet from the initial point for soundings on the downstream side of the bridge. The length of the chain is 16.20 feet. The bench mark is a United States Geological Survey standard aluminum bench-mark tablet, set on the downstream end of the masonry abutment at the right end of the bridge; elevation, 15.995 feet above datum of gage.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 133 of the United States Geological Survey, pages 78–80.

Discharge measurements of Elk River near Trull, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 7..	H. G. Graham	115	315	2.95	7.28	931
June 11	Hinderlider and Graham	115	449	6.01	8.78	2,695
July 25	H. G. Graham	95	125	2.31	6.00	289
August 26	do	86	47	2.30	5.20	108

Daily gage height, in feet, of Elk River near Trull, Colo., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Day.	May.	June.	July.	Aug.	
1	.....	8.9	7.72	6.0	5.1	17	8.15	8.65	6.52	5.3	.....
2	.....	8.95	7.8	5.85	5.1	18	8.5	8.55	6.38	5.3	.....
3	.....	9.08	8.52	5.78	5.1	19	8.75	8.3	6.38	5.28	.....
4	.....	9.5	7.85	5.72	5.1	20	8.8	8.28	6.42	5.25	.....
5	.....	9.55	7.25	5.7	5.2	21	8.9	8.4	6.3	5.2	.....
6	.....	9.1	7.15	5.65	5.25	22	9.02	8.35	6.28	5.18	.....
7	7.25	9.05	7.2	5.65	5.32	23	9.22	8.45	6.32	5.15	.....
8	7.4	9.25	7.25	5.62	5.32	24	9.15	8.52	6.15	5.15	.....
9	7.9	9.42	6.95	5.6	5.22	25	8.85	8.45	6.0	5.2	.....
10	7.8	9.0	6.9	5.6	.....	26	8.78	8.2	5.95	5.2	.....
11	7.5	8.78	6.85	5.65	.....	27	8.8	8.05	5.9	5.2	.....
12	7.4	8.88	6.85	5.65	.....	28	8.72	8.15	5.9	5.18	.....
13	7.45	8.85	6.82	5.55	.....	29	8.45	8.0	5.82	5.15	.....
14	7.45	8.88	6.7	5.52	.....	30	8.3	8.1	5.88	5.18	.....
15	7.4	8.9	6.78	5.42	.....	31	8.55	.....	5.88	5.15	.....
16	7.85	8.85	6.65	5.38	.....						

m rating table for Elk River near Trull, Colo., from May 2, 1904, to September 9, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
5.00	60	6.00	312	7.00	785	8.00	1,520
5.10	73	6.10	350	7.10	845	8.20	1,710
5.20	88	6.20	390	7.20	905	8.40	1,910
5.30	107	6.30	430	7.30	975	8.60	2,120
5.40	130	6.40	470	7.40	1,045	8.80	2,365
5.50	156	6.50	520	7.50	1,115	9.00	2,630
5.60	184	6.60	570	7.60	1,190	9.20	2,910
5.70	213	6.70	620	7.70	1,270	9.40	3,190
5.80	244	6.80	670	7.80	1,350	9.60	3,485
5.90	277	6.90	725	7.90	1,430		

E.—The above table is applicable only for open-channel conditions. It is based on discharge irements made during 1904-1 05. It is fairly we l defined between gage heights 5.5 feet and 9 feet.

Estimated monthly discharge of Elk River near Trull, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
-31	2,938	940	1,841	91,290
	3,410	1,520	2,303	137,000
	2,032	250	667	41,010
st	312	80	146	8,977
mber 1-9	111	73	87.9	1,569
The period				279,800

FORTIFICATION CREEK AT CRAIG, COLO.

rtification Creek rises near Mount Walba, in northeastern Routt County, Colo., flows ward, southeastward, and southwestward, and joins Yampa River at Craig.

ıe gaging station was established June 12, 1905. It is located at the highway bridge ıt one-fourth mile east of Craig, Colo., in sec. 6, T. 6 N., R. 90 W.

ıe channel is straight for about 50 feet above and 20 feet below the station. The right : is low and overflows at very high water; the left bank is high. The bed of the stream is posed of sand and silt and is shifting. There is at all stages but one channel, which y late in the summer.

scharge measurements are made from the downstream side of the single-span bridge to h the gage is fastened. The initial point for soundings is the lower side of the bridge, with the west abutment.

e gage, which was read twice each day by H. W. Rose, a civil engineer who lives at the ın, is a vertical staff, fastened to the east abutment on the lower side of the bridge.

neasurement made June 12, 1905, by H. G. Graham, gave the following results: Width, ·t area, 84 square feet; mean velocity, 2.52 feet per second; gage height, 4.40 feet; arge, 212 second-feet.

Daily gage height, in feet, of Fortification Creek at Craig, Colo., for 1905.

Day.	June.	Day.	June	Day.	June.	Day.	Ju
1	5.55	7	5.1	13	4.15	19	
2	5.92	8	5.05	14	3.95	20	
3	5.88	9	5.05	15	3.75	21	
4	6.2	10	5.45	16	3.7	22	
5	6.4	11	4.7	17	3.5	23	
6	6.1	12	4.6	18	3.35	24	

NOTE.—Creek dry after June 24.

WILLIAMS RIVER AT HAMILTON, COLO.

Williams River rises in the White River Plateau, the highest portion of which reach elevation of 11,000 feet. It flows northwestward and unites with Yampa River ab miles below Craig. It is joined by numerous small tributaries which drain portions o Williams River Mountains on the east and the Danforth Hills on the south. The larg these tributaries is Marapos Creek, which rises near the Milk Creek divide, flows east and joins Williams River at Hamilton. The entire drainage area is hilly or mountai and throughout the upper portion of it there are extensive forests, mainly of white and spruce. Farther down the forests give way to a growth of willows and cottonwood the river bottom and oak brush and shrubbery on the hillsides. Agriculture is confin the narrow valley extending along the river and some of its largest tributaries. Wild h the principal crop, and cattle raising is carried on extensively. The precipitation co chiefly of snow during the winter months. The maximum discharge occurs during the part of May.

The gaging station was established April 29, 1904. It is located at the highway brid Hamilton, on the stage road from Meeker to Craig, Colo., about 17 miles from Craig, i 20, T. 5 N., R. 91 W.

The channel is straight for about 150 feet above and 100 feet below the station. The bank is high, rocky, and clean; the left bank is low and wooded, but does not overflo cept at extreme high stages. The bed of the stream is composed of cobblestones and g but is shifting. There is but one channel at all stages. Gage heights have an ordinary of about 3 feet. During the winter season ice obstructs the channel to such an exten gage readings are impracticable.

Discharge measurements are made from the lower side of the single-span bridge to the gage is attached. The initial point for soundings is the downstream end of the ve log abutment at the left end of the bridge.

The gage, which during the early part of 1905 was read twice each day by Mrs. Th Hamilton, was a 14-foot timber, driven vertically into the bottom of the river, with the end fastened to the lower side of the bridge. May 21, 1905, a standard chain gage w stalled, the datum being the same as that of the original gage. The length of the ch 14.94 feet. The gage is referred to bench marks as follows: (1) A nail driven into th log at the northeast corner of the left abutment of the bridge; elevation, 12.22 feet. (2 head of a nail driven into a root on the west side of a small cottonwood tree about 2 from the left end of the bridge and just east of the road; elevation, 10.08 feet. (3) driven into the southeast corner of the foundation of the blacksmith shop about 2 from the left end of the bridge; elevation, 10.08 feet. (4) A United States Geologica vey standard iron post at the southeast corner of the wagon bridge; elevation, 10.7 Elevations are above the zero of the gage.

A description of this station, with gage-height and discharge data, is Supply Paper No. 133 of the United States Geological Survey, pages 8

Discharge measurements of Williams River at Hamilton, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	H. G. Graham	46	149	2.87	4.10	428
.....	.....do.....	60	262	4.91	6.05	1,286
.....	Hinderlider, Hoyt, and Graham...	55	199	4.22	5.48	840
.....	H. G. Graham.....	55	203	4.98	5.55	1,011
.....	.....do.....	39	76	1.17	3.25	89
.....	.....do.....	39	80	1.10	3.30	88
.....	.....do.....	38	64	.55	2.90	35

Daily gage height, in feet, of Williams River at Hamilton, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	2.78	4.25	5.95	3.8	3.48	2.78	3.02
.....	2.8	4.55	6.02	3.85	3.25	2.8	2.95
.....	2.8	4.15	6.05	3.82	3.2	2.82	2.95
.....	2.78	3.78	6.5	3.75	3.12	2.85	2.92
.....	2.75	3.7	6.4	3.62	3.0	2.88	2.9
.....	2.78	3.6	5.82	3.65	3.08	3.05	2.9
.....	2.78	3.52	5.75	3.6	3.0	3.08	2.88
.....	2.88	3.8	5.82	3.55	3.0	3.0	3.35
.....	2.95	4.4	6.15	3.5	2.98	2.98	2.9
.....	2.95	4.32	5.72	3.4	2.92	2.88	2.95
.....	2.92	4.1	5.32	3.6	3.0	2.88	2.85
.....	2.95	4.0	5.3	3.3	3.1	2.85	2.9
.....	2.9	4.08	5.4	3.35	3.15	2.82	2.98
.....	2.92	3.95	5.35	3.3	3.05	2.9	2.92
.....	2.92	3.95	5.40	3.25	2.98	2.85	2.95
.....	2.95	4.3	5.40	3.12	2.92	2.82	2.95
.....	3.0	4.9	4.85	3.18	2.8	2.78	2.98
.....	3.0	5.32	4.95	3.2	2.82	2.85	2.92
.....	3.1	5.6	4.78	3.2	2.88	2.88	2.85
.....	3.15	5.95	4.60	3.45	2.9	2.85	2.85
.....	3.1	5.92	4.65	3.58	2.88	2.92	2.88
.....	3.02	6.28	4.65	3.38	2.82	2.92	2.9
.....	3.05	6.65	4.78	3.28	2.82	2.85	3.0
.....	3.1	6.62	4.65	3.18	2.85	2.88	3.05
.....	3.18	5.9	4.4	3.05	2.9	2.88	3.0
.....	3.18	5.82	4.3	3.05	2.95	3.0	2.98
.....	3.28	6.0	4.18	3.05	2.9	2.98	3.0
.....	3.6	5.6	4.08	3.5	2.85	2.92	2.98
.....	3.65	5.22	4.05	3.2	2.85	2.98	2.98
.....	3.82	5.28	3.92	3.12	2.8	3.05	3.0
.....	.....	5.65	.....	3.15	2.78	.....	3.0

Station rating table for Williams River at Hamilton, Colo., from April 1 to May 23,

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-fee*
2.70	60	3.80	330	4.90	720	6.00	1,240
2.80	80	3.90	360	5.00	760	6.10	1,300
2.90	100	4.00	390	5.10	800	6.20	1,360
3.00	125	4.10	420	5.20	845	6.30	1,430
3.10	150	4.20	455	5.30	890	6.40	1,500
3.20	175	4.30	490	5.40	935	6.50	1,570
3.30	200	4.40	525	5.50	980	6.60	1,640
3.40	225	4.50	560	5.60	1,030	6.70	1,710
3.50	250	4.60	600	5.70	1,080		
3.60	275	4.70	640	5.80	1,130		
3.70	300	4.80	680	5.90	1,180		

NOTE.—The above table is applicable only for open-channel conditions. It is based on two di measurements made during 1905. It is not well defined.

Station rating table for Williams River at Hamilton, Colo., from May 24 to October 31

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharg
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-fe*
2.70	15	3.80	200	4.90	565	6.00	1,160
2.80	25	3.90	225	5.00	605	6.10	1,230
2.90	35	4.00	255	5.10	650	6.20	1,310
3.00	50	4.10	285	5.20	700	6.30	1,390
3.10	65	4.20	315	5.30	750	6.40	1,470
3.20	80	4.30	345	5.40	800	6.50	1,550
3.30	95	4.40	375	5.50	850	6.60	1,630
3.40	110	4.50	410	5.60	910	6.70	1,710
3.50	130	4.60	445	5.70	970		
3.60	150	4.70	485	5.80	1,030		
3.70	175	4.80	525	5.90	1,090		

NOTE.—The above table is applicable only for open-channel conditions. It is based on four d measurements made during 1905. It is well defined between gage heights 2.9 feet and 3.3 feet.

Estimated monthly discharge of Williams River at Hamilton, Colo., for 1905.

Month.	Discharge in second-feet.			T
	Maximum.	Minimum.	Mean.	
April	336	70	135	
May	1,675	255	737	
June	1,550	231	745	
July	212	58	115	
August	126	23	46.6	
September	62	23	36.6	
October	102	30	43.6	
The period				

MILK CREEK NEAR AXIAL, COLO.

ilk Creek rises in the northeastern part of Rio Blanco County, Colo., flows northwestward, enters Yampa River about 20 miles below Craig.

ıe gaging station was established April 20, 1904. It is located at the highway bridge ıt 4 miles below Axial, Colo., in sec. 19, T. 4 N., R. 92 W.

ıe channel is straight for 75 feet above and 50 feet below the station. Both banks are and clean and do not overflow. The bed of the stream is composed of sand, and shifts ıch an extent that it is difficult to obtain a good rating curve. There is but one channel l stages, the current being swift at high and medium at low water. Gage heights have a ıe of about 3.5 feet during an ordinary season. Ice conditions render gage readings ıacticable during the winter months.

ischarge measurements are made from the lower side of the single-span bridge to which gage is attached. The initial point for soundings is at the left end of the bridge, at the ır's edge, on the downstream side.

he original gage, which was read once each day during 1905 by Mrs. O. M. Hoback, who ı three-fourths of a mile east of the station, is a vertical staff, 10 feet long, driven 2 feet the sandy bed of the stream, the top being nailed to the bridge timbers. The gage is ıred to bench marks as follows: (1) A nail driven about 4 inches above the ground into the side of a telephone pole 25 feet south of the bridge; elevation, 10.96 feet. (2) A nail en into the north side of a 12-inch pile at the northeast corner of the bridge; elevation 8 feet. (3) A United States Geological Survey standard iron bench-mark post, set 21, 1904, about 50 feet southeast of the gage rod; elevation 12.33 feet. Elevations are ıe the zero of the gage.

his station has been discontinued.

description of this station, with gage-height and discharge data, is contained in Water-ply Paper No. 133, of the United States Geological Survey, pages 83–85.

Discharge measurements of Milk Creek near Axial, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
1905.		*Feet.*	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
2	H. G. Graham	25	77	2.23	5.80	172
20	do	30	128	1.90	6.80	242
13	do	22	39	1.75	4.85	68
22	do	15	8.7	.31	3.45	2.7
28	do	16	10	.37	3.50	3.7

Daily gage height, in feet, of Milk Creek near Axial, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Day.	Apr.	May.	June.	July.	Aug.
.....	3.6	5.5	6.45	3.45	3.7	17.....	3.8	6.1	4.35	3.4	.....
.....	3.55	5.8	6.4	3.5	3.6	18.....	3.8	6.5	4.25	3.4	.....
.....	3.55	5.5	6.3	3.5	3.6	19.....	4.0	6.9	4.1	3.5	.....
.....	3.5	5.3	6.35	3.5	3.6	20.....	4.0	6.8	4.1	3.6	.....
.....	3.5	4.85	6.2	3.5	3.6	21.....	3.9	7.1	4.0	3.5	.....
.....	3.5	4.9	5.8	3.45	3.6	22.....	3.8	6.95	3.85	3.45	.....
.....	3.55	4.8	5.6	3.5	3.5	23.....	3.85	7.1	3.8	3.5	.....
.....	3.6	4.95	5.5	3.45	3.5	24.....	3.9	7.15	3.7	3.45	.....
.....	3.65	5.7	5.4	3.45	3.5	25.....	4.0	6.85	3.65	3.4	.....
.....	3.75	5.8	5.15	3.5	3.5	26.....	4.1	6.8	3.5	3.4	.....
.....	3.75	5.4	4.7	3.6	3.6	27.....	4.2	6.8	3.5	3.4	.....
.....	3.8	5.35	4.9	3.4	3.6	28.....	4.8	6.55	3.5	3.5	.....
.....	3.9	5.25	4.8	3.5	3.5	29.....	4.95	6.3	3.5	3.45	.....
.....	3.8	5.3	4.6	3.5	3.5	30.....	5.15	6.2	3.5	3.5	.....
.....	3.8	5.3	4.4	3.5	3.5	31.....	.....	6.4	.....	3.4	.....
.....	3.8	5.65	4.4	3.4	3.5						

Station rating table for Milk Creek near Axial, Colo., from April 20, 1904, to May 17, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.20	2	4.10	48	5.00	111	5.80	175
3.30	4	4.20	55	5.10	119	5.90	183
3.40	8	4.30	62	5.20	127	6.00	191
3.50	12	4.40	69	5.30	135	6.10	200
3.60	17	4.50	76	5.40	143	6.20	209
3.70	23	4.60	83	5.50	151	6.30	218
3.80	29	4.70	90	5.60	159	6.40	227
3.90	35	4.80	97	5.70	167	6.50	236
4.00	41	4.90	104				

NOTE.—The above table is applicable only for open channel conditions. It is based on five discharge measurements made during 1904, and it is fairly well defined.

Station rating table for Milk Creek near Axial, Colo., from May 18 to August 16, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.40	2	4.40	41	5.40	111	6.40	201
3.50	4	4.50	46	5.50	119	6.50	211
3.60	7	4.60	52	5.60	128	6.60	221
3.70	10	4.70	58	5.70	137	6.70	231
3.80	13	4.80	65	5.80	146	6.80	241
3.90	17	4.90	72	5.90	155	6.90	251
4.00	21	5.00	79	6.00	164	7.00	261
4.10	26	5.10	87	6.10	173	7.10	271
4.20	31	5.20	95	6.20	182	7.20	281
4.30	36	5.30	103	6.30	191		

NOTE. The above table is applicable only for open-channel conditions. It is based on four discharge measurements made during 1905, and it is fairly well defined.

Estimated monthly discharge of Milk Creek near Axial, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet
	Maximum.	Minimum.	Mean.	
April	123	12	35.9	2,1
May	276	97	184	11,3
June	206	4	70.4	4,1
July	7	2	3.5	
August 1-16	10	4	5.7	
The period				18,0

MISCELLANEOUS MEASUREMENTS.

he following miscellaneous measurements were made in the Yampa River basin in 5:

Miscellaneous discharge measurements made in Yampa River drainage basin in 1905.

Date.	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
y 26.....	Little Snake....	Maybell, Colo.....	105	918	5.50	.....	5,050
ie 24.....	.....do.....	.....do.....	99	430	3.45	3.50	1,483

WHITE RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

White River rises in Trappers Lake, which lies at an elevation of 9,500 feet above sea level a small mountain basin of the White River Plateau in eastern Garfield County, Colo.; ence it flows westward to its point of junction with Green River in west-central Uinta unty, Utah. Throughout its course it occupies a narrow, mountainous valley, with alter- ting parks and canyons, entering the longest and deepest of the canyons, in which it con- nues to its mouth, about 8 miles east of the Colorado-Utah State line.

The basin comprises an arid, broken, and much eroded plateau region, which topographically a continuation of the Grand River Mesa south of Grand River. The headwater portion vers the greater area and is called the White River Plateau; below this and to the south is e Roan or Book Cliffs Plateau. Fragmentary plateaus also occur along the northern side the river.

Numerous small streams, among which are Marvine Creek and South Fork, join the White the upper, mountainous portion of the basin. Douglas, Piceance, and Evacuation Creeks, aining the Book Cliffs Plateau, enter White River from the south. In the spring these eks carry considerable water, derived mainly from melting snow, but in the summer they e very nearly dry.

The rocks of the basin are largely of sedimentary origin, and west of the Great Hog Back e relief features produced by erosion are characteristic and remarkably uniform. The ales and marls, wherever sufficiently compact, have been made into steep, inaccessible iffs, and sandstones have become vertical cliffs. The stream channels are deeply cut, and flood waters carry a large amount of silt. The soils derived from these rocks vary from dy to adobe texture, have practically no organic ingredients, and are very friable, and id and water are constantly breaking them up and transporting them lower down in the in each year.

Short grasses cover the tops of many of the ridges, while juniper and piñon overgrow their es. Greasewood and sage brush occur extensively over dry valleys and along plateau- ridges. In the moist valleys willows and cottonwoods grow in dense masses. In the ite River Forest Reserve, which extends over the greater portion of the headwaters, and eneral at elevations above 7,500 feet, quaking aspens and spruce predominate, while ng the plateaus piñon and cedars are more in evidence.

The mean annual precipitation recorded at Meeker is 15.9 inches; farther west and at er elevations it is undoubtedly much less.

Numerous ditches along the main stream and some of its tributaries divert water for irriga- n, which has been practiced in a desultory way for many years. Native hay and kindred ducts are the chief agricultural staples in the upper part of the area, while grains, grasses, lfa, and some fruits are grown in the lower valleys.

NORTH FORK OF WHITE RIVER NEAR BUFORD, COLO.

This station was established July 28, 1903. It is located at the county bridge at Rawson's ranch, below the mouth of Marvine Creek, 7 miles from Buford, the nearest post-office, and 32 miles from Meeker, Colo.

The channel is straight for 200 feet above and 300 feet below the station. Both banks are high and are not liable to overflow. The bed of the stream is rocky and is free from vegetation. There is but one channel at all stages, broken by the two narrow bridge piers. The current is swift.

Discharge measurements are made from the three-span highway bridge to which the gage is attached. The bridge has a total span of 85 feet. The initial point for soundings is the edge of the abutment at the south end of the bridge.

The gage, which is read twice each day by H. N. Rawson, is a timber spiked to the lower side of the first pier from the south end of the bridge. It reads from 1 foot to 9 feet. The gage is referred to bench marks as follows: (1) The top of a bolt on the bridge nearest the gage; elevation, 11.51 feet. (2) A spike in the trunk of a large cottonwood tree at the southeast corner of the bridge; elevation, 7.46 feet. (3) A spike in one of the abutment logs at the end of the upper sill at the southwest corner of the bridge; elevation, 7.88 feet. Elevations are above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 100, pp; 99-100, 133, pp 91-92.
Discharge: 100, p 100; 133, p 92.
Discharge, monthly: 100, p 101; 133, p 93.
Gage heights: 100, p 100; 133, p 92.
Rating table: 100, p 100; 133, p 93.

Discharge measurements of North Fork of White River near Buford, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 15	H. G. Graham	86	111	3.03	2.20	336
June 17	do	86	205	5.82	3.30	1,194
July 6	do	88	129	3.16	2.35	408
July 18	do	87	107	2.93	2.15	314
August 12	do	87	102	2.95	2.15	301
September 16	do	86	80	1.90	1.85	152

Daily gage height, in feet, of North Fork of White River near Buford, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	1.82	2.55	3.4	2.65	2.2	1.9	1.85
2	1.85	2.5	3.4	2.6	2.15	1.9	1.85
3	1.82	2.3	3.6	2.52	2.1	1.9	1.85
4	1.82	2.18	3.8	2.42	2.1	1.9	1.85
5	1.82	2.12	3.8	2.42	2.05	2.0	1.85
6	1.82	2.15	3.7	2.4	2.05	1.98	1.85
7	1.9	2.22	3.85	2.38	2.0	1.95	1.85
8	1.88	2.48	4.0	2.35	2.0	1.9	1.85
9	1.92	2.48	3.9	2.32	2.0	1.9	1.85
10	1.92	2.32	3.6	2.3	1.98	1.9	1.85
11	1.92	2.28	3.5	2.28	2.05	1.9	1.85
12	1.92	2.22	3.55	2.28	2.1	1.9	1.85
13	1.92	2.22	3.62	2.28	2.02	1.9	1.85

Daily gage height, in feet, of North Fork of White River near Buford, Colo., in 1905—Con.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
4	1.92	2.2	3.68	2.22	2.0	1.9	1.85
5	1.92	2.22	3.7	2.22	2.0	1.9	1.85
6	1.92	2.58	3.55	2.18	1.95	1.85	1.85
7	1.92	2.75	3.45	2.18	1.95	1.85	1.85
8	1.92	2.95	3.4	2.2	1.95	1.9	1.85
9	1.92	3.02	3.32	2.2	1.95	1.85	1.85
10	1.92	3.38	3.3	2.3	1.95	1.85	1.85
11	1.92	3.55	3.25	2.22	1.9	1.85	1.85
12	1.92	3.65	3.2	2.2	1.9	1.85	1.85
13	1.98	3.7	3.2	2.15	1.9	1.85	1.85
14	1.98	3.35	3.2	2.15	1.9	1.85	1.85
15	1.98	3.25	3.15	2.15	1.9	1.92	1.85
16	2.02	3.25	3.2	2.15	1.9	1.92	1.85
17	2.05	3.28	3.0	2.15	1.9	1.85	1.85
18	2.1	3.05	2.85	2.15	1.92	1.85	1.85
19	2.2	2.95	2.78	2.15	1.92	1.85	1.85
20	2.32	3.05	2.72	2.1	1.9	1.9	1.85
21	.....	3.25	.....	2.15	1.92	.....	1.85

Station rating table for North Fork of White River near Buford, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.80	135	2.40	450	3.00	910	3.60	1,505
1.90	180	2.50	515	3.10	1,000	3.70	1,610
2.00	225	2.60	585	3.20	1,095	3.80	1,720
2.10	275	2.70	660	3.30	1,195	3.90	1,835
2.20	330	2.80	740	3.40	1,295	4.00	1,950
2.30	390	2.90	825	3.50	1,400		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904-5. It is well defined between gage heights 1.8 feet and 2.4 feet.

Estimated monthly discharge of North Fork of White River near Buford, Colo., for 1905.

[Drainage area, 181 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	402	144	200	11,900	1.10	1.23
May	1,610	286	756	46,480	4.18	4.82
June	1,950	676	1,332	79,260	7.36	8.21
July	622	275	375	23,060	2.07	2.39
August	330	180	219	13,470	1.21	1.40
September	225	157	176	10,470	.972	1.08
October	157	157	157	9,654	.867	1.00
The period				194,300		

SOUTH FORK OF WHITE RIVER NEAR BUFORD, COLO.

This station was established July 25, 1903. It is located at the county bridge at the lower end of a section of the river known as "Stillwater," about 7 miles from Buford, the nearest post-office, and about 30 miles from Meeker, Colo., in T. 1 S., R. 91 W.

The channel is straight for 50 feet above the station and for 300 feet below. Both banks are high and are covered with grass and sagebrush. The bed of the stream below the "Stillwater" and at the station is covered with bowlders, some of which are 2 or 3 feet in diameter. There is but one channel at all stages, broken by the middle pier of the bridge, and the current is swift. During the winter months ice obstructs the channel to such an extent that gage readings are impracticable.

High-water measurements are made from the bridge, which makes an angle of 20° with the normal to the stream. This is taken into account in making the measurements. The initial point for soundings is the edge of the abutment at the west end of the bridge. At low water, measurements are made by wading.

The gage, which was read twice each day during 1905 by Claud Dobbs, is a 10-foot vertical timber spiked to the upper side of the middle pier. The gage is referred to bench marks as follows: (1) The first bolt on the bridge east of the gage; elevation, 11.95 feet. (2) A spike in one of the logs of the abutment at the southwest corner of the bridge; elevation, 8.57 feet. (3) The corner of a large rock 30 feet west of the bridge and north of the road; elevation, 13.14 feet. (4) The top of a pyramid-shaped rock on the east side of the river below the bridge 41 feet distant from the northeast bolt on the bridge tie and projecting 8 inches above the ground; elevation, 7.02 feet. Elevations are above the zero of the gage. The elevation of the station above sea level, as determined by aneroid barometer, is 7,400 feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 100, pp 97-98; 133, p 94.
Discharge: 100, p 98; 133, p 94.
Discharge, monthly: 100, p 99; 133, p 96.
Gage heights: 100, p 98; 133, p 95.
Rating table: 100, p 99; 133, p 96.

Discharge measurements of South Fork of White River near Buford, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 16	H. G. Graham	55	91	2.93	2.80	267
June 19	do	55	251	6.39	5.70	1,603
July 7	do	55	110	3.61	3.15	397
Juy 19	do	55	97	2.96	2.90	287
August 13	do	55	86	3.04	2.70	262
September 19	do	55	72	2.3	2.45	166

Daily gage height, in feet, of South Fork of White River near Buford, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct
1	2.4	2.95	4.88	3.5	2.72	2.45	2.45
2	2.4	3.05	5.18	3.45	2.7	2.45	2.45
3	2.4	2.95	5.48	3.4	2.7	2.45	2.45
4	2.35	2.82	6.22	3.32	2.7	2.5	2.45
5	2.38	2.8	6.9	3.25	2.68	2.58	2.45
6	2.4	2.75	6.52	3.2	2.65	2.55	2.45
7	2.4	2.76	6.55	3.15	2.62	2.55	2.45

aily gage height, in feet, of South Fork of White River near Buford, Colo., for 1905—Con.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	2.42	2.75	6.68	3.12	2.6	2.55	2.45
2	2.45	2.85	7.4	3.05	2.6	2.5	2.45
3	2.48	2.85	6.85	3.05	2.6	2.5	2.42
4	2.48	2.85	6.28	3.02	2.7	2.48	2.45
5	2.5	2.78	6.25	2.98	2.7	2.45	2.45
6	2.5	2.8	6.5	2.95	2.68	2.45	2.45
7	2.5	2.78	6.12	2.92	2.6	2.45	2.45
8	2.5	2.75	6.42	2.9	2.6	2.45	2.45
9	2.5	2.85	6.75	2.88	2.6	2.45	2.45
10	2.5	3.0	5.75	2.85	2.55	2.45	2.45
11	2.5	3.18	5.6	2.85	2.55	2.45	2.45
12	2.55	3.4	5.2	2.88	2.55	2.45	2.4
13	2.55	3.55	5.0	2.92	2.52	2.45	2.32
14	2.5	3.65	4.7	2.88	2.5	2.45	2.38
15	2.5	3.92	4.8	2.82	2.5	2.45	2.42
16	2.5	4.35	4.95	2.8	2.5	2.45	2.45
17	2.5	4.45	5.05	2.78	2.5	2.45	2.45
18	2.55	4.22	4.5	2.75	2.5	2.45	2.45
19	2.55	4.38	4.45	2.75	2.5	2.45	2.45
20	2.6	4.45	4.15	2.75	2.5	2.45	2.45
21	2.65	4.45	3.92	2.72	2.48	2.45	2.45
22	2.7	4.22	3.7	2.7	2.5	2.45	2.45
23	2.8	4.22	3.6	2.7	2.48	2.52	2.45
24	.....	4.55	.....	2.7	2.48	.....	2.45

tation rating table for South Fork of White River near Buford, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.30	115	3.50	510	4.70	1,050	5.90	1,725
2.40	145	3.60	550	4.80	1,100	6.00	1,790
2.50	175	3.70	590	4.90	1,150	6.20	1,920
2.60	205	3.80	630	5.00	1,200	6.40	2,060
2.70	235	3.90	675	5.10	1,255	6.60	2,200
2.80	265	4.00	720	5.20	1,310	6.80	2,350
2.90	300	4.10	765	5.30	1,365	7.00	2,500
3.00	335	4.20	810	5.40	1,420	7.20	2,660
3.10	370	4.30	855	5.50	1,480	7.40	2,820
3.20	405	4.40	900	5.60	1,540		
3.30	440	4.50	950	5.70	1,600		
3.40	470	4.60	1,000	5.80	1,660		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge easurements made during 1903–1905. It is well defined between gage heights 2.4 feet and 5.7 feet.

Estimated monthly discharge of South Fork of White River near Buford, Colo., for 1905.

[Drainage area, 148 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	265	130	175	10,410	1.18	1.32
May	975	250	497	30,560	3.36	3.87
June	2,820	550	1,569	93,360	10.60	11.83
July	510	235	324	19,920	2.19	2.52
August	241	169	200	12,300	1.35	1.56
September	199	160	167	9,937	1.13	1.26
October	160	121	157	9,654	1.06	1.22
The period				186,100		

WHITE RIVER AT MEEKER, COLO.

This station was established May 24, 1901. It is located about one-half mile above the town of Meeker, at a point where a wagon bridge crosses the stream, on the ranch of L. F. Van Cleave, in sec. 25, T. 1 N., R. 94 W.

The channel is straight for 500 feet above and below the station. Both banks are high and not liable to overflow. The bed of the stream is composed of gravel and cobble-stones and seems to be permanent. There is but one channel at all stages. The current is always swift and is extremely so at high water. Gage heights have an ordinary range of about 2.5 feet. During the winter months ice obstructs the channel to such an extent that gage readings are impracticable.

Discharge measurements are made from either the upstream or downstream side of the bridge, the initial point being at the left end.

The gage, which was read twice each day during 1905 by L. F. Van Cleave, consists of a vertical timber nailed to the left abutment of the bridge on the downstream side. The gage is referred to bench marks as follows: (1) The top of a bolt in the truss immediately above the gage rod; elevation, 10.83 feet above the zero of the gage. (2) A standard United States Geological Survey iron post, located 30 feet north of the north end of the bridge; elevation, 8.807 feet above the zero of the gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 66, pp 91–92; 85, p 50; 100, pp 95–96; 133, p 97.
Discharge: WS 50, p 375; 66, p 92; 85, p 51; 100, p 96; 133, p 97.
Discharge, low-water: Ann 22, iv, p 396.
Discharge, monthly: WS 85, p 52; 100, p 97; 133, p 99.
Gage heights: WS 28, p 143; 66, p 92; 85, p 51; 100, p 96; 133, p 98.
Rating tables: WS 85, p 51; 100, p 97; 133, p 98.

Discharge measurements of White River at Meeker, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
...	Stiles and Hinderlider	79	166	1.80	3.60	299
...	A. J. Stiles	79	166	2.40	3.60	398
...	H. G. Graham	79	233	3.77	4.20	879
...	do	79	271	3.89	4.72	1,052
...	do	79	316	5.04	5.20	1,593
...	do	79	332	5.42	5.40	1,801
...	do	79	403	8.77	6.40	3,536
...	do	78	332	6.40	5.60	2,126
...	do	78	281	4.06	4.90	1,141
...	do	78	207	2.99	4.00	620
...	do	78	203	2.48	3.95	505
...	do	78	184	2.28	3.72	419
...	do	78	191	2.25	3.80	429

Daily gage height, in feet, of White River at Meeker, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	3.6	4.65	5.95	4.72	3.9	3.6	3.7
.....	3.62	4.85	5.98	4.65	3.85	3.6	3.7
.....	3.6	4.58	6.0	4.6	3.85	3.6	3.65
.....	3.6	4.4	6.15	4.48	3.75	3.62	3.65
.....	3.6	4.3	6.32	4.38	3.7	3.75	3.65
.....	3.6	4.25	6.25	4.35	3.7	3.75	3.6
.....	3.65	4.2	6.18	4.3	3.68	3.78	3.6
.....	3.7	4.35	6.18	4.25	3.65	3.7	3.6
.....	3.72	4.75	6.3	4.2	3.65	3.65	3.6
.....	3.75	4.55	6.25	4.12	3.65	3.65	3.6
.....	3.78	4.48	6.05	4.1	3.9	3.62	3.6
.....	3.78	4.4	6.0	4.02	3.98	3.6	3.6
.....	3.8	4.42	6.05	4.0	3.88	3.6	3.6
.....	3.8	4.38	5.95	3.98	3.82	3.6	3.6
.....	3.72	4.35	6.0	3.95	3.75	3.55	3.6
.....	3.72	4.58	6.1	3.9	3.75	3.55	3.6
.....	3.72	4.95	5.9	3.88	3.7	3.55	3.62
.....	3.72	5.15	5.8	3.85	3.65	3.65	3.65
.....	3.85	5.4	5.65	3.85	3.65	3.65	3.6
.....	3.85	5.55	5.52	4.0	3.65	3.65	3.55
.....	3.82	5.58	5.48	3.98	3.65	3.6	3.62
.....	3.8	5.82	5.52	3.9	3.65	3.58	3.62
.....	3.8	5.98	5.52	3.85	3.58	3.55	3.7
.....	3.82	6.02	5.52	3.82	3.55	3.58	3.65
.....	3.88	5.85	5.45	3.8	3.6	3.68	3.62
.....	3.88	5.82	5.35	3.8	3.58	3.68	3.62
.....	4.02	5.9	5.25	3.78	3.55	3.6	3.62
.....	4.12	5.85	5.1	3.72	3.62	3.6	3.62
.....	4.18	5.65	4.95	3.75	3.65	3.68	3.62
.....	4.32	5.62	4.8	3.75	3.62	3.8	3.6
.....	.....	5.68	.....	3.82	3.6	.....	3.6

Station rating table for White River at Meeker, Colo., from April 1 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.50	345	4.30	700	5.10	1,420	5.90	2,580
3.60	370	4.40	760	5.20	1,540	6.00	2,760
3.70	400	4.50	835	5.30	1,670	6.10	2,950
3.80	435	4.60	910	5.40	1,800	6.20	3,140
3.90	480	4.70	1,000	5.50	1,940	6.30	3,330
4.00	530	4.80	1,090	5.60	2,080	6.40	3,530
4.10	580	4.90	1,190	5.70	2,240		
4.20	640	5.00	1,300	5.80	2,410		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5, and is fairly well defined.

Estimated monthly discharge of White River at Meeker, Colo., for 1905.

[Drainage area, 634 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	712	370	443	26,360	0.699	0.78
May	2,798	640	1,490	91,620	2.35	2.71
June	3,370	1,090	2,444	145,400	3.85	4.30
July	1,018	407	572	35,170	.902	1.04
August	520	357	405	24,900	.639	.737
September	435	357	382	22,730	.603	.673
October	400	357	376	23,120	.593	.684
The period				369,300		

WHITE RIVER NEAR RANGELY, COLO.

This station was established April 14, 1904. It is located at the wagon bridge 1 mile west of Rangely, Colo., in sec. 3, T. 2 N., R. 102 W.

The channel is curved at the station and the bridge makes an angle of 15° with the radius of the curve. The right bank is high and clean and does not overflow; the left bank is low and clean, and overflows at high stages. The bed of the stream is composed of sand and gravel and is shifting. There is but one channel at all stages. There is an island about 200 feet above the bridge which breaks the current and causes it to run diagonally across the channel in various directions. The current is swift at all times and at high stages surges rapidly. Conditions at this station are unfavorable for accurate measurements, but there is no other available point on this section of the stream.

Discharge measurements are made from the downstream side of the single-span bridge, to which the gage is attached. The initial point for soundings is the vertical wall of the right abutment.

The gage, which was read twice each day during 1905 by Miss Zinnis Coltharp, is a 12-foot timber fastened to the downstream side of the right abutment of the bridge. The bench mark is a United States Geological Survey standard aluminum tablet, set on the top stone of the right abutment on the downstream side of the bridge; elevation, 16.86 feet above the zero of the gage.

This station was abandoned December 31, 1905.

A description of this station, with gage-height and discharge data, is g
Supply Paper No. 133 of the United States Geological Survey, pa

Discharge measurements of White River near Rangely, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
....	A. J. Stiles.	79	208	2.53	3.70	526
.....	H. G. Graham	90	515	6.48	5.90	3,336
.....	.....do	90	521	6.63	6.00	3,457
.....	.....do	78	239	2.51	3.95	600
.....	.....do	77	238	2.46	3.90	587
5...	.....do	77	260	3.07	4.20	798

Daily gage height, in feet, of White River near Rangely, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	3.78	4.25	5.62	4.8	3.94	3.75	4.88
.....	3.68	4.5	5.85	4.8	3.92	3.78	4.82
.....	3.79	4.5	5.98	4.78	3.9	3.8	4.38
.....	3.81	4.3	6.0	4.75	3.9	3.82	4.18
.....	3.72	4.2	6.0	4.75	3.9	4.15	4.05
.....	3.66	4.1	6.22	4.58	3.88	4.18	3.92
.....	3.69	4.0	6.38	4.45	3.9	4.14	3.78
.....	3.78	4.0	6.22	4.18	3.9	4.1	3.7
.....	3.82	4.1	6.3	4.14	3.88	4.1	3.72
.....	3.9	4.42	6.32	4.14	3.86	3.98	3.78
.....	3.9	4.35	6.45	4.1	3.89	3.99	3.85
.....	3.88	4.26	6.55	3.96	3.9	3.96	3.89
.....	3.88	4.22	6.38	3.89	3.9	3.95	3.9
.....	3.88	4.2	6.12	3.84	3.88	3.8	3.89
.....	3.81	4.22	6.15	3.82	3.9	3.8	3.89
.....	3.81	4.24	6.0	3.79	3.89	3.85	3.9
.....	3.74	4.28	6.11	3.82	3.88	3.8	3.9
.....	3.75	4.5	6.15	3.84	3.89	3.85	3.88
.....	3.76	4.78	5.85	3.82	3.9	3.85	3.88
.....	3.78	4.6	5.5	3.84	3.89	3.9	3.9
.....	3.82	5.15	5.36	3.82	3.86	3.85	3.9
.....	3.81	5.84	5.29	3.86	3.85	3.82	3.9
.....	3.81	5.92	5.22	3.89	3.80	3.92	3.9
.....	3.8	6.0	5.32	3.9	3.92	3.88	3.88
.....	3.81	6.16	5.26	3.81	3.91	3.85	3.88
.....	3.83	6.28	5.19	3.85	3.92	3.9	3.9
.....	3.85	5.95	5.08	3.88	3.95	3.92	3.91
.....	3.88	5.92	4.99	3.89	3.95	4.75	3.92
.....	3.92	5.98	4.95	3.80	3.88	4.92	3.9
.....	4.0	5.92	4.92	3.9	3.85	4.98	3.9
.....	.....	5.5	.....	3.9	3.81	.....	3.9

Station rating table for White River near Rangely, Colo., from April 1 to October 31,

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.60	380	4.40	1,010	5.20	2,020	6.00	3,490
3.70	435	4.50	1,110	5.30	2,180	6.10	3,710
3.80	495	4.60	1,220	5.40	2,350	6.20	3,930
3.90	565	4.70	1,330	5.50	2,520	6.30	4,160
4.00	645	4.80	1,450	5.60	2,700	6.40	4,390
4.10	730	4.90	1,580	5.70	2,890	6.50	4,630
4.20	820	5.00	1,720	5.80	3,080	6.60	4,870
4.30	910	5.10	1,870	5.90	3,280		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1905 and is not well defined.

Estimated monthly discharge of White River near Rangely, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	645	413	506	30,110
May	4,114	645	1,752	107,700
June	4,750	1,608	3,152	187,600
July	1,450	489	748	45,980
August	605	502	561	34,500
September	1,692	381	674	40,110
October	1,554	435	636	39,110
The period				485,100

MARVINE CREEK NEAR BUFORD, COLO.

Marvine Creek rises in Marvine Lake, in the southeastern part of Rio Blanco County, Colo., and flows northwestward to its point of junction with White River.

The gaging station was established July 27, 1903. It is located at a point where the stream is crossed by a large aspen log. The station is 10 miles from Buford, the nearest post-office, and is about 35 miles from Meeker.

The channel is 30 feet wide and is straight for 100 feet above and below the station. The right bank is sloping and will overflow for 10 or 15 feet at high water. The left bank is steep and is not liable to overflow. Both banks are covered with thick brush. The bed of the stream is covered with bowlders and is free from vegetation. The channel is divided into two parts by a large sunken log, which supports the middle of the footbridge. The current is swift.

Discharge measurements are made from the log which spans the stream at the gage. The initial point for soundings is at the gage rod.

The gage, which is read twice daily by James Fitzgerald, is a vertical 5-foot timber, fastened to the lower side of the foot log, which is used as a bridge. It is referred to bench marks as follows: (1) The top of a rock 22 feet west of the gage rod; elevation, 4.62 feet. (2) The top of a triangular-shaped rock between two spruce trees on the west bank; elevation, 6.01 feet. (3) The top of a large rock 30 feet northwest of the gage; elevation, 4.61 feet. Elevations are above the zero of the gage.

ation in regard to this station is contained in the following Water-Supply Papers of d States Geological Survey:

ion: 100, p 101; 133, p 103.
e: 100, p 102; 133, p 103.
e, monthly: 100, p 102; 133, p 105.
ghts: 100, p 102; 133, p 104.
able: 100, p 102; 133, p 104.

Discharge measurements of Marvine Creek near Buford, Colo., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
H. G. Graham	29	35	2.54	1.80	90
do	40	95	7.61	3.50	723
do	29	41	3.66	2.10	150
do	29	41	3.56	2.10	146
do	29	38	3.79	2.00	144
18 do	29	37	3.14	1.95	116

Daily gage height, in feet, of Marvine Creek near Buford, Colo., for 1905.

Day	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
		1.85	2.28	2.32	2.08	1.88	1.95
		1.85	2.28	2.28	2.02	1.88	1.95
		1.85	2.3	2.25	2.02	1.88	1.92
		1.85	2.45	2.22	2.0	1.88	1.92
		1.85	2.52	2.2	2.0	1.95	1.9
		1.85	2.45	2.2	2.0	1.95	1.9
		1.85	2.5	2.15	1.98	1.95	1.9
		1.85	2.68	2.15	1.98	1.92	1.9
		1.85	2.78	2.15	1.98	1.92	1.9
	1.7	1.85	2.7	2.15	2.0	1.92	1.9
	1.7	1.85	2.6	2.1	2.05	1.92	1.9
	1.7	1.85	2.6	2.08	2.0	1.9	1.9
	1.7	1.85	2.7	2.08	1.98	1.9	1.9
	1.7	1.85	2.7	2.08	1.95	1.9	1.95
	1.7	1.85	2.8	2.08	1.98	1.9	1.9
	1.7	1.9	2.7	2.05	1.98	1.9	1.9
	1.7	1.92	2.65	2.05	1.98	1.9	1.9
	1.7	1.98	2.6	2.1	1.98	1.9	1.9
	1.7	2.02	2.55	2.12	1.98	1.9	1.9
	1.7	2.08	2.52	2.15	1.95	1.9	1.9
	1.7	2.12	2.5	2.1	1.92	1.9	1.9
	1.7	2.12	2.55	2.05	1.92	1.9	.....
	1.75	2.2	2.65	2.05	1.92	1.9	.....
	1.75	2.15	2.55	2.05	1.92	1.92	.....
	1.75	2.15	2.45	2.02	1.92	1.92	.....
	1.75	2.15	2.45	2.02	1.95	1.95	.....
	1.75	2.18	2.45	2.02	1.95	1.95	.....
	1.75	2.22	2.38	2.0	1.92	1.95	.....
	1.85	2.15	2.38	2.0	1.92	1.98	.....
	1.85	2.15	2.35	2.0	1.92	1.95	.....
	.....	2.2	.....	2.08	1.92	.....	.....

Station rating table for Marvine Creek near Buford, Colo., from April 10 to October 21, 19

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.70	74	2.00	126	2.30	205	2.60	304
1.80	89	2.10	150	2.40	235	2.70	339
1.90	106	2.20	177	2.50	269	2.80	377

NOTE.—The above table is applicable only for open-channel conditions. It is based on disch measurements made during 1904-5. It is well defined between gage heights 1.8 feet and 2.1 feet.

Estimated monthly discharge of Marvine Creek near Buford, Colo., for 1905.

[Drainage area, 50 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dep inc
April 10-30	98	74	78.6	3,274	1.57	
May	183	98	127	7,809	2.54	
June	377	199	272	16,180	5.44	
July	211	126	153	9,408	3.06	
August	145	110	120	7,379	2.40	
September	122	103	109	6,483	2.18	
October 1-21	116	106	108	4,498	2.16	
The period				55,030		

DUCHESNE RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Duchesne River rises in the high peaks of the Uinta and Wasatch mountains, flow general southeasterly direction, and enters Green River 3 miles above the mouth c White. It is a very crooked stream, swinging back and forth across its valley, its c marked by a thick line of cottonwoods.

The principal tributaries of the Duchesne are Strawberry, East, and Lake creek Uinta River. From the mouth of Strawberry Creek down to Lake Creek the valley Duchesne averages 2 miles in width and is bordered on both sides by sandstone approximately 200 feet high. The cliffs on the northern side of the river are capped heavy deposit of coarse river gravel and cobblestones.

Strawberry Creek, the main upper tributary of the Duchesne, drains an area of 1,166 s miles. The stream rises in the Uinta Mountains and the run-off is derived chiefly melting snow except during the late summer, when the flow comes from small spring distributed over the entire drainage basin. Numerous tributaries enter the stream ticularly from the north and west, Indian, Bryants Fork, Mud, Horse, Sugar Spring Co-op creeks being the principal ones. They are all short and fall rapidly until they the valley, through which they flow sluggishly in well-defined channels. The main s traverses the valley from north to south and is very sluggish. Very little sediment is c by the stream at any stage. The average elevation of Strawberry Valley is 7,500 which is rather high for agricultural purposes but is splendidly adapted to gr Indian Creek, on which a gaging station was maintained during 1905, drains a small a of the southern slopes of the Uinta Mountains. Its basin comprises smoo fairly well timbered with pine and aspen. The normal flow is derived ch

The greater part of the precipitation is in the form of snow, which covers the ground for six to eight months each year.

Uinta River and its principal tributary, Whiterocks River, have their sources in a series of lakes in the Uinta Mountains, fed by the snow that exists the year round in the canyons and on the high slopes. The upper drainage area of these streams is very mountainous and difficult of access. After leaving their canyons, 7 or 8 miles above the Indian agency at Whiterocks, the rivers flow southeastward, uniting in various channels between the agency and Fort Duchesne, from which point they flow in one channel, entering Duchesne River 8 miles below, near the Ouray Indian school. Pole, Farm, and Dry Gulch creeks are small tributaries of the Uinta.

STRAWBERRY CREEK IN STRAWBERRY VALLEY, UTAH.

This station was established May 2, 1903. It is located in the canyon about one-fourth mile above the junction of Strawberry and Indian creeks, and is somewhat inaccessible, the nearest settlement being Heber, 40 miles away. The chief object of the station is the determination of the amount of water available for storage in Strawberry Valley.

The channel is straight for about 600 feet above and 400 feet below the station. The banks are wooded and are sufficiently high to prevent overflow. The bed of the stream is composed of gravel and during the summer months is overgrown with moss and weeds. The current is sluggish. The stream is frozen during the winter months.

Discharge measurements are made by means of a cable and car of regular form. The initial point for soundings is the first metal tag on the tagged wire at the left bank.

Gage readings and discharge measurements during 1905 were made by T. C. Callister. The original gage was of the vertical type and was used until September, 1904, when a new, inclined gage was established at the same locality, about 1,000 feet above the cable. The datum of the new gage is the same as that of the old. The bench mark is a large sandstone bowlder S. 82° E. 175 feet from the gage, 12 feet from the bank of the river, and projecting about 3 feet above the ground. It is marked "Rec. Ser. B. M. No. 7;" elevation, 19.15 feet above the zero of the gage, and 7,496 feet above sea level. July 2, 1905, a low-water station was established at a riffle about 200 feet below the regular gage, where the velocity is sufficiently high to prevent the growth of vegetation, which interferes seriously with the results at the regular station during the summer months. The gage at this point is a vertical staff driven into the stream bed and is referred to bench mark No. 7, above described, its zero having an elevation of 19.93 feet. The annual discharge at this station is therefore represented by two discharge curves.

Beginning April 15, 1905, evaporation and precipitation observations were made at a point near the station. The evaporation records are obtained by means of a 4 by 4 by 4 foot metallic tank set in the ground with its top about 3 inches from the surface. The equipment used in obtaining the precipitation records is of the standard form used by the United States Weather Bureau stations and was furnished by Doctor Hyatt, director of the Utah division of the United States Weather Bureau. The results of the expermients are shown in the following tables:

Evaporation in Strawberry Valley, Utah.

	Inches.
April	1.43
May	2.37
June	5.68
July	6.03
August	4.71
September	3.20
October	1.31

Precipitation in Strawberry Valley, Utah.

	Inches
April	1.6
May	1.8
June	.8
July	1.6
August	1.2
September	1.8
October	.2
November	Missing
December	2.0

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 100, p 112; 133, p. 121.
Discharge: Ann 21, iv, p 322; 22, iv, p 384; WS 50, p 374; 100, p 112, 133, pp 121, 363.
Discharge, monthly: WS 100, p 113; 133, p 122.
Gage heights: WS 100, p 113.
Rating table: WS 100, p 113.

Discharge measurements of Strawberry Creek in Strawberry Valley, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
January 8[a]	C. Tanner	28	20	1.01	.....	2
April 17	T. C. Callister	64	75	1.63	1.43	12
April 21	do	64	81	1.72	1.64	14
April 26	do	66	179	2.61	3.15	47
May 1	do	64	125	2.1	2.28	26
May 4	do	64	96	1.83	1.86	17
May 18	do	64	112	2.01	2.12	22
May 23	T. Thomas	68	156	2.36	2.78	36
June 17	T. C. Callister	63	63	1.39	1.30	8
June 25	do	62	53	1.08	.98	5
July 2[b]	do	37	36	1.23	1.50	4
July 12[b]	do	37	32	1.11	1.40	3
July 28[b]	do	37	29	.92	1.31	2
December 8[a]	A. B. Larson	34	41	.83	1.67	3
December 9[a]	do	34	45	.83	1.75	3
December 11[a]	do	34	50	.76	1.85	3
December 13[a]	do	32	46	.80	1.95	3
December 18[a]	do	26	46	.73	2.22	3

[a] Creek frozen.
[b] Measurement made at riffle 200 feet below gage. Gage heights refer to temporary gage at riffle.

Daily gage height, in feet, of Strawberry Creek in Strawberry Valley, Utah, for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	2.23	2.35	0.81	1.32	1.27	1.42	.....	1
2	.....	2.11	2.34	1.5	1.32	1.3	1.38	1.37	1
3	.....	2.06	2.28	1.5	1.32	.....	1.38	.....	1
4	.....	1.89	2.24	1.48	1.33	1.3	1.38	1.35	
5	.....	1.74	2.11	1.47	1.32	1.33	1.38	.....	
6	.....	1.66	2.0	1.45	1.3	.....	1.38	1.35	
7	.....	1.64	1.96	1.44	1.29	1.35	1.35	.....	
8	.....	1.68	1.94	1.43	1.27	1.36	.....	1.38	
9	.....	1.76	1.89	1.42	1.27	1.37	1.34	.....	
10	.....	1.76	1.76	1.41	.....	.....	1.33	1.38	

Daily gage height, in feet, of Strawberry Creek in Strawberry Valley, Utah, for 1905—Con.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	1.67	1.65	1.41	1.33	.....	1.35	.....	1.85
.....	.....	1.74	1.56	1.4	1.32	1.31	.....	.....	1.91
.....	1.05	1.72	1.48	1.39	1.3	1.31	1.36	1.41	1.95
.....	1.23	1.64	1.4	1.39	1.3	.....	1.35	.....	1.99
.....	1.3	1.6	1.3	1.48	1.28	.....	.....	.....	2.09
.....	1.34	1.7	1.28	1.41	1.27	1.3	1.33	.....	2.12
.....	1.42	1.94	1.24	1.38	.....	1.3	1.32	.....	2.15
.....	1.42	2.08	1.25	1.36	.....	1.33	.....	.....	2.22
.....	1.53	2.2	1.17	1.35	1.25	1.3	1.47	.....	2.23
.....	1.47	2.35	1.13	1.37	1.25	1.31	1.45	.....	2.24
.....	1.72	2.49	1.09	1.36	1.25	.....	.....	.....	2.27
.....	1.84	2.61	1.06	1.38	1.25	1.32	1.43	.....	.....
.....	1.88	2.74	1.02	1.37	1.25	1.31	.....	1.43	.....
.....	2.24	2.59	1.0	1.35	.....	.....	.....	.....	.....
.....	2.88	2.53	.98	1.35	.....	1.45	1.32	1.42	.....
.....	2.9	2.6	.95	1.33	.....	1.4	1.32	1.41	.....
.....	2.47	2.48	.93	1.3	.....	1.35	1.32	1.48	.....
.....	2.38	2.46	.9	1.31	1.3	.....	.....	1.5	.....
.....	2.14	2.3	.9	1.31	1.3	1.51	1.35	1.52	.....
.....	2.26	2.2	.89	1.31	1.31	1.49	.....	1.58	.....
.....	.....	2.26	.....	1.31	1.29	.....	1.38	.....	.....

NOTE.—Gage heights after July 2 refer to new gage at riffle, as the old gage heights were unreliable after at date on account of growing moss.
November 23–26 there was ice along the edges but the flow was unobstructed. November 27–28 back ater caused by ice. November 29 to December 31 the creek was frozen completely over. Gage heights e to water surface.

Station rating table for Strawberry Creek in Strawberry Valley, Utah, from April 13 to July 1, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.80	41	1.40	110	2.00	205	2.60	329
.90	51	1.50	124	2.10	224	2.70	352
1.00	62	1.60	139	2.20	243	2.80	376
1.10	73	1.70	154	2.30	263	2.90	400
1.20	85	1.80	170	2.40	284	3.00	425
1.30	97	1.90	187	2.50	306		

NOTE.—The above table is based on nine discharge measurements made during April to June, 1905. t is well defined between gage heights 0.9 foot and 3 feet.

Station rating table for Strawberry Creek in Strawberry Valley, Utah, from July 2 to November 25, 1905.

Gage. height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.25	23	1.35	31	1.45	39	1.50	44
1.30	27	1.40	35				

NOTE.—The above table is based on three discharge measurements made during July, 1905. It is well defined.

Estimated monthly discharge of Strawberry Creek in Strawberry Valley, Utah, for 190

Month	Discharge in second-feet.			Tota acre-
	Maximum.	Minimum.	Mean.	
April 13–30	400	68	192	
May	362	139	225	1
June	274	50	129	
July	44	27	34.6	
August	29	23	26.1	
September	45	25	30.7	
October	42	29	32.5	
November	38	31	35.0	
December[a]	35	35	35.0	
The period				

[a] Daily discharge estimated at 35 second-feet, based on five discharge measurements.
NOTE.—Daily discharge interpolated for missing gage heights.

INDIAN CREEK IN STRAWBERRY VALLEY, UTAH.

This station was established April 5, 1905. It is located in the canyon about 25 above the junction of the creek with Strawberry Creek. It is about 1 mile below the where Indian Creek leaves Indian Creek Valley and enters the canyon, and is 40 from Heber, the nearest post-office. The records will show the amount of water tha be diverted from Indian Creek into the Strawberry Valley storage reservoir.

The channel is straight for about 25 feet above and below the station. The right is vertical for about 1½ feet above the bed and then slopes gradually upward; the left slopes irregularly from the bed. Both banks are sufficiently high to prevent ove The bed of the stream is smooth and rocky and is not liable to shift. A slight grow moss occurs in the summer, but does not interfere with the rating curve to any great e The velocity is medium and the discharge ranges from 20 to 100 second-feet. De information in regard to winter conditions is lacking.

Discharge measurements are made from two poles laid across the stream. The i point for soundings is at the right bank.

The gage, which was read during 1905 by the men at the Reclamation Service ca Strawberry Valley, under the direction of T. C. Callister, is a large stake driven int bed about 180 feet above the measuring section. It is referred to a bench mark consi of a cross on a large sandstone bowlder 50 feet south of the river; elevation, 16.28 feet a the zero of the gage and 7,480 feet above mean sea level.

Discharge measurements of Indian Creek in Strawberry Valley, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D ch
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Se*
April 15	T. C. Callister	16	16	0.87	1.00	
April 18	do	17	14	.91	1.00	
April 25	J. Thomas	18	18	1.56	1.20	
April 26	T. C. Callister	18	20	1.95	1.38	
May 15	do	16	14	1.39	1.10	
June 17	do	16	13	1.72	1.10	
October 14	do	16	8.3	1.10	.92	
December 9[a]	A. B. Larson	14	16	.63	1.46	
December 10[a]	do	14	12	.78	1.25	
December 11[a]	do	12	18	.72		
December 13[a]	do	14	25	.52		
December 19[a]	do	13	23	.47		

[a] Ice measurement.

easurements of Indian Creek at point of diversion in Strawberry Valley, Utah, in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
T. C. Callister	16	6.8	1.12	0.71	7.6
Callister and Thomas	18	11	1.34	.92	15
T. C. Callister	18	16	1.62	1.11	25
do	18	16	1.62	1.11	25
do	18	19	1.77	1.3	33
do	19	21	1.78	1.41	37

y gage height, in feet, of Indian Creek in Strawberry Valley, Utah, for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
		1.1	1.2	1.02	1.0	0.95			1.2
		1.13	1.2	1.02	1.0	.95	0.96		1.2
		1.12	1.21	1.02	1.0		.95		1.16
		1.1	1.2	1.02	1.0	.95	.93	0.92	1.11
		1.08	1.2	1.02	1.0	1.0	.93		1.1
		1.06	1.19	1.02	.98		.93	.92	1.1
		1.06	1.18	1.02	.98	1.0	.93		1.3
		1.1	1.17	1.02	.97	.98		.91	1.44
		1.11	1.16	1.01	.98	.96	.93		1.46
		1.11	1.13	1.01			.92	.92	1.25
		1.1	1.11	1.0	1.0		.93		1.67
		1.1	1.12	1.0	.99	.95			1.75
		1.11	1.12	1.0	1.0	.94	.92	.86	1.81
	1.0	1.09	1.11	1.0	.99		.92		1.9
	1.0	1.1	1.11	1.01	.98				1.94
	1.01	1.12	1.11	1.0	.97	.94	.92		2.0
	1.02	1.19	1.1	1.0			.92		2.01
	1.0	1.22	1.11	1.0		.95			2.03
	1.02	1.3	1.1	.99	.96	.94	.95		2.08
	1.04	1.31	1.08	1.0	.96	.93	.93		2.09
	1.14	1.34	1.08	1.0	.96				2.16
	1.15	1.37	1.06	1.0	.97	.95	.92		
	1.15	1.39	1.05	1.0	.95	.93		.88	
	1.36	1.35	1.05	1.0					
	1.56	1.32	1.05	1.0		.98	.92	.87	
	1.25	1.31	1.04	1.0		.95	.92	.88	
	1.14	1.3	1.04	.98		.94	.92	1.0	
	1.15	1.29	1.03	1.0	.97			1.2	
	1.07	1.28	1.04	1.0	.97	1.01	.94	1.58	
	1.07	1.24	1.03	1.0	.98	.99		1.4	
		1.24		1.0	.97		.96		

eek frozen November 27 to December 31.

Station rating table for Indian Creek in Strawberry Valley, Utah, from April 14 to November 26, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.90	8.2	1.10	20	1.30	35	1.50	51
1.00	13.2	1.20	27	1.40	43	1.60	59

NOTE.—The above table is applicable only for open-channel conditions. It is based on seven discharge measurements made during 1905. It is well defined between gage heights 0.9 foot and 1.4 feet.

Estimated monthly discharge of Indian Creek in Strawberry Valley, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet
	Maximum.	Minimum.	Mean.	
April 14–31	56	13	22.3	732
May	42	17	27.1	1,666
June	28	15	20.9	1,244
July	15	12	13.6	836
August	13	11	12.1	744
September	14	10	11.1	660
October	11	9	9.8	603
November	11	6.5	8.4	500
December [a]	11	11	11.0	676
The period				7,661

[a] Daily discharge estimated at 11 second-feet, based on five measurements.
NOTE.—Daily discharge interpolated for missing gage heights.

Table of evaporation at Fort Duchesne, Utah, for 1904.

Month.	Total evaporation in inches.
August 26–27	0.35
September	3.18
October	1.84
November 1–16	.43
Total for period	5.80
Average daily evaporation	0.0734

MISCELLANEOUS MEASUREMENTS.

The following miscellaneous measurements were made in the Duchesne River basin in 1904:

Miscellaneous discharge measurements made in Duchesne River drainage basin 1904.

Date.	Stream.	Locality.	Gage height.	Discharge.
			Feet.	*Sec.-ft.*
April 21	Duchesne	Myton, Utah	6.20	901
April 22	do	do	6.08	766
May 19	do	do	8.13	3,289

PRICE RIVER DRAINAGE BASIN.

PRICE RIVER NEAR HELPER, UTAH.

Price River rises in the Wasatch Mountains, in the southeastern part of Utah County, ows in a general southeasterly direction, and unites with Green River at a point about 14 iles above Greenriver, Utah. The main source of supply is the snow in the upper reaches f the basin, where elevations range from 8,000 to 9,000 feet. The region is extremely ough and rugged. The principal rock is a loose and badly disintegrated sandstone. There but little soil and practically no vegetation except for small groves of scrubby cedar and few scattered pines. The original scanty underbrush and grass have been almost entirely amped out by sheep and cattle. The river is subject to floods in the spring and early mmer, during which time it carries immense quantities of sediment. Gordon and Pleasnt creeks are the main tributaries. They are both short, steep streams and enter the river om the west almost at right angles.

The gaging station was established February 21, 1904. It is located on the upper side f the ford near the settlement of Spring Glen, about 3 miles south of Helper, Utah, and 50 feet west of the main line of the Denver and Rio Grande Railroad.

The channel is straight for about 125 feet above and 400 feet below the station, and the anks are sufficiently high to prevent any overflow. The bed of the stream is composed of ne gravel and sand and shifts slightly, especially during high water. Information in gard to winter conditions is incomplete.

Low-water measurements are made by wading. The initial point for soundings is a 2 by 4 ch post driven in the left bank S. 8° W., 2½ feet from the gage. The course of the section s N. 44° W. A 2 by 4 inch post marks the position of the gaging station on the right ank. Measurements during high water are impossible, as there is no provision for crossing xcept by wading.

The gage, which was read daily during 1905 by John Tryon, is a staff driven into the tream bed and supported at the top by a timber buried in the bank. The gage is referred o bench marks as follows: (1) A Standard United States Geological Survey cap cemented n a sandstone bowlder embedded in the bank at a point S. 65° E. 23 feet from the gage; levation, 12.55 feet above the zero of the gage, and so marked. (2) A cross chiseled on a arge bowlder embedded in the bank S. 6° E. 19.2 feet from the gage, marked "B. M.;" levation, 11.19 feet above the zero of the gage.

A description of this station, with gage height and discharge data, is contained in Water-upply Paper No. 133 of the United States Geological Survey, pages 128–130.

Discharge measurements of Price River near Helper, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
anuary 21.....	C. Tanner	38	25	0.87	3.35	22
February 17....	W. G. Swendsen.....	48	37	1.02	3.40	38
March 17.....	.....do.....	52	50	1.36	3.65	68
April 25.....	.....do.....	55	63	1.88	3.95	119
May 13.....	.....do.....	53	78	1.96	4.00	154
June 2.....	.....do.....	79	153	3.76	4.92	575
August 24.....	A. B. Larson.....	47	24	.48	3.22	11.5

Daily gage height, in feet, of Price River near Helper, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr	May.	June.	July.	Aug.	Sept.	Oct.	Nov	De
1	3.3	3.35	3.45	3.55	4.5	4.9	3.5	3.4	3.2	3.5	3.3	
2	3.3	3.35	3.45	3.6	4.5	4.9	3.4	3.4	3.2	3.5	3.3	
3	3.35	3.35	3.45	3.65	4.5	4.9	3.4	3.5	3.2	3.4	3.4	
4	3.3	3.35	3.45	3.65	4.3	4.9	3.4	3.4	3.2	3.4	3.4	
5	3.3	3.35	3.45	3.65	4.2	4.9	3.4	3.4	3.3	3.4	3.3	
6	3.3	3.35	3.45	3.45	4.2	4.8	3.4	3.4	3.4	3.4	3.3	
7	3.3	3.4	3.45	3.15	4.1	4.6	3.4	3.4	3.4	3.4	3.3	
8	3.3	3.4	3.5	3.15	4.2	4.6	3.4	3.3	3.4	3.4	3.3	
9	3.3	3.4	3.45	3.15	4.2	4.5	3.4	3.3	3.4	3.4	3.3	
10	3.3	3.4	3.45	3.15	4.1	4.5	3.4	3.3	3.4	3.4	3.3	
11	3.3	3.4	3.5	3.25	4.0	4.4	3.4	3.4	3.4	3.3	3.3	
12	3.3	3.4	3.4	3.35	4.0	4.3	3.4	3.4	3.3	3.3	3.3	
13	3.4	3.55	3.55	3.35	4.0	4.2	3.4	3.4	3.3	3.3	3.3	
14	3.3	3.6	3.55	3.35	4.1	4.2	3.4	3.3	3.3	3.3	3.3	
15	3.3	3.6	3.55	3.45	4.1	4.2	3.4	3.3	3.2	3.3	3.3	
16	3.3	3.6	3.55	3.5	4.1	4.1	3.4	3.2	3.2	3.3	3.3	
17	3.4	3.6	3.65	3.45	4.3	4.1	3.4	3.2	3.2	3.3	3.3	
18	3.3	3.4	3.65	3.45	4.4	4.1	3.3	3.2	3.2	3.3	3.4	
19	3.3	3.4	3.65	3.45	4.6	4.1	3.3	3.2	3.2	3.3	3.3	
20	3.3	3.4	3.65	3.45	4.8	3.9	3.3	3.2	3.2	3.3	3.3	
21	3.35	3.4	3.65	3.4	4.9	3.9	3.3	3.2	3.2	3.3	3.3	
22	3.35	3.4	3.6	3.4	4.9	3.8	3.3	3.2	3.2	3.4	3.3	
23	3.35	3.5	3.55	3.4	4.9	3.8	3.3	3.2	3.2	3.4	3.4	
24	3.35	3.45	3.55	3.4	4.9	3.7	3.3	3.2	4.5	3.4	3.4	
25	3.35	3.45	3.65	3.95	5.0	3.6	3.4	3.2	3.5	3.4	3.4	
26	3.35	3.5	3.65	4.0	5.0	3.6	3.3	3.2	3.4	3.4	3.3	
27	3.35	3.5	3.6	4.2	5.0	3.6	3.3	3.3	3.3	3.4	3.4	
28	3.35	3.5	3.55	4.3	5.1	3.5	3.3	3.2	3.3	3.4	3.3	
29	3.35	.....	3.55	4.3	5.1	3.5	3.3	3.3	6.8	3.4	3.2	
30	3.35	.....	3.45	4.4	5.1	3.5	3.3	3.3	3.6	3.4	3.3	
31	3.35	.....	3.45	.....	4.9	3.5	3.4	3.3	.....	3.3	.....	

NOTE.—These gage heights are liable to some error. Observer made no report of ice conditio but it is probable that the river was frozen for short periods.

Station rating table for Price River near Helper, Utah, from January 1 to December 31, 19

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.10	4	3.60	60	4.10	182	4.60	404
3.20	9	3.70	78	4.20	219	4.70	455
3.30	18	3.80	98	4.30	260	4.80	508
3.40	30	3.90	122	4.40	305	4.90	563
3.50	44	4.00	150	4.50	354	5.00	620

NOTE.—The above table is applicable only for open-channel conditions. It is based on 12 discha measurements made during 1904–1905. It is well defined between gage heights 3.2 feet and 4.9 feet.

Estimated monthly discharge of Price River near Helper, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	30	18	21.1	1,297
.....	60	24	36.3	2,016
.....	69	37	49.8	3,062
.....	305	6	71.5	4,254
.....	678	150	379	23,300
.....	563	44	254	15,110
.....	44	18	25.8	1,586
.....	44	9	18.8	1,156
r.....	1,740	9	87.8	5,224
.....	44	18	26.3	1,617
r.....	30	9	20.5	1,220
·a	18	4	12.0	738
ı year.....	1,740	4	83.6	60,580

a No ice record, discharge applied as for open channel.

GRAND RIVER DRAINAGE BASIN.

AREA AND EXTENT.

River and its tributaries drain an area comprising approximately 26,180 square which 22,290 are in Colorado and the rest in eastern Utah. East and southeast the limited by the high ranges of the Continental Divide, which separate it from the f the Platte and the Arkansas rivers. On the north are the White River and Book ıteaus, while westward it extends to the canyon district of the Colorado.

ibutaries include innumerable small creeks and five large streams, viz, Blue, Eagle, Fork, Gunnison, and Dolores rivers.

following account of the work of the United States Geological Survey in this region 1905 the basin has been subdivided, the main river being described first and the ies afterwards in their order, from the head down.

GRAND RIVER.

DESCRIPTION OF BASIN.

River rises on the western slopes of the Rocky Mountains among the high peaks of ıt Range, flows in a general southwesterly direction across Colorado into Utah, and ıith Green River to form the Colorado. From source to mouth the total distance d is about 350 miles.

st respects the Grand is a typical mountain stream, flowing throughout its course in sion of deep canyons, with precipitous and ofttimes perpendicular walls varying in p to 3,000 feet above the water's edge, alternating with long, narrow, fertile valleys. eadwater region, comprising approximately 50 per cent of the basin, consists of a ɛtch of the western portion of the Continental Divide, extending from the north- portion of Colorado southward nearly to the Colorado-New Mexico line, a distance of ɛs, and separating the waters of the Grand from those of the Platte and Arkansas The area is extremely rugged, elevations ranging from 7,000 to 14,000 feet. Gradi- steep, stream channels are numerous, and tributaries are rapid, the fall varying from 0 feet. The streams of this region derive their waters chiefly from the snow masses ontinental Divide and furnish the perennial discharge of the Grand. The intermedi- iddle portion of the basin, consisting largely of broken and scoured plateaus of sedi- ' origin, contributes a relatively small amount of the run-off, the tributaries being

few and, with the exception of Gunnison River, insignificant. The lower portion of the basin, immediately adjacent to the Colorado-Utah State line, is an arid, much eroded region furnishing an appreciable run-off, which carries a large amount of sediment.

The largest tributaries of the headwater region are Frazer, Williams Fork, Troublesome, Blue, and Muddy rivers, which add their waters to the Grand before it leaves Middle Park. Eagle River comes in near Eagle, just above the point where the river enters Grand River Canyon, and Roaring Fork unites with it just below the mouth of the canyon at Glenwood Springs. At Grand Junction, Colo., the river receives the waters of its largest tributary, Gunnison River, and thereafter no other stream of importance enters until the Dolores comes in, 15 miles west of the Utah boundary.

A peculiar feature of the drainage is what might be termed its one-sided nature, practically all its important tributaries entering the river from the east. That part of the basin lying north and west of the Grand is much less extensive in area, is lower, and is generally broken and barren, and a considerable portion of the waters of its streams is diverted for irrigation.

The geological formations of the basin range from the granite and masses of igneous origin on the crest of the Continental Divide to the younger and less resistant sedimentary rocks of the plateau region. The soils of the upper basin, though shallow, generally contain considerable organic matter; those of the intermediate basin are largely decomposed and disintegrated sedimentary rocks, in the lower basin the soils consist of adobe clays and sandy loams, which grade imperceptibly from one to the other. The scant vegetation of the lower basin renders soil erosion large.

The mountainous portion of the basin is still well covered with forests of spruce, quaking aspen, cedar, and pinon, and the forestation of the intermediate basin is fair. The controlling vegetation of the lower basin is sagebrush, chico, and cactus pads, with scattered pines, cedars, and pinons.

The precipitation ranges from 5 to 10 inches in the lower basin, 10 to 20 inches in the intermediate region, and 20 to 30 inches in the headwater region. By far the greater part of this is in the form of snow.

Natural storage within the basin is limited to a few small, high, mountain lakes. The stream channels of the upper basin are bordered to some extent by flat bottom lands, which are used as meadows and which are irrigated by a large number of small ditches. In the intermediate basin are a few small reservoirs storing snow and flood waters. A number of pumping plants also draw upon this district. Irrigation is extensively practiced in the Uncompahgre, Gunnison, and Grand valleys, and a large project now under construction by the Reclamation Service will require 1,200 second-feet of the discharge of Gunnison River. The immense power possibilities of the Grand are at present but little developed.

NORTH FORK OF GRAND RIVER NEAR GRAND LAKE, COLO.

This station was established July 29, 1904. It is located at the highway bridge between Grand Lake and Hot Sulphur Springs, Colo., about 3 miles southwest of Grand Lake post-office, in T. 3 N., R. 76 W. The nearest railroad station is at Granby, on the Denver, Northwestern and Pacific, 15 miles distant.

The channel is straight for about 500 feet above and for 150 feet below the station. Both banks are about 2 feet high and are covered with heavy sod, willows, and scattered pine trees. The ground slopes upward from the top of the banks rather abruptly, so that even at very high stages the overflow is confined to a comparatively narrow channel. The bed of the stream at the station and for a considerable distance above and below is covered with large bowlders, which at high water cause a boiling and wave motion and at low stages eddies and in some places dead water. The channel is very rough and has a great fall. There is but one channel at all stages. The ordinary range of gage heights is about 3 feet. Gage readings are impracticable during the winter months owing to the [illegible] at the rod. The section is not entirely satisfactory, but it is the best a[illegible]

ge measurements are made at the higher stages from the downstream side of the n wooden bridge to which the gage is attached. The initial point for soundings nny nail driven into the bridge floor over the north face of the right abutment ed zero with black paint.

ge, which was read twice each day during 1905 by G. W. Carr, is a staff attached to the downstream edge of the right abutment of the bridge. The gage reads 10.3 feet, the 2-foot mark resting on the bed of the stream. The bench mark is y nail driven into a notch cut in the northeast root of a 12-inch pine tree which the right end of the bridge on the downstream side; elevation, 8.36 feet above f the gage. The elevation of the station above sea level is about 8,400 feet.

iption of this station with gage-heights and discharge data is contained in Water- aper No. 133, United States Geological Survey, pages 130-132.

ge measurements of North Fork of Grand River near Grand Lake, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	W. A. Lamb.....	39	80	1.80	4.10	144
.....	.....do.....	43	122	3.47	4.80	423
.....	.....do.....	53	159	4.99	5.60	793
.....	.....do.....	52	137	4.20	5.20	576
.....	.....do.....	39	99	3.08	4.60	305
.....	.....do.....	39	87	1.59	4.15	138
.....	.....do.....	39	80	1.28	4.00	102
.....	.....do.....	39	63	1.02	3.76	64
9...	.....do.....	38	55	.75	3.60	41
18..	.....do.....	38	49	.65	3.49	32

ge height, in feet, of North Fork of Grand River near Grand Lake, Colo., for 1905.

Day.	Apr.	May	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	3.3	4.38	5.2	5.05	4.02	3.58	3.55	3.48	4.28
.....	3.3	4.4	5.22	5.05	4.0	3.6	3.52	3.5	3.45
.....	3.3	4.3	5.4	4.95	3.98	3.62	3.5	3.62	3.4
.....	3.3	4.2	5.8	4.7	3.98	3.68	3.5	3.68	3.38
.....	3.3	4.08	5.8	4.6	3.92	3.62	3.5	3.6	3.4
.....	3.35	3.95	5.78	4.6	3.9	3.6	3.48	3.58	3.88
.....	3.3	4.12	5.8	4.55	3.88	3.6	3.45	3.48	3.8
.....	3.3	4.28	5.88	4.62	3.82	3.58	3.45	3.35	3.4
.....	3.35	4.35	6.2	4.6	3.8	3.55	3.48	3.38	3.38
.....	3.3	4.25	6.1	4.58	3.8	3.55	3.48	3.45	3.85
.....	3.3	4.12	5.6	4.58	3.82	3.55	3.5	3.5	3.65
.....	3.35	4.1	5.7	4.5	4.02	3.5	3.5	3.5	.....
.....	3.4	4.15	5.85	4.55	3.98	3.5	3.5	3.45	.....
.....	3.4	4.1	5.7	4.52	3.85	3.5	3.5	3.5	.....
.....	3.4	4.1	5.75	4.62	3.8	3.48	3.5	3.45	.....
.....	3.4	4.3	5.85	4.58	3.78	3.48	3.5	3.35	.....
.....	3.42	4.6	5.68	4.52	3.72	3.45	3.5	3.38	.....
.. ..	3.5	4.72	5.45	4.45	3.7	3.5	3.48	3.4	.....
.....	3.48	4.75	5.35	4.3	3.7	3.52	3.42	3.55	.....
.....	3.5	4.8	5.2	4.3	3.68	3.5	3.52	3.5	.....
.....	3.52	4.88	5.3	4.32	3.65	3.5	3.65	3.45	.....
.....	3.52	4.95	5.3	4.22	3.62	3.5	3.68	3.4	.....

Daily gage height, in feet, of North Fork of Grand River near Grand Lake, Colo., for 190[illegible] Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D[illegible]
23	3.55	5.1	5.38	4.15	3.6	3.48	3.62	3.4	.....
24	3.58	5.02	5.65	4.15	3.6	3.45	3.6	3.5	.....
25	3.6	4.92	5.75	4.18	3.6	3.5	3.52	3.52	.....
26	3.62	4.88	5.7	4.12	3.6	3.5	3.5	3.55	.....
27	3.75	4.92	5.7	4.15	3.6	3.48	3.5	3.45	.....
28	3.92	4.95	5.55	4.15	3.6	3.45	3.5	3.4	.....
29	4.02	4.88	5.42	4.1	3.68	3.45	3.5	3.4	.....
30	4.15	4.85	5.35	4.1	3.62	3.52	3.48	3.5	.....
31	.....	5.05	.....	4.05	3.6	.....	3.45	.....	.....

NOTE.—Ice conditions during December.

Station rating table for North Fork of Grand River near Grand Lake, Colo., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.30	17	4.10	130	4.90	434	5.70	861
3.40	24	4.20	160	5.00	479	5.80	927
3.50	33	4.30	194	5.10	526	5.90	996
3.60	43	4.40	230	5.20	575	6.00	1,067
3.70	55	4.50	267	5.30	627	6.10	1,141
3.80	69	4.60	306	5.40	681	6.20	1,220
3.90	85	4.70	347	5.50	738		
4.00	105	4.80	390	5.60	798		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is well defined between gage heights 3.5 feet and 5.6 feet.

Estimated monthly discharge of North Fork of Grand River near Grand Lake, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	145	17	35.8	2,130
May	526	95	291	17,890
June	1,220	575	816	48,560
July	502	118	254	15,620
August	110	43	67.5	4,150
September	53	28	35.7	2,120
October	53	26	34.2	2,100
November	53	20	31.1	1,851
The period	.....	.....	.....	94,420

GRAND LAKE OUTLET AT GRAND LAKE, COLO.

This station was established July 31, 1904. It is located at the footbridge at the west end of Grand Lake, about one-half mile south of Grand Lake post-office, Colo., in [illegible] R. 75 W. The nearest railroad station is 18 miles distant, at Granby, on the [illegible] western and Pacific Railway.

straight for about 300 feet above and for 150 feet below the boat station. bout 3 feet high, and their level tops are covered with white pine trees. not overflow at this point, which is one-fourth mile below the gage and ent is swift at high water and medium at lower stages. The bed of the ed of gravel and cobblestones and is firm and free from vegetation. At ks are low and are liable to overflow. There is but one channel at all stages. e an ordinary range of 2.5 feet. Ice conditions render gage readings ing the winter months.

asurements are made from a boat at a ford about one-fourth mile below for soundings are marked at 5-foot intervals by tin tags fastened to a wire he stream 50 feet above the ford. The initial point for soundings is the wire is fastened on the right bank. At ordinary and low stages measure- y wading at convenient points below the gage.

was read twice each day during 1905 by J. W. Davies, is a staff attached outheast corner of the second pier from the north end of the footbridge, esting on the bed of the stream. The gage is referred to bench marks cross on the top of a large granite bowlder 85 feet south of the left bank 40 feet west of the lake, marked with black paint "U. S. G. S. B. M." et above the zero of the gage. (2) A cross cut in the top of a granite north from the initial point for soundings and marked "B. M.;" elevation, he zero of the gage. Elevation above sea level is about 8,500 feet.

f this station, with gage-height and discharge data, is contained in Water- . 133, United States Geological Survey, pages 132–134.

measurements of Grand Lake Outlet at Grand Lake, Colo., in 1905.

Hydrographer.	Width	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
m. A. Lamb	48	49	1.53	2.00	75
.do	56	105	3.28	2.90	345
.do	170	347	2.39	3.88	830
.do	156	275	2.13	3.42	585
.do	151	222	1.39	2.77	308
.do	120	137	1.34	2.42	184
.do	126	124	1.07	2.21	133
.do	49	47	1.40	1.95	66
.do	36	34	.82	1.62	28
.do	36	30	.57	1.50	17

ients made at different sections.

height, in feet, of Grand Lake Outlet at Grand Lake, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
	1.34	1.92	3.22	3.37	2.34	1.76	1.48
	1.36	2.02	3.46	3.24	2.28	1.74	1.48
	1.38	2.04	3.64	3.01	2.22	1.62	1.48
	1.39	2.0	3.98	2.82	2.19	1.66	1.48
	1.39	1.96	4.18	2.74	2.16	1.68	1.48
	1.39	1.9	4.03	2.71	2.13	1.68	1.47
	1.39	1.85	4.02	2.7	2.1	1.69	1.45
	1.39	1.84	4.11	2.74	2.06	1.7	1.43
	1.4	1.92	4.44	2.72	2.03	1.68	1.42
	1.48	1.96	4.21	2.71	2.0	1.66	1.4
	1.52	1.96	3.9	2.75	2.0	1.65	1.39

Daily gage height, in feet, of Grand Lake Outlet at Grand Lake, Colo., for 1905—Continu

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oc
12	1.54	1.92	3.9	2.78	2.06	1.62	
13	1.54	1.9	4.0	2.75	2.08	1.59	
14	1.54	1.9	3.9	2.74	2.06	1.55	
15	1.56	1.87	3.98	2.76	2.04	1.54	
16	1.56	1.86	4.12	2.76	2.0	1.54	
17	1.57	1.96	3.72	2.68	1.94	1.52	
18	1.57	2.12	3.69	2.62	1.9	1.5	
19	1.58	2.24	3.46	2.56	1.86	1.49	
20	1.62	2.36	3.32	2.56	1.84	1.49	
21	1.62	2.48	3.4	2.54	1.82	1.49	
22	1.63	2.66	3.38	2.52	1.8	1.48	
23	1.64	2.94	3.46	2.47	1.78	1.47	
24	1.64	3.06	3.66	2.42	1.78	1.46	
25	1.64	2.96	3.76	2.4	1.78	1.44	
26	1.64	2.88	3.87	2.42	1.8	1.44	
27	1.66	2.9	3.84	2.43	1.79	1.44	
28	1.72	2.97	3.74	2.41	1.8	1.44	
29	1.76	2.89	3.66	2.41	1.8	1.45	
30	1.82	2.8	3.56	2.42	1.8	1.46	
31	.....	2.9	.....	2.38	1.8	.....	

Station rating table for Grand Lake Outlet at Grand Lake, Colo., from January 1 to Dec 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet*
1.30	10	2.20	122	3.10	433	4.00	900
1.40	13	2.30	148	3.20	479	4.10	956
1.50	18	2.40	176	3.30	527	4.20	1,013
1.60	25	2.50	207	3.40	578	4.30	1,071
1.70	34	2.60	240	3.50	630	4.40	1,130
1.80	46	2.70	275	3.60	682	4.50	1,190
1.90	60	2.80	312	3.70	735		
2.00	77	2.90	350	3.80	789		
2.10	98	3.00	390	3.90	844		

NOTE.- The above table is applicable only for open-channel conditions. It is based on disch measurements made during 1905 and is well defined.

Estimated monthly discharge of Grand Lake Outlet at Grand Lake, Colo., for 1905.

Month.	Discharge in second-feet.			Tota acre-
	Maximum.	Minimum.	Mean.	
April	49	11	22.7	
May	416	52	168.	
June	1,154	489	785	
July	563	170	267	
August	159	44	76.2	
September	41	15		
October	17	12		
The period				

NORTH INLET TO GRAND LAKE AT GRAND LAKE, COLO.

his station was established August 3, 1905. It is located at the footbridge which crosses stream about 100 yards north of the mouth and 300 yards east of Grand Lake postce, in sec. 5, T. 3 N., R. 75 W.

he channel is straight for 300 feet above and for 200 feet below the station. The right ık is low, is covered with grasses and scattered willows and white pine trees, and at high ges overflows to a considerable extent. The left bank is high and is covered with a dense wth of white pines and underbrush. The bed of the stream is composed of large cobblenes and gravel and is permanent. There is but one channel at all ordinary stages, ıken by the middle pier of the bridge. The current is swift at high and medium at low ter.

High-water measurements are made from the upstream side of the two-span footbridge. e initial point for soundings is a 40-penny nail driven in the top of the west end of the rth stringer of the bridge, 97 feet from bench mark No. 2. The point is marked with ack paint. Low-water measurements are made by wading at convenient points above e bridge.

The gage, which was read twice each day during 1905 by J. Cairns, is a 4-foot timber fasned to the west face of the outer pier of the bridge. It is referred to bench marks as llows: (1) A 40-penny nail driven horizontally in the west face of a white pine tree 8 inches diameter located on the left bank of the stream, 20 feet northeast of the east end of the idge, marked "U. S. B. M.;" elevation, 5.32 feet above the zero of the gage. (2) A -penny nail driven horizontally in the east face of a white pine tree 1 foot in diameter ated on the right bank of the stream 97 feet west of the initial point for soundings; eletion, 4.43 feet above the zero of the gage.

Discharge measurements of North Inlet to Grand Lake at Grand Lake, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
y 4	W. A. Lamb	48	43	1.37	2.30	58
y 31	do	50	111	1.84	3.05	204
y 27	do	48	53	1.62	2.40	86
gust 3	do	46	50	1.36	2.30	68
tember 11	do	34	23	.61	1.90	14
tember 18	do	30	15	.63	1.85	9.4

OTE.—Measurements made at different sections.

Daily gage height, in feet, of North Inlet to Grand Lake at Grand Lake, Colo., for 1905.

Day.	Aug.	Sept.	Oct.	Nov.	Dec.	Day.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	2.0	1.8	1.85	1.85	17.....	2.1	1.9	1.8	1.9	1.8
.....	.....	2.0	1.8	1.85	1.8	18.....	2.1	1.9	1.8	1.9	1.8
.....	2.3	1.9	1.8	1.85	1.8	19.....	2.0	1.9	1.8	1.9	1.8
.....	2.3	1.9	1.8	1.85	1.8	20.....	2.0	1.9	1.85	1.9	1.8
.....	2.3	1.9	1.8	1.9	1.8	21.....	2.0	1.9	1.95	1.9	1.8
.....	2.3	1.9	1.8	1.9	1.8	22.....	2.0	1.9	1.9	1.9	1.8
.....	2.3	2.0	1.8	1.9	1.8	23.....	2.0	1.9	1.9	1.9	1.8
.....	2.2	1.9	1.8	1.9	1.8	24.....	2.0	1.8	1.9	1.9	1.8
.....	2.2	1.9	1.8	1.9	1.8	25.....	2.0	1.8	1.85	1.9	1.8
.....	2.2	1.9	1.8	1.9	1.8	26.....	2.0	1.8	1.85	1.9	1.8
.....	2.2	1.9	1.8	1.9	1.8	27.....	2.0	1.8	1.8	1.9	1.8
.....	2.2	1.9	1.8	1.9	1.8	28.....	2.0	1.8	1.8	1.9	1.8
.....	2.2	1.9	1.8	1.9	1.9	29.....	2.0	1.8	1.85	1.9	1.8
.....	2.2	1.9	1.8	1.9	1.9	30.....	2.0	1.8	1.9	1.9	1.8
.....	2.15	1.9	1.8	1.9	1.9	31.....	2.0	.....	1.95	.....	1.8
.....	*2.1*	*1.9*	*1.8*	*1.9*	1.9						

GRAND RIVER AT HOT SULPHUR SPRINGS, COLO.

This station was established July 27, 1904. It is located at the highway bridge one-eighth mile below Hot Sulphur Springs, Colo., in sec. 3, T. 1 N., R. 78 W., and is 5 miles above the mouth of Williams Fork River.

The channel is straight for about 200 feet below the station. Above the station it is curved at almost a right angle. Both banks are high and can not overflow. The bed of the stream is composed of bed rock, heavy gravel, and large bowlders on the right side, while on the left side it is a sloping gravel bar extending outward to the left abutment of the bridge. It is free from vegetation and, except for the gravel bar, is permanent. There is but one channel at all stages broken by the two piers of the bridge. The current is swift and at low water passes under the bridge squarely. At high water the current in the greater part of the section passes under the bridge at an angle. The accuracy of measurements is affected by the boiling of the water at the piers and by the large bowlders in the channel beneath the bridge. During the spring and early summer of 1905 the channel 100 feet below the station was somewhat obstructed by large bowlders which were blasted from a railroad cut on the right bank. This obstruction backs the water up on the gage to a considerable extent and at extreme low stages causes dead water in a portion of the cross sections.

Discharge measurements, except at very low stages, are made from the upstream side of the three-span bridge. The initial point for soundings is located over the inner face of the right abutment and is marked with a circle on the upstream hub rail. A stay line is located 30 feet above the bridge.

The gage, which was read once each day during 1905 by Mrs. Carrie Wills, consists of a vertical staff, bolted vertically to the downstream end of the first pier from the right bank. The gage reads from 2 to 10.8 feet, the 2-foot mark resting on bed rock. The gage is referred to bench marks as follows: (1) A cross painted on the north pier above the gage rod; elevation, 16.48 feet above the zero of the gage. (2) A cross cut in the top of a bench on the northwest face of a sandstone cliff on the east side of the road 50 feet south of the bridge; elevation, 25.49 feet above the zero of the gage. The elevation of the station above sea level is approximately 6,550 feet.

A description of this station and gage-height and discharge data are contained in Water-Supply Paper, No. 133, United States Geological Survey, pages 135–137.

Discharge measurements of Grand River at Hot Sulphur Springs, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 1	W. A. Lamb	80	401	3.16	5.22	1,269
May 6	do	66	333	2.14	4.40	722
May 29	do	97	517	5.10	6.55	2,638
June 3	do	106	665	6.27	7.85	4,167
June 9	do	102	782	7.33	9.15	5,733
July 5	do	74	446	3.46	5.52	1,542
July 25	do	70	359	2.10	4.58	731
August 16	do	63	269	1.28	3.95	343
August 29	do	58	279	.99	3.74	277
September 9	do	58	284	.99	3.60	281
September 15	do	54	250	.81	3.45	203
October 2	do	54	251	.73	3.43	183

Daily gage height, in feet, of Grand River at Hot Sulphur Springs, Colo., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	2.65	2.9	5.35	7.4	6.75	4.55	3.35	3.5	3.45
2	2.7	2.95	5.58	7.55	6.35	4.6	3.3	3.5	3.45
3	2.7	2.75	5.38	7.8	6.1	4.6	3.4	3.5	3.45
4	2.68	2.65	4.98	8.5	6.0	4.45	3.4	3.4	3.5
5	2.68	2.75	4.8	8.95	5.45	4.3	3.32	3.4	3.5
6	2.68	2.8	4.58	8.4	5.45	4.3	3.32	3.4	3.5
7	2.68	3.0	4.7	8.5	5.45	4.25	3.4	3.4	3.5
8	2.68	3.15	4.8	9.05	5.42	4.2	3.4	3.4	3.5
9	2.7	3.4	5.2	8.75	5.42	4.22	3.32	3.4	3.5
10	2.65	3.6	4.98	8.25	5.45	4.28	3.3	3.4	3.48
11	2.65	3.58	4.78	8.25	5.42	4.2	3.32	3.4	3.45
12	2.65	3.62	4.7	8.25	5.42	4.05	3.3	3.4	3.42
13	2.65	3.58	4.8	8.0	5.42	4.0	3.32	3.42	3.42
14	2.68	3.55	4.62	8.05	5.42	4.0	3.22	3.48	3.42
15	2.65	3.5	4.62	7.65	5.45	4.02	3.2	3.42	3.42
16	2.68	3.75	4.88	7.55	5.22	4.08	3.2	3.4	3.42
17	2.7	3.6	5.45	7.65	5.18	3.95	3.0	3.4	3.4
18	2.65	3.78	5.85	7.88	5.05	3.92	3.0	3.4	3.4
19	2.65	4.02	6.15	7.85	5.02	3.9	3.4	3.4	3.4
20	2.7	3.95	6.38	7.4	4.98	3.88	3.5	3.4	.....
21	2.65	3.8	6.48	7.4	4.9	3.85	3.4	3.4	.....
22	2.7	3.88	6.72	7.45	4.75	3.8	3.4	3.4	.....
23	2.7	3.95	7.05	7.1	4.58	3.78	3.4	3.4	.....
24	2.65	4.22	7.12	7.15	4.45	3.75	3.4	3.4	.....
25	2.7	4.05	6.75	7.5	4.42	3.58	3.4	3.4	.....
26	2.7	4.08	6.62	7.45	4.42	3.45	3.4	3.4	.....
27	2.65	4.48	6.75	7.5	4.46	3.4	3.4	3.45	.....
28	2.75	4.62	6.85	7.55	4.46	3.4	3.4	3.45	.....
29	2.75	4.65	6.6	7.4	4.46	3.42	3.4	3.45	.....
30	2.8	4.88	6.48	7.1	4.6	3.38	3.48	3.45	.....
31	2.85	.....	6.6	.....	4.6	3.4	.....	3.45	.....

ation rating table for Grand River at Hot Sulphur Springs, Colo., from July 27, 1904, to April 15, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.60	185	2.90	276	3.20	402	3.50	554
2.70	215	3.00	313	3.30	450	3.60	609
2.80	245	3.10	355	3.40	501		

OTE.—The above table is applicable only for open-channel conditions. It is based on four discharge surements made during 1904 and is well defined.

Station rating table for Grand River at Hot Sulphur Springs, Colo., from May 1 to De ber 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.00	95	4.20	500	5.40	1,430	7.20	3,380
3.10	110	4.30	560	5.50	1,530	7.40	3,600
3.20	130	4.40	620	5.60	1,630	7.60	3,840
3.30	150	4.50	680	5.70	1,730	7.80	4,080
3.40	180	4.60	750	5.80	1,830	8.00	4,320
3.50	210	4.70	820	5.90	1,930	8.20	4,560
3.60	240	4.80	900	6.00	2,030	8.40	4,800
3.70	280	4.90	980	6.20	2,250	8.60	5,040
3.80	320	5.00	1,060	6.40	2,470	8.80	5,280
3.90	360	5.10	1,150	6.60	2,690	9.00	5,540
4.00	400	5.20	1,240	6.80	2,910	9.20	5,800
4.10	450	5.30	1,330	7.00	3,130		

NOTE.—The above table is applicable only for open-channel conditions. It is based on twelve disc measurements made during 1905. It is well defined above gage height 3.4 feet. Owing to cha conditions from April 15 to April 30 the above table has been applied indirectly for that period.

Estimated monthly discharge of Grand River at Hot Sulphur Springs, Colo., for 190

Month.	Discharge in second-feet.			To acre
	Maximum.	Minimum.	Mean.	
March	260	200	212	1
April	1,036	200	550	3
May	3,264	736	1,755	10
June	5,605	3,240	4,137	24
July	2,855	632	1,265	7
August	750	174	410	2
September	210	95	164	9
October	210	180	186	11
November 1-19	210	180	195	7
The period				55

GRAND RIVER NEAR KREMMLING, COLO.

This station was established July 24, 1904. It is located at the mouth or upper en Gore Canyon, about 3 miles southwest of Kremmling, Colo.

The channel is straight for about 100 feet above and for 150 feet below the station. right bank is the grade of the Denver, Northwestern and Pacific Railway; the left ban abrupt and is covered with bowlders and bushes; neither bank overflows. The bed of stream is composed of sand, silt, and bowlders and is very shifting, the change in cha being as great as 10 feet in places. The channel scours out during high-water stages gradually fills up again as the water subsides. There is but one channel at all stages. current is very sluggish at low water and medium to swift at high water. Gage hei have a range of about 15 feet during an ordinary season. Gage readings in the wi months are somewhat affected by ice in the channel. The shifting of the bed makes development of a good rating curve a difficult matter. The station is not factory, but it is the best location available below the mouth of Blue Ri

Discharge measurements are made from a cable stretched across the gage and about 150 feet above the wagon bridge. The cable is

d is tagged with tin tags marked every 5 feet from the top of the right bank, which h sandstone cliff, to the top of the left bank. The initial point for soundings is the the rock to which the cable is anchored on the right bank.

readings at this station were made twice each day during 1905 by J. C. Harper. iginal equipment consisted of a wire gage attached to the cantilever arm of the o which the gage rod was spiked in a horizontal position. This gage was destroyed ı water in June, 1905, and after the water had subsided the old gage was placed on a ıtilever arm similar to the old one but about 3 feet higher, the gage datum remain- same and the wire was replaced by a standard chain. The length of the chain is ɛet. Bench mark No. 1 is a cross cut in the east face of a large bowlder on the right bout 20 feet south of the cable marked with black paint "U.S. B.M.;" elevation, ɛet above the zero of the gage. The elevation above sea level is about 7,250 feet. mark No. 2 is a cross cut and painted block on top of a cone-shaped granite bowlder left bank of the river about 50 feet downstream from the gage. Elevation of bench bove gage datum is 9.57 feet. This bench mark is submerged at high water.

scription of this station, with gage-height and discharge data, is contained in Water- Paper No. 133, United States Geological Survey, pages 137–139.

Discharge measurements of Grand River near Kremmling, Colo., in 1905.

te.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	W. A. Lamb.....	115	775	2.27	5.24	1,762
.....	.....do.....	118	1,190	1.97	6.48	2,344
.....	.....do.....	141	1,810	3.08	10.98	5,575
.....	..... do.....	160	2,688	4.24	15.14	11,400
.....	.....do.....	150	2,362	3.67	13.05	8,668
.....	M. C. Hinderlider.....	142	2,183	3.32	11.81	7,248
.....	W. A. Lamb.....	135	1,945	2.97	10.22	5,777
.....	.....do.....	106	1,293	1.49	5.80	1,927
.....	.....do.....	116	1,310	1.30	5.15	1,703
10.....	.....do.....	104	920	.93	3.10	852
25.....	.....do.....	102	409	1.68	2.38	689
ɛer 5...	.....do.....	104	380	1.72	2.29	655
ɛer 14..	..... do.....	100	271	1.85	1.83	500
ɛer 27..	.....do.....	101	202	2.09	1.60	423

Daily gage height, in feet, of Grand River near Kremmling, Colo., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.41	0.95	1.09	2.08	6.88	11.83	8.81	4.54	2.90	1.90	1.32	0.92
.....	1.36	.97	1.06	2.21	7.50	12.42	8.33	4.27	2.48	1.75	1.23	1.15
.....	1.18	.95	1.14	2.03	7.22	12.92	8.04	3.99	2.46	1.85	1.58	1.06
.....	1.01	.95	1.09	1.53	6.50	14.03	7.40	3.88	2.22	1.70	1.88	1.13
.....	.98	.93	1.06	1.65	5.98	15.42	6.76	3.70	2.32	1.68	1.92	1.18
.....	.94	.97	1.16	2.08	5.40	15.25	6.61	3.72	2.40	1.65	1.97	1.06
.....	.88	.85	1.19	2.68	5.22	14.46	6.34	3.76	2.52	1.54	1.82	.75
.....	.76	.93	1.14	2.61	5.35	14.66	6.32	3.32	2.46	1.50	1.68	.82
.....	.78	.83	1.16	2.93	6.40	15.28	6.21	3.38	2.34	1.50	1.56	1.26
.....	.98	.75	1.09	3.31	6.38	15.43	5.48	3.18	2.26	1.46	1.44	1.60
.....	.96	.84	1.14	3.38	6.45	14.45	5.46	3.15	2.14	1.24	1.20	1.90
.....	.88	.80	1.16	3.25	6.54	13.46	5.90	3.56	2.02	1.36	1.21	1.64
.....	.88	.95	1.22	3.33	5.65	13.54	5.87	3.76	1.90	1.42	1.32	1.90
.....	.86	.95	1.24	3.35	5.68	13.45	5.76	3.44	1.84	1.56	1.60	1.72

Daily gage height, in feet, of Grand River near Kremmling, Colo., for 1905—Continued.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
15	.84	.90	1.32	3.05	5.50	12.77	5.98	3.18	1.74	1.64	1.55	1.35
16	.98	1.05	1.39	2.98	5.87	13.06	5.88	3.00	1.68	1.60	1.48	1.23
17	.98	1.05	1.49	2.91	6.99	12.54	5.95	2.76	1.64	1.92	1.65	1.09
18	1.01	1.10	1.44	3.01	7.88	11.75	5.42	2.66	1.66	1.90	1.75	1.05
19	1.04	1.03	1.29	3.48	8.78	11.53	5.36	2.38	1.78	1.82	1.67	.89
20	.88	.93	1.34	3.48	9.61	11.37	5.24	2.48	1.79	1.70	1.20	.80
21	.84	1.03	1.49	3.11	9.78	10.29	5.35	2.41	1.79	1.50	1.28	.76
22	.86	1.05	1.52	3.05	10.52	10.29	5.14	2.32	1.72	1.65	1.48	.69
23	.96	1.07	1.46	3.31	11.31	10.51	4.64	2.29	1.65	1.75	1.45	.64
24	1.04	1.05	1.34	3.68	11.59	10.43	4.50	2.36	1.60	1.82	1.82	.58
25	.98	1.03	1.44	3.71	11.08	10.35	4.46	2.41	1.60	1.82	1.32	.59
26	.78	1.03	1.59	3.48	10.70	10.35	4.45	2.46	1.60	1.61	1.34	.64
27	.78	1.07	2.04	4.11	11.00	10.35	4.42	2.42	1.60	1.66	1.49	.65
28	.86	1.07	1.79	5.05	10.95	10.04	4.51	2.36	1.58	1.83	1.30	.52
29	.81	.....	1.46	5.32	10.44	9.46	4.61	2.48	1.58	1.85	1.08	.58
30	.94	.....	1.49	5.85	10.09	9.32	4.64	2.55	1.68	1.82	.68	.46
31	.96	.....	1.82	.....	10.65	.....	4.66	2.82	.....	1.68	.....	.34

NOTE.—No ice record.

Station rating table for Grand River near Kremmling, Colo., from January 1 to December 31, 1905.[a]

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.20	220	1.60	440	3.00	830	5.80	1,950
.30	230	1.70	465	3.20	900	6.00	2,050
.40	240	1.80	490	3.40	970	6.20	2,170
.50	250	1.90	515	3.60	1,040	6.40	2,290
.60	260	2.00	540	3.80	1,110	6.60	2,410
.70	275	2.10	565	4.00	1,180	6.80	2,530
.80	290	2.20	590	4.20	1,250	7.00	2,670
.90	305	2.30	620	4.40	1,330	7.20	2,810
1.00	320	2.40	650	4.60	1,410	7.40	2,950
1.10	340	2.50	680	4.80	1,490	7.60	3,090
1.20	360	2.60	710	5.00	1,570	7.80	3,250
1.30	380	2.70	740	5.20	1,650	8.00	3,410
1.40	400	2.80	770	5.40	1,750		
1.50	420	2.90	800	5.60	1,850		

[a] From May 14 to July 10, inclusive, the table was applied indirectly, owing to shifting conditions.

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is well defined between gage heights 1.6 feet and 6.5 feet.

Estimated monthly discharge of Grand River near Kremmling, Colo., for 1905.

[Drainage area, 2,380 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	402	287	314	19,310	0.132	0.152
February	340	282	316	17,550	.133	.138
March	550	332	390	23,980	.164	.189
April	1,975	426	924	54,980	.388	.433
May	6,430	1,660	3,523	216,600	1.48	1.71
June	11,820	4,850	7,999	476,000	3.36	3.75
July	4,340	1,338	2,046	125,800	.860	.992
August	1,386	617	866	53,250	.364	.420
September	800	436	532	31,660	.224	.250
October	520	368	475	29,210	.200	.231
November	532	272	419	24,930	.176	.196
December	515	228	325	19,980	.137	.158
The year	11,820	228	1,511	1,093,000	.635	8.62

GRAND RIVER AT GLENWOOD SPRINGS, COLO.

This station is located in the mountains, midway between the Continental Divide and the Colorado-Utah boundary line, and just above the third large tributary of the Grand, which is called Roaring Fork.

A comparison of the miscellaneous discharge measurements made at the mouth of Roaring Fork, at Glenwood Springs, during 1903 and 1904, with the discharge of the Grand, at Glenwood Springs, shows that the volume of water being discharged by the Roaring Fork augments the volume of water which passes the Glenwood station by 50 per cent. While there is a moderate amount of irrigation of the first bottom lands from the tributaries above this point, relatively little of the run-off of the basin is used.

The station was established May 12, 1899, at the request of the Denver and Rio Grande Railroad Company. It was at first located at the railroad bridge, a quarter of a mile west of the depot and just above the mouth of Roaring Fork; but at the beginning of 1900 it was removed to a point near the electric-light works. The measuring section is located at the State Street Bridge, which crosses the river at the main thoroughfare of Glenwood Springs, and is about 10 feet below the point at which all discharge measurements from 1900 to 1904, inclusive, were made.

The channel at the cable section is straight for a distance of several hundred feet each way. The left bank is the Denver and Rio Grande Railroad embankment and is well protected by a concrete and dry rubble retaining wall. The right bank is a low wall composed of bowlders, without any binding material, and protects the grounds of the Hotel Colorado. At extremely high water these grounds have been flooded, but this is a rare occurrence. The bed of the stream is composed of bowlders and cobblestones and is permanent. A small amount of silt is deposited at low water, but it scours out in the spring and does not change the cross section materially. There is but one channel at all stages. At high water the current is swift, often reaching a velocity as high as 20 feet per second; at low water the current has a moderate velocity. Gage heights range from 2.5 to 12 feet.

Discharge measurements since May 16, 1905, have been made by means of a cable, car, and stay line 60 feet upstream, the cable being anchored to the piers of the State Street Bridge. Measurements from 1900 to 1904, inclusive, were made from the footway which

crosses the stringers of the bridge below the roadway, about 10 feet above the present section. Plottings of old and new cross sections show no material difference.

Gage readings at this station are made by W. H. Richardson, the manager of the Glenwood Electric Light and Power Company, morning and evening each day during the entire year. The first gage was wire, but when the station was removed to the electric-light works a new gage rod was placed. This consisted of a light vertical staff, to the lower end of which was attached a wooden float, which rested on the surface of the water, standing in a well or box made of 6-inch boards. The bottom of this well connected with a small wooden flume extending out into the river, which allowed the water in the well to assume the level of the river surface. In July, 1902, this gage being in bad repair was replaced by an automatic water register, the site being the same as that of the old float gage. The register never worked satisfactorily and was later replaced by another float gage, using the same well and intake flume. The present gage consists of a copper float and counterweight connected with a silk line passing over pulleys so arranged that a rise of 1 foot of the river registers but one-half foot on the rod. By this arrangement the large rise and fall of the river is readily accommodated by a length of gage that would be impossible with a direct-reading gage. The gage rod proper consists of a light pine rod, 1 by 1 inch by 5 feet, securely fastened in a vertical position inside a small house in which the apparatus is located and which sets on top of the vertical well. A pointer attached to a counterweight slides along the gage rod and registers the rise and fall of the river. This gage has given entire satisfaction. The original basis for the installation of this gage and the method of correction since that time is the relation of the depth of water in the well to the gage reading. When the gage reads correctly the difference between the depth of water in the well and the gage reading is 2.25 feet. The bench mark established June 27, 1904, is a cross cut in the top of the foundation capstone of the power house directly in front of the gage house, east of the power-house door, and is indicated by the letters "B.M." cut in the vertical face of the foundation stone on which the bench mark is located. Elevation of bench mark above the datum of the gage is 17.77 feet.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 37, pp 293-294; 50, pp 375-376; 66, p 92; 85, p 48; 100, pp 89-90; 133, pp 139-140.
Discharge: WS 37, p 294; 50, p 376; 85, p 49; 100, p 90; 133, p 140.
Discharge, monthly: Ann 22, iv, p 389; WS 75, p 174; 85, p 50; 100, p 92; 133, p 141.
Gage heights: WS 37, p 294; 50, p 376; 66, p 93; 85, p 49; 100, p 91; 133, p 140.
Hydrographs: Ann 22, iv, p 389; WS 75, p 174.
Rating tables: WS 52, p 520; 66, p 174; 85, p 50; 100, p 91; 133, p 141.

Discharge measurements of Grand River at Glenwood Springs, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
March 28	R. I. Meeker	190	508	2.01	3.77	1,019
May 16	do	200	871	4.01	5.50	3,496
June 2	do	210	1,630	10.07	9.12	16,410
June 5	do	215	1,983	13.91	10.70	27,580
July 9	do	208	906	4.35	5.82	3,941
July 10	do	208	904	4.28	5.78	3,871
August 13	do	194	643	2.98	4.68	1,919
September 26	do	185	486	2.35	3.95	1,142

Daily gage height, in feet, of Grand River at Glenwood Springs, Colo., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct	Nov.	Dec.
.....	3.34	3.29	3.36	3.68	5.95	8.55	7.32	5.05	4.35	3.88	3.95	3.25
.....	3.4	3.29	3.46	3.82	6.4	9.1	6.75	4.95	4.45	3.9	3.85	3.32
.....	3.34	3.26	3.48	3.88	6.42	9.2	6.58	4.85	4.32	3.98	3.88	3.25
.....	3.4	3.24	3.56	3.78	6.12	9.9	6.45	4.82	4.35	3.95	3.85	3.35
.....	3.44	3.24	3.61	3.72	5.85	10.7	6.15	4.72	4.32	3.92	3.98	3.38
.....	3.47	3.24	3.61	3.72	5.6	10.7	6.02	4.68	4.3	3.92	4.0	3.3
.....	3.47	3.24	3.64	3.78	5.45	10.4	5.95	4.65	4.35	3.92	3.98	3.18
.....	3.44	3.19	3.51	3.92	5.48	10.3	5.88	4.65	4.4	3.9	3.98	3.18
.....	3.42	3.19	3.44	4.1	5.8	10.72	5.85	4.58	4.32	3.85	3.92	3.15
.....	3.37	3.19	3.46	4.28	6.05	10.58	5.78	4.5	4.22	3.85	3.92	3.1
.....	3.32	3.19	3.48	4.48	5.88	10.48	5.7	4.5	4.22	3.85	3.88	2.9
.....	3.32	3.12	3.51	4.5	5.68	10.38	5.7	4.52	4.15	3.82	3.82	3.0
.....	3.22	2.96	3.56	4.48	5.58	10.02	5.7	4.7	4.12	3.85	3.8	3.1
.....	3.22	2.99	3.61	4.45	5.65	9.68	5.65	4.78	4.1	3.85	3.78	3.02
.....	3.32	3.04	3.66	4.5	5.62	9.68	5.65	4.62	4.05	3.85	3.85	2.95
.....	3.4	3.09	3.66	4.45	5.68	9.25	5.68	4.52	4.02	3.88	3.9	3.35
.....	3.37	3.14	3.71	4.32	6.0	8.85	5.58	4.42	4.0	3.9	3.88	3.4
.....	3.4	3.29	3.64	4.3	6.62	8.58	5.5	4.35	4.0	3.95	3.88	3.4
.....	3.47	3.24	3.66	4.45	7.1	8.25	5.5	4.32	4.02	3.95	3.88	3.38
.....	3.44	3.29	3.66	4.52	7.48	7.9	5.42	4.25	4.05	3.92	3.82	3.4
.....	3.4	3.29	3.64	4.58	7.68	7.8	5.28	4.22	4.1	3.82	3.78	3.4
.....	3.42	3.29	3.66	4.4	7.92	7.75	5.3	4.15	4.05	3.82	3.82	3.3
.....	3.42	3.26	3.66	4.4	8.4	7.78	5.28	4.12	4.02	3.95	3.78	3.25
.....	3.4	3.26	3.64	4.48	8.58	7.8	5.2	4.12	4.0	3.98	3.75	3.22
.....	3.4	3.32	3.61	4.6	8.45	7.78	5.12	4.15	3.98	3.95	3.65	3.2
.....	3.37	3.32	3.68	4.62	8.2	7.65	5.12	4.18	3.95	3.95	3.68	3.28
.....	3.37	3.34	3.68	4.62	8.2	7.65	5.02	4.15	3.92	3.95	3.68	3.32
.....	3.27	3.39	3.81	4.92	8.22	7.58	5.02	4.15	3.92	3.95	3.85	3.4
.....	3.24	.....	3.78	5.35	8.08	7.5	5.05	4.18	3.9	4.0	3.48	3.32
.....	3.27	.....	3.68	5.52	7.85	7.42	5.02	4.18	3.95	4.02	3.12	3.22
.....	3.32	.....	3.65	.....	8.0	.....	5.02	4.3	.....	3.95	.....	3.22

m rating table for Grand River at Glenwood Springs, Colo., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.90	530	4.40	1,640	5.90	4,000	7.80	9,380
3.00	570	4.50	1,760	6.00	4,210	8.00	10,210
3.10	610	4.60	1,880	6.10	4,420	8.20	11,110
3.20	660	4.70	2,010	6.20	4,640	8.40	12,090
3.30	710	4.80	2,150	6.30	4,860	8.60	13,160
3.40	770	4.90	2,290	6.40	5,090	8.80	14,350
3.50	830	5.00	2,440	6.50	5,330	9.00	15,660
3.60	900	5.10	2,590	6.60	5,580	9.20	17,030
3.70	970	5.20	2,740	6.70	5,840	9.40	18,410
3.80	1,050	5.30	2,890	6.80	6,110	9.60	19,800
3.90	1,130	5.40	3,050	6.90	6,390	9.80	21,200
4.00	1,220	5.50	3,220	7.00	6,670	10.00	22,600
4.10	1,320	5.60	3,400	7.20	7,260	10.20	24,020
4.20	1,420	5.70	3,590	7.40	7,910	10.40	25,440
4.30	1,530	5.80	3,790	7.60	8,620	10.60	26,860

OTE.—The above table *is applicable only for* open-channel conditions. It is based on discharge *surements made during 1903–1905. It is* well defined between gage heights 3.5 feet and 10.7 feet.

Daily gage height, in feet, of Grand River near Palisades, Colo., for 1905—Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
23	13.3	19.45	18.2	14.3	12.6	12.5	12.7
24	13.35	19.95	18.2	14.15	12.6	12.5	12.7
25	13.5	19.8	17.95	14.0	12.7	12.7	12.7
26	13.6	19.55	18.0	13.9	12.75	12.6	12.7
27	13.75	19.5	17.95	13.85	12.7	12.5	12.7
28	13.95	19.4	17.7	13.75	12.65	12.5	12.7
29	14.35	19.0	17.4	13.7	12.65	13.0	12.7
30	14.85	18.7	17.3	13.85	12.7	12.9	12.7
31	.....	18.8	.....	13.95	12.75	.....	12.75

Station rating table for Grand River near Palisades, Colo., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
12.00	1,120	13.70	3,440	15.30	7,120	17.80	15,430
12.10	1,210	13.80	3,640	15.40	7,380	18.00	16,250
12.20	1,300	13.90	3,850	15.50	7,650	18.20	17,080
12.30	1,400	14.00	4,060	15.60	7,920	18.40	17,920
12.40	1,500	14.10	4,270	15.70	8,200	18.60	18,780
12.50	1,610	14.20	4,490	15.80	8,480	18.80	19,650
12.60	1,720	14.30	4,710	15.90	8,770	19.00	20,530
12.70	1,830	14.40	4,940	16.00	9,070	19.20	21,430
12.80	1,950	14.50	5,170	16.20	9,680	19.40	22,340
12.90	2,070	14.60	5,400	16.40	10,320	19.60	23,260
13.00	2,200	14.70	5,640	16.60	10,980	19.80	24,200
13.10	2,350	14.80	5,880	16.80	11,660	20.00	25,160
13.20	2,510	14.90	6,120	17.00	12,370	20.50	27,640
13.30	2,680	15.00	6,360	17.20	13,100	21.00	30,210
13.40	2,860	15.10	6,610	17.40	13,850	21.50	32,860
13.50	3,050	15.20	6,860	17.60	14,630	22.00	35,590
13.60	3,240						

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1903-1905 and three high-water measurements of 1906. It is well defined.

Estimated monthly discharge of Grand River near Palisades, Colo., for 1905.

[Drainage area, 8,546 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
April	6,000	1,500	2,644	157,300	.309	.345
May	24,920	6,120	13,080	804,300	1.53	1.76
June	35,870	13,470	24,440	1,454,000	2.86	3.19
July	12,370	3,440	6,084	374,100	.712	.821
August	4,600	1,720	2,527	155,400	.296	.341
September	2,275	1,610	1,830	108,900	.214	.239
October	1,890	1,610	1,747	107,400	.204	.235
The period	.....	.....	.....	3,161,000	.....	.....

MISCELLANEOUS MEASUREMENTS.

›wing miscellaneous discharge measurements were made in the Grand River 05.

laneous discharge measurements made in Grand River drainage basin in 1905.

	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
....	Willow Creek...	Near Hot Sulphur Springs, Colo.	42	115	5.77	[a] 3.90	664
....	....do.....	....do.....	28	30	1.67	[a] 6.20	38
....	East Inlet.....	Grand Lake, Colo.	33	47	1.64	[b] 7.30	77
....	....do.....	....do.....	21	25	.92	[b] 7.80	23
1...	....do.....	....do.....	24	13	.77	[c] 8.15	10
....	Yampa Hot Spring.	Glenwood Springs	2.6	2.5	2.28	0.97	5.66
....	....do.....	....do.....	2.6	2.6	2.31	.99	6.00
....	....do.....	....do.....	2.6	2.9	2.21	1.10	6.40

[a] Distance to water surface from bolt in stringer of southwest corner of bridge.
[b] Distance to water surface from knot indicated in overhanging tree.
[c] U. S. B. M.

FRASER RIVER DRAINAGE BASIN.

FRASER RIVER AT GRANBY, COLO.

River rises among the peaks of the Front Range in southeastern Grand County, flows in a general northwesterly direction to its point of junction with Grand ıe east-central part of Middle Park. The stream receives a number of small tribu- ›ng which are Elk, St. Louis, Crooked, and Pole creeks, all short mountain streams ıe eastern slopes of the Vasquez Mountains.

ing station was established July 28, 1904. It is located on the main road between d Grand Lake, at the wagon bridge three-fourths mile southwest of Granby and iles above the mouth of the river, in sec. 9, T. 1 N., R. 76 W. In the 1904 Prog- ·t this station was called Fraser River, near Coulter, Colo.

nnel is straight for about 100 feet above and curved for 100 feet below the station. bank is about 2 feet high, is covered with willows, and overflows at high stages. ınk above the station is a high, abrupt mesa; below the station it is a 6-foot mesa 50 feet, then a low, brush-covered flat, which is overflowed at high stages. The bed am is composed of smooth cobblestones, and the cross section is fairly uniform, permanent. There is but one channel at all stages, broken by two crib piers, ıe boiling effects and back water at high stages. The current is swift at high and : low water. Gage heights have a range of about 2.5 feet during an ordinary sea- conditions render winter gage readings impracticable.

0 feet below the bridge a small temporary diversion dam is placed in the stream · for the greater part of the low-water season to divert water into an irrigation ıe left bank. This weir backs the water up on the gage to a considerable depth ıitates the construction of a separate rating curve for this period.

ge measurements are made from the downstream side of the three-span bridge to gage is attached. The initial point for soundings is immediately over the inner · left abutment and is marked with a circle on the downstream hand rail.

e, which was read twice each day during 1905 by J. N. Ostrander, a civil engineer, but a few hundred feet away, is a staff, spiked vertically to the downstream inner · first pier from the left bank. The gage reads from 2 feet to 10.8 feet, the 2-foot *ng on the bed of the stream.* The gage is referred to bench marks as follows.

(1) A nail in the top of the white-pine stake driven into the left bank about 30 feet south of the left end of the bridge, projecting about 6 inches above the surface of the ground, and marked "U. S. G. S. B. M.;" elevation, 13.12 feet above the zero of the gage. (2) A cross cut on the top of the foundation stone at the southeast corner of the residence of the observer. The stone is marked "U. S. B. M." on the east face; elevation, 13.09 feet above the zero of the gage.

Discharge measurements of Fraser River near Granby, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 3	W. A. Lamb	53	122	2.16	5.10	263
May 30	do	58	168	4.03	5.70	677
June 11	do	68	192	5.70	6.20	1,095
June 30	do	54	145	3.41	5.50	495
July 8	do	56	149	2.03	5.50	303
July 26	do	52	118	1.40	5.01	165
August 2	do	50	118	1.38	5.05	163
August 16	do	44	94	1.06	4.75	100
September 9 [a]	do	42	61	1.26	4.60	77
October 2 [a]	do	39	60	1.17	4.60	70

[a] Made by wading above bridge.

Daily gage height, in feet, of Fraser River at Granby, Colo., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Day.	May.	June.	July.	Aug.	Sept.	Oct.
1		6.1	5.45	5.1	4.7	4.6	17	5.22	6.15	5.2	4.75	4.6	4.3
2		6.12	5.4	5.05	4.62	4.6	18	5.32	6.05	5.2	4.7	4.55	4.3
3		6.22	5.35	5.0	4.6	4.55	19	5.42	5.9	5.15	4.65	4.55	4.3
4		6.55	5.3	4.96	4.6	4.5	20	5.48	5.85	5.25	4.65	4.5	4.3
5		6.65	5.25	4.9	4.7	4.5	21	5.55	5.85	5.25	4.62	4.5	4.3
6		6.4	5.25	4.9	4.7	4.5	22	5.69	5.85	5.15	4.6	4.5	4.3
7	4.88	6.5	5.15	4.9	4.7	4.5	23	5.88	5.85	5.1	4.6	4.5	4.3
8	5.08	6.5	5.3	4.85	4.72	4.5	24	5.78	5.8	5.12	4.62	4.5	4.3
9	5.15	6.6	5.5	4.82	4.6	4.5	25	5.65	5.72	5.08	4.62	4.5	4.3
10	4.98	6.42	5.4	4.8	4.6	4.42	26	5.68	5.75	5.05	4.65	4.45	4.3
11	4.92	6.35	5.35	4.92	4.6	4.4	27	5.78	5.7	5.0	4.65	4.45	4.3
12	4.9	6.3	5.3	5.05	4.6	4.35	28	5.9	5.58	4.98	4.65	4.4	4.3
13	5.02	6.35	5.28	4.95	4.6	4.35	29	5.72	5.55	5.0	4.7	4.5	4.3
14	4.92	6.3	5.3	4.88	4.6	4.35	30	5.72	5.5	5.1	4.7	4.5	4.3
15	4.9	6.35	5.3	4.82	4.6	4.3	31	5.78		5.1	4.65		4.3
16	5.05	6.35	5.3	4.75	4.6	4.3							

Station rating table for Fraser River at Granby, Colo., from January 1 to July 8, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.90	180	5.40	431	5.90	819	6.40	1,313
5.00	218	5.50	499	6.00	910	6.50	1,422
5.10	262	5.60	572	6.10	1,005	6.60	1,533
5.20	313	5.70	649	6.20	1,104		
5.30	369	5.80	732	6.30	1,207		

NOTE.—The above table is applicable only for open-channel conditions. It is based on measurements made during 1904-5 and is well defined.

m rating table for Fraser River at Granby, Colo., from July 9 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.20	26	4.60	74	5.00	154	5.40	267
4.30	35	4.70	91	5.10	179	5.50	302
4.40	46	4.80	110	5.20	206		
4.50	59	4.90	131	5.30	235		

—The above table is applicable only for open-channel conditions. It is based on discharge nents made during 1905. It is well defined between gage heights 4.6 feet and 5.5 feet. This sec- is necessary on account of a dam which was put in a short distance below the gage.

Estimated monthly discharge of Fraser River at Granby, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	819	172	451	22,360
.....	1,590	499	1,030	61,290
.....	465	149	250	15,370
.....	179	74	110	6,764
er.....	95	46	70.1	4,171
.....	74	30	47	2,890
e period.....				112,800

WILLIAMS FORK DRAINAGE BASIN.

WILLIAMS FORK NEAR HOT SULPHUR SPRINGS, COLO.

ams Fork rises in the Williams River Mountains in southeastern Grand County, a general northwesterly direction, and unites with Grand River in the central part lle Park, Colorado.

gaging station was established July 25, 1904. It is located at the wagon bridge on ch of F. A. Field, in T. 1 N., R. 79 W., about 9 miles west of Hot Sulphur Springs, 4 bove the mouth of the stream, and below all the tributaries.

channel is straight for about 100 feet above and below the station. The right bank r gravel bar, lined with willows, and at extreme high stages is overflowed for a dis- f 75 feet from the second channel. The left bank is a level pasture land, about 4 gh, and is not liable to overflow. The bed of the stream is composed of small and n-sized bowlders and is permanent. At low water there is but one channel; at high a second channel begins about 300 feet above the bridge, on the right side of the , passes about 100 feet from the right end of the bridge, and enters the main stream t below. This channel is very rough and irregular and is almost entirely covered ass and shrubbery. The current is swift at high and medium at low stages. Gage have a range of about 1.8 feet in an ordinary season. During the winter months ructs the channel to such an extent as to make gage readings impracticable. High- neasurements are affected by the back water and boiling caused by the middle pier ridge and by the roughness of bed of the second channel.

large measurements are made from the downstream side of the 2-span wooden to which the gage is attached. The initial point for soundings is a 60-penny nail into the top of the left end of the downstream guard rail of the bridge, immediately e inside face of the abutment. The second channel formed at high water is meas- wading at convenient points.

gage, which was read twice each day during 1905 by F. A. Field, is a staff, graduated to 8 feet, fastened vertically to the downstream end of the middle crib pier, the 2-foot *sting on the bed of the stream.* The bench mark is a 60-penny nail driven into the

south face of a white-pine tree standing on the left bank of the river 30 feet north of t west end of the bridge; elevation, 6.03 feet above the zero of the gage. Elevation abo sea level is about 7,600 feet.

A description of this station, with gage-height and discharge data, is contained in Wat Supply Paper No. 133, United States Geological Survey, pages 146–148.

Discharge measurements of Williams Fork near Hot Sulphur Springs, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis char
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.*
May 2	W. A. Lamb	50	85	2.73	3.89	
May 8	do	44	74	2.26	3.70	
May 29	do	54	103	3.65	4.15	
June 5	do	66	157	5.39	4.85	
June 8	do	64	147	5.60	4.80	
June 29	do	47	99	3.90	4.20	
July 12	do	48	91	2.36	3.85	
July 24	do	43	73	1.89	3.61	
August 29	do	33	54	1.13	3.31	
September 8	do	33	54	1.19	3.30	
September 29	do	25	44	1.11	3.23	

Daily gage height, in feet, of Williams Fork near Hot Sulphur Springs, Colo., for 190

Day.	Apr.	May.	June.	July.	Aug.	Sept.
1	3.19	3.84	4.39	4.18	3.58	3.33
2	3.14	3.88	4.48	4.11	3.52	3.29
3	3.12	3.80	4.55	4.09	3.51	3.3.
4	3.13	3.70	4.72	4.02	3.52	3.30
5	3.18	3.62	4.82	3.98	3.50	3.31
6	3.20	3.57	4.72	3.94	3.51	3.34
7	3.24	3.63	4.82	3.90	3.50	3.34
8	3.25	3.71	4.78	3.90	3.50	3.30
9	3.32	3.74	4.89	3.89	3.48	3.29
10	3.36	3.65	4.80	3.84	3.49	3.28
11	3.34	3.62	4.68	3.84	3.50	3.28
12	3.36	3.60	4.68	3.82	3.52	3.26
13	3.40	3.71	4.74	3.80	3.50	3.26
14	3.34	3.63	4.68	3.81	3.48	3.25
15	3.28	3.60	4.70	3.80	3.46	3.22
16	3.30	3.69	4.68	3.76	3.40	3.21
17	3.30	3.84	4.65	3.71	3.40	3.26
18	3.38	3.92	4.55	3.70	3.38	3.29
19	3.44	3.98	4.52	3.76	3.39	3.36
20	3.38	4.05	4.45	3.76	3.35	3.30
21	3.32	4.05	4.46	3.72	3.34	3.30
22	3.39	4.15	4.42	3.71	3.36	3.28
23	3.39	4.22	4.40	3.64	3.38	3.28
24	3.42	4.22	4.43	3.62	3.36	3.24
25	3.42	4.18	4.34	3.61	3.31	3.24
26	3.45	4.18	4.36	3.61	3.30	3.26
27	3.56	4.25	4.28	3.62	3.28	3.26
28	3.62	4.24	4.25	3.60	3.28	3.23
29	3.66	4.12	4.21	3.58	3.37	
30	3.78	4.18	4.17	3.58	3.	
31		4.31		3.58		

Station rating table for Williams Fork near Hot Sulphur Springs, Colo., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.10	25	3.60	130	4.10	335	4.60	650
3.20	40	3.70	160	4.20	390	4.70	730
3.30	60	3.80	200	4.30	450	4.80	810
3.40	80	3.90	240	4.40	510	4.90	900
3.50	105	4.00	285	4.50	580		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–1905 and is well defined.

Estimated monthly discharge of Williams Fork near Hot Sulphur Springs, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
April	192	28	74.1	4,409
May	456	122	253	15,560
June	891	374	628	37,370
July	379	125	201	12,360
August	125	56	87.6	5,386
September	76	42	56.5	3,362
October	64	25	46.6	2,865
The period				81,310

TROUBLESOME RIVER DRAINAGE BASIN.

TROUBLESOME RIVER AT TROUBLESOME, COLO.

Troublesome River rises among the peaks of the Continental Divide in the northern part of Grand County, Colo., and flows southward to its point of junction with Grand River in Middle Park.

The gaging station was established July 22, 1904. It is located about 100 yards below the highway bridge at Troublesome, Colo., in sec. 12, T. 1 N., R. 80 W.

The channel is straight for about 50 feet above and 100 feet below the station. The right bank is about 3 feet high and is lined with a heavy growth of willows; the left bank is precipitous, is about 4 feet high, and is bordered by a level meadow; neither bank overflows. The bed of the stream is composed of small cobblestones and gravel, and is clean, uniform, and permanent. There is but one channel, broken by the piers of the bridge, which form eddies and undercurrents in a portion of the cross section. The current is very swift at high and medium at low stages. Gage heights have a range of about 2.5 feet in an ordinary season. During the winter months the channel is so obstructed by ice as to make gage readings impracticable.

Discharge measurements are ordinarily made by wading at convenient points near the gage rod. At extremely high stages they are made from the 2-span bridge about 100 yards above the gage-rod. The initial point for soundings is the west face of the stake driven into the top of the left bank, to which the gage rod is fastened.

The gage, which was read twice each day during 1905 by Mrs. Eva M. Becker, is an inclined staff, graduated from 0.8 foot to 5.8 feet, securely fastened to stakes driven into the left bank and bed of the stream. One vertical foot equals 1.525 feet on the slope. The gage is referred to bench marks as follows: (1) A 10-penny nail driven into the top of the stake on the left bank to which the gage is fastened; elevation, 5.83 feet above the zero of the gage.

(2) The center of a black cross painted on the bottom log near the southeast corner of Mrs. E. M. Becker's house, marked "U. S.+B. M.;" elevation, 16.08 feet above the zero of the gage.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 133, United States Geological Survey, pp. 148–150.

Discharge measurements of Troublesome River at Troublesome, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 29	W. A. Lamb	30	39	2.28	2.57	9
May 8	do	31	45	2.71	2.72	12
May 28	do	42	95	4.73	3.40	44
June 5	do	43	108	5.32	3.70	57
June 8	do	40	93	5.14	3.35	47
June 29	do	26	36	1.64	1.75	5
July 11	do	16	9.3	0.86	1.12	8
July 24	do	18	19	0.58	1.18	11
August 13	do	23	25	0.88	1.38	22
August 27	do	22	23	0.83	1.34	19
September 7	do	24	25	0.92	1.40	23
September 29	do	23	23	0.87	1.35	20

NOTE.—Measurements made at different sections.

Daily gage height, in feet, of Troublesome River at Troublesome, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	2.0	2.8	3.3	1.6	1.48	1.35	1.32
2	2.0	2.95	3.4	1.65	1.38	1.3	1.3
3	1.95	2.82	3.45	1.68	1.35	1.3	1.3
4	1.9	2.7	3.75	1.6	1.35	1.3	1.3
5	1.95	2.6	3.7	1.52	1.3	1.35	1.25
6	2.1	2.52	3.18	1.42	1.35	1.38	1.22
7	2.1	2.5	3.32	1.3	1.3	1.4	1.2
8	2.1	2.55	3.28	1.18	1.3	1.38	1.2
9	2.1	2.82	3.22	1.15	1.3	1.35	1.2
10	2.1	2.75	3.12	1.12	1.3	1.35	1.28
11	2.15	2.72	2.88	1.1	1.32	1.35	1.25
12	2.1	2.6	2.75	1.08	1.38	1.35	1.38
13	2.1	2.62	2.78	1.05	1.38	1.3	1.4
14	2.1	2.6	2.75	1.02	1.35	1.3	1.4
15	2.05	2.62	2.58	1.08	1.35	1.3	1.4
16	2.1	2.8	2.55	1.05	1.35	1.29	1.42
17	2.1	3.15	2.42	1.05	1.32	1.28	1.45
18	2.1	3.28	2.32	0.95	1.32	1.3	1.42
19	2.15	3.52	2.25	1.0	1.3	1.35	1.38
20	2.15	.....	2.22	1.15	1.3	1.35	1.35
21	2.1	.....	2.15	1.32	1.32	1.35	1.3
22	2.15	.....	2.18	1.25	1.35	1.35	1.35
23	2.2	.....	2.08	1.2	1.35	1.32	1.4
24	2.2	.....	1.98	1.28	1.35	1.3	1.4
25	2.3	.....	1.95	1.3	1.35	1.3	1.4
26	2.25	.....	1.9	1.42	1.35	1.35	1.4
27	2.3	.....	1.8	1.4	1.35	1.35	1.4
28	2.42	3.35	1.72	1.35	1.35	1.35	1.4
29	2.5	3.25	1.7	1.4	1.35	1.35	1.4
30	2.55	3.2	1.68	1.4	1.35	1.3	1.42
31	.....	3.08	.....	1.42	1.35	.....	1.48

ı rating table for Troublesome River at Troublesome, Colo., from January 1 to May 19, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.90	14	2.40	63	2.90	167	3.40	322
2.00	21	2.50	78	3.00	196	3.50	357
2.10	29	2.60	96	3.10	226	3.60	392
2.20	39	2.70	117	3.20	257		
2.30	50	2.80	141	3.30	289		

ɛ.—The above table is applicable only for open-channel conditions. It is based on discharge ements made during 1904–1905. It is well defined between gage heights 1.9 feet and 2.7 feet.

ı rating table for Troublesome River at Troublesome, Colo., from May 20 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	5	1.80	68	2.60	229	3.40	475
1.10	7	1.90	84	2.70	255	3.50	510
1.20	10	2.00	102	2.80	282	3.60	546
1.30	15	2.10	121	2.90	311	3.70	584
1.40	22	2.20	141	3.00	342	3.80	623
1.50	31	2.30	162	3.10	374		
1.60	42	2.40	183	3.20	407		
1.70	54	2.50	205	3.30	441		

ɛ.—The above table is applicable only for open-channel conditions. It is based on 10 discharge rements made during 1905. It is well defined between gage heights 1.1 feet and 1.8 feet, and is ccurate to gage height 3.8 feet.

'stimated monthly discharge of Troublesome River at Troublesome, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	87	14	35.1	2,089
3 days.....	458	78	192	8,759
.....	604	52	259	15,410
.....	52	4.5	17.5	1,076
t.....	29	15	18.0	1,107
nber.....	22	14	17.3	1,029
er.....	39	10	19.1	1,174
The period.....	.....	.....	.....	30,640

MUDDY RIVER DRAINAGE BASIN.

MUDDY RIVER AT KREMMLING, COLO.

ıddy River rises among the high peaks in the northwestern part of Grand County, ., and flows southeastward to the point where it unites with Grand River.

ıe gaging station was established July 24, 1904. It is located at the highway bridge ıt one-eighth mile northwest of Kremmling, in sec. 7, T. 1 N., R. 80 W., about 2 miles ve the mouth of the river. The station is below all tributaries of importance.

The channel is curved for about 100 feet above and straight for 50 feet below the stati
The right bank is about 8 feet high above and 10 feet high below the station, and is d
and almost perpendicular. The left bank below the bridge is 10 feet high, slopes at an a
of about 45 degrees, and is lined with willows; above the bridge it is irregular and abo
feet high. The stream at this point does not overflow except at extremely high stages,
then only for a short distance back from the left bank. The bed of the stream is comp
of mud, with some sand and a few loose rocks washed from the riprap near the south a
ment of the bridge, and is clean but shifting. There is but one channel at all stages, bu
by the middle pier of the bridge, which is irregularly shaped and causes back water
undercurrents in a portion of the cross section, affecting the discharge measurement
high stages. The current is medium at high and very sluggish at low water. The shi
of the bed makes it very difficult to obtain a good rating curve. Gage heights have a r
of about 6 feet during an ordinary season. In the winter months ice obstructs the ch
to such an extent that gage readings are impracticable.

At high-water stages discharge measurements are made from the downstream side o
two-span highway bridge to which the gage is attached. The initial point for soun
is a 10-penny nail driven into the downstream hand rail over the north face of the left
ment. The hand rail is marked from 0 to 58 feet with nails driven at 2-foot intervals.
ordinary and low-water stages measurements are made by wading at convenient p
below the station.

The gage, which was read twice each day during 1905 by C. S. McGee, is a staff attu
vertically to the lower left corner of the middle pier of the bridge. The gage reads fr
to 14 feet, the 2-foot mark resting on the bed of the stream. The gage is referred to l
marks as follows: (1) A 60-penny spike driven horizontally into the west face of th
end of the downstream bridge stringer over the left abutment; elevation, 13.65 feet
the zero of the gage. (2) A 30-penny nail driven horizontally in the stringer at the
end of the north abutment of the bridge; elevation, 13.95 feet above the zero of the

A description of this station with gage height and discharge data is contained in W
Supply Paper No. 133, United States Geological Survey, pp. 150–151.

Discharge measurements of Muddy River at Kremmling, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	I ch
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*S*
April 28	Wm. A. Lamb	42	99	1.75	6.32	
May 8	do	41	140	1.81	6.90	
May 27	do	49	338	1.98	9.95	
June 7	do	48	354	1.90	10.10	
June 15	do	49	264	1.32	8.38	
June 26	do	52	66	1.18	6.35	
July 11	do	14	11	1.45	4.61	
July 24	do	11	6.6	.95	4.30	
August 12	do	12	7.0	1.44	4.45	
August 25	do	9	4.0	.72	4.10	
September 7	do	10	5.2	1.21	4.25	
September 29	do	10	5.6	1.02	4.25	

NOTE.—Measurements made at different sections.

Daily gage height, in feet, of Muddy River at Kremmling, Colo., for 1905.

Day	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
.....	7.35	6.9	8.9	5.55	4.7	4.1	4.4
.....	7.3	7.32	9.35	5.15	4.6	4.0	4.4
.....	6.82	7.5	9.5	5.15	4.6	4.05	4.4
.....	6.68	7.2	10.15	5.1	4.6	4.1	4.4
.....	6.35	7.05	10.0	5.0	4.6	4.1	4.4
.....	6.38	6.4	9.45	5.0	4.5	4.2	4.4
.....	6.3	6.45	9.55	4.7	4.5	4.2	4.4
.....	6.35	6.65	9.55	4.6	4.5	4.2	4.4
.....	6.25	7.3	10.1	4.6	4.5	4.2	4.4
.....	6.1	7.35	10.15	4.5	4.5	4.0	4.4
.....	5.9	6.9	9.45	4.5	4.55	4.0	4.3
.....	5.6	6.6	8.9	4.5	4.3	4.0	4.3
.....	5.25	6.7	8.65	4.5	4.25	4.0	4.3
.....	5.1	6.75	8.75	4.4	4.3	4.0	4.3
.....	5.0	6.65	8.4	4.3	4.3	4.0	4.3
.....	5.15	7.0	8.15	4.4	4.3	4.0	4.3
.....	5.18	8.1	7.95	4.4	4.2	4.0	4.3
.....	5.2	8.3	7.45	4.4	4.2	4.0	4.3
.....	5.25	9.15	7.3	4.35	4.2	4.0	4.4
.....	5.05	9.6	7.05	4.3	4.1	4.0	4.4
.....	5.02	9.5	6.9	4.3	4.1	4.0	4.4
.....	4.95	9.75	6.75	4.3	4.1	4.0	4.4
.....	5.1	10.1	6.65	4.3	4.1	4.0	4.4
.....	5.25	10.65	6.5	4.3	4.1	3.7	4.4
.....	5.18	9.85	6.35	4.3	4.1	3.7	4.4
.....	5.3	9.45	6.25	4.3	4.1	4.0	4.5
.....	5.38	9.35	6.1	4.3	4.1	4.0	4.5
.....	5.9	9.45	6.05	4.3	4.1	4.0	4.5
.....	6.25	8.9	5.95	4.85	4.1	4.2	4.5
.....	6.48	8.55	5.7	4.7	4.1	4.3	4.4
.....	.....	8.6	.....	4.7	4.1	.....	4.4

n rating table for Muddy River at Kremmling, Colo., from July 25, 1904, to June 4, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.20	5	5.50	85	6.70	223	7.90	380
4.30	8	5.60	95	6.80	236	8.00	394
4.40	11	5.70	105	6.90	249	8.20	422
4.50	15	5.80	116	7.00	262	8.40	450
4.60	19	5.90	127	7.10	275	8.60	478
4.70	24	6.00	138	7.20	288	8.80	506
4.80	29	6.10	150	7.30	301	9.00	534
4.90	35	6.20	162	7.40	314	9.20	562
5.00	42	6.30	174	7.50	327	9.40	590
5.10	50	6.40	186	7.60	340	9.60	618
5.20	58	6.50	198	7.70	353	9.80	646
5.30	67	6.60	210	7.80	366	10.00	674
5.40	76						

E.—The above table is applicable only for open-channel conditions. It is based on discharge rements made during 1904–5 and is well defined. Above gage height 10 feet the rating curve is a lt, *the difference being 15 per tenth.*

Station rating table for Muddy River at Kremmling, Colo., from June 5 to December 31, 1905

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.00	2	5.20	31	6.40	90	8.20	309
4.10	3	5.30	34	6.50	98	8.40	341
4.20	5	5.40	38	6.60	106	8.60	374
4.30	7	5.50	42	6.70	115	8.80	409
4.40	9	5.60	46	6.80	125	9.00	445
4.50	11	5.70	50	6.90	136	9.20	483
4.60	13	5.80	54	7.00	147	9.40	523
4.70	16	5.90	59	7.20	171	9.60	564
4.80	19	6.00	64	7.40	195	9.80	606
4.90	22	6.10	70	7.60	221	10.00	649
5.00	25	6.20	76	7.80	249	10.15	682
5.10	28	6.30	83	8.00	278		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1905 and it is not well defined.

Estimated monthly discharge of Muddy River at Kremmling, Colo., for 1904.

Month.	Discharge in second-feet.			Total acre-
	Maximum.	Minimum.	Mean.	
July 25-31	8	5.6	6.9	
August	29	5	11.4	
September	36.4	5	14.8	
October	19	8	13	

Estimated monthly discharge of Muddy River at Kremmling, Colo., for 1905.

Month.	Discharge in second-feet.			Total acre-
	Maximum.	Minimum.	Mean.	
April	308	38	121	
May	772	186	408	
June	606	50	337	
July	44	7	14	
August	16	3	7.1	
September	7	.5	2.7	
October	11	7	8.7	
The period				

BLUE RIVER DRAINAGE BASIN.

BLUE RIVER NEAR KREMMLING, COLO.

Blue River rises among the peaks of the Continental Divide in the extreme southe part of Summit County, Colo., and flows in a general northwesterly direction until i Grand River above the point where the latter stream enters Gore Canyon.

The gaging station was established July 21, 1904. It is located at the bridge on the road between Kremmling and Dillon, Colo., 17 miles from miles from the latter, in T. 2 S., R. 80 W., and is below all tribute

channel is straight for about 400 feet above and 200 feet below the station. The are lined with willows and are not liable to overflow. The bed of the stream is very but is clean and stable. There is but one channel at all stages, broken by the center the bridge. Several large bowlders in the channel near the gaging section cause a and boiling motion of the water at high stages and eddies and dead water during ages. Gage heights have a range in an ordinary season of about 2.5 feet. During nter months ice forms in the channel to such an extent as to make gage readings ticable.

harge measurements are made from the downstream side of the two-span iron bridge ch the gage is attached. The initial point for soundings is a 4-penny nail driven e downstream guard rail at the left end of the bridge immediately over the east face left abutment. It is marked zero.

gage at this station is read once each day by Mrs. Dolly Heatherly, who lives 1 mile of the bridge. The original gage was a staff, graduated from 2 to 11 feet, fastened lly to the west face of the middle masonry pier near the downstream end. On t 26, 1904, this gage was removed and was replaced by a regulation chain gage, the on of the datum of the two gages being the same. In September, 1905, the wooden as reset in its original position and datum and is to be used during season of high water; other times the chain gage is to be used. The gage is referred to bench marks as s: (1) A cross cut in the top of the second step from the top of the downstream wing left abutment, painted black, and marked "U. S.+B. M."; elevation, 9.04 feet above ro of the gage. (2) A 60-penny spike driven vertically into the west end of the to which the pulley of the gage is fastened; elevation, 11.69 feet above the zero of ge.

scription of this station, with gage height and discharge data, is contained in Water- r Paper No. 133, United States Geological Survey, pages 151–153.

Discharge measurements of Blue River near Kremmling, Colo., in 1905.

ate.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec. ft.*
a	W. A. Lamb	108	151	2.29	2.50	346
	do	131	210	2.80	2.90	589
	do	147	371	5.01	3.50	1,860
	do	166	541	6.06	4.60	3,276
	do	151	382	4.53	3.45	1,732
	do	139	236	2.97	3.12	702
12	do	125	212	2.70	2.82	572
26	do	118	182	2.30	2.58	420
ber 6	do	115	182	2.43	2.59	422
ber 13	do	110	151	1.88	2.45	284
ber 28	do	99	125	1.69	2.30	211

[a] Channel partly filled with ice along sides and piers.

Daily gage height, in feet, of Blue River near Kremmling, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
		2.9	3.95	3.4	2.85	2.7	2.2	2.15	2.2
		3.0	4.0	3.4	2.8	2.5	2.3	2.15	2.0
		2.9	4.1	3.4	2.75	2.45	2.3	2.2	2.1
		2.95	4.2	3.2	2.7	2.5	2.25	2.3	2.0
	2.1	2.8	4.3	3.1	2.7	2.5	2.2	2.25	1.7
	2.1	2.6	4.0	3.1	2.7	2.5	2.25	2.25	1.7

Daily gage height, in feet, of Blue River near Kremmling, Colo., for 1905—Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
7	2.2	2.65	4.1	3.0	2.7	2.5	2.25	2.25	2.0
8	2.2	2.8	4.15	3.0	2.7	2.5	2.25	2.2	2.2
9	2.25	2.9	4.45	3.0	2.6	2.45	2.2	2.15	2.3
10	2.3	3.0	4.0	2.9	2.6	2.3	2.2	2.1	.....
11	2.3	2.8	4.0	2.9	2.6	2.3	2.15	2.2	.....
12	2.3	2.75	3.95	2.9	2.6	2.3	2.1	2.2	.....
13	2.3	2.95	4.05	2.9	2.7	2.3	2.2	2.2	.....
14	2.35	2.8	3.95	2.8	2.6	2.3	2.2	2.2	.....
15	2.2	2.7	4.0	2.95	2.6	2.3	2.2	2.2	.....
16	2.3	2.7	3.95	2.9	2.6	2.25	2.2	2.15	.....
17	2.3	2.9	4.0	2.9	2.5	2.2	2.25	2.1	.....
18	2.35	3.05	3.75	2.8	2.5	2.25	2.25	2.15	.....
19	2.5	3.6	3.65	2.85	2.45	2.3	2.2	2.1	.....
20	2.4	3.65	3.65	2.8	2.45	2.3	2.2	2.15	.....
21	2.35	3.65	3.55	2.8	2.45	2.3	2.3	2.3	.....
22	2.4	3.55	3.5	2.85	2.4	2.3	2.25	2.2	.....
23	2.35	3.75	3.7	2.8	2.4	2.3	2.25	2.1	.....
24	2.4	3.65	3.75	2.8	2.4	2.25	2.25	2.1	.....
25	2.4	3.6	3.55	2.85	2.45	2.3	2.25	2.2	.....
26	2.4	3.5	3.65	2.9	2.5	2.3	2.3	2.1	.....
27	2.5	3.6	3.55	2.85	2.45	2.3	2.3	2.2	.....
28	2.6	3.55	3.55	2.8	2.45	2.25	2.3	2.15	.....
29	2.65	3.6	3.45	2.8	2.5	2.2	2.25	2.0	.....
30	2.8	3.65	3.4	2.8	2.5	2.2	2.2	2.0	.....
31	.....	3.7	.....	2.8	2.65	.....	2.2	.....	.....

EAGLE RIVER DRAINAGE BASIN.

EAGLE RIVER NEAR EAGLE, COLO.

Eagle River, an important headwater tributary of Grand River, rises among the high peaks of the Continental Divide, in Eagle County, Colo., immediately opposite the headwaters of Arkansas River, flows a little north of west for about 20 miles, and then in a general westerly direction to its junction with the Grand. It is a very rapid stream throughout its entire course, flowing alternately through canyons and narrow, terraced valleys.

The drainage area is almost wholly in Eagle County. The upper third of the basin is entirely mountainous, the general elevation at the crest of the divide being 12,000 feet above sea level, with peaks over 14,000 feet in altitude. In this part of its course the river descends in falls and cascades, the average slope above the mouth of Roche Moutonnée Creek being 150 feet per mile. The rocks are about equally divided between metamorphic granites and sedimentary formations. The forest cover is excellent, soil is shallow, and erosion is small. The annual precipitation, which is mostly in the form of snow, varies from 20 to 30 inches. This portion of the basin furnishes 90 per cent of the discharge of the stream.

The lower two-thirds of the basin is also mountainous but is less accentuated, the elevations varying from 7,000 to 11,000 feet. The rocks are largely sedimentary, erosion is greater, and the forest cover is meager. The precipitation is approximately 20 inches.

The principal tributaries of the Eagle are Gore, Roche Moutonnée, Gypsum, and Brush creeks.

Below Wolcott a few small ditches divert water for irrigation of the narrow first bench lands, and there is enough irrigation in Gypsum and Brush Creek valleys to divert the entire flow during the latter part of the season.

e gaging station was established March 12, 1905. It is located at Rule's private road e, in T. 5 S., R. 85 W., 2½ miles below Eagle, Colo. The chief object of the station is ollection of power data.

e channel is straight for 250 feet above and 150 feet below the station. The right bank h, is composed of bowlders, cobblestones, and gravel, and does not overflow; the left , a long, narrow bottom bordered by abrupt mesa bluffs, overflows at high water to of bluffs. Both banks are covered with scattered trees and brush. The bed of the m is composed of cobblestones and bowlders and is permanent but very rough. There one channel at all stages. At low water there is an area of dead water at the left abut- , due to a depression in the bed of the stream under the bridge, and the current is slug- at high water this area of dead water disappears. The center of the current is very during high water. Above and below the bridge the velocity is much greater than at ridge. The height of water ranges from 0.8 foot to 6 feet on the gage. Ice forms over hannel under the bridge during cold weather.

scharge measurements are made from the downstream side of the 66-foot single-span en bridge, which stands at right angles to the stream current. The initial point for lings is the face of the left abutment.

vertical staff gage, which was read twice each day during 1905 by Kenneth Rule, is d to the face of the left abutment of the bridge. The gage is graduated from zero to 10 The bench mark is a point encircled by paint and marked "B.M." on a large bowlder right of the bridge; elevation, 15.72 feet above the zero of the gage.

Discharge measurements of Eagle River near Eagle, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
18.....	R. I. Meeker.....	40	119	1.57	0.80	187
2.....	.....do.....	50	207	3.55	2.20	735
0.....	.....do.....	45	233	3.41	2.40	794
st 15[a].....	.....do.....	45	202	2.01	1.55	406
mber 25[a].....	.....do.....	60	162	1.22	1.00	198

[a] Made from Eagle bridge.

Daily gage height, in feet, of Eagle River near Eagle, Colo., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	0.7	2.65	4.45	3.25	1.75	1.15	1.15	0.9	0.9
.....	.....	.8	3.0	4.7	3.05	1.7	1.05	1.15	.9	.95
.....	.....	.7	2.6	4.9	2.85	1.6	.95	1.15	1.0	.9
.....	.....	.65	2.35	5.8	2.65	1.65	1.25	1.05	.95	.8
.....	.....	.7	2.25	5.45	2.6	1.6	1.35	1.05	.95	.8
.....	.....	.7	2.9	5.35	2.6	1.6	1.35	1.05	.95	.8
.....	.....	.75	2.05	5.45	2.55	1.6	1.35	1.05	.9	.8
.....	.....	.9	2.25	5.45	2.6	1.6	1.45	1.05	.9	.9
.....	.....	1.0	2.5	5.65	2.4	1.65	1.4	1.0	.9	1.0
.....	.....	1.15	2.45	5.65	2.4	1.6	1.35	1.0	.9	1.2
.....	.....	1.15	2.25	5.15	2.35	1.7	1.3	1.0	.9	1.5
.....	.....	1.25	2.15	4.8	2.3	1.75	1.35	.95	.9	2.0
.....	.....	1.2	2.4	4.9	2.25	1.7	1.3	.95	.8	1.8
.....	.....	1.25	2.25	4.95	2.2	1.65	1.25	.9	.8	2.0
.....	.....	1.15	2.25	4.65	2.15	1.6	1.2	.9	.9	2.4
.....	.....	1.2	2.5	4.4	2.05	1.55	1.05	.95	.9	2.4
.....	.....	1.15	2.95	4.15	2.0	1.35	1.1	.95	.9	2.5

Daily gage height, in feet, of Eagle River near Eagle, Colo., for 1905—Continued.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
18	.....	1.2	3.25	4.2	1.85	1.3	1.1	0.95	0.9	
19	0.8	1.4	3.55	3.9	1.85	1.15	1.1	.9	.9	
20	.8	1.35	3.75	3.85	1.8	1.15	1.0	.95	.9	
21	.7	1.25	3.85	3.95	1.75	1.1	1.0	.95	.9	
22	.75	1.3	4.2	3.7	1.7	1.0	1.05	.9	.9	
23	.7	1.3	4.5	3.8	1.7	1.0	1.0	.9	.9	
24	.65	1.4	4.5	3.85	1.7	.95	1.0	.9	.9	
25	.7	1.4	4.1	3.75	1.7	1.0	1.0	.9	.9	....
26	.7	1.35	4.15	3.8	1.7	1.0	1.0	.9	.9	....
27	.78	1.5	4.25	3.7	1.65	1.05	1.0	.95	.9	....
28	.7	1.75	4.2	3.7	1.75	1.05	1.0	1.0	.9	..
29	.65	2.2	3.9	3.45	1.8	1.15	1.15	1.0	.9	...
30	.7	2.35	3.9	3.4	1.7	1.25	1.2	1.1	.9	...
31	.7	.....	4.4	.....	1.7	1.3	.....	1.1	.....	

GUNNISON RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Gunnison River is formed in Gunnison County, Colo., by the union of East and T rivers, two streams that have their origin among the snow-covered peaks and on the s of the Continental Divide in the northeastern part of the county and which descend thr narrow mountain valleys and unite about 12 miles above Gunnison. From the junct these rivers the Gunnison flows west and southwest to the point where it enters Grand l at Grand Junction, in the central part of Mesa County, Colo.

The upper course of the river lies through a broad, mountainous valley, but nea mouth of Lake Fork the valley narrows and the river enters the Black Canyon of the G son, through which it winds in a tortuous course for 56 miles between granite walls tha precipitously 3,000 feet above the water's edge. A short distance below the mou North Fork, the largest tributary of the river, the canyon walls break abruptly, an valley is broad and fertile. Below Delta the river enters another narrow canyon, with averaging 800 feet in height, and this continues irregularly to Grand Junction, a few t of narrow bottom land lying between the channel and the canyon walls.

As an aid to description the basin may be divided into an upper, mountainous area lower, plateau area, the two being divided roughly by a north-south line drawn throug town of Hotchkiss.

The mountainous portion of the basin is the greater in area and varies in altitude 6,000 to 14,000 feet. The geologic formations include large areas of igneous as well as mentary rocks, the soil cover is shallow, and large tracts are entirely barren. In the inaccessible parts of the region the primeval forest still exists, but at many places, espe in the neighborhood of the mining camps, the timber has all been cut off. The prev forests are spruce, aspen, cedar, and characteristic mountain undergrowth. All the a land in the high mountain valleys is devoted to forage crops, and a number of small di divert water for their irrigation. Power development of considerable magnitude is fe in this part of the basin.

The plateau region embraces the Uncompahgre Plateau along the southwestern bor the basin, the Vernal and Inclinado mesas in the central part, and the Grand Mesa i northern part. These plateaus have an extreme elevation of 10,000 feet above sea leve break down in a series of broad steps to the valleys, with parallel drainag deeply at right angles through these steps. The topography is the produc on sedimentary formations. The soil of the lower valleys is chiefly ad

mesas have large content of gravel and sand. Groves of quaking aspen, interspersed with large, open grazing plots, cover broad areas of this plateau region. Forests of pine and aspen occur on the top of the Grand Mesa, with pinon pines and cedars along the foothills. In the valleys chico and sagebrush form the controlling vegetation, except along the streams, which are bordered to some extent by cottonwood, willow, and undergrowth.

The chief tributaries of the Gunnison are Ohio, Tomichi, Lake Fork, and Cimarron creeks and Smith, North Fork, and Uncompahgre rivers, the North Fork being the largest.

North Fork River rises in the Huntsman Hills, 20 miles south of Glenwood Springs, flows in a general south and southwesterly course, and unites with the Gunnison about 8 miles west of Hotchkiss. The drainage area is highly mountainous, except for a small portion which lies below Paonia, extreme points reaching an altitude of 13,000 feet. The mesa lands at the lower end of the valley stand 5,500 feet above sea level. The higher peaks are formed of granitic rocks, but lower down Cretaceous formations occupy at least 80 per cent of the area of the basin. The mountains are forested and the mesa lands are covered with sagebrush. All the tillable lands of the North Fork and its tributaries have been brought under cultivation, and irrigation is practiced to such an extent that the entire flow is needed for existing systems.

Uncompahgre River, the principal tributary of the Gunnison from the south, rises among the snowy peaks of the highly serrated Uncompahgre Mountains and flows a little west of north to its junction with the Gunnison at Delta. The basin embraces a mountainous, plateau, and valley area of 1,130 square miles, oblong in shape, the width increasing slightly at the lower end. The mountain area occupies but a small part of the basin, but contributes the perennial waters of the stream. The plateau area is greatest in extent and borders the valley on both sides, the larger Uncompahgre Plateau lying to the southwest. Escarpments are conspicuous features of this plateau. The relief features are terraced mesas flanked by shale buttes and ridges, trenched by deep, narrow canyons. Uncompahgre Valley proper begins at a point near Eldredge Siding, on the Denver and Rio Grande Railroad.

The other tributaries of the Gunnison need not here be described. Ohio, Tomichi, Lake Fork, and Cimarron creeks are perennial streams, but almost their entire volume is diverted for irrigation during the growing season, so that very little of their water reaches the Gunnison except at times of heavy storms or during spring floods.

Precipitation records for the Gunnison basin are meager. Those which exist show a range from 9 inches in the plateau region to about 25 inches in the mountains.

The natural flow of the Uncompahgre and North Fork rivers is diverted for irrigation along their respective valleys, and the Gunnison tunnel will divert water from the mountainous area and transmit it to the Uncompahgre Valley, which has been an irrigated district since the early eighties.

EAST RIVER AT ALMONT, COLO.

East River rises in the Elk Mountains in the northern part of Gunnison County, Colo., flows in a general southerly direction, and unites with Taylor River to form the Gunnison.

The gaging station was established April 17, 1905. It is located at the county highway bridge at Almont, 100 feet above Taylor River, in T. 51 N., R. 85 W. The object of the station is the determination of the amount of flood waters available for storage in connection with the Uncompahgre Valley project and the collection of power data.

The channel section measures 75 feet between the bridge abutments and is straight for 100 feet both above and below the station. The banks are low and are liable to overflow at extreme high water. The bed of the stream is composed of bowlders and cobblestones and is very rough but generally permanent. There are two channels at all stages, divided by the center pier of the bridge, and the current is swift. Gage heights range from 0.7 foot to 5 feet.

Discharge measurements are made from the downstream side of the two-span wooden bridge. The initial point for soundings is the face of the left abutment and is indicated by a brass-headed tack in the hand rail, marked with a circle.

The gage, which was read during 1905 by Vernon Davis, is a vertical staff graduated from zero to 7 feet, spiked to the right end of the pier on the downstream side of the bridge. The bench mark is a point on a large stump in Cottage Grove on the right bank of the river, about 25 feet from the bridge, encircled by black paint and marked "B. M.;" elevation, 6.51 feet above the zero of the gage.

Discharge measurements of East River at Almont, Colo., in 1904 and 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
1904.		*Feet.*	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
June 14	R. I. Meeker	73	182	6.62	2.60	1,205
July 19	do	73	112	3.30	1.65	370
August 16	do	73	105	3.01	1.55	316
September 23	do	72	76	2.00	1.15	152
1905.						
April 15	do	58	75	2.53	0.80	190
May 26	A. A. Weiland	73	256	7.62	2.90	1,951
June 17	do	73	237	7.89	3.10	1,869
July 6	do	71	153	5.08	2.10	777
August 10	do	64	94	2.86	1.50	269
August 29	do	51	75	2.28	1.30	171

NOTE.—The 1904 measurements were made before the station was established. The gage heights were obtained from reference points.

Daily gage height, in feet, of East River at Almont, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	.....	1.75	3.25	2.35	1.9	1.3	1.0
2	.....	1.8	3.6	2.35	1.8	1.2	.9
3	.....	1.7	4.35	2.3	1.7	1.2	.9
4	.....	1.45	4.7	2.25	1.7	1.2	.9
5	.....	1.4	4.55	2.15	1.7	1.2	.9
6	.....	1.3	4.0	2.2	1.7	1.2	.9
7	.....	1.3	3.85	2.0	1.7	1.3	.9
8	.....	1.4	4.4	2.0	1.6	1.2	.9
9	.....	1.55	4.75	1.95	1.5	1.2	.....
10	.....	1.45	4.15	1.85	1.5	1.2	.....
11	.....	1.45	3.85	1.85	1.5	1.2	.....
12	.....	1.4	3.55	1.85	1.5	1.2	.....
13	.....	1.5	3.65	1.85	1.5	1.2	.....
14	.....	1.5	3.55	1.85	1.4	1.2	.....
15	.....	1.45	3.55	1.85	1.4	1.2	.....
16	0.8	1.7	3.35	1.85	1.4	1.1	.....
17	.75	1.9	2.95	1.85	1.4	1.1	.....
18	.8	2.05	2.9	1.85	1.4	1.1	.....
19	.9	2.45	2.7	1.8	1.4	1.1	.....
20	.85	2.6	2.4	1.7	1.4	1.0	.....
21	.8	2.75	2.55	1.8	1.4	1.0	.....
22	.9	2.85	2.4	1.7	1.4	1.0	.....
23	.85	3.3	2.5	1.7	1.4	1.0	.....
24	.85	3.15	2.6	1.7	1.5	1.0	.....
25	1.05	2.85	2.5	1.75	1.5	1.0	.....
26	1.0	3.1	2.45	1.7	1.4	1.0	.....
27	1.1	3.0	2.4	1.75	1.4	1.0	.....
28	1.2	2.75	2.4	1.7	1.4	1.0	.....
29	1.45	2.55	2.4	1.7	1.4	1.0	.....
30	1.65	2.5	2.35	1.8	1.4	1.0	.....
31	.....	2.85	.....	2.1	1.4	.....	.....

rating table for East River at Almont, Colo., from April 16 to June 1, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.80	190	1.50	420	2.20	850	2.90	1,610
0.90	210	1.60	470	2.30	940	3.00	1,750
1.00	240	1.70	520	2.40	1,030	3.10	1,900
1.10	270	1.80	580	2.50	1,130	3.20	2,060
1.20	300	1.90	640	2.60	1,240	3.30	2,220
1.30	340	2.00	700	2.70	1,360		
1.40	380	2.10	770	2.80	1,480		

:.—The above table is applicable only for open-channel conditions. It is based on discharge ements made during 1905. It is not well defined. Estimates based on this table are rough imations.

tation rating table for East River at Almont, Colo., from June 2 to October 8, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	80	2.00	610	3.00	1,750	4.00	3,430
1.10	110	2.10	700	3.10	1,900	4.10	3,620
1.20	140	2.20	790	3.20	2,050	4.20	3,810
1.30	180	2.30	890	3.30	2,210	4.30	4,000
1.40	220	2.40	990	3.40	2,370	4.40	4,190
1.50	270	2.50	1,100	3.50	2,540	4.50	4,380
1.60	330	2.60	1,220	3.60	2,710	4.60	4,570
1.70	390	2.70	1,340	3.70	2,890	4.70	4,770
1.80	460	2.80	1,470	3.80	3,070	4.80	4,970
1.90	530	2.90	1,610	3.90	3,250		

E.—The above table is applicable only for open-channel conditions. It is based on discharge rements made during 1904–1905, and is well defined between gage heights 1.3 feet and 3.1 feet.

Estimated monthly discharge of East River at Almont, Colo., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
16-30	495	180	249	7,408
	2,220	340	910	55,950
	4,870	940	2,329	138,600
	940	390	537	33,020
t	530	220	280	17,220
nber	180	80	117	6,962
er 1–8	80	60	62.5	992
The period				260,200

TAYLOR RIVER NEAR ALMONT, COLO.

ylor River rises in northeastern Gunnison County, Colo., among the high peaks of the ental Divide, flows in a general southwesterly direction, and unites with East River m the Gunnison.

e gaging station was established April 17, 1905. It is located at George Clark's private bridge, 14 miles above Almont, Colo., in T. 15 S., R. 83 W. The object of the station

is the determination of the amount of flood water available for storage in connection with the Uncompahgre Valley project, and the collection of power data.

The channel is straight for several hundred feet both above and below the station. The banks are both low, composed of bowlders and earth, are partly lined with willows, and are not liable to overflow. The stream bed is made up of large bowlders and cobblestones, and is very rough but permanent. The fall is large, the slope being equal to 0.016, or about 80 feet per mile. The crib piers of the bridge divide the channel into three parts. The velocity is rapid at all stages. Ice conditions interfere with measurements during the winter months. Accurate measurements are exceedingly hard to obtain on account of the roughness of the channel.

Discharge measurements are made from the downstream side of a pole bridge, which is 75 feet between abutments and is supported by two crib piers. The gage, which was read during 1905 by George Clark, is a vertical staff, graduated from zero to 7 feet, spiked to the left side of the left pier. The bench mark is a point, encircled with white paint and marked "B. M.," on top of a granite bowlder on the left bank just below the bridge; elevation above the zero of the gage, 4.34 feet.

Discharge measurements of Taylor River near Almont, Colo., in 1904 and 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
1904.		*Feet.*	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
June 15	R. I. Meeker	58	142	5.61	2.22	796
July 18	do	58	101	3.27	1.47	330
August 17	do	58	104	3.88	1.77	404
September 21	do	58	69	2.33	1.12	161
1905.						
April 17	R. I. Meeker	44	64	1.78	1.00	114
May 26	A. A. Weiland	58	173	5.76	2.60	996
June 17	do	58	174	5.86	2.60	1,044
July 6	do	58	130	3.32	1.70	432
August 10	do	58	100	2.27	1.20	227
August 29	do	58	99	2.03	1.10	201

NOTE.--The 1904 measurements were made before the station was established. The gage heights were obtained from reference points.

Daily gage height, in feet, of Taylor River near Almont, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1		2.1	3.4	1.9	1.45	1.1	1.1	1.0
2		1.8	3.55	1.85	1.35	1.1	1.1	1.0
3		1.35	3.75	1.75	1.4	1.1	1.1	1.0
4		1.3	4.15	1.75	1.4	1.1	1.1	1.0
5		1.25	4.25	1.7	1.35	1.1	1.1	1.0
6		1.25	3.85	1.75	1.35	1.1	1.1	1.0
7		1.15	3.8	1.65	1.3	1.1	1.1	1.0
8		1.75	4.2	1.65	1.25	1.1	1.1	1.0
9		1.55	4.4	1.6	1.2	1.1	1.1	1.0
10		1.4	3.7	1.6	1.2	1.1	1.0	1.0
11		1.4	3.4	1.55	1.25	1.1	1.0	1.0
12		1.4	3.4	1.55	1.3	1.1	1.0	1.0
13		1.45	3.6	1.55	1.25	1.1	1.0	1.0
14		1.5	3.4	1.55	1.2	1.1	1.0	1.0
15		1.6	3.4	1.55	1.2	1.1	1.0	1.0
16		1.8	3.1	1.55	1.2	1.1	1.0	1.0

ily gage height, in feet, of Taylor River near Almont, Colo., for 1905—Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	1.0	1.85	2.8	1.55	1.2	1.1	1.0	0.95
.....	1.05	2.15	2.7	1.45	1.15	1.1	1.0	.85
.....	1.1	2.3	2.5	1.45	1.1	1.1	1.0	.8
.....	1.1	2.4	2.6	1.45	1.1	1.1	1.0	.7
.....	1.1	2.6	2.45	1.45	1.1	1.1	1.0	.7
.....	1.1	2.7	2.4	1.45	1.1	1.1	1.0	.65
.....	1.1	2.95	2.45	1.35	1.1	1.1	1.0	.5
.....	1.15	2.95	2.4	1.35	1.1	1.1	1.0	.4
.....	1.2	2.9	2.4	1.35	1.1	1.1	1.0	.....
.....	1.2	2.8	2.4	1.35	1.1	1.1	1.0	.....
.....	1.4	2.55	2.25	1.35	1.1	1.1	1.0	.....
.....	1.8	2.4	2.2	1.35	1.1	1.1	1.0	.....
.....	1.95	2.3	2.15	1.35	1.1	1.1	1.0	.....
.....	2.05	2.3	2.15	1.35	1.1	1.1	1.0	.....
.....	.....	3.0	.....	1.45	1.1	.....	1.0	.....

on rating table for Taylor River near Almont, Colo., from April 17 to May 26, 1905

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	115	1.60	365	2.20	725	2.80	1,190
1.10	150	1.70	420	2.30	795	2.90	1,280
1.20	185	1.80	475	2.40	870	3.00	1,370
1.30	225	1.90	535	2.50	945		
1.40	270	2.00	595	2.60	1,025		
1.50	315	2.10	660	2.70	1,105		

E.—The above table is applicable only for open-channel conditions. It is based on discharge rements made during 1904–5 and is well defined.

m rating table for Taylor River near Almont, Colo., from May 27 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.40	70	1.30	255	2.20	725	3.20	1,555
.50	85	1.40	290	2.30	795	3.40	1,750
.60	100	1.50	330	2.40	870	3.60	1,950
.70	115	1.60	375	2.50	945	3.80	2,160
.80	135	1.70	425	2.60	1,025	4.00	2,370
.90	155	1.80	480	2.70	1,105	4.20	2,580
1.00	175	1.90	535	2.80	1,190	4.40	2,790
1.10	200	2.00	595	2.90	1,280		
1.20	225	2.10	660	3.00	1,370		

OTE.—The above table is applicable only for open-channel conditions. It is based on discharge surements made during 1904–5. It is well defined between gage heights 1 foot and 2.6 feet.

Estimated monthly discharge of Taylor River near Almont, Colo., for 1905.

Month.	Discharge in second-feet.			To acre
	Maximum.	Minimum.	Mean.	
April 17 to 30	628	115	248	
May	1,370	168	650	
June	2,790	692	1,518	
July	535	272	351	
August	310	200	182	
September	200	200	200	
October	200	175	121	
November 1 to 24	175	70	156	
The period				

GUNNISON RIVER NEAR CIMARRON, COLO.

This station was established September 18, 1903. It is located at the Denver a Grande Railroad bridge, 1½ miles from Cimarron, Colo., 1,000 feet above the mouth of (ron River, in T. 19 S., R. 91 W. The purpose of the station was the collection of graphic data relative to the Uncompahgre Valley project, which comtemplates the di of 1,300 cubic feet of water per second from Gunnison River about 12 miles below. station was discontinued December 16, 1905, having been replaced by the station estal at the east portal of Gunnison tunnel in April, 1905.

The channel is straight for 1,000 feet above and 300 feet below the station. The lef is a granite cliff which rises vertically from the water. The right bank is a mountai of about 45°. The bed of the stream, which is permanent, is composed of granite ders along the sides with an even deposit of small cobblestones in the center. T but one channel at all stages. At the cable section the left bank is an offset in the channel filled with a deposit of mud. The velocity is swift at low stages and very during high water. Gage heights range from 3 to 12 feet.

Discharge measurements are made by means of a cable, car, stay, and tag lines. initial point for soundings is at the face of the left cliff, 20 feet from the eye bolt to cable is fastened, and is marked zero on the tag line.

A standard chain gage, which was read twice daily during 1905 by G. C. Gates, is in on the upstream side of the Denver and Rio Grande Railroad bridge near the west end, 75 feet downstream from the cable. The gage scale reads from zero to 10 feet, wit markers, giving a range of 20 feet in gage heights. The length of chain from end of to center of first marker is 56.06 feet. The bench mark is the top of the southeast capstone of the east masonry abutment of the Denver and Rio Grande Railroad bridge, being cut across the corner of the capstone to indicate the bench mark; elevation, feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply I of the United States Geological Survey:

Description: 100, pp 80–81; 133, p 157.
Discharge: 100, p 81; 133, p 157.
Discharge, monthly: 100, p 82; 133, p 159.
Gage heights: 100, p 81; 133, p 158.
Rating table: 100, p 82; 133, p 158.

Discharge measurements of Gunnison River near Cimarron, Colo., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
R. I. Meeker	90	235	2.71	4.30	636
A. A. Welland	115	1,420	6.84	14.50	9,719
do	110	1,612	7.37	16.50	11,880
do	110	1,249	6.01	13.20	7,506
do	100	768	4.86	9.40	3,736
do	95	436	3.47	6.50	1,513
do	85	362	3.35	5.90	1,214
R. I. Meeker	78	239	2.44	4.40	583
do	78	232	2.23	4.30	517

Daily gage height, in feet, of Gunnison River near Cimarron, Colo., for 1905.

...	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
...	...	4.35	10.05	14.85	9.4	8.25	4.75	4.9	4.45	3.45
...	...	4.45	10.15	15.6	8.95	7.35	4.7	4.55	4.05	3.25
...	...	4.5	9.65	16.05	8.45	7.15	4.45	4.55	4.1	3.5
...	...	4.45	8.25	17.15	7.55	7.0	4.55	4.4	4.15	3.95
...	...	4.1	7.75	17.9	7.95	6.7	4.7	4.3	4.35	3.6
...	...	4.25	7.55	16.6	7.8	6.45	4.75	4.25	4.25	3.75
...	...	4.5	8.35	16.2	7.6	6.5	4.75	4.2	4.15	3.85
...	...	4.8	8.5	16.9	7.5	6.35	4.7	4.1	4.1	3.85
...	...	4.85	9.2	17.3	7.35	5.85	4.65	4.05	4.2	3.7
...	4.85	5.8	8.75	16.5	7.15	5.75	4.6	4.1	3.95	3.8
...	4.75	5.8	8.15	15.35	7.05	5.9	4.5	4.15	4.0	3.9
...	4.65	5.8	7.85	15.2	6.65	5.85	4.4	4.15	4.0	3.75
...	4.8	5.65	8.0	14.85	6.5	5.8	4.35	4.15	3.75	4.05
...	4.75	5.5	8.2	14.8	6.65	5.65	4.2	4.15	3.7	4.1
...	4.85	5.65	8.7	14.8	6.6	5.5	4.15	4.05	4.0	3.95
...	5.2	5.45	9.25	14.35	6.75	5.4	4.25	4.15	3.95	4.1
...	5.15	5.5	10.92	14.3	6.65	5.2	4.2	4.35	4.0	3.8
...	5.2	5.55	11.45	13.2	6.6	5.0	4.1	4.25	4.05	...
...	5.0	5.9	12.5	12.55	6.5	4.95	4.1	4.05	4.0	...
...	5.05	5.9	13.0	12.25	6.5	4.75	4.15	3.95	3.9	...
...	4.7	5.65	13.25	12.2	6.55	4.55	4.2	4.1	4.1	...
...	4.85	5.55	13.9	12.0	6.55	4.75	4.2	4.05	4.05	...
...	4.45	5.75	14.6	11.45	6.35	4.8	4.1	4.3	4.15	...
...	4.3	5.75	14.7	11.35	6.35	4.8	4.15	4.5	3.85	...
...	4.3	5.9	14.2	11.3	6.2	5.05	4.2	4.25	3.7	...
...	4.45	6.1	14.4	11.15	6.15	5.05	4.25	4.25	3.55	...
...	4.5	6.55	14.8	11.1	6.05	5.0	4.3	4.25	4.35	...
...	4.55	6.7	14.55	10.8	6.15	4.7	4.2	4.35	3.85	...
...	4.25	8.3	12.5	10.6	6.65	4.9	4.15	4.2	3.4	...
...	4.35	9.5	12.15	10.15	7.15	5.0	4.45	4.25	3.35	...
...	4.3	...	13.15	...	7.9	5.0	...	4.3	...	...

Station rating table for Gunnison River near Cimarron, Colo., from March 10 to December 11, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.20	300	5.00	775	6.80	1,660	10.20	4,535
3.30	320	5.10	815	6.90	1,725	10.40	4,750
3.40	340	5.20	855	7.00	1,790	10.60	4,970
3.50	360	5.30	895	7.20	1,925	10.80	5,190
3.60	380	5.40	940	7.40	2,065	11.00	5,410
3.70	400	5.50	985	7.60	2,215	11.50	5,960
3.80	425	5.60	1,030	7.80	2,365	12.00	6,535
3.90	450	5.70	1,075	8.00	2,520	12.50	7,110
4.00	475	5.80	1,120	8.20	2,680	13.00	7,685
4.10	500	5.90	1,165	8.40	2,840	13.50	8,260
4.20	526	6.00	1,215	8.60	3,000	14.00	8,860
4.30	553	6.10	1,265	8.80	3,180	14.50	9,460
4.40	580	6.20	1,315	9.00	3,360	15.00	10,060
4.50	610	6.30	1,370	9.20	3,540	15.50	10,660
4.60	640	6.40	1,425	9.40	3,725	16.00	11,260
4.70	670	6.50	1,480	9.60	3,915	16.50	11,860
4.80	705	6.60	1,540	9.80	4,115		
4.90	740	6.70	1,600	10.00	4,325		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is fairly well defined between gage heights 4 feet and 9.4 feet. The table has been extended beyond these limits. Above gage height 16.5 feet the rating curve is a tangent, the difference being 125 per tenth.

Estimated monthly discharge of Gunnison River near Cimarron, Colo., for 1905.

[Drainage area, 3,844 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 10–31	855	540	676	29,500	0.176	0.144
April	3,820	500	1,118	66,520	.291	.325
May	9,820	2,178	5,511	338,900	1.43	1.65
June	13,610	4,482	8,867	527,600	2.31	2.56
July	3,725	1,240	1,863	114,600	.485	.559
August	2,720	625	1,101	67,700	.286	.330
September	688	500	576	34,270	.150	.167
October	740	462	540	33,200	.140	.161
November	595	330	472	28,090	.123	.137
December 1–17	500	310	424	14,300	.110	.070
The period				1,255,000		

GUNNISON RIVER AT EAST PORTAL OF GUNNISON TUNNEL, COLORADO.

This station was established April 1, 1905, and replaces the Cimarron station, 12 miles above. It is located about 100 yards above the portal of the tunnel and is in T. 49 N., R. 7 W., 21 miles by wagon road from Montrose. The object of the station is to determine the volume of flow of the river at this point, as 1,300 second-feet will be diverted by the Gunnison tunnel when it is completed.

annel is straight for 500 feet above and 300 feet below the station. The banks are ky mountain sides, and do not overflow. The bed of the stream is composed pri- solid ledges of schists with a shifting deposit of gravel and sand which reaches a 3 to 4 feet at low water. There is but one channel at all stages. The current is t low water, but becomes swift during high water. Gage heights range from 5 to

rge measurements are made by means of a cable, car, and tag line. The initial soundings is the left bank at high-water mark and is indicated by zero on tag line. ge, which is read twice daily by H. L. Daniels, is a vertical staff, graduated from feet, bolted to a vertical cliff on the right bank of the river 50 feet upstream from The bench mark is a United States Geological Survey standard aluminum tablet ck ledge 50 feet south of the mouth of Gunnison tunnel; elevation of bench mark zero of the gage, 29.11 feet.

measurements of Gunnison River at east portal of Gunnison tunnel, Colorado, in 1905.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Sq. ft.	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	O. McDermith	1,301	3.48	9.05	4,529
.....	....do	1,793	4.76	11.80	8,540
.....	....do	2,105	5.32	12.80	11,200
.....	....do	1,758	4.04	11.25	7,100
.....	....do	1,649	4.06	10.60	6,690
.....	....do	1,410	3.04	9.25	4,184
.....	....do	1,166	2.17	7.60	2,525
.....	....do	1,054	1.61	6.85	1,695
.....	....do	1,091	1.87	7.12	2,044
.....	....do	917	1.12	6.00	1,025
.....	....do	860	.89	5.60	763
.....	....do	846	.81	5.50	689
13..	....do	806	.71	5.24	575

ge height, in feet, of Gunnison River at east portal of Gunnison tunnel, Colorado, for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	8.95	11.95	8.75	7.85	5.5	5.55	5.3	5.2
.....	.....	9.05	12.55	8.45	7.4	5.5	5.35	5.3	5.4
.....	.....	8.65	12.85	8.15	7.15	5.4	5.3	5.3	5.6
.....	.....	8.1	13.35	8.0	7.05	5.5	5.3	5.3	5.6
.....	.....	7.8	13.95	7.85	6.85	5.5	5.25	5.3	5.6
.....	.....	7.6	13.15	7.65	6.75	5.6	5.2	5.3	5.6
.....	.....	7.6	12.9	7.6	6.65	5.6	5.2	5.25	5.7
.....	.....	7.9	13.1	7.6	6.4	5.5	5.2	5.2	6.0
.....	5.9	8.4	13.65	7.45	6.2	5.5	5.2	5.2	6.0
.....	6.05	8.75	13.05	7.25	6.2	5.45	5.15	5.2	6.0
.....	6.2	7.95	12.55	7.05	6.15	5.35	5.1	5.2	6.0
.....	6.25	7.8	12.25	7.0	6.05	5.3	5.1	5.1	6.0
.....	6.1	8.0	12.1	6.85	6.0	5.25	5.1	5.1	6.0
.....	6.15	7.9	11.9	6.8	6.0	5.2	5.1	5.0	6.0
.....	6.0	8.05	11.9	6.8	6.0	5.2	5.1	5.1	6.0
.....	e6.1	8.48	11.75	6.8	5.85	5.2	5.1	5.05	6.0
.....	6.18	9.5	11.2	6.8	5.8	5.15	5.2	5.1	6.1

Daily gage height, in feet, of Gunnison River at east portal of Gunnison tunnel, Colorado, 1905—Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
18	6.28	9.9	10.95	6.8	5.7	5.1	5.2	5.2	
19	6.42	10.5	10.65	6.7	5.6	5.1	5.2	5.15	
20	6.38	10.85	10.6	6.6	5.6	5.2	5.2	5.0	
21	6.2	11.15	10.5	6.6	5.5	5.2	5.2	5.1	
22	6.15	11.45	10.15	6.6	5.5	5.1	5.2	5.15	
23	6.2	11.95	9.95	6.6	5.5	5.1	5.2	5.2	
24	6.3	11.9	9.85	6.6	5.5	5.1	5.25	5.1	
25	6.4	11.7	9.8	6.5	5.65	5.1	5.2	5.1	
26	6.55	11.75	9.75	6.5	5.65	5.2	5.3	5.1	
27	6.82	11.75	9.65	6.65	5.5	5.1	5.3	5.2	
28	7.28	11.5	9.6	6.5	5.5	5.2	5.3	5.2	
29	7.8	10.75	9.35	6.5	5.7	5.2	5.3	5.2	
30	8.35	10.8	9.05	6.9	5.65	5.4	5.3	5.2	
31	.....	10.9	.....	7.8	5.6	.....	5.3	.....	

GUNNISON RIVER NEAR CORY, COLO.

This station was established April 30, 1903, It is located at the wooden highway bri on the road between Delta and Cory, Colo., about 6 miles east of Delta.

The channel is over 200 feet wide and is straight for 300 feet above and 500 feet below station. The right bank is abrupt, high, and wooded, and does not overflow; the left b is a gradual slope of cobblestones, gravel, and sand to the annual flood plain; is partly c ered with trees and underbrush, and overflows at extreme high water. The bed of stream is composed of bowlders and cobblestones and is permanent. There is but channel at all stages. The current is swift at high water. Gage heights range from 5 t feet.

Discharge measurements are made from the downstream side of the two-span bridge. initial point for soundings is a brass tack in the hand rail at the center of the left downstream side of bridge.

A standard chain gage, which was read twice daily during 1905 by John Shea, is loc on the downstream side of the bridge 90 feet from the right bank. The gage scale r from zero to 10 feet, with two markers, allowing for a range of 20 feet in gage heights second marker being used above 10 feet. The length of the chain from the end of weight to the center of the second marker is 14.12 feet. The bench mark is the top ed the iron rim of the northwest cylinder pier, downstream side of bridge, marked with paint at the point of B. M.; elevation above the datum of the gage, 17.59 feet.

Information in regard to this station is contained in the following Water-Supply Pap the United States Geological Survey:

Description: 100, p 76; 133, p 159.
Discharge: 100, pp 76, 93; 133, p 160.
Discharge, monthly: 100, p 78; 133, p 161.
Gage heights: 100, p 77; 133, p 160.
Rating table: 100, p 77; 133, p 161.

Discharge measurements of Gunnison River near Cory, Colo., in 1905.

te.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis-charge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	R. I. Meeker	188	760	2.70	6.85	2,052
.....	Oro McDermith	213	1,090	4.03	8.20	4,388
.....	A. A. Weiland	256	1,682	7.88	10.95	13,280
.....	R. I. Meeker	260	1,785	8.11	11.35	14,480
.....	A. A. Weiland	260	1,785	8.04	11.25	14,350
.....	.....do	256	1,688	7.64	10.95	12,890
.....	.....do	269	2,056	8.86	12.20	18,220
.....	.....do	266	1,893	8.38	11.80	15,860
.....	.....do	232	1,329	5.57	9.45	7,405
.....	.....do	200	852	3.09	7.30	2,632
.....	.....do	210	942	3.46	7.70	3,263
2.....	R I. Meeker	180	566	1.54	5.90	870

Daily gage height, in feet, of Gunnison River near Cory, Colo., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug	Sept.	Oct.	Nov	Dec
.....	5.25	5.5	5.6	6.0	9.8	11.75	8.75	7.6	5.8	5.8	5.7	5.35
.....	5.3	5.5	5.8	6.0	10.2	12.15	8.55	7.35	5.85	5.8	5.75	5.3
.....	5.3	5.5	5.8	6.0	9.5	12.2	8.4	7.05	5.85	5.8	5.7	5.3
.....	5.4	5.5	5.85	6.0	8.9	12.7	8.25	7.0	5.95	5.7	5.7	5.3
.....	5.45	5.5	5.85	5.9	8.5	13.1	7.95	6.9	5.8	5.7	5.7	5.4
.....	5.45	5.4	5.9	5.9	8.25	12.7	7.9	6.75	5.8	5.7	5.6	5.4
.....	5.45	5.5	6.0	5.9	8.4	12.35	7.8	6.55	5.8	5.7	5.6	5.4
.....	5.4	5.4	6.0	6.2	8.55	12.8	7.65	6.5	5.85	5.7	5.6	5.45
.....	5.3	5.5	5.9	6.65	9.3	12.85	7.55	6.45	5.8	5.7	5.6	5.4
.....	5.3	5.5	6.0	6.85	9.0	12.63	7.45	6.45	5.8	5.7	5.6	5.3
.....	5.3	5.45	6.0	6.85	8.65	12.13	7.3	6.4	5.75	5.6	5.6	5.3
.....	5.25	5.4	6.0	6.95	8.55	11.93	7.25	6.4	5.7	5.6	5.6	5.35
.....	5.25	5.4	6.0	6.95	8.7	11.88	7.2	6.4	5.75	5.6	5.55	5.35
.....	5.25	5.5	6.0	6.95	8.7	11.53	7.05	6.4	5.7	5.6	5.55	5.4
.....	5.25	5.45	6.05	6.85	8.75	11.43	7.0	6.3	5.7	5.65	5.5	5.4
.....	5.3	5.4	6.1	6.95	9.2	11.28	7.0	6.2	5.7	5.75	5.6	5.4
.....	5.3	5.5	6.1	7.0	10.2	10.88	6.9	6.0	5.7	5.7	5.6	5.4
.....	5.4	5.5	6.2	7.05	10.55	10.58	6.8	6.0	5.8	5.75	5.6	5.4
.....	5.4	5.5	6.3	7.2	11.1	10.48	6.8	6.0	5.7	5.8	5.6	5.4
.....	5.4	5.45	6.3	7.15	11.35	10.28	6.75	5.9	5.75	5.8	5.5	5.4
.....	5.4	5.4	6.3	7.05	11.5	10.06	6.75	5.8	5.75	5.8	5.5	5.45
.....	5.4	5.4	6.2	7.05	11.8	9.96	6.7	5.8	5.7	5.8	5.5	.....
.....	5.3	5.4	6.2	6.95	12.2	9.81	6.7	5.8	5.7	5.8	5.5	.....
.....	5.35	5.4	6.1	7.25	12.3	9.76	6.75	5.75	5.7	5.7	5.5	.....
.....	5.35	5.4	6.0	7.45	11.9	9.56	6.7	5.7	5.7	5.7	5.5	.....
.....	5.3	5.4	6.0	7.5	11.9	9.51	6.75	5.7	5.7	5.7	5.5	.....
.....	5.3	5.5	6.0	7.75	11.95	9.41	6.8	5.7	5.7	5.7	5.55	.....
.....	5.35	5.5	6.0	8.3	11.65	9.4	6.85	5.8	5.7	5.7	5.6	.....
.....	5.3	.....	6.0	8.85	10.85	9.15	6.9	5.8	5.7	5.7	5.5	.....
.....	5.4	.....	6.0	9.25	10.5	8.9	7.05	5.85	5.75	5.7	5.45	.....
.....	5.5	.....	6.0	.....	10.95	.....	7.4	5.8	.....	5.75	.....	6.50

Station rating table for Gunnison River near Cory, Colo., from January 1 to December 21, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
5.20	430	6.60	1,630	8.00	3,810	9.80	8,490
5.30	480	6.70	1,750	8.10	4,010	10.00	9,180
5.40	530	6.80	1,870	8.20	4,210	10.20	9,910
5.50	580	6.90	2,000	8.30	4,410	10.40	10,660
5.60	680	7.00	2,130	8.40	4,620	10.60	11,450
5.70	730	7.10	2,270	8.50	4,840	10.80	12,280
5.80	810	7.20	2,420	8.60	5,070	11.00	13,130
5.90	900	7.30	2,570	8.70	5,300	11.20	14,000
6.00	990	7.40	2,730	8.80	5,540	11.40	14,880
6.10	1,090	7.50	2,900	8.90	5,790	11.60	15,790
6.20	1,190	7.60	3,070	9.00	6,050	11.80	16,730
6.30	1,290	7.70	3,250	9.20	6,600	12.00	17,700
6.40	1,400	7.80	3,430	9.40	7,190		
6.50	1,510	7.90	3,620	9.60	7,820		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–1905. It is fairly well defined above gage height 5.9 feet. Above gage height 12 feet the rating curve is a tangent, the difference being 500 per tenth.

Estimated monthly discharge of Gunnison River near Cory, Colo., for 1905.

[Drainage area, 5,233 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	590	455	503	30,930	0.096	0.111
February	590	530	563	31,270	0.108	0.113
March	1,290	660	1,013	62,290	0.194	0.224
April	6,745	900	2,251	133,900	0.430	0.480
May	19,200	4,310	10,320	634,600	1.97	2.27
June	23,200	5,790	14,110	839,600	2.70	3.01
July	5,420	1,750	2,643	162,500	0.505	0.582
August	3,070	730	1,306	80,300	0.250	0.288
September	945	730	775	46,120	0.148	0.165
October	810	660	744	45,750	0.142	0.164
November	770	560	645	38,380	0.123	0.137
December 1–21	560	480	517	21,530	0.099	0.077
The period				2,127,000		

GUNNISON RIVER AT WHITEWATER, COLO.

This station was regularly established April 10 1902, incomplete series of gage heights having been obtained during 1895, 1897, and 1901. It is located at the steel wagon bridge constructed by the State of Colorado at a point about one-half mile above the railroad station at Whitewater, on the Denver and Rio Grande Railroad. It was intended that this station should replace that formerly maintained on the Gunnison at Grand Junction, which was abandoned on account of conditions that rendered accurate gagings impossible.

The channel is straight for 1,000 feet above and 500 feet below the station. The cross section at the bridge is 282 feet wide, is uniform in area, and is clean. The right bank is of *alluvial material*, with abrupt slopes about 14 feet high; the left bank is of the same material.

t slopes more gently and overflows at extreme high water. The bed of the stream is nposed of cobblestones, coarse gravel, and sand, and is fairly permanent. At the center the cross section the current is broken by cylindrical piers and old sheet piling, and a all area adjacent to these fills in with silt at low water but scours out during high water. ere is but one channel at all stages. The current is moderate at low water but swift at h. Gage heights range from 3.5 to 14 feet.

Discharge measurements are made from the downstream side of the two-span steel bridge. stay line is used at high water. The initial point for soundings is the edge of the capstone the left masonry abutment on the downstream side of the bridge.

The gage, which was read twice daily during 1905 by James Page, was originally of wire, d was located on the downstream side of the right span. On April 8, 1904, the old gage s replaced by a new chain gage with the same datum. The gage scale is graduated from o to 10 feet, with two markers, giving a range of 20 feet in gage heights. The length of chain from the end of the weight to the center of the first marker is 21.59 feet. The ond marker is 11.59 feet from end of weight and is used when gage heights are above 10 t. The bench mark, established July 3, 1904, is a standard United States Geological rvey iron bench-mark post located about 40 feet southeast of the east end of the bridge; is stamped 4,653.6 feet above sea level; the elevation of the bench mark above the datum gage is 6.83 feet.

Information in regard to this station is contained in the following publications of the ited States Geological Survey (Bull=Bulletin; WS=Water-Supply Paper):

Description: Bull 140, p 189; WS 16, p 140; 66, p 94; 85, p 42; 100, pp 64–65; 133, p 162.
Discharge: WS 85, p 43; 100, p 65; 133, p 163.
Discharge, monthly: WS 85, p 44; 100, p 67; 133, p 164.
Gage heights: WS 16, p 140; 66, p 95; 85, p 43; 100, p 66; 133, p 163.
Rating table: WS 85, p 44; 100, p 66; 133, p 164.

Discharge measurements of Gunnison River at Whitewater, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
rch 30	R. I. Meeker	246	487	2.17	4.25	1,059
y 21	do	275	2,744	6.76	11.95	18,560
y 22	do	275	2,797	7.22	12.15	20,210
ne 4	do	275	3,092	8.08	13.25	25,000
y 12	do	262	978	2.68	5.62	2,622
gust 11	do	253	691	1.95	4.45	1,345
ptember 28	do	205	513	1.66	3.90	824

Daily gage height, in feet, of Gunnison River at Whitewater, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
	4.3	9.4	11.65	7.7	6.4	4.0	4.65
	4.3	10.1	12.45	7.35	6.15	4.05	4.65
	4.35	9.6	12.75	7.1	5.65	3.9	4.45
	4.25	8.85	13.15	6.85	5.3	3.95	4.35
	4.4	8.35	13.85	6.55	5.15	4.6	4.25
	4.25	7.75	13.6	6.45	5.05	4.4	4.2
	4.2	7.65	13.05	6.25	5.05	4.45	4.25
	4.5	7.95	13.2	6.05	4.95	4.35	4.15
	4.85	8.7	13.5	6.05	4.75	4.25	4.05
	5.1	8.8	13.55	5.95	4.6	4.2	4.0
	5.55	8.35	12.95	5.8	4.45	4.05	3.95

Daily gage height, in feet, of Gunnison River at Whitewater, Colo., for 1905—Continued.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
12	5.8	7.95	12.5	5.65	4.55	4.05	3.9
13	5.7	7.8	12.25	5.5	4.55	4.0	3.9
14	5.55	7.85	12.05	5.5	4.5	3.9	3.9
15	5.4	7.8	11.85	5.4	4.45	3.8	4.0
16	5.3	8.35	11.7	5.45	4.4	3.8	3.95
17	5.55	9.4	11.1	5.35	4.25	3.8	4.0
18	5.75	10.3	10.45	5.35	4.1	3.75	4.05
19	5.75	10.9	10.15	5.15	4.0	3.7	4.2
20	5.9	11.6	9.9	5.15	3.95	3.7	4.15
21	5.75	11.95	9.6	5.1	3.9	3.75	4.15
22	5.5	12.15	9.35	5.1	3.8	3.75	4.0
23	5.65	12.6	9.15	5.1	3.7	3.75	4.3
24	5.75	12.75	9.05	5.05	3.85	3.7	4.3
25	6.05	12.55	8.8	4.85	3.8	3.8	4.25
26	6.4	12.45	8.75	4.65	3.85	3.95	4.3
27	6.7	12.35	8.5	4.7	3.95	3.95	4.25
28	7.35	12.05	8.4	4.7	3.85	3.9	4.3
29	8.1	11.3	8.2	4.65	3.8	4.35	4.25
30	8.65	10.65	8.0	5.0	3.95	4.55	4.25
31	.....	10.95	.....	5.8	4.05	.....	4.25

Station rating table for Gunnison River at Whitewater, Colo., from April 1 to May 1, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.00	695	5.20	1,860	6.40	3,530	7.60	5,610
4.10	765	5.30	1,985	6.50	3,690	7.70	5,800
4.20	840	5.40	2,110	6.60	3,850	7.80	5,990
4.30	920	5.50	2,240	6.70	4,010	7.90	6,190
4.40	1,005	5.60	2,370	6.80	4,180	8.00	6,400
4.50	1,095	5.70	2,505	6.90	4,350	8.20	6,830
4.60	1,190	5.80	2,640	7.00	4,520	8.40	7,300
4.70	1,290	5.90	2,780	7.10	4,690	8.60	7,810
4.80	1,395	6.00	2,920	7.20	4,870	8.80	8,350
4.90	1,505	6.10	3,070	7.30	5,050	9.00	8,910
5.00	1,620	6.20	3,220	7.40	5,230	9.20	9,490
5.10	1,740	6.30	3,370	7.50	5,420	9.40	10,090

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904-5. Below 7.8 feet the table is the same as for 1904.

n rating table for Gunnison River at Whitewater, Colo., from May 2 to October 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.70	720	5.20	2,085	6.70	4,280	9.40	10,180
3.80	795	5.30	2,205	6.80	4,450	9.60	10,750
3.90	870	5.40	2,330	6.90	4,625	9.80	11,340
4.00	950	5.50	2,460	7.00	4,800	10.00	11,960
4.10	1,030	5.60	2,590	7.20	5,160	10.20	12,600
4.20	1,115	5.70	2,725	7.40	5,540	10.40	13,250
4.30	1,200	5.80	2,865	7.60	5,930	10.60	13,920
4.40	1,290	5.90	3,010	7.80	6,340	10.80	14,610
4.50	1,380	6.00	3,160	8.00	6,760	11.00	15,320
4.60	1,470	6.10	3,310	8.20	7,200	11.50	17,180
4.70	1,565	6.20	3,465	8.40	7,650	12.00	19,240
4.80	1,660	6.30	3,620	8.60	8,120	12.50	21,520
4.90	1,760	6.40	3,780	8.80	8,600	13.00	23,920
5.00	1,860	6.50	3,945	9.00	9,100	13.50	26,370
5.10	1,970	6.60	4,110	9.20	9,630		

E.—The above table is applicable only for open-channel conditions. It is based on discharge rements made during 1904–1905, and is fairly well defined.

Estimated monthly discharge of Gunnison River at Whitewater, Colo., for 1905.

[Drainage area, 7,868 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	7,945	840	2,494	148,400	.317	.354
.....	22,710	6,030	12,720	782,100	1.62	1.87
.....	28,080	6,760	16,810	1,000,000	2.14	2.39
.....	6,130	1,518	2,783	171,100	.354	.408
st.....	3,780	720	1,429	87,860	.182	.210
mber.....	1,470	720	962	57,240	.122	.136
ıer.....	1,518	870	1,103	67,820	.140	.161
The period.....	.....	.....	.....	2,315,000	.....	.....

NORTH FORK OF GUNNISON RIVER NEAR HOTCHKISS, COLO.

is station was established April 13, 1904. It is located 1 miles below Hotchkiss, Colo., ıe ranch of L. Gorsuch, and replaces the station maintained during 1903 at the high-bridge one-half mile east of Hotchkiss and abandoned because of unsatisfactory con-ns.

e channel is 180 feet wide and is straight for 800 feet both above and below the station. banks are composed of alluvial material and are not liable to overflow. The bed of tream is composed of large and small cobblestones, with some gravel, and changes during extreme high water. There are two channels at low water, divided by a bar; gh stages there is but one channel. The current is swift at all stages. Gage heights ı from 1 foot to 6 feet.

scharge measurements are made by means of a cable and car, the property of the ver. The initial point for soundings is near the left end of the cable and is marked o" on the tag line. A stay line 40 feet upstream is used during high water.

ıe gage, which was observed during 1905 by L. Gorsuch, is an inclined timber, gradu-from *zero to 7 feet, and is located* on the right bank about 800 feet downstream from

the cable. The bench mark is a point on a large bowlder on the right bank of the stre about 50 feet to the right of the gage, designated by a circle of white paint and mar "B. M.;" elevation above the zero of the gage, 9.34 feet.

A description of this station, with gage-height and discharge data, is contained in Wa Supply Paper No. 133, United States Geological Survey, pages 167–170.

Discharge measurements of North Fork of Gunnison River near Hotchkiss, Colo., in 190

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di chan
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.*
April 11	R. I. Meeker	160	204	3.78	3.10	
May 7	Oro McDermith	164	365	4.94	3.95	1
May 20	A. A. Weiland	175	714	7.80	5.40	5
June 2	do	175	698	8.12	5.30	5
June 14	do	170	583	6.59	4.70	3
June 28	do	170	374	4.49	3.60	1
July 12	do	143	187	3.42	2.60	
August 2	do	115	122	2.52	2.2	
October 3	R. I. Meeker	65	48	2.35	1.78	

Daily gage height, in feet, of North Fork of Gunnison River near Hotchkiss, Colo., for 19

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	2.3	2.3	2.6	2.52	5.0	5.45	3.25	2.45	1.28	1.88	1.8	
2	2.3	2.32	2.75	2.6	5.32	5.55	3.2	2.3	1.18	1.8	1.8	
3	2.3	2.35	2.8	2.58	4.65	5.45	3.02	2.18	1.15	1.78	1.75	
4	2.3	2.4	2.7	2.55	4.2	5.8	2.95	2.1	1.20	1.7	1.75	
5	2.35	2.4	2.6	2.55	4 05	5.95	2.95	2.05	1.25	1.7	1.7	
6	2.35	2.4	2.6	2.65	3.85	5.45	2.9	2.0	1.32	1.7	1.7	
7	2.38	2.35	2.6	2.85	3.92	5.45	2.82	2.0	1.42	1.7	1.7	
8	2.4	2.3	2.58	3.02	4.35	5.45	2.85	1.92	1.48	1.68	1.7	
9	2.4	2.25	2.5	3.15	4.75	5.7	2.75	1.88	1.4	1.65	1.7	
10	2.4	2.25	2.5	3.28	4.35	5.45	2.72	1.78	1.35	1.65	1.7	
11	2.4	2.25	2.5	3.3	4.1	5.25	2.62	1.78	1.32	1.65	1.7	
12	2.38	2.25	2.5	3.35	4.15	5.1	2.58	1.82	1.25	1.65	1.65	
13	2.35	2.2	2.5	3.35	4.25	5.05	2.52	1.88	1.25	1.65	1.65	
14	2.35	2.2	2.5	3.35	4.15	4.95	2.5	1.82	1.25	1.7	1.65	
15	2.32	2.2	2.58	3.25	4.25	4.9	2.48	1.78	1.25	1.7	1.72	
16	2.3	2.2	2.65	3.32	4.6	4.7	2.42	1.72	1.25	1.7	1.75	
17	2.3	2.2	2.68	3.32	5.08	4.5	2.4	1.62	1.25	1.75	1.8	
18	2.35	2.25	2.7	3.35	5.38	4.35	2.32	1.52	1.3	1.78	1.8	
19	2.35	2.28	2.6	3.52	5.6	4.15	2.3	1.42	1.32	1.68	1.75	
20	2.3	2.3	2.62	3.35	5.7	4.02	2.3	1.42	1.3	1.65	1.7	
21	2.2	2.3	2.62	3.28	5.7	3.95	2.22	1.4	1.3	1.6	1.65	
22	2.2	2.32	2.58	3.32	5.9	3.78	2.2	1.35	1.3	1.65	1.68	
23	2.2	2.25	2.52	3.32	6.0	3.72	2.18	1.3	1.3	1.72	1.82	
24	2.2	2.25	2.5	3.55	6.0	3.72	2.1	1.22	1.32	1.8	1.78	
25	2.25	2.28	2.5	3.68	5.7	3.7	2.08	1.2	1.42	1.75	1.68	
26	2.25	2.28	2.5	3.62	5.7	3.6	2.05	1.22	1.48	1.7	1.78	
27	2.3	2.25	2.6	3.82	5.65	3.5	2.0	1.4	1.5	1.7	1.95	
28	2.35	2.3	2.58	4.2	5.55	3.55	1.98	1.42	1.5	1.7	2.0	
29	2.35	.....	2.52	4.4	4.95	3.42	1.95	1.4	1.55	1.7	1.85	
30	2.35	.....	2.5	4.65	4.65	3.35	2.1	1.35	1.82	1.72		
31	2.35	.....	2.52	.....	5.25	.....	2.45	1.35	.....			

NOTE.—No ice record.

'tation rating table for North Fork of Gunnison River near Hotchkiss, Colo., from January 1 to May 16, 1905.

Gage. height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.20	120	3.10	790	4.00	2,200	4.90	4,290
2.30	150	3.20	920	4.10	2,400	5.00	4,570
2.40	190	3.30	1,050	4.20	2,610	5.10	4,850
2.50	240	3.40	1,190	4.30	2,820	5.20	5,140
2.60	300	3.50	1,340	4.40	3,040	5.30	5,440
2.70	370	3.60	1,500	4.50	3,270	5.40	5,740
2.80	460	3.70	1,660	4.60	3,510		
2.90	560	3.80	1,830	4.70	3,760		
3.00	670	3.90	2,010	4.80	4,020		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge easurements made during 1905. It is well defined between gage heights 2.2 feet and 3.1 feet. Above ge height 3.5 the table is uncertain.

'ation rating table for North York of Gunnison River near Hotchkiss, Colo., from May 17 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	0	2.10	260	3.20	1,280	4.60	3,680
1.10	2	2.20	320	3.30	1,410	4.80	4,150
1.20	8	2.30	390	3.40	1,540	5.00	4,640
1.30	18	2.40	460	3.50	1,680	5.20	5,140
1.40	32	2.50	540	3.60	1,830	5.40	5,660
1.50	50	2.60	630	3.70	1,980	5.60	6,190
1.60	75	2.70	720	3.80	2,140	5.80	6,740
1.70	105	2.80	820	3.90	2,310	6.00	7,300
1.80	135	2.90	930	4.00	2,480		
1.90	170	3.00	1,040	4.20	2,850		
2.00	210	3.10	1,160	4.40	3,250		

OTE.—The above table is applicable only for open-channel conditions. It is based on discharge asurements made during 1905. It is well defined above gage height 1.7 feet.

timated monthly discharge of North Fork of Gunnison River near Hotchkiss, Colo., for 1905.

[Drainage area, 850 square miles.]

Month.	Discharge in second-feet			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
anuary	190	120	159	9,777	0.187	0.216
ebruary	190	120	146	8,108	.172	.179
larch	460	240	292	17,950	.344	.397
April	3,635	252	1,162	69,140	1.37	1.53
May	7,300	1,920	4,476	275,200	5.27	6.08
June	7,160	1,475	3,986	237,200	4.69	5.23
July	1,345	190	577	35,480	.679	.783
August	500	8	125	7,686	.147	.170
September	142	5	27.5	1,636	.032	.036
October	163	75	108	6,641	.127	.146
November	210	90	121	7,200	.142	.158
December	355	105	199	12,240	.234	.270
The year	7,300	5	948	688,300	1.12	15.20

CIMARRON CREEK AT CIMARRON, COLO.

Cimarron Creek rises in the extreme southwestern part of Gunnison County and flows northward to its point of junction with Gunnison River. The drainage area is entirely mountainous. During the summer and fall short, heavy rainstorms occur frequently, and the rapid run-off induced by the steep slopes of the basin causes sudden fluctuations in gage heights.

The gaging station was established April 28, 1903. It is located at Smith's private bridge, 1,000 feet south of the Denver and Rio Grande Railroad station at Cimarron, in T. 48 N., R. 6 W., and about 1 mile above the mouth of Cimarron Creek.

The channel is straight for 100 feet above and 250 feet below the bridge. Both banks are low, rocky, and partly wooded and have not been known to overflow during the past ten years. The bed of the stream is composed of bowlders and cobblestones and is very rough, but is stable. The gradient is steep, though somewhat uneven. At low water there is but one channel. At high water there are two channels divided by the central pier of the bridge. The current is always rapid. Gage heights range from 1.5 to 4 feet. Accurate measurements are difficult to secure on account of the roughness of the section and the swift and irregular velocities.

Discharge measurements are made from the downstream side of the footbridge, which is supported by two log abutments and one log crib pier in the center of the stream. The initial point for soundings is the left abutment on the downstream side and is marked zero on the bridge. The bridge was washed away in June, 1905, but was replaced shortly afterwards at a greater elevation.

The gage, which was read during 1905 by J. L. Linscott, is a vertical staff graduated from zero to 6 feet, spiked to the face of the left abutment of the bridge on the downstream side. The bench mark consists of two nails driven into the root of a cottonwood tree 50 feet west of gage; elevation above the zero of the gage, 8.24 feet. This station was discontinued December 31, 1905.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 100, pp 82–83; 133, p 165.
Discharge: 66, p 55; 85, p 77; 100, pp 83, 94; 133, p 165.
Discharge, monthly: 100, p 84; 133, p 167.
Gage heights: 100, pp 83–84; 133, p 166.
Rating table: 100, p 84; 133, p 166.

Discharge measurements of Cimarron Creek at Cimarron, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
April 1	R. I. Meeker	32	20	2.20	1.70	44
May 11	Oro McDermith	39	45	3.33	2.30	153
May 23	A. A. Weiland	47	108	6.67	3.50	720
May 23	R. I. Meeker	48	103	6.65	3.48	685
June 6	A. A. Weiland	47	140	7.76	4.20	1,087
June 19	do	62	103	5.99	3.45	617
July 18	do	33	28	3.00	2.00	84
August 11	do	35	23	2.30	1.85	53
October 5	R. I. Meeker	24	18	1.72	1.65	31

Daily gage height, in feet, of Cimarron Creek at Cimarron, Colo., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	1.95	2.65	3.7	2.85	2.5	1.63	1.77	1.63	1.55
2	.....	1.68	2.82	3.85	2.77	2.3	1.6	1.87	1.65	.....
3	.....	1.68	2.5	3.92	2.75	2.25	1.63	1.65	1.65	.....
4	.....	1.75	2.38	4.1	2.5	2.17	1.6	1.9	1.63	.....
5	.....	1.68	2.35	4.25	2.6	2.1	1.63	1.65	1.65	.....
6	.....	1.68	2.28	4.1	2.55	2.07	1.73	1.65	1.65	.....
7	.....	1.65	2.2	4.1	2.55	2.0	1.63	1.63	1.57	.....
8	.....	1.78	2.2	4.08	2.55	2.05	1.57	1.6	1.55	.....
9	.....	1.82	2.62	4.12	2.4	1.8	1.6	1.65	1.57	.....
10	1.8	1.82	2.28	4.03	2.45	1.7	1.57	1.65	1.55	.....
11	1.6	1.82	2.3	4.0	2.4	1.85	1.6	1.6	1.53	.....
12	1.75	1.78	2.28	3.91	2.35	1.8	1.6	1.55	1.53	.....
13	1.72	1.72	2.38	3.82	2.3	1.8	1.6	1.57	1.57	.....
14	1.75	1.75	2.3	3.8	2.25	1.77	1.63	1.55	1.6	.....
15	1.78	1.65	2.42	3.87	2.3	1.73	1.5	1.6	1.57	.....
16	1.78	1.7	2.85	3.65	2.15	1.7	1.47	1.6	1.57	.....
17	1.75	1.82	2.95	3.52	2.1	1.67	1.5	1.63	1.6	.....
18	1.78	1.82	3.0	3.53	2.0	1.7	1.63	1.6	1.57	.....
19	1.8	1.85	3.1	3.37	2.13	1.57	1.63	1.63	1.53	.....
20	1.82	1.78	3.1	3.33	2.3	1.63	1.57	1.6	1.57	.....
21	1.72	1.68	3.28	3.3	2.15	1.6	1.55	1.6	1.53	.....
22	1.8	1.78	3.55	3.3	2.15	1.6	1.63	1.63	1.55	.....
23	1.7	1.82	3.65	3.13	2.03	1.63	1.63	1.87	1.55	.....
24	1.78	1.78	3.4	3.2	1.9	1.63	1.63	1.63	1.5	.....
25	1.8	1.8	3.3	3.23	2.1	1.63	1.77	1.53	1.55	.....
26	1.72	1.85	3.5	3.1	2.1	1.6	1.67	1.63	1.53	.....
27	1.8	1.92	3.55	3.07	2.2	1.6	1.63	1.65	1.63	.....
28	1.75	2.25	3.5	3.05	2.15	1.63	1.7	1.63	1.57	.....
29	1.75	2.3	3.22	2.97	2.95	1.65	1.77	1.65	1.55	.....
30	1.78	2.4	3.2	2.95	2.85	1.7	2.05	1.65	1.55	.....
31	1.8	.....	3.45	.....	2.73	1.73	.....	1.7	.....	.....

NOTE.—River frozen during December.

tation rating table for Cimarron Creek at Cimarron, Colo., from March 10 to December 1, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.50	22	2.30	152	3.10	473	3.90	973
1.60	28	2.40	181	3.20	526	4.00	1,050
1.70	37	2.50	213	3.30	582	4.10	1,130
1.80	49	2.60	247	3.40	640	4.20	1,213
1.90	65	2.70	285	3.50	700	4.30	1,300
2.00	83	2.80	327	3.60	763		
2.10	105	2.90	373	3.70	830		
2.20	126	3.00	422	3.80	900		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–1905. It is well defined between gage heights 1.7 feet and 3.5 feet.

Estimated monthly discharge of Cimarron Creek at Cimarron, Colo., for 1905.

[Drainage area, 210 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
March 10-31	52	28	44.5	1,942	.212	.17
April	181	32	57.5	3,422	.274	.30
May	796	126	389	23,920	1.85	2.13
June	1,256	397	796	47,360	3.79	4.23
July	397	65	185	11,380	.881	1.02
August	213	26	59.4	3,652	.283	.32
September	93	20	32.4	1,928	.154	.17
October	65	24	33.4	2,054	.159	.18
November	32	22	26.7	1,589	.127	.1
The period				97,250		

UNCOMPAHGRE RIVER NEAR COLONA, COLO.

This station was established April 9, 1904. It is located at the private road bridge of J. M. Duckett, in T. 47 N., R. 8 W., one-half mile above Eldredge siding on the Denver and Rio Grande Railroad and 3 miles above Colona, Colo. It is best reached by driving from Montrose. The station replaces one that was established August 10, 1903, at Kettle's bridge, 1 mile south of Colona, to take the place of the original station, which was located one-half mile northeast of Colona. Both of these stations were abandoned because of unsatisfactory conditions.

The channel is straight for about 300 feet above and below the station. The banks are about 4 feet high, are rocky and partly wooded, and neither is subject to overflow. The bed of the stream is composed of large and small cobblestones, and a loose deposit of silt shifts along each side. There is but one channel at all stages and the current is swift. Gage heights range from 0.5 foot to 4 feet. Accurate measurements are difficult to secure on account of the rough bed and steep gradient of the channel.

Discharge measurements are made from the downstream side of the 46.2-foot single-span bridge to which the gage is attached. The initial point for soundings is the downstream edge of the left abutment.

The gage, which was read during 1905 by Miss Clara Duckett, is an 8-foot board graduated from zero to 7 feet. It was spiked vertically to the upstream side of the left abutment. The high water of June, 1905, caused the pier to sink 0.18 foot during July, and on August 14, 1905, the gage was moved to the downstream side of the left pier and set at the original datum. The bench mark is the upper edge of a large screw set about 3 feet above the ground in an 8-inch willow tree 75 feet south and upstream from the right end of the bridge; elevation, 9.97 feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 100, pp 72-73; 133, pp 171-172.
Discharge: 100, p. 73; 133, p 172.
Discharge, monthly: 100, p 75; 133, p 174.
Gage heights: 100, p 74; 133, p 173.
Rating tables: 100, pp 74-75; 133, pp 173-174

Discharge measurements of Uncompahgre River near Colona, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft*
ril 13	R. I. Meeker	46	49	2.84	1.10	139
y 3	Oro McDermith	47	91	4.27	1.90	389
y 18	A. A. Welland	47	110	4.88	2.30	537
y 29	do	47	114	4.94	2.20	564
ne 8	do	47	170	8.15	3.75	1,384
ne 21	do	47	129	6.38	2.80	822
y 8	do	47	98	4.95	2.12	485
y 24	do	47	76	3.92	1.72	298
gust 7	do	47	73	3.96	1.72	289
gust 14	do	47	63	3.39	1.40	214
tober 1	R. I. Meeker	43	57	3.25	1.56	185

Daily gage height, in feet, of Uncompahgre River near Colona, Colo., for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
		1.2	1.05	2.2	2.95	2.62	1.87	1.2	1.47	1.06	0.96
		1.15	1.1	2.25	3.25	2.42	1.97	1.2	1.22	1.11	.96
		1.15	1.0	1.9	3.4	2.32	1.97	1.2	1.27	1.11	.....
		1.0	.95	1.85	4.2	2.27	1.82	1.3	1.22	1.11	.....
	0.7	1.1	.95	1.75	4.1	2.22	1.82	1.35	1.27	0.96	.....
	.75	1.05	1.0	1.7	4.0	2.07	1.82	1.3	1.27	1.01	.....
	.75	1.0	1.05	1.65	4.0	1.82	1.72	1.3	1.27	.96	.....
	.7	1.0	1.15	1.75	4.1	1.82	1.72	1.3	1.22	1.01	.....
	.7	1.0	1.2	1.9	4.2	1.92	1.72	1.3	1.22	1.01	.....
	.7	1.0	1.3	1.75	4.0	1.92	1.62	1.3	1.22	.96	.....
	.7	1.0	1.3	1.7	4.0	1.87	1.52	1.15	1.12	1.01	.....
		1.0	1.3	1.75	4.0	1.82	1.47	1.15	1.12	1.01	.....
		1.0	1.15	1.8	4.1	1.82	1.47	1.2	1.17	.96	.....
		1.0	1.0	1.7	4.05	1.92	1.6	1.2	1.12	.96	.....
		.9	1.0	1.8	4.0	2.02	1.6	1.15	1.07	1.01	.....
		.9	1.0	2.15	3.8	1.82	1.6	1.25	1.22	.96	.....
		.9	1.2	2.6	3.4	1.82	1.4	1.1	1.22	.96	.....
		.95	1.2	2.65	3.5	1.82	1.4	1.15	1.22	1.01	.....
	.8	1.0	1.4	2.55	3.0	1.87	1.35	1.15	1.22	1.01	.....
	.8	1.0	1.35	2.55	3.4	2.02	1.2	1.2	1.22	.96	.....
	.85	1.0	1.35	2.5	3.2	1.87	1.2	1.1	1.22	.96	.....
	.85	.95	1.2	2.9	2.95	1.87	1.2	1.15	1.12	1.01	.....
	.9	1.0	1.7	2.9	3.0	1.72	1.1	1.15	1.12	.96	.....
	.9	1.15	1.2	2.9	3.0	1.82	1.1	1.0	1.22	1.06	.....
	.9	1.0	1.3	2.9	3.0	1.72	1.1	1.05	1.17	1.06	.....
	.8	1.0	1.45	2.75	3.0	1.72	1.1	1.0	0.97	1.06	.....
	.8	1.0	1.75	2.8	3.0	1.87	1.1	1.0	1.02	.96	.....
	.9	1.0	1.9	2.75	3.0	1.97	1.25	1.15	1.07	.96	.....
		1.0	2.1	2.3	2.95	2.47	1.15	1.3	1.12	1.01	.....
		.9	2.1	2.2	2.8	2.87	1.35	1.15	1.12	1.01	.....
		.9	.....	2.65	.....	2.47	1.45	.....	1.17	.....	.....

NOTE.—River frozen February 12–18.

Station rating table for Uncompahgre River near Colona, Colo., from February 5 to Dec. 2, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.70	75	1.60	275	2.50	645	3.40	1,165
.80	85	1.70	310	2.60	695	3.50	1,235
.90	100	1.80	345	2.70	750	3.60	1,305
1.00	120	1.90	380	2.80	805	3.70	1,380
1.10	140	2.00	420	2.90	860	3.80	1,460
1.20	165	2.10	460	3.00	920	3.90	1,540
1.30	190	2.20	505	3.10	980	4.00	1,625
1.40	215	2.30	550	3.20	1,040	4.10	1,710
1.50	245	2.40	595	3.30	1,100	4.20	1,800

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–1905. It is fairly well defined between gage heights 1.2 feet and 4.8 feet.

Estimated monthly discharge of Uncompahgre River near Colona, Colo., for 1905.

[Drainage area, 433 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
February, 17 days	100	75	85.8	2,893	0.198	0.12
March	165	100	122	7,501	.282	.32
April	460	110	197	11,720	.455	.51
May	800	293	543	33,300	1.25	1.44
June	1,800	805	1,279	76,110	2.95	3.29
July	844	317	436	26,810	1.01	1.16
August	408	140	246	15,130	.568	.65
September	202	120	161	9,580	.372	.41
October	236	114	161	9,900	.372	.43
November	143	112	121	7,200	.279	.31
The period				200,200		

UNCOMPAHGRE RIVER AT MONTROSE, COLO.

This station was established April 22, 1903. It is located at the iron highway bridge west of Montrose and one-fourth mile west of the Denver and Rio Grande Railroad near Haskell Park.

The channel is straight for 100 feet above and 300 feet below the bridge. The right bank is of earth; the left bank is of earth below the bridge, but above the bridge is the steep slope of a shale bluff. Both banks are liable to overflow at extreme high water. The bed of the stream is composed of cobblestones and gravel and is quite rough. There is but one channel at all stages, broken during high water by the left pier of the bridge. The higher portion of the left side of the channel is covered with undergrowth which obstructs the flow during high stages. The current is rapid at all times. Gage heights range from 2 to 6 feet.

Discharge measurements are made from either side of the bridge. The initial point for soundings is at the inner edge of the lower cylinder bridge pier at the right bank.

The gage, which was read twice daily during 1905 by Herbert Reeves, is a vertical staff, graduated from zero to 8 feet, spiked to a wing dam 20 feet above the bridge. The zero of this gage, which was established April 15, 1904, is 1.45 feet higher than that of the gage which it replaced. The bench mark consists of two nails driven into root of a cottonwood tree 50 feet to the right of the gage; elevation, 8. zero of the gage.

ıtion in regard to this station is contained in the following publications of the ates Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

on: WS 50, p 379–380; 100, p 70; 133, p 175.
e: WS 50, p 380; 66, p 98; 100, p 70; 133, p 175.
e, monthly: Ann 22, iv, p 392; WS 100, p 72; 133, p 177.
ghts: WS 11, p 69; 50, p 380; 100, p 71; 133, p 176.
ables: WS 52, p 520; 100, pp 71–72; 133, p 176.

Discharge measurements of Uncompahgre River at Montrose, Colo., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
.....	R. I. Meeker	35	40	2.72	2.40	109
....	Oro McDermith	37	66	4.21	3.22	278
....	A. A. Welland	43	120	5.64	4.30	677
.....	R. I. Meeker	91	218	6.78	5.38	1,479
.....	A. A. Welland	40	96	5.33	3.73	512
.....	.....do	35	64	2.89	2.57	185
....	.....do	32	48	1.98	2.05	95
....	.....do	35	44	1.73	1.95	76
30...	.....do	34	44	2.93	2.45	129

ily gage height, in feet, of Uncompahgre River at Montrose, Colo., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	2.35	2.22	2.35	2.28	3.7	4.15	3.35	2.33	1.4	1.9	1.33	2.25
.....	2.38	2.2	2.4	2.4	4.25	4.8	3.3	2.05	1.23	1.77	1.43	2.25
.....	2.3	2.2	2.55	2.4	3.6	5.0	2.4	2.1	1.57	1.5	1.33	2.45
.....	2.28	2.2	2.6	2.32	3.2	5.8	2.2	2.0	1.73	1.45	1.45	2.35
.....	2.3	2.2	2.45	2.15	3.08	5.65	2.15	1.95	1.47	1.45	1.45	2.35
.....	2.32	2.2	2.48	2.35	2.7	5.15	2.3	2.0	1.33	1.35	1.43	2.25
.....	2.25	2.2	2.4	2.35	2.55	5.55	2.35	2.05	1.5	1.35	1.4	2.3
.....	2.38	2.2	2.32	2.5	2.45	5.5	2.4	1.93	1.4	1.4	1.45	2.15
.....	2.32	2.2	2.3	2.55	2.5	5.25	2.25	2.0	1.47	1.2	1.4	2.15
.....	2.2	2.2	2.3	2.5	2.55	5.05	2.15	2.03	1.5	1.2	1.4	2.05
.....	.....	2.2	2.3	2.45	2.75	5.25	2.15	1.93	1.4	1.2	1.4	2.25
.....	.....	2.2	2.3	2.4	3.3	5.0	2.15	1.93	1.45	1.2	1.3	2.3
.....	.....	2.2	2.3	2.4	3.35	4.85	2.25	2.25	1.57	1.2	1.2	2.35
.....	.....	.....	2.3	2.4	3.62	4.7	2.1	2.0	1.5	1.23	1.35	2.3
.....	.....	.....	2.3	2.25	3.62	4.53	2.15	1.95	1.5	1.23	1.5	2.25
.....	.....	.....	2.2	2.02	3.65	4.6	2.25	1.93	1.5	1.2	1.35	2.1
.....	.....	.....	2.2	2.02	3.5	4.45	2.15	1.9	1.47	1.2	1.45	2.2
.....	.....	.....	2.25	2.02	3.6	4.3	2.0	1.73	1.35	1.17	1.35	2.3
.....	2.25	.....	2.21	2.0	3.6	4.3	1.95	1.63	1.45	1.23	1.45	2.35
.....	2.3	2.2	2.2	2.0	3.75	3.45	2.4	1.57	1.4	1.17	1.35	2.2
.....	2.3	2.2	2.2	2.0	3.85	3.35	2.0	1.55	1.25	1.17	1.25	2.3
.....	2.35	2.22	2.2	2.0	3.92	3.45	2.2	1.45	1.4	1.23	1.3	2.35
.....	2.3	2.2	2.35	2.02	4.48	3.4	2.05	1.43	1.4	1.35	1.55	2.25
.....	2.28	2.25	2.25	2.25	4.5	3.5	2.05	1.45	1.43	1.35	1.5	2.3
.....	2.3	2.25	2.45	2.35	4.55	3.45	1.97	1.35	1.53	1.4	1.65	2.2
.....	2.2	2.22	2.35	2.5	4.45	3.55	1.95	1.4	1.47	1.45	1.65	2.1
.....	2.2	2.22	2.35	2.85	4.25	3.7	2.0	1.4	1.43	1.35	1.75	2.05
.....	2.2	2.3	2.32	3.85	4.1	3.4	2.15	1.85	1.33	1.5	1.7	2.05
.....	2.22	.....	2.25	3.88	4.0	3.25	2.75	1.53	1.55	1.5	1.75	2.05
.....	2.22	.....	2.22	3.7	4.05	3.2	2.83	1.37	1.87	1.45	2.05	2.1
.....	2.2	.....	2.3	.....	3.9	.....	2.8	1.37	.....	1.37	.....	2.15

River frozen January 11–17. February 14–19.

Station rating table for Uncompahgre River at Montrose, Colo., from January 1 to June 3, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.00	57	2.80	184	3.60	412	4.40	717
2.10	69	2.90	207	3.70	446	4.50	765
2.20	82	3.00	231	3.80	481	4.60	817
2.30	96	3.10	257	3.90	516	4.70	874
2.40	111	3.20	285	4.00	552	4.80	936
2.50	127	3.30	315	4.10	590	4.90	1,004
2.60	144	3.40	346	4.20	630	5.00	1,080
2.70	163	3.50	379	4.30	672		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is fairly well defined between gage heights 2 feet and 4.3 feet.

Station rating table for Uncompahgre River at Montrose, Colo., from June 4 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	6	2.00	86	3.00	288	4.00	595
1.10	10	2.10	100	3.10	315	4.20	671
1.20	14	2.20	116	3.20	343	4.40	755
1.30	19	2.30	133	3.30	371	4.60	850
1.40	25	2.40	151	3.40	400	4.80	970
1.50	32	2.50	170	3.50	430	5.00	1,125
1.60	40	2.60	191	3.60	461	5.20	1,300
1.70	50	2.70	213	3.70	493	5.40	1,500
1.80	61	2.80	237	3.80	526	5.60	1,725
1.90	73	2.90	262	3.90	560	5.80	1,970

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is well defined between gage heights 2 feet and 4 feet. Below 1.9 the table is very uncertain. The table has been extended beyond these limits.

Estimated monthly discharge of Uncompahgre River at Montrose, Colo., for 1905.

[Drainage area, 565 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January (23 days)	108	82	93.1	4,247	.165	.141
February (22 days)	96	82	83.8	3,657	.148	.121
March	144	82	99.7	6,130	.176	.203
April	446	57	115	6,843	.204	.228
May	791	119	433	26,620	.766	.883
June	1,970	343	873	51,950	1.55	1.73
July	386	80	140	8,608	.248	.286
August	138	22	64.4	3,960	.114	.131
September	69	16	30.1	1,791	.053	.059
October	73	13	23.3	1,433	.041	.047
November	93	14	31.2	1,856	.055	.061
December	160	93	121	7,440	.214	.247
The period				124,500		

UNCOMPAHGRE RIVER AT DELTA, COLO.

his station was established April 29, 1903. It was originally located at a highway bridge fourth mile above the Denver and Rio Grande Railroad bridge, but on November 17, 3, the station was removed to the Denver and Rio Grande Railroad bridge, one-fourth northwest of the Denver and Rio Grande Railroad station, in order that the measured harge of the river might include the mill-ditch waste. Excluding the discharge of sea- l high water in May or June and an occasional rise from local storms, the water passing station is entirely seepage water from irrigation above.

he channel at the gage rod and the bridge below is a long gentle curve. The right bank f earth, is high and clean, and is not subject to overflow. The left bank is also of earth is clean; but it is low and may overflow during extreme high water. The bed of the am is composed of earth and fragments of rock and is fairly permanent. There is but channel at all stages. The current is sluggish at low and swift at high water. Gage hts range from 0.6 foot to 4 feet.

Discharge measurements were originally made from the highway bridge, to which the gage was attached, or by wading near the gage. From November 17, 1903, to May 2, 4, measurements were made from the Denver and Rio Grande Railroad bridge. After latter date measurements were made from the single-span road bridge 100 feet below the gage. The initial point for soundings is the face of the left abutment at the down- am side of the road bridge and is marked by a brass-headed nail in the hand rail. At -water measurements are made by wading near the bridge.

Gage readings at this station are made by Michael O'Rourke. The first gage at the rail- d bridge was a vertical rod nailed to a 12-inch pile on the downstream side of the bridge. ead from 1 foot to 6 feet. Readings were taken from this gage until April 21, 1904, when a gage was installed on the right bank 45 feet east of the center of the Denver and Rio nde Railroad track at the south approach to the bridge. There is no definite and constant ation between the new and old rods as the cross sections are not identical. The new gage n inclined rod, graduated up to 6 feet. The bottom of the rod rests on the river bottom and eld in place by six 2- by 4-inch timbers driven firmly into the bank. The bench mark for vertical gage was a cross on the top of the lower chord of the bridge over the gage rod; elevation was 8.75 feet above the zero of the gage. The bench mark for the inclined gage point marked with black paint and the letters "B. M.," on the surface of the northeast ner of the stone abutment where the south end of the steel bridge rests, on the down- eam side; elevation, 7.36 feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers the United States Geological Survey:

Description: 100, p 67; 133, pp 177-178.
Discharge: 66, p 98; 100, p 68; 133, p 178.
Discharge, monthly: 100, p 69; 133, p 180.
Gage heights: 100, p 68; 133, p 179.
Rating tables: 100, p 69; 133, pp 179-180.

Discharge measurements of Uncompahgre River at Delta, Colo., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
ril 12	R. I. Meeker	58	64	1.78	1.45	114
y 5	Oro McDermith	64	110	2.21	2.05	243
y 19	A. A. Weiland	64	179	4.95	3.30	887
y 31	do	64	145	3.23	2.42	469
ne 12	do	64	240	5.88	3.90	1,411
ne 26	do	64	122	2.93	2.22	358
ly 11	do	49	38	.53	.80	20
ly 31	do	47	40	.62	.90	[illegible]
tober 2	R. I. Meeker	50	44	.82	1.00	[illegible]

Daily gage height, in feet, of Uncompahgre River at Delta, Colo., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
1	1.6	1.57	2.0	1.47	2.62	2.92	1.48	1.14	0.76	0.99	0.8	1
2	1.8	1.58	2.22	1.52	3.08	3.28	1.32	.98	.72	.95	.81	1
3	1.74	1.64	2.07	1.61	2.94	3.44	1.06	.9	.71	.91	.82	1
4	1.8	1.69	2.08	1.45	2.39	3.66	.96	.84	.76	.88	.83	1
5	1.76	1.73	1.98	1.36	2.06	4.2	.92	.8	.87	.86	.84	1
6	1.8	1.66	1.84	1.23	1.78	4.2	.88	.82	.86	.78	.84	1
7	1.84	1.62	1.79	1.2	1.72	3.79	.78	.88	.87	.82	.86	1
8	.....	1.64	1.76	1.4	1.87	4.0	.81	.82	.8	.84	.86	1
9	.....	1.54	1.67	1.42	2.0	4.23	.81	.81	.81	.84	.84	1
10	.....	1.5	1.59	1.49	1.91	4.38	.8	.78	.84	.84	.83	1
11	.....	1.58	1.53	1.46	1.67	3.97	.8	.78	.84	.82	.82	1
12	.....	1.5	1.49	1.44	1.5	3.88	.77	.81	.79	.83	.84	1
13	.....	1.39	1.47	1.22	1.43	3.7	.78	.8	.78	.82	.86	1
14	.....	1.35	1.47	1.13	1.38	3.57	.76	.81	.76	.82	.85	1
15	.....	.....	1.49	1.13	1.32	3.54	.76	.79	.76	.82	.84	1
16	.....	.....	1.5	1.03	1.55	3.45	.74	.72	.76	.82	.85	1
17	.....	.....	1.53	1.04	2.52	3.15	.73	.69	.7	.8	.91	1
18	.....	.....	1.58	0.95	2.94	3.03	.71	.69	.77	.78	.9	1
19	.....	.....	1.5	.98	3.34	3.0	.7	.71	.78	.79	.89	1
20	.....	.....	1.5	1.06	3.54	2.8	.68	.72	.79	.83	.9	
21	.....	.....	1.56	.96	3.5	2.68	.68	.72	.82	.82	.91	
22	1.56	1.68	1.59	.87	3.54	2.43	.7	.73	.82	.81	.9	
23	1.6	1.66	1.59	.88	3.68	2.2	.74	.73	.83	.82	.86	
24	1.62	1.63	1.47	.87	3.76	2.22	.74	.73	.84	.83	.88	
25	1.61	1.66	1.45	.82	3.58	2.14	.69	.72	.78	.8	.93	...
26	1.62	1.69	1.46	.78	3.53	2.12	.66	.78	.92	.82	1.0	...
27	1.6	1.75	1.54	.76	3.41	2.08	.67	.77	.83	.82	1.13	...
28	1.56	1.85	1.58	1.65	3.26	2.04	.7	.74	.84	.84	1.25	...
29	1.5	.....	1.48	2.23	2.96	1.83	.68	.77	.84	.79	1.29	...
30	1.56	.....	1.47	2.42	2.59	1.7	.7	.77	.85	.78	1.26	...
31	1.56	.....	1.43	.....	2.56	.....	1.21	.76	.....	.8	.....	...

NOTE.—River frozen January 8 21 and February 15–21.

Station rating table for Uncompahgre River at Delta, Colo., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.60	3	1.60	150	2.60	535	3.60	1,145
.70	8	1.70	180	2.70	585	3.70	1,220
.80	15	1.80	210	2.80	640	3.80	1,295
.90	24	1.90	240	2.90	695	3.90	1,375
1.00	35	2.00	275	3.00	750	4.00	1,455
1.10	50	2.10	315	3.10	810	4.10	1,535
1.20	65	2.20	355	3.20	870	4.20	1,630
1.30	85	2.30	395	3.30	935	4.30	1,710
1.40	105	2.40	440	3.40	1,005	4.40	1,800
1.50	125	2.50	485	3.50	1,075		

NOTE.—The above table is applicable only for open-channel conditions. It is based on measurements made during 1904–1905, and is not well defined.

Estimated monthly discharge of Uncompahgre River at Delta, Colo., for 1905.

[Drainage area, 1,130 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
nuary 1–7; 22–31	222	125	167	5,631	0.148	0.094
bruary 1–14; 22–28	225	95	157	6,539	.139	.109
arch	363	111	161	9,900	.142	.164
pril	449	6	88.1	5,242	.078	.087
ay	1,265	89	597	36,710	.528	.609
ne	1,782	180	894	53,200	.791	.882
ly	121	6	21.0	1,291	.019	.022
gust	56	8	15.3	941	.014	.016
ptember	26	8	15.8	940	.014	.016
tober	34	14	18.1	1,113	.016	.018
vember	83	15	27.9	1,660	.025	.028
cember	254	119	156	7,426	.138	.123
The period				130,600		

MISCELLANEOUS MEASUREMENTS.

The following miscellaneous measurements were made in the Gunnison River basin in 905:

Miscellaneous discharge measurements made in Gunnison River drainage basin in 1905.

Date.	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Sec.-ft.*
ugust 10	Lotis Creek	Just above mouth	14	13	1.92	25
ugust 22	East River	1 mile below Brush Creek	40	34	1.88	64
ugust 22	Slate River	1 mile below Crested Butte, Colo.	60	34	1.12	38

COLORADO RIVER DRAINAGE BASIN BETWEEN JUNCTION OF GRAND AND GREEN RIVERS AND YUMA.

COLORADO RIVER.

DESCRIPTION OF RIVER.

From the junction of Grand and Green rivers the Colorado flows southwestward, passes across the northwestern corner of Arizona, then turns to the south and for the remainder of its course forms a part of the southeastern boundary of Nevada and California and the western boundary of Arizona. It empties into the Gulf of California about 60 miles below Yuma, Ariz. The canyons through which it flows are world famed and need not here be described.

The Colorado has been called the Nile of America, and like the Nile it is subject to an annual summer rise which comes at the time when it is most needed for irrigation. It is of interest to compare the Colorado with the Nile and Susquehanna rivers. The Nile being similar in type, the Susquehanna being contrasted and showing the difference in flow between arid and humid regions. In this comparison a normal year based upon records of the past ten years for the Colorado and Susquehanna rivers and such data as could be found in regard to the Nile has been *used. The Colorado* has been taken as the standard of comparison

The Nile has 5.7 times the drainage area and the Susquehanna about one-eighth the area. The rainfall in the Nile basin is 3.8 times greater; that in the Susquehanna basin is 4.1 times greater. The run-off per square mile from the Nile basin is 1.9 times greater; that from the Susquehanna basin is 37 times greater. The ratio of run-off to rainfall in the Nile basin is 2 times smaller; that of the Susquehanna basin is 8.2 times greater.

The discharge of the Nile is 10.8 times greater; that of the Susquehanna is 4.5 times greater.

The maximum flow of the Colorado is from 70,000 to 110,000 second-feet and occurs in May, June, or July; for the Nile it is about 353,000 second-feet and occurs about the first of September; for the Susquehanna it is from 200,000 to 400,000 second-feet and occurs during March, April, and May.

The minimum flow of the Colorado is from 2,500 to 3,000 second-feet and occurs during January and February; that of the Nile is about 14,500 second-feet and occurs about the end of May; for the Susquehanna it is from 2,500 to 5,000 second-feet and occurs in September and October.

The mean flow of the Colorado is about 10,700 second-feet; for the Nile it is about 115,800 second-feet; for the Susquehanna it is about 43,000 second-feet.

The water of the Colorado carries an immense amount of sediment, reaching as high as 2,000 parts of sediment to 100,000 parts of water. Prof. R. H. Forbes, in Bulletin No. 44, University of Arizona Agricultural Experiment Station, says:

> On the basis of the profile constructed from available data for the volume of flow of the Colorado, and of the year's silt determinations made in the laboratory, it is estimated conservatively that the river during 1900 brought down about 61,000,000 tons of sedimentary material, which, condensed to the form of solid rock, is enough to cover 26.4 square miles 1 foot deep, or to make about 164 square miles of recently settled, submerged mud 1 foot deep, reckoning the whole amount of mud for the year to average 4 times the bulk of the solid sediment.

A comparatively small amount of land is irrigated by the waters of the Colorado, owing to the fact that the stream and its tributaries are situated so far below the level of the irrigable lands as to render their diversion extremely difficult or impracticable. There are two pumping plants that lift water for irrigation at Yuma and several at other points on the river above Yuma. The Imperial canal diverts water from the river at a point about 10 miles by river below Yuma.

The principal tributaries of the Colorado below the Grand and Green are the San Juan, Little Colorado, Bill Williams Fork, and Gila rivers, which enter from the east, and the Virgin River, which enters from the west. With the exception of the Virgin and Bill Williams Fork rivers, these streams and their various tributaries are described in other parts of this report.

COLORADO RIVER AT HARDYVILLE, ARIZ.

This station was established May 11, 1905. It is maintained in cooperation with the State of California, and is located one-fourth mile above the deserted town of Hardyville and 7 miles above Fort Mohave, Ariz.

The right bank is composed of cemented gravel, is high, and is not subject to overflow. The left bank is made up of alluvial material, easily eroded, is low and wooded, and is liable to overflow at flood stages. The bed is composed of cemented gravel and changes gradually as the river falls from flood stage to low water, a bar forming in that portion of the section nearest the right bank and altering the section materially. There is but one channel at all stages. The flow ranges from 3,000 to 100,000 second-feet, with velocities of from 2 to 12 feet per second and a variation of probably 12 feet in gage heights.

Discharge measurements are made from a car and cable located 250 feet above the pumping plant of the Rattan mill. The initial point for soundings is the end of the turn-buckle farthest from the river on the Nevada side.

The gage, which was read once each day during 1905 by Marion Herrick, is located 100 feet below the cable on the left bank. The gage is in two sections: The lower section is an *inclined rod* fastened to posts buried in the bank; the upper section is a timber set verti

from the bank. The bench mark is the top of a 3-inch iron pipe buried in the gravel bank 100 feet from the river and 40 feet below the gage rod. Its elevation is 20.54 feet above the zero of the gage and 507.18 feet above sea level.

Discharge measurements of Colorado River at Hardyville, Ariz., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
May 17	O. W. Peterson	6.65	33,140	August 13	C. W. Jenkins	4.20	12,270
May 20	do	6.95	33,910	August 27	do	4.00	11,650
May 27	C. W. Jenkins	11.20	69,010	September 2	do	3.20	5,934
June 4	do	10.50	64,750	September 17	do	3.40	7,523
June 10	do	14.50	107,700	October 1	do	3.00	4,657
June 18	do	12.80	81,030	October 15	do	3.90	6,579
June 25	do	10.15	52,860	October 29	do	3.60	6,574
July 9	do	6.70	30,650	November 4	Jenkins and Lee	3.48	5,949
July 16	do	5.70	22,400	November 12	C. W. Jenkins	3.85	6,504
July 23	do	5.10	17,620	November 19	do	3.70	5,979
July 30	do	4.60	14,590	November 25	do	3.60	5,757
August 6	do	5.00	17,040	December 3	do	6.00	17,850

Daily gage height, in feet, of Colorado River at Hardyville, Ariz., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1		11.8	8.55	4.5	3.4	3.75	3.45	7.4
2		11.5	8.4	4.5	3.4	4.05	3.45	7.1
3		11.1	8.3	4.65	3.2	4.7	3.5	6.05
4		10.7	8.0	4.8	3.2	4.35	3.45	5.35
5		10.8	7.9	5.2	3.45	5.1	3.5	4.8
6		11.85	7.55	5.0	3.55	4.8	3.5	4.5
7		12.5	7.3	4.7	3.5	4.8	3.6	4.3
8		13.1	7.0	4.7	3.6	4.7	4.0	4.2
9		13.7	6.7	4.85	3.5	4.7	3.85	4.1
10		14.4	6.7	4.6	3.6	4.45	3.85	3.9
11	6.85	14.3	6.5	4.5	4.0	4.25	3.75	3.75
12	6.9	14.0	6.15	4.3	3.7	4.1	3.85	3.75
13	6.95	14.3	6.0	4.25	3.5	4.0	3.8	3.8
14	7.15	14.45	5.85	4.15	3.5	3.95	3.65	3.8
15	7.15	14.5	5.2	4.0	3.45	3.85	3.85	3.7
16	6.95	13.8	5.85	4.0	3.45	3.8	3.75	3.7
17	6.7	13.3	5.5	3.9	3.4	3.7	3.7	3.7
18	6.8	12.8	5.3	3.8	3.3	3.7	3.7	3.7
19	6.95	12.5	5.25	3.8	3.2	3.7	3.7	3.6
20	7.0	12.2	5.2	3.8	3.2	3.6	3.7	3.6
21	7.55	11.85	5.1	3.75	3.05	3.55	3.6	3.65
22	8.1	11.35	5.1	3.75	3.05	3.5	3.6	3.7
23	8.8	10.8	5.1	3.6	3.0	3.5	3.6	3.8
24	9.5	10.5	4.95	3.6	3.05	3.5	3.7	3.8
25	9.9	10.15	4.85	3.6	2.95	3.45	3.6	3.8
26	10.6	10.0	4.7	4.75	2.95	3.5	5.4	3.95
27	11.1	9.5	4.7	3.7	2.95	3.45	5.4	3.9
28	11.5	9.1	4.7	3.4	2.95	3.5	5.1	3.9
29	12.7	9.2	4.7	3.3	3.95	3.55	5.0	3.9
30	12.4	9.6	4.65	3.4	3.95	3.5	5.1	3.8
31	12.1	.....	4.6	3.4	.....	3.5	.....	3.8

Daily discharge, in second-feet, of Colorado River at Hardyville, Ariz., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	73,460	45,260	14,080	7,160	9,290	5,650	[illegible]
2	.....	70,700	44,020	14,080	7,160	11,600	5,700	[illegible]
3	.....	67,090	43,200	15,090	5,970	15,900	6,000	[illegible]
4	.....	63,550	40,750	16,110	5,970	13,100	5,750	[illegible]
5	.....	64,430	39,940	18,950	7,460	18,200	5,800	[illegible]
6	.....	73,920	37,120	17,500	8,065	15,600	5,500	[illegible]
7	.....	80,000	35,120	15,430	7,760	15,300	6,000	[illegible]
8	.....	85,780	32,750	15,430	8,370	14,300	8,500	[illegible]
9	.....	91,700	30,410	16,460	7,760	14,000	7,200	[illegible]
10	.....	98,780	30,410	14,750	8,370	12,000	7,000	[illegible]
11	31,580	97,760	28,850	14,080	10,850	10,300	6,000	[illegible]
12	31,970	94,700	26,160	12,770	8,980	8,900	6,500	[illegible]
13	32,360	97,760	25,000	12,440	7,760	7,900	6,200	[illegible]
14	33,940	99,290	23,840	11,800	7,760	7,200	5,200	[illegible]
15	33,940	99,800	18,950	10,850	7,460	6,200	6,700	[illegible]
16	32,360	92,700	23,840	10,850	7,460	6,000	6,100	[illegible]
17	30,410	87,740	21,180	10,200	7,160	5,300	5,800	[illegible]
18	31,190	82,880	19,690	9,600	6,560	5,600	5,900	[illegible]
19	32,360	80,000	19,320	9,600	5,970	5,600	5,980	[illegible]
20	32,750	77,180	18,950	9,600	5,970	5,200	6,000	[illegible]
21	35,520	73,920	18,220	9,290	5,090	4,850	5,400	[illegible]
22	41,560	69,340	18,220	9,290	5,090	4,800	5,500	[illegible]
23	47,330	64,430	18,220	8,370	4,800	4,800	5,600	[illegible]
24	53,230	61,810	17,150	8,370	5,090	5,050	6,350	[illegible]
25	56,640	58,790	16,460	8,370	4,515	4,700	5,760	[illegible]
26	62,680	57,500	15,430	15,770	4,515	5,400	17,800	[illegible]
27	67,090	53,230	15,430	8,980	4,515	5,050	17,300	[illegible]
28	70,700	49,840	15,430	7,160	4,515	5,700	14,500	[illegible]
29	81,920	50,680	15,430	6,560	10,540	6,050	13,200	[illegible]
30	79,060	54,080	15,090	7,160	10,540	5,900	13,300	[illegible]
31	76,240	.....	14,750	7,160	.....	5,900	.....	[illegible]

NOTE.—Rating table used May 11 to October 1. For the remainder of the period indirect method was used.

Estimated monthly discharge of Colorado River at Hardyville, Ariz., for 1905.

[Drainage area, 138,600 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
May 11 to 31	81,920	30,410	47,370	1,973,000	.342	.39
June	99,800	49,840	75,760	4,508,000	.547	.61
July	45,260	14,750	25,310	1,556,000	.183	.21
August	18,950	6,560	11,810	726,200	.085	.09
September	10,850	4,515	6,972	414,900	.050	.05
October	18,200	4,700	8,571	527,000	.062	.07
November	17,800	5,200	7,606	452,600	.055	.06
December	29,500	5,300	9,097	559,400	.066	[illegible]
The period	.....	.....	.....	10,720,000	.....	[illegible]

SAN JUAN RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

San Juan River rises among the snow masses that crown the high peaks of the San Juan mountains in southwestern Colorado, flows southwestward into New Mexico, then swings to the west and northwest, passing from San Juan County, N. Mex., across the extreme southwestern corner of Colorado into San Juan County, Utah, in the southwestern part of which it unites with the Colorado.

For the first 75 miles of its course the San Juan is a typical mountain stream, but at Canon Largo, N. Mex., where it turns westward, its character changes, and it occupies a broad-winding, sandy channel in an arid valley, bordered on each side by terraced mesas. Below the mouth of Mancos River the valley narrows and the river bottom is bounded by abrupt bluffs, broken and cut by dry water channels, and merging farther on into the walls of a deep, narrow, box canyon in which the river flows to its end.

The drainage area includes portions of four States and Territories. Its topography ranges in type from mountainous at the headwaters in Colorado to the types exemplified in the valleys, plateaus, and eroded mesas of Utah, New Mexico, and Arizona. Large areas of eruptive rocks occur in the highest portions of the basin, but the predominating formations are of sedimentary origin. The headwater streams are protected by fine forests of spruce and yellow pine and, at lower elevations, large areas of aspen. The lower basin is practically barren except for an extensive growth of sagebrush, scattered cedars, piñons, and range grasses.

The principal tributaries of the San Juan are Navajo, Piedra, Pine, Florida, Animas, and La Plata rivers, the Animas being the most important.

Animas River has its source in the region above Silverton, draining portions of the Needle and La Plata mountains, the former being the most rugged of the Rocky Mountain ranges. The river flows southward to the Colorado-New Mexico line and thence southwestward to the point where it joins the San Juan at Farmington, N. Mex. The upper portion of the basin, above Durango, is very mountainous and furnishes the greater part of the run-off. This region is generally well timbered with pine, spruce, and aspen, but large areas consist of naked granite peaks. Immediately above and below Durango the valley broadens and is bordered by mesas and bluffs cut by narrow canyons and covered with sagebrush and scattered pines and piñons; along the stream channels cottonwoods predominate. The rocks of this region are chiefly of sedimentary origin. The soils of the lower valleys consist of sandy loam and are very fertile.

La Plata River rises in the granite masses known as La Plata Mountains, about 25 miles northwest of Durango, Colo., and flows southward to its point of junction with the San Juan. Its drainage basin is a narrow strip parallel to and adjoining the Animas basin. The upper portion of the basin is a well-watered and forest-clad mountain region which merges southward into an arid mesa, plateau, and canyon country. La Plata Valley proper is a narrow, shallow depression from Hesperus down, bounded on both sides by high, broken table-lands and deeply eroded mountains. The lower mountain slopes are covered with piñon, scrub oak, and cedar; the lower valleys support heavy growths of sagebrush and chico; the upper mountain slopes were at one time heavily timbered with spruce and yellow and white pine, but these forests have been largely removed by lumbermen.

The other tributaries of the San Juan need not here be described. Those mentioned are perennial streams but much of their water is diverted for irrigation and never reaches the main river. In addition to the perennial streams are many intermittent creeks throughout New Mexico which contribute large volumes of water during heavy storms.

Much land is now under cultivation along the valleys of the San Juan, Animas, Pine, Florida, and La Plata rivers and the smaller tributaries in Colorado. Numerous small lakes high up in the mountains tend to equalize the flow of some of the tributaries, and many large and small storage-reservoir sites are available which will in time be developed.

One large power plant has been constructed in this basin and others are contemplated. The largest deposits of lignite and bituminous and coking coal to be found in the West are in the drainage area.

SAN JUAN RIVER NEAR FARMINGTON, N. MEX.

This station was established June 18, 1904. It is located near the Methodist Indian school about 3 miles south of Farmington, N. Mex., and about 2 miles below the mouth of Animas River.

The channel is straight for about 900 feet above and below the station. The right bank is a high sandstone cliff and can not overflow. The left bank at low water is a gravel bar extending out to 325 feet from the initial point for soundings, when it rises to a height of 6 feet; it probably never overflows beyond this point. The bed of the stream is composed of cobblestones, shale, and a few large, scattered bowlders. It is clean and permanent except on the left side where sand rests on the shale. There is but one channel at all stages. The current is swift at high and medium at low water. Gage heights range from 3 to 12 feet.

Discharge measurements were made from the suspension footbridge, which was carried away by the high water of 1905. Since then discharge measurements have been impracticable as there is no other bridge on the river.

The gage, which was read during 1905 by Elmer King, is a standard chain gage and is attached to a framework extending from the top of a sandstone cliff, about 15 feet above low water, on the right bank of the river, about 300 yards above the bridge. The gage scale is placed horizontally on the top of the cliff and is graduated from zero to 20 feet. The length of the wire from the end of the weight to the marker, which is a knot tied in the wire near the ring, is 20.79 feet. On May 23, 1905, a high-water gage, consisting of an inclined staff graduated to read from 8.6 to 16.4 feet, was set in the right bank about 150 feet below the wire gage. The bench mark is a cross, painted black and marked "U. S. G. S. B. M.," on the top of the sandstone cliff about 50 feet east of the gage. Its elevation above the datum of the wire gage, 12.79 feet. The top of the gage rod (above the brace) is 0.82 foot above the bench mark. The elevation of the bench mark above the datum of the new gage is 12.94 feet, and hence the datum of the new gage is 0.15 foot above the datum of the old gage.

A description of this station, with gage-height and discharge data, is contained in Water Supply Paper No. 133, United States Geological Survey, pp. 180–183.

A measurement made by M. C. Hinderlider May 23, 1905, gave the following results: Width, 302 feet; area, 1,764 square miles; mean velocity, 9.73 feet per second; gage height, 10.55 feet; discharge, 17,170 second-feet.

Daily gage height, in feet, of San Juan River near Farmington, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	3.22	3.3	4.15	4.18	7.0	10.05	7.4	5.55	4.25	5.95	4.22	
2	3.35	3.4	4.25	4.32	7.5	10.7	6.15	5.3	4.28	5.5	4.25	
3	3.3	3.35	4.75	4.4	7.25	12.4	6.05	5.0	4.22	5.12	4.2	
4	3.25	3.35	5.1	4.15	6.9	12.25	6.0	4.95	4.32	4.85	4.22	
5	3.3	3.75	5.0	4.15	6.75	12.35	6.0	4.95	4.68	4.75	4.2	
6	3.15	3.08	4.95	4.35	6.6	13.1	5.85	4.9	4.65	4.55	4.22	
7	3.2	3.55	5.4	4.5	6.4	11.65	5.6	4.8	4.62	4.52	4.25	
8	3.3	3.58	5.05	4.88	6.35	11.8	5.85	4.7	4.65	4.48	4.32	
9	3.22	3.5	4.6	4.75	6.2	12.0	5.8	4.65	4.58	4.48	4.22	
10	3.3	3.55	4.45	5.0	6.4	11.9	5.65	4.55	4.55	4.55	4.2	
11	3.22	3.45	4.15	6.95	6.3	12.0	5.6	4.7	4.55	4.52	4.15	
12	3.1	3.85	4.25	7.1	6.05	12.05	5.45	4.7	4.55	4.45	4.2	
13	3.1	3.2	4.15	6.35	5.95	11.9	5.4	4.8	4.5	4.48	4.15	

ily gage height, in feet, of San Juan River near Farmington, N. Mex., for 1905—Cont'd.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
4	3.12	3.35	4.15	6.15	6.05	11.6	5.25	4.7	4.5	4.48	4.18	4.18
5	2.75	3.35	4.55	6.22	6.1	11.4	5.15	4.55	4.45	4.45	4.2	4.15
6	3.25	3.25	4.55	6.35	6.7	11.4	5.2	4.45	4.45	4.42	4.2	4.2
7	3.3	3.3	4.6	6.0	7.65	11.75	5.15	4.4	4.42	4.4	4.22	4.2
8	3.35	3.35	4.8	5.9	8.0	10.6	5.1	4.35	4.38	4.38	4.2	4.12
9	3.35	3.4	4.7	5.95	8.35	10.7	5.15	4.25	4.32	4.38	4.2	4.15
10	3.1	3.4	4.7	5.95	8.75	10.75	5.1	4.12	4.32	4.3	4.2	4.2
11	3.15	3.4	4.65	5.8	8.8	9.9	5.05	4.08	4.35	4.28	4.15	4.2
12	3.38	3.8	4.48	5.95	8.1	10.05	5.2	4.05	4.3	4.3	4.6	4.1
13	3.2	5.02	4.0	6.75	11.2	10.0	5.1	3.95	4.28	4.28	4.4	3.95
14	3.2	4.95	3.9	7.0	11.05	9.85	5.05	4.65	4.3	4.28	4.2	4.0
15	3.25	4.85	4.12	6.55	11.1	9.75	5.05	4.52	4.58	4.3	4.15	3.98
16	3.2	4.25	4.18	6.15	10.85	9.55	4.85	4.1	4.6	4.22	4.18	4.0
17	3.2	3.95	4.42	6.1	11.0	9.6	4.82	4.15	4.62	4.28	4.9	4.12
18	3.2	4.0	4.2	6.55	10.15	9.55	4.9	4.28	4.6	4.28	5.08	4.2
19	3.22	.....	4.15	6.8	9.95	8.45	4.95	4.25	4.62	4.3	4.75	4.0
20	3.2	.....	4.2	6.7	9.55	8.4	6.25	4.4	6.05	4.25	4.15	4.05
21	3.2	.....	4.15	.....	9.55	.....	5.65	4.2	.....	4.28	.....	3.95

tation rating table for San Juan River near Farmington, N. Mex., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.70	25	4.00	900	5.60	3,850	8.20	10,400
2.80	55	4.10	1,020	5.80	4,290	8.40	10,960
2.90	90	4.20	1,150	6.00	4,750	8.60	11,520
3.00	130	4.30	1,300	6.20	5,230	8.80	12,080
3.10	180	4.40	1,450	6.40	5,710	9.00	12,640
3.20	230	4.50	1,610	6.60	6,200	9.50	14,050
3.30	290	4.60	1,780	6.80	6,700	10.00	15,500
3.40	350	4.70	1,950	7.00	7,200	10.50	17,000
3.50	420	4.80	2,140	7.20	7,720	11.00	18,500
3.60	500	4.90	2,340	7.40	8,240	11.50	20,000
3.70	580	5.00	2,540	7.60	8,780	12.00	21,500
3.80	680	5.20	2,970	7.80	9,320	12.50	23,000
3.90	780	5.40	3,410	8.00	9,860	13.00	24,500

OTE.—The above table is applicable only for open-channel conditions. It is based on 13 discharge surements made during 1904, and one h.gh-water measurement made during 1905. Low-water est'-es based on this table are therefore uncertain. The table has been extended beyond these limits.

Daily gage height, in feet, of Animas River at Durango, Colo., for 1905.

Day.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	7.6	9.9	11.9	9.0	8.2	7.0	7.8	6.8	6.7
2	7.8	10.4	12.05	8.7	8.0	7.0	7.7	6.8	6.7
3	7.8	10.0	12.3	8.7	8.0	7.0	7.5	6.7	6.6
4	8.0	9.6	12.6	8.6	8.0	7.0	7.5	6.7	6.6
5	8.1	9.4	12.45	8.4	8.0	7.0	7.5	6.7	6.6
6	8.2	8.6	12.0	8.4	8.0	7.0	7.3	6.7	6.6
7	8.2	8.6	12.0	8.4	7.9	7.0	7.3	6.7	6.6
8	8.4	8.7	12.5	8.4	7.7	7.0	7.2	6.7	6.6
9	8.4	8.7	11.9	8.4	7.7	7.0	7.2	6.7	6.6
10	8.5	8.7	11.8	8.3	7.5	7.0	7.0	6.7	6.6
11	8.6	8.8	11.6	8.3	7.6	7.0	7.0	6.7	6.6
12	8.6	8.7	11.7	8.1	7.6	6.9	7.0	6.7	6.6
13	8.7	8.8	11.7	8.0	7.5	6.9	7.0	6.7	6.6
14	8.6	9.0	11.5	8.0	7.3	6.9	7.0	6.7	6.6
15	8.6	9.3	11.5	8.0	7.3	6.9	7.0	6.7	6.6
16	8.7	9.5	11.3	8.0	7.2	6.9	6.9	6.6	6.6
17	8.8	10.2	11.4	8.0	7.2	6.9	6.9	6.6	6.6
18	9.0	11.2	11.4	8.0	7.1	6.8	6.9	6.6	6.6
19	8.9	11.3	11.3	8.0	7.1	6.8	6.9	6.7	6.6
20	8.9	11.4	11.3	8.1	7.0	6.8	6.9	6.7	6.6
21	8.9	11.6	11.1	8.2	7.0	6.8	6.8	6.7	6.6
22	8.8	11.5	11.2	8.2	7.0	6.8	6.8	6.7	6.6
23	8.9	11.8	10.8	8.2	7.0	6.8	6.8	6.7	6.6
24	9.1	11.8	10.5	8.0	7.2	6.8	6.8	6.7	6.6
25	9.4	11.6	10.3	7.8	7.0	6.9	6.8	6.7	6.6
26	9.3	11.85	10.0	7.8	7.0	6.8	6.8	6.7	6.6
27	9.3	11.5	9.6	7.8	7.0	7.0	6.8	6.7	6.6
28	9.6	11.1	9.5	8.0	7.0	7.2	6.8	6.7	6.6
29	9.8	10.7	9.1	8.6	7.0	9.0	6.8	6.7	.....
30	9.8	11.25	9.0	9.0	7.0	7.8	6.9	6.7	.....
31	.....	11.6	.....	8.7	7.0	.....	6.9	.....	.....

Station rating table for Animas River at Durango, Colo., from April 1 to June 4, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
7.60	550	8.70	1,340	9.80	2 980	10.90	4,970
7.70	600	8.80	1,450	9.90	3,150	11.00	5,160
7.80	650	8.90	1,570	10.00	3,320	11.20	5,550
7.90	700	9.00	1,700	10.10	3,490	11.40	5,950
8.00	760	9.10	1,840	10.20	3,670	11.60	6,350
8.10	820	9.20	1,990	10.30	3,850	11.80	6,750
8.20	890	9.30	2,150	10.40	4,050	12.00	7,150
8.30	960	9.40	2,310	10.50	4,210	12.20	7,590
8.40	1,040	9.50	2,470	10.60	4,400	12.40	8,030
8.50	1,130	9.60	2,640	10.70	4,590	12.60	8,470
8.60	1,230	9.70	2,810	10.80	4,780		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1903-1905. It is very poorly defined. Estimates based upon it are roughly approximate.

ge read zero when the vertical gag. read 5 feet. All 1903 readings were reduced
m of the vertical gage.
on was discontinued December 31, 1905.
on in regard to this station is contained in the following publications of the
tes Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-
er):

1: Ann 18, iv, pp 283-284; Bull 140, pp 198-199; WS 16, p 146; 28, p 132; 38, p 310; 50, p 383; 66, 5-36; 100, pp 51-52; 133, pp 183-184.
Ann 18, iv, p 284; Bull 140, p 199; WS 16, p 146; 28, p 142; 38, p 310; 50, p 383; 66, p 97; 85, p 133, p 185.
monthly: Ann 18, iv, p 285; 19 iv, p 414; 20, iv, pp 379, 403; 21, iv, p 301; 22, iv, p 394; WS 54; 133, p 186.
yearly: Ann 20, iv, p 59.
ts: Bull 140, p 200; WS 11, p 72; 16, p 146; 28, p 139; 38, p 311; 50, p 384; 66, p 97; 85, p 36; p 185.
hs: Ann 18, iv, p 285; 19, iv, p 415; 20, iv, p 403; 21, iv, p 301; 22, iv, p 394.
d run-off relation: Ann 20, iv, p 379.
les: Ann 18, iv, p 284; 19, iv, p 414; Bull 140, p 199; WS 28, p 145; 39, p 452; 52, p 520; 66, p 100, p 53; 133, p 186.

Discharge measurements of Animas River at Durango, Colo., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
M. C. Hinderlider	89	195	6.14	8.70	1,198
do	189	513	6.49	10.00	3,330
do	189	756	6.85	11.00	5,179
O. H. Timmerman	183	648	4.32	8.75	2,703
do	158	435	3.04	7.90	1,321
do	158	446	3.05	7.93	1,360
do	158	448	3.16	8.00	1,417
do	163	509	3.80	8.30	1,935
do	156	407	2.50	7.75	1,017
do	143	296	1.99	7.00	590
do	143	273	1.92	6.90	525
do	143	281	1.84	7.05	516
do	143	239	1.64	6.90	391
do	143	223	1.59	6.86	355
do	143	244	1.62	6.90	396
do	143	318	2.17	7.38	690
do	163	440	3.66	8.04	1,514
do	163	434	3.33	7.96	1,447
do	163	390	2.71	7.80	1,057
do	163	382	2.74	7.78	1,048
do	160	370	2.54	7.64	939
do	158	362	2.56	7.61	928
do	158	324	2.32	7.42	757

A standard chain gage, which is read twice each day by Mrs. Adellie Ricketts, is attached to the downstream side of the bridge, 40 feet from the left end. The gage scale is graduated from 2 to 7.8 feet. The length of the chain is 12.78 feet. The bench mark is a United States Geological Survey standard bench-mark tablet set into the southwest face of a 12-inch cottonwood tree about 50 feet north of the right end of the bridge; its elevation is 11.13 feet above the datum of the gage and 3.17 feet below the top of the horizontal bridge chord on which the gage box rests.

A description of this station, with gage-height and discharge data, is contained in Water Supply Paper No. 133, United States Geological Survey, pp. 191–195.

Discharge measurements of Animas River near Farmington, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 24	M. C. Hinderlider	179	849	7.72	8.34	6,5[illegible]
July 6	O. H. Timmerman	144	449	3.59	6.25	1,61[illegible]
July 20	do	141	323	2.71	5.35	87[illegible]
July 27	do	141	280	2.45	5.05	68[illegible]
August 2	do	146	399	3.40	5.82	1,35[illegible]
August 9	do	126	286	2.56	5.10	73[illegible]
August 21	do	112	172	1.31	4.22	22[illegible]
August 24	do	107	139	1.00	3.92	12[illegible]
August 24	do	107	136	1.00	3.92	13[illegible]
August 26	do	75	122	.93	3.90	11[illegible]
August 26	do	75	120	.93	3.90	11[illegible]
September 12	do	107	139	1.62	4.19	22[illegible]
October 8	do	137	269	2.26	5.02	61[illegible]

Daily gage height, in feet, of Animas River near Farmington, N. Mex., for 1905.

Day	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
1	4.53	4.47	4.92	5.34	7.08	8.29	7.32	6.03	3.84	6.4
2	4.59	4.56	5.2	5.3	7.26	8.8	7.06	5.78	3.81	5.94
3	4.51	4.5	5.2	5.24	6.99	9.29	6.78	5.64	3.76	5.66
4	4.5	4.59	5.37	5.22	6.64	9.4	6.6	5.58	3.82	5.44
5	4.48	4.52	5.43	5.25	6.38	9.75	6.54	5.5	4.26	5.34
6	4.48	4.44	5.56	5.3	6.19	9.72	6.36	5.46	4.47	5.22
7	4.57	4.37	5.66	5.52	6.18	9.55	6.2	5.37	4.38	5.14
8	4.46	4.32	5.66	5.77	6.27	9.7	6.2	5.2	4.34	5.04
9	4.49	4.22	5.36	5.88	6.4	9.6	6.08	5.05	4.3	4.96
10	4.38	4.16	5.3	5.89	6.46	9.3	5.92	4.94	4.22	4.95
11	4.38	4.28	5.3	5.92	6.37	9.12	5.8	4.94	4.18	4.93
12	4.3	4.28	5.26	6.6	6.22	9.02	5.7	5.05	4.16	4.86
13	4.36	4.2	5.22	6.3	6.3	9.0	5.56	5.0	4.18	4.81
14	4.32	4.06	5.28	6.1	6.4	8.91	5.42	4.9	4.11	4.76
15	4.3	4.28	5.48	5.85	6.46	8.88	5.58	4.78	4.16	4.68
16	4.3	4.18	5.32	5.9	6.8	9.04	5.7	4.71	4.14	4.6
17	4.34	4.3	5.28	5.94	7.32	8.68	5.51	4.66	4.07	4.58
18	4.38	4.3	5.36	5.91	7.67	8.52	5.4	4.53	4.0	4.57
19	4.38	4.33	5.54	5.92	7.82	8.49	5.35	4.41	3.96	4.54
20	4.36	4.3	5.52	5.9	7.98	8.36	5.32	4.36	3.96	4.5
21	4.48	4.34	5.46	5.91	8.02	8.14	5.38	4.28	3.94	4.47
22	4.31	4.32	5.36	5.92	7.98	8.0	5.33	4.16	3.94	4.46
23	4.26	4.42	5.3	6.05	8.1	7.84	5.38	4.07	3.93	4.48

ily gage height, in feet, of Animas River near Farmington, N. Mex., for 1905—Continued.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.
4	4.24	4.58	5.2	6.3	8.35	7.9	5.3	3.96	3.92	4.47
5	4.26	4.75	5.16	6.13	8.54	7.84	5.2	3.91	4.04	4.46
6	4.24	4.84	5.23	6.12	8.58	7.72	5.14	3.92	4.55	4.4
7	4.4	4.75	5.33	6.04	8.63	7.72	5.06	4.05	4.4	4.36
8	4.39	4.68	5.4	6.26	8.38	7.7	5.06	4.04	4.38	4.35
9	4.39	.....	5.29	6.49	8.02	7.59	5.09	3.96	4.47	4.34
0	4.36	.....	5.3	6.75	7.56	7.48	6.23	3.91	6.5	4.33
1	4.34	.....	5.3	.....	7.75	.....	6.4	3.88	.....	4.33

tion rating table for Animas River near Farmington, N. Mex., from October 20, 1904, to May 16, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.20	125	5.00	450	5.80	1,145	6.60	2,400
4.30	150	5.10	510	5.90	1,265	6.70	2,580
4.40	177	5.20	580	6.00	1,385	6.80	2,760
4.50	208	5.30	655	6.10	1,530	6.90	2,940
4.60	243	5.40	735	6.20	1,700	7.00	3,120
4.70	287	5.50	825	6.30	1,870	7.10	3,300
4.80	337	5.60	925	6.40	2,040	7.20	3,485
4.90	390	5.70	1,030	6.50	2,220	7.30	3,670

OTE.—The above table is applicable only for open-channel conditions. It is based on 7 discharge asurements made after October 25, 1904, and is well defined.

tion rating table for Animas River near Farmington, N. Mex., from May 17 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.70	65	4.90	570	6.10	1,665	7.60	4,560
3.80	95	5.00	630	6.20	1,800	7.80	5,055
3.90	125	5.10	695	6.30	1,945	8.00	5,575
4.00	155	5.20	765	6.40	2,100	8.20	6,135
4.10	190	5.30	840	6.50	2,265	8.40	6,735
4.20	225	5.40	920	6.60	2,435	8.60	7,370
4.30	265	5.50	1,005	6.70	2,615	8.80	8,025
4.40	310	5.60	1,095	6.80	2,800	9.00	8,700
4.50	355	5.70	1,195	6.90	2,995	9.20	9,380
4.60	405	5.80	1,300	7.00	3,200	9.40	10,060
4.70	455	5.90	1,415	7.20	3,630	9.60	10,740
4.80	510	6.00	1,535	7.40	4,085		

OTE.—The above table is applicable only for open-channel conditions. It is based on discharge asurements made during 1904–1905. It is well defined between gage heights 3.9 feet and 5.8 feet.

Estimated monthly discharge of Animas River near Farmington, N. Mex., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	239	135	176	10,820
February	358	95	186	10,330
March	988	402	695	42,730
April	2,670	595	1,338	79,620
May	7,468	1,666	3,962	243,600
June	11,250	4,273	7,655	455,300
July	3,901	669	1,448	89,000
August	1,574	119	534	32,830
September	2,265	83	275	16,360
October	2,100	278	576	35,420
The period				1,016,000

LA PLATA RIVER AT HESPERUS, COLO.

This station was established June 14, 1904, in connection with investigations relating to the La Plata project in New Mexico. It is located at the highway bridge on the west side of Hesperus, Colo.

The channel is straight for about 50 feet above and below the station. Both banks are low and covered with brush and scattered trees, but neither is liable to overflow. The bed of the stream is composed of large and small cobblestones, but is not permanent. A small island above the bridge, dead water at low stages, and a tortuous channel below the bridge affect the accuracy of meter measurements at the bridge. The current is swift. The fall of the river, according to levels run by the La Plata Ditch Company for about 10 miles, is 135 feet per mile. Gage heights range from 0.8 foot to 3.5 feet.

Discharge measurements are made by wading at suitable points along the stream at low stages, as the conditions at the bridge are at some stages unfavorable to careful gagings. At high stages measurements are made from the wooden wagon bridge on the west side of Hesperus. The initial point for soundings is a nail driven into the downstream side of the wagon bridge over the south face of the north abutment.

The gage was read twice daily during 1905 by Fred Harrison. The original gage was a 4-foot board graduated from zero to 3.9 feet. This gage was spiked to the upstream end of the south face of the north abutment, with the zero mark resting on the bed of the river. The bench mark is a nail driven horizontally into the west face of a 12-inch cottonwood tree about 8 inches above the ground, about 75 feet northeast of the gage rod, on the right bank of the river; elevation, 9.15 feet above the zero of the gage. On account of the boiling action of the water at this gage, a new staff gage was installed on April 26, 1905. The new gage is graduated from zero to 5.2 feet and is spiked in a vertical position to the south face of the north abutment on the downstream side of the bridge. The datum of the new gage is not the same as that of the old, being 8.09 feet below the above bench mark.

On August 20, 1905, it was found necessary to transfer this gage to the north face of the south abutment downstream side of the bridge where it is now located. Elevation of gage datum same as that last described, viz, 8.09 feet below the bench mark.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 133, United States Geological Survey, pp. 195-196.

harge measurements of La Plata River at Hesperus, Colo., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
M. C. Hinderlider	29	35	2.86	1.20	100
O. H. Timmerman	29	32	3.94	1.70	126
do	29	33	3.85	1.70	127
do	29	19	2.29	1.25	44
do	29	16	2.60	1.15	42
do	29	21	2.90	1.31	61
do	29	19	2.39	1.28	45
do	23	11	1.51	.95	16
do	16	28	.96	1.00	27
do	29	24	2.67	1.70	63
do	29	21	2.53	1.55	54

e heights refer to datum of April 26, 1905.

ily gage height, in feet, of La Plata River at Hesperus, Colo., for 1905.

ay.	Apr.	May.	June.	July.	Aug.	Sept.	Oct	Nov.	Dec.
		1.92	2.7	1.9	1.25	0.92	1.32	0.92	1.18
		1.88	2.85	1.9	1.2	.92	1.22	.9	1.3
		1.62	2.85	1.75	1.2	.92	1.18	.9	1.1
		1.5	3.15	1.68	1.18	1.0	1.18	.9	1.0
		1.3	2.85	1.65	1.18	.92	1.18	.9	1.0
		1.25	2.8	1.55	1.18	.92	1.18	.9	.95
		1.22	2.9	1.48	1.15	.92	1.12	.95	.9
		1.5	3.1	1.45	1.1	.92	1.12	.88	.9
		1.48	2.9	1.35	1.02	.92	1.1	.85	.85
		1.32	2.9	1.35	1.02	.92	1.1	.85	.85
		1.38	2.8	1.3	1.02	.92	1.1	.85	.85
		1.4	2.85	1.22	1.02	.92	1.1	.9	.85
		1.4	2.8	1.22	1.0	.92	1.1	.9	.88
		1.45	2.95	1.22	1.0	.92	1.1	.85	.88
		1.68	3.3	1.2	1.0	.92	1.1	.85	.85
		1.9	3.0	1.18	.98	.9	1.1	.85	.85
		2.0	2.9	1.18	.98	.9	1.05	.85	.82
		2.18	2.75	1.12	.92	.9	1.0	.9	.8
		2.45	2.5	1.12	.92	.9	1.0	.8	.8
		2.15	2.55	1.15	.92	.9	1.0	.8	.8
		2.25	2.45	1.15	.92	.9	1.0	.85	.8
		2.6	2.45	1.15	.92	.9	1.0	.9	.75
		2.35	2.45	1.12	.92	.9	1.0	.92	.75
		2.45	2.35	1.15	.92	.9	1.0	1.05	.7
		2.65	2.35	1.1	.92	.9	1.0	1.1	.7
	1.35	2.85	2.35	1.1	.92	.9	1.0	1.1	.95
	1.38	2.4	2.25	1.12	.92	.9	.95	1.12	.78
	1.6	2.3	2.15	1.1	.92	.9	.95	1.15	.5
	1.65	2.3	2.05	1.32	.92	1.02	.95	1.1	.5
	1.78	2.4	2.0	1.3	.92	1.55	.92	1.15	.5
		2.65		1.3	.92		.9		.45

e heights refer to datum of April 26, 1905.

LA PLATA RIVER NEAR LA PLATA, N. MEX.

This station was established June 1, 1905, in connection with investigations relating to the La Plata project. It is located on the single-span wooden highway bridge 1 mile southeast of La Plata post-office, N. Mex., in sec. 3, T. 31, R. 13 W., below all points of diversion.

The channel is straight for 50 feet above the bridge, beyond which it bends to the right; below the bridge it is straight for 300 feet. The left bank is well defined but is liable to overflow at high stages. During high water the right bank overflows below the bridge but does not overflow above. Both banks are lined with sagebrush and willows. There is but one channel at all stages. Gage heights range from 1 foot to 4.5 feet. At gage height of 1 foot the river is dry.

Discharge measurements are made from the downstream side of the bridge.

The gage, which was read twice each day during 1905 by Frank Williams, is a vertical staff graduated from 3 to 10.1 feet, spiked to the northwest corner of the east abutment of the bridge. The 3-foot mark rests on the bed of the stream and the 9.4-foot mark is even with the surface of the bridge floor. The gage is referred to bench marks as follows: (1) The head of a 20-penny spike driven vertically into the top of the second log from the bottom at the northeast corner of Mr. Williams's house; elevation, 21.37 feet above the zero of the gage. (2) A nail driven into the spur root on the south side of a cottonwood tree southeast of house; elevation, 19.47 feet above the zero of the gage.

Discharge measurements of La Plata River near La Plata, N. Mex., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
May 25	M. C. Hinderlider	36	107	5.22	4.40	559
July 7	O. H. Timmerman				1.10	a3
July 10	do					a.4
July 26	do					a2.0

a Estimated.

Daily gage height, in feet, of La Plata River near La Plata, N. Mex., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1		3.49	2.32	(a)	(a)	4.11	(a)	1.3
2		3.78	1.84	(a)	(a)	3.86	(a)	1.3
3		3.92	1.46	(a)	(a)	3.62	(a)	1.3
4		4.01	1.09	(a)	(a)	3.08	(a)	1.3
5		4.26	1.14	(a)	(a)	1.74	1.52	1.3
6		3.42	1.09	(a)	(a)	1.14	(a)	1.3
7		4.32	1.09	(a)	(a)	(a)	(a)	1.2
8		4.51	1.14	(a)	(a)	(a)	(a)	1.2
9		3.72	1.14	(a)	(a)	(a)	(a)	1.2
10		3.48	1.09	(a)	(a)	(a)	(a)	1.2
11		3.77	1.09	(a)	(a)	(a)	(a)	1.2
12		3.67	1.09	(a)	(a)	(a)	(a)	1.2
13		4.36	1.09	(a)	(a)	(a)	(a)	1.2
14		3.47	(a)	(a)	(a)	(a)	(a)	1.2
15		3.57	(a)	(a)	(a)	(a)	(a)	1.2
16		3.47	(a)	(a)	(a)	(a)		

a Standing in pools.

height, in feet, of La Plata River near La Plata, N. Mex., for 1905—Continued.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
		3.37	(a)	(a)	(a)	(a)	(a)	1.2
		3.27	(a)	(a)	(a)	(a)	(a)	1.2
		3.22	1.44	(a)	(a)	(a)	(a)	1.2
		3.07	(a)	(a)	(a)	(a)	(a)	1.2
		2.98	(a)	(a)	(a)	(a)	(a)	1.2
		2.83	(a)	(a)	(a)	(a)	(a)	1.2
		2.79	(a)	(a)	(a)	(a)	(a)	1.2
		2.6	(a)	(a)	(a)	(a)	(a)	1.2
	4.33	2.46	(a)	(a)	(a)	(a)	1.20	1.2
	4.28	2.49	1.84	(a)	(a)	(a)	(a)	1.2
	3.76	2.42	1.39	(a)	(a)	(a)	1.48	1.2
	3.77	2.42	1.19	(a)	(a)	(a)	1.32	1.2
	3.37	2.22	1.09	(a)	4.4	(a)	1.3	1.2
	3.2	2.22	1.09	(a)	4.36	(a)	1.3	1.2
	3.28		(a)			(a)		1.2

a Standing in pools.

MISCELLANEOUS MEASUREMENTS.

owing miscellaneous measurements were made in the San Juan basin in 1905:

neous discharge measurements made in San Juan River drainage basin in 1905.

	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Sec.-ft.*
....	Boyle ditch	Hesperus, Colo	4	3.4	3.59	12.2
2...	.....do	.....do		1.5	1.00	1.5
....	.....do	.....do				.2
18..	.....do	Kline, Colo				.00
....	Brown Bros. ditch	Hesperus, Colo				.3
18..	.....do	.....do		1.5	1.00	1.5
....	Enterprise ditch	La Plata, Colo				(a)
18..	Fort Lewis ditch No.1.	Fort Lewis, Colo		2.0	1.00	b2
....	Fort Lewis ditch No.2.	.....do		1.0	1.00	b1
....	Fort Lewis ditch	Hesperus, Colo		.8	1.00	.8
....	Freed ditch	Kline, Colo				(a)
18..	.....do	.....do				(a)
....	Green canal	.....do				(a)
....	H. and H. ditch	Hesperus, Colo	4.7	4.2	1.02	4.3
18..	.....do	.....do		2.0	1.00	b2
....	Hay Gulch ditch	.....do	5	5.8	2.48	14.41
2...	.....do	.....do	4	3.2	1.91	6.1
7...	.....do	.....do	5.6	3.01	5.28	15.92
30..	.....do	.....do	5.6	5.0	4.42	22.1
....	Helton ditch	Kline, Colo	4	2.0	1.10	2.2
18..	.....do	.....do				(a)
....	Indian ditch	Hesperus, Colo		1.0	.75	.8
....	Kellar ditch	.....do				(a)
....	La Plata canal	.....do				8.8
....	.....do	.....do	10	9.2	.66	6.1
....	.....do	.....do	4	2.8	2.29	6.4

a Dry. b Estimated.

Miscellaneous discharge measurements made in San Juan River drainage basin in 1905—Continued.

Date.	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Sec.-ft.*
July 17	La Plata canal	Hesperus, Colo	4	1.6	1.75	2.8
July 29	do	do	4	2.4	2.42	5.8
August 5	do	do	4	1.6	1.06	1.7
September 2	do	do	4	2.4	1.21	2.9
September 4	do	do	4	2.0	1.35	27.1
July 15	La Plata and Cherry Creek ditch.	do	4.8	3.4	5.68	19.93
September 2	do	do		2.0	1.0	[a]2.0
September 30	do	do				[b]
October 4	do	do				[b]
April 25	Lightner Creek	Durango, Colo				17.7
July 14	do	do				[a]6.5
July 31	do	do				[a]6
August 7	do	do				[a]7
September 9	do	do				[a]9
September 15	do	do				[a]7
September 20	do	do				[a]6
October 1	do	do				[a]7
October 4	Placer ditch	Hesperus, Colo				[b]
July 15	Parrott ditch	do				[b]
September 16	do	do				[b]
October 4	do	do				[b]
September 30	Parrott City canal	Parrott City, Colo				[b]
September 2	Ramott canal	Hesperus, Colo				[b]
July 18	Revival ditch		2	1.0	1.00	1.00
July 17	Short Line ditch	Hesperus, Colo	4	1.2	.92	1.1
September 18	do	Kline, Colo				[b]
July 17	Slate ditch		8	4.8	2.17	10.4
July 18	Stinebaugh ditch					[b]
September 5	Steinmegger canal	Hesperus, Colo				[b]
July 17	Trainor ditch	Kline, Colo				[a].5
September 18	do	do				[b]
Do	Ute Indian ditch	Fort Lewis, Colo				[b]
July 18	Warren ditch					[b]

[a] Estimated.

[b] Dry.

LITTLE COLORADO RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

ɔuntry drained by the Little Colorado River consists of a high plateau with an ele-
ıver 4,000 feet above sea level, extending from the Continental Divide in north-
New Mexico westward to the San Francisco Mountains in Arizona, and from the
'anyon of the Colorado southward to the Mogollon Mesa. The greater part of this
is composed of rolling plains with a few feet of soil at the surface underlain by
Through this plateau the river winds northwestward to its junction with the great
).

un-off from approximately 6,000 square miles of the drainage area finds its way
Little Colorado above the mouth of Rio Puerco, the largest tributary which joins
ı stream 2 miles above the town of Holbrook, Ariz. Both the Little Colorado and
Puerco are flashy streams, seldom clear even during low stages. They have shifting,
ottoms, and when not confined in canyons the stream beds are wide with abrupt
ınks. The discharge fluctuates greatly, being insignificant in dry seasons. The
e short and violent and carry large quantities of silt in suspension.

LITTLE COLORADO RIVER AT WOODRUFF, ARIZ.

ıtation was established March 16, 1905. It is located about 100 yards below the
of the Holbrook-Winslow wagon road and one-fourth mile below the Woodruff dam.
hannel is straight for 300 feet above and 100 feet below the station. The banks are
th some brush, and neither is liable to overflow. The bed of the stream is composed
The current is swift at high and medium stages of water.
arge measurements are made by means of a cable, car, and tag wire. The initial
r soundings is the iron hook on the chain connecting the cable with anchorage on
rest bank of stream.
age is observed twice each day by R. L. Newman. The original gage was a com-
ɪrtical and inclined rod located on the right or east bank of the stream about 60 feet
ıe measuring section. This gage was destroyed on May 3, 1905, by high water, caused
ɔreaking of the St. John and Woodruff dams. It was replaced on May 6, 1905, with
rary gage, which was used until July 30, 1905, when a permanent gage was installed
ɔriginal location. The bench mark is a nail driven into a 6-inch cottonwood tree
N. 10° W. from east end of gage. The original elevation of this bench mark was
et above the zero of the gage. This tree was so bent over by the rush of water on
hat the bench mark is about 0.05 foot lower than it was originally. The zero of the
ablished July 30, 1905, was set 13.03 feet below the elevation of the bench mark, or
mately 13.07 feet below the original elevation. On July 30, 1905, the water stood at
on the temporary gage set by the observer May 6, and registered 0.8 foot at the same
the new permanent gage.

Discharge measurements of Little Colorado River at Woodruff, Ariz., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
Mar. 22	W. A. Farish	9.25	736	September 27	R. L. Newman	2.1	137
May 1	do	7.4	480	September 28	do	1.4	66
July 31	Newman and Farish.	3.05	459	September 29	do	1.7	173
August 3	R. L. Newman	.8	54	September 30	do	1.3	80
August 4	do	.5	28	October 1	do	1.0	63
August 6	do	.3	18.1	October 3	do	.8	32
August 7	do	.5	30	October 4	do	0.8	30
August 8	do	.8	49	October 6	do	0.7	35
August 9	do	.5	45	October 7	do	0.7	35
August 10	do	.5	53	October 8	do	0.7	22
August 11	do	1.3	201	October 10	do	0.6	15.4
August 13	do	.4	94	October 12	do	0.6	15.1
August 14	do	.5	58	October 13	do	6.6	13.8
August 15	do	.4	77	October 14	do	0.6	11.5
August 16	do	.3	44	October 16	do	0.5	16
August 17	do	.3	46	October 17	do	0.5	14.8
August 18	do	.3	12	October 19	do	0.5	14.8
August 19	do	.1	6.2	October 20	do	0.5	15.1
August 22	do	.0	9.3	October 21	do	0.5	14.7
August 24	do	1.3	132	October 23	do	0.4	12.8
August 25	do	1.1	99	October 24	do	0.4	12.7
August 27	do	3.7	342	October 25	do	0.4	13.4
August 29	do	.5	30	October 26	do	0.4	12.5
August 31	do	.5	17.4	October 27	do	0.4	13.6
September 1	do	.3	13.1	October 28	do	0.4	13.7
September 3	do	.3	17.7	October 30	do	0.4	11.6
September 4	do	.2	11.4	October 31	H. S. Reed	0.4	14.4
September 6	do	6	1,216	October 31	do	0.4	14
September 7	do	1.4	131	November 1	R. L. Newman	6.4	11
September 9	do	1.4	114	November 7	do	1.0	39
September 11	do	.5	33	November 8	do	1.0	38
September 12	do	.5	28	November 9	do	3.35	249
September 13	do	.3	17.8	November 10	do	1.4	52
September 14	do	.3	19	November 11	do	1.1	38
September 16	do	.2	13.7	November 20	do	.7	25
September 20	do	.1	8	November 21	do	1.5	67
September 21	do	.1	8.3	November 22	do	2.0	130
September 23	do	.1	8.7	November 23	do	2.7	172
September 24	do	4.75	880	November 24	do	1.2	46
September 25	do	3.7	657	November 25	do	1.0	33

ily gage height, in feet, of Little Colorado River at Woodruff, Ariz., for 1905.

	Mar	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	5.9	7.5	3.65	2,0	2.4	0.3	1.1	0.4	1.7
.....	.....	8.05	6.95	3.6	2.0	1.55	.6	.95	.4	1.55
.....	.....	11.2	19.65	3.5	2.0	.8	.25	.8	.4	1.45
.....	.....	11.1	11.5	3.45	1.95	.5	.75	.75	4.0	1.3
.....	.....	12.4	9.75	3.4	1.9	.3	.75	.7	2.2	1.3
.....	.....	12.8	8.75	3.35	1.9	.3	2.5	.7	1.15	1.2
.....	.....	12.15	8.0	3.25	1.9	.5	1.7	.7	.9	1.05
.....	.....	11.4	7.5	3.85	1.9	.65	1.4	65	1.65	.8
.....	.....	10.15	7.0	3.95	2.8	.6	1.35	.6	2.65	.7
.....	.....	10.0	6.5	3.75	2.7	.5	.95	.6	1.4	.7
.....	.....	8.25	7.25	3.45	2.6	.9	.6	.6	1.1	.7
.....	.....	12.3	7.55	3.2	2.5	.55	.5	.6	1.0	.55
.....	.....	13.4	5.95	3.2	2.4	.45	.35	.6	1.0	.75
.....	.....	9.2	5.4	3.2	2.3	.4	.3	.6	.9	.6
.....	.....	8.65	5.35	3.15	2.25	.4	.3	.5	.85	.5
.....	7.4	7.4	4.95	3.1	2.0	.3	.2	.5	.8	.5
.....	10.3	6.7	4.75	3.05	1.95	.3	.2	.5	.8	.5
.....	10.45	6.3	4.6	3.0	1.9	.25	.2	.5	.8	.5
.....	9.75	5.9	4.5	3.0	2.1	.1	.1	.5	.75	.5
.....	9.45	5.45	4.45	2.5	3.6	.0	.1	.5	.7	.6
.....	12.4	5.65	4.4	2.0	2.0	.0	.1	.5	.7	.6
.....	8.05	5.25	4.3	2.0	1.95	.0	.1	.5	1.35	.6
.....	7.85	5.3	4.35	2.0	2.05	.0	.15	.4	2.3	.55
.....	7.35	8.9	4.25	2.0	2.0	.65	3.95	.4	1.25	.5
.....	7.35	11.95	4.2	2.0	1.9	1.15	4.55	.4	1.1	.4
.....	6.95	18.55	4.1	2.0	2.15	.8	4.0	.4	1.0	.4
.....	6,3	13.55	4.1	2.0	2.05	2.85	1.9	.4	21.9	.4
.....	6.3	9.9	4.0	2.0	2.1	1.35	1.35	.4	7.75	.4
.....	6.4	8.05	4.0	2.0	5.2	0.5	1.6	.4	5.5	.35
.....	6.7	7.85	4.0	2.0	7.25	.5	1.4	.4	2.0	.3
.....	5.7	.....	3.8	.....	4.75	.5	.....	.4	.....	.3

Daily discharge, in second-feet, of Little Colorado River at Woodruff, Ariz., for 1905.

Day.	Mar.	Apr.	May.	Aug.	Sept.	Oct.	Nov.
1	.....	320	492	317	13	80	12
2	.....	560	432	145	32	53	12
3	.....	1,028	2,296	54	15	32	12
4	.....	1,013	.....	28	47	26	323
5	.....	1,208	.....	18	47	22	126
6	.....	1,268	.....	18	948	35	42
7	.....	1,170	.....	29	190	35	36
8	.....	1,058	.....	38	122	18	80
9	.....	870	.....	53	80	15	167
10	.....	848	.....	53	65	15	52
11	.....	589	.....	122	40	15	38
12	.....	1,193	.....	93	28	15	36
13	.....	1,358	.....	100	20	14	36
14	.....	728	.....	49	19	12	22
15	.....	646	.....	47	19	15	31
16	481	481	.....	44	14	15	29
17	893	404	.....	46	14	15	29
18	916	362	.....	10	14	15	29
19	810	320	.....	6	8	15	36
20	766	274	.....	5	8	15	25
21	1,208	294	.....	5	8	15	25
22	562	254	.....	9	8	15	71
23	534	259	.....	9	10	13	135
24	475	683	.....	54	684	13	44
25	475	1,140	.....	106	868	13	36
26	432	2,030	.....	64	848	13	33
27	362	1,380	.....	166	234	13	10,000
28	362	830	.....	46	118	13	2,980
29	372	561	.....	30	155	13	1,735
30	404	534	.....	23	92	13	85
31	299	.....	.....	17	.....	13	.....

NOTE.—Owing to no measurements being made during May, June, and July, no estimates have b made. Discharge obtained by indirect method.

Estimated monthly discharge of Little Colorado River at Woodruff, Ariz., for 1905.

[Drainage area, 6,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inche
March 16-31	1,208	299	584	18,530	0.097	0.(
April	2,030	254	789	46,950	.132	.1
August	317	5	58.2	3,579	.0097	.(
September	948	8	159	9,461	.026	.
October	80	12	20.1	1,236	.0034	.
November	10,000	12	543	32,310	.090	.
December	72	25	37.4	2,300	.0062	.
The period	.....	.....	.....	114,400	.....	[redacted]

LITTLE COLORADO RIVER AT HOLBROOK, ARIZ.

tation was established March 17, 1905. It is located at the county bridge across olorado River at Holbrook, Ariz.

ıannel is straight for about 300 feet both above and below the station. A stone ng the side of the wagon road forms the right bank; the left bank is clean and overflow. The bed of the stream is sand to an average depth of 3 to 5 feet, and is table. The entire flow of the river passes under the bridge; but as the section is current does not always flow at right angles to the bridge.

ırge measurements are made from the downstream side of the bridge. The initial soundings is the face of the bridge abutment on west bank of stream. Soundings n at each of the floor beams.

age, which was read twice each day during 1905 by Mrs. Anna Connor, is a staff in an upright position to the downstream face of the first pier from the west bank. e is referred to bench marks as follows: (1) The corner of the top of the bridge pier ı the gage is fastened; elevation, 11.80 feet above the zero of the gage. (2) The outside edge of the bridge chord; elevation, 12.73 feet above the zero of the gage.

Discharge measurements of Little Colorado River at Holbrook, Ariz., in 1905.

e.	Hydrographer.	Gage height.	Dis-charge.	Date.	Hydrographer.	Gage height.	Dis-charge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
.....	W. A. Farish....	5.9	942	September 18...	R. L. Newman...	2.9	11
.....	.....do.....	6.6	1,380	September 19...	.....do.....	2.9	11
.....	.....do.....	6.35	1,139	September 22...	.....do.....	2.9	12
.....	.....do.....	4.6	923	September 25...	.....do.....	3.95	500
.....	.....do.....	4.7	568	September 27...	.....do.....	3.6	174
.....	E. C. Murphy.....	3.48	175	September 30...	.....do.....	4.0	464
.....	W. A. Farish.....	4.4	1,215	October 2.....	.....do.....	3.3	96
.....	R. L. Newman....	3.5	176	October 4.....	.....do.....	3.3	87
.....	.....do.....	3.5	170	October 6.....	.....do.....	3.3	79
.....	.....do.....	3.0	58	October 8.....	.....do.....	3.2	29
.....	.....do.....	3.0	43	October 11.....	.....do.....	3.0	15
11.....	.....do.....	3.2	55	October 13.....	.....do.....	3.0	22
12.....	.....do.....	3.3	174	October 16.....	.....do.....	3.0	27
15.....	.....do.....	3.0	33	October 18.....	.....do.....	3.1	25
17.....	.....do.....	3.1	95	October 20.....	.....do.....	3.0	20
21.....	.....do.....	2.9	64	October 23.....	.....do.....	3.1	25
25.....	.....do.....	3.2	60	October 25.....	.....do.....	3.0	18
27.....	.....do.....	3.8	714	October 27.....	.....do.....	3.0	20
30.....	.....do.....	3.3	116	October 30.....	H. S. Reed.....	3.0	11
31.....	.....do.....	2.9	47	November 1....	R. L. Newman....	3.0	11
ber 2...	.....do.....	3.3	81	November 8....	.....do.....	4.3	624
ber 4...	.....do.....	3.3	59	November 9....	.....do.....	4.25	412
ber 6...	.....do.....	5.5	3,444	November 13...	.....do.....	3.3	49
ber 8...	.....do.....	3.6	124	November 18...	.....do.....	3.1	40
ber 10...	.....do.....	3.5	81	November 22...	.....do.....	3.7	225
ber 11...	.....do.....	3.2	46	November 24...	.....do.....	4.0	112
ber 13...	.....do.....	3.1	11	November 29...	.....do.....	3.9	479
ber 15...	.....do.....	2.9	15				

Daily gage height, in feet, of Little Colorado River at Holbrook, Ariz., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	De
1		5.45	4.78	3.4	3.0	3.5	3.3	3.6	3.1	
2		5.9	4.72	3.35	3.0	3.5	3.45	3.45	3.1	
3		5.9	6.2	3.3	2.9	3.4	3.3	3.3	3.1	
4		6.25	.....	3.2	2.8	3.3	3.1	3.3	4.25	
5		6.8	.....	3.2	2.8	3.15	4.2	3.3	3.9	
6		6.9	.....	3.0	2.8	3.15	4.8	3.3	3.5	
7		6.45	.....	3.0	2.8	2.95	4.15	3.3	3.2	
8		5.85	.....	3.0	2.8	3.3	3.7	3.3	3.7	
9		5.9	.....	3.2	2.8	3.05	3.7	3.3	4.85	
10		5.4	5.8	3.4	2.8	3.2	3.7	3.2	3.6	
11		5.7	5.55	3.3	2.8	3.45	3.4	3.2	3.6	
12		6.45	4.9	3.2	2.8	3.55	3.3	3.2	3.45	
13		6.15	4.25	3.2	2.8	3.2	3.0	3.2	3.4	
14		5.35	4.0	3.2	2.8	3.2	3.0	3.1	3.4	
15		5.3	3.9	3.2	2.8	3.1	3.0	3.1	3.3	
16		4.75	3.85	3.2	3.5	3.25	3.0	3.1	3.3	
17	6.1	4.55	3.8	3.2	3.05	3.15	3.0	3.1	3.2	
18	6.25	4.6	3.8	3.2	3.0	3.0	3.0	3.1	3.2	
19	5.95	4.6	3.7	3.2	3.0	2.9	3.0	3.1	3.1	
20	6.05	4.65	3.7	3.2	4.05	2.9	3.0	3.1	3.1	
21	6.4	4.6	3.95	3.2	3.25	2.9	3.0	3.1	3.1	
22	5.5	4.7	3.9	3.2	2.9	3.0	3.0	3.1	4.55	
23	5.3	4.6	3.65	3.15	3.0	2.9	3.0	3.1	4.25	
24	5.55	6.45	3.4	3.1	3.0	2.9	4.9	3.1	4.0	
25	5.45	6.8	3.4	3.1	3.0	2.9	4.45	3.1	3.7	
26	5.45	7.35	3.4	3.1	3.0	3.75	4.8	3.1	3.5	
27	5.42	5.55	3.4	3.0	3.0	4.1	4.1	3.1	8.55	
28	5.42	5.8	3.4	3.0	2.8	3.5	3.5	3.1	5.75	
29	5.3	4.65	3.4	3.0	3.25	3.5	3.7	3.0	4.05	
30	5.22	4.7	3.4	3.0	4.5	3.5	4.0	3.0	3.80	
31	5.22	.....	3.4	.....	4.05	3.0	.....	3.0	.....	

Daily discharge, in second-feet, of Little Colorado River at Holbrook, Ariz., for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	.....	792	578	145	44	170	130	220	30	
2	.....	940	558	132	44	170	160	140	30	
3	.....	940	1,055	120	22	145	75	91	30	
4	.....	1,081	.....	88	5	120	30	87	410	
5	.....	1,570	.....	88	5	77	280	83	295	
6	.....	1,665	.....	44	5	77	1,480	79	160	
7	.....	1,238	.....	44	5	33	545	75	60	
8	.....	923	.....	44	5	120	175	75	225	
9	.....	940	.....	88	5	55	175	75	1,620	
10	.....	776	905	115	5	88	175	39	195	
11	.....	872	824	120	5	125	85	39	195	
12	.....	1,238	616	88	5	310	50	39	145	
13	.....	1,035	408	88	5	100	15	39	130	
14	.....	760	328	88	5	85	15	29	130	
15	.....	741	296	88	5	50	15	29	95	
16	.....	568	280	88	170	115	15	29	95	

harge, in second-feet, of Little Colorado River at Holbrook, Ariz., for 1905—Cont'd.

y.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1,015	504	264	88	55	115	15	29	60	45
.....	1,081	520	264	88	44	80	15	29	60	45
.....	958	520	232	88	44	64	15	29	30	45
.....	995	526	232	88	344	64	15	29	30	45
.....	1,190	520	312	88	99	64	15	29	30	45
.....	808	552	296	88	22	80	15	29	860	70
.....	744	520	216	77	44	64	15	29	412	95
.....	824	1,238	145	66	44	64	1,760	29	325	95
.....	792	1,570	145	66	44	64	875	29	225	95
.....	792	2,075	145	66	44	310	1,480	29	160	95
.....	782	824	145	44	44	1,200	520	29	20,180	205
.....	782	905	145	44	5	430	155	29	7,295	205
.....	744	536	145	44	99	340	265	19	1,000	270
.....	718	552	145	44	488	215	465	19	260	205
.....	718	.....	145	.....	344	60	.....	19	.....	205

Daily discharge obtained by indirect method.

imated monthly discharge of Little Colorado River at Holbrook, Ariz., for 1905.

[Drainage area, 17,630 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ıl.....	1,190	718	863	25,680	0.049	0.027
.....	2,075	504	915	54,450	.052	.058
ays).....	1,055	145	353	17,500	.020	.019
.....	145	44	82.6	4,915	.0047	.0052
.....	488	5	67.9	4,175	.0039	.0045
.....	1,200	33	163	10,020	.0092	.011
.....	1,760	15	302	17,970	.017	.019
.....	220	19	50.7	3,117	.0029	.0033
.....	20,180	30	1,159	68,960	.066	.074
.....	325	45	113	6,948	.0064	.0074
period.....	.....	.....	.....	213,700	.....	.....

Summary of observations of evaporation at Holbrook, Ariz., in 1905.

AUGUST.

Day.	Period (in hours) in which measured evaporation has occurred.	Amount of evaporation.	Temperature of water in pan.			Temperature of wat outside pan.		
			A. M.	P. M.	Mean.	A. M.	P. M.	Me
2	12 hours	0.06	.....	72	.....	.....	72	.....
3	24 hours	.19	66	77	71.5	66	77	
4	.....do	.24	68	77	72.5	69	78	
5	.....do	.26	78	79	78.5	71	79	
6	.....do	.27	71	80	75.5	71	80	
7	.....do	.29	72	78	75.0	72	79	
8	.....do	.23	74	78	76.0	73	78	
9	.....do	.26	71	72	71.5	70	72	
10	.....do	.29	70	75	72.5	70	75	
11	.....do	.12	68	77	72.5	69	77	
12	.....do	.24	69	78	73.5	70	78	
13	.....do	.25	69	76	72.5	70	76	
14	.....do	.29	69	77	73.0	69	77	
15	.....do	.24	70	77	73.5	71	77	
16	.....do	.23	70	78	74.0	70	77	
17	.....do	.19	70	78	74.0	71	78	
18	.....do	.26	70	78	74.0	71	77	
19	.....do	.21	69	77	73.0	70	78	
20	.....do	.24	70	76	73.0	70	77	
21	.....do	.23	69	76	72.5	70	77	
22	.....do	.31	70	74	72.0	71	75	
23	.....do	.10	70	75	72.5	71	75	
24	.....do	.20	70	75	72.5	71	75	
25	.....do	.09	70	76	73.0	70	75	
26	.....do	.21	71	78	74.5	71	78	
27	.....do	.19	71	71	71.0	71	71	
28	.....do	.22	70	78	74.0	71	77	
29	.....do	.16	71	81	76.0	71	80	
30	.....do	.23	72	76	74.0	72	76	
31	.....do	.30	72	76	74.0	72	76	

[a] Slight wind. [b] Rain. [c] High wind.

nary of observations of evaporation at Holbrook, Ariz., in 1905—Continued.

SEPTEMBER.

od (in hours) in which asured evaporation has urred.	Amount of evaporation.	Temperature of water in pan.			Temperature of water outside pan.		
		A. M.	P. M.	Mean.	A. M.	P. M.	Mean.
urs	0.19	69	76	72.5	70	76	73.0
o	.24	79	78	78.5	70	78	74.0
o	.26	69	71	70.0	69	71	70.0
o	.06	69	70	69.5	68	70	69.0
o	.09	66	66	66.0	67	66	66.5
o	.11	64	70	67.0	65	70	67.5
o	.14	64	73	68.5	65	72	68.5
o	.18	65	71	68.0	65	71	68.0
o	.18	65	73	69.0	65	73	69.0
o	.17	64	72	68.0	65	70	67.5
o	.16	62	73	67.5	63	72	67.5
o	.22	65	71	68.0	65	71	68.0
o	.21	65	72	68.5	66	72	69.0
o	.21	66	72	69.0	66	72	69.0
o	.21	61	73	67.0	61	73	67.0
o	.27	65	72	68.5	65	72	[a] 68.5
o	.22	63	70	66.5	63	70	[a] 66.5
o	.20	65	68	66.5	65	68	66.5
o	.20	59	70	64.5	60	70	65.0
o	.18	60	69	64.5	61	70	65.5
o	.17	60	70	65.0	61	71	66.0
o	.16	61	71	66.0	62	71	66.5
o	.06	62	62	62.0	62	62	62.0
o	.0	61	65	63.0	61	65	63.0
o	.0	60	60	60.0	60	60	60.0
o	.10	61	61	61.0	62	61	61.5
o	.14	65	72	68.5	64	71	67.5
o	.09	63	61	62.0	63	61	62.0
o	.05	61	59	60.0	63	60	61.5
o	.10	55	61	58.0	56	62	59.0

[a] High wind.

Summary of observations of evaporation at Holbrook, Ariz., in 1905—Continued.

OCTOBER.

Day.	Period (in hours) in which measured evaporation has occurred.	Amount of evaporation.	Temperature of water in pan.			Temperature of water outside pan.		
			A. M.	P. M.	Mean.	A. M.	P. M.	Mean.
1	24 hours	0.08	55	67	61.0	56	66	61.0
2	do	.14	56	68	62.0	57	68	62.5
3	do	.12	59	67	63.0	59	67	63.0
4	do	.11	57	69	63.0	57	69	63.0
5	do	.12	59	70	64.5	60	69	64.5
6	do	.11	60	70	65.0	60	70	65.0
7	do	.15	59	73	66.0	61	73	67.0
8	do	.26	61	65	63.0	60	64	[a]62.0
9	do	.16	58	64	61.0	58	64	61.0
10	do	.16	58	65	61.5	58	64	61.0
11	do	.17	58	67	62.5	58	67	62.5
12	do	.08	55	62	58.5	55	60	57.5
13	do	.14	56	58	57.0	56	58	57.0
14	do	.14	55	60	57.5	54	60	57.0
15	do	.18	55	64	59.5	54	64	59.0
16	do	.20	52	57	54.5	51	56	53.5
17	do	.19	50	55	52.5	50	54	52.0
18	do	.18	49	53	51.0	49	54	51.5
19	do	.14	50	56	53.0	49	56	52.5
20	do	.10	42	49	45.5	42	48	45.0
21	do	.08	42	62	52.0	49	59	54.0
22	do	.13	57	64	60.5	56	63	59.5
23	do	.09	52	57	54.5	52	56	54.0
24	do	.11	52	58	55.0	51	57	54.0
25	do	.14	50	59	54.5	51	58	54.5
26	do	.08	51	54	52.5	51	55	53.0
27	do	.10	48	53	50.5	49	52	50.5
28	do	.11	48	52	50.0	50	52	51.0
29	do	.16	49	59	54.0	50	57	53.5
30	do	.17	42	60	51.0	43	59	51.0
31	do	.16	41	56	48.5	42	57	49.5

[a] High wind.

mary of observations of evaporation at Holbrook, Ariz., in 1905—Continued.

NOVEMBER.

iod (in hours) in which easured evaporation has ccurred.	Amount of evaporation.	Temperature of water in pan.			Temperature of water outside pan.		
		A. M.	P. M.	Mean.	A. M.	P. M.	Mean.
hours	0.07	42	52	47.0	43	51	47.0
.do	.00	43	59	51.0	42	57	49.5
.do	.06	50	54	52.0	50	54	52.0
.do	.04	51	59	55.0	51	59	55.0
.do	.02	50	54	52.0	50	53	51.5
.do	.03	52	50	51.0	52	50	51.0
.do	.07	50	55	52.5	50	55	52.5
.do		51	47	49.0	51	48	49.5
.do	.08	47	52	49.5	47	52	49.5
.do	.07	45	48	46.5	46	48	47.0
.do	.08	45	50	47.5	45	50	47.5
.do	.10	47	52	49.5	47	52	49.5
.do	.04	43	54	48.5	44	54	49.0
.do	.06	52	51	51.5	52	51	51.5
.do	.08	43	52	47.5	44	52	48.0
.do	.06	47	50	48.5	47	50	48.5
.do	.07	45	51	48.0	46	51	48.5
.do	.06	40	52	46.0	41	52	46.5
.do	.06	43	52	47.5	45	50	47.5
.do	.08	49	50	49.5	49.5	50	49.5
.do	.05	44	50	47.0	45	50	47.5
.do	.00	45	48	46.5	45	48	46.5
.do	.02	45	48	46.5	45	48	46.5
.do	.07	45	48	46.5	45	48	46.5
.do	.05	45	49	47.0	45	49	47.0
.do	.00	50	49	49.5	50	48	49.0
.do	.00	45	48	46.5	45	48	46.5
.do	.10	40	49	44.5	42	49	[a] 45.5
.do	.00	41	49	45.0	41	49	45.0
.do	.03	40	45	42.5	40	45	42.5

[a] High wind.

Summary of observations of evaporation at Holbrook, Ariz., in 1905—Continued.

DECEMBER.

Day.	Period (in hours) in which measured evaporation has occurred.	Amount of evaporation.	Temperature of water in pan.			Temperature of water outside pan.		
			A. M.	P. M.	Mean.	A. M.	P. M.	Mean.
1	24 hours	0.08	38	48	43.0	41	48	44.5
2	do	.00	38	42	40.0	40	42	41.0
3	do	.05	40	45	42.5	40	42	41.0
4	do	.00	40	45	42.5	40	45	42.5
5	do	.04	40	45	42.5	40	45	42.5
6	do	.00	40	45	42.5	40	45	42.5
7	do	.04	40	48	44.0	40	48	44.0
8	do	.00	40	43	41.5	40	43	41.5
9	do	.00	40	42	41.0	40	42	41.0
10	do	.00	40	41	40.5	40	41	40.5
11	do	.00	35	38	36.5	34	38	36.0
12	do	.00	40	42	41	40	42	41.0
13	do	.00	40	42	41.0	40	42	41.0
14	do	.00	38	41	39.5	34	40	37.0
15	do	.00	40	43	41.5	40	43	41.5
16	do	.00	39	41	40.0	40	41	40.5
17	do	.00	39	40	39.5	40	41	40.5
18	do	.00	37	39	38.0	39	40	39.5
19	do	.00	37	39	38.0	39	40	39.5
20	do	.01	35	40	37.5	37	40	38.5
21	do	.00	35	40	37.5	36	40	38.0
22	do	.00	33	38	35.5	34	39	36.5
23	do	.00	32	34	33.0	32	34	33.0

CHEVLON FORK NEAR WINSLOW, ARIZ.

This station was established December 18, 1905. It is located 4½ miles above the mouth of the river, in sec. 34, T. 18 N., R. 17 E., 19 miles east of Winslow, Ariz.

The channel is straight for 150 feet above and below the station. The current is very swift during high water. At extreme low water the current is rather sluggish, but it has a good velocity at ordinary stage. Both banks are practically vertical cliffs about 33 feet high. A dirt bank extending about 12 feet from the base of the cliff and 3 or 4 feet high has been deposited at the foot of the cliff on the left bank. The bed is of solid rock excepting a small bank of sand on the left bank which is alternately deposited and scoured out.

Discharge measurements are made by means of a cable, car, and tagged and stay wires The initial point for soundings is the face of the eyebolt to which the tagged wire is fastened on the left bank of the stream. A secondary cable has been stretched across the river 100 feet downstream from the tagged wire for use in making float measurements at very high stages.

An automatic water stage register is placed on an overhanging platform 26.5 feet above the bed of the creek. The station is visited and the register reset once each week by R. L. Newman. The distance to the center of the first band from the top of the baseboard upon which the register sets is 5.90 feet; to the center of the second band, from the same point, 9.57 feet. The base of the register baseboard is 27.30 feet above the datum of the gage.

Discharge measurements of Chevlon Fork near Winslow, Ariz., in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
er 25..	H. S. Reed	5.0	1.36	0.65	1.00	0.88
r 19...	.....do	42.0	104	.32	2.10	33.3

MISCELLANEOUS MEASUREMENTS.

ollowing miscellaneous measurements were made in the Little Colorado River drain- in during 1905:

neous discharge measurements made in Little Colorado River drainage basin in 1905.

te.	Stream.	Locality.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
			Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
19.....	Chevlon Fork...	Crossing of Holbrook-Winslow wagon road.	26.7	8.2	1.10	.....	9.1
19.....	.....do.....	.....do.....	26.7	7.9	1.39	0.5	11.1
10.....	.....do.....	.....do.....	25.5	13.7	.92	.7	12.6
er 10...	.....do.....	.....do.....	23.6	9.9	.65	.4	6.4
er 19...	.....do.....	.....do.....	26.0	7.0	.65	.5	4.5
er 29...	.....do.....	.....do.....	24.0	12.7	1.34	.7	17.0
9.....	.....do.....	.....do.....	19.7	9.0	1.03	.5	9.3
18.....	.....do.....	.....do.....	20.1	9.1	1.16	.5	10.6

VIRGIN RIVER DRAINAGE BASIN.

MUDDY RIVER NEAR MOAPA, NEV.

ly River is a branch of the Virgin, one of the more important tributaries of the Colo- The stream drains a long narrow strip of country in the eastern part of Lincoln , Nev., flows southward, and joins the Virgin about 25 miles above the point where er stream enters the Colorado.

gaging station was established January 1, 1904. It is located near the crossing of Pedro, Los Angeles and Salt Lake Railroad, about 6 miles downstream from Moapa. The station is above the Narrows and will show the amount of water available for at the proposed reservoir site in the Narrows.

channel is straight for 35 feet above and below the station, and high, brush-covered slope up from the vertical sides of the channel. The immediate banks are low, but ble to overflow. The bed of the stream is composed of sand and is shifting. It is l with vegetation, which is kept grubbed out near the station. The current has a te velocity.

large measurements are made from a footbridge 450 feet downstream from the gage. tial point for soundings is a nail driven into the downstream side of the bridge at the nk.

gage, which was read twice each day during 1905 by J. V. Houghton, is a vertical iled to a post driven into the right bank. The bench mark is the top of a 2-inch post into the ground in a willow clump 20 feet from the gage on the right bank; elevation, t above the zero of the gage.

scription of this station, with gage-height and discharge data, is contained in Water-Paper *No. 133, United States* Geological Survey, pages 196–197.

Daily gage height, in feet, of Muddy River near Moapa, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.2	3.6	2.0	2.0	2.1	1.9	1.9	2.0	1.9	2.2	2.3	2.1
2	2.2	3.6	2.0	2.2	2.0	1.9	1.9	2.0	2.0	2.2	2.4	2.1
3	2.2	3.6	2.0	2.2	2.0	1.9	1.9	2.0	1.9	2.2	2.	2.0
4	2.2	3.6	2.0	2.2	2.0	1.9	1.9	1.9	1.95	2.2	2.	2.0
5	2.2	3.6	2.0	2.2	1.9	2.0	1.9	1.9	1.9	2.2	2.4	2.0
6	2.2	3.6	2.0	2.2	1.9	2.0	1.9	1.9	1.9	2.2	2.4	2.7
7	2.2	3.6	2.0	2.2	2.0	2.0	1.9	1.9	1.9	2.0	2.4	2.7
8	2.2	3.6	2.0	2.2	2.0	2.0	1.9	2.0	1.9	2.0	2.4	2.7
9	2.2	3.6	2.0	2.2	2.0	2.0	1.9	2.0	2.0	2.0	2.4	2.7
10	2.2	3.4	2.0	2.3	2.0	2.0	1.9	6.5	1.9	2.0	2.	2.8
11	2.3	3.4	2.0	3.6	2.0	1.9	1.9	5.8	1.8	2.0	2.	2.6
12	2.3	3.3	3.0	3.8	2.0	1.9	1.9	2.5	1.8	2.0	2.	2.8
13	2.3	3.3	3.5	3.4	2.0	1.9	1.9	2.0	1.8	1.0	2.	2.7
14	2.3	2.7	4.0	3.4	2.0	1.9	1.7	2.0	1.9	1.9	2.	2.7
15	2.3	2.7	4.2	3.2	2.0	1.9	1.5	2.0	2.0	1.9	2.	2.7
16	2.3	2.6	4.4	3.2	1.9	1.9	1.2	2.0	2.0	1.9	2.4	2.7
17	2.3	2.5	4.4	2.6	1.9	1.9	3.6	2.0	2.0	1.9	2.4	2.7
18	2.5	2.5	4.2	2.4	1.9	1.9	3.5	2.0	2.0	2.0	2.4	2.7
19	2.5	2.4	4.0	2.2	1.9	1.9	3.4	2.0	2.0	2.15	2.5	2.6
20	2.45	2.3	3.5	2.1	1.9	1.9	3.0	2.0	2.0	2.2	2.5	2.6
21	2.45	2.3	3.5	2.1	1.8	1.9	3.0	1.9	1.9	2.2	2.	2.6
22	2.45	2.2	3.0	2.1	1.8	1.9	3.0	1.9	1.9	2.2	2.	2.6
23	2.45	2.2	2.2	2.1	1.8	1.9	2.5	1.9	1.9	2.25	2.	2.6
24	2.45	2.1	2.2	2.15	1.8	1.9	2.3	1.9	2.0	2.3	2.	2.6
25	2.45	2.0	2.2	2.1	1.8	1.9	2.3	2.0	2.0	2.3	2.5	2.6
26	2.45	2.0	2.1	2.1	1.8	1.9	2.0	2.0	2.0	2.3	2.5	2.6
27	2.45	2.0	2.0	2.1	1.8	1.9	2.0	2.0	2.0	2.3	2.6	2.7
28	2.45	2.0	2.0	2.1	1.8	1.9	2.0	2.0	2.0	2.3	2.6	2.7
29	2.45	.....	2.0	2.1	1.8	1.9	1.9	1.90	2.6	2.3	2.6	2.7
30	2.45	.....	2.0	2.1	1.8	1.9	1.9	1.90	2.15	2.3	2.	2.7
31	3.8	.....	2.0	.....	1.8	.....	1.9	1.90	.....	2.3	.....	2.7

GILA RIVER DRAINAGE BASIN.

DESCRIPTION OF BASIN.

Gila River rises in western and southwestern New Mexico, receiving its waters from mountains having an elevation of from 7,000 to 8,000 feet. At the point where it crosses into Arizona it still has an elevation of 6,000 feet. From this place it flows between mountain ranges, falling rapidly, until at Florence, 180 miles away, it is about 1,500 feet above sea level. At a point about 15 miles above Florence the river emerges upon the plains, through which it winds for about 75 miles before receiving the waters of its principal tributary, the Salt. From the junction of the Salt the Gila continues west and southwest and enters the Colorado at Yuma, Ariz., near the southwestern corner of the Territory.

The principal tributaries are the San Pedro and Santa Cruz rivers from the south, and the San Francisco, Salt, Aqua Fria, and Hassayampa rivers from the north.

San Francisco River rises in the southwestern part of Socorro County, N. Mex., and flows southwestward into Graham County, Ariz., where it unites with the Gila. The basin comprises approximately 1,800 square miles of high, mountainous country.

t River, though considered a tributary of the Gila, is in fact larger both in catchment ınd in discharge. It receives the drainage from central Arizona, its principal tribu- the Verde, flowing southeasterly and south from the mountains and table-lands south Colorado River. The Verde Valley is situated in Yavapai County, Ariz., on the head- s of the stream, and extends from a canyon above Camp Verde to a point about 10 below the fort. About a mile above the junction of the Verde and 30 miles above ıix the Salt enters upon the plains of the Gila Valley.

ı Pedro River rises in the northern part of the Mexican State of Sonora, flows north- for more than 100 miles, and empties into the Gila a few miles below the town of Dud- le, 45 miles above Florence, Ariz. Rising in a country of very light snowfall, the river ıds for the greater part of its water supply on the frequent showers of the rainy seasons. ws over a sandy bed between high, steep banks, and during the dry season it shrinks insignificant stream of clear water which rises and sinks in the sand with the varying ı of bed rock.

ɜ floods of the upper Gila and its tributaries are usually short and violent, occurring g the months of January and February. The season of low water occurs in June and

GILA RIVER NEAR CLIFF, N. MEX.

is station was established September 9, 1904. It is located 9 miles below Cliff post- and one-half mile below the mouth of Mangos River. It is 40 miles from Silver N. Mex. The station is best reached by stage from Silver City to Gila Store, thence ivate conveyance. If the river is in flood, the latter part of the journey must be made rseback.

ɜ channel is straight for 400 feet above and 300 feet below the station. The banks bout 6 feet high, are clean, and are subject to overflow during extreme high water. ıed of the stream is composed of sand and gravel, is free from vegetation, and is shift- There is but one channel at all stages. At low water the channel, although straight, ıcross the section at a slight angle; during freshets the channel will be at right angles ɜ measuring section.

ıcharge measurements are made by means of a cable and car. The initial point for lings is the zero of the tagged wire.

ɜ gage is read twice each day by Mrs. Winnie P. Clark. The original gage was a staff ıed to a large cottonwood tree on the east side of the river. This gage was carried y heavy freshets in the early part of 1905, but observations of gage heights were con- d on a temporary gage until February 17, 1905, when the station was temporarily loned. On May 22, 1905, the gage was reestablished and the station put in order, ıbservations of gage heights were again begun. The bench mark is a point marked .G.S. B.M." with black paint in a blaze on a sycamore tree N. 84° E. 293 feet from ıge; elevation, 8.55 feet above the zero of the gage.

lescription of this station, with gage-height data, is contained in Water-Supply Paper 33, United States Geological Survey, page 198.

Discharge measurements of Gila River, near Cliff, N. Mex., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
June 14	F. Asplind	3.15	358	September 20	F. Asplind	2.70	70
June 14[a]	do	3.15	337	September 21	do	2.65	61
July 7	do	2.10	85	September 22	do	2.75	80
July 8	do	2.05	73	September 23	do	2.75	82
July 9[a]	do	2.05	82	September 24[a]	do	10.20	5,520
July 9[a]	do	2.05	73	September 25	do	3.85	270
July 24	do	2.50	153	September 25	do	3.65	222
July 25	do	2.38	126	September 26	do	3.65	220
July 26	do	2.25	110	September 27	do	3.55	201
July 26[a]	do	4.05	602	September 28	do	3.65	225
July 27	do	2.65	192	October 26	do	3.10	118
July 27	do	2.58	173	October 27	do	3.10	118
July 27	do	2.45	144	October 28	do	3.10	121
July 28	do	2.60	178	October 29	do	3.10	119
July 28	do	2.40	131	October 30	do	3.10	122
July 29	do	3.30	338	October 31	do	3.10	121
August 18	do	2.90	184	November 1	do	3.10	120
August 19	do	2.72	106	November 2	do	3.15	126
August 20	do	2.70	95	November 4	do	3.35	160
August 21	do	2.70	93	November 5	do	3.35	160
August 22	do	2.80	120	November 21	do	3.25	154
August 23	do	2.65	96	November 22	do	3.98	316
August 24	do	2.65	74	November 23[a]	do	5.85	1,091
August 25	do	2.65	74	November 23	do	6.00	1,210
August 26	do	2.80	121	November 24	do	5.15	714
August 27	do	2.75	111	November 25	do	4.60	495
September 19	do	2.70	71	November 26	do	4.45	427

[a] Float measurement.

Daily gage height, in feet, of Gila River, near Cliff, N. Mex., for 1905.

Day.	Jan.	Feb.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec
1	.95	1.05	.....	3.45	2.18	2.9	2.82	3.85	3.1	6.45
2	.9	1.05	.....	3.42	2.18	2.85	4.4	3.7	3.12	5.98
3	.9	1.67	.....	3.48	2.18	2.8	3.8	3.62	3.12	5.55
4	.9	3.97	.....	3.5	2.18	2.9	3.6	3.52	3.22	5.38
5	.9	4.07	.....	3.5	2.18	3.25	3.9	3.42	3.35	5.15
6	.9	4.02	.....	3.35	2.12	2.9	3.75	3.4	3.35	5.0
7	.9	3.4	.....	3.3	2.1	2.9	3.52	3.9	3.4	4.98
8	.9	2.9	.....	3.37	2.08	3.55	3.5	3.28	4.17	4.75
9	.93	2.72	.....	3.62	2.05	3.1	3.85	3.22	4.12	4.62
10	.....	2.65	.....	3.55	2.05	3.48	3.65	3.2	4.05	4.6
11	.....	2.6	.....	3.35	2.08	3.5	3.5	3.18	3.85	4.6
12	.....	2.5	.....	3.25	2.1	3.4	3.32	3.15	3.72	4.6
13	.....	2.3	.....	3.18	2.18	3.15	3.22	3.15	3.6	4.55
14	.....	2.15	.....	3.12	2.18	3.07	3.2	3.12	3.65	4.5
15	.....	2.12	.....	3.02	2.18	3.02	3.1	3.1	3.5	4.5
16	.....	2.8	.....	2.97	2.15	2.95	2.95	3.1	3.42	4.45
17	.....	6.45	.....	2.9	2.12	2.9	2.9	3.1	3.4	4.4
18	.....	.....	.....	2.85	2.18	2.95	2.82	3.1	3.35	4.4
19	.....	.....	.....	2.78	2.22	2.75	2.72	3.12	3.3	4.7

Daily gage height, in feet, of Gila River, near Cliff, N. Mex., for 1905—Continued.

Day.	Jan.	Feb.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.2	.....	.....	2.7	2.28	2.7	2.7	3.1	3.2	4.52
.....	1.1	.....	.....	2.65	2.35	2.7	2.68	3.1	3.22	4.48
.....	1.1	.....	4.2	2.52	2.3	2.8	2.72	3.1	3.95	4.42
.....	1.09	.....	4.05	2.45	2.3	2.67	2.75	3.08	5.8	4.35
.....	1.09	.....	4.0	2.38	2.32	2.67	4.88	3.08	5.1	4.22
.....	1.1	.....	3.92	2.38	2.32	2.67	3.78	3.1	4.6	4.15
.....	1.1	.....	3.85	2.28	3.37	2.85	3.58	3.1	4.42	4.15
.....	1.1	.....	3.72	2.28	2.55	2.72	3.55	3.1	11.9	4.15
.....	1.1	.....	3.68	2.25	2.6	2.65	3.6	3.1	9.9	4.18
.....	1.1	.....	3.62	2.25	3.28	2.65	3.48	3.1	8.25	4.2
.....	1.1	.....	3.52	2.22	3.55	2.62	3.9	3.1	7.1	4.2
.....	1.1	.....	3.4	.....	2.95	2.7	.....	3.1	.....	4.2

Daily discharge, in second-feet, of Gila River, near Cliff, N. Mex., for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	405	93	165	87	268	127	3,190
.....	.....	396	93	150	411	235	130	2,387
.....	.....	414	93	130	255	219	130	1,570
.....	.....	420	93	165	215	219	147	1,247
.....	.....	420	93	270	280	183	170	810
.....	.....	375	83	165	245	179	170	655
.....	.....	360	80	165	199	161	179	552
.....	.....	381	77	436	195	158	348	550
.....	.....	458	72	250	267	147	335	498
.....	.....	436	72	418	225	144	317	490
.....	.....	375	77	420	195	141	268	490
.....	.....	346	80	385	165	136	239	490
.....	.....	326	93	270	147	136	215	470
.....	.....	310	93	235	144	130	225	450
.....	.....	282	93	215	127	127	195	450
.....	.....	268	88	185	105	127	183	430
.....	.....	250	83	165	98	127	179	411
.....	.....	237	93	185	87	127	170	411
.....	.....	218	99	110	73	130	161	530
.....	.....	198	110	95	70	127	144	458
.....	.....	186	123	95	68	127	147	442
.....	648	158	113	130	73	127	292	419
.....	598	144	113	85	77	120	985	397
.....	582	129	117	85	602	120	715	361
.....	556	129	117	85	251	127	490	342
.....	532	110	381	150	211	127	419	342
.....	490	110	164	100	205	127	13,640	342
.....	478	104	178	80	215	127	9,835	349
.....	458	104	354	80	192	127	6,700	355
.....	426	99	436	65	280	127	4,515	355
.....	390	.....	263	95	.....	127	.....	355

NOTE.—Daily discharge obtained by indirect method.

Estimated monthly discharge of Gila River, near Cliff, N. Mex., for 1905.

[Drainage area, 2,450 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
May 22-31	648	390	516	10,230	0.211	0.078
June	458	99	272	16,180	.111	.124
July	436	72	133	8,178	.054	.062
August	436	65	182	11,190	.074	.085
September	602	68	192	11,420	.078	.087
October	268	120	149	9,162	.061	.070
November	13,640	127	1,392	82,830	.568	.634
December	3,190	342	665	40,890	.271	.312
The period				190,100		

GILA RIVER AT SAN CARLOS, ARIZ.

This station was established July 11, 1899, in connection with the investigation of the water supply of the Gila Valley.[a] It is located one-half mile south of the Indian agency at San Carlos and below the mouth of San Carlos Creek.

The channel is straight for some distance above and below the station, and the water is comparatively swift. The right bank is high, but the left is low and liable to overflow. The bed of the stream is sandy and shifting.

Discharge measurements are made from a cable and car a short distance above the gage rod. The gage at this station is read by R. H. Ross. The original gage was an inclined rod securely fastened to posts driven into the left bank. During the heavy floods of January, February, and March, 1905, the cable and gage were washed away, and there are breaks in the gage records for those months. In April and May, 1905, the station was visited by Mr. Gerard H. Matthes, who constructed an approximate gage record covering the period between April 1 and May 14, based on the data available at that time. On May 14 a chain gage was established on the right bank of the river about 500 feet below the new cable. In August, 1905, new cables were placed in position and the station was rebuilt. Owing to the fact that the channel left the chain gage during low water, an inclined gage was placed on the right bank of the stream about 60 feet above the cable for use at low stages. The zero of this gage coincides in elevation with the zero of the chain gage. The bench marks are as follows: (1) Nail in cottonwood tree on edge of bank 50 yards upstream from gage; elevation, 23.38 feet. (2) Nail in cottonwood tree near ditch back of gage; elevation, 20.58 feet. (3) Three nails driven at the same level in three forks of old cottonwood tree on irrigating ditch one-third mile north of gage; elevation, 23.85 feet. Elevations are above the zero of the gage. This station was discontinued December 31, 1905.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 38, pp 313-314; 50, p 385; 66, p 98; 85, pp 32-33; 100, p 48; 133, p 199.
Discharge: WS 38, p 314; 50, p 386; 66, p 99; 85, p 33; 100, p 50; 133, pp 200-202.
Discharge, mean daily: WS 133, p 203.
Discharge, monthly: Ann 21, iv, p 332; 22, iv, p 397; WS 75, p 179; 85, p 35; 100, p 51; 133, p 204.
Gage heights: WS 38, p 314; 50, p 386; 66, p 99; 85, p 34; 100, p 49; 133, p 202.
Hydrographs: Ann 21, iv, p 332; 22, iv, p 398; WS 75, p 180.
Rating tables: WS 39, p 452; 52, p 520; 85, pp 34-35.

[a] The results of this investigation are set forth in Water-Supply and Irrigation Paper No. 33, entitled "Storage of Water on Gila River, Arizona," by J. B. Lippincott.

Discharge measurements of Gila River at San Calos, Ariz., in 1905.

	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*
.....	R. H. Ross.....	1.45	127
.....	Matthes & Rabinnovitz.	11.12	422
.....	F. Rabinnovitz...	10.80	28
.....	.....do.....	10.50	58
.....	.....do.....	10.82	178
.....	.....do.....	11.44	243
.....	.....do.....	11.15	213
.....	.....do.....	11.57	957
17..	.....do.....	11.50	168
24..	.....do.....	11.35	89
30..	.....do.....	12.10	760
.....	.....do.....	11.40	109
.....	.....do.....	11.30	78
.....	.....do.....	11.15	36
.....	.....do.....	11.10	46

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*
October 15.....	F. Rabinnovitz...	11.25	117
October 17.....	.....do.....	11.20	65
October 26.....	.....do.....	11.05	42
October 28.....	.....do.....	11.00	28
October 30.....	.....do.....	11.05	57
November 2.....	.....do.....	11.15	58
November 4.....	.....do.....	11.10	76
November 6.....	.....do.....	11.45	292
November 10.....	.....do.....	12.45	1,438
November 13.....	.....do.....	11.90	766
November 15.....	.....do.....	11.75	461
November 17.....	.....do.....	11.80	492
November 20.....	.....do.....	11.70	381
November 22.....	.....do.....	12.00	951
November 24.....	.....do.....	13.20	3,237

Daily gage height, in feet, of Gila River, at San Carlos, Ariz., for 1905.

ıy.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
.....	1.5	1.7	5.6	.....	13.35	11.05	10.5	11.38	11.38	12.05	11.15
.....	1.5	1.7	5.3	12.8	13.3	11.05	10.5	11.3	11.22	11.88	11.15
.....	1.5	1.7	5.5	13.65	13.3	11.01	10.5	11.16	11.3	11.9	11.12
.....	1.5	5.55	5.4	14.4	13.2	11.99	10.5	11.2	11.8	11.82	11.1
.....	1.45	4.9	5.35	14.35	13.0	11.01	10.5	11.15	11.8	11.72	11.18
.....	1.45	4.9	4.9	13.45	12.85	11.02	10.5	11.12	12.6	11.62	11.48
.....	1.45	4.4	4.5	12.8	12.6	11.99	10.5	11.1	12.35	11.52	11.42
.....	1.45	3.8	4.8	13.0	12.35	11.07	10.5	11.22	12.17	11.48	11.7
.....	1.45	3.42	6.7	12.7	12.3	11.11	10.5	11.78	11.8	11.4	12.78
.....	7.0	3.2	5.55	12.75	12.2	11.36	10.5	11.52	11.92	11.35	12.48
.....	.....	3.15	5.1	12.9	12.2	11.26	10.55	11.52	11.95	11.35	12.2
.....	.....	3.05	4.6	14.7	12.2	11.25	10.38	11.42	11.8	11.32	12.05
.....	.....	2.95	4.1	14.9	12.05	11.22	10.62	11.34	11.7	11.3	11.92
.....	.....	2.78	5.1	14.65	11.95	11.14	10.88	11.38	11.65	11.28	11.8
.....	.....	2.7	5.1	14.15	11.9	11.14	10.7	11.27	11.6	11.22	11.78
.....	.....	2.85	4.5	14.1	11.86	11.08	10.68	11.1	11.5	11.2	11.72
.....	.....	5.05	8.0	14.3	11.82	11.06	10.6	11.07	11.5	11.2	11.75
.....	.....	7.9	.....	14.5	11.81	11.07	10.58	11.02	11.42	11.15	11.7
.....	.....	9.0	.....	14.0	11.8	11.05	10.5	11.04	11.35	11.15	11.65
.....	.....	4.45	.....	13.9	11.77	11.01	10.48	11.1	11.32	11.15	11.68
.....	.....	3.7	.....	13.75	11.69	11.26	10.45	11.04	11.28	11.15	11.65
.....	.....	3.35	.....	13.7	11.65	10.72	10.28	11.55	11.25	11.15	12.0
.....	.....	3.2	.....	13.7	11.59	10.92	10.18	11.17	11.25	11.12	13.02
.....	.....	3.65	.....	14.3	11.57	10.9	10.13	11.56	11.75	11.1	13.2
.....	.....	4.95	.....	14.5	11.48	10.84	10.13	[a]11.45	12.08	11.1	13.1
.....	.....	3.75	.....	14.85	11.43	10.79	10.1	11.45	12.62	11.05	12.8
.....	.....	3.4	.....	14.6	11.35	10.72	10.11	11.35	12.35	11.0	14.88
.....	.....	3.3	.....	14.0	11.28	10.66	10.87	11.22	12.15	11.0	.....
.....	.....	.....	.....	13.7	11.21	10.62	11.5	11.65	12.0	11.0	.....
.....	.....	.....	.....	13.45	11.16	10.55	11.58	11.1	12.08	11.02	.....
.....	.....	.....	.....	.....	11.13	.....	11.4	11.1	.....	11.08	.....

[a] Gage washed out. River changed its course. New gage set same level.

GILA RIVER AT DOME (GILA CITY), ARIZ.

This station was established October 15, 1903. It is located 20 miles above the junction of the Gila with the Colorado. The point of gaging first established was one-fourth mile north of the depot at Dome. The river now flows in a channel fully 1 mile north of the original channel.

The Gila carries an enormous amount of mud and sand. At times the waves of sand traveling along the bed of the stream are so large, the current is so swift, and the stream to shallow, that the water is broken into a uniform succession of waves 2 feet high and over. During 1905 there have been ten floods reaching a maximum mean discharge for twenty-four hours, as follows: Two floods of 95,000 second-feet or over; 1 flood of 80,000 second-feet or over; 2 floods of 40,000 second-feet or over; 5 floods of 13,000 second-feet or over. At every flood the channel shifts. The valley at its narrowest is half a mile wide and the waters may occupy any part or all of it. There is no place on the lower part of the Gila where a permanent cable can be erected at a reasonable expense.

Up to about 8,000 second-feet discharge measurements are made by means of a boat and cable above that by means of floats. When the Colorado above the Gila is known to be constant the crest of the flood is measured after it joins the Colorado at Yuma, and an allowance of 5 per cent is made for flattening of the crest between Dome and Yuma.

The gage observer is B. Rinehart. Fourteen gages have been put in by the hydrographer since the establishment of the station, not including temporary rods placed by the observer.

The permanent bench mark is a standard United States Geological Survey iron post at the southwest corner of depot under platform, marked "189 Y"; elevation, 189.60 feet above sea level and 31.97 feet above the zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 133, p 204.
Discharge: 133, p 205.
Discharge, monthly: 133, p 206.
Gage heights: 100, p 27; 133, p 205.

Discharge measurements of Gila River at Dome (Gila City), Ariz., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
January 14	W. D. Smith	8.25	3,323	April 14	W. D. Smith	12.60	[b]88,000
January 15	do	9.20	4,287	May 30	do	7.00	[c]2,200
January 15	do	9.90	4,941	June 13	do	5.90	740
January 16	do	12.80	17,300	September 19	do	3.70	31
January 17	do	14.60	[a]23,000	October 5	do	6.00	755
January 24	do	6.10	2,305	October 9	do	4.70	374
February 8	do	16.95	[a]80,000	November 28	do	7.10	2,467
March 20	do	13.10	[a]95,000	November 29	do	14.70	[d]95,000
April 4	do	9.00	[b]6,552				

[a] Estimated from gaging at Yuma, Ariz.
[b] Float measurement.
[c] Measurement made 4 miles above Yuma, Ariz.
[d] Estimated from the discharge of the Colorado River at Yuma and from gage observations at Dome, Picacho, and Laguna.

Daily gage height, in feet, of Gila River at Dome (Gila City), Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Sept.	Oct.	Nov.	Dec.
.....	.....	3.1	8.05	8.5	9.1	6.7	.....	.....	.....	.....	.....
.....	.....	2.75	10.65	8.5	8.8	6.5	4.4	.....	.....	.....	.....
.....	.....	2.45	11.55	8.3	8.9	6.0	.....	.....	6.6	.....	.....
.....	.....	2.3	9.5	8.6	8.7	.....	4.2	.....	6.4	.....	.....
.....	.....	3.55	8.0	8.9	8.3	.....	.....	.....	6.0	.....	8.2
.....	.....	7.0	7.3	9.6	8.4	.....	4.0	.....	5.6	.....	8.0
.....	.....	14.0	6.15	9.8	8.3	.....	.....	.....	5.0	.....	7.7
.....	.....	16.95	5.4	9.0	8.0	.....	3.9	.....	.....	.....	7.6
.....	.....	15.45	5.2	8.8	8.0	.....	.....	.....	4.7	.....	7.5
.....	3.0	13.1	5.0	8.9	8.0	.....	3.8	.....	.....	.....	7.7
.....	7.0	10.75	8.0	9.0	7.7	.....	.....	.....	4.3	.....	7.5
.....	7.5	7.25	9.2	8.9	8.2	.....	3.7	.....	.....	.....	7.4
.....	7.8	4.25	7.6	10.7	8.0	5.9	.....	4.8	4.0	.....	.....
.....	7.95	6.75	7.5	12.6	7.8	5.9	3.7	4.6	.....	4.5	7.4
.....	9.45	5.0	9.25	11.55	7.9	.....	.....	4.4	3.7	5.0	.....
.....	13.7	4.0	11.8	10.8	8.0	6.0	3.6	.....	.....	5.0	7.5
.....	14.6	4.55	10.5	10.0	8.0	.....	.....	3.8	3.6	.....	.....
.....	12.0	4.8	11.15	9.35	7.9	5.9	3.6	.....	.....	4.5	7.6
.....	10.1	10.95	12.55	8.85	7.6	.....	.....	3.7	3.5	.....	.....
.....	8.7	11.95	13.1	8.35	7.8	5.7	3.5	.....	.....	4.2	7.6
.....	8.05	12.05	11.0	8.05	7.6	.....	.....	3.6	.....	.....	.....
.....	7.45	11.85	10.5	8.4	7.7	5.4	3.5	3.5	.....	4.1	7.6
.....	6.65	5.7	10.3	8.85	7.8	.....	.....	3.5	.....	.....	7.7
.....	6.1	5.0	10.1	8.75	7.6	5.1	.....	.....	.....	4.1	7.7
.....	5.75	6.0	9.9	9.05	7.5	.....	.....	.....	.....	.....	.....
.....	5.45	9.05	9.7	9.65	7.5	4.9	.....	.....	.....	4.1	7.8
.....	5.25	8.05	9.5	9.55	7.5	.....	.....	.....	.....	.....	.....
.....	4.95	8.1	9.3	9.7	7.4	4.7	.....	.....	.....	6.1	7.5
.....	4.6	.....	9.1	9.65	7.2	.....	.....	.....	.....	14.7	.....
.....	4.1	.....	8.9	9.4	7.0	4.5	.....	.....	.....	12.6	7.4
.....	3.6	.....	8.7	.....	6.9	.....	.....	.....	.....	.....	7.4

NOTE.—No gage record June 4 to 12. No flow during August.

Daily discharge, in second-feet, of Gila River at Dome (Gila City), Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Sept.	Oct.	Nov.	Dec.
.....	.....	80	5,150	6,800	9,500	1,850	280	.....	.....	.....	30,700
.....	.....	.....	21,500	6,800	8,100	1,550	270	.....	.....	.....	24,400
.....	.....	.....	34,000	6,000	8,500	900	240	.....	940	.....	18,200
.....	.....	.....	11,800	7,300	7,700	880	210	.....	870	.....	11,900
.....	.....	280	5,000	8,500	6,000	860	180	.....	750	.....	5,700
.....	.....	2,220	3,050	12,400	6,400	840	150	.....	630	.....	5,000
.....	.....	20,800	1,050	13,800	6,000	830	140	.....	450	.....	4,100
.....	.....	82,000	450	9,000	5,000	810	120	.....	400	.....	3,800
.....	.....	35,800	370	8,100	5,000	790	100	.....	360	.....	3,600
.....	40	14,900	300	8,500	5,000	770	90	.....	300	.....	4,100
.....	2,220	6,900	5,000	9,000	4,100	750	80	.....	240	.....	3,600
.....	2,600	2,920	10,000	8,500	5,600	730	60	.....	200	.....	3,300
.....	2,840	60	3,800	22,000	5,000	720	60	390	150	.....	3,300
.....	2,960	1,920	3,500	64,000	4,400	720	60	330	100	390	3,300
.....	4,680	300	10,300	34,000	4,700	740	40	270	60	450	3,400
.....	18,600	.....	39,000	23,000	5,000	750	30	180	40	450	3,600

Daily discharge, in second-feet, of Gila River at Dome (Gila City), Ariz., for 1905—Cont'd.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Sept.	Oct.	Nov.	Dec.
17	26,000	140	20,000	15,300	5,000	740	30	90	30	380	3,700
18	10,200	230	27,800	10,900	4,700	720	30	80	20	300	3,800
19	5,650	24,800	62,000	8,300	3,800	690	20	60	.....	280	3,800
20	3,690	42,800	95,000	6,200	4,400	660	.....	40	.....	210	3,800
21	3,060	45,200	25,500	5,150	3,800	620	.....	30	.....	200	3,800
22	2,560	40,200	20,000	6,400	4,100	570	.....	20	.....	180	3,800
23	1,990	630	18,000	8,300	4,400	520	.....	.....	.....	180	4,100
24	1,660	300	16,100	7,900	3,800	480	.....	.....	.....	180	4,100
25	1,460	900	14,500	9,250	3,500	450	.....	.....	.....	180	4,200
26	1,290	9,250	13,100	12,750	3,500	420	.....	.....	.....	180	4,400
27	1,180	5,150	11,800	12,100	3,500	390	.....	.....	.....	480	4,000
28	1,020	5,300	10,600	13,100	3,300	360	.....	.....	.....	780	3,600
29	830	.....	9,500	12,750	2,800	330	.....	.....	.....	95,000	3,400
30	560	.....	8,500	11,200	2,350	300	.....	.....	.....	36,900	3,300
31	310	.....	7,700	.....	2,150	.....	.....	.....	.....	.....	3,300

NOTE.—Daily discharge obtained from several rating tables, each covering a short period of time. Discharge estimated for missing gage heights. No flow during August.

Estimated monthly discharge of Gila River at Dome (Gila City), Ariz., for 1905.

[Drainage area, 71,050 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	26,000	0	3,077	189,200	0.043	0.050
February	82,000	0	12,250	680,300	.172	.179
March	95,000	300	16,590	1,020,000	.233	.269
April	64,000	5,150	12,910	768,200	.182	.203
May	9,500	2,150	4,874	299,700	.069	.080
June	1,850	300	725	43,140	.010	.011
July	280	0	70.6	4,341	.00099	.001
August	0	0	0	0	.0	.0
September	390	0	49.7	2,957	.00070	.000
October	940	0	179	11,010	.0025	.002
November	95,000	0	4,557	271,200	.064	.071
December	30,700	3,300	6,100	375,100	.086	.099
The year	95,000	0	5,115	3,665,000	.072	.967

SAN FRANCISCO RIVER AT ALMA, N. MEX.

This station was established October 18, 1904. It is located about one-half mile sout of Alma, N. Mex., and 85 miles northwest of Silver City. It is best reached by stage fro Silver City, which makes the trip daily except Sundays.

The channel is straight for about 500 feet above and below the station. The banks ar about 4 feet high, are clean, and are subject to overflow during extreme high water. Th bed of the stream is composed of gravel, is free from vegetation, and is firm and regula The current is swift.

Discharge measurements are made by means of a cable, car, and tagged wire. Th *initial point* for soundings is the zero of the tagged wire. The cable was carried away b

eavy flood on March 16, 1905, but was recovered and restored at a point about 600 feet her upstream on March 24. Measurements prior to March 16 were taken at the lower tion; since then the upper section has been used.

The gage, which is read twice each day by Mrs. Ella D. Hollimon, consists of a staff tened to the east or left bank of the stream. The gage was washed out by the flood of rch 16, 1905, but was immediately replaced in its old position. The bench mark is a penny nail driven into a blaze in a cottonwood tree 118.5 feet N. 73° E. from the gage; s marked "U. S. G. S. B. M."; elevation above the zero of the gage, 9.06 feet.

A description of this station with gage height and discharge data is contained in Water-pply Paper No. 133, United States Geological Survey, pages 206–208.

Discharge measurements of San Francisco River at Alma, N. Mex., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
ɔruary 8	Frank Asplind	4.50	a362	May 30	Frank Asplind	2.25	63
ɔruary 10	do	3.70	a172	May 30	do	2.25	a60
ɔruary 14	do	3.90	a209	May 31	do	2.2	54
ɔruary 27	do	4.30	a294	June 3	do	2.15	43
rch 4	do	5.20	a1,463	June 4	do	2.15	a45
rch 11	do	3.80	a767	June 6	do	2.10	35
rch 13	do	3.20	a385	June 7	do	2.10	a32
rch 14	do	4.4	a1,098	June 16	do	2.65	24
rch 15	do	4.6	a1,207	June 17	do	2.05	a22
rch 16	do	4.0	a925	June 19	do	2.00	22
rch 25	do	4.1	a1,068	June 20	do	2.00	a21
rch 27	do	4.2	a1,065	June 21	do	1.95	16.8
il 3	do	5.70	a2,835	June 23	do	1.90	12.4
il 4	do	4.30	a1,634	June 24	do	1.85	9.1
il 6	do	5.40	a2,517	June 26	do	1.80	5.8
il 7	do	5.00	a2,115	June 29	do	1.75	4.0
il 11	do	4.20	a1,336	July 15	do	1.95	15.5
il 12	do	4.70	a1,719	July 15	do	2.00	21
il 14	do	4.50	a1,546	July 18	do	1.90	12.5
il 18	do	3.90	933	July 20	do	2.15	40
il 19	do	3.80	806	July 21	do	2.20	52
il 22	do	3.55	502	August 1	do	2.15	33
il 24	do	4.50	1,478	August 2	do	2.15	29
l 26	do	4.05	1,128	August 3	do	2.10	23
l 27	do	3.90	970	August 4	do	2.18	33
l 29	do	3.75	828	August 5	do	2.20	40
2	do	3.55	629	August 8	do	2.50	104
4	do	3.30	479	August 9	do	2.20	39
6	do	3.00	a359	August 10	do	2.20	40
9	do	3.00	333	August 11	do	2.22	46
12	do	2.90	289	August 11	do	2.45	79
12	do	2.90	a251	August 12	do	2.30	54
14	do	2.85	261	August 14	do	2.15	27
14	do	2.85	a238	August 15	do	2.10	19.2
16	do	2.80	234	August 16	do	2.05	16.7
16	do	2.80	a211	August 30	do	2.15	10.9
25	do	2.4	95	August 31	do	2.30	31
26	do	2.4	a95	September 2	do	2.20	16.1
27	do	2.35	83	September 3	do	3.55	a741
28	do	2.30	72	September 4	do	2.40	65
28	do	2.30	a70	September 4	do	4.30	a1,218

aFloat measurement.

Discharge measurements of San Francisco River at Alma, N. Mex., in 1905—Continued.

Date	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
September 5	Frank Asplind	2.82	248	October 24	Frank Asplind	2.40	68
September 6	do	3.25	455	November 7	do	2.40	59
September 7	do	2.32	80	November 8	do	3.20	220
September 8	do	2.25	58	November 9	do	2.72	99
September 9	do	2.30	71	November 10	do	2.52	66
September 11	do	2.20	49	November 11	do	2.40	51
September 12	do	2.15	39	November 13	do	2.45	61
September 13	do	2.10	30	November 15	do	2.40	54
September 14	do	2.10	28	November 17	do	2.40	55
September 16	do	2.10	28	November 18	do	2.40	55
October 2	do	2.30	[a] 58	December 6	do	2.25	167
October 3	do	2.25	[a] 46	December 7	do	1.95	107
October 4	do	2.20	37	December 9	do	1.75	72
October 5	do	2.20	37	December 11	do	1.75	68
October 6	do	2.20	36	December 12	do	1.70	60
October 7	do	2.20	36	December 13	do	1.70	59
October 9	do	2.20	37	December 14	do	1.65	50
October 10	do	2.20	36	December 15	do	1.60	42
October 11	do	2.20	34	December 16	do	1.62	46
October 12	do	2.20	36	December 18	do	1.60	42
October 13	do	2.20	36	December 19	do	1.60	42
October 14	do	2.20	35	December 20	do	1.60	42
October 16	do	2.20	35	December 22	do	1.60	42
October 18	do	2.20	34	December 23	do	1.50	34
October 19	do	2.20	36	December 26	do	1.45	30
October 20	do	2.20	35	December 28	do	1.50	33
October 21	do	2.20	33	December 29	do	1.45	28
October 23	do	2.40	68	December 30	do	1.45	27

[a] Float measurement.

Daily gage height, in feet, of San Francisco River at Alma, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.2	2.2	5.85	3.6	3.52	2.2	1.8	2.35	2.3	2.5	2.3	.....
2	1.2	2.8	5.5	4.15	3.5	2.18	1.8	2.1	2.2	2.48	2.5	.....
3	1.2	2.45	5.55	5.0	3.4	2.1	1.8	2.05	2.2	2.35	2.5	2.42
4	1.2	5.0	5.55	4.4	3.4	2.1	1.78	2.05	2.5	2.3	2.6	2.42
5	1.2	5.0	5.6	4.9	3.3	2.0	1.75	2.1	2.5	2.3	2.9	2.32
6	1.2	5.15	4.7	4.85	3.15	2.0	1.78	2.15	2.4	2.2	3.8	2.25
7	1.2	4.8	5.0	4.75	3.1	2.0	1.8	2.05	2.3	2.2	3.6	2.1
8	1.2	4.5	5.42	4.6	3.1	2.2	1.8	3.25	2.3	2.2	3.8	1.85
9	1.75	4.25	4.35	4.25	3.1	2.18	1.8	2.35	2.3	2.2	3.0	1.8
10	5.85	3.7	3.75	4.25	3.0	2.1	1.8	2.2	2.25	2.15	2.52	1.72
11	3.4	3.2	3.6	4.2	3.0	2.1	1.8	2.5	2.22	2.15	2.5	1.7
12	2.65	3.5	3.4	4.45	2.95	2.1	1.8	2.35	2.22	2.2	2.42	1.68
13	2.4	3.7	3.2	4.95	2.9	2.0	1.8	2.3	2.15	2.2	2.4	1.68
14	2.35	3.9	4.35	4.42	2.82	2.0	1.8	2.2	2.12	2.2	2.4	1.68
15	2.3	3.65	4.3	4.2	2.8	2.0	1.9	2.2	2.1	2.2	2.4	1.62
16	2.3	3.85	4.0	3.95	2.8	2.0	1.9	2.18	1.98	2.2	2.4	1.62
17	2.3	6.3	5.9	3.85	2.77	2.0	2.0	2.12	2.0	2.2	2.4	1.58
18	2.3	6.4	5.1	3.85	2.75	1.92	1.9	2.1	2.0	2.2	2.4	1.52

ily gage height, in feet, of San Francisco River at Alma, N. Mex., for 1905—Continued.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	2.3	3.75	4.7	3.8	2.75	1.95	1.9	2.1	2.0	2.2	2.35	1.52
.....	2.22	3.8	5.2	3.7	2.7	1.9	2.1	2.0	2.0	2.2	2.35	1.52
.....	2.22	3.0	4.6	3.6	2.7	1.9	2.1	2.85	2.1	2.2	2.52	1.62
.....	2.21	2.9	4.5	3.52	2.7	1.9	2.1	2.8	2.2	2.2	3.85	1.65
.....	2.21	4.35	4.5	4.55	2.55	1.9	2.15	2.35	3.2	2.2	3.62	1.62
.....	2.2	3.22	4.3	4.7	2.5	1.9	2.0	2.1	4.65	2.4	3.3	1.62
.....	2.15	3.95	4.1	4.4	2.45	1.88	2.0	2.05	3.5	2.38	2.7	1.52
.....	2.1	3.75	4.1	4.0	2.42	1.82	2.0	2.1	3.2	2.3	2.62	1.42
.....	2.1	4.4	4.0	3.9	2.37	1.8	2.0	2.1	3.2	2.3	.....	1.42
.....	2.1	6.05	3.85	4.0	2.3	1.8	2.0	2.15	3.12	2.3	.....	1.42
.....	2.2	.....	3.75	3.7	2.27	1.8	2.75	2.3	2.8	2.3	.....	1.38
.....	2.35	.....	3.5	3.5	2.25	1.8	2.25	3.05	2.6	2.3	.....	1.38
.....	2.5	.....	3.55	.....	2.22	.....	2.35	2.85	.....	2.3	.....	1.38

Daily discharge, in second-feet, of San Francisco River at Alma, N. Mex., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	10	190	3,410	681	618	52	6	72	27	115	45	.....
.....	10	570	2,360	1,155	602	48	6	24	16	100	85	.....
.....	10	287	2,510	2,048	548	32	6	18	75	65	85	215
.....	10	910	2,510	1,380	548	32	5	21	90	55	115	215
.....	10	910	2,660	1,932	494	20	4	26	120	55	210	185
.....	10	1,310	460	1,874	413	20	5	32	85	36	755	162
.....	10	560	910	1,758	386	20	6	20	74	36	575	120
.....	10	370	2,120	1,590	386	52	6	425	74	36	550	74
.....	80	295	325	1,245	386	48	6	72	74	36	190	67
.....	3,162	170	180	1,245	332	32	6	40	63	25	75	56
.....	1,080	110	155	1,200	332	32	6	110	36	25	70	53
.....	357	140	130	1,430	306	32	6	63	56	36	60	51
.....	260	170	110	1,990	280	20	6	50	42	36	55	51
.....	240	210	325	1,400	240	20	6	33	36	36	55	51
.....	220	163	310	1,200	230	20	12	30	32	36	55	44
.....	220	200	230	975	230	20	12	30	18	36	55	44
.....	220	4,760	3,092	885	215	20	20	23	17	36	55	40
.....	220	5,060	2,164	885	205	14	12	19	17	36	55	35
.....	220	180	1,700	840	205	16	12	16	17	36	45	35
.....	196	190	2,280	760	180	12	32	9	17	36	45	35
.....	196	90	1,590	681	180	12	32	75	25	36	85	44
.....	193	80	1,480	618	180	12	32	55	40	36	750	48
.....	193	325	1,480	1,535	135	12	42	42	415	36	585	44
.....	190	112	1,290	1,700	120	12	20	12	1,575	68	405	44
.....	175	220	1,110	1,380	107	11	20	8	565	60	125	35
.....	160	180	1,110	1,020	99	8	20	11	405	45	110	27
.....	160	340	1,020	930	88	6	20	9	405	45	.....	27
.....	160	4,010	885	1,020	74	6	20	11	365	45	.....	27
.....	190	.....	800	760	88	6	205	23	195	45	.....	25
.....	240	.....	602	602	64	6	63	220	125	45	.....	25
.....	315	.....	642	.....	58	.....	85	160	.....	45	.....	25

NOTE.—Daily discharge obtained by indirect method.

Estimated monthly discharge of San Francisco River at Alma, N. Mex., for 1905.

[Drainage area, 1,800 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	3,162	10	282	17,340	0.157	0.181
February	5,060	80	790	43,870	.439	.457
March	3,410	110	1,289	79,260	.716	.826
April	2,048	602	1,224	72,830	.680	.759
May	618	58	269	16,540	.149	.172
June	52	6	21.8	1,297	.012	.013
July	205	4	23.8	1,463	.013	.015
August	425	8	56.7	3,486	.032	.037
September	1,575	16	170	10,120	.094	.105
October	115	25	45.6	2,804	.025	.029
November 1-26	755	45	204	10,520	.113	.109
December 3-31	215	25	65.7	3,779	.036	.029
The period	.....	.....	.....	263,300	.....	.....

SAN PEDRO RIVER AT CHARLESTON, ARIZ.

This station was established January 22, 1904. It is located about one-half mile west of Charleston station on the El Paso and Southwestern Railroad and 6 miles south of Fairbank, Ariz.

The channel is straight for about 800 feet above and 500 feet below the station. Both banks are nearly vertical for 20 feet, are clean, and are not subject to overflow. The bed of the stream is composed of sand and is shifting. At high water there is but one channel, but at low water the channel is divided by sand bars. The current is swift.

Discharge measurements are made at high water by a cable and car 10 feet below the gage. The initial point for soundings is 21 feet from the cable support on the east bank. Low-water measurements are made by wading.

The gage is read twice each day by H. R. Fry. The original gage was read until March 28, 1904, when a second gage was established 200 feet upstream from the first. The second gage, which was read from March 29 to July 30, 1904, is in two sections: The upper section is attached vertically to a cottonwood tree on the left bank; the upper end of the lower section, which is inclined, is fastened to the same tree and the lower end is set in the bed of the stream. In July and August, 1904, floods changed the channel to such an extent that a third gage became necessary. This was established August 15, 1904, on the east bank, directly opposite the old or second gage, and consists of a vertical rod fastened to a dead-man in the bank at the same datum as the old gage. Readings have since been made from the third gage. The bench marks are as follows: (1) A United States Geological Survey standard iron bench-mark post near a post on the east side of the El Paso and Southwestern Railroad station at Charleston: elevation, 57.265 feet above the zero of the gage and 3,957.265 feet above mean sea level. (2) A spike in the west side of the root of a tree on the west bank of the river, 100 feet above the gage; elevation, 35.860 feet above the zero of the gage and 3,935.860 feet above mean sea level.

A description of this station, with gage-height and discharge data, is contained in Water-Supply Paper No. 133, United States Geological Survey, pages 208–211.

Discharge measurements of San Pedro River at Charleston, Ariz., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft*
uary 4	H. R. Fry	26.05	24	June 28	H. R. Fry	26.30	17
uary 11	do	26.90	124	July 5	do	26.15	12
uary 18	do	26.80	35	July 12	do	27.30	122
uary 25	do	26.70	31	July 19	do	26.25	14
ruary 1	do	26.40	23	July 29	do	26.50	61
ruary 9	do	27.25	120	August 7	do	.....	38
ruary 15	do	26.60	36	August 12	do	26.00	46
ruary 21	do	27.35	147	August 17	do	26.05	82
ch 1	do	27.10	111	August 26	do	26.80	133
ch 22	do	26.85	81	September 7	do	26.30	80
ch 30	do	26.80	99	September 15	do	25.60	37
il 5	do	26.30	71	September 21	do	25.70	38
il 12	do	26.20	50	September 28	do	26.10	62
il 19	do	26.30	79	October 4	W. Rayling	25.60	28
il 26	do	26.00	37	October 11	do	25.50	34
y 3	do	26.15	51	October 18	do	25.60	31
y 10	do	25.95	31	October 25	do	25.50	27
y 17	do	25.85	25	November 1	do	25.50	23
y 24	do	25.85	22	November 8	do	25.40	24
y 24	do	25.85	20	November 15	do	25.70	42
y 31	do	25.82	18	November 22	do	25.80	54
e 7	do	25.80	18	December 6	do	.....	98
e 14	do	26.65	52	December 13	do	.....	102
e 21	do	26.35	20	December 20	do	25.50	61
e 28	do	26.30	20	December 27	do	25.40	54

OTE.—Gage washed away by flood on November 28.

Daily gage height, in feet, of San Pedro River at Charleston, Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	26.15	26.4	27.1	26.65	26.35	25.82	26.25	.....	25.65	25.8	25.5	.....
.....	26.1	26.4	28.02	26.57	26.25	25.82	26.25	.....	26.85	25.8	25.5	.....
.....	26.1	26.4	27.52	26.45	26.15	25.82	26.25	.....	27.6	25.7	25.5	.....
.....	26.05	26.5	27.7	26.3	26.15	25.82	26.22	.....	27.75	25.6	25.5	.....
.....	26.05	27.1	27.8	26.27	26.05	25.78	26.15	.....	28.25	25.5	25.5	.....
.....	26.05	26.62	27.45	26.22	26.05	25.8	26.18	.....	26.5	25.5	25.5	.....
.....	26.1	27.9	27.75	26.17	26.05	25.8	26.18	.....	26.35	25.35	25.35	.....
.....	26.1	27.6	28.85	26.1	25.92	25.85	26.18	.....	26.45	25.5	27.2	.....
.....	26.1	27.2	27.85	26.1	25.92	26.00	26.22	27.5	26.0	25.5	27.55	.....
.....	26.65	26.87	28.5	26.1	25.95	27.65	26.22	26.9	25.95	25.5	26.75	.....
.....	26.9	26.85	27.35	26.1	25.9	27.15	26.48	26.8	25.55	25.5	26.7	.....
.....	26.9	26.8	27.87	26.2	25.9	26.85	27.28	26.0	25.55	27.0	25.9	.....
.....	26.85	26.7	27.1	26.47	25.87	26.68	27.32	26.35	25.55	27.0	25.8	.....
.....	26.9	26.65	27.06	27.3	25.85	26.6	26.62	27.0	25.55	26.45	25.7	.....
.....	26.9	26.6	27.1	26.9	25.85	26.6	26.45	26.05	25.9	26.2	25.7	.....
.....	26.95	26.6	26.9	26.5	25.82	26.52	26.35	26.85	26.3	26.0	25.7	.....
.....	26.85	26.65	30.85	26.3	25.82	26.5	26.32	27.92	26.4	25.8	25.7	25.5
.....	26.85	26.85	28.25	26.3	25.82	26.42	26.25	26.1	26.35	25.6	25.6	25.5
.....	26.8	27.65	27.6	26.27	25.82	26.42	26.25	27.75	25.9	25.6	25.6	25.5
.....	26.8	27.8	27.23	26.2	25.8	26.35	26.2	28.15	25.7	25.6	25.6	25.5
.....	26.8	27.27	26.95	26.15	25.83	26.35	26.22	29.1	26.2	25.6	25.6	25.6

Daily gage height, in feet, of San Pedro River at Charleston, Ariz., for 1905—Continued.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
22	26.8	27.12	26.85	26.2	25.83	26.3	26.22	27.85	26.25	25.5	26.0	25.5
23	26.8	26.9	26.9	26.17	25.83	26.3	26.18	27.15	25.8	25.5	25.8	25.4
24	26.75	26.82	26.9	26.15	25.83	26.28	26.18	26.45	25.9	25.5	26.1	25.4
25	26.65	26.6	26.85	26.0	25.83	26.28	28.1	27.15	27.8	25.5	25.8	25.4
26	26.55	26.75	26.6	26.97	25.83	26.25	28.45	26.8	27.25	25.5	25.8	25.4
27	26.5	26.6	26.42	25.95	25.83	26.25	28.32	26.6	26.4	25.5	29.15	25.4
28	26.45	26.65	26.32	25.95	25.82	26.3	26.95	26.1	26.15	25.5	29.3	25.4
29	26.45	.....	26.3	26.2	25.82	26.25	26.5	25.85	26.1	25.5	.....	25.4
30	26.45	.....	26.82	26.41	25.82	26.28	26.5	25.75	25.9	25.5	.....	25.4
31	26.4	.....	26.75	.....	25.82	.....	26.3	25.85	.....	25.5	.....	25.4

NOTE.—Gage washed out by flood November 28.

Daily discharge, in second-feet, of San Pedro River at Charleston, Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	36	23	110	91	64	18	15	.....	44	41	23	.....
2	30	23	247	86	58	18	15	.....	49	41	23	.....
3	30	23	172	79	51	18	15	.....	177	34	23	.....
4	24	25	164	71	51	18	14	.....	186	28	23	.....
5	24	47	114	70	42	16	12	.....	219	24	23	.....
6	24	27	162	56	42	17	13	.....	95	25	23	.....
7	30	235	207	48	42	17	13	.....	83	17	21	.....
8	30	180	370	44	43	18	13	.....	90	29	149	.....
9	30	108	222	44	31	25	14	135	61	30	174	.....
10	94	70	319	44	32	135	14	93	58	31	118	.....
11	124	67	148	44	29	97	33	86	30	34	112	.....
12	124	61	76	50	28	74	118	46	30	134	56	.....
13	66	49	110	67	25	57	123	77	30	134	49	.....
14	41	43	104	122	25	48	49	129	30	96	42	.....
15	41	36	110	96	25	47	31	70	57	79	42	.....
16	44	36	81	69	22	39	20	62	82	62	42	.....
17	35	43	668	79	23	36	18	211	88	47	42	61
18	35	73	281	79	24	28	14	86	86	31	38	61
19	31	191	185	75	24	28	14	198	55	31	38	61
20	31	214	129	65	22	20	13	225	40	31	38	61
21	31	136	86	58	23	20	13	287	73	32	38	68
22	31	113	81	65	23	15	13	206	76	25	68	61
23	31	81	87	61	23	15	12	164	45	25	53	58
24	30	69	87	58	21	12	12	110	52	26	74	58
25	28	36	81	44	21	12	177	157	183	27	45	58
26	26	58	51	145	19	10	201	134	143	26	45	58
27	25	36	30	30	18	10	192	120	82	26	286	58
28	24	43	17	30	18	18	96	86	65	25	296	58
29	24	.....	15	50	18	16	61	69	55	24	.....	58
30	24	.....	100	75	18	16	61	62	48	23	.....	58
31	23	.....	89	.....	18	.....	55	69	.....	23	.....	58

NOTE.—Daily discharge obtained by indirect method.

Estimated monthly discharge of San Pedro River at Charleston, Ariz., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
ıry	124	23	39.4	2,423
ıary	235	23	76.6	4,254
ı	668	15	152	9,346
	145	30	66.5	3,957
	64	18	29.8	1,832
	135	10	30.6	1,821
	201	12	47.2	2,902
st (9-31)	287	46	125	5,702
mber	219	30	80.4	4,784
ıer	134	17	40.7	2,502
mber (1-28)	296	21	71.6	3,976
ıber (17-31)	68	54	57.3	1,705
The period				45,200

SALT RIVER AT ROOSEVELT, ARIZ.

is station was established February 7, 1901. It is located at the town of Roosevelt, h is the United States Reclamation Service construction camp for the Salt River dam reservoir, and is about 12 miles west of Livingston, Ariz. The gage rod and cable t the upper end of the gorge, about 2,000 feet below the mouth of Tonto Creek and) feet above the dam site.

scharge measurements are made by means of a car suspended from a cable.

e gage is a vertical rod fastened to the rocks on the left bank of the river.

formation in regard to this station is contained in the following Water-Supply Papers e United States Geological Survey:

iption: 66, pp 99–100; 85, p 25; 100, p 42; 133, p 212.
arge: 66, p 100; 85, pp 26–27; 100, pp 42–43; 133, pp 212–213.
arge, mean daily: 133, p 214.
arge, monthly: 75, p 178; 85, p 29; 100, p 45; 133, p 214.
heights: 66, p 100; 85, p 28; 100, p 44; 133, p 213.
ıg table: 85, p 28.

Discharge measurements of Salt River at Roosevelt, Ariz., in 1905.

Date.	Hydrographer.	Gage height.	Discharge	Date.	Hydrographer.	Gage height.	Discharge
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
ary 4	Osburn Richins	21.00	30,360	February 4	Osburn Richins	23.50	[a]43,350
ary 4	do	20.50	26,680	February 7	do	11.50	[a]6,872
ary 4	do	23.50	38,530	February 14	do	9.60	3,424
ary 4	do	16.00	16,200	February 17	do	17.40	[a]22,640
ary 7	do	11.50	6,107	February 18	do	17.10	25,610
ary 10	do	11.50	[a]3,189	February 18	do	16.80	[a]23,000
ary 11	do	15.80	[a]12,600	February 23	do	10.90	[a]5,384
ary 13	do	10.00	4,528	February 27	do	10.10	[a]5,166
ary 18	do	8.10	742	February 28	do	11.80	11,790
ary 21	do	8.10	751	February 28	do	15.95	[a]19,920
ary 27	do	7.70	554	February 28	do	18.00	[a]28,120
uary 4	do	16.00	[a]18,220	February 28	do	19.50	[a]33,430
uary 4	do	21.00	[a]34,160	February 28	do	20.00	[a]36,340
uary 4	do	20.50	[a]30,020	March 2	do	11.40	[a]11,610

[a] Float measurement.

Discharge measurements of Salt River at Roosevelt, Ariz., in 1905—Continued.

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*
March 10	Osburn Richins	11.55	a10,060
March 13	do	13.00	a13,540
March 14	do	20.50	a40,520
March 17	do	20.70	a41,380
March 18	do	19.70	a39,850
March 20	do	21.30	a51,130
March 24	do	10.50	11,000
March 29	do	9.50	6,748
April 4	do	13.70	14,600
April 6	do	12.00	7,154
April 10	do	12.40	7,908
April 12	Richins and Farish.	23.50	a43,560
April 12	do	25.00	a47,620
April 13	do	20.00	40,230
April 14	do	12.90	19,030
April 15	do	11.80	13,370
April 16	do	11.40	11,500
April 18	Osburn Richins	10.00	8,875
April 20	do	10.15	9,262
April 22	do	9.60	8,335
April 24	do	10.95	11,050
April 25	do	11.85	13,920
April 26	do	11.75	13,840
April 27	do	11.10	11,470
April 28	do	10.90	9,814
May 1	do	10.50	9,524
May 3	do	10 60	9,534
May 4	do	10.20	8,390
May 5	do	9 80	6,522
May 6	do	9 30	5,811
May 10	do	9 30	5,471
May 11	do	9.00	5,606
May 12	do	8.80	4,956
May 13	do	8.60	4,269
May 15	Murphy and Richins	8.42	4,080
May 17	Osburn Richins	8 40	4,026
May 18	do	8.40	4,043
May 19	do	8.45	4,155
May 20	do	8.35	4,012
May 22	do	7.90	3,299
May 23	do	7.80	3,131
May 24	do	7.65	2,846
May 25	do	7.50	2,841
May 27	do	7.30	2,420
May 29	do	7.00	2,272
May 31	do	6.70	1,921
June 2	do	6.55	1,840
June 5	do	6.70	1,957
June 7	do	6.50	1,701
June 8	do	6.60	1,881
June 9	do	7.20	2,414
June 10	do	7.10	2,275
June 12	Osburn Richins	6.70	1,823
June 13	do	6.50	1,702
June 14	do	6.30	1,387
June 16	do	6.10	1,376
June 17	do	6.10	1,309
June 19	do	5.85	1,256
June 20	do	5.70	1,070
June 21	do	5.60	938
June 22	do	5.55	905
June 23	do	5.45	877
June 24	do	5.40	904
June 26	do	5.30	808
June 27	do	5.20	770
June 28	do	5.15	730
June 29	do	5.10	711
June 30	do	5.05	695
July 1	do	5.05	687
July 7	do	4.60	495
July 8	do	4.50	433
July 10	do	4.40	374
July 12	do	4.30	344
July 13	do	4.40	358
July 14	do	4.30	283
July 15	do	4.30	313
July 17	do	4.60	477
July 18	do	4.50	400
July 19	do	4.50	392
July 20	do	4.35	363
July 22	do	4.40	412
July 24	do	4.50	466
August 1	do	5.20	630
August 2	do	5.00	603
August 4	do	4.60	554
August 5	do	4.40	522
August 7	do	4.50	537
August 8	do	4.30	466
August 10	do	5.30	634
August 11	do	5.90	736
August 12	do	5.10	603
August 14	do	4.90	536
August 15	do	4.70	461
August 17	do	4.80	471
August 18	do	4.70	436
August 19	do	4.50	394
August 21	do	5.50	774
August 22	do	4.70	452
August 23	do	7.20	2,495
August 25	do	6.70	1,578
August 26	do	5.20	705
August 28	do	5.00	557
August 30	do	5.20	593
August 31	do	5.10	557
September 1	do	5.00	540
September 2	do	5.30	54[illegible]

a Float measurement.

of Salt River at Roosevelt, Ariz., in 1905—Continued.

Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
5.20	741	November 8...	E. O. Blades.....	6.60	2,045
6.65	2,031	November 9...	.....do.....	5.40	1,292
5.40	913	November 10..	.....do.....	5.00	791
4.70	762	November 11..	.....do.....	4.80	715
4.60	653	November 13..	.....do.....	4.50	638
4.40	612	November 14..	.....do.....	4.40	587
4.20	448	November 15..	.....do.....	4.30	510
4.00	316	November 16..	.....do.....	4.20	539
3.80	315	November 17..	.....do.....	4.20	524
3.80	292	November 18..	.....do.....	4.15	491
3.60	227	November 20..	.....do.....	4.10	471
6.15	1,252	November 21..	.....do.....	4.15	484
6.30	1,321	November 22..	.....do.....	6.75	3,168
6.90	1,414	November 23..	.....do.....	6.55	2,230
5.60	710	November 24..	.....do.....	6.75	2,660
5.30	574	November 25..	.....do.....	6.50	1,827
5.10	500	December 5...	.....do.....	7.65	2,497
4.90	385	December 6....	.....do.....	7.55	2,347
4.70	261	December 7....	.....do.....	7.45	1,993
4.40	283	December 8....	.....do.....	7.35	1,762
4.20	231	December 9....	.....do.....	7.30	1,561
4.00	316	December 11...	.....do.....	7.10	1,341
3.90	297	December 12...	.....do.....	7.10	1,276
3.90	302	December 13...	.....do.....	7.00	1,149
3.90	300	December 14...	.....do.....	7.00	1,168
		December 15...	.....do.....	6.90	1,091
3.80	308	December 16...	.....do.....	6.90	981
3.80	307	December 18...	.....do.....	6.80	888
3.80	335	December 19...	.....do.....	6.80	869
3.80	320	December 20...	.....do.....	6.80	865
3.80	331	December 21...	.....do.....	7.00	1,041
3.80	314	December 22...	.....do.....	7.00	1,213
3.80	304	December 23...	.....do.....	6.95	945
3.80	305	December 26...	.....do.....	6.60	697
3.80	299	December 27...	.....do.....	6.70	829
3.80	306	December 28...	.....do.....	6.80	887
4.25	628	December 29...	.....do.....	6.80	945
4.20	610				

in feet, of Salt River at Roosevelt, Ariz., for 1905.

r.	Apr.	May.	June.	July.	Aug.	Sept.	Oct	Nov.	Dec.
8	10.0	10.5	6.55	5.0	5.2	5.05	6.15	3.8	8.75
1	10.3	10.6	6.52	4.9	4.95	5.15	5.6	3.8	8.5
0	11.35	10.6	6.45	4.85	4.75	6.05	5.2	3.8	8.1
8	13.2	10.25	6.72	4.8	4.55	4.95	5.05	3.8	7.85
05	12.6	9.75	6.7	4.7	4.4	5.5	4.9	3.95	7.65
1	11.6	9.25	6.7	4.6	4.45	6.4	4.75	4.25	7.55
9	11.9	9.0	6.5	4.6	4.45	5.65	4.65	4.2	7.45
6	11.9	9.0	6.62	4.5	4.3	5.3	4.45	6.65	7.55
9	12.15	9.2	7.2	4.45	4.2	4.8	4.3	5.4	7.3
45	12.6	9.25	7.05	4.4	5.15	4.75	4.2	5.0	7.2
4	16.2	9.0	6.85	4.4	5.75	4.65	4.2	4.75	7.1
85	23.5	8.75	6.65	4.3	5.15	4.5	4.1	4.65	7.0

Daily gage height, in feet, of Salt River at Roosevelt, Ariz., for 1905—Continued.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
13	9.9	10.1	15.5	22.5	8.6	6.5	4.35	4.95	4.5	4.0	4.5	7.0
14	9.0	9.5	19.95	13.35	8.5	6.25	4.3	4.9	4.2	4.0	4.4	7.0
15	8.65	9.3	14.1	11.9	8.42	6.2	4.3	4.7	4.0	4.0	4.3	6.9
16	8.55	9.92	12.5	10.9	8.4	6.1	4.6	4.8	4.0	4.0	4.2	6.9
17	8.45	17.35	20.25	9.9	8.4	6.1	4.6	4.75	3.9	4.0	4.2	6.8
18	8.35	16.70	19.35	9.9	8.4	5.9	4.45	4.7	3.8	4.0	4.15	6.8
19	8.25	11.45	14.65	9.9	8.42	5.82	4.5	4.6	3.8	4.0	4.1	6.8
20	8.13	10.35	19.65	10.15	8.3	5.7	4.5	4.5	3.8	3.9	4.1	6.8
21	8.1	9.7	14.0	9.75	8.07	5.6	4.5	5.15	3.7	3.9	4.15	7.0
22	8.04	9.5	10.9	9.55	7.87	5.55	4.45	4.6	3.6	3.9	6.75	7.0
23	7.97	10.25	10.25	9.85	7.75	5.42	4.4	6.8	3.6	3.9	6.55	6.95
24	7.88	11.75	10.35	11.4	7.62	5.4	4.5	5.15	5.45	3.8	6.75	6.95
25	7.84	10.47	9.85	11.65	7.5	5.35	4.5	6.35	5.55	3.8	6.4	6.72
26	7.77	10.18	9.8	11.6	7.4	5.3	4.5	5.4	5.9	3.8	7.5	6.6
27	7.71	10.1	9.7	11.0	7.27	5.15	4.5	5.25	5.1	3.8	26.7	6.7
28	7.68	17.95	9.5	10.9	7.15	5.12	6.1	5.0	5.0	3.8	17.3	6.8
29	7.65	.....	9.3	10.65	6.95	5.08	6.85	5.0	5.9	3.8	10.7	6.8
30	7.65	.....	9.45	10.5	6.8	5.05	5.7	5.15	6.8	3.8	9.4	6.8
31	7.65	.....	9.8	.....	6.7	.....	5.1	5.05	.....	3.8	.....	6.8

Daily discharge, in second-feet, of Salt River at Roosevelt, Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov	Dec.
1	172	526	17,100	7,548	9,350	1,800	650	655	380	1,132	313	3,700
2	172	625	12,150	8,076	9,700	1,770	600	590	460	710	313	4,700
3	172	3,900	9,250	9,819	9,700	1,700	575	572	1,497	527	313	3,670
4	165	31,400	8,925	12,020	8,475	1,970	550	545	526	480	313	3,020
5	165	18,800	11,300	8,937	6,738	1,950	500	522	1,000	385	420	2,497
6	165	16,700	11,330	6,495	5,675	1,950	455	523	1,806	310	628	2,347
7	165	8,250	11,220	6,989	5,175	1,750	455	515	1,136	250	610	1,903
8	165	4,500	11,060	6,989	5,175	1,870	415	490	891	250	2,210	1,702
9	346	3,145	11,220	7,437	5,575	2,450	395	475	783	260	1,292	1,561
10	5,900	2,959	11,540	8,937	5,675	2,300	375	612	772	230	790	1,451
11	12,300	2,037	11,500	20,040	5,175	2,100	375	705	707	230	695	1,341
12	9,460	8,306	8,200	43,350	4,675	1,900	345	612	632	217	670	1,158
13	4,000	4,400	22,050	45,470	4,375	1,750	358	547	632	231	638	1,158
14	2,400	3,238	38,700	20,370	4,200	1,500	335	530	448	245	587	1,138
15	1,685	2,867	17,600	14,010	4,060	1,450	335	461	316	259	510	1,091
16	1,513	4,040	12,150	10,620	4,025	1,350	427	471	316	274	539	981
17	1,341	21,550	39,800	8,864	4,025	1,350	427	450	310	298	524	935
18	1,170	20,450	36,550	8,864	4,025	1,150	378	438	303	302	491	888
19	999	7,000	23,200	8,864	4,060	1,086	392	413	303	316	471	867
20	828	4,800	44,400	9,303	3,850	1,000	392	390	303	300	471	867
21	743	3,614	23,440	8,601	3,455	950	392	625	265	300	484	1,041
22	715	3,238	11,940	8,250	3,159	925	403	427	227	300	3,168	1,213
23	682	4,250	9,524	8,777	3,012	860	402	1,864	227	300	2,230	945
24	640	7,700	9,895	11,500	2,870	850	406	625	970	313	2,660	860
25	620	4,990	8,040	12,750	2,750	825	406	1,327	1,010	313	1,755	765
26	588	4,560	7,855	12,500	2,650	800	406	803	1,150	313	2,150	697
27	560	4,400	7,484	11,160	2,520	725	406	680	830	313	97,710	829
28	546	27,550	6,742	10,800	2,400	712	1,300	527	790	313	45,250	867
29	526	.....	6,000	9,906	2,200	690	2,000	527	1,150	313	14,050	945
30	526	.....	6,700	9,370	2,050	675	935	350	1,515	313	9,480	945
31	526	.....	7,300	.....	1,950	.....	617	325	.....	333	.....	945

NOTE.—Daily discharge obtained by indirect method.

Estimated monthly discharge of Salt River at Roosevelt, Ariz., for 1905.

[Drainage area, 5,756 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	12,300	165	1,611	99,060	0.280	0.323
February	31,400	526	8,207	455,800	1.43	1.49
March	44,400	6,000	15,300	940,800	2.66	3.07
April	45,470	6,495	12,550	746,800	2.18	2.43
May	9,700	1,950	4,604	283,100	.800	.922
June	2,450	675	1,405	83,600	.244	.272
July	2,000	335	529	32,530	.092	.106
August	1,864	325	600	36,890	.104	.120
September	1,497	227	722	42,960	.125	.140
October	1,132	217	342	21,030	.059	.068
November	97,710	313	6,391	380,300	1.11	1.24
December	8,700	697	1,684	103,600	.293	.338
The year	97,710	217	4,495	3,226,000	.781	10.52

SALT RIVER AT M'DOWELL, ARIZ.

This station was established April 20, 1897. It is located one-third mile above the junction of Salt and Verde rivers, 30 miles northeast of Phoenix, 15 miles northeast of Mesa, and 1¼ miles above the Arizona canal diversion dam.

The channel is straight for about 500 feet above the station. The right bank is about 3½ feet high at the water's edge and rises with a gradual slope for 400 feet; it is clean and is subject to overflow. The left bank rises vertically for about 5 feet, at which point there is a small bench, from which the rocks rise to a considerable height; this bank is clean and does not overflow. The bed of the stream is composed of sand and is shifting, and it is necessary to make a large number of measurements in order to obtain an accurate estimate of the discharge. The current is swift.

Discharge measurements are made by means of a cable and car. The initial point for soundings is 120 feet south of the standard under the cable at the north bank. Low-water measurements are made by wading about 1,000 feet upstream from the cable, where a tag wire has been placed.

Gage heights and measurements are taken by W. Richins, who devotes his whole time to the work. There have been five gages in use at this station, as follows:

Gage No. 1, set April 20, 1897, was a 2- by 6-inch timber bolted to the rocks on the south bank of the river, about one-fourth mile above the cable. This gage, which has since been removed, was used until November 30, 1899, when the station was temporarily abandoned. The bench mark is a nail in a palo verde tree about 75 feet west of the cable anchorage on the north bank; elevation, 17.33 feet above the zero of the gage.

Gage No. 2 was established in 1901. It consists of a 2- by 6-inch timber fastened to a tree on the north bank of the river three-fourths mile above the cable. The zero of this gage is 1,323.54 feet above sea level. Its bench mark is a nail in a root of a willow tree, to which the gage is fastened; elevation, 1,328.69 feet above sea level, and 5.10 feet above the zero of the gage. On April 2, 1903, high water in Verde River backed up the water on gage No. 2 and changed the cross section by depositing sand.

Gage No. 3 was installed May 19, 1903. It consists of a 1- by 6-inch stadia rod spiked to a 2- by 4-inch timber and fastened to a tree on the south bank 1½ miles above the cable. The water surface at this gage is about 15 feet higher than at the mouth of the Verde River.

and the zero of the gage is 1,336.27 feet above sea level. Three bench marks have been established for this gage, as follows: (1) A nail in a mesquite stump 200 feet east of Peters's corral; elevation, 1,363.2 feet above sea level and 26.93 feet above the zero of the gage. (2) A nail in the root of a mesquite tree on top of the bank 50 feet northwest of the northwest corner of Peters's corral and about 75 feet from the gage; elevation, 1,356 feet above sea level and 19.73 feet above the zero of the gage. (3) A nail in the willow tree to which the gage is attached; elevation, 1,344.27 feet above sea level and 8.00 feet above the zero of the gage.

Gage No. 4 was a temporary gage on the north side of the river about 600 yards above the section and was read in conjunction with gage No. 3. This temporary gage, No. 4, was washed out by heavy floods early in 1905.

Gage No. 5 was established because of the difficulty and time involved in reaching gage No. 3 during high water and also because the river had changed its channel in such a way as to leave gage No. 3 dry. It was located on the right bank of the river about one-fourth mile below the location of No. 3. No. 5 was read from March 10, the date of its establishment, to March 20, 1905, on which date it was destroyed.

The river swept back to gage No. 3, which was used until April 14, when another change of channel rendered No. 3 useless. A temporary gage was then established at the old location of No. 4. This was observed until September 1, 1905, when a permanent gage was established. The zero of this gage is at an elevation of 1,326.62 feet above sea level and is referred to two bench marks: (1) On a mesquite tree 200 feet northwest of the gage; elevation, 1,346.12 feet above sea level. (2) A nail in tree at gage; elevation, 1,336.37 feet above sea level.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: Ann 19, iv, pp 418–419, 420–421; WS 16, p 148; 28, p 133; 38, p 321; 50, pp 386–387; 66, p 101; 85, pp 23–24; 100, pp 36–37; 133, pp 215–216.
Discharge: Ann 19, iv, p 419; WS 16, p 148; 28, p 143; 38, p 321; 66, p 102; 85, p 24; 100, pp 38–39; 133, pp 215–216.
Discharge, mean daily: WS 133, p 220.
Discharge, monthly: Ann 20, iv, p 406; 21, iv, p 386; WS 75, p 179; 85, p 25; 100, pp 40–41; 133, p 221.
Discharge, yearly: Ann 20, iv, p 59.
Gage heights: WS 16, p 149; 28, p 140; 38, p 322; 66, p 102; 85, p 25; 100, p 40; 133, p 219.
Hydrographs: Ann 19, iv, p 423; 20, iv, p 406; 21, iv, p 387.
Rating tables: Ann 19, iv, p 419; WS 28, p 145; 100 pp 40–41.

Discharge measurements of Salt River at McDowell, Ariz., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
January 11	W. Richins	9.30	18,500	March 11	W. Richins	5.68	9,981
January 13	do	5.25	5,134	March 14	do	10.20	[a]29,040
January 16	do	3.25	1,235	March 17	do	11.20	[a]37,970
January 20	do	2.95	1,110	March 29	do	6.05	6,385
January 24	do	2.44	569	March 31	do	6.00	6,461
January 27	do	2.37	477	April 4	do	6.55	7,657
January 31	do	2.32	439	April 5	do	6.55	9,070
February 3	do	3.70	1,474	April 12	do	10.60	60,570
February 4	do	12.10	[a]43,280	April 13	do	10.20	54,190
February 7	do	7.95	13,890	April 14	do	.....	21,840
February 10	do	5.00	4,797	April 19	do	4.40	9,756
February 14	do	4.83	4,464	April 21	do	4.30	9,657
February 17	do	9.50	25,560	April 25	do	5.20	15,990
February 21	do	5.00	6,207	April 28	do	4.50	11,920
February 24	do	6.75	10,150	May 2	do	4.35	10,680
March 1	do	8.65	24,780	May 5	do	3.65	8,173
March 8	do	5.40	[b]8,408	May 10	do	3.42	7,427

[a] Flat measurement.

[b] Gage height of new gage No. 4=5.9.

ge measurements of Salt River at McDowell, Ariz., in 1905—Continued.

Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
	Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
W. Richins	2.92	5,604	July 29	W. Richins	−0.35	874
do	2.50	4,329	August 1	do	− .26	752
do	2.40	4,243	August 3	do	− .05	546
do	1.85	3,327	August 5	do	− .04	493
do	1.75	3,149	August 8	do	− .06	463
do	1.57	2,889	August 10	do	− .08	557
do	1.30	2,228	August 16	do	− .20	445
do	1.25	2,066	August 22	do	− .05	507
do	1.20	1,848	August 24	do	.50	1,098
do	1.28	1,888	August 29	do	− .10	457
do	1.20	1,838	August 31	do	− .28	354
do	1.77	2,859	September 2	do	5.03	[a] 1,815
do	1.25	2,077	September 5	do	4.25	781
do	1.12	1,861	September 7	do	5.18	1,993
do	.92	1,600	September 9	do	4.30	842
do	.83	1,683	September 12	do	4.03	640
do	.80	1,532	September 15	do	3.80	458
do	.78	1,336	September 19	do	3.56	330
do	.65	1,210	September 21	do	3.50	302
do	.63	1,155	September 23	do	3.45	266
do	.60	1,081	September 26	do	4.90	1,614
do	.55	1,000	September 30	do	5.15	1,995
do	.49	968	October 4	do	4.14	718
do	.45	860	October 7	do	3.88	477
do	.42	819	October 10	do	3.70	374
do	.39	776	October 12	do	3.63	339
do	.37	791	October 14	do	3.60	350
do	.35	716	October 17	do	3.55	315
do	.31	676	October 19	do	3.52	311
do	.29	684	October 21	do	3.50	289
do	.18	575	October 26	do	3.52	297
do	.16	526	October 28	do	3.52	302
do	.12	521	October 31	do	3.50	284
do	.08	496	November 2	do	3.47	300
do	.02	460	November 4	do	3.50	308
do	−.04	459	November 7	do	3.90	515
do	−.17	368	November 9	do	5.25	1,843
do	−.26	345	November 11	do	4.12	665
do	−.02	481	November 14	do	4.02	534
do	−.12	428	November 16	do	3.90	495
do	−.24	370	November 18	do	3.84	460
do	−.25	355	November 22	do	4.50	1,045
do	−.13	445	November 24	do	5.25	2,219
do	−.17	415				

[a] s are from rod No. 4. Four feet on this rod is the same as zero on the other. All subs are from this rod.

Daily gage height, in feet, of Salt River at McDowell, Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.82	2.32	9.5	5.9	4.2	1.2	0.28	0.25	3.68	a 4.9	3.47	b 6.1
2	1.82	2.32	6.65	6.35	4.35	1.2	.25	.15	5.05	a 4.62	3.47	6.07
3	1.82	3.8	6.05	6.0	4.3	1.2	.2	.03	a 4.0	4.22	3.47	6.1
4	1.82	10.25	5.25	6.85	4.05	1.25	.16	.09	4.47	4.12	3.5	6.1
5	1.82	10.9	5.2	6.55	3.65	1.32	.11	−.04	4.52	4.02	a 3.66	6.2
6	1.81	9.15	5.35	6.2	3.3	1.26	.06	−.05	4.33	3.94	3.76	6.13
7	1.8	8.05	5.23	6.2	3.35	1.2	.02	−.05	5.05	3.86	3.92	6.09
8	1.82	6.6	5.07	6.05	3.4	1.18	−.05	−.08	4.55	a 3.8	4.75	5.92
9	1.85	5.85	4.95	5.85	3.2	1.72	−.09	−.05	4.3	3.75	5.12	5.85
10	8.9	5.15	5.75	5.9	3.37	1.5	−.14	+.06	a 4.12	3.68	4.32	5.88
11	9.3	5.05	5.85	5.35	3.15	1.5	−.18	+.03	4.03	3.64	4.12	5.82
12	7.35	5.7	4.57	10.3	2.87	1.28	−.24	.24	4.01	3.62	a 4.1	5.78
13	5.2	5.5	6.18	10.6	2.75	1.12	−.14	.03	3.92	3.6	4.08	5.8
14	3.85	4.8	10.1	6.75	2.7	.96	−.23	−.03	3.85	3.6	4.01	5.4
15	3.2	4.25	7.62	5.6	2.5	.84	−.01	−.14	3.77	a 3.58	3.94	5.35
16	3.2	4.7	5.78	4.95	2.45	.81	−.03	−.21	3.74	3.56	3.89	5.32
17	3.1	9.2	10.85	4.85	2.42	.78	−.08	−.22	a 3.67	3.54	3.87	a 5.25
18	3.2	9.65	10.85	4.6	2.45	.67	−.14	−.26	3.6	3.53	3.84	5.22
19	3.15	7.6	9.3	4.35	2.38	.68	−.2	−.23	3.54	3.52	a 3.82	5.18
20	2.95	6.1	10.0	4.5	2.3	.62	−.26	−.22	3.52	3.51	3.81	5.1
21	2.9	4.9	9.25	4.25	2.25	.58	−.3	−.21	3.49	3.5	3.88	5.05
22	2.78	4.1	8.25	3.9	2.0	.54	−.25	−.03	3.46	a 3.53	4.95	5.05
23	2.6	4.35	7.4	3.85	1.82	.48	−.22	.58	3.45	3.53	5.5	5.12
24	2.44	6.45	6.82	4.7	1.72	.44	−.15	.50	a 5.9	3.53	5.2	a 5.25
25	2.41	5.8	6.51	5.1	1.65	.42	−.14	.35	5.0	3.52	5.4	5.1
26	2.38	5.45	6.4	5.1	1.58	.42	−.13	.4	5.02	3.51	b 6.0	5.1
27	2.37	4.45	6.35	4.6	1.45	.38	−.19	.18	4.32	3.5	b 21.2	5.0
28	2.37	8.65	6.33	4.5	1.43	.36	+.32	.05	4.03	3.52	b 15.0	5.02
29	2.35	.....	6.13	4.3	1.38	.33	.35	−.12	3.97	a 3.5	b 10.0	5.04
30	2.34	.....	5.75	4.2	1.28	.3	1.5	−.23	a 5.32	3.5	b 7.5	5.05
31	2.32	.....	5.95	.....	1.25	.....	.63	−.28	.....	3.49	.....	5.0

a Interpolated gage heights.
b Approximate flood heights during time gage was out.

NOTE.—Several gages used during the year. See station description.

Daily discharge, in second-feet, of Salt River at McDowell, Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	184	527	29,060	5,678	10,140	2,020	660	735	380	1,635	275	6,000
2	184	527	14,700	8,026	10,760	2,020	630	635	1,838	1,262	275	5,100
3	184	1,576	11,680	6,200	10,560	2,020	580	530	595	764	275	4,770
4	184	26,860	7,651	10,636	9,579	2,200	552	575	1,061	685	290	4,400
5	184	32,320	7,399	9,070	8,192	2,237	517	493	1,127	610	370	4,170
6	177	17,870	8,154	7,244	6,976	2,128	486	475	879	550	426	3,900
7	170	14,280	7,530	7,244	7,155	2,020	462	475	1,838	492	535	3,330
8	184	9,544	6,745	6,460	7,323	1,984	420	450	1,168	450	1,438	2,750
9	205	7,095	6,140	5,417	6,629	2,977	396	515	840	420	1,936	2,300
10	17,050	3,882	11,720	5,678	7,219	2,570	376	685	685	380	970	1,815
11	18,870	3,632	12,100	4,366	6,457	2,570	362	650	617	360	665	1,625
12	11,990	6,606	7,121	55,080	5,484	2,164	351	895	602	350	670	1,540
13	5,008	5,953	13,390	60,600	5,093	1,876	376	640	535	340	655	1,460
14	1,663	3,006	28,650	22,720	4,945	1,616	352	570	495	340	534	1,300

harge, in second-feet, of Salt River at McDowell, Ariz., for 1905—Continued.

Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1,132	2,626	19,000	17,850	4,430	1,430	483	485	432	330	490	1,340
1,132	3,755	11,830	14,420	4,335	1,385	475	440	414	320	490	1,300
1,063	24,650	34,850	13,760	4,278	1,340	445	425	365	310	490	1,228
1,132	26,630	34,850	12,100	4,335	1,178	410	400	340	305	445	1,195
1,097	17,620	25,540	10,760	4,202	1,192	390	415	310	300	455	1,120
959	11,040	28,260	11,530	4,050	1,108	365	415	300	295	450	1,075
926	5,768	35,800	10,350	3,958	1,050	350	415	285	290	505	1,440
843	2,250	17,940	9,058	3,495	990	355	565	270	305	975	1,820
720	3,354	13,510	8,884	3,162	904	377	1,180	265	305	3,176	1,495
609	9,471	10,490	12,760	2,977	852	425	1,100	4,220	305	2,060	1,330
589	8,008	8,861	15,420	2,847	826	440	860	1,770	300	2,903	1,075
568	7,220	8,287	15,420	2,718	826	440	920	1,797	295	4,545	1,075
561	3,792	8,027	12,100	2,477	776	395	660	866	290	138,000	975
561	24,780	7,922	11,530	2,441	752	830	550	610	300	83,530	990
547	.....	6,878	10,560	2,348	716	874	445	580	290	33,100	1,020
541	.....	5,066	10,140	2,164	680	2,780	375	2,430	290	17,710	1,030
527	.....	5,939	.....	2,110	.....	1,260	355	.....	285	.....	975

ly discharge obtained by indirect method.

stimated monthly dischagre of Salt River at McDowell, Ariz., for 1905.

[Drainage area, 6,260 square miles.]

onth.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	18,870	170	2,250	138,300	0.359	0.414
.....	32,320	527	10,170	564,800	1.62	1.69
.....	35,800	5,066	14,680	902,600	2.35	2.71
.....	60,600	4,366	13,700	815,200	2.19	2.44
.....	10,760	2,110	5,253	323,000	.839	.967
.....	2,977	680	1,547	92,050	.247	.276
.....	2,780	350	568	34,920	.091	.105
.....	1,180	355	591	36,340	.094	.108
.....	4,220	265	930	55,340	.149	.166
.....	1,635	285	444	27,300	.071	.082
.....	138,000	275	9,954	592,300	1.59	1.77
.....	6,000	975	2,047	125,900	.327	.377
.....	138,000	170	5,178	3,708,000	.827	11.10

VERDE RIVER AT M'DOWELL, ARIZ.

n was established April 20, 1897. It is located 30 miles northeast of Phoenix, theast of Mesa, 2⅛ miles above the Arizona Canal diversion dam, and three- above the mouth of the river.

el is straight for 300 feet above and below the station, with a width of 100 ater and 450 feet at high water. The right bank is high, rocky, and clean, and t to overflow; the left bank is low, clean, and is liable to overflow. The bed l is composed of sand and is shifting. The current is swift.

measurements are made by means of a cable, car, and tagged wire. At low annel is oblique to the gaging section and measurements are made by wading *0 feet above* the cable.

Gage heights are observed by W. Richins. Three gages have been in use at this station, as follows:

Gage No. 1, established April 20, 1897, consisted of a vertical rod attached to a large cottonwood tree on the east bank about 60 feet below the cable. This was read until November 11, 1899, when the station was temporarily abandoned. The bench mark is a point on a cat's claw (acacia) tree about 100 feet southeast of the gage; elevation, 27.02 feet above the zero of the gage.

Gage No. 2 was established in January, 1901, and observations were resumed. It is an inclined 2- by 4-inch timber, fastened to the rocks on the west bank about 500 feet above the cable, the zero of the gage being 1,325.4 feet above sea level. Three bench marks were established for this gage, as follows: (1) A nail in a mesquite tree about 6 feet below the cable anchorage on the east bank; elevation, 1,345.5 feet above sea level, and 20.10 feet above the zero of the gage. (2) A nail in the cable standard at the east bank; elevation, 1,341.3 feet above sea level, and 15.90 feet above the zero of the gage. (3) A mark on rock at the gage; elevation, 1,330.4 feet above sea level, and 5.00 feet above the zero of the gage.

Gage No. 3 was established May 16, 1904, on account of water piling up at No. 2 during flood. It is a vertical rod fastened to a willow tree on the east bank about one-half mile above the cable. The zero of the gage is 1,339.26 feet above sea level. Two bench marks were established for this gage: (1) A nail in a large cottonwood tree on the top of the east bank near the gage; elevation, 1,354.11 feet above sea level, 14.85 feet above the zero of the gage. (2) A nail in the willow tree to which the gage is attached; elevation, 1,347.26 feet above sea level, and 8.00 feet above the zero of the gage.

Gage No. 3, with the tree to which it was attached, was washed out during the heavy flood February 25, 1905. As the water showed no tendency to pile up at Gage No. 2, readings were resumed on that gage, which was used to the end of the year.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report, Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 19, iv, pp 420-421; Bull 131, p 49; WS 16, p 150, 28 p 133; 38, p 323; 50 p 387; 66, pp 102-103, 85, p 21; 100, pp 31-32; 133, pp 222-223.

Discharge: WS 16, p 150; 38 p 323, 66, p 103; 85, p 22; 100, pp 33-34, 133, pp 223-226.

Discharge, mean daily: WS 133, p 227

Discharge, monthly: Ann 11, ii, p 100; 19, iv, p 423; 20, iv, p 407, 21, iv, p 387; WS 75, p 177; 100, p 35; 133, p 227.

Discharge, yearly: Ann 20, iv, p 59.

Gage heights: Bull 131, p 51; WS 16, p 150; 28, pp 141,143; 38 p 324; 66, p 103; 85, p 23; 100, p 35; 133, p 226

Hydrographs: Ann 19, iv, p 423; 20, iv, p 407; 21, iv, p 388; WS 75, p 177.

Rating table: Ann 19 iv, p 422.

Discharge measurements of Verde River at McDowell, Ariz., in 1905.

Date.	Hydrographer.	Gage height.	Discharge.	Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*			*Feet.*	*Sec.-ft.*
January 11	W. Richins	7.00	9,159	February 14	W. Richins	3.90	[a]1,648
January 13	do	3.70	2,183	February 17	do	7.60	[a]8,174
January 16	do	2.65	876	February 21	do	5.90	4,195
January 20	do	2.62	739	February 24	do	9.70	11,670
January 24	do	2.30	612	March 1	do	14.5	23,280
January 27	do	2.25	580	March 6	do	8.75	5,433
January 31	do	2.18	462	March 11	do	6.95	2,617
February 4	do	13.20	32,990	March 14 [a]	do	16.0	28,850
February 7	do	7.75	7,921	March 17 [a]	do	17.0	31,090
February 10	do	4.60	2,706	March 29	do	7.75	2,973

[a] Float measurement.

rge measurements of Verde River at McDowell, Ariz., in 1905—Continued.

	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*
...	W. Richins	7.00	1,954
...	.....do.....	6.70	1,341
...	Parish and Richins.	6.6	1,363
...	.....do.....	6.6	1,393
...	.....do.....	6.65	1,383
...	.....do.....	6.65	1,436
...	.....do.....	6.65	1,448
...	Richins and Earle	19.0	35,550
...	W. Richins.....	11.4	15,110
...	.....do.....	6 8	3,115
...	.....do.....	6.3	2,041
...	.....do.....	6.15	1,694
...	.....do.....	6.2	1,797
...	.....do.....	5.76	1,195
...	.....do.....	5.4	980
...	.....do.....	5.8	1,282
...	.....do.....	5.4	989
...	.....do.....	4.70	640
...	.....do.....	4.48	470
...	.....do.....	4.45	428
...	.....do.....	4.4	408
...	W. B. Richins	4.3	389
...	.....do.....	4.3	389
...	.....do.....	4.25	385
...	.....do.....	4.13	410
...	.....do.....	4.1	358
...	.....do.....	4.15	334
...	.....do.....	4.05	291
...	W. Richins.....	4.03	279
...	.....do.....	3.98	278
...	.....do.....	3.95	299
...	.....do.....	3.91	245
...	.....do.....	3.86	237
...	.....do.....	3.81	237
...	.....do.....	3.75	188
...	.....do.....	3.72	191
...	.....do.....	3.7	205
...	.....do.....	3.61	157
...	.....do.....	3.58	131
...	.....do.....	3.57	132
...	.....do.....	3.56	128
...	.....do.....	3.55	132
...	.....do.....	4.12	323
...	.....do.....	3.80	243
...	.....do.....	3.70	181
...	.....do.....	3.61	158

Date.	Hydrographer.	Gage height.	Discharge.
		Feet.	*Sec.-ft.*
July 25.....	W. Richins	3.70	178
July 27.....	.....do.....	3.70	180
July 29.....	.....do.....	4.83	668
August 1	.....do.....	4.50	517
August 3	.....do.....	4.38	436
August 5	.....do.....	4.10	330
August 8	.....do.....	4.00	291
August 10.....	.....do.....	4.67	540
August 12	.....do.....	5.00	737
August 16	.....do.....	4.25	372
August 22	.....do.....	4.20	333
August 24	.....do.....	4.95	764
August 29	.....do.....	5.07	746
August 31	.....do.....	4.70	491
September 2...	.....do.....	4.73	521
September 5...	.....do.....	4.45	426
September 7...	.....do.....	6.90	2,961
September 9...	.....do.....	5.40	1,046
September 12..	.....do.....	4.65	426
September 15..	.....do.....	4.38	391
September 19..	.....do.....	4.15	302
September 21..	.....do.....	4.00	280
September 23..	.....do.....	4.00	275
September 26..	.....do.....	5.23	975
September 30..	.....do.....	8.80	5,899
October 4.....	.....do.....	4.70	675
October 7.....	.....do.....	4.35	404
October 10.....	.....do.....	4.20	364
October 12.....	.....do.....	4.10	361
October 14.....	.....do.....	4.08	321
October 17.....	.....do.....	4.05	302
October 19.....	.....do.....	4.02	316
October 21.....	.....do.....	4.0	293
October 26.....	.....do.....	4.01	308
October 28.....	.....do.....	4.03	319
October 31.....	.....do.....	4.01	311
November 2.....	.....do.....	3.96	328
November 4.....	.....do.....	3.99	301
November 7.....	.....do.....	4.20	392
November 9.....	.....do.....	5.70	1,885
November 11....	.....do.....	5.15	1,168
November 14....	.....do.....	4.45	622
November 16....	.....do.....	4.35	466
November 18....	.....do.....	4.3	415
November 22....	.....do.....	4.5	504
November 24....	.....do.....	5.0	1,012

Daily gage height, in feet, of Verde River at McDowell, Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.08	2.16	15.0	a6.9	5.85	4.25	3.7	4.45	4.98	b7.4	4.01	a6.6
2	1.09	2.18	11.35	6.82	5.65	4.22	b3.6	4.39	a4.75	b5.95	4.01	a5.9
3	1.08	2.74	10.45	6.75	5.55	4.2	3.63	4.31	b4.65	4.92	4.0	5.3
4	1.06	13.25	10.1	6.68	5.48	b4.15	3.6	4.19	4.55	4.68	a3.99	4.8
5	1.05	13.25	9.75	6.6	5.4	4.13	3.57	a4.1	4.4	4.52	b4.05	4.7
6	1.05	10.25	9.0	6.65	5.45	4.12	3.57	b4.08	5.53	4.42	4.12	4.6
7	a1.05	8.15	8.65	6.65	a5.45	4.1	3.57	4.02	6.65	4.32	4.5	4.2
8	b1.15	6.4	8.4	6.62	6.0	4.1	3.56	3.98	5.62	b4.25	5.12	4.2
9	1.25	5.3	7.8	6.6	6.15	4.13	b3.55	4.75	a5.4	4.22	5.62	a4.1
10	6.75	4.6	7.38	6.66	5.7	a3.98	3.56	4.75	b4.65	4.18	5.45	a4.0
11	7.4	a4.62	6.95	9.4	5.5	b4.0	3.55	5.08	4.75	4.12	a5.15	4.0
12	6.15	a5.4	6.9	17.75	5.32	4.05	3.54	5.2	4.62	4.09	b4.8	3.9
13	3.8	a4.8	9.85	15.0	6.1	4.02	3.56	4.63	4.52	4.09	4.6	3.8
14	3.1	3.85	15.1	11.4	a5.7	3.97	3.68	a4.5	4.42	a4.08	4.45	3.8
15	2.85	3.55	11.35	10.85	5.25	3.97	a4.1	4.35	4.36	b4.07	4.38	3.7
16	2.65	3.5	11.45	9.7	4.95	3.97	b3.95	4.28	a4.3	4.06	4.35	a3.7
17	2.55	6.1	16.25	8.5	4.85	3.95	3.88	4.25	b4.21	4.03	4.32	b3.7
18	2.85	8.6	14.55	7.7	4.75	3.9	3.79	4.3	4.12	4.01	a4.3	3.6
19	2.72	7.95	a12.0	7.0	4.68	b3.9	3.73	a4.15	4.12	4.02	b4.27	3.6
20	2.59	6.5	b11.4	6.45	4.65	3.9	3.68	4.08	4.08	4.0	4.25	3.6
21	a2.5	5.85	b10.8	6.25	a4.6	3.85	3.63	4.05	4.0	a4.0	4.35	3.7
22	b2.41	5.45	b10.2	a6.1	4.52	3.85	a3.61	4.18	4.0	b4.0	4.6	3.7
23	2.32	6.2	b9.6	b6.1	4.46	3.82	b3.62	5.0	a4.0	4.0	5.0	3.8
24	2.28	12.0	a9.0	6.2	4.42	3.8	3.64	4.9	4.3	4.0	4.98	b3.7
25	2.26	b9.1	8.75	6.5	b4.42	3.78	3.68	5.52	4.75	4.02	a4.95	a3.6
26	2.29	b8.2	a8.6	6.85	4.38	3.76	3.65	a6.1	5.02	4.0	b5.5	3.6
27	2.27	8.25	b8.2	6.35	4.35	3.74	3.68	b5.7	4.8	4.0	17.0	3.6
28	2.27	14.0	a7.8	6.2	a4.32	3.72	4.4	5.25	4.85	a4.03	b10.0	3.6
29	2.25	.....	7.6	a6.1	4.28	3.71	a4.85	5.02	5.4	b4.0	b8.0	3.6
30	b2.2	.....	7.15	b6.0	4.27	3.69	a5.5	4.85	8.45	3.99	a7.2	3.6
31	2.16	.....	6.95	.....	4.27	.....	4.85	4.65	.....	4.01	.....	b3.6

a One gage reading. b Estimated.

NOTE.—Gage changes from No. 3 to No. 2 February 24.

Daily discharge, in second-feet, of Verde River at McDowell, Ariz., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	248	499	25,130	1,819	1,342	370	205	490	720	4,080	325	3,280
2	250	507	10,580	1,710	1,145	370	185	452	535	2,200	340	2,400
3	248	968	8,800	1,615	1,082	380	173	403	490	920	321	1,850
4	243	32,970	8,107	1,520	1,037	380	155	365	455	665	301	1,535
5	241	32,970	7,414	1,411	987	385	137	330	410	515	325	1,310
6	241	19,310	5,928	1,478	1,018	400	132	325	1,200	440	355	1,087
7	241	9,743	5,276	1,478	1,018	380	132	297	2,550	390	575	961
8	263	5,400	4,884	1,439	1,507	358	130	285	1,270	370	1,200	905
9	285	3,750	3,946	1,411	1,696	335	128	630	1,046	360	1,775	880
10	8,674	2,700	3,289	1,493	1,177	277	130	585	475	355	1,550	750
11	10,060	2,730	2,617	6,433	1,050	283	128	785	535	355	1,168	750
12	7,394	3,900	2,539	32,140	949	291	125	860	410	355	865	694
13	2,379	3,000	7,612	24,640	1,655	280	130	525	400	340	700	656
14	1,400	1,637	25 500	15,160	1,205	270	164	455	385	321	622	632

y discharge, in second-feet, of Verde River at McDowell, Ariz., for 1905—Continued.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1,100	1,403	10,580	13,720	925	275	315	404	380	318	525	596
.....	860	1,367	10,780	10,710	760	290	280	385	360	305	466	590
.....	755	4,950	29.410	7,566	715	300	262	364	325	298	435	560
.....	1,100	9,767	23,460	5,471	660	267	240	383	300	300	415	548
.....	944	8,641	12,120	3,639	630	255	207	327	297	316	400	536
.....	791	6,130	10,630	2,337	600	237	175	315	293	298	383	536
.....	710	5,004	9,368	1,893	555	230	165	280	275	293	423	578
.....	642	4,311	8,110	1,617	495	235	158	327	275	296	580	596
.....	583	5,010	6,85o	1,617	440	230	160	753	275	300	1,000	632
.....	559	12,170	5,594	1,782	422	230	165	735	345	303	1,000	590
.....	548	6 126	5,070	2,448	415	217	175	1,085	570	306	955	548
.....	564	4,572	4,755	3,246	400	200	165	1,617	805	305	1,610	530
.....	553	4,650	3,916	2,115	390	183	175	1,160	625	305	a61,460	524
.....	553	21,050	3,077	1,782	380	187	435	870	650	319	13,115	518
.....	542	.....	2,770	1,617	375	190	685	715	1,125	305	5,520	506
.....	515	.....	2,158	1,507	375	192	1,080	590	5,350	305	4,240	506
.....	499	.....	1,887	.....	375	.....	710	465	.....	311	.....	506

a Calculated from Kutter's formula.

.—Daily discharge obtained by indirect method.

Estimated monthly discharge of Verde River at McDowell, Ariz., for 1905.

[Drainage area, 6,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum	Mean.		Second-feet per square mile.	Depth in inches.
r.....	10,060	241	1,419	87,250	0.236	0.272
ry.....	32,970	499	7,709	428,100	1.28	1.33
.....	29,410	1,887	8,780	539,900	1.46	1.68
.....	32,140	1,411	5,227	311,000	.871	.972
.....	1,606	375	832	51,160	.139	.160
.....	400	183	283	16,840	.047	.052
.....	1,080	125	245	15,060	.041	.047
.....	1,617	280	567	34,860	.094	.108
ber.....	5,350	275	771	45,880	.128	.143
.....	4,080	293	544	33,450	.091	.105
ber.....	61,460	301	3,432	204,200	.572	.638
ber.....	3,280	506	875	53,800	.146	.168
he year.....	61,460	125	2,557	1,822,000	.426	5.68

SANTA CRUZ RIVER AT TUCSON, ARIZ.

s station was established October 15, 1905, by G. E. P. Smith. It is located at ess Street Bridge, Tucson, Ariz.

channel is straight for 500 feet above and 300 feet below the station. The current t. The left bank is low, wooded, and liable to overflow. The right bank is about 12 igh and not liable to overflow. The bed of the stream is composed of bowlders, ifts during floods.

Discharge measurements are made from the bridge, which consists of one steel span 100 feet long and four pile bents each 15 feet long. The initial point for soundings is the east edge of upstream cylindrical pier on the west bank.

The gage is painted on the pier, which is taken as the initial point. During 1905 the gage was read twice each day by George S. Calliahan.

Discharge measurements of Santa Cruz River at Tucson, Ariz., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Sq. ft.*	*Ft. per sec.*	*Feet.*	*Sec.-ft.*
November 27...	G. E. P. Smith	68	46	5.40	1.58	24
November 28...	do	90	317	7.90	3.60	2,5
December 27...	do	44	17	2.40	0.65	4

Daily gage height, in feet, of Santa Cruz River at Tucson, Ariz., for 1905.

Day.	Nov.	Dec.	Day.	Nov.	Dec.
1		1.0	25	1.3	
2		1.0	26	1.1	
8	1.65		27	1.38	
9	1.25		28	3.85	
22	1.65		29	2.4	
23	1.20		30	1.45	
24	2.0				

NOTE.—All water taken out by canals heading above station, leaving the river channel dry at station except on days for which gage heights are recorded.

INDEX.

A.

Page.

..... 12
on of..... 4

River at:
L..... 166–167
..... 167–168
daily..... 169
monthly..... 170
ts..... 168–169

L..... 101–102
..... 102
monthly..... 103
ts..... 102
e..... 103
ear:
..... 103–104
..... 104
monthly..... 106
s..... 104–105
e..... 105

lo.:
..... 134–135
..... 135
nonthly..... 137
s..... 136
e..... 136–137
on, N. Mex.:
..... 137–138
..... 138
nonthly..... 140
s..... 138–139
..... 139

:
..... 47
..... 47
nonthly..... 48
s..... 47
..... 48

B.

o.:
..... 96-97
..... 97
..... 97–98

ear:
..... 30
..... 30
nonthly..... 32

Boulder, Wyo.—Continued. Page.
Boulder Creek near:
gage heights..... 31
rating table..... 31
Boulder Creek near—
Boulder, Wyo.:
description..... 30
discharge..... 30
discharge, monthly..... 32
gage heights..... 31
rating table..... 31
Buford, Colo.
Marvine Creek near:
description..... 58–59
discharge..... 59
discharge, monthly..... 60
gage heights..... 59
rating table..... 60
North Fork of White River near:
description..... 50
discharge..... 50
discharge, monthly..... 51
gage heights..... 50–51
rating table..... 51
South Fork of White River near:
description..... 52
discharge..... 52
discharge, monthly..... 54
gage heights..... 52–53
rating table..... 53

C.

Charleston, Ariz.
San Pedro River at:
description..... 170
discharge..... 171
discharge, daily..... 172
discharge, monthly..... 173
gage heights..... 171–172
Chevlon Fork near
Winslow, Ariz.:
description..... 156
discharge..... 157
Cimarron, Colo.
Cimarron River at:
description..... 118
discharge..... 118
discharge, monthly..... 120
gage heights..... 119
rating table..... 119
Gunnison River near:
description..... 106
discharge..... 107
discharge, monthly..... 106
gage heights..... 107
rating table..... 108

Cimarron River at— Page.
Cimarron, Colo.:
description 118
discharge 118
discharge, monthly 120
gage heights 119
rating table 119
Cliff, N. Mex.
Gila River near:
description 159
discharge 160
discharge, daily 161
discharge, monthly 162
gage heights 160–161
Colona, Colo.
Uncompahgre River near:
description 120
discharge 121
discharge, monthly 122
gage heights 121
rating table 122
Colorado River, description of 127–128
at Hardyville, Ariz.:
description 128–129
discharge 129
discharge, daily 130
discharge, monthly 130
gage heights 129
Colorado River drainage basin, description of 12–13
Cora, Wyo.
Newfork River near:
description 22
discharge 22
gage heights 23
Cory, Colo.
Gunnison River near:
description 110
discharge 111
discharge, monthly 112
gage heights 111
rating table 112
Craig, Colo.
Fortification Creek at:
description 43
gage heights 44
Yampa River near:
description 37–38
discharge 38
discharge, monthly 39
gage heights 38
rating table 39

D.

Delta, Colo.
Uncompahgre River at:
description 125
discharge 125
discharge, monthly 127
gage heights 126
rating table 126
Discharge, methods of measuring and computing 6–11
Dome, Ariz.
Gila River at:
description 164
discharge 164
discharge, daily 165–166
Dome, Ariz.—Continued. Page.
Gila River at:
discharge, monthly 166
gage heights 165
Drainage basins, list of 2-3
Duchesne River drainage basin, description of 60-61
miscellaneous measurements in 66
Durango, Colo.
Animas River at:
description 134-135
discharge 135
discharge, monthly 137
gage heights 136
rating table 136-137

E.

Eagle, Colo.
Eagle River near:
description 98-99
discharge 99
gage heights 99-100
Eagle River near—
Eagle, Colo.:
description 98-99
discharge 99
gage heights 99-100
East River at—
Almont, Colo.:
description 101-102
discharge 102
discharge, monthly 103
gage heights 102
rating table 103
Eastfork River at—
Newfork, Wyo.:
description 32
discharge 33
discharge, monthly 34
gage heights 33
rating table 34
Elk River near—
Trull, Colo.:
description 41-42
discharge 42
discharge, monthly 43
gage heights 42
rating table 43
Equivalents, table of 5-6

F.

Fall Creek near—
Fayette, Wyo.:
description 28
discharge 28
discharge, monthly 29
gage heights 29
rating table 29
Farmington, N. Mex.
Animas River near:
description 137-138
discharge 138
discharge, monthly 140
gage heights 138-139
rating table 139
San Juan River near:
description 132
discharge 132

Page.	Grand Lake, Colo.	Page.
	Grand Lake outlet at:	
134	description	72–73
132–133	discharge	73
133	discharge, monthly	74
	gage heights	73–74
	rating table	74
28	North Fork of Grand River near:	
28	description	70–71
29	discharge	71
29	discharge, monthly	72
29	gage heights	71–72
	rating table	72
25–26	Grand Lake north inlet at:	
26	description	75
27	discharge	75
26–27	gage heights	75
27	Grand Lake north inlet at—	
8	Grand Lake, Colo.:	
66	description	75
	discharge	75
	gage heights	75
43	Grand Lake, outlet at—	
44	Grand Lake, Colo.:	
	description	72–73
	discharge	73
87–88	discharge monthly	74
88	gage heights	73–74
89	rating table	74
88	Grand River—	
88–89	at Glenwood Springs, Colo.:	
	description	81–82
	discharge	82
	discharge, monthly	84
7	gage heights	83
	rating table	83
	at Palisades, Colo.:	
	description	84–85
164	discharge	85
164	discharge, monthly	86
165 166	gage heights	85–86
166	rating table	86
165	at Hot Sulphur Springs, Colo.:	
	description	76
162	discharge	76
163	discharge, monthly	78
163	gage heights	77
	rating table	77–78
159	near Kremmling, Colo.:	
160	description	78–79
161	discharge	79
162	discharge, monthly	81
160 161	gage heights	79–80
158 159	rating table	80
	Grand River drainage basin, description of	69–70
	miscellaneous measurements in	87
87–88	Grand River, North Fork, near—	
88	Grand Lake, Colo.	
89	description	70–71
88	discharge	71
88 89	discharge, monthly	72
	gage heights	71–72
	rating table	72
81 82	Greenbrier, Wyo.	
82	Greenbrier River at:	
84	description	14
83	discharge	15
83	discharge, monthly	17

Greenbrier, Wyo.—Continued. Page.
Greenbrier River at:
gage heights ... 16
rating table ... 16
Greenriver, Utah.
Green River at:
description ... 19
discharge ... 20
discharge, monthly ... 21
gage heights ... 20
rating table ... 21
Green River at—
Greenbrier, Wyo.:
description ... 14
discharge ... 15
discharge, monthly ... 17
gage heights ... 16
rating table ... 16
Greenriver, Utah:
description ... 19
discharge ... 20
discharge, monthly ... 21
gage heights ... 20
rating table ... 21
Jensen, Utah:
description ... 17
gage heights ... 17
Ouray, Utah:
description ... 18
gage heights ... 18
Green River drainage basin, description of. 13–14
Gunnison River—
at Gunnison Tunnel, east portal, Colo.:
description ... 108–109
discharge ... 109
gage heights ... 109–110
at Whitewater, Colo.:
description ... 112–113
discharge ... 113
discharge, monthly ... 115
gage heights ... 113–114
rating table ... 114
near Cimarron, Colo.:
description ... 106
discharge ... 107
discharge, monthly ... 108
gage heights ... 107
rating table ... 108
near Cory, Colo.:
description ... 110
discharge ... 111
discharge, monthly ... 112
gage heights ... 111
rating table ... 112
Gunnison River drainage basin, description of ... 100–101
miscellaneous measurements in ... 127
Gunnison River, North Fork, near—
Hotchkiss, Colo.:
description ... 115–116
discharge ... 116
discharge, monthly ... 117
gage heights ... 116
rating table ... 117
Gunnison Tunnel, east portal, Colo.
Gunnison River at:
description ... 108–109
discharge ... 109
gage heights ... 109–110

H. Page.
Hamilton, Colo.
Williams River at:
description ... 44
discharge ... 45
discharge, monthly ... 46
gage heights ... 45
rating table ... 46
Hardyville, Ariz.
Colorado River at:
description ... 128-129
discharge ... 129
discharge, daily ... 130
discharge, monthly ... 130
gage heights ... 130
Helper, Utah.
Price River near:
description ... 67
discharge ... 67
discharge, monthly ... 68
gage heights ... 68
rating table ... 68
Hesperus, Colo.
La Plata River at:
description ... 140
discharge ... 141
gage heights ... 141
Holbrook, Ariz.
Little Colorado River at:
description ... 149
discharge ... 149
discharge, daily ... 150-151
discharge, monthly ... 151
evaporation ... 152-153
gage heights ... 150
Hot Sulphur Springs, Colo.
Grand River at:
description ... 76
discharge ... 76
discharge, monthly ... 76
gage heights ... 77
rating table ... 77-78
Williams Fork near:
description ... 89-90
discharge ... 90
discharge, monthly ... 91
gage heights ... 90
rating table ... 91
Hotchkiss, Colo.
North Fork of Gunnison River near:
description ... 115-116
discharge ... 116
discharge, monthly ... 117
gage heights ... 116
rating table ... 117
Hydrographers, list of ... 12
Hydrographic surveys, annual appropriations for ... 4
organization and scope of ... 1-4

I.

Ice-covered streams, flow of, measurement of ... 10
Indian Creek in—
Strawberry Valley, Utah:
description ...
discharge ...
discharge, monthly ...
gage heights ...
rating table ...

J.

Page.

ren, Utah.
Green River at:
description 17
gage heights 17

K.

mmling, Colo.
Blue River near:
description 96–97
discharge 97
gage heights 97–98
Grand River at:
description 78–79
discharge 79
discharge, monthly 81
gage heights 79–80
rating table 80
Muddy River at:
description 93–94
discharge 94
discharge, monthly 96
gage heights 95
rating table 95–96

L.

Plata, N. Mex.
La Plata River near:
description 142
discharge 142
gage heights 142–143
Plata River—
at Hesperus, Colo.:
description 140
discharge 141
gage heights 141
near La Plata, N. Mex.:
description 142
discharge 142
gage heights 142–143
le Colorado River at—
Holbrook, Ariz.:
description 149
discharge 149
discharge, daily 150–151
discharge, monthly 151
gage heights 150
Woodruff, Ariz.:
description 145
discharge 146
discharge, daily 148
discharge, monthly 148
gage heights 147
le Colorado River drainage basin, description of 145
niscellaneous measurements in 157

M.

owell, Ariz.
lalt River at:
description 177–178
discharge 178–179
discharge, daily 180–181
discharge, monthly 181
gage heights 180
Verde River at:
description 181–182
discharge 182–183
discharge, daily 184–185
discharge, monthly 185
gage heights 184

Marvine Creek near— Page.
Buford, Colo.:
description 58–59
discharge 59
discharge, monthly 60
gage heights 59
rating table 60
Maybell, Colo.
Yampa River near:
description 39
discharge 40
discharge, monthly 41
gage heights 40
rating table 41
Meeker, Colo.
White River at:
description 54
discharge 55
discharge, monthly 56
gage heights 55
rating table 56
Mill Creek near—
Axial, Colo.:
description 47
discharge 47
discharge, monthly 48
gage heights 47
rating table 48
Moapa, Nev.
Muddy River near:
description 157
gage heights 158
Montrose, Colo.
Uncompahgre River at:
description 122–123
discharge 123
discharge, monthly 124
gage heights 123–124
rating table 124
Muddy River—
at Kremmling, Colo.:
description 93–94
discharge 94
discharge, monthly 96
gage heights 95
rating table 95–96
near Moapa, Nev.:
description 157
gage heights 158
Multiple-point method of measuring discharge, description of 9

N.

Newfork, Wyo.
Eastfork River near:
description 32
discharge 33
discharge, monthly 34
gage heights 33
rating table 34
Newfork River near—
Cora, Wyo.:
description 22
discharge 22
gage heights 23
Newfork River drainage basin, description of 21

O.

Page.

Ouray, Utah,
Green River at:
description..... 18
gage heights..... 18

P.

Palisades, Colo.
Grand River at:
description..... 84,85
discharge..... 85
discharge, monthly..... 86
gage heights..... 85-86
rating table..... 86
Pine Creek near—
Pinedale, Wyo.:
description..... 23
discharge..... 24
discharge, monthly..... 25
gage heights..... 24
rating table..... 25
Pinedale, Wyo.
Pine Creek near:
description..... 23
discharge..... 24
discharge, monthly..... 25
gage heights..... 24
rating table..... 25
Pole Creek at—
Fayette, Wyo.:
description..... 25,26
discharge..... 26
discharge, monthly..... 27
gage heights..... 26,27
rating table..... 27
Price River near—
Helper, Utah:
description..... 67
discharge..... 67
discharge, monthly..... 49
gage heights..... 68
rating table..... 68

R.

Rangely, Colo.
White River near:
description..... 56
discharge..... 57
discharge, monthly..... 58
gage heights..... 57
rating table..... 58
Rating curves, construction of, methods of . 10-11
Rating tables, construction of, methods of. 10, 11
Roosevelt, Ariz.
Salt River at:
description..... 173
discharge..... 173, 175
discharge, daily..... 176
discharge, monthly..... 176
gage heights..... 175, 176
Rules for computation, fundamental and special..... 4, 5
Run-off in inches, definition of..... 4

S.

Salt River at—
McDowell, Ariz.:
description..... 177, 178
discharge..... 178, 179
Salt River at—
McDowell, Ariz.—Continued.
discharge, daily..... 18
discharge, monthly.....
gage heights.....
Roosevelt, Ariz.:
description.....
discharge..... 1
discharge, daily.....
discharge, monthly.....
gage heights..... 1
San Carlos, Ariz.
Gila River at—
description.....
discharge.....
gage heights.....
San Francisco River at—
Alma, N. Mex.:
description..... 1
discharge.....
discharge, daily.....
discharge, monthly.....
gage heights.....
San Juan River near—
Farmington, N. Mex.:
description.....
discharge.....
discharge, monthly.....
gage heights.....
rating table.....
San Juan drainage basin, description of..
miscellaneous measurements in.....
San Pedro River at—
Charleston, Ariz.:
description.....
discharge.....
discharge, daily.....
discharge, monthly.....
gage heights.....
Santa Cruz River at—
Tucson, Ariz.:
description.....
discharge.....
gage heights.....
Second-feet per square mile, definition of..
Second-foot, definition of .....
Single-point method of measuring dis har
description of.....
Slope method of measuring discharge, t
and value of.....
Strawberry Creek in—
Strawberry Valley, Utah:
description.....
discharge.....
discharge, monthly.....
gage heights.....
rating table.....
Strawberry Valley, Utah,
Indian Creek in:
description.....
discharge.....
discharge, monthly.....
gage heights.....
rating table.....
Strawberry Creek in:
description.....
discharge.....
discharge, monthly.....

awberry Valley, Utah—Continued. Page.
Strawberry Creek in:
evaporation 61, 66
gage heights 62–63
precipitation 62
rating table 63
amboat Springs, Colo.—
Yampa River at:
description 35
discharge 35
discharge, monthly 38
gage heights 36
rating table 36–37

T.

bles, explanation of 4
lor River near—
Almont, Colo.:
description 103–104
discharge 104
discharge, monthly 106
gage heights 104–105
rating table 105
ublesome, Colo.
Troublesome River at:
description 91–92
discharge 92
discharge, monthly 93
gage heights 92
rating table 93
ublesome River at—
Troublesome, Colo.:
description 91–92
discharge 92
discharge, monthly 93
gage heights 92
rating table 93
ll, Colo.,
Elk River near:
description 41–42
discharge 42
discharge, monthly 43
gage heights 42
rating table 43
son, Ariz.,
Santa Cruz River at:
description 185–186
discharge 186
gage heights 186

U.

ompahgre River—
at Delta, Colo.:
description 125
discharge 125
discharge, monthly 127
gage heights 126
rating table 126
at Montrose, Colo.:
description 122–123
discharge 123
discharge, monthly 124
gage heights 123–124
rating table 124
near Colona, Colo.:
description 120
discharge 121
Uncompahgre River— Page.
near Colona, Colo.—Continued.
discharge, monthly 122
gage heights 122
rating table 122

V

Velocity methods of measuring discharge, description of 7–10
Verde River at—
McDowell, Ariz.:
description 181–182
discharge 182–183
discharge, daily 184–185
discharge, monthly 185
gage heights 184
Vertical velocity-curve method of measuring discharge, description of 9

W.

Weir method of measuring discharge, description of 7
White River—
at Meeker, Colo.:
description 54
discharge 55
discharge, monthly 56
gage heights 55
rating table 56
White River—
near Rangely, Colo.:
description 56
discharge 57
discharge, monthly 58
gage heights 57
rating table 58
White River drainage basin, description of. 49
White River, North Fork, near—
Buford, Colo.:
description 50
discharge 50
discharge, monthly 51
gage heights 50–51
rating table 51
White River, South Fork, near—
Buford, Colo.:
description 52
discharge 52
discharge, monthly 54
gage heights 52–53
rating table 53
Whitewater, Colo.,
Gunnison River at:
description 112–113
discharge 113
discharge, monthly 115
gage heights 113–114
rating table 114
Williams Fork near—
Hot Sulphur Springs, Colo.:
description 89–90
discharge 90

Page.

Williams Fork near—
Hot Sulphur Springs, Colo.—Continued.
discharge, monthly 91
gage heights 90
rating table 91
Williams River at—
Hamilton, Colo.:
description 44
discharge 45
discharge, monthly 46
gage heights 45
rating table 46
Winslow, Ariz.,
Chevlon Fork near:
description 156
discharge 157
Woodruff, Ariz.,
Little Colorado River at:
description 145
discharge 146
discharge, daily 148
discharge, monthly 148
gage heights 147

Y.

Page.

Yampa River—
at Steamboat Springs, Colo.:
description 35
discharge 35
discharge, monthly 36
gage heights 36
rating table 36-37
near Craig, Colo.:
description 37-38
discharge 38
discharge, monthly 39
gage heights 38
rating table 39
near Maybell, Colo.:
description 39
discharge 40
discharge, monthly 41
gage heights 40
rating table 41
Yampa River drainage basin, description of 34-35
miscellaneous measurements in 40

CLASSIFICATION OF THE PUBLICATIONS OF THE UNITED STATES GEOLOGICAL SURVEY.

[Water-Supply Paper No. 175.]

The publications of the United States Geological Survey consist of (1) Annual Reports; (2) Monographs; (3) Professional Papers; (4) Bulletins; (5) Mineral Resources; (6) Water-Supply and Irrigation Papers; (7) Topographic Atlas of United States—folios and separate sheets thereof; (8) Geologic Atlas of United States—folios thereof. The classes numbered 2, 7, and 8 are sold at cost of publication; the others are distributed free. A circular giving complete lists may be had on application.

Most of the above publications may be obtained or consulted in the following ways:

1. A limited number are delivered to the Director of the Survey, from whom they may be obtained, free of charge (except classes 2, 7, and 8), on application.

2. A certain number are delivered to Senators and Representatives in Congress, for distribution.

3. Other copies are deposited with the Superintendent of Documents, Washington, D. C., from whom they may be had at practically cost.

4. Copies of all Government publications are furnished to the principal public libraries in the large cities throughout the United States, where they may be consulted by those interested.

The Professional Papers, Bulletins, and Water-Supply Papers treat of a variety of subjects, and the total number issued is large. They have therefore been classified into the following series: A, Economic geology; B, Descriptive geology; C, Systematic geology and paleontology; D, Petrography and mineralogy; E, Chemistry and physics; F, Geography; G, Miscellaneous; H, Forestry; I, Irrigation; J, Water storage; K, Pumping water; L, Quality of water; M, General hydrographic investigations; N, Water power; O, Underground waters; P, Hydrographic progress reports.

Series P.—The hydrographic progress reports contain the results of stream measurements. A report is issued for every calendar year, containing the results of data collected during that year. These reports were first published as a part of the Director's annual report or as a bulletin; they are now published as water-supply and irrigation papers. The following is a list, by years, of the publications containing the progress reports of stream measurements. A detailed index of these reports (1888–1903) is published as Water-Supply Paper No. 119.

1888. Tenth Annual Report, Part II.
1889. Eleventh Annual Report, Part II.
1890. Twelfth Annual Report, Part II.
1891. Thirteenth Annual Report, Part III.
1892. Fourteenth Annual Report, Part II.
1893. Bulletin No. 131.
1894. Bulletin No. 131; Sixteenth Annual Report, Part II.
1895. Bulletin No. 140.
1896. Water-Supply Paper No. 11; Eighteenth Annual Report, Part IV.
1897. Water-Supply Papers Nos. 15 and 16; Nineteenth Annual Report, Part IV.
1898. Water-Supply Papers Nos. 27 and 28; Twentieth Annual Report, Part IV.
1899. Water-Supply Papers Nos. 35, 36, 37, 38, and 39; Twenty-first Annual Report, Part IV.
1900. Water-Supply Papers Nos. 47, 48, 49, 50, 51, and 52; Twenty-second Annual Report, Part IV.
1901. East of Mississippi River, Water-Supply Papers Nos. 65 and 75.
West of Mississippi River, Water-Supply Papers Nos. 66 and 75.

1902. East of Mississippi River, Water-Supply Papers Nos. 82 and 83.
West of Mississippi River, Water-Supply Papers Nos. 84 and 85.
1903. East of Mississippi River, Water-Supply Papers Nos. 97 and 98.
West of Mississippi River, Water-Supply Papers Nos. 99 and 100.
1904. East of Mississippi River, Water-Supply Papers, Nos. 124, 125, 126, 127, 128, and 129.
West of Mississippi River, Water-Supply Papers Nos. 130, 131, 132, 133, 134, and 135.
1905. East of Mississippi River, Water-Supply Papers Nos. 165, 166, 167, 168, 169, 170, and 171.
West of Mississippi River, Water-Supply Papers Nos. 171, 172, 173, 174, 175, 176, 177, and 178.

The Geological Survey and the Reclamation Service have suboffices in different parts of the United States, from which hydrographic and reclamation work in the respective localities is carried on and where data may be obtained on application. These offices are located as follows:

Boston, Mass., 6 Beacon street; Utica, N. Y., 75 Arcade; Atlanta, Ga., 409 Temple court; Austin, Tex., University of Texas; Chicago, Ill., 876 Federal Building; Belle Fourche, S. Dak.; Cody, Wyo.; Denver, Colo., Chamber of Commerce Building; Salt Lake, Utah; Los Angeles, Cal., 1106 Braly Building; San Francisco Cal., 432 Merchants' Exchange Building; Phoenix, Ariz.; Carlsbad, N. Mex.; El Paso, Tex.; Billings, Mont.; Great Falls, Mont.; Hazen, Nev.; Boise, Idaho; Spokane, Wash., 424 Peyton Block; Pendleton, Oreg.

Correspondence should be addressed to

THE DIRECTOR,
UNITED STATES GEOLOGICAL SURVEY,
WASHINGTON, D. C.

SEPTEMBER, 1906.

O

ter—Supply and Irrigation Paper No. 176 Series P, Hydrographic Progress Reports, 52

DEPARTMENT OF THE INTERIOR
UNITED STATES GEOLOGICAL SURVEY
CHARLES D. WALCOTT, DIRECTOR

REPORT

OF

ROGRESS OF STREAM MEASUREMENTS

FOR

THE CALENDAR YEAR 1905

PREPARED UNDER THE DIRECTION OF F. H. NEWELL

PART XII.—The Great Basin Drainage

BY

M. C. HINDERLIDER, G. L. SWENDSEN, and HENRY THURTELL

WASHINGTON
GOVERNMENT PRINTING OFFICE
1906

CONTENTS.

	Page.
luction	5
rganization and plan of work	5
efinitions	7
xplanation of tables	8
onvenient equivalents	9
ield methods of measuring stream flow	10
ffice methods of computing run-off	14
ooperation and acknowledgments	15
al description of Great Basin	16
ch Mountains drainage	17
rincipal streams	17
ear River basin	18
Description of basin	18
Bear Lake at Fish Haven, Idaho	19
Bear River at Dingle, Idaho	20
Bear River near Preston, Idaho	22
Bear River near Collinston, Utah	25
Logan River near Logan, Utah	28
Blacksmith Fork near Hyrum, Utah	31
Blacksmith Fork power plant race near Hyrum, Utah	33
Veber River basin	35
Description of basin	35
Weber River near Oakley, Utah	36
Weber River near Croyden, Utah	38
Weber River near Plain City, Utah	41
Lost Creek near Croyden, Utah	43
Chalk Creek at Coalville, Utah	45
merican Fork basin	47
American Fork near American Fork, Utah	47
rovo River basin	50
Description of basin	50
Provo River above Telluride Power Company's dam near Provo, Utah	50
Provo River at mouth of canyon near Provo, Utah	53
Provo River at Rio Grande Western Railway bridge near Provo, Utah	56
Hobble Creek basin	58
Hobble Creek near Springville, Utah	58
Spanish Fork basin	60
Spanish Fork near Spanish Fork, Utah	60
Spanish Fork near Lake Shore, Utah	63
Sevier River basin	65
Sevier River near Gunnison, Utah	65
San Pitch River near Gunnison, Utah	67
boldt Sink drainage	70
Humboldt River basin	70
Description of basin	70
North Fork of Humboldt River near Elburz, Nev	70
South Fork of Humboldt River near Elko, Nev	72
Humboldt River at Palisade, Nev	74
Humboldt River near Golconda, Nev	76
Humboldt River near Oreana, Nev	79

Page.
Sierra Nevada drainage 81
Principal streams 81
Truckee River basin 82
Description of basin 82
Truckee River near Wadsworth, Nev 82
Truckee River at Vista, Nev 84
Truckee River at Nevada-California State line 86
Truckee River at Tahoe, Cal 88
Lake Winnemucca Inlet near Wadsworth, Nev 90
Little Truckee River at Pine Station, Cal 92
Independence Creek below Independence Lake, Cal 94
Prosser Creek near Hobart Mills, Cal 96
Donner Creek near Truckee, Cal 97
Walker River basin 99
Description of basin 99
West Fork of Walker River near Coleville, Cal 99
East Fork of Walker River near Yerington, Nev 101
Walker River near Wabuska, Nev 103
Carson River basin 105
Description of basin 105
West Fork of Carson River near Woodfords, Cal 106
East Fork of Carson River near Gardnerville, Nev 108
Carson River near Empire, Nev 111
Susan River basin 113
Description of basin 113
Susan River near Susanville, Cal 114
Willow Creek at Merrillville, Cal 116
Willow Creek near Standish, Cal 118
Owens River drainage basin 120
Minor Great Basin drainage 121
Principal streams 121
Malheur Lake basin 121
Malheur Lake at The Narrows, Oreg 121
Silvies River near Silvies, Oreg 122
Silvies River near Burns, Oreg 123
Harney Lake basin 125
Silver Creek near Riley, Oreg 125
Silver Lake basin 127
Silver Creek near Silver Lake, Oreg 127
Bridge Creek near Silver Lake, Oreg 129
Bear Creek near Silver Lake, Oreg 131
Summer Lake basin 132
Ana River near Summer Lake, Oreg 132
Abert Lake basin 133
Chewaucan River at Paisley, Oreg 133
Miscellaneous measurements in Great Basin 135
Index 137

ILLUSTRATIONS.

PLATE I. Map of the United States, showing location of principal gaging stations maintained during 1905 .....
FIG. 1. Cable station, showing section of river, car, gage, etc. .....
2. Discharge, area and mean velocity curves for South Fork Sk... River near Index, Wash .....

ROGRESS REPORT OF STREAM MEASUREMENTS FOR THE CALENDAR YEAR 1905.

PART XII.

By M. C. HINDERLIDER, G. L. SWENDSEN, and HENRY THURTELL.

INTRODUCTION.

ORGANIZATION AND SCOPE OF WORK.

The hydrographic work of the United States Geological Survey includes the collection f facts concerning and the study of conditions affecting the behavior of water from the me it reaches the earth as rain or snow until it joins the oceans or great navigable rivers. hese investigations became a distinct feature of the work of the Survey in the fall of 1888, hen an instruction camp was established at Embudo, N. Mex. The first specific appro- riation for gaging streams was made by the act of August 18, 1894, which contained an em of $12,500 "for gauging the streams and determining the water supply of the United tates, including the investigation of underground currents and artesian wells in the arid nd semiarid sections." (28 Stat. L., p. 398.)

Since that time appropriations have been gradually increased, as shown by the following ble:

nual appropriations for hydrographic surveys for the fiscal years ending June 30, 1895 to 1906.

5	$12,500	1901	$100,000
6	20,000	1902	100,000
7	50,000	1903	200,000
8	50,000	1904	200,000
9	50,000	1905	200.000
0	50.000	1906	200.000

As a result of the increased appropriations the work has been greatly extended, and at e same time it has been more thoroughly systemized by the adoption of standard methods d by grouping the States into districts, in each of which a district hydrographer and a rps of assistants carry on a comprehensive study of the hydrographic resources.

The chief features of the hydrographic work are the collection of data relating to the w of the surface waters and the study of the conditions affecting this flow. Information also collected concerning river profiles, duration and magnitude of floods, water power, c., which may be of use in hydrographic studies. This work includes the study of the drography of every important river basin in the United States, and is of direct value in e commercial and agricultural development of the country.

In order to collect the material from which estimates of daily flow are made gaging ations are established. The selection of a site for a gaging station and the length of time is maintained depend largely on the physical features and the needs of each locality. If e water is to be used for power, special effort is made to obtain information concerning e minimum flow; if water is to be stored, the maximum flow receives special attention.

Page.
Sierra Nevada drainage 81
Principal streams 81
Truckee River basin 82
Description of basin 82
Truckee River near Wadsworth, Nev 82
Truckee River at Vista, Nev 84
Truckee River at Nevada-California State line 86
Truckee River at Tahoe, Cal 88
Lake Winnemucca Inlet near Wadsworth, Nev 90
Little Truckee River at Pine Station, Cal 92
Independence Creek below Independence Lake, Cal 94
Prosser Creek near Hobart Mills, Cal 96
Donner Creek near Truckee, Cal 97
Walker River basin 99
Description of basin 99
West Fork of Walker River near Coleville, Cal 99
East Fork of Walker River near Yerington, Nev 101
Walker River near Wabuska, Nev 103
Carson River basin 105
Description of basin 105
West Fork of Carson River near Woodfords, Cal 106
East Fork of Carson River near Gardnerville, Nev 108
Carson River near Empire, Nev 111
Susan River basin 113
Description of basin 113
Susan River near Susanville, Cal 114
Willow Creek at Merrillville, Cal 116
Willow Creek near Standish, Cal 118
Owens River drainage basin 120
Minor Great Basin drainage 121
Principal streams 121
Malheur Lake basin 121
Malheur Lake at The Narrows, Oreg 121
Silvies River near Silvies, Oreg 122
Silvies River near Burns, Oreg 123
Harney Lake basin 125
Silver Creek near Riley, Oreg 125
Silver Lake basin 127
Silver Creek near Silver Lake, Oreg 127
Bridge Creek near Silver Lake, Oreg 129
Bear Creek near Silver Lake, Oreg 131
Summer Lake basin 132
Ana River near Summer Lake, Oreg 133
Abert Lake basin 133
Chewaucan River at Paisley, Oreg 133
Miscellaneous measurements in Great Basin 135
Index 137

ILLUSTRATIONS.

PLATE I. Map of the United States, showing location of principal gaging stations maintained during 1905 6
FIG. 1. Cable station, showing section of river, car, gage, etc 11
2. *Discharge*, area and mean velocity curves for South Fork Skykomish River near Index, Wash 14

ROGRESS REPORT OF STREAM MEASUREMENTS FOR THE CALENDAR YEAR 1905.

PART XII.

By M. C. HINDERLIDER, G. L. SWENDSEN, and HENRY THURTELL.

INTRODUCTION.

ORGANIZATION AND SCOPE OF WORK.

The hydrographic work of the United States Geological Survey includes the collection facts concerning and the study of conditions affecting the behavior of water from the ne it reaches the earth as rain or snow until it joins the oceans or great navigable rivers. ese investigations became a distinct feature of the work of the Survey in the fall of 1888, en an instruction camp was established at Embudo, N. Mex. The first specific appro- iation for gaging streams was made by the act of August 18, 1894, which contained an m of $12,500 "for gauging the streams and determining the water supply of the United ates, including the investigation of underground currents and artesian wells in the arid d semiarid sections." (28 Stat. L., p. 398.)

Since that time appropriations have been gradually increased, as shown by the following ble:

nual appropriations for hydrographic surveys for the fiscal years ending June 30, 1895 to 1906.

95	$12,500	1901	$100,000
96	20,000	1902	100,000
97	50,000	1903	200,000
98	50,000	1904	200,000
99	50,000	1905	200,000
00	50,000	1906	200,000

As a result of the increased appropriations the work has been greatly extended, and at e same time it has been more thoroughly systemized by the adoption of standard methods d by grouping the States into districts, in each of which a district hydrographer and a rps of assistants carry on a comprehensive study of the hydrographic resources.

The chief features of the hydrographic work are the collection of data relating to the w of the surface waters and the study of the conditions affecting this flow. Information also collected concerning river profiles, duration and magnitude of floods, water power, ., which may be of use in hydrographic studies. This work includes the study of the drography of every important river basin in the United States, and is of direct value in commercial and agricultural development of the country.

n order to collect the material from which estimates of daily flow are made gaging tions are established. The selection of a site for a gaging station and the length of time s maintained depend largely on the physical features and the needs of each locality. If water is to be used for power, special effort is made to obtain information concerning minimum flow; if water is to be stored, the maximum flow receives special attention.

In all sections of the country permanent gaging stations are maintained for general s tical purposes, to show the conditions existing through long periods. They are alsc as primary stations, and their records, in connection with short series of measurer serve as bases for estimating the flow at other points in the drainage basin.

During the calendar year 1905 the division of hydrography has continued measuri flow of streams on the same general lines as in previous years. Many new and imp methods have been introduced, by which the accuracy and value of the results hav increased. Approximately 800 regular gaging stations were maintained during the and an exceptionally large number of miscellaneous measurements and special inv tions were made. The "Report of Progress of Stream Measurements," which co the results of this work, is published in a series of fourteen Water-Supply and Irri Papers, Nos. 165 to 178, as follows:

No. 165. Atlantic coast of New England drainage.
No. 166. Hudson, Passaic, Raritan, and Delaware river drainages.
No. 167. Susquehanna, Gunpowder, Patapsco, Potomac, James, Roanoke, and Yadkin drainages.
No. 168. Santee, Savannah, Ogeechee, and Altamaha rivers and eastern Gulf of Mexico ages.
No. 169. Ohio and lower eastern Mississippi river drainages.
No. 170. Great Lakes and St. Lawrence River drainages.
No. 171. Hudson Bay, and upper eastern and western Mississippi River drainages.
No. 172. Missouri River drainage.
No. 173. Meramec, Arkansas, Red, and lower western Mississippi river drainages.
No. 174. Western Gulf of Mexico and Rio Grande drainages.
No. 175. Colorado River drainage.
No. 176. The Great Basin drainage.
No. 177. The Great Basin and Pacific Ocean drainages in California.
No. 178. Columbia River and Puget Sound drainages.

These papers embody the data collected at the regular gaging stations, the results computations based on the observations, and such other information as may have a bearing on the study of the subject, and include, as far as practicable, descriptions basins and the streams draining them.

For the purpose of introducing uniformity into the reports for the various yea drainages of the United States have been divided into eleven grand divisions, which been again divided into secondary divisions, as shown in the following list. The Pr Report has been made to conform to this arrangement, each part containing the da one or more of the secondary divisions. The secondary divisions have in most case redivided, and the facts have been arranged, as far as practicable, geographically.

Drainage basins in the United States.

NORTHERN ATLANTIC DRAINAGE BASINS.

St. John.	Thames.
St. Croix.	Housatonic.
Penobscot.	Hudson.
Kennebec.	Passaic.
Androscoggin.	Raritan.
Presumpscot.	Delaware.
Saco.	Susquehanna.
Merrimac.	Potomac.
Connecticut.	Minor Chesapeake Bay.
Blackstone.	Minor northern Atlantic.

SOUTHERN ATLANTIC DRAINAGE BASINS.

James.	Great Pedee (Yadkin).
Chowan.	Santee.
Roanoke.	Savannah.
Tar.	Ogechee.
Neuse.	Altamaha.
Cape Fear.	Minor Southern Atlantic.


81° 79° 77° 75° 73° 71° 69° 67°
VT.
N. H.
MASS.
CONN. R.I.
NEW YORK
PENNSYLVANIA
NEW JERSEY
DEL.
MD.
WEST VIRGINIA
VIRGINIA
NORTH CAROLINA
SOUTH CAROLINA
GEORGIA
FLORIDA
500 miles
119° 117° 85° 83° 81° 79° 77°
49° 47° 45° 43° 41° 39° 37° 35° 33° 31° 29° 27° 25°

DURING 1905.



EASTERN GULF OF MEXICO DRAINAGE BASINS.

	Pearl.
)la.	Minor eastern Gulf of Mexico.

EASTERN MISSISSIPPI RIVER DRAINAGE BASINS.

tern Mississippi.	Upper eastern Mississippi.

ST. LAWRENCE RIVER DRAINAGE BASINS.

rior.	Niagara River.
igan.	Lake Ontario.
)n.	Lake Champlain (Richelieu River).
lair.	Minor St. Lawrence.

WESTERN MISSISSIPPI RIVER DRAINAGE BASINS.

ıtern Mississippi.	Lower western Mississippi.
	Arkansas.
	Red.

WESTERN GULF OF MEXICO DRAINAGE BASINS.

	Guadelupe.
	San Antonio.
	Nueces.
	Rio Grande.
of Texas).	Minor western Gulf of Mexico.

COLORADO RIVER DRAINAGE BASIN.

THE GREAT BASIN.

ıountains.	Sierra Nevada.
	Minor streams in Great Basin.

PACIFIC COAST DRAINAGE BASINS.

Pacific.	Columbia.
isco Bay.	Puget Sound.
Pacific.	

HUDSON BAY DRAINAGE BASINS.

DEFINITIONS.

)lume of water flowing in a stream—the "run-off" or "discharge"—is expressed s terms, each of which has become associated with a certain class of work. These ay be divided into two groups—(1) those which represent the rate of flow, as et, gallons per minute, miner's inch, and run-off in second-feet per square mile; hose which represent the actual quantity of water, as run-off in depth in inches feet. They may be defined as follows:

ıd-foot" is an abbreviation for cubic foot per second, and is the rate of discharge flowing in a stream 1 foot wide, 1 foot deep, at a rate of 1 foot per second. It is used as a fundamental unit from which others are computed.

)ns per minute" is generally used in connection with pumping and city water

niner's inch" is the rate of discharge of water passing through an orifice 1 inch ıder a head which varies locally. It has been commonly used by miners and throughout the West, and is defined by statute in each State in which it is used. States the California miner's inch is used, which is the fiftieth part of a second-foot.

ıd-feet per square mile" is the average number of cubic feet of water flowing per om each square mile of area drained, on the assumption that the run-off is dis- uniformly both as regards time and area.

"Run-off in inches" is the depth to which the drainage area would be covered if all the water flowing from it in a given period were conserved and uniformly distributed on the surface. It is used for comparing run-off with rainfall, which is usually expressed in depth in inches.

"Acre-foot" is equivalent to 43,560 cubic feet, and is the quantity required to cover an acre to the depth of 1 foot. It is commonly used in connection with storage for irrigation work. There is a convenient relation between the second-foot and the acre-foot. One second-foot flowing for twenty-four hours will deliver 86,400 cubic feet, or approximately 2 acre-feet.

EXPLANATION OF TABLES.

For each regular gaging station are given, as far as available, the following data:

1. Description of station.
2. List of discharge measurements.
3. Gage-height table.
4. Rating table.
5. Table of estimated monthly and yearly discharges and run-off, based on all the facts obtained to date.

The descriptions of stations give such general information about the locality and equipment as would enable the reader to find and use the station. They also give, as far as possible, a complete history of all the changes since the establishment of the station that would be factors in using the data collected.

The discharge-measurement table gives the results of the discharge measurements made during the year, including the date, the name of the hydrographer, the gage height, the area of cross section, the mean velocity, and the discharge in second-feet.

The table of daily gage heights gives the daily fluctuations of the surface of the river as found from the mean of the gage readings taken each day. The gage height given in the table represents the elevation of the surface of the water above the zero of the gage. At most stations the gage is read in the morning and in the evening.

The rating table gives discharges in second-feet corresponding to each stage of the river as given by the gage heights.

In the table of estimated monthly discharge the column headed "Maximum" gives the mean flow for the day when the mean gage height was highest; this is the flow as given in the rating table for that mean gage height. As the gage height is the mean for the day, there might have been short periods when the water was higher and the corresponding discharge larger than that given in this column. Likewise, in the column of "Minimum" the quantity given is the mean flow for the day when the mean gage height was lowest. The column headed "Mean" is the average flow for each second during the month. On this are based computations for the three remaining columns, which are defined above.

In the computations for the tables of this report the following general and special rules have been used:

Fundamental rules for computation.

1. The highest degree of precision consistent with the rational use of time and money is imperative.
2. All items of computation should be expressed by at least two, and not more than four, significant figures.
3. Any measurement in a vertical velocity, mean velocity, or discharge curve whose per cent of error is five times the average per cent of error of all the other measurements should be rejected.
4. In reducing the number of significant figures, or the number of decimal places, by dropping the last figure, the following rules apply:

(*a*) When the figure in the place to be rejected is less than 5, drop it without changing the preceding figure. Example: 1,827.4 becomes 1,827.

(*b*) When the figure in the place to be rejected is greater than 5, drop it and increase the preceding figure by 1. Example: 1,827.6 becomes 1,828.

(*c*) When the figure in the place to be rejected is 5 and it is preceded by an even figure, drop it. Example: 1,828.5 becomes 1,828.

(*d*) When the figure in the place to be rejected is 5 and it is preceded by an odd figure, drop it and increase the preceding figure by 1. Example: 1,827.5 becomes 1,828.

Special rules for computation.

ating tables are to be constructed as closely as the data on which they are based will warrant.
cimals are to be used when the discharge is over 50 second-feet.
aily discharges shall be applied directly to the gage heights as they are tabulated.
lonthly means are to be carried out to one decimal place when the quantities are below 100 second-
Between 100 and 10,000 second-feet the last figure in the monthly mean shall be a significant figure.
lso applies to the yearly mean.
econd-feet per square mile and depth in inches for the individual months shall be carried out to
st three significant figures, except in the case of decimals where the first significant figure is pre-
by one or more naughts (0), when the quantity shall be carried out to two significant figures.
ple: 1.25, 0.125, 0.012, 0.0012. The yearly means for these quantities are always to be expressed in
significant figures and at least two decimal places.

CONVENIENT EQUIVALENTS.

econd-foot equals 50 California miner's inches.
econd-foot equals 38.4 Colorado miner's inches.
econd-foot equals 40 Arizona miner's inches.
econd-foot equals 7.48 United States gallons per second; equals 448.8 gallons per minute; equals
72 gallons for one day.
econd-foot equals 6.23 British imperial gallons per second.
econd-foot for one year covers 1 square mile 1.131 feet deep; 13.572 inches deep.
econd-foot for one year equals 0.000_14 cubic mile; equals 31,536,000 cubic feet.
econd-foot equals about 1 acre-inch per hour.
econd-foot falling 10 feet equals 1.136 horsepower.
California miner's inches equal 15 United States gallons per second.
California miner's inches equal 77 Colorado miner's inches.
California miner's inches for one day equals 4 acre-feet.
Colorado miner's inches equal 2.60 second-feet.
Colorado miner's inches equal 19.5 United States gallons per second.
Colorado miner's inches equal 130 California miner's inches.
Colorado miner's inches for one day equal 5.2 acre-feet.
United States gallons per minute equal .223 second-foot.
United States gallons per minute for one day equal 0.44 acre-foot.
00,000 United States gallons per day equal 1.55 second-feet.
00,000 United States gallons equal 3.07 acre-feet.
00,000 cubic feet equal 22.95 acre-feet.
cre-foot equals 325,850 gallons.
nch deep on 1 square mile equals 2,323,200 cubic feet.
nch deep on 1 square mile equals 0.0737 second-foot per year.
nch equals 2.54 centimeters.
oot equals 0.3048 meter.
ard equals 0.9144 meter.
nile equals 1.60935 kilometers.
nile equals 1,760 yards; equals 5,280 feet; equals 63,360 inches.
quare yard equals 0.836 square meter.
cre equals 0.4047 hectare.
cre equals 43,560 square feet; equals 4,840 square yards.
cre equals 209 feet square, nearly.
quare mile equals 259 hectares.
quare mile equals 2.59 square kilometers.
ubic foot equals 0.0283 cubic meter.
ubic foot equals 7.48 gallons; equals 0.804 bushel.
ubic foot of water weighs 62.5 pounds.
ubic yard equals 0.7646 cubic meter.
ubic mile equals 147,198,000,000 cubic feet.
bic mile equals 4,667 second-feet for one year.
llon equals 3.7854 liters.
llon equals 8.36 pounds of water.
llon equals 231 cubic inches (liquid measure).
ound equals 0.4536 kilogram.
oirdupois pound equals 7,000 grains.
oy pound equals 5,760 grams.
eter equals 39.37 inches. Log. 1.5951654.
eter equals 3.280833 feet. Log. 0.5159842.
eter equals 1.093611 yards. Log. 0.0388629.
lometer equals 3,281 feet; equals five-eighths mile, nearly.

1 square meter equals 10.764 square feet; equals 1.196 square yards.
1 hectare equals 2.471 acres.
1 cubic meter equals 35.314 cubic feet; equals 1.308 cubic yards.
1 liter equals 1.0567 quarts.
1 gram equals 15.43 grains.
1 kilogram equals 2.2046 pounds.
1 tonneau equals 2,204.6 pounds.
1 foot per second equals 1.097 kilometers per hour.
1 foot per second equals 0.68 mile per hour.
1 cubic meter per minute equals 0.5886 second-foot.
1 atmosphere equals 15 pounds per square inch; equals 1 ton per square foot; equals 1 kilogram per square centimeter.
Acceleration of gravity equals 32.16 feet per second every second.
1 horsepower equals 550 foot-pounds per second.
1 horsepower equals 76 kilogram-meters per second.
1 horsepower equals 746 watts.
1 horsepower equals 1 second-foot falling 8.8 feet.
1½ horsepowers equal about 1 kilowatt.
To calculate water power quickly: $\frac{\text{Sec.-ft.} \times \text{fall in feet}}{11}$ = Net horsepower on water wheel, realizing 80 per cent of the theoretical power.
Quick formula for computing discharge over weirs: Cubic feet per minute equals $0.4025\, l\sqrt{h^3}$; l = length of weir in inches; h = head in inches flowing over weir, measured from surface of still water.
To change miles to inches on map:

Scale 1:125000, 1 mile=0.50688 inch.
Scale 1:90000, 1 mile=0.70400 inch.
Scale 1:62500, 1 mile=1.01376 inches.
Scale 1:45000, 1 mile=1.40800 inches.

FIELD METHODS OF MEASURING STREAM FLOW.

The methods used in collecting these data and in preparing them for publication are given in detail in Water-Supply Papers No. 94 (Hydrographic Manual, U. S. Geol. Survey) and No. 95 (Accuracy of Stream Measurements). In order that those who use this report may readily become acquainted with the general methods employed, the following brief description is given.

Streams may be divided, with respect to their physical conditions, into three classes—(1) those with permanent beds; (2) those with beds which change only during extreme low or high water; (3) those with constantly shifting beds. In estimating the daily flow special methods are necessary for each class. The data on which these estimates are based and the methods of collecting them are, however, in general the same.

There are three distinct methods of determining the flow of open-channel streams—(1) by measurements of slope and cross section and the use of Chezy's and Kutter's formulas; (2) by means of a weir; (3) by measurements of the velocity of the current and of the area of the cross section. The method chosen for any case depends on the local physical conditions, the degree of accuracy desired, the funds available, and the length of time that the record is to be continued.

Slope method.—Much information has been collected relative to the coefficients to be used in the Chezy formula, $v = c\sqrt{r\,s}$. This has been utilized by Kutter, both in developing his formula for c and in determining the values of the coefficient n, which appears therein. The results obtained by the slope method are in general only roughly approximate, owing to the difficulty in obtaining accurate data and the uncertainty of the value for n to be used in Kutter's formula. The most common use of this method is in estimating the flood discharge of a stream when the only data available are the cross section, the slope, as shown by marks along the bank, and a knowledge of the general conditions.

Weir method.—When funds are available and the conditions are such that sharp-crested weirs can be erected, these offer the best facilities for determining flow. If dams are suitably situated and constructed, they may be utilized for obtaining reliable estimates of flow. The conditions necessary to insure good results may be divided into two classes—(1) those relating to the physical characteristics of the dam itself and (2) those relating to *submersion* and use of water around and through the dam.

The physical requirements are as follows: (*a*) Sufficient height of dam, so that backwater will not interfere with free fall over it; (*b*) absence of leaks of appreciable magnitude; (*c*) topography or abutments which confine the flow over the dam at high stages; (*d*) level crests, which are kept free from obstructions caused by floating logs or ice; (*e*) crests of a type for which the coefficients to be used in $Q=c\ b\ h^{\frac{3}{2}}$, or some similar standard weir formula, are known (see Water-Supply Paper No. 150); (*f*) either no flash boards or exceptional care in reducing leakage through them and in recording their condition.

Preferably there should be no diversion of water through or around the dam. Generally, however, a dam is built for purposes of power or navigation, and part or all of the water flowing past it is diverted for such uses. This water is measured and added to that passing over the dam. To insure accuracy in such estimates the amount of water diverted should be reasonably constant. Furthermore, it should be so diverted that it can be measured, either by a weir, a current meter, or a simple system of water wheels which are of standard make, or which have been rated as meters under working conditions, and so installed that the gate openings, the heads under which they work, and their angular velocities may be accurately observed.

The combination of physical conditions and uses of the water should be such that the estimates of flow will not involve, for a critical stage of considerable duration, the use of a head, on a broad-crested dam, of less than 6 inches. Moreover, when all other conditions are good, the cooperation of the owners or operators of the plant is still essential if reliable results are to be obtained.



FIG. 1.—Cable station showing section of river, car, gage, etc.

A gaging station at a weir or dam has the general advantage of continuity of record through the period of ice and floods, and the disadvantages of uncertainty of coefficient to be used in the weir formula and of complications in the diversion and use of the water.

Velocity method.—The determination of the quantity of water flowing past a certain section of a stream at a given time is termed a discharge measurement. This quantity is the product of two factors—the mean velocity and the area of the cross section. The mean velocity is a function of surface slope, wetted perimeter, roughness of bed, and the channel conditions at, above, and below the gaging section. The area depends on the contour of the bed and the fluctuations of the surface. The two principal ways of measuring the velocity of a stream are by floats and current meters.

Great care is taken in the selection and equipment of gaging stations for determining discharge by velocity measurements in order that the data may have the required degree of accuracy Their essential requirements are practically the same whether the velocity is determined by meters or floats. They are located as far as possible where the channel is straight both above and below the gaging section; where there are no cross currents, backwater, or boils; where the bed of the stream is reasonably free from large projections of a permanent character; and where the banks are high and subject to overflow only at flood stages. The station must be so far removed from the effects of tributary streams and dams or other artificial obstructions that the gage height shall be an index of the discharge.

Certain permanent or semipermanent structures, usually referred to as "equipment," are generally pertinent to a gaging station. These are a gage for determining the fluctuations of the water surface, bench marks to which the datum of the gage is referred, permanent marks on a bridge or a tagged line indicating the points of measurement, and, where the current is swift, some appliance (generally a secondary cable) to hold the meter in position in the water. As a rule, the stations are located at bridges if the channel conditions are satisfactory, as from them the observations can more readily be made and the cost of the equipment is small.

The floats in common use are the surface, subsurface, and tube or rod floats. A corked bottle with a flag in the top and weighted at the bottom makes one of the most satisfactory surface floats, as it is affected but little by wind. In case of flood measurements, good results can be obtained by observing the velocity of floating cakes of ice or débris. In case of all surface-float measurements coefficients must be used to reduce the observed velocity to the mean velocity. The subsurface and tube or rod floats are intended to give directly the mean velocity in the vertical. Tubes give excellent results when the channel conditions are good, as in canals.

In measuring velocity by a float, observation is made of the time taken by the float to pass over the "run," a selected stretch of river from 50 to 200 feet long. In each discharge measurement a large number of velocity determinations are made at different points across the stream and from these observations the mean velocity for the whole section is determined. This may be done by plotting the mean positions of the floats as indicated by the distances from the bank as ordinates and the corresponding times as abscissas. A curve through these points shows the mean time of run at any point across the stream, and the mean time for the whole stream is obtained by dividing the area bounded by this curve and its axis by the width. The length of the run divided by the mean time gives the mean velocity.

The area used in float measurements is the mean of the areas at the two ends of the run and at several intermediate sections.

The essential parts of the current meters in use are a wheel of some type, so constructed that the impact of flowing water causes it to revolve, and a device for recording or indicating the number of revolutions. The relation between the velocity of the moving water and the revolutions of the wheel is determined for each meter. This rating is done by drawing the meter through still water for a given distance at different speeds, and noting the number of revolutions for each run. From these data a rating table is prepared, which gives the velocity per second for any number of revolutions.

Many kinds of current meters have been constructed. They may, however, be classed in two general types—those in which the wheel is made up of a series of cups, as the Price, and those having a screw-propeller wheel, as the Haskell. Each meter has been developed for use under some special condition. In the case of the small Price meter, which has been largely developed and extensively used by the United States Geological Survey, an attempt has been made to get an instrument which could be used under practically all conditions.

Current-meter measurements may be made from a bridge, cable, boat, or by wading; and gaging stations may be classified in accordance with such use. Fig. 1 shows a typical cable station.

In making the measurement an arbitrary number of points are laid off on a line perpendicular to the thread of the stream. The points at which the velocity and depth are observed are known as measuring points and are usually fixed at regular intervals, varying from 2 to 20 feet, depending on the size and condition of the stream. Perpendiculars dropped from the measuring points divide the gaging section into strips. For each strip or pair of strips the mean velocity, area, and discharge are determined independently, so that conditions existing in one part of the stream may not be extended to parts where they do not apply.

Three classes of methods of measuring velocity with current meters are in general use—multiple-point, single-point, and integration.

The three principal multiple-point methods in general use are the vertical velocity curve, *0.2 and 0.8* depth; and top, bottom, and mid-depth.

In the vertical velocity curve method a series of velocity determinations are made in each vertical at regular intervals, usually from 0.5 to 1 foot apart. By plotting these velocities as abscissas and their depths as ordinates, and drawing a smooth curve among the resulting points, the vertical velocity curve is developed. This curve shows graphically the magnitude and changes in velocity from the surface to the bottom of the stream. The mean velocity in the vertical is then obtained by dividing the area bounded by this velocity curve and its axis by the depth. On account of the length of time required to make a complete measurement by this method, its use is limited to the determination of coefficients for purposes of comparison and to measurements under ice.

In the second multiple-point method the meter is held successively at 0.2 and 0.8 of the depth and the mean of the velocities at these two points is taken as the mean velocity for that vertical. On the assumption that the vertical velocity curve is a common parabola with horizontal axis, the mean of the velocities at 0.22 and 0.79 of the depth will give (closely) the mean velocity in the vertical. Actual observations under a wide range of conditions show that this second multiple-point method gives the mean velocity very closely for open-water conditions where the depth is over 5 feet and the bed comparatively smooth, and moreover the indications are that it will hold nearly as well for ice-covered rivers.

In the third multiple-point method the meter is held at mid-depth, at 0.5 foot below the surface and at 0.5 foot above the bottom, and the mean velocity is determined by dividing by 6 the sum of the top velocity, four times the mid-depth velocity, and the bottom velocity. This method may be modified by observing at 0.2, 0.6, and 0.8 depth.

The single-point method consists in holding the meter either at the depth of the thread of mean velocity or at an arbitrary depth for which the coefficient for reducing to mean velocity has been determined.

Extensive experiments by vertical velocity curves show that the thread of mean velocity generally occurs at from 0.5 to 0.7 of the total depth. In general practice the thread of mean velocity is considered to be at 0.6 depth, at which point the meter is held in a majority of the measurements. A large number of vertical velocity-curve measurements taken on many streams and under varying conditions show that the average coefficient for reducing the velocity obtained at 0.6 depth to mean velocity is practically unity.

In the other principal single-point method the meter is held near the surface, usually 1 foot below, or low enough to be out of the effect of the wind or other disturbing influences. This is known as the subsurface method. The coefficient for reducing the velocity taken at the subsurface to the mean has been found to be from 0.85 to 0.95, depending on the stage, velocity, and channel conditions. The higher the stage the larger the coefficient. This method is specially adapted for flood measurements, or when the velocity is so great that the meter can not be kept at 0.6 depth.

The vertical-integration method consists in moving the meter at a slow, uniform speed from the surface to the bottom and back again to the surface, and noting the number of revolutions and the time taken in the operation. This method has the advantage that the velocity at each point of the vertical is measured twice. It is well adapted for measurements under ice and as a check on the point methods.

The area, which is the other factor in the velocity method of determining the discharge of a stream, depends on the stage of the river, which is observed on the gage, and on the general contour of the bed of the stream, which is determined by soundings. The soundings are usually taken at each measuring point at the time of the discharge measurement, either by using the meter and cable or by a special sounding line or rod. For streams with permanent beds standard cross sections are usually taken during low water. These sections serve to check the soundings which are taken at the time of the measurements, and from them any change which may have taken place in the bed of the stream can be detected. They are also of value in obtaining the area for use in computations of high-water measurements, as accurate soundings are hard to obtain at high stages.

In computing the discharge measurements from the observed velocities and depths at various points of measurement, the measuring section is divided into elementary strips, as

shown in fig. 1. and the mean velocity, area, and discharge are determined separately for either a single or a double strip. The total discharge and the area are the sums of those for the various strips, and the mean velocity is obtained by dividing the total discharge by the total area.

The determination of the flow of an ice-covered stream is difficult, owing to diversity and instability of conditions during the winter period and also to lack of definite information in regard to the laws of flow of water under ice. The method now employed is to make frequent discharge measurements during the frozen periods by the vertical velocity-curve method and to keep an accurate record of the conditions, such as the gage height to the surface of the water as it rises in a hole cut in the ice, the thickness and character of the ice, etc. From these data an approximate estimate of the daily flow can be made by constructing a rating curve (really a series of curves) similar to that used for open channels, but considering, in addition to gage heights and discharge, varying thickness of ice. Such data as are available in regard to this subject are published in Water-Supply Paper No. 146, pages 141–148.

OFFICE METHODS OF COMPUTING RUN-OFF.

There are two principal methods of estimating run-off, depending on whether or not the bed of the stream is permanent.


MEAN VELOCITY, AREA AND RATING CURVES FOR SKYKOMISH RIVER (SO. FORK) NEAR INDEX, WASH.
MEASUREMENTS IN 1902 NO. 1 TO 7
" 1903 8 " 12
RATING CURVE
AREA CURVE
MEAN VELOCITY CURVE
GAGE HEIGHT IN FEET
AREA IN SQUARE FEET
VELOCITY IN FEET PER SECOND
DISCHARGE IN SECOND-FEET

FIG. 2—Rating, area, and mean-velocity curves for South Fork of Skykomish River near Index, Wash.

For stations on streams with permanent beds the first step in computing the run-off is the construction of the rating table, which shows the discharge corresponding to any stage of the stream. This rating table is applied to the record of stage to determine the amount of water flowing. The construction of the rating table depends on the method used in measuring flow.

For a station at a weir or dam, the basis for the rating table is some standard weir formula. The coefficients to be used in its application depend on the type of dam and other conditions near its crest. After inserting in the weir formula the measured length of crest and assumed coefficient, the discharge is computed for various heads and the rating table constructed.

The data necessary for the construction of a rating table for a velocity-area station are the results of the discharge measurements, which include the record of stage of the river at the time of measurement, the area of the cross section, the mean velocity of the current, and the quantity of water flowing. A thorough knowledge of the conditions at and in the *vicinity of* the station is also necessary.

The construction of the rating table depends on the following laws of flow for open, permanent channels: (1) The discharge will remain constant so long as the conditions at or ar the gaging station remains constant. (2) The discharge will be the same whenever stream is at a given stage, if the change of slope due to the rise and fall of the stream neglected. (3) The discharge is a function of and increases gradually with the stage. The plotting of results of the various discharge measurements, using gage heights as inates, and discharge, mean velocity, and area as abscissas, will define curves which w the discharge, mean velocity, and area corresponding to any gage height. For the elopment of these curves there should be, therefore, a sufficient number of discharge surements to cover the range of the stage of the stream. Fig. 2 shows a typical rating ve with its corresponding mean-velocity and area curves.

s the discharge is the product of two factors, the area and the mean velocity, any change either factor will produce a corresponding change in the discharge. Their curves are refore constructed in order to study each independently of the other.

The area curve can be definitely determined from accurate soundings extending to the its of high water. It is always concave toward the horizontal axis or on a straight line, ess the banks of the stream are overhanging.

The form of the mean-velocity curve depends chiefly on the surface slope, the roughness the bed, and the cross section of the stream. Of these, the slope is the principal factor. accordance with the relative change of these factors the curve may be either a straight e, convex or concave toward either axis, or a combination of the three. From a careful dy of the conditions at any gaging station the form which the vertical velocity curve l take can be predicted, and it may be extended with reasonable certainty to stages beyond limits of actual measurements. Its principal use is in connection with the area curve locating errors in discharge measurements and in constructing the rating table.

The discharge curve is defined primarily by the measurements of discharge, which are died and weighted in accordance with the local conditions existing at the time of each surement. The curve may, however, best be located between and beyond the measure-nts by means of curves of area and mean velocity. The discharge curve under normal ditions is concave toward the horizontal axis and is generally parabolic in form.

n the preparation of the rating table the discharge for each tenth or half-tenth on the e is taken from the curve. The differences between successive discharges are then taken adjusted according to the law that they shall either be constant or increasing.

The determination of the daily discharge of streams with changeable beds is a difficult blem. In case there is a weir or dam available, a condition which seldom exists on ams of this class, estimates can be obtained by its use. In the case of velocity-area ions frequent discharge measurements must be made if the estimates are to be other n rough approximations. For stations with beds which shift slowly or are materially nged only during floods, rating tables can be prepared for periods between such changes, l satisfactory results obtained with a limited number of measurements, provided that e of them are taken soon after the change occurs. For streams with continually ting beds, such as the Colorado and Rio Grande, discharge measurements should be made ry two or three days and the discharges for intervening days obtained either by inter-ation modified by gage height or by Professor Stout's method, which has been described ull in the Nineteenth Annual Report of the United States Geological Survey, Part IV, e 323, and in the Engineering News of April 21, 1904. This method, or a graphical lication of it, is also much used in estimating flow at stations where the bed shifts but wly.

COOPERATION AND ACKNOWLEDGMENTS.

Most of the measurements presented in this paper have been obtained through local drographers. Acknowledgment is extended to other persons and corporations who re assisted local hydrographers or have cooperated in any way, either by furnishing ords of the height of water or by assisting in transportation.

The following list, arranged alphabetically by States, gives the names of the hydrographers and others who have assisted in furnishing and preparing the data contained in this report:

California.—The hydrographic work in Susan and Owens rivers drainages in eastern California was under the direction of J. B. Lippincott, supervising engineer; W. B. Clapp, district hydrographer; assisted by R. J. Taylor, J. S. Evans, F. R. S. Buttemer, and J. Branham. The results of the data collected in Owens River Valley are contained in Water-Supply Paper No. 177, which contains the results of all the hydrographic data collected in the State of California during 1905.

The work in the Truckee, Carson, and Walker rivers drainages was under the direction of Henry Thurtell, State engineer of Nevada, assisted by W. A. Wolf.

Idaho.—The work in that portion of Idaho which lies in the Great Basin was under the direction of George L. Swendsen, district engineer, assisted by W. G. Swendsen, hydrographer.

Nevada.—The hydrographic work in this section has been carried on in cooperation with the State by Henry Thurtell, State engineer, assisted by W. A. Wolf. Acknowledgment is due to the Southern Pacific Company and also to the San Pedro, Los Angeles and Salt Lake Railroad Company for transportation furnished.

Oregon.—District engineer, John T. Whistler, assisted by Wilbur C. Sawyer, Edwards N. Smith, and Ivan Landes. Acknowledgment and thanks are due the Oregon Railroad and Navigation Company, the Oregon Short Line Railroad, the Sumpter Valley Railway, and the Columbia Southern Railway Company for transportation furnished.

Utah.—District engineer, George L. Swendsen, assisted by W. G. Swendsen, hydrographer. Acknowledgments are also due to the Oregon Short Line Railroad, the Denver and Rio Grande Railroad, and the San Pedro, Los Angeles and Salt Lake Railroad Company, for transportation furnished; to the Telluride Power Company; Logan River canal companies; Jordan River canal companies, Salt Lake engineer; J. Fewson Smith, jr., water commissioner for Jordan Valley; William Knight, superintendent of pumping plant at Utah Lake; and others who have given assistance from time to time. All daily papers of the State have supported the work strongly and have done much to emphasize the importance of hydrographic information to a proper development of irrigation interests.

GENERAL DESCRIPTION OF THE GREAT BASIN.

In the interior of the North American continent, west of the Rocky Mountains, is an immense area known as the Great Basin, the streams of which do not discharge to the ocean. The area is not one single drainage basin, but consists rather of a number of basins, some of which are connected and others closed; the outer rim of all, however, is at such an elevation that the region as a whole has no surface outlet.

In outline the Great Basin is rudely triangular. It is bordered on the west by the Sierra Nevada, on the north by the Columbia plateaus, on the east by the Rocky Mountains and the Colorado plateaus, and the southern extremity extends almost to the Gulf of California. This inclosed area is approximately 800 miles long from north to south, 500 miles broad at its widest part, and has been estimated to include 208,000 square miles. It comprises the western part of Utah, almost all of Nevada, and contiguous parts of Idaho, Oregon, and California.

Topographically this interior drainage area is characterized by isolated, narrow mountain ranges, trending north and south, which are seperated by broad valleys varying considerably in altitude. In the southern part the valleys are low, Death Valley being below sea level, while in the north the valleys have a general elevation of from 4,000 to 5,000 feet. The intervening highlands often rise several thousand feet above their bases, and some of the peaks of the bordering ranges attain elevations of 13,000 feet above sea level.

Upper branches of the intermontane valleys extend into the interior ranges as narrow drainage ways that are dry during most of the year; but the drainage from the high mountains on the east and west borders of the basin passes through deep canyons into the broad valleys, where the perennial streams maintain lakes. Among these are Great Salt, Utah, and Sevier lakes in the eastern part, and Pyramid, Winnemucca, Honey, Walker, Mono, and Owens lakes in the western part of the Great Basin. With the exception of Utah Lake, which discharges by Jordan River into Great Salt Lake, these lakes are saline in character, as a consequence of the concentration of salts due to evaporation. Bear Lake, in the mountains of the eastern border, and Lake Tahoe, in the Sierras, are *large bodies* of fresh water that drain, respectively, to Great Salt and Pyramid lakes. *Shallow, temporary* bodies of water accumulate in some of the broad intermontane val-

leys during the wet season, but completely evaporate during the summer, leaving muddy plains called playas.

Geologically the Great Basin is well known as the type region of the "Basin Range structure." Many of the isolated, narrow mountain ranges that trend north and south are steep on one side, exposing cross sections of the rocks, and sloping on the other, conforming with the dip of the strata. These ranges have been uplifted by movements of the earth's crust which have broken it into tilted blocks. The greatest displacements of the Great Basin are associated with the eastern and western borders, the Wasatch Mountains and the Sierra Nevada having been uplifted many thousand feet. The mountains of the Great Basin are commonly composed of Paleozoic strata, often modified by vulcanism, and the products of weathering and disintegration of these rocks have accumulated in the broad intervening valleys, which are strewn to great depths with unconsolidated débris.

The climate of the Great Basin is extremely arid, and except a few favored spots where irrigation is practiced, the region in general is a desert. Over the larger part of the area the annual precipitation is less than 10 inches, but it is greater on the bordering high lands, especially on the Sierra Nevada, where it is over 40 inches. Temperature varies widely, owing to the large extent of the area and to differences in elevation. Over most of the region the heat of the summer days is intense, but the diurnal variation is considerable. Evaporation is enormous. From the surface of water in the vicinity of Salt Lake City it amounts to about 60 inches in a year, and over the major part of the Great Basin it is much greater, amounting in places possibly to 150 inches.

An arid climate, however, has not always prevailed in this region. In late geologic time (early Quaternary) the bordering high mountains supported glaciers, and enormous lakes, the old shore lines of which are now plainly marked on the sides of many valleys, accumulated in the Great Basin. The two largest of these lakes have been named after early explorers. Lake Bonneville occupied a considerable part of western Utah, its shrunken remnants being represented by Sevier, Utah, and Great Salt lakes; and Lake Lahontan covered an immense area in western Nevada.

The chief rivers of the Great Basin rise in the mountains which form its eastern and western borders and receive their principal supply from melting snow. The nature of the stream discharge is characteristic; the maximum commonly occurs in late spring or early summer, after which the flow decreases, reaching a minimum during the winter months. After leaving the mountains the streams receive little or no increment; in the broad, waste-filled valleys evaporation and seepage cause diminution in size, and often they entirely cease to flow.

For convenience of treatment, the drainage of the Great Basin has been divided into four areas, viz, Wasatch Mountains, Humboldt Sink, Sierra Nevada, and minor Great Basin drainages. The data collected in these areas during 1905 are given in the following pages:

WASATCH MOUNTAINS DRAINAGE.

PRINCIPAL STREAMS.

The Wasatch Mountains drainage area includes the western half of Utah and small portions of Idaho and Wyoming. The headwaters of the various streams lie either in the Wasatch Mountains or in the plateaus to the south, and they drain either into Great Salt Lake or Sevier Lake. The following are the principal rivers of the area:

Bear and Weber rivers, discharging into Great Salt Lake.

City, Parleys, Emigration, Mill, and Big and Little Cottonwood creeks, tributary to Jordan River and thus to Great Salt Lake. These creeks have small watersheds, but in the mountain courses maintain perennial flows. On reaching the main valley they are extensively used for irrigation and the first three furnish the chief water supply for Salt Lake City.

American Fork and Hobble creeks, Spanish Fork, and Provo River, discharging into Utah Lake.

Sevier River, *with its tributary*, San Pitch River, draining into Sevier Lake.

BEAR RIVER BASIN.

DESCRIPTION OF BASIN.

Bear River rises on the northern slope of the Uinta Mountains, in the northeastern part of Utah, and after a circuitous course—in which it leaves Utah and enters Wyoming, reenters Utah, appears again in Wyoming, and makes a long detour in Idaho—it returns again to Utah and finally discharges its waters into Great Salt Lake. The maximum elevation of the upper rim of the basin is 13,000 feet.

In the upper part of its course, above the Dingle gaging station, the country is rough and broken, the rocks of the extreme headwater regions being principally sandstone and quartzite, covered with a thin layer of soil which supports scattered groves of fir and aspen. Farther down the prevailing formation is a compact limestone covered with a clayey soil, generally dry and with a rank growth of sagebrush. The tributary streams are numerous and well distributed, but they are generally short and confined to steep, narrow canyons. There are no marshes, extensive meadows, or forests, but a few small lakes lie near the head of the river. Numerous small springs and the melting snow which comprises the greater part of the precipitation are the chief sources of suppply. The annual high-water period occurs during May and June, and the stream is not subject to quick floods or freshets.

Just below Dingle the main stream passes through the north end of Bear Lake Valley in a well-defined channel with no overflow, and from this point to Preston it is confined largely to a steep, narrow canyon, with occasional small, narrow valleys containing irrigated farms. The tributaries in this portion of the basin are few, the principal ones being Mink and Cottonwood creeks. About 10 miles below Dingle the outlet to Bear Lake joins the river. This is a small, crooked, sluggish stream, that discharges but little water at any time, though it is the only visible outlet to Bear Lake, which has an area of about 144 square miles.

The total unappropriated flow between Dingle and Preston is used for irrigation. There is no storage on the main stream, but on Mink Creek a number of small storage reservoirs are contemplated or in process of construction, the water to be diverted for the irrigation of lands in the northwest end of Cache Valley.

Between Preston and Collinston the Bear is a sluggish stream, traversing the west side of Cache Valley in a well-defined channel, which during extreme floods overflows slightly and covers a very narrow strip immediately along the river. The principal tributary streams in this portion of the course are Cub Creek and Logan River. The former has its source in the Bear River Range, and drains a rough country composed of limestone with but little overlying soil. The creek is confined to a steep, narrow canyon until it reaches Cache Valley, where it flows sluggishly for about 15 miles through a winding, but well-defined, channel into Bear River. It discharges considerable water into the main stream during flood and winter seasons, but its entire summer flow is used for irrigation in the north end of Cache Valley. A gaging station was maintained during a part of 1900 and 1901 on Cub Creek about 4 miles northeast of Franklin, at the mouth of the canyon, but, owing to unfavorable conditions, it was discontinued.

Logan River enters the Bear about 7 miles above the gaging station at Collinston, a short distance above the point where it leaves Cache Valley and enters the canyon.

Practically the only inflow to the Bear in Cache Valley is from seepage and springs. The lower portions of the valley form an artesian basin containing numerous small, flowing wells. The water table lies very near the surface, and during the early spring the lower lands are largely swamp.

The Bear River Canal Company diverts the entire summer flow of the stream above Collinston onto agricultural lands lying on both sides of the river below Bear River Canyon. This system has a capacity of about 1,000 second-feet, and during the winter and flood seasons a part of the water is used to develop electric power at a point about one-fourth mile above the Collinston station, being returned to the river at Collinston. From 10 to 30 second-feet reach the stream through leaks and as seepage from the diversion canals

wing to the complete control of the stream by irrigation works, the discharge is liable xtreme variation at any period.

BEAR LAKE AT FISHHAVEN, IDAHO.

his station was established October 5, 1903. It is located at Fishhaven, Idaho, on west shore of Bear Lake, about 4 miles north of the Idaho-Utah State line. It is on l used as a summer resort, owned by G. C. Gray, of Montpelier, Idaho, and is immedi- y south of the summer resort known as Nelsons Camp.

. plain staff gage, read when the surface of the lake is calm by John L. Nelson, is driven tically into the bed of the lake 10 feet east of a crib where water from a spring rises he surface. The gage is protected by 2 by 4 inch stakes driven on either side. The ing melts the ice before the regular breaking-up season, the consequence being that the re at this point is comparatively free from ice, while only a few hundred feet away it piled up in great, grinding masses. The gage is referred to bench marks as follows: A wooden hub driven flush with the ground, 1 foot south of a 15-inch cottonwood tree, ot east of a fence on the east side of the county road, 142 feet north of the gage, and ut 18° to the west; elevation above zero of gage, 12.19 feet. (2) A shoulder cut on above-ground root of a 20-inch cottonwood tree, 2 feet southeast of the southeast cor- of the porch of a house on the summer-resort grounds; it bears 81° W., 93 feet south the gage rod; elevation above zero of gage, 7.13 feet. By readings on the lake surface e and at the north end of the lake, October 5, 1903, the elevation of the zero of gage s found to be 12.26 feet by the datum used on canal surveys, etc., during 1903. This vation is probably correct to within 0.05 foot. The elevation above sea level is approxi- tely 6,000 feet.

An extreme high-water mark pointed out by the observer, who has lived here thirty- ee years, indicates that twenty or thirty years ago the surface of the lake stood at proximately gage height 6.5 feet. A more definite mark shows a gage height of 6 feet occurring twenty years ago

Daily gage height, in feet, of Bear Lake at Fishhaven, Idaho, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
									2.7			
	2.5							3.0				
		2.55										
				2.9			3.05			2.4		
			2.7			3.15						1.85
											2.05	
								2.9				
					3.15				2.6			
		2.55										
	2.5									2.3		
			2.7	2.95								
												1.8
								2.8				
						3.15	3.03				2.0	
		2.6										
					3.2							
	2.5											
			2.75	2.1								
									2.5	2.2		
												1.8
		2.65										
							3.03					
				3.05		3.1						
	2.5		2.8		3.25						1.9	

NOTE.—*Lake frozen over from* February 22 to March 17.

BEAR RIVER AT DINGLE, IDAHO.

This station was established May 9, 1903. It is located in a cut made by the Oregon Sh Line Railroad Company one-fourth mile east of the Dingle railroad station and about 1 feet south of the track.

The channel is straight for about 400 feet above and below the station. Both ba are high, are not liable to overflow, and are barren except for small brush. The bed of t stream is of well-compacted small gravel and soil and seems to be permanent. The velo is moderate at ordinary stages, and is well distributed. The stream freezes over late November or early in December, and ordinarily the ice does not begin to break up until lat February. There is no anchor or needle ice at any stage. Winter records at this sta are of special importance, as the object of the station is the collection of facts concern the amount of water available for storage in Bear Lake.

Discharge measurements are made by means of a cable and car of the regular form, length of the span being 151 feet. The cable is marked at 10-foot intervals with white pa The initial point for soundings is the first mark from the north and is 8 feet from the n cable support.

The gage, which is read daily by M. K. Hopkins, was originally of the vertical type, in December, 1905, it was replaced by a new inclined gage, consisting of a 6 by 6 inch fastened to three vertical double posts well embedded in the bank. It is located 3 feet b the old gage and about 25 feet above the cable. The datum of the new gage was mad agree with that of the old one. The gage is referred to bench marks as follows: (1 United States Geological Survey standard metallic post bearing N. 33° 15′ E., 37 feet f as north end of cable; elevation above zero of gage, 15.59 feet; elevation above mean sea l determined from Oregon Short Line Railroad elevations, 6,000 feet. (2) Top of south c post; elevation, 18.04 feet above zero of gage. (3) Top of 4-foot stick of timber pla 2.7 feet in the ground; elevation above zero of gage, 18.42 feet. During the winte 1904–5 gage readings were taken once or twice each week, the surface of the water b read after the ice had been cut around the gage and the thickness of the ice in each case no

Information in regard to this station is contained in the following Water-Supply Pa of the United States Geological Survey:

Description: 100, p 135; 133, p 238.
Discharge: 100, p 135; 138, p 238.
Discharge, monthly: 100, p 137; 133, p 240.
Gage heights: 100, p 136; 133, p 239.
Rating table: 100, p 136; 133, p 240.

Discharge measurements of Bear River at Dingle, Idaho, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis charg
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Secon fee*
February 13 [a]	C. Tanner	92	136	1.43	[b] 4.45	
March 24	W. G. Swendsen	107	210	1.80	4.22	
September 19	do	97	136	.98	3.48	

[a] Stream frozen; ice 1 foot thick near the center and increasing gradually to 1.5 feet at either side. anchor or slush ice.
[b] Surface of water in hole cut in ice.

Daily gage height, in feet, of Bear River at Dingle, Idaho, for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	4.8	.....	.....	4.2	4.2	3.7	3.85	3.35	3.3	3.5	3.55	3.5
.....	4.7	.....	4.8	4.1	4.15	3.95	3.8	3.4	3.3	3.5	3.55	3.5
.....	4.6	4.8	.....	4.1	4.2	4.0	3.75	3.35	3.3	3.5	3.55	3.5
.....	4.6	4.8	4.7	4.1	4.2	3.95	3.75	3.4	3.3	3.5	3.6	3.55
.....	4.4	4.8	.....	4.1	4.2	4.05	3.8	3.4	3.3	3.5	3.55	3.5
.....	4.4	.....	4.45	4.05	4.15	4.2	3.8	3.35	3.4	3.5	3.55	3.5
.....	4.5	.....	4.45	4.0	4.1	4.25	3.65	3.3	3.4	3.5	3.55	4.4
.....	4.5	.....	.....	4.0	4.1	4.5	3.5	3.3	3.4	3.5	3.5	4.4
.....	4.5	.....	4.4	4.1	4.1	4.65	3.4	3.3	3.4	3.5	3.55	4.5
.....	4.5	.....	.....	4.1	4.1	4.6	3.45	3.3	3.4	3.5	3.55	4.25
.....	4.6	4.6	4.4	4.1	4.05	4.6	3.5	3.3	3.4	3.5	3.55	.....
.....	4.6	.....	4.4	4.1	4.05	4.7	3.5	3.3	3.35	.....	3.55	.....
.....	.....	4.45	4.7	4.1	4.0	4.9	3.65	3.3	3.35	3.5	3.5	.....
.....	4.6	4.45	4.4	4.1	4.0	5.0	3.7	3.3	3.35	3.5	3.55	4.35
.....	.....	.....	4.4	4.15	4.0	4.8	3.7	3.3	3.35	3.5	3.55	.....
.....	.....	.....	4.45	4.2	3.9	4.7	3.7	3.3	3.35	3.5	3.55	.....
.....	4.7	.....	4.45	4.2	3.9	4.75	3.65	3.3	3.35	3.5	3.5	4.6
.....	.....	4.45	4.4	4.2	4.0	4.9	3.6	3.3	3.35	3.5	.....	.....
.....	.....	.....	4.4	4.2	3.9	5.05	3.6	3.3	3.45	3.5	3.55	.....
.....	.....	.....	4.4	4.2	3.9	4.95	3.6	3.2	3.5	3.5	3.55	.....
.....	4.7	.....	4.4	4.2	3.9	4.8	3.6	3.2	3.5	3.5	3.5	4.9
.....	.....	4.7	4.3	4.2	3.9	4.65	3.55	3.2	3.5	3.5	3.55	.....
.....	.....	.....	4.3	.....	3.95	4.35	3.5	3.2	3.5	3.5	3.55	.....
.....	4.8	.....	4.2	4.2	3.95	4.2	3.5	3.2	3.5	3.5	3.55	.....
.....	.....	4.7	.....	4.2	3.95	4.1	3.5	3.2	3.5	3.55	3.55	3.8
.....	.....	.....	4.2	4.2	3.9	4.0	3.4	3.2	3.45	3.55	3.55	.....
.....	.....	4.8	4.2	4.2	3.9	3.95	3.4	3.2	3.5	3.55	.....	.....
.....	4.7	.....	4.2	4.2	3.8	4.0	3.35	3.3	3.45	3.55	3.5	3.8
.....	.....	.....	4.2	4.2	3.8	3.95	3.3	3.3	3.5	3.6	3.3	.....
.....	4.8	.....	4.2	4.1	3.8	3.9	3.4	3.3	3.5	3.55	3.2	.....
.....	.....	.....	4.2	.....	3.75	.....	3.35	3.3	.....	3.55	.....	4.0

River frozen January 1 to about March 14 and December 7 to 31. During this period the ere to the water surface in a hole cut in the ice.

owing thicknesses of ice were recorded:

	Thickness in feet.		Thickness in feet.
.....	0.75	February 11.....	1.1
.....	1.0	February 18.....	1.2
1.....	1.2	February 22.....	1.2
1.....	1.2	February 25.....	1.3
3.....	1.2	February 27.....	1.3
4.....	1.1	March 2.....	1.2
5.....	1.1	March 6.....	.7

1, ice nearly gone. March 18, no ice at gage.

Station rating table for Bear River at Dingle, Idaho, from March 11 to December 6, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.10	60	3.90	260	4.70	590	5.50	1,020
3.20	75	4.00	295	4.80	635	5.60	1,085
3.30	90	4.10	330	4.90	685	5.70	1,155
3.40	110	4.20	370	5.00	740	5.80	1,230
3.50	135	4.30	410	5.10	790	5.90	1,300
3.60	160	4.40	455	5.20	840	6.00	1,375
3.70	190	4.50	495	5.30	895	6.10	1,460
3.80	225	4.60	540	5.40	955		

The above table is applicable only for open-channel conditions. It is based on 11 discharge measurements made during 1903–1905. It is well defined between gage heights 3.5 feet and 7.4 feet. Above gage height 6.1 feet the rating curve is a tangent, the difference being 90 per tenth.
The above table is the same as that used for 1904.

Estimated monthly discharge of Bear River at Dingle, Idaho, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	310	180	259	15,930
February	310	195	259	14,380
March	590	180	365	22,440
April	370	295	348	20,710
May	370	208	294	18,080
June	765	190	467	27,790
July	242	90	157	9,654
August	110	75	89	5,472
September	135	90	113	6,724
October	160	135	138	8,486
November	160	75	141	8,390
December 1–6	147	135	137	1,630
The period				179,730

NOTE.—Discharge interpolated for days when the gage was not read.
Estimates for January, February, and March corrected for effect of ice. They are merely approximate.

BEAR RIVER NEAR PRESTON, IDAHO.

This station was established October 11, 1889. It is located about 6 miles from Preston, Idaho, 10 miles north of the Idaho-Utah boundary line and about 300 feet below the county road crossing at the old bridge of the Oregon Short Line Railroad. The data collected at this station are of extreme importance as showing the amount of water that passes from Idaho into Utah and will be of great value in the final adjudication of water rights on the stream.

The channel is straight for about 250 feet above and below the station. Both banks are barren and are sufficiently high to prevent overflow. The bed of the stream is of gravel and clay and is permanent. A light growth of moss near the north side of the gaging section interferes slightly with summer records; otherwise the conditions are good. The stream is ice covered from about the end of December to the middle of February. There is no needle ice and but little fluctuation.

Discharge measurements are made by means of a cable and car, rebuilt in 190[illegible] cable has a span of about 250 feet and is marked at 10-foot intervals with red [illegible] *initial* point for soundings is the north post supporting the cable.

, which is read daily by Mrs. Hannah Nelson, was originally of the vertical onsisted of a board nailed to a pile of the highway bridge. This was replaced 1899, by a wire gage, which proved unsatisfactory, and October 31, 1903, a new gage was again attached to the bridge pile. In December, 1904, a new inclined stablished at a point about 50 feet below the bridge. It consists of a piece of fir, supported by three vertical double posts. The bench mark is a United States Survey standard metallic post, set flush with the surface of the ground at a t 8 feet upstream from the south post supporting the cable; elevation above e, 7.428 feet. All readings have been reduced as nearly as possible to the same

ion in regard to this station is contained in the following publications of the ates Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-per):

n: Ann 14, ii, pp 118–119; 18, iv, p 313; Bull 131, p 53; 140, pp 225; WS 16, p 157; 28, p 146; 3; 51, p 409; 66, p 117; 85, p 82; 100, pp 133–134; 133, p 241.
: Ann 18, iv, p 314; Bull 131, pp 53, 92; 140, p 226; WS 16, p 157; 28, p 153; 35, pp 18–19; 38, p ; 66, p 117; 85, p 83; 100, p 134; 133, p 241.
monthly: Ann 11, ii, p 102; 12, ii, pp 352, 360; 13, iii, p 96; 14, i, p 119; 18, iv, p 315; 19, iv, p 459; 21, iv, p 394; 22, iv, p 407; Bull 140, p 227; WS 75, p 191; 85, p 84; 133, p 243.
yearly: Ann 11, ii, p 69; 13, p 99; 20, iv, p 60.
nts: Bull 131, pp 54–55; 140, p 226; WS 11, p 76; 16, p 157; 28, p 149; 38, p 334; 51, p 410; 66, 3; 100, p 134; 133, p 242.
ohs: Ann 12, ii, p 330; 14, ii, p 118; 18, iv, p 316; 19, iv, p 433; 20, iv, p 460; 22, iv, p 407; 75

oles: Ann 18, iv, p 314; 19, iv, p 432; Bull 131, p 54; 140, p 226; WS 28, p 154; 39, p 452; 52, 76; 85, p 84; 133, p 242.

Discharge measurements of Bear River near Preston, Idaho, in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
...	W. G. Swendsen	188	348	1.78	1.60	617
a..	C. Tanner	197	524	1.46	2.80	766
...	W. G. Swendsen	192	470	2.26	2.15	1,059
...	....do	192	470	2.27	2.15	1,067
...	....do	196	513	2.64	2.45	1,354
...	....do	187	358	1.60	1.45	574
...	....do	152	203	.89	.60	182
...	W. D. Beers	145	216	.82	.60	177
5..	W. G. Swendsen	171	239	1.22	.80	291
...	....do	186	340	1.56	1.43	528

ercaused by a large quantity of floating ice piled up near the gaging station. This rendered zero for 60 feet in the middle of the stream. There was a small amount of ice on the edges n at the gaging station, but none near the gage.

Daily gage height, in feet, of Bear River near Preston, Idaho, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	2.6	1.5	1.5	1.88	2.15	1.7	.....	0.5	0.7	1.0	1.04	
2	2.6	1.5	1.52	1.8	2.33	1.7	.....	.5	.7	1.0	1.04	
3	2.6	1.6	1.55	1.8	2.42	1.62	.....	.5	.7	1.07	1.04	
4	2.6	1.6	1.6	1.8	2.38	1.6	.....	.5	.7	1.18	1.04	
5	2.5	.....	1.6	1.8	2.3	1.63	0.6	.62	.7	1.32	1.04	
6	2.5	1.6	1.68	1.8	2.23	1.53	.62	.5	.7	1.3	1.04	
7	2.45	1.6	1.68	1.8	2.1	1.43	.7	.5	.72	1.3	1.04	
8	2.4	1.6	1.72	1.8	2.1	1.47	.68	.5	.7	1.3	1.04	
9	2.4	1.6	1.78	1.8	2.1	1.4	.63	.5	.7	1.3	1.04	
10	2.4	1.8	1.78	1.8	2.1	1.43	.6	.5	.7	1.3	1.04	
11	2.4	1.9	1.85	1.8	2.05	1.53	.6	.5	.7	1.3	1.04	
12	2.4	.....	1.92	1.8	2.05	1.65	.6	.5	.72	1.3	1.04	
13	2.4	.....	2.0	1.8	2.0	1.67	.6	.5	.8	1.35	1.04	
14	2.4	.....	2.07	1.87	1.95	1.85	.6	.5	.8	1.32	1.04	
15	.....	2.8	2.15	1.9	1.95	1.68	.6	.5	.8	1.22	1.04	
16	3.5	2.72	2.2	1.9	2.0	1.6	.6	.5	.8	1.05	1.04	
17	3.5	2.7	2.15	1.97	2.05	1.72	.6	.5	.8	1.05	1.35	
18	3.5	2.55	2.25	2.02	2.15	1.87	.6	.5	.77	1.04	1.3	
19	1.5	2.57	2.3	2.08	2.15	1.9	.6	.5	.7	1.04	1.3	
20	1.5	2.48	2.27	2.0	2.15	1.9	.6	.5	.8	1.04	1.35	
21	1.5	1.5	2.23	1.95	2.1	1.65	.8	.5	.8	1.04	1.32	
22	1.5	1.5	2.2	1.97	2.07	1.5	.8	.6	.8	1.04	1.3	
23	1.6	1.5	2.12	2.0	2.0	1.42	.8	.75	.8	1.04	1.3	
24	1.6	1.5	2.1	2.0	1.95	1.32	.8	.63	.8	1.04	1.27	
25	.....	1.58	2.05	2.07	1.9	1.25	.75	.7	1.0	1.04	1.25	
26	1.55	1.6	2.07	2.1	1.9	1.2	.7	.67	.95	1.45	1.25	
27	1.5	1.55	2.1	2.05	1.9	1.0	.65	.65	.9	1.45	1.25	
28	1.5	1.52	2.0	2.05	1.9	.....	.6	.7	1.0	1.45	1.25	
29	1.5	.....	2.0	2.05	1.87	.....	.6	.7	1.0	1.45	1.27	
30	1.5	.....	2.0	2.05	1.8	.....	.55	.7	1.0	1.41	1.3	
31	1.5	.....	1.95	.....	1.72	.....	.52	.7	.....	1.41	.....	

NOTE.—River frozen January 1-18 and February 10-20. Ice conditions December 7-31.

Station rating table for Bear River near Preston, Idaho, from January 1 to December 31, 19

Gage height.	Discharge	Gage height.	Discharge.	Gage height	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.50	158	1.10	371	1.60	642	2.10	1,020
.60	186	1.20	418	1.70	708	2.20	1,110
.70	217	1.30	468	1.80	779	2.30	1,205
.80	251	1.40	522	1.90	855	2.40	1,300
.90	288	1.50	580	2.00	935	2.50	1,400
1.00	328						

NOTE.—The above table is applicable only for open-channel conditions. It is based on 15 discha measurements made during 1904–5. It is well defined throughout.

Estimated monthly discharge of Bear River near Preston, Idaho, for 1905.

[Drainage area, 4,500 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
' 19–31	642	580	595	15,340	0.132	0.064
y 1–9; 21–28	642	580	615	20,740	.137	.087
	1,205	580	907	55,770	.202	.233
	1,020	779	871	51,830	.194	.216
	1,320	722	991	60,930	.220	.254
	855	328	599	35,640	.133	.148
	251	164	201	12,360	.045	.052
	234	158	176	10,820	.039	.045
ber	328	217	250	14,880	.056	.062
	551	328	429	26,380	.095	.110
ber	495	346	401	23,860	.089	.099
er 1–6	468	418	443	5,272	.098	.022
ie period				333,800		

NOTE.—Discharge interpolated on days when gage was not read.

BEAR RIVER NEAR COLLINSTON, UTAH.

station was established July 1, 1889. It is located 6 miles from Collinston station Oregon Short Line Railroad, about one-fourth mile below the electric-power plant River Canyon. It is at the lower end of the canyon separating Cache and Great ke valleys, at a point below all diversion from the stream. It shows the amount of opriated water that is discharged as waste into Great Salt Lake.

stream at this point is wide and shallow. Both banks are sufficiently high to prevent r; the west bank slopes gradually, while the east is abrupt. The bed is composed lders and clay and is somewhat rough, but apparently permanent. A deposit of l which was washed into the stream by the water from a spillway at the power plant 1903 changed the original condition considerably during 1903 and 1904. The cross was rechecked, however, in March, 1905, and found to agree very closely with the standard cross section, the new material having been washed out. The velocity from 2 to 4 feet per second. There is a free flow except at a small hole near the east The discharge ranges from 7,000 feet during flood season to nothing during the , when the entire flow is diverted for irrigation above the station. The stream y never freezes entirely over, but ice forms along the edges to quite an extent during ber and January.

large measurements were originally made from a small boat attached by means of a nd pulley to a cable stretched across the stream. During 1904 discharge measure- were made from a bridge recently built across the stream at the power house, but o poor conditions at this point a cable and car were established at the old section in , 1905. The total length of the span is 301 feet. The cable is marked at 20-foot s with paint, beginning at the west post, which is the initial point for soundings.

gage, which is read daily by D. A. Cannon, a watchman along the Bear River canals, d originally of a vertical iron bar driven into the river bed and supported at the top rizontal bar fastened to posts on the bank. It was replaced in February, 1905, by ned gage. This is a 6 by 6 inch fir, fastened by means of iron straps to three posts mbedded in the bank, and graduated to read vertically. It is located at the same the old vertical gage. The low-water gage is an iron peg driven into the bed of am about 50 feet from the west bank. It has the same datum as the regular gage.

The gage is referred to bench marks as follows: (1) A metallic post, 3 inches in di and 4 feet long, set in the ground at a point 30 feet S. 74° W. from the west post supp the cable; elevation, 9.59 feet above zero of gage, and so stamped on the top; (2) in an oak post 20 feet west of the gage and 20 feet north of the cable; elevation gage datum, 7.35 feet.

Information in regard to this station is contained in the following publications United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS= Supply Paper):

Description: Ann 18, iv, p 319; Bull 131, pp 55–56; 140, p 227; WS 16, p 159; 28, p 146; 38, pp 51, p 413; 66, p 120, 85, p 80; 100, p 131; 133, p 433.

Discharge: Ann 18, iv, p 319; Bull 131, pp 90, 92; 140, p 228; WS 16, p 159; 28, p 153; 35, pp 18-336; 51, p 413; 66, p 120; 85, p 80; 100, p 131; 133, p 244.

Discharge, monthly: Ann 11, ii, p 103; 12, ii, pp 352, 360; 13, iii, p 96; 14, ii, pp 120–121; 18, iv 19, iv, p 435; 20, iv, pp 458–460; 21, iv, p 395; 22, iv, p 410; Bull 140, p 229; WS 76, p 193; 85, p 8 133; 133, p 245.

Discharge, yearly: Ann 11, ii, p 69; 13, iii, p 99; 20, iv, p 60.

Gage heights: Bull 131, pp 56–57; 140, p 229; WS 11, p 77; 16, p 159; 28, p 150; 38, p 336; 51, p p 121; 85, p 81; 100, p 132; 133, p 244.

Hydrographs: Ann 12, ii, p 332; 14, ii, p 121; 18, iv, p 320; 19, iv, p 435; 20, iv, p 461; 21, iv, p iv, p 411.

Rainfall and run-off relation: Ann 20, iv, p 459.

Rating tables: Ann 18, iv, p 320; 19, iv, p 434; Bull 140, p 228; WS 28, p 154; 39, p 453; 52, p 52 176; 85, p 81; 100, p 132; 133, p 245.

Discharge measurements of Bear River near Collinston, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	c
		Feet.	*Square feet.*	*Feet per second.*	*Feet*	S
February 10....	C. Tanner	270	486	2.46	1.75	
March 29.....	W. G. Swendsen	275	711	2.73	2.50	
March 29.....	.....do	275	711	2.78	2.50	
May 17.....	.....do	275	684	2.79	2.45	
September 7[a]..	A. B. Larson	19	19	1.64	.37	
October 31.....	W. G. Swendsen	268	466	2.32	1.60	

[a] 350 feet below regular station.

Daily gage height, in feet, of Bear River near Collinston, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.7	1.9	1.95	2.35	2.6	2.25	−0.1	−0.5	−0.5	1.2	1.55	1.4
2	1.8	1.95	1.95	2.3	2.8	2.2	− .1	− .5	− .5	1.2	1.55	1.45
3	1.75	2.0	2.0	2.2	3.1	2.1	− .15	− .5	− .5	1.1	1.55	1.45
4	1.75	2.0	2.0	2.15	3.15	2.1	.....	− .55	− .5	1.1	1.55	1.45
5	1.8	2.0	2.0	2.1	3.0	2.05	− .2	− .55	− .5	1.1	1.55	1.5
6	1.9	2.0	1.95	2.1	2.9	1.95	− .2	− .55	− .5	1.1	1.55	1.45
7	1.8	1.9	1.9	2.1	2.75	1.8	− .25	− .55	.....	1.1	1.6	1.4
8	1.6	1.85	1.95	2.15	2.65	1.6	− .25	− .55	− .4	1.15	1.6	1.3
9	1.75	1.8	1.95	2.2	2.6	1.4	− .3	− .55	− .4	1.15	1.6	1.2
10	1.9	1.75	1.9	2.2	2.6	1.35	− .3	− .55	− .4	1.2	1.6	1.1
11	1.7	1.7	1.9	2.3	2.6	1.3	− .4	− .55	− .4	1.2	1.6	1.0
12	1.7	1.5	1.95	2.3	2.6	1.3	− .4	− .55	− .35	1.2	1.6	1.0
13	1.8	1.3	2.0	2.25	2.6	1.35	− .45	− .5	− .3	1.2	1.6	1.05
14	1.6	1.4	2.1	2.2	2.5	1.4	− .45	− .5	− .3	1.25	1.55	1.05
15	1.6	1.6	2.1	2.3	2.4	1.4	− .45	− .5	+ .3	1.3	1.55	1.1
16	1.65	1.7	2.1	2.3	2.4	1.35	− .5	− .5	.3	1.3	1.55	1.1
17	1.7	1.7	2.1	2.3	2.4	1.3	− .5	− .5	.3	1.3	1.55	1.15
18	1.75	1.7	2.15	2.3	2.5	1.4	− .5	− .55	.3	1.35	1.55	1.15
19	1.75	1.7	2.25	2.4	2.8	1.4	− .5	− .55	.4	1.4	1.5	1.2
20	1.75	1.65	2.5	2.6	2.95	1.45	− .5	− .55	.4	1.45	1.5	1.25
21	1.7	1.65	2.4	2.6	3.0	1.45	− .5	− .55	.4	1.45	1.5	1.25
22	1.75	1.7	2.35	2.55	3.0	1.4	− .5	− .55	.4	1.4	1.45	1.2
23	1.8	1.7	2.35	2.55	2.9	1.35	− .45	− .55	.4	1.45	1.45	1.2
24	1.8	1.8	2.4	2.5	2.85	1.1	− .45	− .5	.35	1.5	1.45	1.25
25	1.85	1.9	2.4	2.45	2.8	.6	− .45	− .5	.3	1.5	1.45	.....
26	1.85	1.9	2.4	2.5	.....	.6	− .45	− .45	.3	1.5	1.45	1.3
27	1.85	1.9	2.5	2.55	.....	.55	− .45	− .45	.35	1.5	1.45	1.35
28	1.85	1.95	2.5	2.6	2.5	.55	− .5	− .5	.7	1.5	1.45	1.4
29	1.9	.....	2.5	2.6	2.55	.55	− .5	− .5	.65	1.5	1.5	1.45
30	1.95	.....	2.4	2.6	2.55	.5	− .5	− .5	.7	1.5	1.5	1.4
31	2.0	.....	2.4	.....	2.4	.....	− .5	− .5	.....	1.6	.....	1.35

Station rating table for Bear River near Collinston, Utah, from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second feet.*	*Feet.*	*Second feet.*	*Feet.*	*Second feet.*	*Feet.*	*Second feet.*
−0.55	10	0.40	266	1.40	868	2.40	1,850
−0.50	15	.50	310	1.50	950	2.50	1,960
−0.40	29	.60	356	1.60	1,035	2.60	2,075
−0.30	47	.70	406	1.70	1,125	2.70	2,190
−0.20	68	.80	460	1.80	1,220	2.80	2,310
−0.10	92	.90	518	1.90	1,320	2.90	2,435
.00	120	1.00	580	2.00	1,420	3.00	2,560
.10	152	1.10	646	2.10	1,525	3.10	2,690
.20	187	1.20	716	2.20	1,630	3.20	2,830
.30	225	1.30	790	2.30	1,740		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–05. It is well defined between gage heights 1.3 feet and 2.5 feet.

Estimated monthly discharge of Bear River near Collinston, Utah, for 1905.

[Drainage area, 6,000 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	1,420	1,035	1,199	73,720	0.200	0.231
February	1,420	790	1,199	66,590	.200	.208
March	1,960	1,320	1,605	98,690	.268	.309
April	2,075	1,525	1,800	107,100	.300	.335
May	2,760	1,850	2,201	135,300	.367	.423
June	1,685	310	895	53,260	.149	.166
July	120	15	36.4	2,238	.0061	.0070
August	22	10	13.0	779	.0022	.0025
September	406	15	158	9,402	.026	.029
October	1,035	646	806	49,560	.134	.154
November	1,035	909	976	58,080	.163	.182
December	950	580	767	47,160	.128	.148
The year	2,760	10	971	701,900	.160	2.17

NOTE.—Discharge interpolated on days when gage was not read. Discharge applied for open channel during winter months.

LOGAN RIVER NEAR LOGAN, UTAH.

Logan River rises on the west slope of the Bear River Range, flows southwest, then northwest, and unites with Bear River near Benson, Utah. The entire basin is rough and rugged, the elevations ranging from 4,500 to 9,000 feet and the stream being confined largely to a steep and rough channel in a comparatively narrow canyon. The principal formation is a compact limestone, with little or no soil except near the summit of the range, where a thin layer supports quite extensive groves of fir and aspen. The lower reaches of the stream are practically barren of timber, except for a few scattered pine and mahogany trees and a rather thick growth of underbrush. A large amount of timber has been cut out and the area has been overgrazed by sheep and cattle. There are no flood basins or marshes in the region. Probably three-fourths of the precipitation in the basin is snow, the melting of which forms the chief source of supply for the spring and early summer flow; the late summer and winter flow is derived chiefly from springs, which are well distributed over the basin. In its upper course the stream has numerous small tributaries, all short and swift. Temple Fork and South Fork, which enter the river about 10 and 15 miles, respectively, above the gaging station, are perennial streams and furnish from one-third to one-fourth of the total flow. Blacksmith Fork comes in below the gaging station. There is no storage on the stream at present. The entire flow, after being utilized to furnish power at two electric plants near the mouth of the canyon, is used for irrigation.

A gaging station was established June 1, 1896, about 2 miles east of the city of Logan, near the mouth of the canyon. It was discontinued July 18, 1903, and reestablished April 13, 1904, at a point along the canyon road about 50 feet below the highway bridge, at the mouth of the canyon, 800 feet below the Hercules power house and about 1,000 feet above the old gaging station.

Th channel is straight for about 150 feet above and 75 feet below the gaging section. The banks are of rock and soil, permanent, and are sufficiently high to prevent overflow. The bed of the stream was originally of bowlders and gravel, well cemented together, very rough, and of such shape that the stream was not well distributed. When the station was reestablished the channel was improved by removing large bowlders and sufficient of the finer material to distribute the flow and render the bed comparatively smooth. During the

lood of 1904 a deposit of bowlders and gravel was made at the section, reducing it to he original conditions, but leaving a loose and probably shifting bed. There is but nnel at all stages. Discharge ranges from about 150 to 1,000 second-feet, with a of from 3 to 7 feet per second. The depth is 1.5 to 3.5 feet. There are no dams or ad the grade of the stream is about uniform. Winter flow is affected but little by ice, tream never freezes over.

arge measurements are made by means of a cable and car of the regular form. The marked at 4-foot intervals with red paint. A guy line is stretched about 25 feet he cable, for use during high water. The initial point for soundings is a 4 by 4 inch t in the west bank and projecting about 4 feet above the ground.

rvations are taken by the Telluride Power Company, under the direction of E. P. manager. The gage is of the vertical type, consisting of a 2 by 2½ inch steel rod, with tream side drawn to an edge. It is driven into the bed of the stream and is supported op by a horizontal 4 by 4 inch fir buried in the bank and fastened to a vertical post e water edge. The bench mark is a United States Geological Survey standard metal-, cemented in a limestone ledge 250 feet N. about 30° W. of the cable. on a prominent ear the north side of a road leading to the power house; elevation, 24.85 feet above gage; elevation above mean sea level, as determined from Oregon Short Line d elevations, 4,502 feet.

mation in regard to this station is contained in the following publications of the States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

ion: Ann 18, iv, pp 316–317; 19, iv, p 433; 20, iv, p 462; 21, iv, p 397; WS 16, p 158; 28, p 146; 38, 51, p 411; 66, p 118; 85, pp 86–87; 100, p 137; 133, p 246.
ge: Ann 18, iv, p 317; WS 16, p 158; 28, p 153; 38, p 335; 51, p 411; 66, p 118; 85, p 87; 100, p 137; 246.
ge, monthly: Ann 18, iv, p 318; 19, iv, p 434; 20, iv, p 462; 21, iv, p 397; 22, iv, p 408; WS 75, p 192; 248.
ge, yearly: Ann 20, iv, p 60.
ghts: WS 11, p 77; 16, p 158; 28, p 150; 38, p 335; 51, p 412; 66, p 119; 100, p 138; 133, pp 247, 248.
aphs: Ann 19, iv, p 434; 20, iv, p 463; 22, iv, p 409.
ables: Ann 18, iv, p 318; 19, iv, p 433; WS 28, p 154; 39, p 453; 52, p 521; 66, p 176; 133, p 247.

Discharge measurements of Logan River near Logan, Utah, in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
22....	W. G. Swendsen	51	49	3.16	4.40	155
y 21...	do	50	49	3.26	4.45	160
l.....	do	51	52	2.57	4.40	134
.....	do	51	58	3.02	4.50	175
.....	do	57	109	5.86	5.61	637
21.....	W. D. Beers	52	56	2.79	4.55	155
24[a]....	do	39	59	2.53	4.48	149
er 14..	W. G. Swendsen	51	50	3.20	4.52	161
29.....	do	51	43	2.89	4.40	124
er 26...	do	51	42	3.02	4.37	126

[a] Measured 300 feet below station.

Daily gage height, in feet, of Logan River near Logan, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	D
1	4.45	4.48	4.4	4.43	4.9	5.5	5.1	4.59	4.5	4.43	4.4	
2	4.4	4.48	4.38	4.41	4.95	5.5	5.05	4.6	4.5	4.43	4.4	
3	4.4	4.53	4.38	4.41	4.9	5.55	5.05	4.57	4.5	4.43	4.4	
4	4.4	.....	4.4	4.41	4.85	5.55	5.05	4.57	4.5	4.4	4.4	
5	4.4	4.5	4.4	4.41	4.75	5.57	5.0	4.57	4.52	4.4	4.4	
6	4.4	4.4	4.4	4.4	4.7	5.58	4.95	4.57	4.52	4.4	4.4	
7	4.4	4.4	4.4	4.45	4.75	5.45	4.9	4.57	4.53	4.4	4.4	
8	4.4	4.4	4.4	4.45	4.8	5.5	4.85	4.57	4.5	4.42	4.4	
9	4.4	4.4	4.42	4.48	4.85	5.5	4.8	4.57	4.48	4.45	4.4	
10	4.4	4.4	4.42	4.46	4.75	5.5	4.75	4.56	4.48	4.45	4.4	
11	4.4	4.4	4.42	4.5	4.8	5.5	4.7	4.56	4.48	4.45	4.4	
12	4.35	4.25	.....	4.47	4.8	5.5	4.7	4.56	4.48	4.43	4.4	
13	4.35	4.28	4.42	4.46	4.8	5.45	4.67	4.56	4.47	4.43	4.4	
14	4.45	4.3	4.42	4.5	4.85	5.45	4.65	4.56	4.47	4.43	4.38	
15	4.43	4.35	4.42	4.45	4.75	5.4	4.65	4.55	4.47	4.43	4.38	
16	4.44	4.38	4.48	4.49	4.85	5.4	4.65	4.55	4.5	4.43	4.38	
17	4.43	4.35	4.48	4.47	4.93	5.35	4.65	4.54	4.45	4.43	4.38	
18	4.43	4.3	4.47	4.48	5.3	5.2	4.65	4.54	4.45	4.45	4.35	
19	4.43	4.35	4.45	4.5	5.3	5.2	4.65	4.55	4.47	4.45	4.35	
20	4.43	4.3	4.47	4.5	5.3	5.1	4.65	4.54	4.47	4.45	4.35	
21	4.43	4.3	4.41	4.55	5.3	5.1	4.65	4.5	4.46	4.43	4.35	
22	4.45	.....	4.45	4.55	5.25	5.07	4.65	4.54	4.45	4.43	4.33	
23	4.45	4.38	4.4	4.65	5.25	5.1	4.65	4.5	4.45	4.42	4.35	
24	4.47	4.4	4.45	4.65	5.2	5.1	4.65	4.48	4.45	4.42	4.35	
25	4.45	4.38	4.43	4.65	5.25	5.1	4.6	4.5	4.48	4.42	4.35	
26	4.45	4.3	.....	4.7	5.3	5.1	4.6	4.5	4.49	4.4	4.32	
27	4.43	4.38	4.42	4.8	5.3	5.1	4.6	4.48	4.47	4.4	4.29	
28	4.43	4.38	4.45	4.8	5.35	5.1	4.6	4.5	4.47	4.4	4.4	
29	4.43	.....	4.45	4.75	5.3	5.1	4.6	4.5	4.47	4.4	4.38	
30	4.43	.....	4.45	4.8	5.3	5.1	4.6	4.45	4.45	4.4	4.3	
31	4.43	.....	4.45	.....	5.35	.....	4.6	4.5	.....	4.4	.....	

NOTE.—Stream does not freeze at this point during winter months in sufficient amount to ma rially affect the rating.

Station rating table for Logan River near Logan, Utah, from April 25, 1904, to December 1905.

Gage height	Discharge	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.30	109	5.00	350	5.70	675	6.40	1,052
4.40	136	5.10	394	5.80	726	6.50	1,108
4.50	164	5.20	438	5.90	779	6.60	1,164
4.60	195	5.30	483	6.00	833	6.70	1,222
4.70	230	5.40	529	6.10	887	6.80	1,280
4.80	268	5.50	577	6.20	941	6.90	1,338
4.90	308	5.60	625	6.30	996		

NOTE.—The above table is applicable only for open-channel conditions. It is based on 21 disc measurements made during 1904–1905. It is fairly well defined between gage heights 4.4 feet an feet.

Estimated monthly discharge of Logan River near Logan, Utah, for 1905.

[Drainage area, 218 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	155	122	142	8,731	0.651	0.750
.....	173	96	131	7,275	.601	.626
.....	157	131	144	8,854	.661	.762
.....	268	139	177	10,530	.812	.906
.....	506	230	368	22,630	1.69	1.95
.....	615	382	496	29,510	2.28	2.54
.....	394	195	248	15,250	1.14	1.31
.....	195	150	176	10,820	.807	.930
.....	173	150	158	9,402	.725	.809
.....	150	136	143	8,793	.656	.756
.....	136	106	129	7,676	.592	.660
.....	136	96	118	7,256	.541	.624
ar.....	615	96	202	146,700	.930	12.62

scharge interpolated on days when gage was not read.

BLACKSMITH FORK NEAR HYRUM, UTAH.

am rises on the western slope of the Bear River Range and flows southwest and west into Logan River. The drainage basin of the tributary is in every way hat of the main stream. Only the flood and winter discharge, however, reaches the entire spring and summer flow being used for irrigation on the tillable lands ;aging station.

ng station was established July 19, 1900, near the tollgate in the mouth of the r Hyrum, Utah, which is the nearest post-office. The station was discontinued 31, 1902, and reestablished May 16, 1904, about 1,000 feet downstream from ; and 800 feet above the Hyrum city electric-power plant. A station is also at the power-plant race.

nel is straight for 200 feet above and 50 feet below the station. The right bank back is a low, wooded flat, subject to overflow during extreme high water; ı point the bank is high and barren. The left bank is wooded and high and does w. The bed of the stream is composed of bowlders and gravel and is somewhat apparently permanent, though a slight change seems to have occurred during 1904. During flood stages the velocity is high, ranging from 4 to 6 feet per der normal conditions it is 2 to 3 feet per second. The discharge varies from) 1,000 second-feet. Ice does not form in sufficient quantity to interfere with at any stage.

e measurements are made by means of a cable and car of regular form. The rked at 4-foot intervals with red paint. A guy line for use during high water across the stream about 30 feet above the cable. The initial point for soundings ı post supporting the cable.

, which is observed daily by Uriah Benson, a farmer living at the tollgate, is of type, and consists of a 2 by 2½ inch iron bar with the upstream side drawn driven into the bed of the stream and supported by a horizontal piece buried t. The gage is referred to bench marks as follows: (1) A United States Geo- ey standard metallic plug, set in a solid limestone ledge about 40 feet east of ost supporting the cable; elevation above zero of gage, 17.875 feet. (2) Top of of the north anchor of the cable; elevation above zero of gage, 9.578 feet.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann = Annual Report; WS = Water-Supply Paper):

Description: WS 51, p 412; 66, p 119; 85, p 84, 133; p 249.
Discharge: WS 51, p 412; 66, p 119; 85, p 85; 133, p 249.
Discharge, monthly: Ann 22, iv, p 409; WS 75, p 192; 85, p 86; 133, p 251.
Gage heights: WS 51, p 413; 66, p 120; 85, p 85; 133, p 250.
Hydrograph: Ann 22, iv, p 410.
Rating tables: WS 52, p 521; 66, p 176; 85, p 86; 133, p 250.

Discharge measurements of Blacksmith Fork near Hyrum, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 23	W. G. Swendsen	38	35	2.26	3.50	79
February 22	do	38	24	2.32	3.50	56
April 16	do	39	44	2.72	3.70	119
May 4	do	41	58	3.18	3.98	185
July 9	do	39	41	2.29	3.60	95
August 22	W. D. Beers	37	39	1.91	3.60	77
October 28	W. G. Swendsen	30	23	1.23	3.30	28
November 27	do	30	23	1.33	3.31	31

Daily gage height, in feet, of Blacksmith Fork near Hyrum, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	3.5	3.5	3.5	3.6	4.0	4.1	3.6	3.6	4.8	3.6	3.3	3.3
2	3.5	3.5	3.5	3.6	4.0	4.1	3.6	3.6	4.8	3.6	3.3	3.3
3	3.5	3.5	3.5	3.6	4.0	4.1	3.6	3.6	4.8	3.6	3.3	3.3
4	3.5	3.5	3.5	3.6	4.0	4.1	3.6	3.6	4.8	3.6	3.3	3.3
5	3.5	3.5	3.5	3.6	4.0	4.1	3.6	3.6	4.8	3.6	3.3	3.3
6	3.4	3.5	3.5	3.6	3.9	3.9	3.6	3.6	4.8	3.6	3.3	3.3
7	3.4	3.5	3.5	3.6	3.9	3.9	3.6	3.6	4.8	3.6	3.3	3.3
8	3.5	3.5	3.5	3.7	3.9	3.9	3.6	3.6	4.8	3.6	3.3	3.3
9	3.5	3.4	3.5	3.7	3.9	3.9	3.6	3.6	4.8	3.6	3.3	3.3
10	3.5	3.4	3.5	3.6	3.9	3.8	3.6	3.6	4.8	3.6	3.3	3.3
11	3.5	3.4	3.5	3.6	3.9	3.8	3.6	3.6	4.8	3.6	3.3	3.2
12	3.5	3.4	3.5	3.6	3.9	3.8	3.6	3.6	4.8	3.6	3.3	3.2
13	3.5	3.4	3.5	3.7	3.9	3.8	3.6	3.6	4.8	3.6	3.3	3.2
14	3.5	3.5	3.5	3.7	3.9	3.8	3.6	3.6	4.8	3.6	3.3	3.2
15	3.5	3.5	3.5	3.7	3.9	3.8	3.6	3.6	3.6	3.6	3.3	3.2
16	3.5	3.5	3.5	3.7	3.9	3.8	3.6	3.6	3.6	3.6	3.3	3.3
17	3.5	3.5	3.5	3.7	3.9	3.8	3.6	3.6	3.6	3.6	3.3	3.3
18	3.5	3.5	3.5	3.7	4.0	3.8	3.6	3.6	3.6	3.6	3.3	3.3
19	3.5	3.5	3.5	3.8	4.0	3.8	3.6	3.6	3.6	3.6	3.3	3.2
20	3.5	3.5	3.5	3.8	4.0	3.8	3.6	3.6	3.6	3.6	3.3	3.2
21	3.5	3.5	3.5	3.8	4.0	3.8	3.6	3.6	3.6	3.6	3.3	3.2
22	3.5	3.5	3.5	3.8	4.0	3.8	3.6	3.6	3.6	3.5	3.3	3.3
23	3.5	3.4	3.6	3.9	4.1	3.8	3.6	3.6	3.6	3.3	3.3	3.3
24	3.5	3.4	3.6	3.9	4.1	3.8	3.6	3.6	3.6	3.3	3.3	3.3
25	3.5	3.4	3.6	4.0	4.1	3.7	3.6	3.6	3.6	3.3	3.3	3.3
26	3.5	3.5	3.6	4.0	4.1	3.7	3.6	3.6	3.6	3.3	3.3	3.3
27	3.5	3.5	3.6	4.0	4.1	3.7	3.6	3.6	3.6	3.3	3.3	3.3
28	3.5	3.5	3.6	4.0	4.1	3.7	3.6	3.6	3.6	3.3	3.3	3.3
29	3.5	.....	3.6	4.0	4.1	3.7	3.6	3.6	3.6	3.3	3.3	3.3
30	3.5	.....	3.6	4.0	4.1	3.7	3.6	3.6	3.6	3.3	3.3	3.3
31	3.5	.....	3.6	.....	4.1	.....	3.6	4.8	.....	3.3	.....	3.3

NOTE.—Stream does not freeze at this point during the winter months in sufficient quantity to materially affect the rating.

y table for Blacksmith Fork near Hyrum, Utah, from January 1 to July 31, 1905.

Discharge.	Gage height.	Discharge.	Gage height	Discharge.	Gage height.	Discharge.
Second-feet	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
64	3.60	98	3.80	140	4.00	190
80	3.70	118	3.90	164	4.10	216

above table is applicable only for open-channel conditions. It is based on five discharge
made during January to July, 1905. It is well defined throughout.

y table for Blacksmith Fork near Hyrum, Utah, from August 1 to December 31, 1905.

Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Second-feet.	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
18	3.70	94	4.10	189	4.50	304
29	3.80	115	4.20	216	4.60	336
42	3.90	138	4.30	244	4.70	369
57	4.00	163	4.40	273	4.80	402
75						

above table is applicable only for open-channel conditions. It is based on three dis-
ements made during August to December, 1905, and the form of the 1904 curve. It is
tween gage heights 3.2 feet and 4 feet.

imated monthly discharge of Blacksmith Fork near Hyrum, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	80	64	79.0	4,858
.....	80	64	75.4	4,188
.....	98	80	85.2	5,239
.....	190	98	132.	7,855
.....	216	164	187.	11,500
.....	216	118	151.	8,985
.....	98	98	98.0	6,026
.....	402	75	85.5	5,257
.....	402	75	228.	13,570
.....	75	29	61.1	3,757
.....	29	29	29.0	1,726
.....	29	18	26.2	1,611
.....	402	18	103	74,570

ve estimates do not represent total flow of river. See Blacksmith Fork power plant
).

SMITH FORK POWER PLANT RACE, NEAR HYRUM, UTAH.

on was established May 16, 1904, for the purpose of ascertaining the amount
erted around the regular gaging station at the tollgate and thus determining
v of the stream at that point. It is located about 600 feet down the canyon
e tollgate at the mouth of the canyon, about 200 feet below the head of the
, and about 500 feet south of the river station.

el is straight for 100 feet above and 200 feet below the station. Both banks
ly high to prevent overflow. The bed of the stream is of gravel and is appar-
ent, except for probable slight changes near the edges. The depth varies
eet and the velocity from 2 to 3 feet per second. Practically no ice forms in
t any time.

Discharge measurements are made from a foot plank placed across the stream and fastened at the ends to pieces of timber buried in the bank. The plank is marked at 1-foot intervals. The initial point for soundings is the north end of the plank, marked zero.

The gage, daily readings of which are made by Uriah Benson, is a 2 by 2½ inch iron bar driven vertically into the bed of the stream, supported at the top by the plank from which the measurements are made, and graduated by means of punch holes. The bench mark is a point on a projecting rock on the southeast corner of a rock house about 400 feet northwest from the station. It is marked with red paint. Elevation above zero of gage, 8.845 feet.

A description of this station, gage height, and discharge data and rating table are contained in Water-Supply Paper No. 133 of the United States Geological Survey, pp. 251-253.

Discharge measurements of Blacksmith Fork power plant race, near Hyrum, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 23	W. G. Swendsen	12.0	23	2.55	4.50	58
October 28	do	13.5	28	3.02	4.90	85

Daily gage height, in feet, of Blacksmith Fork power plant race near Hyrum, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	4.5	4.5	4.5	4.5	4.5	4.6	4.6	4.6	.....	4.4	4.9	4.9
2	4.5	4.5	4.5	4.5	4.5	4.6	4.6	4.6	.....	4.4	4.9	4.9
3	4.5	4.5	4.6	4.5	4.5	4.6	4.6	4.6	.....	4.4	4.9	4.9
4	4.45	4.5	4.6	4.5	4.5	4.6	4.6	4.6	.....	4.4	4.9	4.9
5	4.45	4.5	4.5	4.5	4.5	4.6	4.6	4.6	.....	4.4	4.9	4.9
6	4.45	4.5	4.5	4.6	4.5	4.6	4.6	4.6	.....	4.4	4.9	4.9
7	4.45	4.5	4.5	4.6	4.4	4.6	4.6	4.6	.....	4.4	4.9	4.9
8	4.45	4.5	4.5	4.6	4.4	4.6	4.6	4.6	.....	4.4	4.9	4.9
9	4.45	4.4	4.5	4.6	4.4	4.6	4.6	4.6	.....	4.4	4.9	4.9
10	4.5	4.4	4.5	4.6	4.4	4.5	4.6	4.6	.....	4.4	4.9	4.9
11	4.5	4.4	4.5	4.6	4.4	4.5	4.6	4.6	.....	4.4	4.9	4.5
12	4.5	4.4	4.5	4.6	4.4	4.5	4.6	4.6	.....	4.4	4.9	4.5
13	4.5	4.4	4.5	4.6	4.4	4.5	4.6	4.6	.....	4.4	4.9	4.5
14	4.5	4.5	4.5	4.6	4.4	4.5	4.6	4.6	.....	4.4	4.9	4.5
15	4.5	4.5	4.5	4.7	4.4	4.5	4.6	4.6	4.5	4.4	4.9	4.6
16	4.5	4.5	4.5	4.7	4.4	4.4	4.6	4.6	4.5	4.4	4.9	4.7
17	4.5	4.45	4.5	4.7	4.4	4.4	4.6	4.6	4.5	4.4	4.9	4.6
18	4.5	4.45	4.5	4.7	4.5	4.4	4.6	4.6	4.4	4.4	4.9	4.6
19	4.5	4.45	4.5	4.8	4.5	4.4	4.6	4.5	4.4	4.4	4.9	4.5
20	4.5	4.45	4.5	4.8	4.5	4.4	4.6	4.5	4.4	4.4	4.9	4.5
21	4.5	4.45	4.5	4.8	4.5	4.4	4.6	4.5	4.4	4.4	4.9	4.5
22	4.5	4.45	4.5	4.8	4.5	4.4	4.6	4.5	4.4	4.7	4.9	4.6
23	4.5	4.45	4.6	4.5	4.5	4.4	4.6	4.4	4.4	4.9	4.9	4.6
24	4.5	4.45	4.6	4.5	4.6	4.4	4.6	4.4	4.4	4.9	4.9	4.7
25	4.5	4.45	4.6	4.5	4.6	4.6	4.6	4.4	4.4	4.9	4.9	4.7
26	4.5	4.45	4.6	4.5	4.6	4.6	4.6	4.3	4.4	4.9	4.9	4.7
27	4.5	4.45	4.6	4.5	4.6	4.6	4.6	4.3	4.4	4.9	4.9	4.8
28	4.5	4.5	4.5	4.5	4.6	4.6	4.6	4.3	4.4	4.9	4.9	4.8
29	4.5	.....	4.5	4.5	4.6	4.6	4.6	4.3	4.4	4.9	4.9	4.8
30	4.5	.....	4.5	4.5	4.6	4.6	4.6	4.3	4.4	4.9	4.9	4.8
31	4.5	.....	4.5	.....	4.6	.....	4.6	.....	.....	4.9	.....	4.8

NOTE.—Flow not materially affected by ice conditions.

Station rating table for Blacksmith Fork power plant race near Hyrum, Utah, from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.30	44	4.50	58	4.70	73	4.90	88
4.40	51	4.60	66	4.80	80		

NOTE.—The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during 1904-5. It is fairly well defined.

Estimated monthly discharge of Blacksmith Fork power plant race near Hyrum, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	58	54	57.2	3,517
February	58	51	55.2	3,066
March	66	58	59.8	3,677
April	80	58	65.3	3,886
May	66	51	57.6	3,542
June	66	51	59.9	3,564
July	66	66	66.0	4,058
August 1-30	66	44	59.8	3,558
September 15-30	58	51	52.3	1,659
October	88	51	62.5	3,843
November	88	88	88.0	5,236
December	88	58	74.5	4,581
The year	88	51	63.2	44,190

WEBER RIVER BASIN.

DESCRIPTION OF BASIN.

Weber River rises on the northern slope of the Uinta Mountains and flows in a tortuous course northwestward into Great Salt Lake.

The upper portion of the basin is very rough. The highest peaks, reaching an elevation of about 13,000 feet, are masses of sandstone and quartzite, entirely barren of vegetation and covered with snow for almost the entire year. Farther down the prevailing formation is limestone, overlain with sandstone and conglomerate. A thin layer of soil covers the basin in patches and supports small groves of fir and aspen. There are no extensive forests, meadows, or marshes. The greater part of the precipitation is in the form of snow, the melting of which is the chief source of the spring flood and early summer flow. A large part of the normal flow is derived from springs, which are well distributed over the area. Numerous tributaries, all short and confined to steep, narrow canyons, enter all along the course.

Between Oakley and Croyden the river traverses a very narrow valley comprising irrigated farms. The principal formation over this area is of conglomerate and sandstone, with but little loose and porous overlying soil except near the stream bed, where the deposit of bowlders and soil ranges from 10 to 20 feet in depth. The chief tributaries in this stretch of the river are Beaver Creek, which enters from the south about 6 miles below Oakley and drains a rough country about 71 square miles in extent; Chalk Creek, from the east, which drains a rough, dry country, about 248 square miles in area, and enters the Weber 15 miles above Croyden; and Lost Creek, which comes in from the east at a point about one-half

mile above the Devils Slide gaging station and has a watershed of 205 square mile. ing stations are maintained near the mouth of Chalk and Lost creeks.

Between Croyden and Plain City the stream flows in a well-defined channel thr comparatively narrow, steep canyon, with occasional stretches of narrow valley con irrigated farming lands. The rock is a porous and badly fissured sandstone and cong ate, with but little overlying soil. Near the mouth of the canyon the material is rough but compact limestone. East Creek, which enters near Morgan, discharges l water into the river, as its flow is completely controlled by a storage reservoir about above its mouth, the water being used for irrigation in the Morgan Valley, throug the Weber flows. After leaving the Wasatch Range the Weber enters the Great Sa Valley, through which it flows in a well-defined channel with no overflow.

Ogden River joins the Weber about 8 miles above Plain City. It drains a ro rugged limestone area, 363 square miles in extent, in the western slopes of the W Range. The main stream and its numerous short tributaries are confined to steep canyons. The entire normal flow of the stream is diverted for irrigation near the the canyon about 3 miles above the mouth of the river, after being used for the d ment of power by the Utah Light and Railway Company. The flood and wint therefore, is all that reaches the Weber, except for a small amount of seepage fr irrigated district. The city of Ogden also derives its water supply from Ogden Ri

There are at present no storage reservoirs on the Weber, but a number of pos exist.

WEBER RIVER NEAR OAKLEY, UTAH.

This station was established October 22, 1904. It is located approximately south of the main canyon road, about 3 miles above Oakley, Utah, and is above a sions to the Kamas prairie region. The object of the station is to determine the of water available for diversion through the low Kamas Pass into Provo River, a part of the reclamation scheme in the development of the Weber River project.

Except for a slight depression, which probably carries a small amount of wate extreme floods, there is but one channel at all stages. The right bank for about from the main channel is a low, wooded bottom, and is liable to overflow at extre water; the left bank is high and wooded. The bed of the stream, which is comp large bowlders, gravel, and soil, is very rough, but thus far has been found to be per Ice forms during December and January to a sufficient extent to render open-channe useless. The flow, which ranges from about 75 to 1,000 second-feet, reaches a ma during May and a minimum during the winter months. The velocity ranges from feet per second.

Discharge measurements are made by means of a cable and car. The cable is ma 4-foot intervals with paint, the anchor bolt which supports the cable on the left ban the initial point. A guy line stretched across the stream about 40 feet above the section is found useful at all stages.

The gage, which is read daily by John Franson, a farmer, is of the inclined ty consists of three sections of 2-foot by one-half inch iron, fastened to the solid li ledge by means of bolts set in cement. It is graduated with chisel marks and paint vertically. The bench mark is a United States Geological Survey standard metall set in the ledge 0.5 foot from the anchor bol used as initial point for soundings: el above zero of gage, 14.79 feet.

A description of this station and gage height and discharge data are contained in Supply Paper No. 133 of the United States Geological Survey, pp. 253–254.

Discharge measurements of Weber River near Oakley, Utah, in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
W. G. Swendsen	41	55	1.13	4.10	63
do	41	55	1.17	4.10	65
do	47	91	2.65	4.92	243
do	51	137	5.75	6.00	787
do	49	116	3.34	5.30	389
C. Tanner	42	57	1.26	4.20	72
W. D. Beers	42	62	1.10	4.18	68

Daily gage height, in feet, of Weber River near Oakley, Utah, for 1905.

Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	4.05	4.1	4.15	4.95	6.0	5.0	4.3	4.05	4.35	4.15	4.05
.....	.....	.....	4.15	5.05	6.15	4.95	4.3	4.05	4.3	4.15	4.0
.....	.....	.....	4.2	5.05	6.3	4.9	4.3	4.05	4.3	4.15	4.0
5.4	.....	.....	4.25	4.9	6.4	.....	4.3	4.05	4.25	4.15	4.0
.....	.....	.....	4.3	4.8	6.45	4.8	4.3	4.05	4.25	4.15	.....
.....	.....	.....	4.35	4.7	6.5	4.75	4.3	4.05	4.2	4.15	4.1
.....	.....	.....	4.35	4.75	6.6	4.75	4.3	4.1	4.2	4.15	4.2
.....	4.05	.....	4.4	4.8	7.0	4.7	4.2	4.1	4.2	4.1	.....
.....	.....	4.1	4.4	4.8	6.8	4.7	4.2	4.1	4.2	4.1	4.8
.....	.....	4.1	4.35	4.75	6.3	4.7	4.2	4.1	4.2	4.1	.....
4.7	.....	4.1	4.3	4.7	6.25	4.65	4.2	4.1	4.2	4.1	.....
.....	.....	4.15	4.3	4.7	6.3	4.65	4.2	4.1	4.2	4.1	.....
.....	.....	4.15	4.3	4.7	6.3	4.6	4.2	4.1	4.2	4.1	5.15
.....	.....	4.15	4.3	4.7	6.3	4.6	4.2	4.1	4.2	4.1	.....
.....	5.1	4.15	4.35	4.7	6.25	4.65	4.15	4.1	4.2	4.1	.....
.....	.....	4.15	4.35	4.8	6.0	.....	4.15	4.1	4.2	4.1	4.6
.....	.....	4.15	4.35	5.0	5.9	4.55	4.15	4.1	4.2	4.1	.....
4.5	.....	4.2	4.4	5.2	5.7	4.55	4.15	4.1	4.2	4.1	.....
.....	.....	4.2	4.45	5.3	5.7	4.55	4.15	4.1	4.2	4.1	.....
.....	.....	4.2	4.45	5.35	5.8	4.5	4.15	4.1	4.2	4.1	4.75
.....	.....	4.2	4.45	5.4	5.75	4.5	4.15	4.1	4.2	4.1	.....
.....	4.3	4.2	4.45	5.65	5.75	4.5	4.1	4.1	4.2	4.1	.....
.....	.....	4.15	4.55	5.7	5.7	4.5	4.1	4.1	4.2	4.1	4.85
.....	.....	4.15	4.6	5.7	5.6	4.45	4.1	4.1	4.15	4.1	.....
4.05	.....	4.15	4.65	5.7	5.55	4.4	4.1	4.1	4.15	4.1	.....
.....	.....	4.15	4.75	5.75	5.4	4.35	4.1	4.1	4.1	4.1	.....
.....	.....	4.15	4.8	5.75	5.35	4.35	4.1	4.1	4.1	4.1	5.25
.....	.....	4.15	4.85	5.75	5.35	4.3	4.1	.....	4.1	4.1	.....
.....	.....	4.15	4.9	5.8	5.2	4.3	4.1	4.2	4.15	4.1	.....
.....	.....	4.15	4.9	5.85	5.1	4.3	4.1	4.35	4.15	4.1	5.1
.....	.....	4.15	.....	5.85	.....	4.3	4.1	.....	4.15	.....	.....

conditions January, February, and December noted on observer's records as follows:
ce at banks; river open in the center.
ice 1 foot thick at banks; 0.5 foot thick in the center.
ice broken up.
river clear.
river clear.
ice at banks; river open in the center.
, ice 0.5 foot thick at banks; 0.25 foot thick in the center.
, ice broken up.

March 1, river clear.
December 2, ice 0.3 foot thick at banks.
The following thicknesses of ice were recorded during December:

	Feet.		Feet.
December 9	0.7	December 23	0.7
December 13	.5	December 27	.8
December 16	.6	December 30	1.15
December 20	.6		

Observer reports no anchor ice during December.
Gage readings during December are to the surface of the water in a hole cut in the ice.

Station rating table for Weber River near Oakley, Utah, from October 23, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.00	46	4.80	209	5.60	542	6.40	1,066
4.10	58	4.90	241	5.70	597	6.50	1,145
4.20	73	5.00	275	5.80	655	6.60	1,227
4.30	90	5.10	312	5.90	716	6.70	1,312
4.40	109	5.20	352	6.00	780	6.80	1,400
4.50	130	5.30	395	6.10	847	6.90	1,490
4.60	154	5.40	441	6.20	917	7.00	1,580
4.70	180	5.50	490	6.30	990		

NOTE.—The above table is applicable only for open-channel conditions. It is based on eight discharge measurements made during 1904–5. It is well defined between gage heights 4 feet and 6 feet.

Estimated monthly discharge of Weber River near Oakley, Utah, for 1904 and 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
1904.				
October 23–31	82	82	82.0	1,464
November 1–26	100	66	72.1	3,718
1905.				
March	73	58	64.3	3,954
April	241	66	124	7,379
May	686	180	372	22,870
June	1,580	312	808	48,080
July	275	90	156	9,592
August	90	58	70.4	4,329
September	100	52	58.9	3,505
October	100	58	73.0	4,488
November	66	58	59.9	3,564
The period (1905)				107,900

NOTE.—Ice conditions November 27, 1904, to February 28, 1905, and December 2–31, 1905. Discharge interpolated on days when gage was not read.

WEBER RIVER NEAR CROYDEN, UTAH.

This station was established February 1, 1905. It is located about 1½ miles west of the town of Croyden, one-fourth mile below the junction of Lost Creek and Weber River, about three-fourths mile up the river from Croyden station on the Union Pacific Railroad, and 10 miles down the river from the town of Echo, just below the narrow canyon at the lower end of Henefer Valley.

The station is important as showing the amount of water available for storage in the Weber basin, about 2 miles above the station, the development of which is a part of the irrigation scheme on the Weber River project. The winter records will be of special value, since the entire winter flow of the stream is at present discharged as waste into Great Salt Lake.

The channel is straight for about 1,000 feet above and 700 feet below the station. Both banks are sloping and sufficiently high to prevent overflow. The bed of the stream is of gravel, compact gravel and soil and is smooth and permanent. The velocity is moderate and uniform. The stream is shallow, especially during low water, the depth seldom exceeding 3 feet. There is a free flow, no obstruction to gage readings or discharge measurements existing. Information as to winter conditions is as yet rather indefinite. Discharge measurements are made by means of a cable and car. The cable is marked at 5-foot intervals, the west face of a tree to which the east end of the cable is attached being the initial points for soundings.

The gage, which is read daily by Isaiah Stewart, a farmer who lives about 300 feet from the station, is an inclined piece of 4 by 4 inch fir, fastened to vertical posts near the water's edge and to a large cottonwood tree on the right bank about 75 feet above the cable. It is graduated to read vertically. The gage is referred to bench marks as follows: (1) A 3-inch metal post set 3½ feet in the ground on the bank 20 feet north from the gage; elevation above datum of gage, 8.41 feet; (2) a 30-penny nail driven in the tree which supports the upper end of the gage; elevation above gage datum, 7.87 feet.

Results of discharge measurements at this station are contained in Water-Supply Paper No. 133 of the United States Geological Survey, page 364.

Discharge measurements of Weber River near Croydon, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 31 [a]	W. G. Swendsen	90	95	2.04	1.90	193
March 7	do	95	126	2.67	2.22	337
May 2	do	102	192	3.73	2.85	703
June 17	do	100	213	4.10	3.05	875
June 28	do	91	113	2.45	2.10	277
August 19	W. D. Beers	89	56	.92	1.40	51
November 16	W. G. Swendsen	91	88	1.76	1.75	155

[a] Measurement made by wading.

Daily gage height, in feet, of Weber River near Croydon, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	1.95	1.95	1.95	2.65	2.85	1.9	1.4	1.4	1.65	1.8	1.8
2	.....	1.95	1.95	2.0	2.8	3.0	1.9	1.4	1.4	1.65	1.8	1.8
3	.....	1.95	2.0	2.0	2.75	3.1	1.85	1.4	1.45	1.65	1.8	1.8
4	.....	1.95	2.1	1.95	2.6	3.55	1.8	1.4	1.45	1.6	1.8	1.8
5	.....	1.9	2.2	1.95	2.6	3.6	1.75	1.4	1.5	1.6	1.8	1.7
6	.....	1.9	2.1	1.95	2.55	3.35	1.7	1.4	1.5	1.6	1.8	1.6
7	.....	1.9	2.2	1.95	2.5	3.3	1.65	1.4	1.5	1.6	1.8	1.6
8	.....	1.9	2.1	1.95	2.45	3.9	1.6	1.4	1.5	1.6	1.8	1.7
9	.....	1.85	2.1	1.95	2.5	3.9	1.55	1.4	1.5	1.6	1.8	1.7
10	.....	1.8	2.1	2.2	2.5	3.9	1.5	1.4	1.5	1.6	1.8	1.7
11	.....	1.8	2.1	2.3	2.4	3.4	1.5	1.5	1.5	1.6	1.8	1.6
12	.....	1.65	2.1	2.25	2.4	3.4	1.5	1.5	1.5	1.6	1.75	1.6
13	.....	1.65	2.05	2.2	2.4	3.4	1.5	1.5	1.5	1.6	1.75	1.6
14	.....	1.65	2.05	2.15	2.35	3.45	1.5	1 4	1 5	1.6	1.75	1.6
15	.....	1.65	2.0	2.15	2.3	3.5	1.5	1.4	1.5	1.6	1.75	1.6
16	.....	1.65	2.0	2.2	2.3	3.5	1.5	1.4	1.5	1.6	1.75	1.65
17	.....	1.8	1.95	2.25	2.3	3.0	1.55	1.4	1.5	1.6	1.8	1.6
18	.....	1.8	2.0	2.3	2.4	2.9	1.75	1.4	1.5	1.6	1.8	1.6
19	.....	1.8	2.1	2.3	2.6	2.8	1.9	1.4	1.5	1.6	1.8	1.6
20	.....	1.8	2.05	2.4	2.7	2.7	1.9	1.4	1.5	1.6	1.8	1.6
21	.....	1.8	2.0	2.6	2.8	2.7	1.9	1.4	1.5	1.6	1.8	1.6
22	.....	1.8	1.95	2.4	2.95	2.65	1.9	1.4	1.5	1.7	1.85	1.5
23	.....	1.9	1.9	2.2	2.95	2.6	1.8	1.4	1.5	1.75	1.8	1.6
24	.....	1.9	1.95	2.3	2.95	2.6	1.8	1.4	1.5	1.75	1.8	1.5
25	.....	1.95	2.0	2.3	2.9	2.4	1.8	1.4	1.5	1.75	1.8	1.6
26	.....	1.95	2.0	2.4	2.85	2.3	1.6	1.4	1.5	1.75	1.75	1.7
27	.....	1.95	2.0	2.6	2.85	2.2	1.5	1.4	1.5	1.75	1.8	1.6
28	.....	1.95	2.0	2.7	2.8	2.0	1.45	1.4	1.5	1.75	1.8	1.6
29	.....	.....	2.0	2.6	2.8	2.0	1.4	1.4	1.55	1.75	1.8	1.6
30	.....	.....	2.0	2.6	2.75	1.95	1.4	1.4	1.7	1.8	1.75	1.6
31	1.9	.....	1.95	.....	2.75	.....	1.4	1.4	.....	1.8	.....	1.6

NOTE.—Narrow strip of ice along edges during part of the winter months, but not enough to materially affect the flow.

Station rating table for Weber River near Croydon, Utah, from January 31 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.40	50	2.10	274	2.80	673	3.40	1,160
1.50	73	2.20	319	2.90	745	3.50	1,250
1.60	99	2.30	368	3.00	820	3.60	1,345
1.70	128	2.40	422	3.10	900	3.70	1,445
1.80	160	2.50	480	3.20	985	3.80	1,545
1.90	195	2.60	541	3.30	1,070	3.90	1,650
2.00	233	2.70	605				

NOTE.—The above table is applicable only for open channel conditions. It is based on seven discharge measurements made during 1905. It is well defined between gage heights 1.4 feet and 3.1 feet.

Estimated monthly discharge of Weber River near Croydon, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
ebruary	214	114	175	9,719
arch	319	135	246	15,130
pril	605	214	346	20,590
ay	782	368	574	35,290
ne	1,650	214	876	52,130
ly	195	50	119	7,317
ugust	73	50	52.2	3,210
ptember	128	50	73	4,344
tober	160	99	115	7,071
vember	178	144	157	9,342
cember	178	73	112	6,887
The period				171,000

NOTE.—See note to gage-height table, p. 40.

WEBER RIVER NEAR PLAIN CITY, UTAH.

This station was established in 1903 by the State of Utah, under the direction of the ate engineer, and was maintained under his direction until May 14, 1905, when it was ken up by the United States Geological Survey with the stipulation that the expense of ily gage readings should be defrayed by the State. It is located at the Plain City and est Weber highway bridge, about 10 miles west of Ogden, on the main road leading to lain City and West Weber, below all points of diversion from and inflow to the stream. The station is important as showing the amount of water discharged by the stream into reat Salt Lake, information necessary to the adjudication of water rights on the Ogden id Weber rivers.

Both banks are abrupt and sufficiently high to prevent overflow. The bed of the stream composed of clay, sand, and gravel and is comparatively smooth, but it is liable to shift uring flood seasons. At normal stages the stream is sluggish, but at high water the veloc- y ranges from 2 to 3.5 feet per second. The discharge at this point may vary from 5,500 cond-feet during the spring flood to almost nothing during summer, when the entire flow diverted above for irrigation, that passing the station being merely seepage from the rigated lands tributary to the stream. Information as to ice conditions is as yet indefinite.

Discharge measurements are made from the upstream side of the bridge, which is a two- an steel truss structure, with a center pier of two metallic cylindrical caissons 4 feet in ameter and filled with concrete. The floor railing of the bridge is marked at 5-foot tervals, beginning at a zero mark which is coincident with the north face of the south outment, this being the initial point for soundings.

The upstream face of the center bridge pier is graduated to feet and tenths, marked with hite paint, and forms the gage, which is read daily by David O. Wadman. No bench arks have yet been established.

Discharge measurements of Weber River near Plain City, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
ay 13	C. Tanner	127	564	2.45	8.30	1,382
ay 18	W. G. Swendsen	132	789	2.40	9.30	1,894
eptember 8[a]	A. B. Larson	19	5.1	.92	2.80	4.7
ovember 17	W. G. Swendsen	105	110	1.04	4.00	115

[a] Measurement made 100 feet below station.

Daily gage height, in feet, of Weber River near Plain City, Utah, for 1905.

Day.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	6.5	3.2	2.8	2.8	3.2	4.1	4
2	.....	6.7	3.1	2.8	2.8	3.3	4.2	4
3	.....	6.7	3.0	2.8	2.8	3.3	4.2	4
4	.....	6.6	3.0	2.8	2.8	3.4	4.2	
5	.....	6.8	3.0	2.8	2.8	3.3	4.2	
6	.....	6.6	3.0	2.8	2.8	3.2	4.2	
7	.....	6.4	2.9	2.8	2.8	3.1	4.2	
8	.....	6.1	2.9	2.8	2.8	3.2	4.2	
9	.....	6.8	2.9	2.8	2.8	3.2	4.2	
10	.....	7.4	2.9	2.8	2.8	3.3	4.2	
11	.....	6.8	2.9	2.8	2.8	3.3	4.2	
12	.....	6.6	3.0	2.8	2.8	3.2	4.2	
13	8.3	6.4	3.0	2.8	2.8	3.1	4.2	
14	8.3	6.2	2.9	2.8	2.8	3.1	4.1	
15	8.2	6.0	2.8	2.8	2.8	3.1	4.1	
16	8.3	5.9	2.8	2.8	2.8	3.2	4.1	
17	8.6	6.0	2.8	2.8	2.9	3.2	4.1	
18	9.1	6.1	2.8	2.8	2.9	3.2	4.1	
19	9.8	5.9	2.8	2.8	3.2	3.3	4.1	
20	9.8	5.6	2.8	2.8	3.2	3.3	4.1	
21	10.1	5.0	2.8	2.8	3.2	3.4	4.1	
22	9.8	5.0	2.8	2.8	3.1	3.4	4.2	
23	9.4	5.1	2.8	2.8	3.1	3.5	4.2	
24	9.0	4.9	2.8	2.8	3.1	3.5	4.3	
25	8.4	4.5	2.8	2.8	3.2	3.6	4.4	
26	8.0	4.3	2.8	2.8	3.2	3.7	4.5	
27	8.0	4.0	2.8	2.8	3.2	3.7	4.5	
28	7.9	3.4	2.8	2.8	3.2	3.8	4.5	
29	7.9	3.0	2.8	2.8	3.2	3.9	4.5	
30	7.4	3.0	2.8	2.8	3.2	4.0	4.5	
31	7.0	.....	2.8	2.8	.....	4.1	.....	

NOTE.—Stream probably frozen after December 17.

Station rating table for Weber River near Plain City, Utah, from May 13 to December 31, 19

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.80	5	4.30	158	5.80	483	7.40	1,007
2.90	8	4.40	174	5.90	511	7.60	1,088
3.00	13	4.50	191	6.00	540	7.80	1,173
3.10	19	4.60	209	6.10	569	8.00	1,260
3.20	26	4.70	228	6.20	599	8.20	1,348
3.30	34	4.80	248	6.30	629	8.40	1,438
3.40	43	4.90	269	6.40	660	8.60	1,530
3.50	53	5.00	290	6.50	691	8.80	1,624
3.60	64	5.10	312	6.60	723	9.00	1,720
3.70	76	5.20	334	6.70	755	9.20	1,817
3.80	88	5.30	357	6.80	788	9.40	1,916
3.90	101	5.40	381	6.90	822	9.60	2,016
4.00	115	5.50	405	7.00	857	9.80	2,117
4.10	129	5.60	430	7.20	930	10.00	2,220
4.20	143	5.70	456				

The above table is applicable only for open-channel conditions. It is based on four discharge m urements made during 1905 and the form of the 1903–4 curve. It is well defined.

Estimated monthly discharge of Weber River near Plain City, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
ıy 13-31	2,272	857	1,544	58,190
ne	1,007	13	501	29,810
y	26	5	8.3	510
gust	5	5	5.0	307
tember	26	5	12.9	768
ober	129	19	45.4	2,792
vember	191	129	148	8,807
ember 1-17	248	191	208	7,014
The period				108,100

LOST CREEK NEAR CROYDEN, UTAH.

ost Creek, which enters Weber River near the town of Croyden, drains an area of 205 are miles. The basin is generally rough and barren, the rocks being conglomerate and dstone, with a few outcropping ledges of loose, porous limestone and but a thin layer soil. The stream flows for the most part in a narrow canyon, with occasional small s devoted to irrigated farms. Near the head the creek receives numerous tributaries, short and confined to steep, narrow canyons. The normal flow comes principally from ings, well distributed over the entire watershed, but the spring flood is caused by the lting of snow, which forms the greater part of the precipitation. There are no forests, mps, or meadows along the stream. A few undeveloped storage sites exist in the upper tion of the basin.

he station was established February 3, 1905. It is located about 150 feet above the ction of Lost Creek with Weber River, about 10 miles down Weber River from Echo, l about 1¼ miles west of the town of Croyden on the main road up Lost Creek. The a derived are of value in connection with the amount of water to be diverted into the nefer reservoir.

he channel is slightly curved for about 100 feet above and 75 feet below the station. right bank is steep and high; the left bank is sloping and near the channel is suffi- ıtly high to prevent overflow, but about 50 feet back there is an old channel, originally upied by the stream, which may contain some water during extreme floods. The bed he creek is composed of gravel and sand and is liable to shift at flood stages. A slight e in the bed about 20 feet below the gage causes a small riffle. The velocity is mod- te and fairly uniform.

Discharge measurements are made by wading. The section is located about 20 feet ve the gage and is marked by a 4 by 4 inch by 2-foot stake, the initial point for sound- s, driven into the right bank about 6 feet from the edge.

The gage, which is read daily by Isaiah Stewart, a farmer, is an inclined 4 by 4 inch by foot piece of Oregon fir, fastened to vertical posts embedded in the right bank. As bank is composed of loose gravel and sand the permanency of the gage is uncertain. e bench mark is a 3-inch metallic post, set 3½ feet in the ground at a point 50 feet north st of the gage and 15 feet northwest of the initial stake; elevation above gage datum 1 feet.

Discharge measurements of Lost Creek near Croyden, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
February 2	W. G. Swendsen	30	24	1.00	2.85	24
May 2 [a]	do	27	72	2.53	3.50	183
June 28	do	26	15	1.00	2.68	15
August 19	W. D. Beers	20	12	.82	2.60	10

[a] Gaging made at bridge.

Daily gage height, in feet, of Lost Creek near Croyden, Utah, for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	2.85	2.85	3.4	2.75	2.7	2.6	2.6	2.55	2.55	2.6
2	2.85	2.85	2.85	3.5	2.75	2.7	2.6	2.6	2.55	2.55	2.65
3	2.85	2.85	2.85	3.45	2.75	2.7	2.6	2.6	2.55	2.55	2.65
4	2.85	2.85	2.85	3.35	2.75	2.7	2.6	2.6	2.55	2.55	2.55
5	2.8	2.85	2.85	3.3	2.75	2.7	2.6	2.6	2.55	2.55	2.65
6	2.8	2.85	2.85	3.3	2.75	2.7	2.6	2.6	2.55	2.55	2.65
7	2.8	2.85	2.85	3.25	2.75	2.7	2.6	2.6	2.55	2.55	2.65
8	2.8	2.85	2.85	3.2	2.8	2.7	2.6	2.6	2.55	2.55	2.65
9	2.8	2.85	2.9	3.25	2.8	2.65	2.6	2.6	2.55	2.55	2.65
10	2.8	2.85	3.0	3.25	2.8	2.6	2.6	2.6	2.55	2.55	2.65
11	2.8	2.85	2.95	3.2	2.8	2.6	2.6	2.6	2.55	2.55	2.65
12	2.7	2.85	2.95	3.2	2.75	2.6	2.6	2.6	2.55	2.55	2.6
13	2.7	2.85	2.9	3.2	2.75	2.6	2.6	2.6	2.55	2.55	2.6
14	2.75	2.85	2.9	3.2	2.75	2.6	2.6	2.6	2.55	2.55	2.6
15	2.75	2.85	2.9	3.2	2.75	2.6	2.6	2.6	2.55	2.55	2.6
16	2.75	2.85	2.9	3.2	2.75	2.6	2.6	2.6	2.55	2.55	2.6
17	2.8	2.85	3.0	3.2	2.75	2.6	2.6	2.6	2.55	2.55	2.6
18	2.8	2.85	3.0	3.25	2.75	2.6	2.6	2.6	2.55	2.55	2.6
19	2.8	2.85	3.0	3.3	2.75	2.6	2.6	2.6	2.55	2.55	2.6
20	2.8	2.85	3.0	3.3	2.75	2.6	2.6	2.6	2.55	2.55	2.6
21	2.8	2.85	3.1	3.3	2.7	2.6	2.6	2.6	2.55	2.55	2.6
22	2.8	2.85	3.05	3.35	2.7	2.6	2.6	2.6	2.55	2.6	2.6
23	2.85	2.85	3.0	3.35	2.7	2.6	2.6	2.6	2.55	2.6	2.6
24	2.85	2.85	3.1	3.35	2.7	2.6	2.6	2.6	2.55	2.6	2.6
25	2.85	2.85	3.1	3.3	2.7	2.6	2.6	2.55	2.55	2.6	2.6
26	2.85	2.85	3.15	3.2	2.7	2.6	2.6	2.55	2.55	2.6	2.6
27	2.85	2.85	3.2	3.2	2.7	2.6	2.6	2.55	2.55	2.6	2.6
28	2.85	2.85	3.3	2.8	2.7	2.6	2.6	2.55	2.55	2.6	2.6
29	.....	2.85	3.3	2.8	2.7	2.6	2.6	2.55	2.55	2.6	2.6
30	.....	2.85	3.3	2.8	2.7	2.6	2.6	2.55	2.55	2.6	2.6
31	.....	2.85	.....	2.75	.....	2.6	2.6	.....	2.55	.....	2.6

NOTE.—Open-channel conditions throughout the year.

CHALK CREEK AT COALVILLE, UTAH.

Creek joins Weber River at Coalville. Its basin is rough and barren, the rocks efly sandstone and conglomerate, with but little overlying soil. Small springs over the entire area furnish the principal part of the normal flow, while the spring run-off is derived from melting snow. The stream has few tributaries. There are os, meadows, or forests in the area. Small tracts of irrigated lands lie near the the canyon. The water supply of the town of Coalville comes mostly from this

ging station was established October 23, 1904. It is located at a foot bridge on the l leading north, one-eighth mile from the county court-house at Coalville.
annel is slightly curved and somewhat irregular for about 150 feet above the sta- low it is wider and is straight for about 100 feet. Both banks are sufficiently high t overflow. The bed of the stream is composed of small cobbles and is somewhat it apparently permanent. There is but one channel at all stages, broken during r by the supporting piles of the bridge. The velocity is moderate and the stream

ge measurements are made from the foot bridge. The initial point for soundings o mark near the left end of the bridge.
ge, which is read daily by Miss Eva Rees, consists of a vertical staff attached to a the right bank of the stream. The bench mark is a cut on the south corner of the itment of the highway bridge; elevation, 0.00 feet above gage datum.
iption of this station and gage height and discharge data are contained in Water- aper No. 133 of the United States Geological Survey, pp. 254–255.

Discharge measurements of Chalk Creek at Coalville, Utah, in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
W. G. Swendsen	34	21	0.77	1.42	16
do	44	64	2.45	2.25	154
do	32	42	1.58	1.86	67
do	38	28	.80	1.50	22

Daily gage height, in feet, of Chalk Creek at Coalville, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	1.5	1.5	1.5	2.19	2.38	1.25	1.2	1.13	1.37	1.47	1.5
2	.....	1.5	1.55	1.63	2.18	2.38	1.25	1.2	1.13	1.32	1.46	1.5
3	1.5	.....	1.55	1.57	2.08	2.32	1.24	1.19	1.13	1.31	1.52	1.5
4	.....	1.5	1.52	1.57	2.03	2.4	1.23	1.18	.....	1.42	1.6	1.6
5	.....	.....	1.52	1.6	1.97	2.32	1.22	1.18	1.13	1.44	1.53	1.6
6	.....	1.5	.....	1.6	1.96	2.19	1.2	1.18	1.13	1.43	1.51	.....
7	1.4	.....	1.52	1.62	1.98	2.2	1.2	1.19	1.15	1.45	1.53	.....
8	.....	.....	1.42	.....	2.03	2.27	1.18	1.19	1.2	.....	1.52	1.4
9	.....	.....	1.5	1.68	1.98	2.35	1.2	1.17	1.2	1.37	1.55	.....
10	.....	1.5	1.5	1.8	1.93	2.25	1.23	1.2	.....	1.37	1.43	.....
11	1.4	1.5	1.54	1.66	1.88	2.15	1.21	1.2	1.2	1.47	1.44	.....
12	.....	.....	1.54	1.65	1.86	2.02	1.17	1.19	1.2	1.47	1.39	1.35
13	.....	.....	1.54	1.69	1.87	2.03	1.2	1.17	1.18	1.45	1.43	.....
14	1.4	1.5	1.56	1.71	1.87	2.02	1.28	1.18	1.19	.....	1.53	.....
15	.....	.....	1.54	1.67	1.91	1.99	.....	1.2	1.2	.....	1.43	1.37
16	.....	.....	1.56	1.73	2.02	1.95	1.21	1.17	1.2	1.45	1.37	1.4
17	.....	1.5	1.55	1.76	2.17	1.92	1.33	1.17	.....	.....	1.55	.....
18	1.51	.....	1.58	1.73	2.4	1.91	1.35	1.15	1.2	1.55	1.5	.....
19	1.52	.....	1.62	1.82	2.4	1.81	1.4	1.15	1.2	1.57	1.35	1.38
20	.....	1.5	1.6	1.83	2.6	1.8	1.57	1.15	1.2	1.55	1.5	.....
21	1.52	.....	1.57	1.81	2.55	1.68	1.54	1.15	1.2	1.55	1.5	1.38
22	.....	.....	1.5	1.8	2.47	1.67	1.52	1.15	1.2	1.57	1.5	.....
23	.....	1.5	1.62	1.8	2.47	1.67	1.53	1.15	1.2	1.56	1.43	.....
24	.....	1.5	1.6	1.82	2.4	1.67	.....	1.15	1.2	1.53	1.43	.....
25	1.5	1.5	1.52	1.9	2.3	1.62	1.5	1.15	1.2	.....	1.36	.....
26	.....	1.5	1.56	1.98	2.3	1.55	.....	1.15	1.22	1.55	1.33	.....
27	.....	1.5	1.55	2.05	2.3	1.55	1.2	1.15	1.2	1.55	.....	.....
28	1.5	.....	1.5	2.1	2.37	1.46	1.23	1.15	.....	1.55	.....	1.4
29	.....	.....	1.53	2.1	2.25	1.36	1.21	1.15	1.3	1.55	.....	.....
30	1.5	.....	1.6	2.11	2.2	1.28	1.17	.....	1.4	1.56	1.3	1.45
31	1.5	.....	1.6	.....	2.3	.....	1.19	1.13	.....	1.58	.....	.....

NOTE.—Ice conditions January 1 to February 22 and December 6–31.

Station rating table for Chalk Creek at Coalville, Utah, from October 23, 1904, to December 31 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.10	3	1.50	22	1.90	74	2.30	168
1.20	6	1.60	31	2.00	94	2.40	197
1.30	10	1.70	43	2.10	116	2.50	227
1.40	15	1.80	57	2.20	141	2.60	258

NOTE.—The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1904-5. It is well defined between gage heights 1.4 feet and 2.25 feet.

CHALK CREEK AT COALVILLE, UTAH.

: joins Weber River at Coalville. Its basin is rough and barren, the rocks sandstone and conglomerate, with but little overlying soil. Small springs the entire area furnish the principal part of the normal flow, while the spring off is derived from melting snow. The stream has few tributaries. There are eadows, or forests in the area. Small tracts of irrigated lands lie near the canyon. The water supply of the town of Coalville comes mostly from this

tation was established October 23, 1904. It is located at a foot bridge on the ling north, one-eighth mile from the county court-house at Coalville.
is slightly curved and somewhat irregular for about 150 feet above the sta- t is wider and is straight for about 100 feet. Both banks are sufficiently high rflow. The bed of the stream is composed of small cobbles and is somewhat parently permanent. There is but one channel at all stages, broken during the supporting piles of the bridge. The velocity is moderate and the stream

easurements are made from the foot bridge. The initial point for soundings k near the left end of the bridge.
hich is read daily by Miss Eva Rees, consists of a vertical staff attached to a ght bank of the stream. The bench mark is a cut on the south corner of the t of the highway bridge: elevation, 0.00 feet above gage datum.
n of this station and gage height and discharge data are contained in Water- No. 133 of the United States Geological Survey, pp. 254–255.

Discharge measurements of Chalk Creek at Coalville, Utah, in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
W. G. Swendsen	34	37	1.77	1.42	36
....do	44	64	2.45	2.25	154
....do	32	42	1.56	1.91	47
....do	30	28	.80	1.30	22

Daily gage height, in feet, of Chalk Creek at Coalville, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	1.5	1.5	1.5	2.19	2.38	1.25	1.2	1.13	1.37	1.47	1.5
2	.....	1.5	1.55	1.63	2.18	2.38	1.25	1.2	1.13	1.32	1.46	1.5
3	1.5	.....	1.55	1.57	2.08	2.32	1.24	1.19	1.13	1.31	1.52	1.5
4	.....	1.5	1.52	1.57	2.03	2.4	1.23	1.18	.....	1.42	1.6	1.6
5	.....	.....	1.52	1.6	1.97	2.32	1.22	1.18	1.13	1.44	1.53	1.6
6	.....	1.5	.....	1.6	1.96	2.19	1.2	1.18	1.13	1.43	1.51	.....
7	1.4	.....	1.52	1.62	1.98	2.2	1.2	1.19	1.15	1.45	1.53	.....
8	.....	.....	1.42	.....	2.03	2.27	1.18	1.19	1.2	.....	1.52	1.4
9	.....	.....	1.5	1.68	1.98	2.35	1.2	1.17	1.2	1.37	1.55	.....
10	.....	1.5	1.5	1.8	1.93	2.25	1.23	1.2	.....	1.37	1.43	.....
11	1.4	1.5	1.54	1.66	1.88	2.15	1.21	1.2	1.2	1.47	1.44	.....
12	.....	.....	1.54	1.65	1.86	2.02	1.17	1.19	1.2	1.47	1.39	1.5
13	.....	.....	1.54	1.69	1.87	2.03	1.2	1.17	1.18	1.45	1.43	.....
14	1.4	1.5	1.56	1.71	1.87	2.02	1.28	1.18	1.19	.....	1.53	.....
15	.....	.....	1.54	1.67	1.91	1.99	.....	1.2	1.2	.....	1.43	1.7
16	.....	.....	1.56	1.73	2.02	1.95	1.21	1.17	1.2	1.45	1.37	1.4
17	.....	1.5	1.55	1.76	2.17	1.92	1.33	1.17	.....	.....	1.55	.....
18	1.51	.....	1.58	1.73	2.4	1.91	1.35	1.15	1.2	1.55	1.5	.....
19	1.52	.....	1.62	1.82	2.4	1.81	1.4	1.15	1.2	1.57	1.35	1.5
20	.....	1.5	1.6	1.83	2.6	1.8	1.57	1.15	1.2	1.55	1.5	.....
21	1.52	.....	1.57	1.81	2.55	1.68	1.54	1.15	1.2	1.55	1.5	1.5
22	.....	.....	1.5	1.8	2.47	1.67	1.52	1.15	1.2	1.57	1.5	.....
23	.....	1.5	1.62	1.8	2.47	1.67	1.53	1.15	1.2	1.56	1.43	.....
24	.....	1.5	1.6	1.82	2.4	1.67	.....	1.15	1.2	1.53	1.43	.....
25	1.5	1.5	1.52	1.9	2.3	1.62	1.5	1.15	1.2	.....	1.36	.....
26	.....	1.5	1.56	1.98	2.3	1.55	.....	1.15	1.22	1.55	1.33	.....
27	.....	1.5	1.55	2.05	2.3	1.55	1.2	1.15	1.2	1.55	.....	.....
28	1.5	.....	1.5	2.1	2.37	1.46	1.23	1.15	.....	1.55	.....	1.4
29	.....	.....	1.53	2.1	2.25	1.36	1.21	1.15	1.3	1.55	.....	.....
30	1.5	.....	1.6	2.11	2.2	1.28	1.17	.....	1.4	1.56	1.3	1.6
31	1.5	.....	1.6	.....	2.3	.....	1.19	1.13	.....	1.58	.....	.....

NOTE.—Ice conditions January 1 to February 22 and December 6–31.

Station rating table for Chalk Creek at Coalville, Utah, from October 23, 1904, to December 31 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.10	3	1.50	22	1.90	74	2.30	168
1.20	6	1.60	31	2.00	94	2.40	197
1.30	10	1.70	43	2.10	116	2.50	227
1.40	15	1.80	57	2.20	141	2.60	258

NOTE.—The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1904-5. It is well defined between gage heights 1.4 feet and 2.25 feet.

l monthly discharge of Chalk Creek at Coalville, Utah, for 1904 and 1905.

[Drainage area, 248 square miles.]

onth.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
1904.						
.....	22	20	21.6	386	0.087	0.029
.....	31	8	20.2	1,202	.081	.090
1905.						
.....	22	22	22.0	262	.089	.020
.....	33	16	26.0	1,599	.105	.121
.....	118	22	55.4	3,296	.223	.249
.....	274	68	139	8,547	.560	.646
.....	197	9	95.2	5,665	.384	.428
.....	28	4.8	11.0	676	.044	.051
.....	6	3.6	4.8	295	.019	.022
.....	15	3.6	5.9	351	.024	.027
.....	29	10	20.9	1,285	.084	.097
.....	31	10	18.7	1,113	.075	.084
.....	22	18	20.6	204	.083	.015
ɔd (1905).....	.....	.....	.....	23,290	.....	.....

ɔonditions December, 1904, January 1 to February 22, and December 6–31, 1905. Dis- lated on days when gage was not read.

AMERICAN FORK BASIN.

AMERICAN FORK NEAR AMERICAN FORK, UTAH.

Fork drains a rough, broken, limestone country, comprising a portion of the ɛs of the Wasatch Mountains. The stream is confined to a steep, narrow receives few tributaries, its normal flow being derived almost entirely from ɛre are no storage reservoirs, swamps, or lakes in the area, and the timber nty. The entire summer flow is diverted for irrigation near the mouth of the winter flow and a part of the spring flood is discharged into Utah Lake.

ı was established May 21, 1900. It is located about 6 miles northeast of the rican Fork, Utah, 50 feet north of the county road, and 200 feet southwest of ower house.

ɛnts are made over a sharp-crested rectangular weir. A nail driven into the e just south of the south opening, and level with the crest of the weir, serves gage heights, which are read daily by Peter Anderson. During floods con- vel is deposited in the weir approach, making measurements at such times ıis condition is partly overcome by raising th crest and sluicing out the

n in regard to this station is contained in the following publication, of the s Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Ann 20, iv, p 469; WS 51, p 417–418; 66, p 124; 100, p 139; 133, p 259.
VS 51, p 418; 66, p 124; 100, p 140.
ally mean. WS 133, p 260.
ıonthly: Ann 13, iii, p 96, 20, iv, p 469; WS 75, p 195; 133, pp 260–261.
early: Ann 13, iii, p 99, 20, iv, p 61.
ı. WS 51, p 419; 66, p 124; 100, p 140; 133, p 259.
: WS 66, p 176; 12, ii, p 361.

Daily gage height, in feet, of American Fork near American Fork, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec
1	0.39	0.38	0.40	0.38	0.90	1.36	0.90	0.48	0.36	0.43	0.37	0
2	.40	.39	.40	.38	.84	1.34	.85	.48	.36	.42	.37	
3	.39	.38	.41	.38	.76	1.45	.85	.47	.....	.41	.37	...
4	.40	.37	.41	.38	.73	1.39	.79	.47	.38	.41	.37	
5	.41	.....	.41	.41	.69	1.39	.79	.47	.39	.40	.37	
6	.39	.37	.42	.43	.66	1.39	.77	.46	.40	.39	.37	
7	.39	.38	.44	.52	.66	1.41	.75	.46	.39	.39	.37	
8	.37	.37	.43	.52	.68	1.57	.78	.46	.38	.40	.37	
9	.38	.37	.43	.....	.69	1.45	.77	.45	.37	.39	.36	
10	.38	.38	.43	.58	.68	1.35	.74	.44	.36	.39	.36	
11	.37	.38	.43	.52	.60	1.35	.75	.44	.36	.39	.36	
12	.38	.23	.44	.50	.60	1.41	.73	.43	.35	.38	.36	
13	.38	.33	.44	.40	.62	1.50	.72	.41	.35	.38	.36	
14	.38	.37	.44	.50	.63	1.50	.71	.41	.35	.38	.36	
15	.38	.37	.44	.51	.64	1.47	.68	.40	.35	.38	.36	
16	.38	.37	.44	.53	.76	1.37	.65	.40	.35	.38	.35	
17	.38	.37	.43	.53	.97	1.34	.65	.40	.35	.37	.35	
18	.38	.37	.43	.53	1.01	1.14	.62	.40	.35	.36	.35	
19	.37	.37	.43	.56	1.11	1.08	.60	.39	.35	.36	.35	
20	.37	.37	.43	.55	1.16	1.14	.56	.38	.35	.36	.36	
21	.38	.37	.42	.55	1.19	1.17	.56	.38	.37	.38	.36	
22	.38	.37	.43	.54	1.16	1.27	.55	.38	.37	.38	.36	
23	.38	.37	.43	.56	1.16	1.24	.53	.38	.37	.38	.36	
24	.37	.37	.44	.59	1.16	1.12	.52	.41	.37	.38	.35	
25	.37	.38	.43	.62	1.28	1.10	.51	.39	.38	.38	.35	
26	.37	.39	.45	.71	1.26	1.05	.49	.37	.37	.38	.35	
27	.37	.39	.45	.72	1.27	1.01	.49	.38	.37	.38	.33	
28	.37	.40	.45	.74	1.16	.96	.49	.38	.47	.38	.30	
29	.37	.....	.45	.75	1.11	.94	.48	.41	.52	.38	.30	
30	.37	.....	.43	.86	1.10	.92	.48	.38	.45	.38	.32	
31	.37	.....	.43	.....	1.32	.....	.49	.38	.....	.38	.....	

NOTE.—January 1 to March 29 and September 28 to December 31, crest 30.5 feet long; March 30 31, crest 33 feet long; April 1 to September 27, crest 36.5 feet long. Ice conditions on the river a the flow at the weir but little.

y discharge, in second-feet, of American Fork near American Fork, Utah, for 1905.

r.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	25	24	26	28	104	193	104	40	26	29	23	19
.....	26	25	26	28	94	189	95	40	26	28	23	20
.....	25	24	27	28	81	212	95	39	a 27	27	23	a 19
.....	26	23	27	28	76	199	85	39	28	27	23	18
.....	27	a 23	27	32	70	199	85	39	30	26	23	18
.....	25	23	28	35	65	199	82	38	31	25	23	16
.....	25	24	30	46	65	203	79	38	30	25	23	16
.....	23	23	29	46	68	239	84	38	28	26	23	18
.....	24	23	29	a 50	70	212	82	37	27	25	22	18
.....	24	24	29	54	68	191	77	35	26	25	22	18
.....	23	24	29	46	56	191	79	35	26	25	22	18
.....	24	11	30	43	56	203	76	34	25	24	22	18
.....	24	19	30	42	59	223	74	32	25	24	22	18
.....	24	23	30	43	61	223	73	32	25	24	22	18
.....	24	23	30	44	62	217	68	31	25	24	22	18
.....	24	23	30	47	81	195	64	31	25	24	21	18
.....	24	23	29	47	116	180	64	31	25	23	21	18
.....	24	23	29	47	123	148	59	31	25	22	21	18
.....	23	23	29	51	142	136	56	30	25	22	21	18
.....	23	23	29	50	152	148	51	28	25	22	22	18
.....	24	23	28	50	158	154	51	28	27	24	22	17
.....	24	23	29	48	152	174	50	28	27	24	22	17
.....	24	23	29	51	152	168	47	28	27	24	22	17
.....	23	23	30	55	152	144	46	32	27	24	21	18
.....	23	24	29	59	176	140	44	30	28	24	21	17
.....	23	25	31	73	172	131	42	27	27	24	21	18
.....	23	25	31	74	174	123	42	28	27	24	19	17
.....	23	26	31	77	152	114	42	28	33	24	17	18
.....	23	.....	31	79	142	111	40	32	38	24	17	18
.....	23	.....	31	97	140	107	40	28	31	24	18	17
.....	23	.....	31	.....	184	.....	42	28	.....	24	.....	18

a Discharge interpolated.

mated monthly discharge of American Fork near American Fork, Utah, for 1905.

[Drainage area, 66 square miles.]

Month.	Discharge in second-feet.			Run-off.		
	Maximum.	Minimum.	Mean.	Total in acre-feet.	Second-feet per square mile.	Depth in inches.
.....	27	23	24.0	1,476	0.364	0.420
y.....	26	11	23.0	1,277	.348	.362
.....	31	26	29.2	1,795	.442	.510
.....	97	28	49.9	2,969	.756	.844
.....	184	56	110	6,763	1.67	1.92
.....	239	107	176	10,470	2.67	2.98
.....	104	40	65.1	4,003	.986	1.14
.....	40	27	32.7	2,011	.495	.571
er.....	38	25	27.4	1,630	.415	.463
.....	29	22	24.5	1,506	.371	.428
er.....	23	17	21.5	1,279	.326	.364
r.....	20	16	17.8	1,094	.270	.311
e year.....	239	11	50.1	36,270	.759	10.31

PROVO RIVER BASIN.

DESCRIPTION OF BASIN.

Provo River has its source in the Uinta Mountains and flows westward in a steep, narrow canyon until it reaches Heber or Provo Valley, through which it winds in a well-defined channel. Leaving the valley, it flows southwestward, cutting through the Wasatch Range in another steep, narrow, and extremely rough canyon, and finally discharging its surplus waters into Utah Lake.

In the mountain regions the principal rock is a compact limestone. Except in Heber Valley there is but little soil in any portion of the basin. Small groves of fir and aspen are, however, scattered over almost the entire area, and there is a light growth of underbrush. There are no extensive forests, meadows, or marshes. In the canyons the stream receives numerous short and swift tributaries, deriving their principal supply from springs, but a part also from the melting of the snow, which covers portions of the high mountains during the entire year. The highest peaks reach elevations of about 13,000 feet.

Heber Valley, which comprises an area of about 20 square miles, is an irrigated farming district, composed of a deposit of loose bowlders, gravel, and soil, very porous. Most of the water comes from the main stream, though a part is received from small creeks which enter the valley from the south. The most important of these is Daniels Creek, into which some water is diverted from Strawberry River, a tributary of Green River, by three small canals in low passes at the head of the creek.

There are a few lakes at the head of the river, but they are so small that they probably have little effect in regulating the flow. There is no storage on the stream at present, but a few possibilities exist which will doubtless be developed in the future, as the entire stream, after being used at the mouth of the canyon for the development of power, is now utilized on lands in the vicinity of Utah Lake, and the supply is altogether insufficient.

PROVO RIVER ABOVE TELLURIDE POWER COMPANY'S DAM, NEAR PROVO, UTAH.

This station was established March 1, 1905. It is located about three-fourths of a mile up the river from Upper Falls, a station on the Provo Canyon branch of the Rio Grande Western Railway, about 4 miles above the mouth of the canyon and 800 feet south of the canyon road, in J. W. Slick's pasture. It is about one-half mile above the Telluride Power Company's dam and above all diversions into Utah Lake Valley. The object of the station is the collection of data concerning the amount of water passing from the river into this valley.

The channel has a slight uniform curvature for about 200 feet above and 300 feet below the station, describing approximately the arc of a circle. Both banks are sufficiently high to prevent overflow; the left bank is formed by the Rio Grande Western Railway grade. The bed of the stream is composed of well-compacted rock and soil, is comparatively smooth, and is not liable to shift, but a slight growth of moss occurs from the time of the spring flood until freezing weather. The velocity is low near the right bank, but increases uniformly to a point near the left. The discharge may vary from 100 to 1,400 second-feet. Conditions of free flow exist except for a very short distance near the left bank.

Discharge measurements are made by means of a cable and car. The cable is marked at 4-foot intervals, beginning at the north support, which is the initial point for soundings.

Daily gage readings are made, without expense to the Geological Survey, by the Telluride Power Company, the observations being under the direction of E. A. Briscoe, an engineer at the power house about 4 miles below the station. The gage is of the inclined type and consists of a 4-by-4 inch by 16-foot fir, bolted to a vertical cedar post embedded in the bank at the water's edge and to a box-elder stump at the shore end, about 25 feet upstream from the cable on the left bank. It is graduated with saw cuts and paint to read vertically. The gage is referred to bench marks as follows: (1) A 4-inch iron pipe with a metallic cap, *set 3½ feet in* the ground at a point 12 feet from the north cable post, under a fence; this *has an elevation* of 7.31 feet above gage datum and is so stamped on the top. (2) A project-

ing point, marked with black paint, on a limestone ledge in a railroad cut about a foot above the track and 22 feet upstream from the line of the gage; elevation, 17.18 feet above datum of gage.

Discharge measurements of Provo River above Telluride Power Company's dam, near Provo, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 26[a]	H. S. Kleinschmidt	70	144	1.51	3.73	217
March 3[b]	W. G. Swendsen	69	130	2.26	3.93	294
May 13	do	71	137	2.35	4.05	309
June 14	Hoyt & Swendsen	75	223	3.68	5.30	820
June 22	do	71	166	2.82	4.43	469
August 28[c]	A. B. Larson	67	94	1.46	3.62	136
September 27[c]	W. G. Swendsen	67	85	1.64	3.57	139

[a] Measurement by wading 35 feet above cable.
[b] Measurement by wading approximately at present cable station.
[c] Growing moss changed conditions.

Daily gage height, in feet, of Provo River above Telluride Power Company's dam, near Provo, Utah, for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	3.85	3.9	3.85	4.4	5.15	4.0	3.9	3.7	3.65	3.75	3.9
2	4.1	4.0	3.85	4.4	5.4	3.95	3.85	3.6	3.65	3.75	3.9
3	3.9	4.0	3.85	4.5	5.5	3.95	3.9	3.6	3.65	3.75	3.9
4	3.9	4.1	3.85	4.4	5.6	3.95	3.8	3.6	3.65	3.75	3.9
5	3.9	4.05	3.8	4.2	5.77	3.95	3.8	3.6	3.65	3.75	3.85
6	3.85	4.05	3.85	4.1	5.5	3.95	3.8	3.6	3.65	3.75	3.65
7	3.85	4.0	3.85	4.1	5.4	3.95	3.8	3.6	3.65	3.75	3.6
8	3.85	3.95	3.85	4.1	5.8	3.95	3.8	3.6	3.55	3.8	3.55
9	3.8	3.9	3.85	4.25	6.1	3.95	3.8	3.6	3.65	3.8	3.55
10	3.8	3.9	3.95	4.2	5.9	3.95	3.8	3.6	3.6	4.0	3.6
11	3.8	3.9	4.1	4.2	5.4	3.95	3.85	3.6	3.6	4.0	3.6
12	5.8	3.9	4.0	4.1	5.15	3.95	3.85	3.6	3.6	3.8	3.6
13	5.1	3.9	4.0	4.1	5.15	3.95	3.8	3.6	3.6	3.85	3.6
14	5.1	3.9	4.0	4.1	5.2	3.95	3.75	3.6	3.6	3.85	3.6
15	4.7	3.9	4.0	4.1	5.1	4.0	3.75	3.6	3.6	3.85	3.8
16	4.1	3.9	4.1	4.0	5.05	3.95	3.8	3.6	3.6	3.85	3.8
17	3.8	3.85	4.1	4.1	4.9	3.95	3.8	3.6	3.6	3.85	3.8
18	3.8	3.85	4.1	4.25	4.8	3.95	3.7	3.6	3.6	3.9	3.8
19	3.8	3.85	4.1	4.4	4.6	3.9	3.8	3.6	3.6	3.9	3.8
20	3.8	3.9	4.1	4.45	4.45	3.9	3.7	3.6	3.6	3.9	3.8
21	3.8	3.9	4.15	4.6	4.4	3.9	3.7	3.6	3.6	3.9	3.7
22	3.8	4.0	4.1	4.7	4.45	3.9	3.7	3.55	3.6	3.9	3.7
23	3.8	3.95	4.1	4.8	4.4	3.9	3.7	3.55	3.65	3.9	3.7
24	3.8	3.9	4.1	4.85	4.35	3.9	3.7	3.55	3.65	3.85	3.8
25	3.8	3.9	4.1	4.8	4.35	3.9	3.7	3.6	3.65	3.85	3.8
26	3.8	3.85	4.3	4.8	4.4	3.85	3.7	3.6	3.65	3.85	3.8
27	3.85	4.0	4.3	4.9	4.1	3.85	3.65	3.6	3.65	3.85	3.8
28	3.9	3.9	4.3	5.0	4.05	3.85	3.7	3.55	3.65	3.9	3.8
29	.....	3.9	4.3	5.1	4.0	3.85	3.65	3.7	3.7	3.9	3.8
30	.....	3.95	4.5	4.9	4.0	3.85	3.7	3.7	3.7	3.9	3.8
31	.....	3.9	.....	4.85	.....	3.9	3.7	.....	3.75	.....	3.8

NOTE.—Ice jam February 12, 13, and 14. Open-channel conditions during the remainder of the winter months.

Daily discharge, in second-feet, of Provo River above Telluride Power Company's dam, near Provo, Utah, for 1905.

Day.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	254	269	254	446	763	301	245	163	159	193	244
2	335	301	254	446	879	285	237	135	159	194	265
3	269	301	254	485	926	285	243	136	160	194	265
4	269	335	254	446	973	285	212	136	160	194	265
5	269	318	238	371	1,054	284	211	137	160	194	239
6	254	318	254	335	926	284	210	137	160	194	170
7	254	301	254	335	879	283	209	138	160	194	158
8	254	285	254	335	1,069	282	208	138	132	210	148
9	238	269	254	389	1,215	281	207	139	161	210	148
10	238	269	285	371	1,117	280	206	139	147	273	157
11	238	269	335	371	879	280	221	140	147	273	157
12	238	269	301	335	763	279	220	140	147	210	157
13	238	269	301	335	763	278	203	141	147	226	157
14	238	269	301	335	786	277	187	141	147	227	158
15	238	269	301	335	740	292	187	142	148	227	216
16	238	269	335	301	717	275	200	142	148	227	216
17	238	254	335	335	651	274	200	143	148	227	216
18	238	254	335	389	608	273	168	143	148	242	216
19	238	254	335	446	525	256	197	144	148	242	216
20	238	269	335	466	466	255	167	144	148	243	216
21	238	269	353	525	446	255	166	145	149	243	157
22	238	301	335	566	466	254	165	132	149	243	157
23	238	285	335	608	446	254	164	133	163	243	157
24	238	269	335	630	427	253	163	133	163	228	217
25	238	269	335	608	427	253	162	147	163	228	217
26	238	254	408	608	446	236	161	147	163	229	218
27	254	301	408	651	335	236	144	147	164	229	218
28	269	269	408	695	318	237	158	132	164	244	218
29		269	408	740	301	237	146	173	178	244	218
30		285	485	651	301	238	162	173	178	244	218
31		269		630		245	162		193		218

NOTE.—Discharge February 12-16 assumed as 238 second-feet, on account of ice conditions. A rating table was used to obtain daily discharge February 1 to July 4. The daily discharge July 5 to December 31 was obtained by indirect methods, as applied to shifting channels. The effect produced by the existence of moss at this station seems to be about the same as by a shifting of the bed, i. e., the moss seems to collect sediment and make a soft coating over the bed of the stream, but does not affect flow near surface.

Estimated monthly discharge of Provo River above Telluride Power Company's dam, near Provo, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
February	335	238	249	13,830
March	335	254	279	17,160
April	485	238	319	18,980
May	740	301	468	28,780
June	1,215	301	687	40,880
July	301	236	267	16,420
August	245	144	190	11,680
September	173	132	143	8,510
October	193	132	157	9,654
November	273	193	226	13,450
December	245	143	200	12,300
The period				191,600

PROVO RIVER AT MOUTH OF CANYON, NEAR PROVO, UTAH.

This station was established July 27, 1889. It is located about 6 miles north of Provo, about 1,000 feet above Olmstead station, on the Provo Canyon branch of the Rio Grande Western Railway, and 1,200 feet above the power house of the Telluride Power Company.

The station was originally established to determine the total flow of the Provo above all diversions to Utah Lake Valley; but since that time a small canal has been taken out about 3 miles above the station and the system of the Telluride Power Company has been extended by a new flume line of sufficient capacity to divert the entire normal flow of the stream. The power plant of the Telluride Power Company has been rebuilt at a point about 1,200 feet below the station, the tailrace discharging directly into the canals at the mouth of the canyon. Practically no water now passes the station except the flood discharge and a small portion of the side drainage between the power company's dam and the gaging station, the greater part of the side drainage being diverted into the flume at various points along the line. The station is thus of little importance, but it is maintained at an extremely low cost, since the gage readings are made by the Telluride Power Company and the discharge curve is so well defined that but few more measurements are necessary.

The channel is straight for about 200 feet above and 100 feet below the station. The right bank is steep and rocky and does not overflow; the left is somewhat low and sloping and is liable to overflow at extreme flood stages. The bed of the stream is composed of bowlders and soil and is very rough, but permanent. The velocity is high, ranging from 4 to 6 feet per second. Ice forms near the banks and appears also as drift or floating ice. It is, however, limited in quantity and probably never piles up or gorges. There is no anchor or needle ice at any time.

Discharge measurements are made by means of a cable and car. The cable is marked at 5-foot intervals with white paint. The initial point for soundings is the first white mark on the cable south of the vertical post that supports the cable on the right bank. A guy line is stretched across the stream about 40 feet above the station and is found useful at all stages.

The original gage was of the inclined type and consisted of a piece of Oregon fir attached to vertical posts embedded in the left bank about 2 feet below the line of the cable. The present gage, daily readings of which are made under the direction of E. A. Brisco, an engineer at the power plant, is a vertical piece of aspen driven into the stream bed and supported at the top by a horizontal piece buried in the bank. It is located on the right bank about 30 feet above the line of the cable. Simultaneous readings on the two gages are found to be equal, but the zero of the new gage is 0.10 foot above that of the old one. The bench marks are as follows: (1) A cross chiseled in a limestone rock about 1 foot square, 100 feet S. 15° E. from the old gage; elevation above old gage datum, 6.98 feet. (2) A standard United States Geological Survey metallic plug, cemented in the top of the south abutment of the highway bridge about one-eighth mile below the station; elevation above zero of gage, 4.75 feet. (3) A cross chiseled on the top of a bowlder projecting 1 foot above the ground, 126 feet N. 75° W. from the north post supporting the cable; elevation above zero of gage, 11.21 feet.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-Supply Paper):

Description: Ann 14, ii, p 123; 18, iv, pp 325–326; Bull 131, p 59; 140, p 234; WS 16, p 162; 28, p 146; 38, pp 338–339; 51, p 416; 66, p 123; 85, p 88; 100, pp 140–141, 142–143; 133, pp 261–262.

Discharge: Ann 18, iv, p 326; Bull 131, p 92; 140, p 234; WS 16, p 162; 28, p 153; 38, p 339; 51, p 416; 100, p 141; 66, p 123; 85, p 88; 100, p 143; 133, p 262.

Discharge, monthly: Ann 11, ii, p 104; 12, ii, pp 354, 361; 13, iii, p 97; 14, ii, pp 123–124; 18, iv, p 327; 19, iv, p 442; 20, iv, pp 458, 468; 21, iv, p 399; 22, iv, p 416; Bull 140, p 235; WS 75, p 195; 100, pp 142, 144; 133, p 264.

Discharge, yearly: Ann 13, iii, p 99; 20, iv, p 61.

Gage heights: Bull 131, p 60; 140, p 234; WS 11, p 79; 16, p 162; 28, p 152; 38, p 339; 51, p 417; 66, p 100, p 141, 143–144; 133, p 263.

Hydrographs: Ann 12, ii, p 340; 14, ii, p 125; 18, iv, p 328; 19, iv, p 442; 20, iv, p 468; 21, iv, p 399; 22, iv, p 417.

Rainfall and run-off relation: Ann 20, iv, p 459.

Rating tables: Ann 18, iv, p 326; 19, iv, p 441; Bull 131, p 59; 140, p 234; WS 28, p 154; 39, p 456; 52, p 52; 66, p 176; 100, pp 142, 144; 133, p 263.

Water powers: Ann 19, iv, p 441.

Discharge measurements of Provo River at mouth of canyon, near Provo, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis-charg
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-fet*
March 4	Henry Kleinschmidt	73	116	2.58	4.50	30
May 24	W. G. Swendsen	75	138	3.52	4.95	48
August 29[a]	A. B. Larson	32	41	.62	3.55	2

[a] Measurement made 100 feet above regular station.

Daily gage height, in feet, of Provo River at mouth of canyon, near Provo, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	4.1	4.21	4.51	4.4	4.78	5.39	4.05	3.65	3.58	3.66	3.51	3.81
2	3.98	4.42	4.56	4.34	4.8	5.63	3.93	3.54	3.5	3.75	3.56	3.81
3	4.12	4.6	4.58	4.37	4.77	5.7	3.87	3.69	3.44	3.76	3.59	3.68
4	4.3	4.52	4.65	4.32	4.72	5.95	3.95	3.52	3.57	3.68	3.52	3.5
5	4.22	4.51	4.46	4.3	4.5	5.87	3.83	3.61	3.67	3.68	3.56	3.62
6	4.14	4.52	4.66	4.3	4.34	5.77	4.0	3.55	3.7	3.71	3.56	3.77
7	4.2	4.21	4.18	4.35	4.22	5.65	3.95	3.53	3.6	3.71	3.52	3.8
8	4.4	4.28	4.0	4.34	4.4	5.86	3.93	3.56	3.58	3.66	3.55	3.68
9	4.1	4.11	3.98	4.24	4.47	6.33	3.83	3.5	3.63	3.69	3.55	3.69
10	4.1	4.14	3.91	4.6	4.5	5.97	3.65	3.51	3.64	3.7	4.04	3.65
11	4.1	4.08	3.88	4.68	4.49	5.65	3.63	3.55	3.48	3.61	3.92	3.63
12	4.38	4.08	4.2	4.35	4.28	5.19	3.6	3.55	.....	3.63	4.05	3.68
13	4.1	4.01	4.14	4.25	4.3	5.75	3.6	3.53	.....	3.6	4.03	3.51
14	4.12	4.0	4.0	4.4	4.28	5.75	3.7	3.49	.....	3.62	3.96	3.47
15	4.05	4.05	4.3	4.44	4.29	5.53	3.67	3.52	.....	3.64	3.98	3.68
16	4.07	4.09	4.52	4.45	4.4	5.5	3.63	3.57	.....	3.63	4.0	3.6
17	3.79	4.2	4.5	4.52	4.45	5.23	3.6	3.5	.....	3.59	3.99	3.62
18	3.78	4.1	4.4	4.52	4.43	5.0	3.63	3.45	.....	3.64	3.89	3.62
19	4.02	4.12	4.5	4.51	4.76	4.87	3.65	3.63	.....	3.65	3.91	.....
20	4.1	4.15	4.57	4.51	4.77	4.78	3.62	3.61	.....	3.58	3.76	.....
21	3.56	4.14	4.18	4.56	4.89	4.71	3.5	3.53	.....	3.61	3.89	.....
22	4.04	4.11	4.45	4.5	5.06	4.77	3.5	3.46	.....	3.63	3.82	.....
23	4.14	4.15	4.43	.....	5.1	4.85	3.5	3.55	.....	3.57	3.88	.....
24	4.13	4.25	4.49	4.4	5.09	4.7	3.55	3.68	.....	3.57	3.	.....
25	4.05	4.22	4.43	4.45	5.0	4.43	3.6	3.59	3.51	3.55	3.74	.....
26	4.08	4.21	4.43	4.75	5.02	4.17	3.6	3.59	3.52	3.6	3.93	.....
27	4.06	4.42	4.49	4.94	5.1	4.2	3.58	3.56	3.49	3.61	3.	.....
28	4.03	4.5	4.48	4.84	5.2	4.15	3.57	3.57	3.55	3.59	3.95	.....
29	4.03	.....	4.43	4.72	5.22	4.05	3.6	.....	3.85	3.58	3.95	.....
30	4.08	.....	4.43	4.78	5.15	3.93	3.6	.....	3.78	3.65	3.91	.....
31	4.13	.....	4.34	.....	5.1	.....	.....	.....	.....	3.64	.....	.....

rating table for Provo River at mouth of canyon, near Provo, Utah, from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet*
3.40	12	4.20	177	5.00	532	5.80	1,050
3.50	20	4.30	212	5.10	589	5.90	1,120
3.60	31	4.40	250	5.20	649	6.00	1,192
3.70	46	4.50	290	5.30	711	6.10	1,265
3.80	64	4.60	332	5.40	775	6.20	1,340
3.90	87	4.70	377	5.50	841	6.30	1,415
4.00	114	4.80	425	5.60	910	6.40	1,490
4.10	144	4.90	477	5.70	980		

E.—The above table is applicable only for open-channel conditions. It is based on discharge irements made during 1903–1905. It is well defined between gage heights 3.5 feet and 6.3 feet.

discharge, in second-feet, of Telluride Power Company's flume near Provo, Utah, for 1905.

Day.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	24	52	40	40	45	79	163	130	136	173
.....	29	40	62	35	62	88	141	130	124	184
.....	23	41	78	40	70	85	117	130	125	170
.....	29	38	77	29	68	82	126	145	124	178
.....	36	36	49	24	75	74	148	150	127	183
.....	41	36	57	59	61	106	131	130	130	175
.....	43	34	66	41	62	80	139	127	130	163
.....	33	45	68	24	59	75	142	130	127	155
.....	37	55	63	70	75	80	137	135	129	167
.....	44	50	49	39	96	69	137	127	162	169
.....	46	26	59	32	95	52	133	130	170	170
.....	27	78	65	39	99	87	136	130	160	150
.....	38	60	66	53	101	80	.....	.....	160	171
.....	25	51	62	48	90	88	.....	.....	155	168
.....	43	55	54	50	98	85	.....	130	153	188
.....	49	55	43	42	97	85	.....	131	160	185
.....	41	48	59	58	100	79	.....	128	160	183
.....	56	36	70	48	94	89	.....	126	160	187
.....	62	83	45	42	92	105	.....	129	161	.....
.....	41	66	55	48	85	124	.....	135	.....	.....
.....	56	60	38	45	87	130	.....	126	.....	.....
.....	62	65	40	41	87	131	.....	158	.....	.....
.....	49	.....	50	42	87	117	.....	150	.....	.....
.....	47	85	44	37	84	123	.....	158	.....	.....
.....	38	75	48	68	81	114	133	161	.....	.....
.....	40	.....	36	81	80	150	124	141	.....	.....
.....	39	.....	65	45	80	146	122	135	.....	.....
.....	32	50	48	47	80	121	119	142	.....	.....
.....	44	37	32	40	77	.....	157	.....	.....	.....
.....	53	33	44	64	78	.....	137	.....	.....	.....
.....	54	.....	30	.....	.....	.....	.....	160	.....	.....

Estimated monthly discharge of Provo River at mouth of canyon, near Provo, Utah, for 1905.

[Drainage area, 640 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	250	27	142	8,731	0.222	0.25
February	332	114	190	10,550	.297	.30
March	359	82	239	14,700	.373	.43
April	499	191	288	17,140	.450	.50
May	661	184	396	24,350	.619	.71
June	1,438	95	687	40,880	1.07	1.19
July	129	20	50.1	3,080	.078	.09
August	44	16	26.8	1,648	.042	.04
September (17 days)	76	15	32.6	1,099	.051	.05
October	56	26	37.1	2,281	.058	.06
November	129	21	73.0	4,344	.114	.12
December 1–18	66	16	38.3	1,368	.060	.04
The period				130,200		

Estimated monthly discharge of Telluride Power Company's flume near Provo, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
March	62	23	41.3	2,539
April (27 days)	85	26	51.5	2,738
May	78	30	53.6	3,296
June	81	24	45.7	2,719
July 1–30	101	45	81.5	4,850
August 1–28	150	52	97.3	5,404
September 1–12, 25–30	163	117	136	4,866
October (27 days)	161	126	137	7,337
November 1–19	170	124	140	5,276
December 1–18	188	150	173	6,176
The period				45,210

NOTE.—To obtain total flow of Provo River at head of diversion dams, the flume discharge should be added to that of the gaging station given above.

PROVO RIVER AT THE RIO GRANDE WESTERN RAILWAY BRIGDE, NEAR PROVO, UTAH.

This station was established January 25, 1905. It is located at the Rio Grande Western Railway bridge about 2 miles northwest of the town of Provo, below all points of diversion and inflowing streams. It replaces the old station maintained at the San Pedro Los Angeles, and Salt Lake Railroad bridge, about 300 feet below, the conditions at the latter point being so changed by the reconstruction of the bridge that the section could no longer be used.

The purpose of the station is to determine the amount of water discharged by the Provo into Utah Lake. As the entire normal spring and summer flow is diverted for irrigation above this point, the station is maintained only during flood and winter seasons.

The channel is straight for about 150 feet above and 200 feet below the station. The normal flow is confined to a comparatively narrow channel near the center, but the high-

ıter channel is much wider, including a small timbered flat on both sides. The railroad ade, however, prevents any overflow at the gaging section. The bed of the stream is mposed of coarse gravel and is liable to change during floods. The velocity is uniform ıt high, ranging from 4 to 7 feet. Information in regard to ice conditions is incomplete. Discharge measurements are made from a foot plank, fastened to 4 by 4 inch pieces fir bolted to the lower chord on the upstream side of the bridge. The plank is graduated ith paint, beginning at the north face of the masonry abutment on the south end of the idge, which is the initial point for soundings. A guy line is stretched 24 feet upstream om the foot plank.

The gage, which is read daily by Lars Thompson, a farmer, is of the inclined type, con-ıting of a 4 by 4 inch by 16-foot timber of Oregon fir drift-bolted to the old piles and sills f the former bridge, about 10 feet east of the present bridge, the incline being such that 5.88 feet along the piece equal 10 feet vertical. It is graduated with saw cuts and paint ı read vertically. The gage is referred to bench marks as follows: (1) A standard United tates Geological Survey metallic plug, cemented in the masonry wall, 0.5 foot south of e face at the southeast corner of the bridge; this is 11.29 feet above the gage datum and ı so stamped. (2) A cross cut in the top of the same wall at the southwest corner of the ridge; elevation above gage datum, 11.25 feet.

Discharge measurements of Provo River at the Rio Grande Western Railway bridge, near Provo, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
anuary 25	H. S. Kleinschmidt	44	54	3.52	2.80	191
ebruary 14[a]	do	37	38	3.12	2.53	120
ebruary 16	do	43	49	3.49	2.74	170
larch 9	do	43	49	3.36	2.70	166
une 21	W. G. Swendsen	17	8.5	1.52	2.00	12.9

[a] Ice divides stream into two channels.

Daily gage height, in feet, of Provo River at the Rio Grande Western Railway Bridge, near Provo, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	Day.	Jan.	Feb.	Mar.	Apr.	May.	June.
1		2.85	2.75	2.6	2.7	2.55	17		2.75	2.65	2.75	2.0	3.05
2		3.1	2.75	2.55	2.8	3.05	18		2.7	2.65	2.7	2.0	2.8
3		3.15	2.8	2.52	2.8	3.5	19		2.7	2.7	2.6	2.0	2.47
4		3.0	2.9	2.53	2.7	3.7	20		2.7	2.85	2.7	2.25	2.18
5		2.95	3.0	2.5	2.6	3.75	21		2.7	2.75	2.75	2.1	2.0
6		2.9	3.0	2.5	2.4	3.6	22		2.7	2.75	2.9	2.15	Dry.
7		2.85	2.9	2.47	2.25	3.54	23		2.7	2.7	2.9	2.6	.....
8		2.8	2.8	2.45	2.2	3.65	24		2.7	2.65	2.9	2.62	.....
9		2.85	2.7	2.6	2.2	4.27	25		2.7	2.65	2.85	2.58	.....
10		2.85	2.7	2.75	2.4	4.2	26	2.8	2.68	2.65	2.75	2.62	.....
11		2.85	2.7	2.85	2.3	3.73	27	2.8	2.65	2.8	2.85	2.68	.....
12		2.8	2.7	2.8	2.15	3.55	28	2.8	2.65	2.7	2.9	2.75	.....
13		2.6	2.67	2.8	2.05	3.53	29	2.8	.....	2.65	2.75	2.8	.....
14		2.55	2.7	2.75	2.1	3.45	30	2.8	.....	2.7	2.7	2.65	.....
15		2.7	2.7	2.7	2.0	3.43	31	2.8	.....	2.65	.....	2.55	.....
16		2.8	2.65	2.7	2.25	3.25							

NOTE.—Station discontinued June 22.

HOBBLE CREEK BASIN.

HOBBLE CREEK NEAR SPRINGVILLE, UTAH.

Hobble Creek rises on the western slope of the Wasatch Mountains and flows in a gen southwesterly direction to Utah Lake. There is little overlying soil and but a sc growth of timber or brush. The steep, narrow canyon in which the stream flows is br here and there by narrow openings or flats, covered with a shallow deposit of bow and soil and comprising irrigated farms. As these tracts lie along the banks of the c a large part of the water used on them is returned to the stream as seepage. Ther no tributaries of importance, but short, intermittent streams, each of which is con to a steep, narrow canyon, enter all along the course. There are no storage reser lakes, or marshes to control the flood discharge, which occurs in the spring as the r of melting snow. The entire normal summer flow is used for irrigation, but the div takes place for the most part at the mouth of the canyon below the gaging station.

The station was established March 23, 1904. It is located about 1 mile above the m of the canyon, 4 miles southeast of Springville, Utah, 600 feet northeast of the he Mapleton Canal, and about 1,200 feet southwest of the Springville electric power

The channel is straight for about 75 feet above and 50 feet below the station. banks are high and wooded. The bed of the stream is of loose, fine gravel, and almost constantly. There is but one channel at all stages. The velocity ranges 3 to 4.5 feet per second. As the normal winter flow comes largely from springs, the s probably does not freeze at the station.

Discharge measurements are made by wading at a point near the gage. The initial for soundings is a 2 by 4 inch post located on the south bank near the water's edge.

The gage, which is read daily by J. B. Stevenson, an electrician, is a vertical staff, c into the bed of the stream and fastened at the top to an overhanging tree. The g referred to bench marks as follows: (1) A nail in the top of the 2 by 4 inch post u the initial point for soundings; elevation above gage datum, 4.91 feet. (2) A nai post set 26 feet south of the initial point; elevation above gage datum, 12.38 feet. 30-penny nail in the east side of a pole of the electric transmission line, 97 feet nort of the initial point; elevation, 21.80 feet above gage datum.

A description of this station, gage height and discharge data, and rating table ar tained in Water-Supply Paper No. 133 of the United States Geological Survey. 268–270.

Discharge measurements of Hobble Creek near Springville, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	I ch
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Se*
February 16...	H. S. Kleinschmidt	14	12	1.62	1.25	
April 5.....	W. G. Swendsen	18	11	2.57	1.42	
May 5.....	W. P. Hardesty	18	18	3.22	1.80	
May 23.....	W. G. Swendsen	19	29	3.92	2.30	
June 6.....	A. B. Larson	18	17	3.84	1.75	
June 11.....	.....do	18	21	3.72	1.80	
June 26.....	.....do	18	16	2.82	1.55	
July 11.....	G. M. P. Dougall	18	9.2	2.35	1.30	
July 17.....	.....do	18	9.8	2.30	1.30	
July 29.....	G. S. Schow	18	8.7	2.21	1.16	
August 9.....	.....do	18	9.5	2.15	1.25	
August 16.....	.....do	17	9.6	1.84	1.24	
August 30.....	A. B. Larson	17	9.7	1.48	1.21	
September 16..	G. S. Schow	17	8.7	1.65	1.20	
September 28..	A. B. Larson	17	8.3	1.60	1.19	
October 12.....	W. D. Beers	16	7.8	1.61	1.20	

Daily gage height, in feet, of Hobble Creek near Springville, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	1.38	1.35	1.4	2.1	1.75	1.35	1.15	1.25	1.2	1.23	1.25
.....	.....	1.4	1.35	.....	2.05	1.8	1.35	1.2	1.25	1.2	1.25	1.22
.....	.....	1.4	1.35	1.4	1.95	.....	1.3	1.3	1.25	1.18	1.22	1.2
.....	.....	1.4	1.35	.....	1.85	1.8	1.35	1.35	1.2	1.15	1.25	1.2
.....	1.3	1.4	1.4	.....	1.8	1.85	1.3	.....	1.2	1.12	1.25	1.2
.....	.....	1.4	1.4	1.45	1.75	1.8	1.26	1.2	1.2	1.12	1.22	1.18
.....	.....	1.38	1.4	.....	1.7	1.8	1.24	1.25	1.25	1.1	1.23	1.2
.....	.....	1.38	1.4	1.5	1.75	2.0	1.25	1.2	1.3	1.1	1.25	1.2
.....	.....	1.38	1.4	1.5	1.75	1.92	1.25	.....	1.3	1.12	1.28	1.2
.....	.....	1.38	.....	1.8	1.75	1.8	1.25	1.22	1.25	1.13	1.3	1.1
.....	.....	.....	1.4	1.6	1.8	1.75	1.25	1.2	1.25	1.15	1.27	1.17
.....	.....	.....	.....	1.6	1.8	1.75	1.25	1.2	1.25	1.17	.....	1.15
.....	1.3	.....	1.4	1.6	1.9	1.75	1.25	1.15	1.25	1.2	1.2	1.15
.....	.....	.....	1.4	.....	1.95	1.85	1.25	1.2	1.25	1.18	1.22	1.18
.....	.....	1.38	1.4	1.6	2.05	1.8	1.3	1.25	1.25	1.17	1.23	1.2
.....	.....	1.35	1.4	1.7	2.1	1.7	1.3	1.2	1.25	1.2	1.22	1.25
.....	1.3	.....	1.4	1.6	2.3	1.6	1.3	1.2	1.25	1.2	1.23	1.22
.....	.....	1.35	1.4	.....	2.35	1.6	1.3	1.14	1.25	1.2	1.2	1.25
.....	1.3	.....	1.4	1.7	2.4	1.65	1.3	1.12	1.22	1.18	1.18	1.25
.....	.....	1.35	1.45	.....	2.35	1.6	1.25	1.2	1.2	1.17	1.2	1.23
.....	.....	1.35	1.4	1.62	2.4	1.53	1.3	1.15	1.2	1.2	1.2	1.22
.....	.....	1.35	1.4	1.65	2.45	1.5	1.3	1.12	1.25	1.2	1.25	.....
.....	1.35	1.35	1.4	1.7	2.4	1.55	1.25	1.16	1.2	1.2	1.22	.....
.....	.....	1.35	1.4	1.7	2.25	1.5	1.2	2.06	1.2	1.2	1.23	.....
.....	1.35	1.35	1.35	1.7	2.2	1.5	1.8	1.25	1.2	1.2	1.2	1.15
.....	.....	1.35	1.35	1.85	2.1	1.55	1.2	1.27	1.2	1.18	1.2	1.15
.....	1.33	1.35	1.45	1.95	2.0	1.5	1.2	1.25	1.2	1.18	1.25	1.25
.....	.....	1.35	1.4	2.0	1.9	1.45	1.15	1.25	1.2	1.17	1.25	1.22
.....	.....	.....	1.4	2.0	1.7	1.42	1.15	1.3	1.35	1.2	1.25	.....
.....	1.33	.....	1.4	.....	1.7	1.4	1.15	1.2	1.2	1.2	1.25	1.23
.....	1.35	.....	1.35	.....	1.7	.....	1.2	1.2	.....	1.22	.....	.....

ation rating table for Hobble Creek near Springville, Utah, from January 1, to May 30, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.30	22.0	1.60	40.5	1.90	68	2.20	100
1.40	27.5	1.70	48.5	2.00	78	2.30	112
1.50	33.5	1.80	58	2.10	89	2.40	125

NOTE.—The above table is applicable only for open-channel conditions. It is based on four discharge asurements made during 1905. It is fairly well defined.

ation rating table for Hobble Creek near Springville, Utah, from May 31, to December 31, 1905.

Gage height.	Discharge	Gage height	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.10	7.0	1.40	30.5	1.70	61	2.00	99
1.20	14.5	1.50	40	1.80	73	2.10	113
1.30	22.0	1.60	50	1.90	86		

NOTE.—The above table is applicable only for open-channel conditions. It is based on nine discharge asurements made during 1905. It is well defined between gage heights 1.2 feet and 1.8 feet.

Estimated monthly discharge of Hobble Creek near Springville, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	24	22	22.8	1,402
February	28	24	25.6	1,422
March	30	24	27.0	1,660
April	78	28	45.2	2,690
May	132	48	81.0	4,980
June	99	30	59.4	3,534
July	26	11	18.6	1,144
August	107	8	18.3	1,125
September	26	14	17.1	1,018
October	16	7	12.5	769
November	22	13	16.9	1,006
December	18	7	14.6	898
The year	132	7	29.9	21,650

NOTE.—Open-channel conditions assumed throughout the year. Discharge interpolated for missing gage heights.

SPANISH FORK BASIN.

SPANISH FORK NEAR SPANISH FORK, UTAH.

Spanish fork rises in the Wasatch Mountains and flows northwestward into Utah Lake. The area is generally barren, with but little timber or brush. The stream is confined to a steep, narrow canyon, with a very few small openings in which are irrigated farms. The tributaries are all short and many of them are intermittent. The most important are Diamond Fork and Thistle Creek, which enter about 8 and 10 miles, respectively, above the gaging station, and which, like the main stream, occupy steep narrow canyons. The normal flow comes largely from springs, scattered over the entire basin; the flood discharge is direct surface run-off from melting snow.

There are no storage reservoirs on the stream and but little of the flow is diverted above the station. The entire normal flow is, however, diverted at the mouth of the canyon, immediately below the station, and used for the irrigation of lands near Utah Lake.

The station was established May 23, 1900, and reestablished March 26, 1903. It is located 600 feet above the dam of the East Bench Irrigation Company, 5 miles southeast of Spanish Fork, and 300 feet southwest of the main line of the Rio Grande Western Railway.

Records at this station are of importance in connection with the Strawberry Valley storage reservoir project, under a plan to divert water from that basin into Spanish Fork near its head and carry it to distribution canals below.

The channel is straight for about 150 feet above and below the station. Both banks slope gradually, are covered with small brush, and are sufficiently high to prevent overflow. The bed is composed of loose gravel and sand, and is smooth but somewhat shifting, especially at flood stages. The velocity is high. There is a free flow, the current being uninterrupted by dams or other obstructions.

Discharge measurements are made by means of a cable and car. The cable is graduated with paint, beginning at the right cable post, which is the initial point for soundings.

The gage, which is read daily by Levi Thorp, a section foreman on the Rio Grande Western Railway, consisted originally of a vertical staff located on the right bank of the stream. In April, 1905, it was replaced by a new 6 by 6 inch inclined gage having the same datum. The bench mark is on a limestone rock 29 feet S. 36° E. from the gage, marked with black paint "U. S. G. S."; elevation above gage datum, 7.16 feet; elevation above mean sea level, 4,785 feet.

on in regard to this station is contained in the following publications of the es Geological Survey (Ann.=Annual Report; WS=Water-Supply Paper):

: WS 100, p 145; 133, p 271.
WS 100, p 145; 133, p 271.
monthly: Ann 13, iii, p 97; WS 100, p 147; 133, p 273.
yearly: Ann 13, iii, p 99; 20, iv, p 61.
:s: WS 100, p 146; 133, p 272.
e: WS 100, pp 146-147; 133, pp 272-273.

harge measurements of Spanish Fork near Spanish Fork, Utah, in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.. H. S. Kleinschmidt	37	30	2.68	1.42	79
.....do	35	28	2.66	1.38	74
.....do	37	29	2.51	1.40	72
.. W. G. Swendsen	39	39	3.17	1.70	111
.. W. P. Hardesty	36	44	3.50	1.90	154
.. W. G. Swendsen	37	49	4.04	2.00	200
.....do	40	85	4.34	2.82	369
.....do	40	85	4.42	2.82	376
.....do	40	85	4.00	2.82	360
.. A. B. Larson	38	68	4.59	2.45	314
.....do	37	49	3.99	2.04	195
.....do	35	30	2.85	1.60	86
.. Beers and Schow	34	25	2.19	1.40	54
.. G. S. Schow	40	21	1.99	1.32	43
.. A. B. Larson	34	20	2.60	1.41	52
.. G. S. Schow	35	25	2.56	1.47	64
.....do	34	20	2.39	1.38	49
.. A. B. Larson	34	22	2.35	1.41	52
.. W. D. Beers	33	24	2.46	1.48	59

y gage height, in feet, of Spanish Fork near Spanish Fork, Utah, for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
...	1.4	1.46	1.6	1.5	2.06	2.56	1.52	1.36	1.36	1.64	1.48	1.46
...	1.26	1.56	1.56	1.48	2.04	2.52	1.5	1.34	1.36	1.56	1.48	1.44
...	1.5	1.5	1.62	1.48	2.02	2.48	1.5	1.4	1.36	1.44	1.48	1.4
...	1.32	1.5	1.54	1.46	1.96	2.38	1.46	1.36	1.61	1.44	1.48	1.44
....	1.4	1.5	1.5	1.48	1.92	2.26	1.44	1.36	1.42	1.42	1.48	1.5
...	1.56	4.48	1.5	1.48	1.82	2.24	1.46	1.36	1.4	1.44	1.48	1.4
...	1.4	1.46	1.48	1.5	1.82	2.14	1.46	1.3	1.44	1.45	1.48	1.44
...	1.4	1.46	1.48	1.52	1.84	2.1	1.46	1.3	1.42	1.42	1.48	1.44
...	1.4	1.4	1.46	1.54	1.98	2.02	1.4	1.3	1.4	1.42	1.48	1.44
...	1.42	1.42	1.46	1.76	1.96	2.02	1.42	1.36	1.4	1.48	1.48	1.4
...	1.44	1.44	1.46	1.7	1.9	2.0	1.42	1.5	1.4	1.48	1.48	1.3
...	1.4	1.26	1.44	1.7	1.84	1.96	1.4	1.4	1.4	1.48	1.48	1.24
...	1.38	1.6	1.46	1.66	2.0	1.88	1.38	1.38	1.4	1.46	1.4	1.25
...	1.42	1.4	1.48	1.64	2.0	1.82	1.4	1.38	1.4	1.46	1.44	1.4
...	1.42	1.4	1.48	1.62	2.0	1.76	1.4	1.36	1.4	1.48	1.44	1.3
...	1.44	1.34	1.44	1.7	2.04	1.76	1.4	1.34	1.4	1.48	1.44	1.25
...	1.42	1.44	1.46	1.7	2.22	1.74	1.4	1.34	1.34	1.48	1.46	1.3
....	1.42	1.42	1.46	1.66	2.41	1.76	1.38	1.34	1.34	1.46	1.46	1.3
...	1.34	1.4	1.5	1.74	2.54	1.78	1.38	1.32	1.38	1.44	1.46	1.3
...	1.44	1.44	1.6	1.72	2.64	1.78	1.36	1.32	1.38	1.44	1.44	1.3

Daily gage height, in feet, of Spanish Fork near Spanish Fork, Utah, for 1905—Continued.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
21	1.44	1.48	1.6	1.72	2.74	1.78	1.34	1.32	1.36	1.44	1.44	1.4
22	1.44	1.48	1.52	1.7	2.84	1.74	1.36	1.3	1.36	1.48	1.5	1.35
23	1.46	1.46	1.5	1.74	2.94	1.72	1.34	1.3	1.36	1.48	1.5	1.4
24	1.44	1.48	1.5	1.76	2.84	1.66	1.34	1.32	1.34	1.48	1.5	1.4
25	1.46	1.48	1.5	1.78	2.74	1.6	1.34	1.66	1.44	1.48	1.46	1.4
26	1.42	1.48	1.48	1.86	2.8	1.6	1.34	1.42	1.48	1.48	1.46	1.4
27	1.36	1.46	1.5	1.92	2.74	1.58	1.34	1.46	1.5	1.48	1.	1.4
28	1.38	1.5	1.5	1.98	2.78	1.58	1.34	1.48	1.46	1.48	1.46	1.5
29	1.44	.....	1.52	1.97	2.7	1.56	1.34	1.4	2.22	1.48	1.46	1.7
30	1.46	.....	1.54	2.0	2.6	1.54	1.34	1.38	1.64	1.48	1.46	1.45
31	1.44	.....	1.46	.....	2.56	.....	1.34	1.34	.....	1.5	..	1.45

NOTE.—January 3 and 6 and February 13, backwater caused by ice; open-channel conditions during the remainder of the winter months. Gage February 6 probably in error.

Daily discharge, in second-feet, of Spanish Fork near Spanish Fork, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	57	86	112	79	192	336	56	48	45	92	60	61
2	39	106	104	76	187	329	54	46	45	76	60	59
3	43	95	115	75	182	322	54	54	45	54	61	53
4	47	95	100	71	168	292	48	48	89	54	61	59
5	57	95	92	74	158	258	47	48	53	50	61	60
6	59	91	92	74	136	252	49	48	50	53	62	53
7	60	87	88	77	136	224	50	42	59	50	62	59
8	61	87	88	81	140	212	51	42	53	50	62	59
9	62	75	84	83	172	190	43	42	52	50	62	59
10	66	79	83	127	168	188	46	46	52	60	62	53
11	70	83	82	114	154	180	47	68	52	60	63	41
12	64	52	78	113	145	168	44	52	52	59	63	35
13	60	64	81	109	189	147	43	49	52	55	50	30
14	69	76	85	100	195	132	46	49	52	55	56	34
15	69	77	84	96	200	118	46	46	52	59	56	42
16	74	65	76	112	203	116	46	44	52	59	56	36
17	71	74	80	112	242	110	47	44	44	59	59	42
18	72	71	79	102	286	112	44	44	44	56	59	42
19	58	76	86	119	315	115	45	41	48	54	59	42
20	77	83	105	114	335	113	43	41	48	54	57	42
21	78	91	105	114	355	111	42	41	45	54	57	55
22	79	91	89	111	375	102	43	38	45	59	67	46
23	81	85	84	119	410	96	42	38	45	59	67	55
24	80	89	84	122	384	81	42	41	43	59	67	55
25	83	89	83	127	360	68	43	95	55	59	60	56
26	76	89	79	144	382	67	43	53	62	60	60	56
27	67	85	82	158	368	64	44	58	66	60	68	56
28	70	94	82	172	383	65	44	62	58	60	61	70
29	82	.....	85	170	364	62	45	50	228	60	61	110
30	85	.....	88	178	340	58	45	47	92	60	61	65
31	82	.....	72	.....	331	.....	46	43	.....	65	.....	65

NOTE.—Daily discharge obtained by indirect method for shifting channels. Discharge January 3 and 6 and February 13 reduced on account of backwater from ice. Discharge February 6 interpolated between February 5 and 7 on assumption that gage height of February 6 was in error.

ated monthly discharge of Spanish Fork River near Spanish Fork, Utah, for 1905.

[Drainage area, 670 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	85	39	67.7	4,163	0.101	0.116
.....	106	52	83.2	4,621	.124	.129
.....	115	72	88	5,411	.131	.151
.....	178	71	111	6,605	.166	.185
.....	410	136	257	15,800	.384	.443
.....	336	58	156	9,283	.233	.260
.....	56	42	46.1	2,835	.069	.080
.....	95	38	48.6	2,988	.073	.084
r.....	228	43	59.3	3,529	.089	.099
.....	92	50	58.5	3,597	.087	.100
r.....	68	50	60.7	3,612	.091	.102
.....	114	35	54.7	3,363	.082	.094
year.....	410	35	90.9	65,810	1.36	1.84

SPANISH FORK NEAR LAKE SHORE, UTAH.

tation was established December 10, 1903, at the highway bridge on the road Spanish Fork and Lake Shore, about 3 miles west of Spanish Fork. In May, 1904, established at a point about 800 feet above the bridge.

entire normal summer flow is diverted at a point above, the station is maintained ing the spring and winter, the object being the determination of the amount of water ed by Spanish Fork into Utah Lake.

annel is straight for about 75 feet above and is slightly curved for 100 feet below on. Both banks are barren and sufficiently high to prevent overflow. The bed oint is composed of fine gravel and sand, smooth but continually shifting. The ranges from 2 to 4 feet per second, and the depth from 1 foot to 3 feet. Informa- egard to winter conditions are incomplete.

rge measurements are made from a cable and car. The cable is marked at 4-foot , beginning at the right cable post, which is the initial point for soundings.

gage readings are made by J. W. Bowen, a farmer. The original gage was a vertical en into the bed of the stream about 10 feet below the bridge. This was abandoned eginning of 1905, and readings have since been taken from the new vertical gage n the right bank near the cable. It consists of a 2 by 4 inch fir post, driven into the e stream and supported at the top by a horizontal piece buried in the bank. The the same as that of the old gage, but simultaneous readings will not agree, as there erable fall to the stream between the two gages. The gage is referred to bench follows: (1) A 30-penny nail driven into a log on the west abutment of the bridge, northwest corner, 10.5 feet S. 18° 30′ W., from the old gage; elevation above gage 1.68 feet. (2) A 20-penny nail driven into the north side of a cedar fence post, 91 5° 30′ E., from the gage; elevation above gage datum, 21.95 feet. (3) A United eological Survey standard metallic post set 197 feet S. 21° 45′ E. from the old gage; above gage datum, 21.76 feet.

ation in regard to this station is contained in the following Water-Supply Papers nited States Geological Survey:

tion: 133, p 274.
ge: 100, p. 224; 133, p. 275.
ge, monthly: 133, p. 276.
ights: 133, p 275.
table: 133, p 276.

Discharge measurements of Spanish Fork near Lake Shore, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 27	H. S. Kleinschmidt	30	26	2.57	4.61	66
February 15	do	26	21	2.31	4.37	49
March 10	do	28	18	2.27	4.12	42
April 6	W. G. Swendsen	28	23	2.41	4.35	55
April 20	do	32	36	2.67	4.78	96
May 4[a]	W. P. Hardesty	6	6.7	2.84	3.85	19
May 22	W. G. Swendsen	24	15	2.55	4.05	38
December 4	do	28	18	2.16	4.12	39

[a] 30 feet below regular station.

Daily gage height, in feet, of Spanish Fork near Lake Shore, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	Nov.	Dec.	Day.	Jan.	Feb.	Mar.	Apr.	May.	Nov.	Dec.
1	4.6	4.67	4.52	4.5	4.75	.....	4.0	17	4.62	4.6	4.08	4.9	3.4	.....	4.3
2	4.1	4.97	4.58	4.35	4.3	.....	4.2	18	4.6	4.6	4.1	5.0	4.0	.....	4.3
3	4.2	4.85	4.52	4.33	4.2	.....	4.2	19	4.5	4.59	4.15	4.9	4.02	.....	4.1
4	4.2	4.8	4.5	4.3	3.85	.....	4.2	20	4.6	4.58	4.3	4.85	3.7	.....	4.1
5	4.1	4.73	4.55	4.31	3.6	.....	4.18	21	4.6	4.6	4.25	4.72	3.7	.....	4.1
6	4.4	4.7	4.53	4.35	3.48	.....	4.1	22	4.63	4.61	4.3	4.71	3.9	.....	4.1
7	4.2	4.68	3.9	4.48	3.43	.....	4.05	23	4.7	4.55	4.3	4.63	4.3	.....	4.2
8	4.45	4.61	4.1	4.58	3.42	.....	4.0	24	4.63	4.55	4.2	4.73	4.03	.....	4.2
9	4.45	4.5	4.11	4.68	3.43	.....	.....	25	4.62	4.55	4.2	4.65	3.5	.....	4.2
10	4.2	4.58	4.15	5.1	3.4	.....	4.0	26	4.61	4.58	4.0	4.68	3.55	.....	4.3
11	4.62	4.6	4.05	4.98	3.42	.....	4.1	27	4.6	4.58	4.15	4.79	3.5	.....	4.3
12	4.7	4.2	4.1	4.88	3.43	.....	4.2	28	4.59	4.51	4.1	4.82	3.53	.....	4.2
13	4.6	4.1	4.12	4.8	3.4	.....	4.2	29	4.58	.....	4.1	4.8	3.4	.....	4.3
14	4.8	4.39	4.2	4.85	3.38	.....	4.3	30	4.6	.....	4.12	4.72	3.0	4.0	4.25
15	4.6	4.38	4.15	4.88	3.38	.....	4.3	31	4.61	.....	4.11	.....	3.0	.....	.....
16	4.6	4.52	4.1	4.9	3.38	.....	4.1								

Daily discharge, in second-feet, of Spanish Fork near Lake Shore, Utah., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	Nov.	Dec.	Day.	Jan.	Feb.	Mar.	Apr.	May.	Nov.	Dec.
1	53.0	71.0	67.0	77.0	83.0	.....	31.5	17	62.0	67.0	41.5	108.0	7.5	.....	51.5
2	22.5	95.5	71.5	65.0	46.0	.....	44.5	18	61.0	67.5	43.0	116.0	33.5	.....	51.5
3	28.0	85.5	68.0	63.5	38.2	.....	44.5	19	53.0	67.0	46.5	106.0	35.0	.....	39.0
4	29.5	81.2	67.0	61.0	19.0	.....	38.5	20	61.0	67.0	58.0	96.0	18.5	.....	38.0
5	23.0	76.0	72.0	62.5	10.3	.....	43.5	21	62.0	69.0	54.0	89.5	19.3	.....	38.0
6	41.0	73.0	71.5	66.0	7.0	.....	38.0	22	65.0	70.5	58.0	88.0	28.5	.....	38.0
7	29.5	72.2	27.5	76.0	6.5	.....	34.7	23	71.0	66.0	58.0	80.0	54.5	.....	44.5
8	45.5	66.0	39.0	83.5	6.0	.....	32.0	24	65.5	66.5	51.0	88.0	36.5	.....	44.5
9	46.0	58.0	41.5	92.0	6.5	.....	32.0	25	64.5	67.5	51.5	80.5	11.2	.....	44.5
10	30.0	64.5	42.0	129.0	6.0	.....	32.0	26	65.0	70.5	38.0	82.0	13.0	.....	51.5
11	58.5	66.0	37.5	117.5	6.5	.....	38.0	27	66.0	71.5	48.0	90.0	11.0	.....	51.5
12	66.0	36.0	41.0	108.0	7.0	.....	44.5	28	64.5	65.5	45.0	91.0	12.0	.....	44.5
13	58.5	30.5	42.5	100.0	6.5	.....	44.5	29	63.5	.....	45.2	89.0	7.5	0.0	51.5
14	75.0	50.0	48.5	104.0	6.2	.....	51.5	30	65.0	.....	46.5	80.0	0.0	32.5	48.0
15	59.0	49.0	45.5	106.5	6.5	.....	51.5	31	65.5	.....	46.0	.....	0.0	.....	48.0
16	60.0	59.5	42.0	108.0	6.8	.....	38.5								

NOTE.—Total flow of river diverted for irrigation May 30 to November 29. Daily discharge obtained by indirect method for shifting channels. Discharge interpolated December 9 and 31.

Estimated monthly discharge of Spanish Fork near Lake Shore, Utah, for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
ıry	75	22.5	54.2	3,333
ıary	95.5	30.5	66.0	3,665
ı	72	27.5	50.1	3,080
	129	61	90.1	5,361
	83	0	17.9	1,101
	0	0	0	0
	0	0	0	0
st	0	0	0	0
mber	0	0	0	0
ber	0	0	0	0
mber	32.5	0	1.08	64
nber	51.5	31.5	42.7	2,626
The year	129	0	26.8	19,230

SEVIER RIVER BASIN.

SEVIER RIVER NEAR GUNNISON, UTAH.

vier River rises in the northwestern part of Kane County, in southern Utah, flows ıeastward to a point near Gunnison, northwestward nearly to Leamington, and then s sharply to the southwest and discharges into Sevier Lake.

ibutary streams are few, San Pitch River and Salina Creek being the most important. San Pitch joins the main stream about 3 miles above the gaging station, but since its is used for irrigation and is completely controlled by storage reservoirs, it furnishes of the supply. Salina Creek, which enters about 15 miles above the station, is subject ıpid run-off and during flood seasons carries an immense amount of sediment.

ıere is considerable irrigation from the Sevier above Gunnison, and a few small storage voirs control the flood discharge.

ıe station was established June 29, 1900. It is located at the wagon bridge over the er about 4 miles west of Gunnison, on the road to Westview precinct.

ıe channel is straight for about 300 feet above and below the station, with banks suffily high to prevent overflow. The bed of the stream is composed of sand and gravel is smooth and apparently permanent. The current is sluggish at low water, but at ıary stages ranges from 2 to 3 feet per second. At the high-water section the velocity ıatest at the right side, decreasing somewhat uniformly toward the left, where it is low. ting ice during the winter season may make records at certain stages impossible. e is a free flow at the low-water but not at the high-water section.

ıring ordinary stages discharge measurements are made from the upstream side of the ge, the floor of which is marked at 5-foot intervals, beginning at the bridge pile to which gage is attached, this being the initial point for soundings. At extreme low water the ity at this point is too low for favorable results, and measurements are made by wading point about 75 feet below the bridge, marked by a 2 by 4 inch post on each bank. The l point for soundings at this section is the post on the left bank.

ıe gage is read daily by L. H. Erickson, a farmer. The original gage is a 1 by 4 inch piece dwood nailed vertically to a bridge pier on the right bank on the upstream side of the ge. In January, 1905, a new 6 by 6 inch inclined gage was established at a point about 25 below the old one. It is fastened to double posts set in the bank. Both gages have the datum and are referred to bench marks as follows: (1) A large spike driven into the side edar post 46 feet S. 74° E. from the gage; elevation, 8.55 feet. (2) A nail in the top of ıg post at the northeast corner of the bridge 13 feet north of the gage; elevation, 13.18 (3) A United States Geological Survey standard iron post set in the ground 153 feet S. 30′ E. from the old gage; elevation, 10.10 feet. Elevations are above datum of gage.

Information in regard to this station is contained in the following publications of United States Geological Survey (Ann=Annual Report; WS = Water-Supply Paper:

Description: WS 51, p 425; 66, p 126; 85, p 88; 100, pp 147–148; 133, pp 277–278.
Discharge: WS 51, p 425; 66, p 126; 85, p 88; 100, p 148; 133, p 278.
Discharge, monthly: Ann 22, iv, p 420; WS 75 p 197; 85, p 90; 100, p 149; 133, p 280.
Gage heights: WS 51, p 426; 66, p 126; 85, p 89; 100, pp 148–149; 133, p 279.
Hydrograph: Ann 22, iv, p 420.
Rating tables: WS 52, p 521; 66, p 176; 85, p 89; 100, p 148; 133, p 280.

Discharge measurements of Sevier River near Gunnison, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Di cha
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Sec fe*
January 19[a]	C. Tanner	50	123	2.60	2.25	
Febrary 7[a]	do	50	120	2.50	2.20	
April 23	W. G. Swendsen	36	35	1.47	.80	
June 19	C. S. Jarvis	35	32	1.51	.76	
July 1	do	30	22	.89	.42	
August 11	do	29	25	1.17	.53	

[a] Measured at bridge.

Daily gage height, in feet, of Sevier River near Gunnison, Utah, for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.
1	.....	.....	2.4	1.1	.72	2.8	.4	.5	.7	.86	.....
2	.....	.....	2.4	1.1	.7	2.86	.4	.5	.7	1.0	1.16
3	.....	.....	2.44	1.1	.7	2.96	.4	.5	.9	1.0	1.16
4	.....	.....	2.34	1.1	.72	2.7	.4	.5	.86	1.02	1.16
5	.....	.....	2.28	1.14	.7	2.46	.....	.5	.7	1.06	1.14
6	.....	2.3	2.1	1.1	.7	2.38	.4	.5	.7	1.06	1.14
7	.....	2.2	1.88	1.1	.7	2.36	.4	.54	.74	1.08	1.16
8	.....	2.2	1.7	1.12	.76	2.24	.42	.54	.74	1.1	1.16
9	.....	2.16	1.76	.....	.78	2.2	.4	.54	.76	1.1	1.14
10	.....	2.22	1.96	1.12	.84	1.76	.4	.54	.9	1.14	1.14
11	.....	2.18	1.9	1.12	.96	1.76	.42	.54	.86	1.16	1.12
12	.....	2.26	1.88	1.06	.98	1.56	.4	.56	.7	1.18	1.12
13	.....	2.6	1.84	1.0	1.0	1.2	.4	.56	.7	1.18	1.12
14	.....	3.1	1.8	.9	1.04	1.1	.4	.56	.72	1.2	1.12
15	.....	2.0	1.76	.9	1.24	.9	.4	.56	.7	1.18	1.14
16	.....	2.0	.....	.86	1.56	.9	.42	.56	.7	1.14	1.12
17	.....	2.02	1.64	.84	1.58	.8	.42	.56	.7	1.1	1.12
18	2.0	2.0	1.6	.78	1.6	.82	.4	.56	.7	1.1	1.1
19	2.25	2.0	1.58	.8	1.66	.82	.4	.56	.7	1.1	1.1
20	2.2	2.0	1.62	.8	1.7	.76	.4	.58	.7	1.1	1.1
21	2.2	2.12	1.56	.78	1.74	.7	.....	.58	.7	1.12	1.1
22	2.2	2.22	.....	.78	1.76	.56	.4	.58	.7	1.16	1.1
23	2.06	2.26	1.5	.....	1.94	.52	.4	.6	.72	1.16	1.12
24	2.2	2.38	1.4	.9	2.44	.5	.4	.6	.74	1.16	1.12
25	2.22	2.38	1.4	.82	3.25	.46	.4	.6	.74	1.16	1.12
26	2.24	2.38	1.34	.78	3.23	.44	.44	.86	.78	1.14	1.12
27	2.26	2.3	1.24	.78	3.3	.42	.44	.96	.78	1.14	1.14
28	2.22	2.3	.....	.74	3.32	.4	.52	.8	.8	1.16	1.14
29	2.22	.....	1.16	.7	3.22	.4	.52	.74	.82	1.16	1.14
30	2.26	.....	1.1	.7	3.24	.4	.5	.7	.86	1.16	1.14
31	2.24	.....	1.14	.....	2.6	.....	.5	.7	.....	1.18	.....

NOTE.—River frozen January 1–17 and December 16–31.

rating table for Sevier River near Gunnison, Utah, from January 18 to December 15, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.40	17	1.20	101	2.00	254	2.80	474
0.50	24	1.30	116	2.10	278	2.90	506
0.60	32	1.40	132	2.20	303	3.00	539
0.70	41	1.50	149	2.30	329	3.10	573
0.80	51	1.60	168	2.40	356	3.20	608
0.90	62	1.70	188	2.50	384	3.30	644
1.00	74	1.80	209	2.60	413	3.40	681
1.10	87	1.90	231	2.70	443		

E.—The above table is applicable only for open-channel conditions. It is based on six discharge rements made during 1905. It is well defined between gage heights 0.4 foot and 1 foot and fairly fined above 1 foot.

Estimated monthly discharge of Sevier River near Gunnison, Utah, for 1905.

[Drainage area, 3,986 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ry 18–31	319	254	303	8,414	0.076	0.040
ary	573	254	318	17,660	.080	.083
	367	87	199	12,240	.050	.058
	92	41	67.0	3,987	.017	.019
	651	41	222	13,650	.056	.065
	525	17	164	9,759	.041	.046
	26	17	18.4	1,131	.0046	.0053
st	69	24	32.3	1,986	.0081	.0093
mber	62	41	46.2	2,749	.012	.013
er	101	58	89.3	5,491	.022	.025
mber	95	87	91.4	5,439	.023	.026
aber 1–15	116	93	98.3	2,925	.025	.014
The period				85,430		

RE.—Discharge interpolated on days when gage heights were missing.

SAN PITCH RIVER NEAR GUNNISON, UTAH.

n Pitch River, which enters Sevier River from the north, flows throughout its course well-defined channel with no overflow. Over the lower portions of the area evapora- and seepage doubtless exceed inflow to the stream. There are small tracts of irrigated at various points along the river, and a storage reservoir about 10 miles above the ıg station completely controls the flow. The tributaries are few and mostly inter- ent. Manti Creek, which enters at a point about 11 miles above the station, drains ren area and is subject to rapid run-off. Its discharge may vary from 4 to 150 second- but it enters above the reservoir dam and is thus completely controlled before reach- he gaging station.

ıe station was established June 30, 1900. It is located 4 miles northeast of Gunnison t one-eighth mile west of the Rio Grande Western Railway, west of the second farm- e along the railroad track north of Gunnison station.

The channel is straight for about 100 feet above and is slightly curved below the station. Both banks slope gradually and are sufficiently high to prevent overflow. The bed of the stream is composed of sand and gravel, and is smooth and apparently permanent. The velocity is high. Information in regard to winter conditions is indefinite.

Discharge measurements are made by wading at a point near the gage, where a tagged wire is stretched. The initial point for soundings is the west side of the supporting post on the left bank.

The gage, which is read daily by Oliver Peterson, is a vertical staff driven into the stream bed. It is referred to bench marks as follows: (1) The top of a cedar post set about 45.5 feet west from the gage; elevation, 5.96 feet. (2) Top of nail driven into top of stake set about 150 feet S. 84° E. from the initial point; elevation, 10.36 feet. Elevations are above datum of gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: WS 51, p 425; 66, p 125; 85, p 94; 100, p 150; 133, p 281.
Discharge: WS 51, p 425; 66, p 125; 85, p 94; 100, p 150; 133, p 281.
Discharge, monthly: Ann 22, iv, p 419; WS 75, p 196; 85, p 96; 100, p 152; 133, p 283.
Gage heights: WS 51, p 425; 66, p 125; 85, p 95; 100, p 151; 133, p 282.
Hydrograph: Ann 22, iv, p 419.
Rating tables: WS 52, p 521; 66, p 176; 85, p 95; 100, p 151; 133, p 282.

Discharge measurements of San Pitch River near Gunnison, Utah, in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 18	C. Tanner	23	20	0.60	1.76	12
June 19	C. S. Jarvis	31	40	2.92	2.46	116
July 1	do	29	36	2.63	2.40	95
August 12	do	29	40	2.88	2.46	114

Daily gage height, in feet, of San Pitch River near Gunnison, Utah, for 1905

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.78	1.78	1.8	1.76	2.44	3.0	2.44	2.54	2.0	2.08	1.96	1.9
2	1.78	1.9	1.78	1.78	2.4	2.9	2.56	2.5	2.06	2.04	1.96	1.9
3	1.78	1.9	1.78	1.78	2.3	2.76	2.54	2.52	2.04	2.04	2.0	1.9
4	1.78	1.9	1.76	1.78	2.3	2.8	2.54	2.5	2.06	2.02	2.0	1.9
5	1.8	1.88	1.76	1.78	2.3	3.1	2.5	2.5	2.08	2.02	1.98	1.9
6	1.8	1.88	1.76	1.78	2.36	2.82	2.58	2.5	2.08	2.02	1.96	1.9
7	1.8	1.86	1.74	1.8	2.3	2.88	2.6	2.5	2.02	2.0	1.96	1.9
8	1.78	1.84	1.7	1.8	2.32	2.9	2.68	2.5	2.04	2.0	1.96	1.9
9	1.78	1.8	1.7	1.8	2.5	2.88	2.66	2.5	2.02	2.0	1.98	1.9
10	1.78	1.74	1.68	1.84	2.5	2.86	2.64	2.5	2.02	2.0	1.96	1.9
11	1.8	1.74	1.68	1.8	2.5	3.0	2.66	2.5	2.04	1.94	1.92	1.9
12	1.8	1.72	1.7	1.8	2.5	3.14	2.64	2.56	2.02	1.94	1.92	1.9
13	1.73	1.7	1.72	1.8	2.52	2.88	2.64	2.46	2.0	1.94	1.92	1.9
14	1.78	1.7	1.73	1.8	2.6	2.9	2.6	2.44	2.06	1.94	1.92	1.9
15	1.76	1.7	1.78	1.8	2.6	2.88	2.64	2.44	2.06	1.94	1.92	1.9
16	1.78	1.68	1.78	1.8	2.78	2.8	2.64	2.46	2.04	1.92	1.92	1.9
17	1.78	1.68	1.78	1.82	2.74	2.7	2.6	2.42	2.03	1.94	1.92	1.9
18	1.76	1.68	1.78	1.84	2.52	2.78	2.6	2.4	2.02	1.94	1.94	1.9
19	1.78	1.68	1.78	1.84	2.8	2.6	2.6	2.36	2.02	1.94	1.94	1.9
20	1.76	1.68	1.8	1.84	2.34	2.52	2.6	2.36	2.02	1.96	1.96	1.9

Daily gage height, in feet, of San Pitch River near Gunnison, Utah, for 1905—Continued.

Daily.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.74	1.68	1.8	1.84	2.54	2.4	2.6	2.36	2.02	1.96	2.0	1.96
.....	1.74	1.78	1.8	1.8	3.24	2.5	2.6	2.36	2.02	1.96	2.0	1.96
.....	1.74	1.72	1.78	1.82	2.8	2.42	2.58	2.36	2.02	1.96	1.88	1.96
.....	1.74	1.74	1.78	1.88	2.78	2.44	2.54	2.36	2.0	1.96	1.88	1.9
.....	1.74	1.78	1.78	1.8	2.7	2.38	2.54	2.36	2.0	1.96	1.88	1.86
.....	1.74	1.78	1.66	1.9	2.6	2.34	2.54	2.3	2.0	1.96	1.9	1.86
.....	1.74	1.78	1.66	2.0	2.5	2.42	2.54	2.24	2.0	1.96	1.92	1.86
.....	1.76	1.8	1.68	2.34	2.6	2.4	2.54	2.22	1.96	1.96	1.9	1.86
.....	1.74	.....	1.66	2.34	2.4	2.42	2.56	4.15	2.3	1.96	1.9	1.86
.....	1.74	.....	1.68	2.36	2.32	2.42	2.56	2.36	2.08	1.96	1.9	1.86
.....	1.74	.....	1.73	.....	2.6	.....	2.56	2.2	.....	1.96	.....	1.86

tion rating table for San Pitch River near Gunnison, Utah, from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.70	10	2.10	49	2.50	123	2.90	227
1.80	15	2.20	64	2.60	146	3.00	258
1.90	24	2.30	82	2.70	171	3.10	290
2.00	35	2.40	102	2.80	198	3.20	324

he above table is applicable only for open-channel conditions. It is based on discharge measure-its made during 1902–1905. It is well defined between gage heights 1.65 feet and 2.5 feet.

Estimated monthly discharge of San Pitch River near Gunnison, Utah, for 1905.

[Drainage area, 836 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
uary	15	11	13.3	818	0.016	0.018
ruary	24	9	14.1	783	.017	.018
rch	15	8	12.1	744	.014	.016
ril	94	13	24.2	1,440	.029	.032
y	338	82	136	8,362	.163	.188
e	304	90	179	10,650	.214	.239
y	166	110	143	8,793	.171	.197
gust	720	64	126	7,747	.151	.174
tember	82	30	40.5	2,410	.048	.054
tober	46	26	32.0	1,968	.038	.044
vember	35	22	28.1	1,672	.034	.038
cember	30	20	23.9	1,470	.029	.033
The year	338	8	64.3	46,860	.077	1.05

OTE.—Open-channel curve assumed to apply throughout the year as the stream is known to freeze slightly at this station.

whence its waters find their way into Humboldt Sink. The tributaries follo
direction of the mountain ranges and flow either to the north or to the south.
stages the water of the river is almost wholly diverted, and for the future
of the country recourse must be had to the construction of storage reservoirs.

Of the tributaries, North Fork enters the stream west of Peko, Nev., and
about 10 miles below Elko. Pine Creek comes in from the south near P
Marys River is one of the headwater branches.

NORTH FORK OF HUMBOLDT RIVER NEAR ELBURZ.

This station was established October 10, 1902. It is located about on
above the junction of North Fork with the main River and 150 feet below
Pacific Railroad bridge. It is 2 miles west of the Southern Pacific Railro
Elburz. The nearest post-office is Halleck, Nev.

The channel is straight for 150 feet above and below the station. Both ba
but the left will overflow at extreme flood stages. The bed of the stream
of gravel and silt and changes slightly. There is but one channel at all st
current is sluggish.

Discharge measurements are made by means of a cable and car. The ini
soundings is the zero on the tagged wire.

The gage, which is read once each day by A. R. Blevins, is an inclined 4 by
fastened to the left bank just above the cable. The bench mark is a 4 by
driven into the ground on the left bank 20 feet upstream from the gage; el
zero of gage, 6.99 feet.

Information in regard to this station is contained in the following Water-S
of the United States Geological Survey:

Description: 100, p 163; 133, p 283.
Discharge: 100, p 164; 133, p 284.
Discharge, monthly: 133, p 285.
Gage heights: 100, p 164; 133, p 284.
Rating table: 133, p 285.

Discharge measurements of North Fork of Humboldt River near Elburz, Nev

ly gage height, in feet, of North Fork of Humboldt River near Elburz, Nev., for 1905.

ay.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	3.6	3.5	3.4	3.5	3.4	3.55	2.85	2.2	2.55	2.6	3.3	3.0
.....	3.6	3.5	3.4	3.5	3.5	3.55	2.85	2.2	2.55	2.6	3.3	3.0
.....	3.6	3.45	3.45	3.45	3.55	3.5	2.8	2.2	2.55	2.6	3.3	3.0
.....	3.6	3.4	3.45	3.45	3.55	3.55	2.8	2.2	2.55	2.6	3.3	3.0
.....	3.6	3.35	3.5	3.4	3.6	3.5	2.8	2.2	2.55	2.6	3.2	3.0
.....	3.55	3.35	3.5	3.35	3.6	3.5	2.8	2.15	2.55	2.6	3.1	3.0
.....	3.55	3.35	3.5	3.35	3.6	3.5	2.8	2.15	2.55	2.6	3.0	3.0
.....	3.6	3.3	3.5	3.3	3.65	3.5	2.8	2.15	2.55	2.6	3.0	3.0
.....	3.6	3.25	3.5	3.3	3.7	3.5	2.85	2.15	2.55	2.6	2.9	3.0
.....	3.55	3.2	3.5	3.3	3.65	3.45	2.85	2.15	2.55	2.6	2.9	3.0
.....	3.55	3.15	3.5	3.3	3.6	3.4	2.85	2.15	2.5	2.6	3.0	3.0
.....	3.55	3.3	3.4	3.3	3.65	3.35	2.85	2.15	2.5	2.6	3.0	3.0
.....	3.55	3.35	3.4	3.25	3.7	3.3	2.8	2.15	2.5	2.6	2.9	3.0
.....	3.55	3.4	3.4	3.25	3.6	3.3	2.8	2.15	2.5	2.6	2.9	3.0
.....	3.6	3.4	3.4	3.2	3.5	3.35	2.8	2.15	2.5	2.6	2.8	3.0
.....	3.6	3.4	3.45	3.25	3.5	3.4	2.75	2.15	2.5	2.6	2.8	3.0
.....	3.6	3.35	3.45	3.25	3.45	3.4	2.75	2.15	2.5	2.6	2.7	3.1
.....	3.6	3.3	3.5	3.3	3.4	3.3	2.75	2.15	2.5	2.6	2.7	3.1
.....	3.6	3.3	3.5	3.3	3.35	3.25	2.75	2.15	2.55	2.6	2.7	3.1
.....	3.8	3.3	3.5	3.3	3.35	3.2	2.7	2.15	2.55	2.6	2.7	3.2
.....	3.8	3.3	3.5	3.35	3.3	3.15	2.7	2.15	2.6	2.6	2.7	3.2
.....	3.8	3.3	3.5	3.35	3.35	3.15	2.7	2.2	2.6	2.6	2.7	3.3
.....	3.75	3.25	3.5	3.3	3.4	3.15	2.65	2.3	2.6	2.7	2.7	3.4
.....	3.7	3.3	3.45	3.3	3.45	3.15	2.65	2.4	2.6	2.7	2.7	3.4
.....	3.6	3.3	3.45	3.25	3.55	3.1	2.6	2.5	2.6	2.8	2.7	3.5
.....	3.6	3.3	3.5	3.3	3.55	3.1	2.55	2.5	2.6	2.9	2.8	3.5
.....	3.6	3.25	3.5	3.3	3.6	3.1	2.4	2.5	2.6	2.9	2.85	3.5
.....	3.6	3.3	3.45	3.3	3.6	3.0	2.32	2.55	2.6	3.0	2.9	3.5
.....	3.6	.....	3.45	3.35	3.6	3.0	2.3	2.55	2.6	3.1	3.0	3.5
.....	3.55	.....	3.45	3.4	3.55	3.0	2.25	2.6	2.6	3.2	3.0	3,5
.....	3.5	.....	3.5	.....	3.6	.....	2.2	2.6	.....	3.3	.....	.....

:.—Ice conditions exist at this station during the winter months. Ice 8 inches thick January 20.

i rating table for North Fork of Humboldt River near Elburz, Nev., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.30	0.0	2.70	0.8	3.10	14	3.50	41
2.40	.2	2.80	1.	3.20	20	3.60	49
2.50	.4	2.90	3.	3.30	27	3.70	57
2.60	.6	3.00	8.	3.40	34	3.80	66

:.—The above table is applicable only for open-channel conditions. It is based on four discharge ements made during 1905. Estimates based on this table can be considered only as approxi- nd especially so for low stages. Zero flow at 2.3 feet is based on observer's statement.

Estimated monthly discharge of North Fork of Humboldt River near Elburz, Nev., for 1905.

[Drainage area, 1,020 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	66	41	53.3	3,277	0.052	0.060
February	41	17	29.0	1,611	.028	.029
March	41	34	38.8	2,386	.038	.044
April	41	20	28.9	1,720	.028	.031
May	57	27	43.8	2,693	.043	.050
June	45	8	28.0	1,666	.027	.030
July	2	.0	.96	59	.00094	.0011
August	.6	.0	.12	7	.00012	.00014
September	.6	.4	.50	30	.00049	.00055
October	27	.6	2.9	178	.0028	.0032
November	27	.8	7.8	464	.0076	.0085
December	41	8	19.1	1,174	.019	.022
The year	66	0	21.1	15,270	.021	.279

NOTE.—Open-channel rating table applied to the winter months without correction. Winter estimates liable to some error.

SOUTH FORK OF HUMBOLDT RIVER NEAR ELKO, NEV.

This station was established August 29, 1896. It is located 10 miles southwest of the town of Elko, at Cislini's (formerly Mason's) ranch, and about 6 miles above the junction of South Fork with the main stream.

The channel is straight for some distance above and below the station and the banks are high. The bed of the stream is composed of gravel and is stable. There is a good site for a reservoir a short distance above the station.

Discharge measurements are made from a cable and suspended car at a point 1 mile above the gage.

The gage, which is placed near the farm of the observer, M. Cislini, for his convenience, is inclined and is spiked to posts driven firmly into the right bank. An inclined gage was installed November 22, 1902, at the site of the old one, the 4-foot marks of the old and new gages coinciding. The bench mark is a 4 by 4 inch timber driven 4 feet south of the gage; elevation above gage datum, 6.29 feet. A new gage was installed May 21, 1905, below a dam which was built just below the old gage. All gage heights for 1905 have been referred to this new datum.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

Description: Ann 18, iv, p 311; WS 16, p 156; 28, p 146; 38 pp 327–328; 51, p 396; 66, p 105; 85, p 101; 100, p 161; 133, p 294.

Discharge: Ann 18, iv, p 311; WS 16, p 156; 28, p 153; 38, p 328; 51, p 396; 66, p 105; 85, p 102; 100, p 161; 133, p 295.

Discharge, monthly: Ann 19, iv, p 430; 20, iv, p 440; 21, iv, p 391; 22, iv, p 400; WS 75, p 182; 85, p 103; 100, p 163; 133, p 296.

Discharge, yearly: Ann 20, iv, p 60.

Gage heights: WS 11, p 76; 16, p 165; 28, pp 148–149; 38, p 328; 51, p 397; 66, p 106; 85, p 102; 100, p 162; 133, p 295.

Hydrographs: Ann 19, iv, p 430; 20, iv, p 441; 21, iv, p 391; 22, iv, p 400.

Rating tables: Ann 19, iv, p 429; WS 28, p 154; 39, p 452; 52, p 520; 66, p 174; 85, p 102; 100, p 162; 133, p 296.

harge measurements of South Fork of Humboldt River near Elko, Nev., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. A. Wolf.....	.....	109	2.24	1.55	244
.....	.....do.....	47	167	3.81	3.85	636
.....	.....do.....	46	157	3.62	3.60	568
.....	.....do.....	46	181	4.30	4.31	779
.....	.....do.....	45	122	2.89	2.88	324
.....	.....do.....	45	86	1.40	1.95	120
r 7...	.....do.....	.....	.....	.....	.60	a.5

a Estimated.

Beginning May 21 gage heights refer to new datum.

y gage height, in feet, of South Fork Humboldt River near Elko, Nev., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	0.5	0.85	(a)	0.4	2.3	3.55	2.75	1.0	1.0	0	1.0	1.1
.....	.5	1.15	(a)	.5	2.1	3.6	2.75	1.0	1.0	0	1.0	1.1
.....	.5	1.15	(a)	.5	2.3	3.6	2.8	1.0	1.0	0	1.0	1.1
.....	.5	1.5	(a)	1.15	2.55	3.7	2.9	1.0	1.0	0	1.0	1.1
.....	.5	1.5	(a)	1.15	2.55	3.7	3.0	1.0	1.0	0	1.0	1.1
.....	.5	1.5	0.4	1.5	2.55	3.6	3.7	1.0	1.0	0	1.1	1.1
.....	.5	1.15	.4	1.65	2.75	3.7	2.9	1.0	1.0	0	1.1	1.1
.....	.5	.5	(a)	1.8	2.9	3.8	2.7	1.0	.6	0	1.1	1.1
.....	.5	.5	(a)	1.8	3.0	3.9	2.6	1.0	.6	0	1.1	1.1
.....	.5	.5	.4	2.1	3.15	3.8	2.5	1.0	.6	0	1.1	1.1
.....	.5	.5	.4	2.3	3.15	3.8	2.4	1.0	.6	0	1.1	1.1
.....	.5	.5	.4	2.1	3.3	3.9	2.4	1.0	.6	0	1.1	1.1
.....	.5	.4	.4	2.1	3.35	4.0	2.4	1.0	.6	0	1.1	1.1
.....	.5	.4	.4	1.8	3.4	4.1	2.4	1.0	.6	0	1.1	1.1
.....	.5	(a)	.4	1.8	3.5	4.2	2.45	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.1	3.65	4.3	2.4	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.1	3.75	4.4	2.2	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.2	3.85	4.3	2.1	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.2	3.85	4.1	2.0	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.3	3.85	4.0	1.8	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.3	3.8	3.8	1.7	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.55	3.7	3.7	1.6	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.55	3.7	3.5	1.5	1.0	.6	1.0	1.1	1.1
.....	.5	(a)	.4	2.55	3.6	3.3	1.4	1.0	0	1.0	1.1	1.1
.....	.5	(a)	.4	2.55	3.6	3.2	1.4	1.0	0	1.0	1.1	1.1
.....	.5	.4	.4	2.55	3.5	3.1	1.4	1.0	0	1.0	1.1	1.1
.....	.5	.4	4	2.55	3.5	3.0	1.3	1.0	0	1.0	1.1	1.1
.....	.5	.4	.4	2.55	3.6	3.0	1.3	1.0	0	1.0	1.1	1.1
.....	.5	.....	.4	2.55	3.5	2.9	1.2	1.0	0	1.0	1.1	1.1
.....	.5	.....	.5	2.3	3.55	2.8	1.1	1.0	0	1.0	1.1	1.1
.....	.5	.....	.4	.....	3.55	.....	1.1	1.0	.....	1.0	.....	1.1

a No flow.

Station rating table for South Fork Humboldt River near Elko, Nev., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.50	0	1.70	88	2.90	350	4.10	720
.60	1	1.80	102	3.00	380	4.20	752
.70	3	1.90	117	3.10	410	4.30	784
.80	7	2.00	133	3.20	440	4.40	816
.90	12	2.10	150	3.30	470	4.50	848
1.00	18	2.20	168	3.40	500	4.60	880
1.10	25	2.30	189	3.50	530	4.70	912
1.20	33	2.40	212	3.60	560	4.80	944
1.30	42	2.50	238	3.70	592	4.90	976
1.40	52	2.60	264	3.80	624	5.00	1,008
1.50	63	2.70	292	3.90	656		
1.60	75	2.80	320	4.00	688		

NOTE.—The above table is applicable only for open-channel conditions. It is based upon 7 discharge measurements made during 1905. It is fairly well defined between gage heights 2 feet and 4 feet. Below 2 feet the table is based on one measurement at 0.6 foot.

Estimated monthly discharge of South Fork Humboldt River near Elko, Nev., for 1905.

[Drainage area, 1,150 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	0	0	0	0	0	0
February	63	0	10.2	567	.0089	.01
March	0	0	0	0	0	0
April	251	0	149	8,866	.130	.14
May	640	150	465	28,590	.404	.46
June	816	320	588	34,990	.511	.57
July	592	25	187	11,500	.163	.19
August	18	18	18	1,107	.016	.01
September	18	0	4.7	280	.0041	.00
October	18	0	9.9	608	.0086	.01
November	25	18	24.7	1,470	.021	.02
December	25	25	25	1,537	.022	.02
The year	816	0	123	89,520	.107	1.45

HUMBOLDT RIVER AT PALISADE, NEV.

This station was established November 27, 1902. It is located at the single-span highway bridge one-fourth mile from the hotel at Palisade, Nev. There is a railroad bridge about 500 feet below.

The channel is straight for 200 feet above and 300 feet below the station. The right bank is low and liable to overflow; the left is high. The bed of the stream is composed of gravel and sand and is permanent. There is but one channel at all stages.

Discharge measurements are made by means of a cable and car about one-fourth mile above the gage. At very low stages, when the current becomes sluggish at the gage, measurements are made by wading a short distance above. The initial point for soundings is the zero on the tagged wire.

The gage, which is read once each day by T. H. Jewell, the hotel keeper, is a vertical 1 by 4 inch board spiked to the right abutment of the bridge. The bench mark consists

ke and three nails driven into the bridge abutment to which the gage is fastened; n above zero of gage, 7.00 feet.

mation in regard to this station is contained in the following Water-Supply Papers United States Geological Survey:

ption: 85, p 100; 100, p 157; 133, p 286.
rge: 100, p 158; 133, p 286.
rge, monthly: 100, p 159; 133, p 288.
eights: 85, p 100; 100, p 158; 133, p 287.
; table 100, p 159, 133, p 287.

Discharge measurements of Humboldt River at Palisade, Nev., in 1905.

.e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. A. Wolf.....	102	258	1.88	• 3.10	485
.....	.....do.....	105	365	2.33	4.10	850
.....	.....do.....	105	414	2.23	4.20	923
.....	.....do.....	105	358	2.12	3.85	759
.....	.....do.....	105	358	2.11	3.85	756
.....	.....do.....	97	204	1.40	2.35	284
ber 8...	.....do.....	10	10	1.30	.90	13

Daily gage height, in feet, of Humboldt River at Palisade, Nev., for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	1.9	2.0	2.4	2.6	2.95	4.6	3.2	1.6	1.1	1.15	1.4	1.4
.....	1.95	2.1	2.4	2.6	3.0	4.6	3.2	1.6	1.1	1.15	1.4	1.4
.....	1.95	2.1	2.4	2.6	3.05	4.6	3.15	1.6	1 1	1.15	1.4	1.46
.....	1.95	2.2	2.4	2.6	3.1	4.55	3.1	1.6	1.1	1.15	1.4	1.46
.....	1.95	2.2	2.4	2.6	3.15	4.55	3.1	1.55	1.1	1.2	1.4	1.46
.....	1.95	2.2	2.4	2.6	3.2	4.55	3.0	1.55	1.1	1.2	1.4	1.46
.....	1.95	2.2	2.4	2.6	3.3	4.5	2.9	1.5	1.1	1.2	1.4	1.46
.....	1.9	2.2	2.4	2.6	3.3	4.5	2.85	1.5	1.1	1.2	1.4	1.46
.....	1.9	2.1	2.4	2.6	3.35	4.5	2.8	1.5	1.1	1.2	1.4	1.46
.....	1.8	2.1	2.4	2.6	3.4	4.45	2.75	1.5	1.1	1.2	1.4	1.4
.....	1.8	2.1	2.4	2.65	3.5	4.45	2.7	1.5	1.1	1.2	1.4	1.4
.....	1.7	2.0	2.4	2.75	3.5	4.4	2.6	1.5	1.1	1.2	1.4	1.4
.....	1.7	2.0	2.4	2.8	3.6	4.2	2.5	1.5	1.1	1.2	1.4	1.4
.....	1.7	2.0	2.4	2.8	3.65	4.0	2.4	1.5	1.1	1.2	1.4	1.4
.....	1.7	2.0	2.4	2.8	3.7	4.0	2.3	1.5	1.1	1.2	1.4	1.4
.....	1.7	2.0	2.4	2.9	3.8	4.0	2.3	1.5	1.1	1.25	1.4	1.4
.....	1.7	2.0	2.4	2.9	3.9	3.95	2.3	1.4	1.1	1.25	1.4	1.45
.....	1.7	2.1	2.4	2.9	4.0	3.9	.2	1.3	1.1	1.3	1.4	1.45
.....	1.75	2.1	2.4	2.9	4.0	3.9	2.1	1.25	1.1	1.3	1.4	1.45
.....	1.75	2.1	2.4	2.95	4.2	3.85	2.0	1.2	1.1	1.3	1.4	1.5
.....	1.8	2.2	2.45	2.95	4.2	3.85	2.0	1.15	1.1	1.3	1.4	1.5
.....	1.8	2.2	2.5	2.95	4.2	3.8	1.9	1.1	1.1	1.35	1.4	1.5
.....	1.8	2.2	2.5	2.95	4.2	3.8	1.9	1.1	1.1	1.35	1.4	1.5
.....	1.85	2.3	2.5	2.95	4.3	3.7	1.9	1.1	1.1	1.35	1.4	1.55
.....	1.95	2.3	2.55	2.95	4.4	3.7	1.8	1.1	1.1	1.35	1.4	1.55
.....	1.9	2.4	2.6	2.95	4.5	3.6	1.75	1.1	1.1	1.35	1.4	1.55
.....	1.9	2.4	2.6	2.95	4.6	3.5	1.75	1.1	1.1	1.4	1.4	1.6
.....	1.9	2.4	2.6	2.95	4.7	3.4	1.75	1.1	1.1	1.4	1.4	1.6
.....	1.9	.....	2.6	2.95	4.8	3.3	1.75	1.1	1.1	1.4	1.4	1.65
.....	2.0	.....	2.6	2.95	4.7	3.2	1.75	1.1	1.1	1.4	1.4	1.7
.....	2.0	.....	2.6	.....	4.6	.....	1.6	1.1	.....	1.4	.....	1.7

Station rating table for Humboldt River at Palisade, Nev., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.10	34	2.10	203	3.10	498	4.00	850
1.20	46	2.20	227	3.20	534	4.10	895
1.30	59	2.30	253	3.30	570	4.20	940
1.40	72	2.40	280	3.40	607	4.30	985
1.50	86	2.50	308	3.50	645	4.40	1,030
1.60	102	2.60	337	3.60	684	4.50	1,075
1.70	120	2.70	367	3.70	724	4.60	1,120
1.80	139	2.80	398	3.80	765	4.70	1,170
1.90	159	2.90	430	3.90	807	4.80	1,220
2.00	180	3.00	463				

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1903-1905. It is fairly well defined.

Estimated monthly discharge of Humboldt River at Palisade, Nev., for 1905.

[Drainage area, 5,014 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inche
January	180	120	149	9,162	0.030	0.(
February	280	180	216	12,000	.043	.(
March	337	280	296	18,200	.059	.(
April	446	337	397	23,620	.079	.(
May	1,220	446	793	48,760	.158	.1
June	1,120	534	884	52,600	.176	.1
July	534	102	286	17,580	.057	.(
August	102	34	66.6	4,095	.013	.(
September	34	34	34.0	2,023	.0068	.(
October	72	40	54.7	3,363	.011	.(
November	72	72	72.0	4,284	.014	.(
December	120	72	85.2	5,239	.017	.(
The year	1,220	34	278	200,900	.055	.7

NOTE. Ice conditions not known. Open-channel rating table applied to the winter months with correction.

HUMBOLDT RIVER NEAR GOLCONDA, NEV.

This station was established October 24, 1894. It is located 1¼ miles north of the t of Golconda, near the great northern bend of Humboldt River and below the central val and is about 12 miles above the mouth of Little Humboldt River.

The channel is straight for 300 feet above and 100 feet below the station. The banks moderately high, but are liable to overflow at extreme high water. The bed of the str is of gravel and sand and is somewhat shifting. There is but one channel at all stages.

Measurements prior to 1904 were made from a cable and suspended car. Subseq measurements have been made from the upper side of a wagon bridge, constructed du the winter of 1903–4, 10 feet above the cable. At low stages, when the current is slug measurements can be made by wading above or below the cable.

The gage was read during 1905 by Charles Shallenberger. A new gage and bench mark ere established October 4, 1904, replacing the inclined gage installed November 28, 1902, hich was fastened to the left bank by 4 by 4 inch stakes, and the zero of which had the me elevation as the original gage. The new gage is a 4 by 4 inch timber, driven vertically to the river bed, and its upper end is securely fastened to a stringer on the downstream de of the north or right end of the wagon bridge. The bench mark of the old gage was a by 4 inch timber, driven 4 feet north of the cable post on the left bank, at an elevation of 1.75 feet above the zero of the gage. The new bench mark is the head of the lowest rivet the strut at the northwest corner of the bridge; elevation above zero of new gage, 13.42 et. The new bench mark is 0.48 foot lower than the old bench mark, so that the new ge zero is 3.15 feet below the old zero.

Information in regard to this station is contained in the following publications of the ited States Geological Survey (Ann=Annual Reports; Bull=Bulletin; WS=Water-pply Paper):

Description: Ann 18, iv, pp 303-304; Bull 131, p 52; 140, pp 217-218; WS 16, p 154; 28, p 146; 38, p 329; 51, 97; 66, p 106; 85, p 98; 100, p 155; 133, pp 288-289.

Discharge: Ann 18, iv, pp 304-305; Bull 131, p 92; 140, p 218; WS 16, p 154; 28, p 153; 38, p 329; 51, p 397; p 106; 85, p 98; 100, p 155; 133, p 289.

Discharge, monthly: Ann 18, iv, p 306; 19, iv, p 427; 20, iv, p 438; 21, iv, p 392; 22, iv, p 401; Bull 140, p ; WS 75, p 192; 85, p 100; 100, p 157; 133, p 291.

Discharge, yearly: Ann 20, iv, p 59.

Gage heights: Bull 140, p 219; WS 11, p 74; 16, p 154; 28, p 148; 38, p 329; 51, p 398; 66, p 107; 85, p 99; , p 156; 133, p 290.

Hydrographs: Ann 19, iv, p 429; 20, iv, p 439; 21, iv, p 392; 22, iv, p 401.

Rating tables: Ann 19, iv, p 427; WS 28, p 154; 39, p 452; 52, p 520; 66, p 175; 85, p 99; 100, p 156; 133, p .

Discharge measurements of Humboldt River near Golconda, Nev., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
pril 25	W. A. Wolf	63	200	0.58	6.55	116
ay 19	do	73	234	1.30	6.95	302
ne 2	do	62	153	1.33	5.98	203
ne 15	do	62	160	1.60	6.40	257
ne 28	do	60	166	1.43	6.30	238
ly 13	do	59	172	1.46	6.35	252
ptember 6	do				3.10	[a].5

[a] Estimated.

Daily gage height, in feet, of Humboldt River near Golconda, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	5.7	6.2	.....	.....	.....	7.4	.....	4.7	.....	3.0	3.0	3.0
2	.....	.....	6.2	.....	7.0	.....	.....	4.7	.....	.....	.....	.....
3	5.5	.....	.....	.....	.....	5.9	.....	4.6	.....	3.0	.....	3.0
4	.....	6.0	.....	6.4	7.1	6.0	6.5	4.3	.....	3.0	.....	3.0
5	5.3	5.9	6.2	6.4	7.0	.....	6.5	.....	.....	3.0	.....	3.0
6	.....	.....	6.3	.....	6.9	5.9	6.5	4.1	3.1	.....	3.0	.....
7	5.5	.....	6.3	6.0	7.0	6.2	.....	4.1	3.1	.....	3.0	.....
8	5.5	5.9	.....	5.8	.....	.....	6.3	.....	3.1	.....	3.0	.....
9	.....	6.0	.....	6.5	6.8	.....	.....	.....	3.1	.....	3.0	2.9
10	.....	6.1	.....	.....	6.4	6.2	6.3	.....	.....	.....	.....	.....
11	5.6	.....	.....	.....	.....	6.4	.....	3.9	.....	.....	.....	.....
12	5.3	6.0	6.2	6.8	6.4	6.2	6.0	3.9	.....	.....	.....	2.9
13	5.0	.....	6.2	7.0	.....	6.0	6.0	3.7	3.0	.....	3.0	2.9
14	.....	.....	.....	.....	.....	6.0	.....	3.7	3.0	.....	3.0	2.9
15	5.0	5.8	6.1	7.0	.....	.....	5.9	3.6	2.9	.....	3.0	2.9
16	.....	.....	6.3	7.0	.....	.....	5.7	.....	2.8	2.9	3.0	.....
17	.....	5.6	.....	7.0	6.9	.....	.....	.....	.....	.....	.....	.....
18	5.3	5.6	.....	.....	6.9	6.0	.....	3.4	2.9	3.0	.....	.....
19	.....	5.6	5.6	6.8	6.9	6.0	5.5	.....	.....	2.9	.....	.....
20	5.6	.....	.....	.....	7.0	.....	.....	.....	.....	3.0	3.0	.....
21	6.3	.....	.....	.....	.....	.....	5.4	3.3	3.0	.....	.....	3.0
22	5.8	5.7	6.0	6.5	7.0	6.3	5.4	3.3	3.0	.....	2.9	3.0
23	.....	.....	6.0	.....	.....	6.5	.....	.....	3.0	2.9	3.0	3.0
24	.....	5.9	6.0	6.5	7.1	.....	.....	3.2	.....	2.9	3.0	3.0
25	5.4	5.9	6.2	6.4	7.3	6.9	5.1	.....	.....	3.0	.....	.....
26	.....	6.0	5.9	.....	.....	.....	5.1	3.0	3.0	.....	3.0	3.0
27	5.2	.....	.....	6.8	7.3	6.9	.....	3.1	.....	.....	3.0	2.9
28	5.4	.....	6.0	.....	.....	6.5	5.0	.....	3.0	.....	.....	3.0
29	.....	.....	.....	7.0	.....	.....	4.9	3.1	3.0	3.0	.....	3.0
30	5.4	.....	6.4	.....	7.4	6.5	.....	3.0	2.9	3.0	.....	.....
31	6.0	.....	6.4	.....	7.4	.....	.....	3.1	.....	3.0	.....	.....

Station rating table for Humboldt River near Golconda, Nev., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.80	0.0	4.00	39.0	5.20	132.0	6.40	247.0
2.90	0.1	4.10	46.0	5.30	141.0	6.50	257.0
3.00	.3	4.20	53.0	5.40	150.0	6.60	268.0
3.10	.5	4.30	60.0	5.50	159.0	6.70	279.0
3.20	2.0	4.40	67.0	5.60	168.0	6.80	290.0
3.30	5.0	4.50	75.0	5.70	177.0	6.90	301.0
3.40	8.0	4.60	83.0	5.80	187.0	7.00	312.0
3.50	12.0	4.70	91.0	5.90	197.0	7.10	323.0
3.60	16.0	4.80	99.0	6.00	207.0	7.20	334.0
3.70	21.0	4.90	107.0	6.10	217.0	7.30	345.0
3.80	27.0	5.00	115.0	6.20	227.0	7.40	356.0
3.90	33.0	5.10	123.0	6.30	237.0		

NOTE.—The above table is applicable only for open-channel conditions. It is based on six discharge measurements made during 1905 and the form of previous curves. It is well defined between gage heights 6 feet and 7 feet. Below gage height 6 feet it is only approximate.

Estimated monthly discharge of Humboldt River near Golconda, Nev., for 1905.

[Drainage area, 10,780 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ıary	237	115	155	9,531	0.014	0.016
uary	227	168	196	10,880	.018	.019
:h	247	168	218	13,400	.020	.023
l	312	187	272	16,180	.025	.028
	356	247	308	18,940	.029	.033
	356	197	239	14,220	.022	.024
	257	95	184	11,310	.017	.020
ıst	91	.3	25.0	1,537	.0023	.0026
:mber	.5	.0	.33	19.6	.000031	.000035
ber	.3	.1	.23	14.1	.000021	.000024
:mber	.3	.1	.29	17.3	.000027	.000030
mber	.3	.1	.22	13.5	.000020	.000023
The year	356	0	133	96,060	.012	.166

TE.—Ice conditions not known. Open-channel rating table applied to the winter months without ction. Discharge interpolated on days when gage was not read.

HUMBOLDT RIVER NEAR OREANA, NEV.

ıis station was established January 27, 1896. It is located near Oreana, Nev., about niles northeast of Lovelocks. The results of the observations at the possible reservoir sites in the vicinity of ıboldt station, and also for the six canal systems now in operation below Oreana.

ıe channel is straight for 300 feet above and 200 feet below the station. The right ı is high and will not overflow; the left bank will overflow only at extreme high water. re is but one channel at all stages. The bed of the stream is sandy and shifting.

ischarge measurements are made at high water by means of a cable and car located he gage. At low water measurements are made by wading a short distance below station.

he gage was read once each day during 1905 by J. J. McCarthy. The original gage located at the old Oreana highway bridge. The abutment to which the gage was ned was undermined and fell May 26, 1897. A temporary gage was used until Sep- ber 8, 1897, when a new inclined one was placed on the left bank of the river, about niles above the site of the old gage and opposite the section house of the Central Pacific road. This gage was washed out. The present gage was established November 29, . It is vertical, in two sections, and is spiked to piles at the site of the old dam. The :h mark consists of four nails driven into the pile to which the upper section of the is fastened; elevation above zero of gage, 5.00 feet. On October 1, 1904, the gage was lowered 2.00 feet, and the elevation of the bench mark is now 7.00 feet above the of the gage:

ıformation in regard to this station is contained in the following publications of the ed States Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water- ıly Paper):

scription: Ann 18, iv, p 306; Bull 140, p 220; WS 16, p 155; 28, p 146; 38, p 330; 51, p 398; 66, p 107; 96; 100, pp 152-153; 133, p 292.

charge: Ann 18, iv, p 307; WS 16, p 155; 28, p 153; 38, p 330; 51, p 398; 66, p 107; 85, p 97; 100, p 153; 292.

charge, monthly: Ann 18, iv, p 308; 19, iv, p 428; 20, iv, p 439; 21, iv, p 393; 22, iv, p 402; WS 75, ; 85, p 98; 100, p. 154; 133, p 294.

charge, yearly: Ann 20, iv, p 60.

ion rating table for Humboldt River near Oreana, Nev., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.10	0.0	1.90	29.0	2.70	152.0	3.50	335.0
1.20	.5	2.00	40.0	2.80	172.0	3.60	360.0
1.30	1.0	2.10	53.0	2.90	193.0	3.70	385.0
1.40	2.0	2.20	67.0	3.00	215.0	3.80	412.0
1.50	3.5	2.30	82.0	3.10	238.0	3.90	440.0
1.60	7.0	2.40	98.0	3.20	261.0		
1.70	12.0	2.50	115.0	3.30	285.0		
1.80	20.0	2.60	133.0	3.40	310.0		

e above table is applicable only for open-channel conditions. It is based on six discharge measents made during 1905. It is fairly well defined between gage heights 1.6 feet and 3 feet. It is approximate below gage height 1.6 feet.

Estimated monthly discharge of Humboldt River near Oreana, Nev., for 1905.

[Drainage area, 13,800 square miles.]

Month.	Discharge in second-feet.			Run-off.		
	Maximum.	Minimum.	Mean.	Total in acre-feet.	Second-feet per square mile.	Depth in inches.
ıary	440	172	260	15,990	0.019	.022
ruary	398	152	252	14,000	.018	.019
:h	398	117	209	12,850	.015	.017
l	152	20	96.0	5,712	.0070	.0078
	34	7	13.2	812	.00096	.0011
	7	0	1.94	115	.00014	.00016
	322	0	156	9,592	.011	.013
ust	162	29	95.3	5,860	.0069	.0080
ember	24	12	17.3	1,029	.0013	.0014
ber	29	12	20.0	1,230	.0014	.0016
ember	46	29	33.1	1,970	.0024	.0027
mber	98	46	62.7	3,855	.0045	.0052
The year	440	0	101	73,020	.0073	.099

TE.—Ice conditions January 1 to February 19. Open-channel rating table applied to the winter ths without correction. Winter estimates liable to considerable error.

SIERRA NEVADA DRAINAGE.

PRINCIPAL STREAMS.

he Sierra Nevada drainage area includes the western part of Nevada, the eastern part alifornia, and a small part of south-central Oregon. The principal rivers of the area, the bodies of water into which they discharge, are the following: Truckee River into amid and Winnemucca lakes, Walker River into Walker Lake, Carson River into on Sink, Susan River into Honey Lake, and Owens River into Owens Lake.

TRUCKEE RIVER BASIN.

DESCRIPTION OF BASIN.

Upper Truckee River rises on the eastern slopes of the Sierra Nevada, in Eldorado Cal., and flows northward, entering Lake Tahoe from the south. The main Trucke the lake, of which it forms the outlet, at the town of Tahoe, in eastern Placer Coun flows north and northeast, and discharges, in Washoe County, Nev., into Pyra Winnemucca lakes, which have no outflowing streams. The drainage basin is v mountainous, the highest peaks reaching altitudes exceeding 10,000 feet. Lak which lies at an elevation of 6,225 feet above sea, has an area of 193 square miles a largest body of fresh water in the United States at this altitude.

In the lower part of its course the Truckee receives several important tributarie which may be mentioned Donner and Prosser creeks and Little Truckee River, t uniting with the main stream at the town of Boca. Independence Creek is a bran Little Truckee.

TRUCKEE RIVER NEAR WADSWORTH, NEV.

This station was established November 6, 1902. It is located one-fourth mil the school at the Indian agency and is 18 miles north of Wadsworth, Nev.

The channel is straight for 200 feet above and below the cable. The right ba and is liable to overflow beyond the cable support at very high water; the left ban and will not overflow. The bed of the stream is composed of sand and gravel a manent. There is but one channel at all stages. The current is swift.

Discharge measurements are made by means of a cable and car about 200 f the gage. The initial point for soundings is the zero of the tagged wire.

The gage, which was read during 1905 twice each day by Edward C. Wood, is inch vertical timber spiked to a cottonwood tree on the right bank. The ben consists of three nails driven into the root of a cottonwood tree 18 feet north of elevation above gage zero, 12.07 feet. The gage was disturbed by a flood early ruary, 1904, and settled 0.31 foot, so that the elevation of the bench mark is 1 above the zero of the present gage datum.

Information in regard to this station is contained in the following Water-Suppl of the United States Geological Survey:

Description: 100, p 188; 133, pp 298–299.
Discharge: 100, p 188; 133, p 299.
Discharge, monthly: 100, p 190; 133, p 300.
Gage heights: 100, pp 188–189; 133, p 299.
Rating table: 100, p 189; 133, p 300.

Discharge measurements of Truckee River near Wadsworth, Nev., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*
May 18	W. A. Wolf	124	528	2.48	6.42
June 8	do	127	418	2.15	5.85
July 11	do	120	254	1.26	4.58

Daily gage height, in feet, of Truckee River near Wadsworth, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	6.3	5.38	6.35	5.52	6.65	6.38	4.85	3.85	4.05	4.77	5.1	4.97
.....	6.1	5.57	6.38	5.6	6.55	6.4	4.82	3.82	4.1	4.7	5.02	5.0
.....	6.0	5.6	6.4	5.6	6.58	6.3	4.78	3.82	4.1	4.65	5.0	5.05
.....	6.0	5.7	6.4	5.8	6.75	6.22	4.65	3.8	4.07	4.52	4.9	5.07
.....	6.0	5.65	6.4	5.8	6.4	6.15	4.8	3.8	4.05	4.6	4.9	5.07
.....	6.0	5.65	6.48	5.88	6.35	5.98	4.82	3.8	4.25	4.4	4.8	4.9
.....	5.9	5.4	6.5	6.0	6.2	5.92	4.75	3.9	4.22	4.65	4.82	4.95
.....	5.85	5.35	6.55	6.0	6.2	5.89	4.64	3.8	4.25	4.75	4.82	4.9
.....	5.85	5.3	6.58	6.0	6.2	5.85	4.64	3.8	4.4	4.87	4.75	4.82
.....	5.85	5.38	6.55	6.1	6.25	5.82	4.52	3.8	4.4	4.95	4.7	4.8
.....	5.85	5.55	6.48	6.18	6.02	6.08	4.52	3.8	4.4	5.0	4.72	4.77
.....	5.98	5.48	6.5	5.98	5.95	6.15	4.4	3.8	4.3	5.0	4.7	4.77
.....	5.9	5.4	6.48	5.82	5.9	6.4	4.36	3.8	4.3	5.12	4.72	4.87
.....	5.9	5.4	6.58	5.78	5.95	6.18	4.35	4.05	4.25	5.02	4.7	4.97
.....	5.9	5.6	6.5	5.7	6.05	6.12	4.4	4.0	4.25	5.05	4.6	5.0
.....	5.55	5.5	6.35	5.7	6.22	6.1	4.36	4.0	4.25	5.27	4.6	5.0
.....	5.5	5.5	6.0	5.65	6.5	6.0	4.22	3.95	4.15	5.25	4.62	4.85
.....	5.4	5.55	6.0	5.65	6.95	6.12	4.1	3.95	4.17	5.2	4.92	4.7
.....	5.32	5.55	6.0	5.65	6.8	5.92	4.1	4.0	4.17	5.25	5.0	4.72
.....	5.3	5.58	6.0	5.52	6.7	5.95	4.0	4.0	4.2	5.1	5.07	4.67
.....	5.3	6.0	6.0	5.3	6.7	5.85	3.98	4.0	4.2	5.2	5.22	4.85
.....	5.55	5.85	6.0	5.2	6.82	5.85	3.98	4.05	4.4	4.92	5.0	5.1
.....	5.68	6.02	5.7	5.18	6.6	5.7	3.95	4.18	4.34	5.0	5.0	4.65
.....	5.6	6.05	5.65	5.25	6.12	5.58	4.0	4.25	4.22	4.95	5.12	4.7
.....	5.55	6.2	5.7	5.35	6.5	5.45	3.9	4.25	4.4	4.9	5.2	4.77
.....	5.42	6.3	5.65	5.84	6.5	5.32	3.88	4.25	4.51	5.05	5.0	4.9
.....	5.4	6.35	6.1	7.12	6.68	5.15	3.9	4.2	4.4	5.1	5.0	4.97
.....	5.4	6.38	6.0	6.8	6.45	5.1	3.9	4.12	4.52	5.1	5.02	5.0
.....	5.38	.....	5.88	6.68	6.6	4.92	3.88	4.0	4.52	5.05	4.95	5.0
.....	5.3	.....	5.78	6.7	6.52	4.82	3.85	4.07	4.5	5.05	4.95	4.85
.....	5.3	.....	5.55	.....	6.5	.....	3.85	4.05	.....	4.95	.....	4.92

tion rating table for Truckee River near Wadsworth, Nev., from January 1 to December 31, 1905.

Gage height	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.80	108	4.70	358	5.60	770	6.50	1,350
3.90	131	4.80	394	5.70	825	6.60	1,430
4.00	155	4.90	432	5.80	885	6.70	1,510
4.10	180	5.00	472	5.90	945	6.80	1,595
4.20	206	5.10	515	6.00	1,005	6.90	1,685
4.30	233	5.20	560	6.10	1,070	7.00	1,775
4.40	262	5.30	610	6.20	1,135	7.10	1,865
4.50	292	5.40	660	6.30	1,205	7.20	1,955
4.60	324	5.50	715	6.40	1,275		

OTE.—The above table is applicable only for open-channel conditions. It is based on discharge asurements made during 1904–5. It is well defined between gage heights 4.6 feet and 8 feet.

Estimated monthly discharge of Truckee River near Wadsworth, Nev., for 1905.

[Drainage area, 2,130 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	1,205	610	826	50,790	0.388	
February	1,261	610	827	45,930	.388	
March	1,414	742	1,133	69,670	.532	
April	1,883	551	935	55,640	.439	
May	1,730	945	1,306	80,300	.613	
June	1,275	402	935	55,640	.439	
July	413	120	241	14,820	.113	
August	220	108	148	9,100	.069	
September	298	168	229	13,630	.108	
October	595	262	457	28,100	.215	
November	570	324	434	25,820	.204	
December	515	341	433	26,620	.203	
The year	1,883	108	659	476,100	.309	

NOTE.—Ice conditions not known; open-channel rating table applied to the winter months without correction.

TRUCKEE RIVER AT VISTA, NEV.

This station was established August 18, 1899. It is located 7 miles east of Reno and one-fourth mile from the Southern Pacific Railroad station at Vista.

The channel is straight for 150 feet above and 400 feet below the station. Both banks are high; the left is liable to overflow at extreme high stages only. There is but one channel at all stages.

Discharge measurements are made by means of a cable and car below the railroad bridge. The initial point for soundings is the zero of the tagged wire.

During 1905 the gage was read once each day by Patrick Fay. The original gage was replaced November 12, 1902, by a new gage, which was installed on the left bank 1 foot above the railroad bridge, its zero having the same elevation as that of the original. April 3, 1903, another new gage was established, consisting of a 4 by 4 inch vertical timber located on the left bank and having the same datum as the previous gages. June 23 this gage was torn out and moved 3 feet farther into the river, in order to place it in deeper water, and the zero of the gage was lowered 2.72 feet. The bench mark is the head of a bolt set in the concrete of the upstream side of the left abutment of the Southern Pacific Railroad bridge, 300 feet from the gage; elevation above zero of gage, 19.74 feet. February 21 the gage rod was washed out by a flood. A new gage was established in the same position as the old gage, but with its zero 1.54 feet above that of the old gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann = Annual Report; WS = Water-Supply Paper):

Discharge: WS 58, pp 331-332; 51, p 404; 66, p 113; 85, pp 117-118; 100, pp 185-186; 133, p 301.
Discharge: WS 58, p 332; 51, p 404; 66, p 113; 85, p 118; 100, p 186; 133, pp 301-302.
Discharge, monthly: Ann 11, ii, p 102; 12, ii, p 351; 13, iii, p 95; 22, iv, p 405; WS 75, p 186; 85, p 120; 100, p 187; 133, p 303.
Discharge, yearly: Ann 13, iii, p 99; 20, iv, p 59.
Gage heights: WS 58, p 332; 51, p 405; 66, p 114; 85, p 118; 100, pp 186-187; 133, p 302.
Hydrographs: Ann 12, ii, p 324; 22, iv, p 405; WS 75, p 186.
Rating tables: WS 52, p 521; 66, p 175; 85, p 119; 100, p 187; 133, p 303.

Discharge measurements of Truckee River at Vista, Nev., in 1905.

te.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. A. Wolf.....	117	518	1.98	5.25	1,027
.....	.....do.....	115	480	1.70	5.00	816
.....	.....do.....	117	593	2.86	6.28	1,698
.....	.....do.....	117	563	2.45	5.85	1,381
.....	.....do.....	118	510	1.98	5.30	1,009
.....	.....do.....	114	368	1.04	4.07	381
.....	.....do.....	114	368	1.07	4.10	394
.....	.....do.....	113	327	.70	3.55	221
er 16	.....do.....	113	337	.79	3.70	266

Daily gage height, in feet, of Truckee River at Vista, Nev., for 1905.

r.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	5.6	4.8	5.8	.....	5.6	5.7	4.1	3.4	3.4	4.0	4.3	4.3
.....	5.4	5.1	5.8	5.0	5.8	5.6	4.1	3.4	3.5	4.0	4.3	4.4
.....	5.4	5.9	5.9	5.0	6.0	5.4	4.1	3.4	3.5	4.0	4.1	4.4
.....	5.4	4.8	5.9	4.9	6.2	5.7	4.1	3.4	3.5	4.0	4.1	4.4
.....	5.3	4.8	6.0	5.3	5.8	5.6	4.1	3.4	3.5	4.0	4.1	4.4
.....	5.3	4.8	6.0	5.4	5.6	5.3	4.1	3.4	3.6	4.0	4.2	4.4
.....	5.2	4.8	6.0	5.5	5.5	5.3	4.0	3.4	3.6	4.1	4.2	4.4
.....	5.2	4.8	6.0	5.5	5.5	5.2	3.9	3.4	3.7	4.1	4.2	4.4
.....	5.2	4.7	6.0	5.3	5.5	5.3	3.9	3.4	3.7	4.1	4.2	4.4
.....	5.1	4.9	5.8	5.5	5.5	5.6	3.8	3.4	3.7	4.1	4.2	4.0
.....	5.1	4.8	5.9	5.4	5.3	5.3	3.7	3.4	3.7	4.2	4.3	4.2
.....	5.1	4.8	5.9	5.2	5.2	5.5	3.7	3.4	3.7	4.2	4.3	4.1
.....	5.0	4.8	6.1	5.0	5.0	5.6	3.7	3.4	3.7	4.2	4.3	4.1
.....	5.0	4.9	6.0	5.0	4.8	5.6	3.5	3.4	3.7	4.2	4.3	4.2
.....	5.0	4.9	5.8	5.1	5.6	5.4	3.5	3.5	3.7	4.2	4.2	4.1
.....	4.9	5.0	5.5	5.0	5.7	5.4	3.5	3.5	3.7	4.2	4.2	4.1
.....	5.8	4.9	5.5	4.9	5.3	5.3	3.4	3.5	3.7	4.2	4.2	4.1
.....	4.8	4.9	5.5	4.8	5.4	5.3	3.4	3.6	3.7	4.2	4.2	4.1
.....	4.7	5.0	5.5	4.8	6.3	5.3	3.4	3.6	3.7	4.2	4.2	4.1
.....	4.8	5.5	5.5	4.9	6.2	5.0	3.4	3.6	3.7	4.2	4.3	4.1
.....	5.2	5.3	5.5	5.0	6.2	5.0	3.4	3.6	3.7	4.2	4.3	4.0
.....	5.3	5.4	5.5	4.5	6.0	4.8	3.4	3.7	3.7	4.2	4.4	3.7
.....	5.0	5.4	5.3	4.7	5.8	4.8	3.4	3.7	3.8	4.2	4.4	3.7
.....	5.0	5.9	5.3	4.5	5.7	4.4	3.4	3.7	3.8	4.3	4.3	3.1
.....	4.9	5.8	5.0	4.5	6.0	4.6	3.2	3.7	3.9	4.3	4.2	3.9
.....	4.8	5.8	5.0	6.0	5.9	4.6	3.2	3.7	3.9	4.3	4.2	4.2
.....	4.8	5.8	5.5	6.5	5.7	4.4	3.3	3.7	3.9	4.2	4.2	4.1
.....	4.7	5.8	5.4	6.3	5.8	4.2	3.4	3.6	3.9	4.2	4.2	4.1
.....	4.8	.....	5.4	6.2	5.7	4.0	3.4	3.6	4.0	4.2	4.2	4.1
.....	4.7	.....	4.9	6.2	5.7	4.0	3.4	3.5	4.0	4.2	4.3	4.1
.....	4.7	.....	.....	.....	5.8	.....	3.4	3.5	.....	4.3	.....	4.1

Estimated monthly discharge of Truckee River near Wadsworth, Nev., for 1905.

[Drainage area, 2,130 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	1,205	610	826	50,790	0.388	0.447
February	1,261	610	827	45,930	.388	.404
March	1,414	742	1,133	69,670	.532	.613
April	1,883	551	935	55,640	.439	.490
May	1,730	945	1,306	80,300	.613	.707
June	1,275	402	935	55,640	.439	.490
July	413	120	241	14,820	.113	.130
August	220	108	148	9,100	.069	.080
September	298	168	229	13,630	.108	.120
October	595	262	457	28,100	.215	.248
November	570	324	434	25,820	.204	.228
December	515	341	433	26,620	.203	.234
The year	1,883	108	659	476,100	.309	4.19

NOTE.—Ice conditions not known; open-channel rating table applied to the winter months without correction.

TRUCKEE RIVER AT VISTA, NEV.

This station was established August 18, 1899. It is located 7 miles east of Reno, Nev., and one-fourth mile from the Southern Pacific Railroad station at Vista.

The channel is straight for 150 feet above and 400 feet below the station. Both banks are high; the left is liable to overflow at extreme high stages only. There is but one channel at all stages.

Discharge measurements are made by means of a cable and car below the railroad bridge. The initial point for soundings is the zero of the tagged wire.

During 1905 the gage was read once each day by Patrick Fay. The original gage was replaced November 12, 1902, by a new gage, which was installed on the left bank 150 feet above the railroad bridge, its zero having the same elevation as that of the original gage. April 3, 1903, another new gage was established, consisting of a 4 by 4 inch vertical timber located on the left bank and having the same datum as the previous gages. June 23, 1903, this gage was torn out and moved 3 feet farther into the river, in order to place it in deeper water, and the zero of the gage was lowered 2.72 feet. The bench mark is the head of a bolt set in the concrete of the upstream side of the left abutment of the Southern Pacific Railroad bridge, 300 feet from the gage; elevation above zero of gage, 19.74 feet. February 21, 1904, the gage rod was washed out by a flood. A new gage was established in the same position as the old gage, but with its zero 1.54 feet above that of the old gage.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann = Annual Report; WS = Water-Supply Paper):

Description: WS 38, pp 331-332; 51, p 404; 66, p 113; 85, pp 117-118; 100, pp 185-186; 133, p 301.
Discharge: WS 38, p 332; 51, p 404; 66, p 113; 85, p 118; 100, p 186; 133, pp 301-302.
Discharge, monthly: Ann 11 ii, p 102; 12, ii, p 351; 13, iii, p 95; 22, iv, p 405; WS 75, p 186; 85, p 119; 100, p 187; 133, p 303.
Discharge, yearly: Ann 13, iii, p 99; 20, iv, p 59.
Gage heights: WS 38, p 332; 51, p 405; 66, p 114; 85, p 118; 100, pp 186-187; 133, p 302.
Hydrographs: Ann 12, ii, p 324; 22, iv, p 405; WS 75, p 186.
Rating tables: WS 52, p 521; 66, p 175; 85, p 119; 100, p 187; 133, p 303.

Discharge measurements of Truckee River at Vista, Nev., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 6	W. A. Wolf	117	518	1.98	5.25	1,027
April 13	do	115	480	1.70	5.00	816
April 28	do	117	593	2.86	6.28	1,698
May 25	do	117	563	2.45	5.85	1,381
June 14	do	118	510	1.98	5.30	1,009
June 22	do	114	368	1.04	4.07	381
July 5	do	114	368	1.07	4.10	394
July 17	do	113	327	.70	3.55	221
September 16	do	113	337	.79	3.70	266

Daily gage height, in feet, of Truckee River at Vista, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	5.6	4.8	5.8	.....	5.6	5.7	4.1	3.4	3.4	4.0	4.3	4.3
2	5.4	5.1	5.8	5.0	5.8	5.6	4.1	3.4	3.5	4.0	4.3	4.4
3	5.4	5.9	5.9	5.0	6.0	5.4	4.1	3.4	3.5	4.0	4.1	4.4
4	5.4	4.8	5.9	4.9	6.2	5.7	4.1	3.4	3.5	4.0	4.1	4.4
5	5.3	4.8	6.0	5.3	5.8	5.6	4.1	3.4	3.5	4.0	4.1	4.4
6	5.3	4.8	6.0	5.4	5.6	5.3	4.1	3.4	3.6	4.0	4.2	4.4
7	5.2	4.8	6.0	5.5	5.5	5.3	4.0	3.4	3.6	4.1	4.2	4.4
8	5.2	4.8	6.0	5.5	5.5	5.2	3.9	3.4	3.7	4.1	4.2	4.4
9	5.2	4.7	6.0	5.3	5.5	5.3	3.9	3.4	3.7	4.1	4.2	4.4
10	5.1	4.9	5.8	5.5	5.5	5.6	3.8	3.4	3.7	4.1	4.2	4.0
11	5.1	4.8	5.9	5.4	5.3	5.3	3.7	3.4	3.7	4.2	4.3	4.2
12	5.1	4.8	5.9	5.2	5.2	5.5	3.7	3.4	3.7	4.2	4.3	4.1
13	5.0	4.8	6.1	5.0	5.0	5.6	3.7	3.4	3.7	4.2	4.3	4.1
14	5.0	4.9	6.0	5.0	4.8	5.6	3.5	3.4	3.7	4.2	4.3	4.2
15	5.0	4.9	5.8	5.1	5.6	5.4	3.5	3.5	3.7	4.2	4.2	4.1
16	4.9	5.0	5.5	5.0	5.7	5.4	3.5	3.5	3.7	4.2	4.2	4.1
17	5.8	4.9	5.5	4.9	5.3	5.3	3.4	3.5	3.7	4.2	4.2	4.1
18	4.8	4.9	5.5	4.8	5.4	5.3	3.4	3.6	3.7	4.2	4.2	4.1
19	4.7	5.0	5.5	4.8	6.3	5.3	3.4	3.6	3.7	4.2	4.2	4.1
20	4.8	5.5	5.5	4.9	6.2	5.0	3.4	3.6	3.7	4.2	4.3	4.1
21	5.2	5.3	5.5	5.0	6.2	5.0	3.4	3.6	3.7	4.2	4.3	4.0
22	5.3	5.4	5.5	4.5	6.0	4.8	3.4	3.7	3.7	4.2	4.4	3.7
23	5.0	5.4	5.3	4.7	5.8	4.8	3.4	3.7	3.8	4.2	4.4	3.7
24	5.0	5.9	5.3	4.5	5.7	4.4	3.4	3.7	3.8	4.3	4.3	3.1
25	4.9	5.8	5.0	4.5	6.0	4.6	3.2	3.7	3.9	4.3	4.2	3.9
26	4.8	5.8	5.0	6.0	5.9	4.6	3.2	3.7	3.9	4.3	4.2	4.2
27	4.8	5.8	5.5	6.5	5.7	4.4	3.3	3.7	3.9	4.2	4.2	4.1
28	4.7	5.8	5.4	6.3	5.8	4.2	3.4	3.6	3.9	4.2	4.2	4.1
29	4.8	.....	5.4	6.2	5.7	4.0	3.4	3.6	4.0	4.2	4.2	4.1
30	4.7	.....	4.9	6.2	5.7	4.0	3.4	3.5	4.0	4.2	4.3	4.1
31	4.7	.....	.....	.....	5.8	.....	3.4	3.5	.....	4.3	.....	4.1

Station rating table for Truckee River at Vista, Nev., from January 1 to December 31, 19

Gage height.	Discharge	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.20	150	4.10	405	5.00	850	5.80	1,350
3.30	171	4.20	445	5.10	910	5.90	1,420
3.40	195	4.30	485	5.20	970	6.00	1,490
3.50	220	4.40	525	5.30	1,030	6.10	1,560
3.60	245	4.50	570	5.40	1,090	6.20	1,635
3.70	275	4.60	620	5.50	1,155	6.30	1,710
3.80	305	4.70	675	5.60	1,220	6.40	1,785
3.90	335	4.80	730	5.70	1,285	6.50	1,860
4.00	370	4.90	790				

The above table is applicable only for open-channel conditions. It is based on 10 discharge meas ments made during 1905. It is well defined between gage heights 3.5 feet and 6.3 feet.

Estimated monthly discharge of Truckee River at Vista, Nev., for 1905.

[Drainage area, 1,519 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Dept inch
January	1,220	675	894	54,970	0.589	(
February	1,420	675	943	52,370	.621	
March	1,560	790	1,237	76,060	.814	
April	1,860	570	1,003	59,680	.660	
May	1,710	730	1,279	78,640	.842	
June	1,285	370	930	55,340	.612	
July	405	150	260	15,990	.171	
August	275	195	224	13,770	.147	
September	370	195	279	16,600	.184	
October	485	370	430	26,440	.283	
November	525	405	460	27,370	.303	
December	525	130	421	25,890	.277	
The year	1,860	130	697	503,100	.459	6

NOTE.—Ice conditions not known; open-channel rating table applied to the winter months with correction.

TRUCKEE RIVER AT NEVADA-CALIFORNIA STATE LINE.

This station was established September 7, 1899. It is located at the State line, 17 m west of Reno, Nev.

The channel is straight for 60 feet above and 75 feet below the cable. Both banks high and rocky and are not liable to overflow. The bed of the stream is composed bowlders and cobblestones. The current is swift.

Discharge measurements are made by means of a cable and car, 2½ miles below gage at Linham Siding and 100 feet below bridge No. 2. The initial point for sound is the zero of the tagged wire.

The gage was read once each day during 1905 by H. E. Dickinson. The original gage vertical, driven into the bed of the river and wired to a granite bowlder. Novembe 1902, a new gage was established on the right bank, 400 feet below the point at whic old gage was located. The new gage consists of two sections of 4 by 4 inch timber. upper section is vertical and is spiked to a cottonwood tree; the lower section is in and is immediately under the vertical section. The gage datum is the same as th the old gage. The bench mark consists of two spikes driven into the root of the c *wood tree* to which the vertical section of the gage is attached; elevation above z *gage, 5.99 feet.*

nation in regard to this station is contained in the following publications of the States Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

ɔtion: WS 38, p 331; 51, p 403; 66, p 112; 85, pp 119–120; 100, pp 192–193; 133, p 304.
rge: WS 38, p 331; 51, p 403; 66, p 112; 85, p 120; 100, p 193; 133, p 304.
rge, monthly: Ann 22, iv, p 404; WS 75, p 185; 85, p 121; 100, p 194; 133, p 306.
eights: WS 38, p 331; 51, p 404; 66, p 113; 85, p 120: 100, pp 193–194; 133, p 305.
graph: Ann 22, iv, p 404.
tables: WS 52, p 521; 66, p 175; 85, p 120; 100. p 194: 133, p 306.

scharge measurements of Truckee River at Nevada-California State line in 1905.

e.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
.....	W. A. Wolf.....	80	344	2.76	2.85	949
.....	.....do.....	80	370	2.91	2.95	1,078
.....	.....do.....	87	441	4.00	3.65	1,761
.....	.....do.....	81	378	3.10	3.08	1,170
.....	.....do.....	80	340	2.66	2.80	905
.....	.....do.....	80	300	1.93	2.25	580
.....	.....do.....	76	277	1.97	2.15	544
.....	.....do.....	76	277	1.95	2.12	539
er 13..	.....do.....	74	274	1.52	1.97	416

ily gage height, in feet, of Truckee River at Nevada-California State line for 1905.

y.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	2.3	3.3	2.4	3.45	3.3	2.3	2.0	2.05	2.02	2.02	1.95
.....	2.8	2.3	3.3	.....	3.35	3.25	2.35	2.07	2.1	2.02	1.9	1.9
.....	2.8	2.3	3.3	2.6	3.25	3.25	2.35	2.1	2.05	2.05	1.95	1.87
.....	2.8	2.3	3.3	2.6	3.2	3.08	2.32	2.07	2.1	2.05	2.0	1.9
.....	2.7	2.28	3.3	2.7	3.15	3.05	2.35	2.5	2.1	2.05	1.95	1.8
.....	2.7	2.3	3.3	2.85	3.08	3.25	2.32	2.15	2.05	2.15	1.97	1.8
.....	2.7	2.3	3.3	2.9	3.3	3.05	2.3	2.1	2.1	2.1	1.85	1.9
.....	.....	2.3	3.3	2.88	3.05	3.05	2.3	2.1	2.1	2.05	1.9	1.9
.....	2.65	2.3	3.3	.....	3.0	3.05	2.25	2.1	2.1	2.1	1.95	1.9
.....	2.7	2.35	3.2	3.25	2.95	3.35	2.2	2.1	2.1	2.1	1.95	1.9
.....	2.6	2.3	3.2	2.85	2.95	3.3	2.2	2.1	2.05	2.2	1.95	1.9
.....	2.6	2.35	3.2	2.8	2.9	3.3	2.1	2.18	2.05	2.15	1.87	1.85
.....	2.6	2.25	3.2	2.8	2.9	3.25	2.1	2.15	2.05	2.1	1.95	1.92
.....	2.2	2.25	3.25	2.8	2.98	3.17	2.25	2.1	2.05	2.1	1.7	1.87
.....	2.4	2.3	3.25	2.85	3.45	3.2	2.25	2.1	2.02	2.05	1.7	1.97
.....	2.4	2.35	2.7	2.85	3.65	.....	2.25	2.12	2.0	2.05	1.85	1.87
.....	2.2	2.4	2.7	2.85	3.95	3.22	2.18	2.1	2.05	2.05	1.98	1.9
.....	2.2	2.47	2.75	2.85	3.7	3.08	2.15	2.15	2.05	2.05	1.97	1.77
.....	2.2	2.4	2.75	2.82	3.75	3.05	2.15	2.1	2.15	2.05	1.8	1.8
.....	2.2	2.65	2.78	.....	3.75	3.0	2.02	2.1	2.1	2.05	1.95	1.8
.....	2.6	2.45	2.8	2.65	3.7	2.8	2.15	2.15	2.05	2.1	1.97	1.7
.....	2.7	2.85	2.8	2.65	3.7	2.8	2.15	2.15	2.05	2.05	2.0	1.7
.....	2.5	2.62	2.6	2.7	3.65	2.75	2.15	2.12	2.05	2.05	1.97	1.8
.....	2.5	3.02	2.45	2.9	3.65	2.6	2.15	2.1	2.05	2.2	2.0	1.8
.....	2.32	3.02	2.4	3.1	3.5	2.6	2.1	2.1	2.05	2.0	1.95	1.8
.....	2.32	3.08	2.95	4.02	3.4	2.5	2.1	2.02	2.05	2.02	1.9	1.82
.....	2.3	3.12	2.95	3.8	3.3	2.45	2.1	2.05	2.05	2.0	1.85	1.82
.....	2.5	3.05	2.5	3.8	3.35	2.4	2.1	2.1	2.05	2.02	1.9	1.8
.....	.....	.....	2.3	3.72	3.38	2.38	2.1	2.05	2.05	2.02	1.95	1.82
.....	2.4	.....	2.4	.....	3.4	2.35	2.1	2.1	2.05	2.0	1.95	1.78
.....	2.3	.....	2.4	.....	3.3	.....	2.0	2.02	.....	2.5	.....	1.75

Station rating table for Truckee River at Nevada-California State line from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.70	300	2.30	610	2.90	1,042	3.50	1,580
1.80	346	2.40	673	3.00	1,126	3.60	1,676
1.90	394	2.50	740	3.10	1,213	3.70	1,772
2.00	444	2.60	810	3.20	1,302	3.80	1,870
2.10	496	2.70	884	3.30	1,393	3.90	1,970
2.20	551	2.80	961	3.40	1,486	4.00	2,070

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1903–1905. It is well defined. Above gage height 3 feet it is the same as 1904 table.

Estimated monthly discharge of Truckee River at Nevada-California State line for 1905.

[Drainage area, 955 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	961	551	755	46,420	0.791	0.912
February	1,228	580	754	41,880	.789	.822
March	1,393	610	1,096	67,390	1.15	1.33
April	2,090	673	1,114	66,290	1.17	1.30
May	2,020	1,042	1,453	89,340	1.52	1.75
June	1,439	642	1,115	66,350	1.17	1.30
July	642	444	548	33,700	.574	.662
August	540	444	503	30,930	.527	.606
September	524	444	477	28,380	.499	.557
October	551	444	487	29,940	.510	.588
November	454	300	405	24,100	.424	.473
December	429	300	366	22,500	.383	.442
The year	2,090	300	756	547,900	.792	10.74

NOTE.—Ice conditions not known; open-channel rating table applied to the winter months without correction. Discharge interpolated on days when gage was not read.

TRUCKEE RIVER AT TAHOE, CAL.

This station was established June 17, 1900, with a view to ascertaining the actual overflow from Lake Tahoe and the real value of the lake as a storage reservoir. It is located at the city of Tahoe. About 500 feet from the lake there is a timber dam across the river, which has been maintained for more than twenty years for the purpose of controlling the discharge from the lake.

The channel is nearly straight for 300 feet above and below the station. At the point of measurement the right bank is low and is subject to overflow at very high stages of the stream; the left bank is rather high. The bed of the stream, which is of gravel and coarse sand, is smooth and stable. The current has a moderate velocity.

Discharge measurements are made from a cable and suspended car about one-fourth mile below the gage. In June, 1904, a new cable was put in 1 mile below the gage.

The gage, which is read once each day by J. U. Haley, is located about 300 feet below the dam, as near the city of Tahoe as possible, for the convenience of the observer. It consists of a vertical timber driven into the stream bed and spiked to the root of a cottonwood tree growing on the bank. November 18, 1902, a new gage was established in the *exact position* of the old gage and with its zero at the same elevation. It is a 4 by 4

l timber. The bench mark is cut in the side of the tree and is 4.00 feet above

.

on in regard to this station is contained in the following publications of the tes Geological Survey (Ann=Annual Report; Bull=Bulletin; WS=Water-er):

: Bull 140, pp 210–211; WS 51, p 402; 66, p 111; 85, pp 115–116; 100, p 183; 133, p 307.
Ann 11, ii, pp 64, 108; WS 51, p 402; 66, p 111; 85, p 116; 100, p 183; 133, p 307.
monthly: Ann 22, iv, p 403; Bull 140, p 212; WS 75, p 184; 85, p 117; 100, p 185; 133, p 309.
:s: Bull 140, p 211; WS 51, p 403; 66, p 112; 85, p 116; 100, p 184; 133, p 308.
n: Ann 22, iv, p 403.
es: WS 52, p 520; 66, p 175; 85, p 117; 100, p 184; 133, p 308.

Discharge measurements of Truckee River at Tahoe, Cal., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
W. A. Wolf	20	15.2	1.01	0.30	15.4
do	73	126	1.61	1.27	203
do	72	125	1.61	1.30	211
do	72	125	1.60	1.30	205
do	79	168	1.96	1.80	328

Daily gage height, in feet, of Truckee River at Tahoe, Cal., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
..	a 2.7	b 1.6	a 2.55	0 4	0.3	1.3	1.45	1.9	2.0	2.0	1.8	1.7
..	a 2.7	b 1.6	a 2.55	.4	.3	1.3	1.45	2.0	2.0	2.0	1.8	1.7
..	a 2.7	b 1.65	a 2.55	.4	.3	1.3	1.45	2.0	2.0	2.0	1.8	1.7
..	a 2.7	b 1.65	a 2.5	.4	.7	1.3	1.5	2.0	2.0	2.1	1.8	1.7
..	a 2.7	b 1.65	a 2.5	.4	1.0	1.3	1.5	2.0	2.0	2.1	1.7	1.7
..	a 2.6	c 1.65	a 2.5	.4	1.0	1.3	1.5	2.0	2.0	2.1	1.7	1.7
..	a 2.6	c 2.0	a 2.5	.4	1.25	1.3	1.5	2.0	2.0	2.1	1.7	1.7
..	a 2.6	c 2.0	a 2.5	.4	1.25	1.3	1.5	2.0	2.0	2.1	1 7	1.7
..	a 2.6	c 2.0	a 2.5	.4	1.25	1.3	1.5	1.95	2.0	2.1	1.7	1.6
..	a 2.6	c 2.0	a 2.5	.4	1.25	1.3	1.5	2.0	2.0	2.1	1.7	1.6
..	b 1.6	c 2.0	a 2.5	.4	1.25	1.3	1.5	2 0	1.9	2.1	1.7	1.6
..	b 1.6	c 2.0	2.5	.3	1.25	1.3	1.5	2.0	1.9	2.1	1.7	1.6
..	b 1.6	c 2.0	2.5	.3	1.25	1.3	1.6	2.0	1.9	2.0	1.7	1.6
..	b 1.6	c 2.0	2.5	.3	1.25	1.3	1.6	2.0	1.9	2.0	1.7	1.6
..	b 1.6	c 2.0	1.6	.3	1.25	1.3	1.6	2.0	1.9	2.0	1.7	1.6
..	b 1.6	c 2.0	1.6	.3	1.25	1.3	1.6	2.0	1.9	2.0	1.7	1.6
..	b 1.6	c 2.0	1.6	.3	1.25	1.3	1.6	2.0	1.9	2 0	1.7	1.5
..	b 1.6	c 2.0	1.6	.3	1.25	1.3	1.6	2.0	2.0	2.0	1.7	1.5
..	b 2.5	a 2.55	1.6	.3	1.25	1.3	1.9	2 0	2.0	2.0	1.7	1.5
..	b 2.5	a 2.55	1.15	.3	1.25	1.3	1.9	2.0	2.0	2.0	1.7	1.5
..	b 2.5	a 2.55	1.15	.3	1.25	1.3	1 9	2.0	2.0	2.0	1.7	1.5
..	b 1.6	a 2.55	1.15	.3	1.25	1.3	1.9	2.0	2.0	1.9	1.7	1.5
..	b 1.6	a 2.55	.4	.3	1.3	1.3	1.9	2.0	2.0	1.9	1.7	1.5
..	b 1.6	a 2.55	.4	.3	1.3	1.35	1.9	2.0	2.0	1.9	1.7	1.5
..	b 1.6	a 2.55	.4	.3	1.3	1.35	1.9	2.0	2.0	1.9	1.7	1.5
..	b 1.6	a 2.55	.4	.3	1.3	1.45	1.9	2.0	2.0	1.9	1.6	1.5
..	b 1.6	a 2.55	.4	.3	1.3	1.45	1.9	2 0	2.0	1.9	1.6	1.5
..	b 1.6	a 2.55	.4	.3	1.3	1.45	1.9	2.0	2.0	1.9	1.6	1.5
..	b 1.6	.....	.4	.3	1.3	1.45	1.9	2.0	2.0	1.9	1.6	1.4
..	b 1.6	.....	.4	.3	1.3	1.45	1.9	2.0	2.0	1.9	1.6	1.4
..	b 1.6	.....	.4	.....	1.3	.....	1.9	2.0	.....	1.8	.....	1.4

a All gates up. b One gate up. c Two gates up.

Station rating table for Truckee River at Tahoe, Cal., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.30	15	1.00	139	1.60	279	2.20	453
0.40	31	1.10	160	1.70	306	2.30	485
0.50	47	1.20	182	1.80	334	2.40	518
0.60	64	1.30	205	1.90	363	2.50	552
0.70	82	1.40	229	2.00	392	2.60	586
0.80	100	1.50	253	2.10	422	2.70	622
0.90	119						

The above table is applicable only for open-channel conditions. It is based on five discharge measurements made during 1905 and the form of previous curves. It is not well defined.

Estimated monthly discharge of Truckee River at Tahoe, Cal., for 1905.

[Drainage area, 519 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	622	279	410	25,210	0.790	0.911
February	569	279	433	24,050	.834	.868
March	569	31	321	19,740	.618	.712
April	31	15	20.9	1,244	.040	.045
May	205	15	173	10,640	.333	.384
June	241	205	212	12,620	.408	.455
July	363	241	303	18,630	.584	.673
August	392	363	391	24,040	.753	.868
September	392	363	385	22,910	.742	.828
October	422	334	390	23,980	.751	.866
November	334	279	305	18,150	.588	.656
December	306	229	271	16,660	.522	.602
The year	622	15	301	217,900	.580	7.87

NOTE.—Ice conditions not known. Open-channel rating table applied to the winter months without correction.

LAKE WINNEMUCCA INLET NEAR WADSWORTH, NEV.

This station was established November 7, 1902. It is located 3 miles north of Pyramid Lake Indian School and 21 miles north of Wadsworth, Nev.

The channel is straight for 150 feet above and below the cable. Both banks are high and not subject to overflow. The bed is composed of gravel and silt and may change slightly. There is but one channel at all stages. The current is moderate.

Discharge measurements are made by means of a cable and car near the gage. The initial point for soundings is the zero of the tagged wire.

The gage, which was read three times each day during 1905 by Edward C. Wood, is a 4 by 4 inch vertical timber spiked to a willow tree on the right bank. The bench mark consists of two spikes driven into the tree to which the gage is attached; elevation above zero of gage, 6.00 feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 100, p 190; 133, p 309.
Discharge. 100, p 191; 133, p 310.
Discharge, monthly: 100, p 192; 133, p 311.
Gage heights: 100, p 191; 133, p 310.
***Rating table*: 100, p 192; 133, p 311.**

Discharge measurements of Lake Winnemucca Inlet near Wadsworth, Nev., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
May 18	W. A. Wolf	46	118	1.66	3.30	196
June 8	do	46	114	1.61	3.20	185
July 11	do	46	85	1.75	2.75	149

Daily gage height, in feet, of Lake Winnemucca Inlet near Wadsworth, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.88	2.21	2.27	2.21	.....	.....	.....	.....	.....	2.2	2.1	.....
2	2.77	.....	.....	2.21	.....	3.45	2.45	2.65	2.35	.....	.....	1.95
3	.....	.....	2.27	.....	3.15	.....	.....	.....	2.35	.....	.....	1.9
4	2.66	2.29	.....	.....	.....	3.25	2.35	.....	.....	2.2	2.1	.....
5	.....	2.27	.....	2.23	.....	.....	.....	2.55	.....	.....	2.0	.....
6	2.66	.....	2.3	.....	3.1	.....	.....	2.6	2.3	2.15	.....	.....
7	.....	.....	.....	.....	3.08	3.12	.....	.....	.....	.....	.....	1.8
8	.....	2.24	.....	2.24	.....	3.1	2.32	2.65	.....	2.2	1.9	.....
9	2.21	.....	2.29	2.24	.....	.....	2.6	.....	2.3	.....	.....	1.8
10	.....	.....	.....	.....	3.1	3.0	.....	2.65	2.3	.....	1.8	1.8
11	2.21	2.21	2.28	.....	.....	2.3	.....	.....	.....	2.3	1.75	.....
12	.....	.....	2.28	2.24	.....	.....	2.65	2.65	.....	.....	1.75	.....
13	2.22	.....	.....	.....	3.05	.....	.....	2.7	2.25	.....	.....	1.85
14	.....	.....	.....	.....	3.05	2.15	.....	.....	.....	2.3	.....	.....
15	2.0	.....	.....	2.22	.....	.....	2.75	2.75	.....	2.2	.....	.....
16	2.0	2.24	2.26	2.2	.....	.....	2.75	.....	2.3	.....	1.8	1.8
17	.....	.....	.....	.....	3.2	2.15	.....	2.7	2.3	.....	.....	2.2
18	2.0	2.25	2.2	.....	.....	2.2	.....	.....	.....	2.25	1.85	.....
19	2.22	2.24	2.24	2.18	.....	.....	2.7	2.75	.....	.....	1.9	.....
20	1.19	.....	.....	.....	3.25	.....	.....	2.5	2.25	.....	.....	2.1
21	.....	.....	.....	.....	3.25	2.1	.....	.....	.....	2.2	.....	.....
22	1.19	2.26	2.24	2.17	.....	.....	2.68	.....	.....	2.2	1.9	.....
23	.....	.....	.....	2.19	.....	.....	2.6	2.6	2.2	.....	.....	2.1
24	.....	.....	.....	.....	3.15	2.05	.....	.....	2.2	.....	.....	2.0
25	2.0	2.29	2.2	2.36	.....	2.9	.....	.....	.....	2.15	1.95	.....
26	.....	2.25	2.22	.....	.....	.....	2.6	2.6	.....	.....	.....	.....
27	2.0	.....	.....	2.58	3.5	.....	.....	2.5	2.3	.....	.....	2.0
28	2.0	.....	.....	.....	3.45	2.65	.....	.....	.....	2.1	.....	.....
29	.....	.....	2.23	2.55	.....	.....	2.58	.....	.....	2.15	1.9	.....
30	2.0	.....	.....	3.2	.....	2.55	2.6	2.5	2.2	.....	.....	2.1
31	.....	.....	.....	.....	3.45	.....	.....	.....	.....	.....	.....	.....

Station rating table for Lake Winnemucca Inlet near Wadsworth, Nev., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.20	27	1.80	67	2.40	116	3.00	170
1.30	33	1.90	75	2.50	125	3.10	179
1.40	39	2.00	83	2.60	134	3.20	188
1.50	46	2.10	91	2.70	143	3.30	197
1.60	53	2.20	99	2.80	152	3.40	206
1.70	60	2.30	107	2.90	161	3.50	216

NOTE.—The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during 1905 and the form of previous curves. It is not well defined.

Estimated monthly discharge of Lake Winnemucca Inlet near Wadsworth, Nev., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	159	26	93.9	5,774
February	106	100	103	5,736
March	107	99	103	6,333
April	188	97	107	6,367
May	216	174	189	11,620
June	211	87	136	8,095
July	148	109	132	8,116
August	148	121	135	8,301
September	116	99	105	6,248
October	107	91	99.0	6,087
November	91	64	75.5	4,495
December	99	67	79.6	4,894
The year	216	26	113	82,040

NOTE.—Ice conditions not known; open-channel rating table applied to the winter months without correction. Discharge interpolated on days when gage was not read.

LITTLE TRUCKEE RIVER AT PINE STATION, CAL.

Little Truckee River rises on the eastern slope of the Sierra Nevada Mountains, in northwestern Nevada County, Cal., flows north, then east, and then south, and unites with the Truckee at the town of Boca, Cal.

The station was established June 25, 1903. The cable station is located about one-fourth mile upstream from Bruhn's mill, known also as Pine station. The road which follows the Little Truckee north from Boca crosses the river at a ford about 150 feet below the cable and the same distance above the gage rod. Pine station, on the Boca and Loyalton Railroad, about one-fourth of a mile distant, is the nearest railroad point.

Above the station the channel is straight for 100 feet at high water and for 30 feet at low water; below the station it is straight for 200 feet at high and low water. The right (south) bank is high, steep, and rocky and is not subject to overflow. It supports some underbrush and a few trees. The left (north) bank is composed of gravel for 40 feet back from the high-water channel, is low, and may be overflowed. The bed of the stream consists of course gravel and is free from vegetation. There is but one channel at all stages. The current is swift.

Discharge measurements are made from a wooden car running on a three-eighth-inch steel cable which is stretched across the river about 5½ feet above the high-water level. A tag wire is stretched just above the cable. The initial point for sounding is the post which supports the cable on the left bank.

The gage, which is read twice each day by S. Wallace, is located about 300 feet below the cable, and consists of a vertical 2 by 6 inch board. The bench mark is the head of a large nail driven into a 2 by 4 inch timber set in the ground in a clump of small willows 8 feet from the gage; willows surrounding the bench mark are blazed and marked "B. M., U. S. G. S."; elevation of bench mark above zero of gage, 4.83 feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 100, p. 195; 133, p 312.
Discharge: 100, p 195; 133, p 313.
Discharge, monthly: 100, p 197; 133, p 314.
Gage heights: 100, p 196; 133, p 313.
Rating table: 100, p 196; 133, p 314.

Discharge measurements of Little Truckee River at Pine Station, Cal., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
pril 16	W. A. Wolf	66	104	2.78	1.85	289
[ay 11	do	66	101	2.71	1.80	274
[ay 27	do	67	126	2.90	2.05	366
une 7	do	68	109	3.15	2.00	343
une 23	do	60	75	1.84	1.36	138
uly 8	do	54	58	1.70	1.12	98
uly 24	do	52	51	1.59	1.03	81

Daily gage height, in feet, of Little Truckee River at Pine Station, Cal., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.28	1.13	1.36	1.53	2.49	2.26	1.28	0.75	0.58	0.7	0.71	1.12
2	1.25	1.19	1.44	1.6	2.5	2.22	1.4	.75	.6	.7	.71	1.2
3	1.24	1.09	1.43	1.64	2.59	2.14	1.4	.73	.58	.7	.7	1.13
4	1.0	1.04	1.46	1.65	2.43	2.09	1.38	.73	.6	.7	.71	1.1
5	0.99	1.0	1.54	1.75	2.29	1.99	1.32	.72	.6	.68	.66	1.15
6	1.14	1.0	1.59	1.76	2.22	1.97	1.22	.7	.6	.68	.65	1.18
7	1.16	1.0	1.6	1.83	2.24	1.96	1.18	.7	.6	.68	.71	1.2
8	1.14	.82	1.62	1.84	2.15	2.04	1.18	.7	.6	.7	.69	1.13
9	1.06	.86	1.6	1.85	2.12	2.12	1.14	.68	.6	.7	.67	1.15
10	1.12	.94	1.59	1.84	1.99	2.16	1.12	.68	.61	.7	.67	1.13
11	1.1	1.02	1.6	1.78	1.95	2.21	1.1	.68	.6	.68	.71	1.26
12	1.06	.94	1.56	1.94	1.9	2.3	1.04	.7	.61	.68	.82	1.23
13	1.01	1.0	1.68	1.74	1.99	2.26	1.04	.7	.61	.68	.8	1.3
14	1.08	1.0	1.58	1.76	2.12	2.19	1.1	.7	.61	.68	.81	1.3
15	1.25	1.02	1.53	1.85	2.1	2.16	1.1	.68	.6	.68	.79	1.3
16	1.25	1.06	1.55	1.8	2.35	2.14	1.06	.65	.6	.69	.83	1.25
17	1.25	1.04	1.56	1.72	2.62	2.16	0.98	.65	.62	.67	.83	1.18
18	1.19	1.02	1.5	1.82	2.58	2.03	.93	.65	.63	.7	.81	1.23
19	1.12	1.1	1.52	1.7	2.5	1.99	.9	.64	.63	.69	.79	1.2
20	1.13	1.18	1.56	1.63	2.5	1.98	.9	.63	.63	.69	.81	1.2
21	1.06	1.05	1.56	1.62	2.52	1.93	.9	.66	.63	.69	.83	1.0
22	1.11	1.05	1.48	1.62	2.44	1.8	.86	.7	.63	.69	.9	1.2
23	1.26	1.06	1.51	1.69	2.25	1.76	.85	.7	.63	.69	.87	1.15
24	1.29	1.14	1.58	1.8	2.29	1.72	1.02	.65	.64	.69	.79	1.2
25	1.23	1.24	1.56	2.46	2.26	1.66	.9	.65	.65	.7	.74	1.25
26	1.3	1.28	1.82	2.74	2.36	1.65	.88	.63	.65	.7	.73	1.3
27	1.26	1.32	1.62	2.69	2.12	1.66	.82	.62	.65	.7	.83	1.25
28	1.14	1.38	1.54	2.72	2.24	1.34	.8	.6	.69	.7	1.0	1.12
29	1.13	.....	1.43	2.85	2.2	1.3	.8	.6	.7	.7	1.2	1.15
30	1.06	.....	1.52	2.59	2.22	1.28	.8	.6	.73	.7	1.12	.....
31	1.14	.....	1.49	.....	2.2	.....	.75	.58	.....	.7	.....	1.23

Station rating table for Little Truckee River at Pine Station, Cal., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.60	35	1.20	107	1.80	270	2.40	531
0.70	45	1.30	126	1.90	307	2.50	580
0.80	55	1.40	148	2.00	347	2.60	630
0.90	66	1.50	174	2.10	390	2.70	681
1.00	78	1.60	203	2.20	436	2.80	733
1.10	91	1.70	235	2.30	483	2.90	786

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is well defined between gage heights 1 foot and 2.1 feet.

Estimated monthly discharge of Little Truckee River at Pine Station, Cal., for 1905.

[Drainage area, 166 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	126	77	101	6,210	.608	.701
February	144	57	89.0	4,943	.536	.558
March	277	139	188	11,560	1.13	1.30
April	760	183	334	19,870	2.01	2.24
May	640	307	477	29,330	2.87	3.31
June	483	122	337	20,050	2.03	2.26
July	148	50	86.3	5,306	.520	.600
August	50	33	42.1	2,589	.254	.293
September	48	33	37.4	2,226	.225	.251
October	45	42	44.2	2,718	.266	.307
November	107	40	55.4	3,296	.334	.373
December	126	78	106	6,518	.637	.734
The year	760	33	158	114,600	.952	12.95

NOTE.—Ice conditions not known; open-channel rating table applied to the winter months without correction.

INDEPENDENCE CREEK BELOW INDEPENDENCE LAKE, CAL.

Independence Creek flows from the east end of Independence Lake northeastward into Little Truckee River.

The gaging station was established October 24, 1902, It is located about one-eighth of a mile below the dam at the lower end of Independence Lake, Cal.

The channel is straight for 50 feet above and below the station. The banks are low and subject to overflow. The bed of the stream is permanent, being composed of gravel and clay, but during high water large quantities of sand are washed down the creek. The current is moderately rapid and the discharge is controlled by the dam at the end of the lake.

Discharge measurements are made from a cable and car.

The gage, which is read twice daily by William Schweinberger, consisted originally of a vertical 4 by 4 inch timber, located about 200 feet upstream from the cable. For the convenience of the observer a new vertical gage, made of 2 by 4 inch timber, was established July 1, 1904, on the left bank of the stream 75 feet below the outlet of the lake. Simultaneous readings taken on the two gages give identical results for the fluctuations of 1904. The bench mark for the original gage consists of three nails driven into the root of a pine tree *55 feet northwest* of the gage; elevation above zero of gage, 5.82 feet. The bench mark for

new gage is the head of four nails driven into the tree stump to which the new gage rod is ened; elevation above zero of new gage, 3.00 feet.

nformation in regard to this station is contained in the following Water-Supply Papers of United States Geological Survey:

scription: 85, p 121; 100, p 197; 133, p 315.
scharge: 85, p 122; 100 p 197; 133, p 315.
scharge, monthly: 100, p 199; 133, p 317.
ge heights: 85, p 122; 100, p 198; 133, p 316.
ting table: 100, p 199; 133, p 317.

ischarge measurements of Independence Creek below Independence Lake, Cal., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
12	W. A. Wolf	28	62	1.24	3.25	77
26	do		3	1.00	1.80	3
7	do	11	9	1.67	2.30	15
ust 3	do	6	3	1.48	2.00	4.3
ember 11	do				1.70	a.5

a Estimated.

ily gage height, in feet, of Independence Creek below Independence Lake, Cal., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
	2.1	2.7	2.5	2.7	3.28	3.2	1.88	2.0	1.65	1.5	1.5	2.18
	2.1	2.58	2.5	2.7	3.5	3.2	2.0	2.0	1.65	1.5	1.5	2.15
	2.15	2.4	2.5	2.45	3.5	3.1	2.1	2.0	1.65	1.5	1.45	2.12
	2.15	2.3	2.5	2.25	3.5	3.1	2.2	2.0	1.65	1.5	1.45	2.1
	2.15	2.2	2.5	2.25	3.5	3.1	2.25	2.0	1.65	1.5	1.45	2.3
	2.18	2.2	2.5	2.25	3.35	3.1	2.3	2.0	1.65	1.5	1.45	2.5
	2.2	2.2	2.5	2.25	3.15	3.05	2.3	1.95	1.65	1.5	1.45	2.25
	2.2	2.2	2.5	2.28	3.1	3.08	2.3	1.95	1.65	1.5	1.45	2.0
	2.2	2.2	2.5	2.3	3.05	3.1	2.3	1.95	1.65	1.5	1.45	2.0
	2.2	2.2	2.5	2.3	3.15	3.15	2.25	1.95	1.65	1.5	1.38	1.98
	2.22	2.2	2.5	2.3	2.7	3.18	2.25	1.9	1.65	1.5	2.35	1.95
	2.25	2.2	2.5	2.3	2.7	3.2	2.25	1.9	1.6	1.5	2.3	1.95
	2.32	2.2	2.5	2.3	2.7	3.2	2.2	1.9	1.6	1.5	2.25	1.92
	2.52	2.22	2.5	2.3	2.7	3.2	2.18	1.9	1.6	1.5	2.2	1.9
	2.6	2.25	2.5	2.3	2.7	3.22	2.1	1.9	1.6	1.5	2.2	1.88
	2.6	2.25	2.5	2.3	2.7	3.22	2.1	1.85	1.6	1.5	2.15	1.88
	2.6	2.25	2.5	2.3	2.88	3.2	2.1	1.85	1.55	1.5	2.15	1.85
	2.62	2.25	2.5	2.65	3.08	3.2	2.05	1.85	1.55	1.5	2.1	1.85
	2.65	2.38	2.5	3.05	3.08	3.2	2.05	1.85	1.55	1.5	2.1	1.9
	2.68	2.48	2.6	3.05	3.28	3.2	2.05	1.85	1.55	1.5	2.15	1.9
	2.88	2.5	2.7	3.05	3.45	3.15	2.08	1.85	1.55	1.5	2.1	1.9
	2.98	2.5	2.7	3.2	3.45	3.15	2.1	1.85	1.55	1.5	2.1	1.85
	2.98	2.5	2.7	3.1	3.45	3.15	2.15	1.85	1.55	1.5	2.1	1.85
	3.02	2.5	2.7	3.1	3.0	3.1	2.2	1.8	1.55	1.5	2.5	1.82
	3.12	2.5	2.8	3.1	2.55	3.08	2.2	1.75	1.55	1.5	2.5	1.84
	3.25	2.5	2.72	3.1	2.55	2.4	2.15	1.75	1.55	1.5	2.25	1.8
	3.25	2.5	2.75	3.1	2.55	1.8	2.1	1.7	1.55	1.5	2.12	1.85
	3.08	2.5	2.75	3.1	3.05	1.8	2.1	1.7	1.5	1.5	2.15	1.85
	2.85	.....	2.75	3.1	3.08	1.82	2.05	1.68	1.5	1.5	2.2	1.9
	2.85	.....	2.75	3.1	3.18	1.88	2.05	1.65	1.5	1.5	2.2	1.9
	2.85	.....	2.75	.....	3.2	.....	2.05	1.65	.....	1.5	.....	1.98

Station rating table for Independence Creek below Independence Lake, Cal., from January 1, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge	Gage height.	Discharge.	Gage height	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.30	0.3	1.90	3.4	2.50	23	3.10	107
1.40	.4	2.00	4.7	2.60	30	3.20	127
1.50	.5	2.10	6.7	2.70	40	3.30	148
1.60	.9	2.20	9.5	2.80	53	3.40	170
1.70	1.5	2.30	13	2.90	69	3.50	192
1.80	2.3	2.40	17	3.00	87		

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904–5. It is well defined between gage heights 2 feet and 3.25 feet. Below 2 feet the table is rather uncertain.

Estimated monthly discharge of Independence Creek below Independence Lake, Cal., for 1905.

[Drainage area, 8.5 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	137	6.7	43.0	2,644	5.06	5.83
February	40	9.5	16.4	911	1.93	2.01
March	53	23	30.7	1,888	3.61	4.16
April	127	11	52.7	3,136	6.20	6.92
May	192	26	107	6,579	12.59	14.52
June	131	2.3	98.9	5,885	11.64	12.98
July	13	3.2	8.2	504	.965	1.11
August	4.7	1.2	3.1	191	.365	.419
September	1.2	.5	.90	54	.106	.118
October	.5	.5	.50	31	.059	.068
November	23	.4	7.0	417	.824	.919
December	23	2.3	5.1	314	.600	.692
The year	192	.4	31.1	22,550	3.66	49.75

NOTE.—Ice conditions not known; open-channel rating table applied to the winter months without correction.

PROSSER CREEK NEAR HOBART MILLS, CAL.

Prosser Creek rises on the eastern slope of the Sierra Nevada in central Sierra County, Cal., flows in a general southeasterly direction, and unites with Truckee River near Prosser.

The station was established June 27, 1903. It is located about 150 feet below the wagon bridge and the road house on the Boca and Truckee highway, 4 miles from Truckee and 3 miles from Hobart Mills. Alder Creek joins Prosser Creek about 200 feet above the station. The nearest dam is located at the ice pond about 2 miles below the station.

The channel is straight for 150 feet above and 200 feet below the cable. The creek bends at the highway bridge. Both banks are high and are not subject to overflow. The right bank is wooded; the left is cleared except for a few willows. The bed is composed of coarse gravel and is free from vegetation. There is but one channel at all stages.

Discharge measurements are made from a wooden car running on a three-eighths inch steel cable, which is stretched across the river about 5 feet above high-water level. A tag wire is stretched just above the cable.

The original gage consisted of a 2 by 4 inch vertical timber. It was located on the left or north bank 50 feet upstream from the cable. The old gage, the zero of which was 9.87 feet below the bench mark, was washed out by a flood February 24, 1904. A new gage was established at the same point, with its zero 9.58 feet below the bench mark. The bench

the northeast pier of the steel wagon bridge, and is the top of the steel casing of te pier above the arrow mark.

tion in regard to this station is contained in the following Water-Supply Papers ted States Geological Survey:

on: 100, pp 200-201; 133, p 318.
: 100, p 201; 133, p 318.
, monthly: 133, p 320.
hts: 100, p 201; 133, p 319.
ble: 133, p 319.

Discharge measurements of Prosser Creek near Hobart Mills, Cal., in 1905.

	Hydrographer.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Square feet.	*Feet per second.*	*Feet.*	*Second-feet.*
....	W. A. Wolf	57	2.22	2.05	129
....	.....do	69	2.60	2.30	179
....	.....do	68	2.43	2.25	165
....	.....do	55	2.20	2.00	120
....	.....do	55	1.91	1.90	101
....	.....do			1.25	11

DONNER CREEK NEAR TRUCKEE, CAL.

Creek flows from the east end of Donner Lake eastward into Truckee River.
ing station was established October 23, 1902. It is located about 150 feet below f the Donner Creek Ice Company and 1½ miles west of Truckee, Cal.
nnel is straight for 150 feet above and below the cable. Both banks are high and erflow. The bed of the stream is composed of gravel, is permanent, and is free tation. There is but one channel at all stages and the current is swift.
ge measurements are made by means of a cable and car 50 feet downstream from

e, which is read twice each day by F. R. Williams, is a 4 by 4 inch vertical timber the left bank. The bench mark consists of four nails driven into the root of a 2 inches in diameter 35 feet north of the gage; elevation above zero of gage, 6.30

tion in regard to this station is contained in the following Water-Supply Papers ted States Geological Survey:

on: 85, p 123; 100, p 202; 133, p 320.
: 51, p 405; 85, p 123; 100, p 202; 133, p 321.
, monthly: 100, p 204; 133, p 322.
hts: 85, p 123; 100, pp 202-203; 133, p 321.
ble: 100, p 203; 133, p 322.

Discharge measurements of Donner Creek near Truckee, Cal., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet*	*Second-feet.*
....	W A. Wolf	36	48	3.27	3.06	157
....	.....do	36	48	3.25	3.01	156
....	.....do	38	56	4.00	3.42	224
....	.....do	20	17	2.18	2.12	37
....	.....do	10	12	1.34	1.74	16.0
....	.....do				1.15	1.0
....	.....do				.90	.2
....	.....do				1.00	.5

Daily gage height, in feet, of Donner Creek near Truckee, Cal., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.9	1.7	3.0	2.7	3.6	3.3	1.9	1.1	1.0	1.0	0.65	2.2
2	1.9	1.8	3.0	2.6	3.5	3.2	1.9	.95	2.25	1.0	.75	.0
3	1.9	1.8	3.0	2.6	3.45	3.15	1.9	.9	2.2	.95	.8	.0
4	1.7	1.8	3.0	2.65	3.4	3.05	1.85	.9	1.1	.95	.8	.0
5	1.7	1.8	3.05	2.75	3.35	3.0	1.8	1.0	1.2	.95	.8	.0
6	1.7	1.8	3.1	2.8	3.3	3.0	1.75	1.05	1.15	.5	.85	.9
7	1.7	1.8	3.1	2.8	3.3	3.0	1.7	1.0	1.0	.45	.9	.9
8	1.7	1.7	3.0	2.9	3.3	3.0	1.7	1.0	1.0	1.0	.9	.9
9	1.7	1.7	3.0	3.0	3.25	3.0	1.65	1.0	1.0	1.5	.9	.9
10	1.6	1.7	3.0	3.1	3.15	3.0	1.6	1.0	1.0	1.6	.9	.9
11	1.6	1.7	3.0	3.0	3.1	3.0	1.55	1.0	1.0	1.75	.9	.9
12	1.6	1.9	3.0	3.1	3.05	3.0	1.55	1.0	1.0	1.6	.9	.9
13	1.6	2.2	3.0	3.1	3.0	2.95	1.5	1.0	1.0	1.8	.9	.9
14	1.9	2. .	2.9	3.1	3.1	2.95	1.45	1.0	1.0	1.8	.9	.9
15	1.9	2.2	2.9	3.1	3.25	2.9	1.5	1.0	1.0	1.55	.9	.9
16	1.9	2.2	2.8	3.1	3.5	2.85	1.4	1.0	1.0	1.35	1.2	.9
17	1.9	2.2	2.8	3.1	3.55	2.85	1.35	1.0	1.0	1.15	1.15	.9
18	1.8	2.2	2.8	3.05	3.6	2.85	1.3	1.0	1.0	1.05	.95	.9
19	1.8	2.25	2.8	3.0	3.6	2.8	1.3	1.0	1.0	1.05	.9	.9
20	1.7	2.5	2.8	3.0	3.5	2.8	1.25	1.0	1.0	1.0	.9	.9
21	1.7	2.4	2.8	3.0	3.5	2.7	1.2	1.0	1.0	1.0	.9	.9
22	1.9	2.3	2.8	3.0	3.5	2.55	1.15	1.0	1.0	1.0	.9	.9
23	1.8	2.35	2.8	3.05	3.4	2.35	1.1	1.0	1.0	1.45	.9	.9
24	1.8	2.35	2.8	3.1	3.4	2.25	1.2	1.0	1.0	1.8	.9	.9
25	1.8	3.2	2.8	3.1	3.4	2.2	1.15	1.0	1.0	1.0	.9	.9
26	1.7	3.15	2.8	3.5	3.4	2.15	1.15	1.0	1.0	.0	.9	.95
27	1.7	3.05	2.8	3.7	3.35	2.1	1.15	1.0	1.0	.0	.9	1.0
28	1.8	3.0	2.8	3.6	3.3	2.1	1.15	1.0	1.0	.0	.9	1.0
29	1.8	.....	2.8	3.65	3.3	2.0	1.15	1.0	1.0	.15	.9	1.0
30	1.7	.....	2.7	3.6	3.3	2.0	1.15	1.0	1.0	.45	.9	1.0
31	1.7	.....	2.7	.....	3.3	.....	1.12	1.0	.....	.55	.....	1.0

Station rating table for Donner Creek near Truckee, Cal., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.70	0.0	1.50	8.3	2.30	52	3.10	166
.80	.1	1.60	11.5	2.40	62	3.20	185
.90	.2	1.70	15	2.50	73	3.30	206
1.00	.5	1.80	19	2.60	86	3.40	227
1.10	1.1	1.90	24	2.70	100	3.50	248
1.20	2.0	2.00	29	2.80	115	3.60	269
1.30	3.5	2.10	35	2.90	131	3.70	290
1.40	5.7	2.20	43	3.00	148		

The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1904-5. It is well defined.

Estimated monthly discharge of Donner Creek near Truckee, Cal., for 1905.

[Drainage area, 30 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	24	11.5	17.8	1,094	0.593	0.684
February	185	15	53.1	2,949	1.77	1.84
March	166	100	130	7,993	4.33	4.99
April	290	86	163	9,699	5.43	6.06
May	269	148	218	13,400	7.27	8.38
June	206	29	114	6,783	3.80	4.24
July	24	1.1	8.6	529	.287	.331
August	1.1	.2	.51	31	.017	.020
September	48	.5	3.6	214	.120	.134
October	19	0	4.4	270	.147	.170
November	2	0	.29	17	.0097	.011
December	43	0	1.6	98	.053	.061
The year	290	0	59.6	43,290	1.98	26.92

NOTE.—Ice conditions not known; open-channel rating table applied to winter months without correction.

WALKER RIVER BASIN.

DESCRIPTION OF BASIN.

Walker River is formed by two branches—East and West forks—which rise on the eastern slopes of the Sierra Nevada, in Mono County, Cal., flow in a general northerly direction, and unite in Lyon County, Nev. From the point of junction the main stream flows northward through Mason Valley, at the upper end of which it turns to the east and southeast and discharges into the north end of Walker Lake.

WEST FORK OF WALKER RIVER NEAR COLEVILLE, CAL.

This station was established October 5, 1902. The cable is located about 1 mile east of the point where the main road from Topaz to Bridgeport crosses Lost Canyon Creek and is 100 feet from the road. The gage is about one-half mile above the cable.

The channel is straight for 150 feet above and below the station. The right bank is low and rocky and is liable to overflow; the left is high and rocky and will not overflow. The bed of the stream is rocky and uneven. There is but one channel at all stages and the current is swift.

Discharge measurements are made by means of a cable and car. The initial point for soundings is the zero of the tagged wire.

The gage, which is read once each day by J. S. Trumbull, is a 4 by 4 inch vertical timber on the left bank, about 300 feet from the observer's house. The bench mark is a spike driven into the tree to which the gage is fastened; elevation above zero of gage, 6.00 feet.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 85, p 108; 100, pp 172-173; 133, p 323.
Discharge: 85, p 108; 100, p 173; 133, p 323.
Discharge, monthly: 100, p 174; 133, p 325.
Gage heights: 85, p 108; 100, p 173; 133, p 324.
Rating table: 100, p 174; 133, p 324.

Discharge measurements of West Fork of West Walker River near Coleville, Cal., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
May 3	J. L. Brambila	51	109	3.20	2.50	349
May 11	do	48	98	2.37	2.15	232
May 24	do	55	165	5.13	3.45	846
June 6	do	55	160	4.11	3.10	657
June 29	do	55	160	4.35	3.20	694
July 8	do	55	147	4.40	3.10	645
July 24	do	47	99	2.04	2.00	202
July 25	do	54	134	2.48	2.30	333
August 30	W. A. Wolf	50	82	.99	1.30	81

Daily gage height, in feet, of West Fork of Walker River near Coleville, Cal., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.3	1.4	1.5	1.7	2.9	3.1	2.9	1.9	1.2	1.2	1.1	0.9
2	1.3	1.4	1.5	1.7	2.7	3.1	2.9	1.9	1.1	1.2	1.1	.9
3	1.2	1.4	1.5	1.8	2.7	3.0	2.8	1.8	1.2	1.2	1.1	1.1
4	1.2	1.4	1.6	1.8	2.6	3.1	2.7	1.8	1.2	1.2	1.9	1.1
5	1.2	1.3	1.7	2.0	2.1	3.1	2.6	1.8	1.2	1.2	1.1	1.1
6	1.2	1.3	1.7	2.1	2.3	3.0	2.7	1.7	1.2	1.05	1.1	1.1
7	1.2	1.4	1.7	2.1	2.3	2.9	2.7	1.6	1.2	1.1	1.1	1.1
8	1.2	1.4	1.7	2.1	2.2	3.0	2.8	1.6	1.2	1.1	1.1	1.1
9	1.2	1.4	1.7	2.2	2.2	3.1	2.8	1.6	1.2	1.05	1.1	1.2
10	1.2	1.3	1.7	2.1	2.1	3.2	2.7	1.6	1.1	1.05	1.1	1.2
11	1.2	1.3	1.7	2.1	2.1	3.5	2.7	1.5	1.1	1.05	1.1	1.1
12	1.2	1.3	1.7	2.1	2.2	3.7	2.6	1.5	1.1	1.05	.9	1.1
13	1.2	1.3	1.7	2.1	2.3	3.9	2.5	1.5	1.1	1.05	.9	1.1
14	1.2	1.3	1.7	2.1	2.9	3.9	2.5	1.5	1.1	1.05	.8	1.1
15	1.2	1.3	1.7	2.0	3.4	3.8	2.4	1.5	1.1	1.05	.8	1.2
16	1.2	1.4	1.7	2.1	3.5	3.6	2.4	1.5	1.1	1.0	.8	1.2
17	1.2	1.4	1.7	2.1	3.5	3.6	2.3	1.4	1.1	1.0	.9	1.1
18	1.2	1.3	1.8	2.2	3.6	3.7	2.2	1.4	1.1	1.0	.9	1.1
19	1.2	1.3	1.8	2.2	3.5	3.8	2.1	1.4	1.1	1.0	.9	1.1
20	1.3	1.3	1.8	2.1	3.5	3.9	2.1	1.4	1.05	1.0	.9	1.1
21	1.3	1.3	1.7	2.0	3.4	3.8	2.2	1.4	1.05	1.0	.9	1.1
22	1.3	1.3	1.7	2.1	3.3	3.7	2.2	1.4	1.05	1.0	.8	1.1
23	1.3	1.3	1.6	2.2	3.2	3.5	2.2	1.4	1.05	1.0	.9	1.1
24	1.4	1.3	1.6	2.2	3.3	3.3	2.2	1.4	1.05	1.0	.9	1.2
25	1.4	1.4	1.6	2.4	3.3	3.1	2.2	1.3	1.05	1.0	.8	1.2
26	1.3	1.4	1.6	2.5	3.2	3.0	2.1	1.3	1.05	1.0	.9	1.2
27	1.3	1.4	1.6	2.4	3.0	2.9	2.1	1.2	1.05	1.0	.9	1.1
28	1.3	1.5	1.6	2.9	2.9	2.8	2.1	1.2	1.2	1.0	.9	1.1
29	1.3	.....	1.6	3.1	2.8	2.8	2.0	1.2	1.2	1.0	1.1	.9
30	1.3	.....	1.8	3.1	3.0	2.9	2.0	1.2	1.2	1.0	1.1	.9
31	1.3	.....	1.7	.....	3.1	.....	2.0	1.2	.....	1.0	.....	.9

n rating table for West Fork of Walker River near Coleville, Cal., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.80	44	1.60	121	2.40	317	3.20	702
.90	50	1.70	138	2.50	353	3.30	762
1.00	56	1.80	157	2.60	393	3.40	823
1.10	62	1.90	178	2.70	436	3.50	886
1.20	70	2.00	201	2.80	483	3.60	952
1.30	80	2.10	226	2.90	534	3.70	1,020
1.40	92	2.20	254	3.00	588	3.80	1,090
1.50	106	2.30	284	3.10	644	3.90	1,160

above table is applicable only for open-channel conditions. It is based on 11 discharge measnts made during 1905. It is well defined between gage heights 1.2 feet and 3.5 feet.

ated monthly discharge of West Fork of Walker River near Coleville, Cal., for 1905.

[Drainage area, 306 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ry	92	70	75.3	4,630	0.246	0.284
ary	106	80	86.1	4,782	.281	.293
	157	106	133	8,178	.435	.502
	644	138	266	15,830	.869	.970
	952	226	558	34,310	1.82	2.10
	1,160	483	791	47,070	2.58	2.88
	534	201	334	20,540	1.09	1.26
t	178	70	107	6,579	.350	.404
ıber	70	59	64.1	3,814	.209	.233
er	70	56	59.4	3,652	.194	.224
ıber	178	44	58.1	3,457	.190	.212
ber	70	50	61.9	3,806	.202	.233
The year	1,160	44	216	156,600	.706	9.60

E.—Ice conditions not known. Open-channel rating table applied to winter months without ion.

EAST FORK OF WALKER RIVER NEAR YERINGTON, NEV.

s station was established October 6, 1902. It is located at Ross Ranch, about 10 southeast of Yerington, Nev., just above the point where the road crosses the river. channel is straight for 200 feet above and for 100 feet below the station. At low the sand bar in the middle of the stream divides the channel into two parts. Both are low and are liable to overflow. The bed of the stream is composed of sand and nd shifts somewhat. The current has a moderate velocity.

charge measurements are made by means of a cable and car. The initial point for ings is the zero of the tagged wire.

gage, which is read once each day by I. A. Strosnider, the ranch owner, is a vertical 4 inch timber fastened to the right bank just below the cable. The bench mark ts of three nails and a spike in a stump 6 inches in diameter 15 feet east of the gage; ion above zero of gage, 5.85 feet.

ormation in regard to this station is contained in the following Water-Supply Papers United States Geological Survey:

ription: 85, p 107; 100, p 170; 133, p 325.
harge: 85, p 108; 100, p 170; 133, p 326.

Discharge, monthly: 100, p 172; 133, p 327.
Gage heights: 85, p 108; 100, pp 170–171; 133, p 326.
Rating table: 100, p 171; 133, p 327.

Discharge measurements of East Fork of Walker River near Yerington, Nev., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
May 4	J. L. Brambila	50	36	1.86	1.80	67
May 9	do	73	36	1.92	1.79	69
May 18	do	73	54	2.10	2.50	113
May 23	do	54	37	2.20	1.92	81
June 5	do	49	28	2.14	1.90	60
June 15	do	72	70	2.43	2.40	170
June 19	do	73	99	2.94	2.75	291
June 30	do	71	69	2.27	2.35	156
July 7	do	72	64	2.19	2.30	141
July 26	do	71	48	1.73	2.08	82
July 28	do	72	51	1.66	2.05	84

Daily gage height, in feet, of East Fork of Walker River near Yerington, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.1	2.2	2.4	2.2	1.5	2.1	2.3	1.9	1.6	1.7	1.9	2.0
2	2.1	2.2	2.4	2.2	1.5	2.1	2.35	1.9	1.6	1.7	1.9	2.0
3	2.1	2.2	2.4	2.2	1.5	2.05	2.4	1.9	1.6	1.7	1.9	2.0
4	2.1	2.2	2.4	2.2	1.5	2.05	2.4	1.8	1.7	1.7	1.9	1.9
5	2.1	2.3	2.35	2.2	1.45	2.0	2.4	1.8	1.7	1.7	1.9	1.9
6	2.1	2.3	2.3	2.2	1.4	1.9	2.3	1.8	1.7	1.7	1.9	1.9
7	2.1	2.3	2.3	2.2	1.4	1.9	2.3	1.8	1.7	1.7	1.9	1.9
8	2.1	2.3	2.3	2.2	1.4	1.9	2.25	1.8	1.7	1.7	1.9	1.9
9	2.1	2.3	2.3	2.2	1.4	1.9	2.2	1.8	1.7	1.7	1.9	1.9
10	2.1	2.3	2.3	2.2	1.4	1.9	2.2	1.7	1.6	1.6	1.9	1.9
11	2.1	2.3	2.3	2.2	1.4	2.0	2.2	1.7	1.6	1.6	1.9	1.9
12	2.1	2.3	2.3	2.1	1.4	2.1	2.3	1.7	1.6	1.6	1.9	1.9
13	2.15	2.3	2.3	2.1	1.45	2.2	2.3	1.7	1.6	1.6	1.9	1.9
14	2.2	2.3	2.3	2.1	1.45	2.3	2.2	1.7	1.6	1.6	1.9	1.9
15	2.2	2.3	2.3	2.1	1.65	2.4	2.1	1.7	1.6	1.6	1.9	1.9
16	2.2	2.3	2.2	2.1	1.75	2.5	2.0	1.7	1.6	1.7	1.9	1.9
17	2.2	2.3	2.2	2.1	2.0	2.65	2.0	1.6	1.7	1.7	1.9	1.9
18	2.2	2.3	2.2	2.0	2.2	2.7	2.0	1.6	1.7	1.7	1.9	1.9
19	2.2	2.4	2.2	2.0	2.2	2.7	2.0	1.6	1.7	1.7	1.9	1.9
20	2.2	2.4	2.2	2.0	2.2	2.75	1.95	1.6	1.7	1.7	2.0	1.9
21	2.2	2.4	2.2	1.9	2.1	2.75	1.9	1.6	1.7	1.7	2.0	1.9
22	2.2	2.4	2.2	1.9	2.1	2.75	1.95	1.75	1.7	1.7	2.0	1.9
23	2.2	2.4	2.2	1.9	2.1	2.85	2.1	1.8	1.7	1.8	2.0	1.9
24	2.2	2.4	2.2	1.8	2.0	2.85	2.1	1.8	1.7	1.8	2.0	1.9
25	2.2	2.4	2.2	1.8	2.0	2.75	2.1	1.8	1.7	1.8	2.0	1.9
26	2.2	2.4	2.2	1.7	2.0	2.55	2.1	1.7	1.7	1.8	2.0	1.9
27	2.2	2.4	2.2	1.7	2.0	2.4	2.1	1.7	1.7	1.9	2.0	1.9
28	2.2	2.4	2.2	1.75	2.2	2.3	2.05	1.7	1.7	1.9	2.0	1.9
29	2.2	.....	2.2	1.6	2.2	2.35	2.0	1.7	1.8	1.9	2.0	1.9
30	2.2	.....	2.2	1.6	2.1	2.4	2.0	1.6	1.8	1.9	2.0	1.9
31	2.2	.....	2.2	.....	2.1	.....	1.9	1.6	.....	1.9	.....	1.9

discharge, in second-feet, of East Fork of Walker River near Yerington, Nev., for 1905.

ay.	May.	June.	July.	Day.	May.	June.	July.	Day.	May.	June.	July.
.....	37	91	146	12.....	15	109	134	22.....	94	280	69
.....	37	91	156	13.....	18	125	134	23.....	110	304	90
.....	37	84	166	14.....	18	150	116	24.....	95	304	90
.....	37	79	162	15.....	25	170	100	25.....	95	275	83
.....	32	72	162	16.....	34	191	80	26.....	87	210	83
.....	27	60	143	17.....	46	237	80	27.....	87	176	83
.....	27	60	143	18.....	69	262	80	28.....	118	156	84
.....	25	66	130	19.....	69	291	80	29.....	115	156	78
.....	25	66	123	20.....	81	306	73	30.....	98	156	78
.....	25	72	123	21.....	82	306	63	31.....	98	.....	65
.....	25	86	115								

ε.—Discharge applied by indirect method for shifting channels. As no measurements were anuary-April and August-December no estimates for these months can be made.

ated monthly discharge of East Fork of Walker River near Yerington, Nev., for 1905.

[Drainage area, 1,103 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
.....	118	15	57.7	3,548	0.052	0.060
.....	306	60	167	9,937	.151	.168
.....	166	63	107	6,579	.097	.112

WALKER RIVER NEAR WABUSKA, NEV.

s station was established July 22, 1902, and equipped December 12, 1902. It is d about 300 feet above the Carson and Colorado Railroad bridge, near the section at Clever station, and about 2½ miles east of Wabuska.

channel is straight for 150 feet above the station and slightly curved for the same ce below. Both banks are high and are not liable to overflow. The bed of the stream ly and shifting. There is but one channel at all stages. The current has a moderate y, and the discharge is small from August to October.

charge measurements are made by means of a cable and car 35 feet below the gage. itial point for soundings is the zero of the tagged wire.

gage is read twice each day by Charles Nelson. The original gage was washed out ber 30, 1903. A new gage, consisting of a 1 by 4 inch board fastened to a vertical inch timber, was installed January 17, 1904. It is on the left bank, 15 feet below int at which the old gage was located and 150 feet south of the section house. The is the same as that of the original gage. The bench mark consists of four nails into the northwest corner of the pump platform 35 feet east of the gage; elevation zero of gage, 6.94 feet.

rmation in regard to this station is contained in the following Water-Supply Papers United States Geological Survey:

ription: 85, p 106; 100, p 167; 133, p 328.
arge: 85, p 107; 100, p 168; 133, p 328.
arge, monthly: 100, p 169; 133, p 330.
heights: 85, p 107; 100, p 168; 133, p 329.
ng table: 100, p 169; 133, p 329–330.

Discharge measurements of Walker River near Wabuska, Nev., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
May 5	J. L. Brambila	74	64	1.46	1.58	94
May 8	do	73	50	1.42	1.39	71
May 19	do	78	136	2.43	2.30	330
May 22	do	72	118	2.55	2.30	304
June 4	do	70	69	1.79	1.60	124
June 18	do	74	186	2.08	2.80	536
July 1	do	70	64	1.78	1.40	114
July 6	do	67	37	1.54	1.10	57
July 27	do	15	.....	.....	.60	a 34

a Estimated.

Daily gage height, in feet, of Walker River, near Wabuska, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.1	1.92	1.98	1.95	1.28	1.72	1.4	0.6	0.45	0.5	0.45	0.75
2	2.05	2.0	2.0	2.0	1.58	1.7	1.4	.55	.45	.5	.45	.75
3	2.05	2.05	2.0	2.0	1.75	1.7	1.33	.55	.45	.5	.45	.7
4	2.0	2.1	2.0	1.98	1.7	1.62	1.28	.55	.45	.5	.45	.75
5	2.0	2.1	2.0	1.94	1.63	1.6	1.2	.55	.45	.5	.45	.8
6	2.0	2.05	2.02	1.92	1.58	1.65	1.2	.55	.45	.5	.45	.95
7	2.0	2.05	2.05	1.82	1.48	1.72	1.13	.55	.45	.5	.45	.95
8	2.0	2.02	2.05	1.8	1.4	1.82	1.1	.5	.45	.5	.45	1.0
9	2.0	2.0	2.05	1.8	1.4	1.92	1.1	.5	.45	.5	.45	1.0
10	2.0	1.95	2.05	1.8	1.35	1.95	1.1	.5	.45	.5	.45	1.0
11	2.0	1.92	2.05	1.8	1.35	1.98	1.08	.5	.45	.45	.45	1.0
12	2.0	1.9	2.05	1.8	1.28	2.13	1.02	.5	.45	.45	.45	1.0
13	2.0	1.87	2.08	1.7	1.25	2.33	1.0	.5	.45	.45	.45	1.0
14	1.95	1.85	2.1	1.6	1.25	2.65	1.0	.5	.45	.45	.45	.95
15	1.95	1.82	2.1	1.52	1.3	2.88	.95	.5	.45	.45	.45	.95
16	1.9	1.78	2.1	1.48	1.3	2.83	.9	.5	.45	.45	.45	.95
17	1.85	1.75	2.1	1.42	1.3	2.78	.85	.5	.45	.45	.45	.95
18	1.85	1.72	2.15	1.4	1.58	2.78	.85	.5	.45	.45	.45	.95
19	1.8	1.8	2.15	1.38	2.38	2.78	.8	.5	.45	.45	.45	.95
20	1.8	1.85	2.15	1.35	2.4	2.7	.8	.45	.45	.45	.45	.95
21	1.85	1.85	2.15	1.35	2.3	2.63	.8	.45	.45	.45	.5	.95
22	1.9	1.88	2.15	1.32	2.3	2.6	.8	.45	.45	.45	.55	.95
23	1.9	1.9	2.15	1.3	2.15	2.6	.75	.48	.45	.45	.7	.95
24	1.9	1.9	2.1	1.28	1.9	2.55	.68	.5	.45	.45	.65	.95
25	1.9	1.9	2.1	1.22	1.85	2.43	.68	.5	.45	.45	.65	.95
26	1.9	1.9	2.08	1.2	1.9	2.15	.6	.5	.45	.45	.7	.95
27	1.9	1.9	2.02	1.2	2.05	1.7	.6	.5	.45	.45	.7	1.0
28	1.9	1.95	2.0	1.2	2.05	1.45	.6	.5	.45	.45	.7	1.0
29	1.9	.....	2.0	1.15	2.0	1.38	.6	.45	.45	.45	.7	1.0
30	1.9	.....	2.0	1.15	1.9	1.33	.6	.45	.5	.45	.75	1.0
31	1.9	.....	2.0	.....	1.82	.....	.6	.45	.....	.45	.....	1.0

NOTE.—Ice conditions not known.

ıtion rating table for Walker River near Wabuska, Nev., from May 1 to June 15, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.20	40	1.70	135	2.20	280	2.60	440
1.30	56	1.80	159	2.30	316	2.70	488
1.40	73	1.90	185	2.40	354	2.80	538
1.50	92	2.00	214	2.50	395	2.90	588
1.60	113	2.10	246				

The above table is based on six discharge measurements made during 1905. Estimates only approxi-ıte owing to shifting character of stream bed.

Station rating table for Walker River near Wabuska, Nev., from June 16 to July 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.60	30	1.20	84	1.80	186	2.40	366
0.70	36	1.30	97	1.90	210	2.50	405
0.80	44	1.40	111	2.00	236	2.60	447
0.90	53	1.50	127	2.10	264	2.70	491
1.00	62	1.60	144	2.20	295	2.80	538
1.10	72	1.70	164	2.30	329		

The above table is based on four discharge measurements made during 1905. Estimates only proximate owing to shifting character of stream bed.

Estimated monthly discharge of Walker River near Wabuska, Nev., for 1905.

[Drainage area, 2,420 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
ıy	354	48	149	9,162	0.062	0.071
ne	578	101	295	17,550	.122	.136
ly	111	30	58.3	3,585	.024	.028

CARSON RIVER BASIN.

DESCRIPTION OF BASIN.

Carson River has its sources on the eastern slopes of the Sierra Nevada in Alpine County, ıl. Flowing northward into Nevada, East and West forks unite near Genoa, in the ıper Carson Valley. At Empire, 3 miles east of the city of Carson, the river turns to the ırtheast and enters a deep canyon, through which it flows for several miles, emerging to a second, smaller valley a short distance above the town of Dayton. After leaving ia valley it passes through two shorter canyons and one rather large valley before entering ver Carson Valley, or Carson Sink Valley, as it is also known, and discharging its waters ;o Carson Sink.

WEST FORK OF CARSON RIVER NEAR WOODFORDS, CAL.

West Fork of Carson River rises in Alpine County, Cal., flows in a general north direction, and unites with East Fork in Douglas County, Nev.

The gaging station was established October 18, 1900. It is located about three-fou of a mile above the post-office at Woodfords, Cal., and 200 feet from the main road bet Woodfords and Blue Lakes.

The channel is straight for 100 feet above and below the cable. Both banks are and rocky and are not liable to overflow. The bed of the stream is rocky and unever is permanent. There is but one channel at all stages. At high water the velocity o current is too great for accurate measurement.

Discharge measurements are made by means of a cable and car just below the The initial point for soundings is the zero of the tagged wire.

The gage, which is read once each day by Miss Bernice Merrill, is a vertical board r to a cottonwood tree on the left bank.

Information in regard to this station is contained in the following publications United States Geological Survey (Ann=Annual Reports; WS=Water-Supply Paper

Description: WS 51, p 400; 66, p 109; 85, pp 113-114; 100, p.180; 133, p 331.
Discharge: WS 66, p 109; 85, p 114; 100, p 181; 133, p 331.
Discharge, monthly: Ann 11, ii, p 102; 12, ii, pp 351, 360; 13, iii, p 96, 14, ii, p 118; WS 75, p 1 p 115; 100, p 182; 133, p 333.
Discharge, yearly: Ann 13, iii, p 99; 20, iv, p 59.
Gage heights: WS 51, p 401; 66, p 110; 85, p 114; 100, p 181; 133, p 332.
Rating tables: WS 66, p 175; 85, p 115; 100, p 182; 133, p 332.

Discharge measurements of West Fork of Carson River near Woodfords, Cal., in 1905

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	D ch
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Se f*
April 1	W. A. Wolf	28	53	1.66	2.85	
April 20	do	31	72	2.59	3.55	
May 2	J. L. Brambila	30	89	3.09	3.95	
May 12	do	29	80	2.61	3.50	
May 16	do	35	113	3.50	4.40	
May 25	do	30	95	3.19	4.15	
May 30	do	30	95	3.11	4.00	
June 7	do	30	80	2.77	3.75	
June 12	do	30	95	3.04	4.10	
June 22	do	30	76	2.48	3.60	
June 28	do	30	57	2.09	3.20	
July 10	do	30	52	2.00	2.90	
July 22	do	29	46	1.57	2.50	
July 30	do	28	34	1.30	2.35	
August 29	W. A. Wolf	28	26	.96	2.10	

Daily gage height, in feet, of West Fork of Carson River near Woodfords, Cal., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	.....	2.97	3.05	2.93	4.16	3.85	3.1	2.3	2.0	2.2	2.2	2.3
.....	.....	3.01	3.18	2.93	4.2	3.8	3.05	2.35	2.0	2.15	2.2	2.3
.....	.....	3.01	3.05	2.97	3.9	3.75	3.05	2.2	2.0	2.1	2.2	2.3
.....	.....	2.97	3 05	2 89	3.85	3.55	2.97	2.3	2.0	2.1	2.2	2.3
.....	.....	2.93	3.05	2.89	3.7	3.5	2.8	2.25	2.05	2.1	2.2	2.4
.....	.....	3.01	2.97	2.97	3.7	3.55	2.89	2.25	2.0	2.15	2.2	2.4
.....	.....	3.05	3.01	3.05	3.65	3.7	2.89	2.25	2.0	2.15	2.2	2.5
.....	2.77	3.05	3.05	3.14	3.6	3.65	2.75	2.15	2.0	2.2	2.2	2.4
.....	2.81	3.05	3.23	3.23	3.6	3.6	2.89	2.15	2.0	2.2	2.2	2.5
.....	2.81	3.14	3.23	3.41	3.65	3.7	3.14	2.25	2.0	2.2	2.2	2.5
.....	2.85	3.05	3.14	3.41	3.6	3.75	3.05	2.2	2.0	2.2	2.2	2.5
.....	2.89	3.05	3.05	3.36	3.65	3.8	3.05	2.2	2.0	2..	2.2	2.5
.....	2.85	2.97	3.05	3.36	3.8	3.75	2.85	2.15	2.0	2.2	2.2	2.6
.....	2.85	3.01	3.14	3.36	3.9	3.75	2.75	2.1	2.0	2.2	2.2	2.55
.....	2.89	2.89	3.23	3.81	4.12	3.75	2.65	2.1	2.0	2.15	2.2	2.6
.....	2.81	2.89	3.18	3.85	4.08	3.6	2.65	2.1	2.0	2.15	2.2	2.55
.....	2.81	2.85	3.5	3.75	4.24	3.65	2.55	2.0	2.0	2.1	2.2	2.6
.....	2.85	2.83	3.41	3.7	4.4	3.65	2.6	2.1	2.05	2.15	2.2	2.6
.....	2.85	2.81	3.28	3.6	4.36	3.6	2.55	2.1	2.05	2.15	2.2	2.6
.....	2.85	2.81	3.23	3.5	4.36	3.5	2.5	2.1	2.1	2.15	2.2	2.55
.....	2.81	2.85	3.14	3.85	4.36	3.5	2.5	2.1	2.1	2.2	2.2	2.55
.....	2.89	2.89	3.14	3.85	4.36	3.41	2.45	2.15	2.1	2.2	2.2	2.55
.....	2.93	2.89	3.23	3.95	4.12	3.36	2.45	2.1	2.1	2.2	2.2	2.65
.....	3.05	2.85	3.14	4.12	4.16	3.32	2.5	2.1	2.1	2.2	2.2	2.65
.....	2.97	2.89	3.14	4.16	4.16	3.32	2.45	2.1	2.1	2.2	2.2	2.55
.....	2.93	2.97	3.23	4.16	4.16	3.28	2.4	2.05	2.2	2.2	2.2	2.55
.....	2.85	2.97	3.28	4.24	4.0	3.23	2.45	2.0	2.2	2.2	2.2	2.55
.....	2.81	3.05	3.14	4.32	3.9	3.23	2.4	2.0	2.2	2.2	2.4	2.5
.....	2.81	.....	3.05	4.32	3.8	3.14	2.5	2.0	2.2	2.2	2.45	2.5
.....	2.85	.....	2.89	4.28	3.85	3.18	2.35	2.0	2.2	2.2	2.3	2.5
.....	2.89	.....	2.89	.....	3.9	.....	2.3	2.0	.....	2.2	.....	2.5

on rating table for West Fork of Carson River near Woodfords, Cal., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.00	20	2.70	74	3.30	146	3.90	251
2.10	26	2.80	84	3.40	161	4.00	272
2.20	33	2.90	95	3.50	177	4.10	294
2.30	40	3.00	107	3.60	194	4.20	318
2.40	48	3.10	119	3.70	212	4.30	343
2.50	56	3.20	132	3.80	231	4.40	370
2.60	65						

TE.—The above table is applicable only for open channel conditions. It is based on 15 discharge urements made during 1905. It is fairly well defined.

Estimated monthly discharge of West Fork of Carson River near Woodfords, Cal., for 1905.

[Drainage area, 70 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January 8–31	113	81	91.0	4,332	1.30	1.16
February	124	85	102	5,665	1.46	1.52
March	177	94	125	7,686	1.79	2.06
April	348	94	202	12,020	2.89	3.22
May	370	194	271	16,660	3.87	4.46
June	241	124	187	11,130	2.67	2.98
July	124	40	75.8	4,661	1.08	1.24
August	44	20	28.7	1,765	.410	.473
September	33	20	23.7	1,410	.339	.378
October	33	26	31.3	1,925	.447	.515
November	52	33	34.4	2,047	.491	.548
December	70	40	56.5	3,474	.807	.930
The period				72,780		

NOTE.—Ice conditions not known; open-channel rating table applied to winter months without correction.

EAST FORK OF CARSON RIVER NEAR GARDNERVILLE, NEV.

East Fork of Carson River rises in southeastern Alpine County, flows in a general northerly direction, and joins West Fork in Douglas County, Nev.

The gaging station was established October 17, 1900. It is located about 5 miles southeast of Gardnerville, and one-half mile southwest of Rodenbah's ranch. It is within one-half mile of the main traveled road between Carson, Nev., and Bridgeport, Cal., and is about 400 feet above a bridge across the river.

The station is located at the place where measurements were made in 1890, 1891, and 1892.

The channel is straight for 300 feet above and below the station and is broad and shallow. Both banks are high and are not liable to overflow. The bed of the stream is composed of gravel and is permanent. There is but one channel at all stages and the current is moderate.

August 2, 1901, a loose-rock dam was raised a short distance below the gaging station, which affected the velocity at the latter point. This dam was washed out by a freshet December 4, 1901. On or about July 15, 1905, the dam was raised and tightened to such an extent that the water backed up to a point well above the old gage, and for this reason the readings from July 15 to October 8, 1905, are not indicative of the quantity of water flowing in the stream.

Discharge measurements are made by means of a cable and car located at the vertical gage about 400 feet above the bridge. The initial point for soundings is the zero of the tagged wire on the right bank.

The gage is read twice each day by Miss Susie Rodenbah. The original gage was an inclined timber securely fastened to posts set in the right bank of the stream. The bench mark was on a basalt rock in the edge of the stream, 20 feet from the gage and at an elevation of 6.30 feet above gage datum. A new gage was established March 10, 1901, a short distance downstream from the original gage, which had been destroyed. It consists of a vertical timber driven into the stream bed at the right bank and spiked to a cottonwood tree. October 3, 1902, a new inclined gage was installed at a point on the left bank of the

feet above the cable. During 1904 and up to and including October 8, 1905, its were read on the vertical gage at the cable. On the latter date a new vertical installed at a point about 300 yards above the old gage and firmly fastened to

The new gage was read from October 8 to the end of the year. The bench the gage at the cable is the top of a granite bowlder 20 feet south of the gage; above zero of gage, 8.10 feet. The bench mark for the new gage is a cross cut ler 8 feet northeast of the gage; elevation, 6.36 feet above zero of gage.

ıtion in regard to this station is contained in the following publications of the ates Geological Survey (Ann=Annual Report; WS=Water-Supply Paper):

on: Ann 14, ii, p 116; WS 51, pp 399–400; 66, p 108; 85, pp 111-112; 100, pp. 177–178; 133, p 333-

e: WS 66, p 108; 85, p 112; 100, p 178; 133, p 334.
e, monthly: Ann 11, ii, p 102; 12, ii, pp 351, 360; 13, iii, p 95; 14, ii, pp. 116–117; WS 75, p. 13; 100, p 180; 133, p 336.
e, yearly: Ann 13, iii, p 99; 20, iv, p 59.
ghts: WS 51, p 400; 66, p 109; 85, p 112; 100, pp 178–179; 133, p 335.
aph: Ann 14, ii, p 116.
ables: WS 66, p 175; 85, p 113; 100, p 179; 133, p 336.

ge measurements of East Fork of Carson River near Gardnerville, Nev., in 1905.

	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
....	W. A. Wolf	88	179	1.15	3.80	206
....	....do	89	201	1.93	4.15	389
....	J. L. Brambila	93	256	3.00	4.65	767
....	....do	88	206	2.15	4.15	444
....	....do	94	277	3.48	5.00	968
....	....do	88	291	4.10	5.22	1,205
....	....do	88	258	3.40	4.85	877
....	....do	89	264	3.48	4.90	929
....	....do	90	297	4.00	5.22	1,186
....	....do	89	270	3.25	4.85	879
....	....do	85	207	2.33	4.25	482
....	....do	87	187	1.62	4.00	304
....	....do	86	168	.96	3.90	161
....	....do	86	171	.61	3.90	105
....	W. A. Wolf	87	147	.70	3.65	90
....	....do	87	176	.62	3.93	111
....	....do	72	115	.51	3.20	60
2...	John Smith	80	127	.56	2.10	71
4...	....do	80	120	.57	2.10	68

Daily gage height, in feet, of East Fork of Carson River near Gardnerville, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	2.3	3.58	5.19	3.85	4.5	4.71	4.37	3.79	3.4	3.33	3.3	3.1
2	2.32	3.58	5.19	4.3	5.1	4.68	4.25	3.8	3.39	3.33	3.25	3.1
3	2.34	3.58	5.2	4.25	5.5	4.3	4.2	3.8	3.39	3.32	3.2	3.
4	2.25	3.6	5.2	4.1	5.2	4.35	4.2	3.82	3.38	3.33	3.2	3.0
5	2.24	3.58	4.88	4.15	4.95	4.45	4.19	3.78	3.37	3.4	3.3	3.0
6	2.24	3.54	4.8	4.2	4.6	4.56	4.15	3.78	3.37	3.4	3.25	3.0
7	2.24	3.54	4.78	4.12	4.15	4.66	4.12	3.72	3.37	3.4	3.2	3.0
8	2.65	3.55	4.68	4.12	4.0	4.69	4.12	3.66	3.36	3.3	3.2	3.0
9	2.8	3.56	4.62	4.1	3.9	4.75	4.11	3.66	3.36	3.3	3.2	3.0
10	2.88	3.58	4.6	3.9	3.8	4.75	4.1	3.95	3.33	3.3	3.2	3.0
11	2.98	3.58	4.6	3.85	4.08	4.8	4.05	4.23	3.32	3.32	3.2	3.0
12	3.2	4.0	4.45	3.85	3.95	4.9	4.0	.....	3.22	3.3	3.2	3.0
13	3.38	4.0	4.5	3.9	4.11	4.95	3.88	4.18	3.21	3.3	3.15	3.0
14	3.6	4.12	4.28	3.9	4.65	4.88	3.83	3.65	3.2	3.3	3.15	3.0
15	3.65	4.12	4.21	3.92	5.4	4.88	3.78	3.78	3.19	3.3	3.15	3.07
16	3.6	4.13	4.19	3.91	6.0	4.85	3.74	3.78	3.19	3.32	3.15	3.0
17	3.6	4.14	4.18	3.9	5.75	4.85	3.9	3.78	3.19	3.3	3.15	3.1
18	3.62	4.14	4.14	3.89	5.65	4.9	3.85	3.78	3.19	3.3	3.15	3.1
19	3.6	4.14	4.05	3.89	5.4	4.93	3.74	3.68	3.19	3.3	3.1	3.1
20	3.62	4.59	4.0	3.9	5.49	4.92	3.7	3.64	3.19	3.3	3.1	3.12
21	3.63	5.0	3.9	3.92	5.42	4.83	3.71	3.62	3.18	3.3	3.1	3.12
22	3.64	5.1	3.95	3.95	5.25	4.8	3.7	3.59	3.18	3.3	3.1	3.12
23	3.66	5.14	3.95	3.98	5.15	4.68	3.72	3.59	3.17	3.2	3.1	3.13
24	3.65	5.16	3.92	4.0	5.18	4.6	3.72	3.52	3.16	3.2	3.1	3.13
25	3.64	5.19	3.95	4.18	5.13	4.53	3.76	3.5	3.15	3.2	3.1	3.13
26	3.6	5.12	3.95	4.2	4.97	4.53	3.79	3.5	3.16	3.2	3.1	3.14
27	3.6	5.12	3.85	4.21	4.85	4.49	3.84	3.5	3.2	3.2	3.1	3.15
28	3.6	5.12	3.8	4.22	4.83	4.41	3.85	3.47	3.3	3.3	3.1	3.15
29	3.6	.....	3.8	4.28	4.85	4.39	3.85	3.41	3.4	3.3	3.1	3.16
30	3.6	.....	3.8	4.3	4.85	4.38	3.86	3.4	3.33	3.3	3.1	3.16
31	3.6	.....	3.85	.....	4.83	.....	3.86	3.4	.....	3.3	.....	3.15

NOTE.—October 8 to December 31, readings made on new gage and reduced to same datum as gage used during the first part of the year.

Station rating table for East Fork of Carson River near Gardnerville, Nev., from January 1 to July 15, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
2.00	8	2.80	43	3.60	158	4.40	527
2.10	9	2.90	51	3.70	186	4.50	600
2.20	11	3.00	60	3.80	218	4.60	675
2.30	14	3.10	71	3.90	254	4.70	753
2.40	18	3.20	83	4.00	295	4.80	833
2.50	23	3.30	97	4.10	342	4.90	915
2.60	29	3.40	114	4.20	397	5.00	1,000
2.70	36	3.50	134	4.30	459		

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during first half of 1904 and 1905, and several low-water measurements of 1903. It is well defined between gage heights 3 feet and 5 feet. Above 5 feet the curve depends on one measurement at gage height 6.15 feet.

Estimated monthly discharge of East Fork of Carson River near Gardnerville, Nev., for 1905.

[Drainage area, 381 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	175	12	110	6,763	0.289	0.333
February	1,166	144	496	27,550	1.30	1.35
March	1,175	218	533	32,770	1.40	1.61
April	450	236	322	19,160	.845	.943
May	1,930	218	949	58,350	2.49	2.87
June	958	459	742	44,150	1.95	2.18
July 1-15	507	212	346	10,290	.908	.506
The period				199,000		

NOTE.—Ice conditions not known. Open-channel rating table applied to winter months without correction.

CARSON RIVER NEAR EMPIRE, NEV.

This station was established October 21, 1900. It is located about three-fourths of a mile east of Brunswick Mill and 2½ miles east of Empire, Nev.

The channel is straight for 100 feet above and below the station. Both banks are high, rocky, and will not overflow. The bed of the stream is composed of solid rock, gravel, and cobblestones, and is not likely to shift. At flood stages the stream is too deep and swift for satisfactory measurement; at low water the current is sluggish.

Discharge measurements are made by means of a cable and car just below the gage. The initial point for soundings is the zero of the tagged wire on the left bank. Low-water measurements are made by wading one-fourth mile below the cable.

The gage is read once each day by David Lloyd. The original gage was located upstream from the site of the present station. February 18, 1901, the erosion of a bar in the channel above the gage caused the division of the stream into two channels, and on this account the present gage was installed March 13, 1901. The gage consists of an inclined 4 by 4 inch timber spiked to a cottonwood tree on the left bank. November 11, 1903, the gage datum was lowered 1.3 feet to enable readings to be made at extreme low water. The gage is referred to bench marks as follows: (1) Top of a bowlder on the left bank 2 feet west of the gage. Its elevation is 7.10 feet above the zero of the gage as originally established and 8.40 feet above the gage in its present position. (2) Top of bowlder on the left bank 10 feet north of the gage. Elevation is 8.38 feet above the zero of the gage as originally established and 9.68 feet above the zero of the gage in its present position.

Information in regard to this station is contained in the following publications of the United States Geological Survey (Ann=Annual Report; Bull.=Bulletin; WS=Water-Supply Paper):

Description: Ann 12, ii, p 325; Bull 140, p 212; WS 51, p 401; 66, p 110; 85, p 109; 100, p 175; 133, p 337.
Discharge: Bull 140, p 213; WS 66, p 111; 85, p 109; 100, p 175; 133, p 337.
Discharge, monthly. WS 75, p 189; 85, p 111; 100, p 177; 133, p 339.
Gage heights: Bull 140, p 213. WS 51, p 401; 66, p 111; 85, p 110; 100, p 176; 133, p 338.
Hydrographs: Ann 12, ii, p 324; WS 75, p 189.
Rating tables: WS 66, p 175; 85, p 110; 100, p 176; 133, p 338.

Discharge measurements of Carson River near Empire, Nev., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
April 3	W. A. Wolf	79	187	1.92	3.25	358
May 7	J. L. Brambilla	85	266	2.75	4.05	731
May 13	do	85	233	2.08	3.50	486
May 20	do	86	327	3.88	4.80	1,270
May 27	do	85	321	3.54	4.60	1,136
June 3	do	85	275	3.01	4.15	830
June 9	do	83	256	2.51	3.90	642
June 17	do	86	288	3.11	4.30	901
June 24	do	80	231	2.33	3.70	539
July 2	do	80	182	1.85	3.18	338
July 11	do	67	124	.90	2.22	111
July 21	do	57	95	.55	1.95	53

Daily gage height, in feet, of Carson River near Empire, Nev., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	3.35	2.9	3.1	3.3	4.9	4.4	3.1	1.4	1.1	1.4	2.1	2.3
2	3.3	3.2	3.1	3.3	4.5	4.4	3.2	1.4	.8	1.5	2.1	2.2
3	2.9	3.2	3.1	3.4	4.4	4.3	3.0	1.3	1.1	1.6	2.0	2.3
4	2.9	3.2	3.1	3.4	4.4	4.1	2.9	1.2	.7	1.6	2.0	2.3
5	3.0	3.2	3.2	3.4	4.3	4.0	2.7	1.3	.7	1.6	2.0	2.4
6	3.0	3.2	3.2	3.5	4.2	3.9	2.5	1.2	1.2	1.7	2.0	2.4
7	3.0	3.2	3.2	3.6	4.1	3.9	2.4	1.2	.8	1.8	2.0	2.4
8	2.9	3.2	3.2	3.6	4.0	3.9	2.5	1.2	.9	1.7	2.0	2.4
9	2.9	3.0	3.2	3.7	3.9	4.0	2.4	1.2	1.3	1.7	2.0	2.4
10	2.9	3.0	3.2	3.7	3.8	4.0	2.2	1.3	1.3	1.7	2.0	2.4
11	2.9	3.0	3.2	3.9	3.8	4.1	2.2	1.2	1.2	1.8	2.1	2.4
12	2.8	2.9	3.2	3.8	3.5	4.3	2.2	1.0	.8	1.8	2.1	2.4
13	2.8	3.1	3.2	3.6	3.5	4.5	2.1	1.0	1.2	1.8	2.1	2.4
14	2.8	3.1	3.3	3.5	3.5	4.6	2.1	1.1	.7	1.8	2.1	2.4
15	3.0	2.9	3.4	3.4	3.7	4.4	2.0	1.2	1.3	1.8	2.1	2.3
16	3.0	2.9	3.4	3.6	3.9	4.4	2.0	1.3	.9	1.9	2.1	2.4
17	3.0	3.0	3.3	3.6	4.5	4.3	2.0	1.2	1.3	1.9	2.1	2.5
18	2.9	3.0	3.3	3.5	4.9	4.3	1.9	1.3	1.3	1.9	2.1	2.4
19	2.9	3.0	3.3	3.5	5.0	4.2	1.9	1.3	.9	1.9	2.1	2.3
20	2.9	3.0	3.3	3.5	4.8	4.1	1.9	1.3	1.3	2.0	2.1	2.4
21	2.9	3.0	3.3	3.3	4.8	4.0	1.8	1.3	.8	2.0	2.1	2.5
22	2.9	3.1	3.3	3.3	4.9	3.9	1.8	1.3	1.3	2.0	2.1	2.5
23	3.0	3.0	3.2	3.3	4.8	3.9	1.7	1.4	1.4	2.0	2.1	2.5
24	3.1	3.0	3.2	3.4	4.4	3.7	1.5	1.5	1.1	2.0	2.2	2.5
25	3.0	3.0	3.1	3.6	4.5	3.6	1.5	1.5	1.4	2.0	2.2	2.4
26	2.9	3.0	3.2	4.1	4.6	3.5	1.5	1.0	1.2	2.0	2.2	2.4
27	2.9	3.1	3.4	4.2	4.6	3.5	1.5	1.2	1.3	2.0	2.2	2.7
28	2.9	3.1	3.4	4.5	4.5	3.4	1.5	1.0	1.3	2.0	2.3	2.7
29	2.9	.....	3.4	4.7	4.4	3.2	1.5	.8	1.4	2.0	2.3	2.6
30	2.9	.....	3.4	4.8	4.3	3.2	1.5	1.0	1.4	2.0	2.2	2.5
31	2.9	.....	3.3	.....	4.3	.....	1.4	.7	.....	2.0	.....	2.5

Station rating table for Carson River near Empire, Nev., from January 1, 1904, to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.00	3	2.10	77	3.10	313	4.10	765
1.10	4	2.20	93	3.20	347	4.20	825
1.20	6	2.30	110	3.30	384	4.30	889
1.30	8	2.40	129	3.40	423	4.40	956
1.40	12	2.50	150	3.50	464	4.50	1,026
1.50	16	2.60	173	3.60	508	4.60	1,100
1.60	23	2.70	197	3.70	554	4.70	1,180
1.70	31	2.80	223	3.80	603	4.80	1,260
1.80	40	2.90	251	3.90	654	4.90	1,345
1.90	51	3.00	281	4.00	708	5.00	1,430
2.00	63						

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1902–1905. It is well defined between gage heights 1.7 feet and 5.4 feet.

Estimated monthly discharge of Carson River near Empire, Nev., for 1905.

[Drainage area, 988 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth in inches.
January	404	223	267	16,420	0.270	0.311
February	384	251	300	16,660	.304	.317
March	423	313	366	22,500	.370	.427
April	1,260	384	561	33,380	.568	.634
May	1,430	464	929	57,120	.940	1.08
June	1,100	347	728	43,320	.737	.822
July	347	12	95.4	5,866	.097	.112
August	16	0	6.9	424	.0070	.0081
September	12	0	5.5	327	.0056	.0062
October	63	12	45.8	2,816	.046	.053
November	110	63	78.1	4,647	.079	.088
December	197	93	135	8,301	.137	.158
The year	1,430	0	293	211,800	.280	4.02

NOTE.—Ice conditions not known; open-channel rating table applied to winter months without correction.

SUSAN RIVER BASIN.

DESCRIPTION OF BASIN.

Susan River rises on the eastern slope of the Sierra Nevada in northeastern California, the rim of the basin having an elevation of 7,000 feet, flows eastward, and discharges into Honey Lake—one of the land-locked lakes of the Great Basin—at an elevation of about 4,000 feet.

The drainage basin is long and narrow, and though numerous small creeks enter the river from both the north and south there are no tributaries of any size. Willow Creek, which joins the stream about 12 miles below Susanville, is the most important.

In the upper reaches of the basin, at an elevation of about 6,000 feet, are numerous small lakes and this region has also good forest cover. Below Susanville, in the area surrounding Honey Lake, the soil deposit has considerable depth and is susceptible of high cultivation; elsewhere the basin is composed of lava rock with a thin covering of soil.

The summer flow of the stream is regulated by several small storage reservoirs, but these have inconsiderable capacity. There are, however, a number of good storage sites in the basin. The precipitation is mostly in the form of snow.

SUSAN RIVER NEAR SUSANVILLE, CAL.

This station was established June 3, 1900. It is located about three-fourths of a mile southwest of Susanville, at the electric-light plant.

The channel is straight for 150 feet above and 250 feet below the cable. The right bank is high and not liable to overflow and is composed of clay covered with vegetation. The left bank is low, is liable to overflow, and is covered with a sparse growth of willows. The bed of the stream is of gravel and cobblestone and is permanent. A short distance above the station a small irrigating ditch, known as the Masten ditch, is taken out on the right bank. There is a flume near its head in which a gage has been placed.

Discharge measurements are made by means of a cable and car. The initial point for soundings is a post in the fence in line with the cable. The cable support on the left bank is 34.8 feet from the initial point for soundings.

The gage is read once each day by James Branham. When the station was first established a temporary gage was installed on the right bank. December 20, 1903, the station at the electric-light plant was reestablished and a new gage was set which was made to read 2 feet more than the original gage. The gage is referred to bench marks as follows: (1) A nail in the fence post which is used as the initial point for soundings; elevation, 11.35 feet. (2) A nail in the cable post; elevation, 9.00 feet. (3) A nail in the cottonwood tree to which the cable is attached; elevation, 10.00 feet. Elevations are above zero of the gage.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey.

Description: 51, p 408; 66, pp 115–116; 85, p 123; 100, pp 204–205; 133, p 339–346.
Discharge: 51, p 408; 66, p 116; 100, p 205; 133, p 340.
Discharge, monthly: 75, p 190; 133, p 341–342.
Gage heights: 51, p 408; 66, p 116; 85, p 124; 100, p 205; 133, p 340.
Rating table: 566, p 175; 133, p 341.

Discharge measurements of Susan River near Susanville, Cal., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
March 21	J. Branham	44	92	4.79	6.60	441
May 12	do	29	48	3.27	5.40	157
June 12	do	25	31	2.32	4.70	72
June 25	do	24	18	1.66	4.20	30
July 23	do	18	10.8	1.19	3.85	12.8
August 29	do	14	8.1	0.85	3.75	6.9
September 26	do	19	13.6	1.13	4.00	15.4

Daily gage height, in feet, of Susan River near Susanville, Cal., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	4.95	5.2	5.25	6.15	5.95	5.15	4.1	4.1	3.8	3.8	4.0	4.0
2	4.8	5.2	5.25	5.95	5.9	5.1	4.1	4.1	3.8	3.8	4.0	4.0
3	4.75	5.2	5.25	5.95	5.8	5.05	4.45	4.1	3.8	3.9	4.0	4.0
4	4.7	5.2	5.25	5.9	5.8	5.05	4.8	4.1	3.8	3.95	4.0	4.0
5	4.65	5.15	5.25	5.9	5.65	5.0	4.6	4.1	3.85	3.95	4.0	4.0
6	4.6	5.05	5.25	6.0	5.55	5.0	4.4	4.1	3.85	3.95	4.0	4.0
7	4.6	4.85	5.25	6.1	5.5	5.0	4.25	4.1	3.85	4.0	4.0	4.0
8	4.55	4.85	5.25	6.1	5.5	4.9	4.1	4.0	3.85	3.95	4.0	4.0
9	4.55	4.75	5.2	6.1	5.5	4.85	4.1	3.9	3.85	3.9	4.0	4.0
10	4.55	4.8	5.2	6.2	5.45	4.75	4.0	3.8	3.85	3.9	4.0	4.0
11	4.55	4.7	5.2	6.1	5.4	4.7	4.0	3.8	3.9	3.9	4.0	4.0
12	4.6	4.65	5.4	6.1	5.4	4.7	4.0	3.8	3.9	3.9	4.0	4.0
13	4.65	4.55	5.9	6.1	5.35	4.65	3.95	3.8	3.9	3.9	4.0	4.0
14	4.7	4.5	5.9	6.1	5.3	4.65	4.2	3.8	3.85	3.9	4.0	4.0
15	4.7	4.45	6.05	6.1	5.3	4.6	4.2	3.75	3.85	3.9	4.0	4.0
16	4.7	4.45	6.1	6.1	5.4	4.5	4.2	3.75	3.8	3.9	4.0	4.0
17	4.7	4.5	6.05	6.05	5.4	4.5	4.0	3.75	3.8	4.0	4.0	4.0
18	4.65	4.55	6.0	6.05	5.4	4.4	4.0	3.75	3.8	4.05	4.0	4.0
19	4.65	5.05	6.6	6.05	5.4	4.4	4.1	3.75	3.9	4.0	4.0	4.0
20	4.65	5.35	6.25	5.95	5.4	4.4	4.05	3.75	3.9	4.0	4.0	4.0
21	4.65	5.35	6.45	5.8	5.4	4.3	3.9	3.8	3.95	4.0	4.0	4.0
22	4.8	5.25	6.15	5.8	5.4	4.3	3.9	3.8	3.95	4.0	4.0	4.0
23	5.5	5.1	6.1	5.8	5.35	4.25	3.85	3.8	3.95	4.0	4.05	4.0
24	5.4	5.1	6.05	5.85	5.35	4.2	3.85	3.75	3.95	4.0	4.05	4.0
25	5.2	5.2	5.85	5.9	5.3	4.2	3.85	3.75	3.95	4.0	4.1	4.0
26	4.95	5.2	6.9	6.0	5.3	4.2	3.85	3.75	4.0	4.0	4.1	4.0
27	4.9	5.25	6.3	6.0	5.3	4.2	3.8	3.75	3.9	4.0	4.1	4.0
28	4.9	5.25	6.1	6.0	5.25	4.2	3.8	3.75	4.0	4.0	4.05	4.0
29	4.85	.....	6.0	6.0	5.25	4.15	3.75	3.8	3.95	4.0	4.05	4.0
30	4.8	.....	6.1	6.0	5.2	4.15	3.75	3.8	3.9	4.0	4.0	4.0
31	4.8	.....	6.0	.....	5.2	.....	4.1	3.8	.....	4.0	.....	4.0

Station rating table for Susan River near Susanville, Cal., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.75	7	4.60	59	5.40	152	6.20	307
3.80	9	4.70	68	5.50	168	6.30	331
3.90	13	4.80	77	5.60	185	6.40	356
4.00	18	4.90	87	5.70	203	6.50	382
4.10	24	5.00	98	5.80	222	6.60	410
4.20	30	5.10	110	5.90	242	6.70	440
4.30	37	5.20	123	6.00	262	6.80	470
4.40	44	5.30	137	6.10	284	6.90	500
4.50	51						

NOTE.—The above table is applicable only for open-channel conditions. It is based on 11 discharge measurements made during 1904–5, and is well defined.

Estimated monthly discharge of Susan River near Susanville, Cal., for 1905.

[Drainage area, 256 square miles.]

Month.	Discharge in second-feet.			Total in acre-feet.	Run-off.	
	Maximum.	Minimum.	Mean.		Second-feet per square mile.	Depth inch
January	168	55	76.9	4,728	0.300	
February	144	48	96.9	5,382	.379	
March	500	123	234	14,390	.914	
April	307	222	264	15,710	1.03	
May	252	123	160	9,838	.625	
June	116	27	61.3	3,648	.239	
July	77	7	23.4	1,439	.091	
August	24	7	12.1	744	.047	
September	18	9	12.3	732	.048	
October	21	9	15.7	965	.061	
November	24	18	19.0	1,131	.074	
December	18	18	18.0	1,107	.070	
The year	500	7	82.8	59,810	.323	

NOTE.—Ice conditions not known; open-channel rating table applied to winter months wi correction.

WILLOW CREEK AT MERRILLVILLE, CAL.

Willow Creek rises from springs directly under Eagle Lake, presumably seepage Eagle Lake, which has no surface outlet; it flows southward, joining Susan River abou miles below Susanville. Its only tributary of importance is Petes Creek, which drai large area in the eastern portion of the basin. The drainage area of the main stream good timber covering, while that tributary to Petes Creek is barren of timber. The e basin is composed of lava rock with a light covering of soil, and contains large stretch barren table-lands with scattered peaks of volcanic origin. There is a large area of c vated land along Willow Creek above the gaging station at Standish and consider water is diverted for irrigation of lands adjoining the stream.

The gaging station at Merrillville was established June 18, 1904. It is located near head of the creek, at the old bridge, 100 feet above the present wagon bridge, on the from Merrillville to Eagle Lake.

The channel is straight above and below the bridge for a distance of 100 feet. The b are low, but as there is very little fluctuation in the discharge of the creek, they are subject to overflow. The bed of the stream is composed of gravel, and is comparati permanent.

Discharge measurements are made from the bridge. The initial point for soundin on the left bank of the stream. The distance across the creek is marked on the footbr at intervals of 2 feet.

The gage, which is read once each day by R. W. Hurlburt, is a 2 by 4 inch vertica fastened to the left end of the bridge.

A description of this station, gage height, discharge data, and rating table are conta in Water-Supply Paper No. 133, of the United States Geological Survey, pp. 339–341

Daily gage height, in feet, of Willow Creek at Merrillville, Cal., for 1905.

	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
..	1.1	1.1	0.95	1.1	0.9	0.95	0.9	0.95	1.0	1.1	1.3	1.25
..	1.05	1.1	1.0	1.05	.9	.95	.9	.95	1.0	1.1	1.25	1.3
..	1.0	1.1	1.0	1.0	.95	.95	.9	.95	1.0	1.1	1.2	1.3
..	1.0	1.05	1.0	1.0	.95	.95	.9	.95	1.0	1.1	1.2	1.3
..	1.0	1.1	.95	1.0	.95	.95	.9	.95	1.0	1.1	1.2	1.3
..	1.0	1.05	.95	1.0	.95	.95	.9	.95	1.0	1.2	1.2	1.3
..	1.0	1.0	1.0	1.0	.95	.95	.9	.95	1.0	1.3	1.2	1.3
..	1.0	1.0	1.05	1.0	.95	1.0	.9	.95	1.0	1.2	1.2	1.3
..	1.0	1.0	1.0	1.0	.95	1.0	.9	1.0	1.0	1.2	1.2	1.3
..	1.0	1.0	1.0	.95	1.0	.95	.95	1.0	1.0	1.2	1.2	1.3
..	1.0	1.0	1.0	.95	1.05	.95	.95	1.0	1.0	1.2	1.2	1.3
..	1.0	1.0	1.0	.95	1.1	.95	1.05	1.0	1.0	1.2	1.2	1.3
..	1.0	1.0	1.05	1.0	1.05	.95	1.05	1.0	1.0	1.2	1.2	1.3
..	1.05	1.0	.95	1.0	1.0	.95	1.0	1.0	1.0	1.2	1.2	1.3
..	1.05	.95	1.05	1.0	.95	.95	1.0	1.0	1.0	1.2	1.2	1.3
..	1.05	1.0	1.1	1.0	.9	.95	1.0	1.0	1.0	1.2	1.2	1.3
..	1.05	1.0	1.1	1.0	.9	.95	.95	1.0	1.05	1.2	1.2	1.3
..	1.05	1.0	1.05	1.0	.9	.95	.95	1.0	1.05	1.2	1.2	1.3
..	1.05	1.25	1.1	1.0	.9	.95	.95	1.0	1.05	1.2	1.2	1.3
..	1.0	1.15	1.05	1.0	.9	.95	.95	1.0	1.05	1.2	1.2	1.3
..	1.05	1.05	1.05	1.0	.9	.95	.95	1.0	1.05	1.2	1.2	1.3
..	1.1	1.05	1.05	1.0	.95	.95	.95	1.0	1.05	1.25	1.2	1.3
..	1.1	1.05	1.05	.9	.95	.95	.95	1.0	1.05	1.25	1.2	1 3
..	1.1	1.0	1.0	.9	.95	.95	.95	1.0	1.05	1.25	1.2	1.3
..	1.05	1.0	1.0	.95	.95	.95	.95	1.0	1.05	1.25	1.2	1.3
..	1.0	1.05	1.1	.95	1.0	.95	.95	1.0	1.05	1.2	1.2	1.3
..	1.0	1.0	1.1	.95	1.0	.95	.95	1.0	1.1	1.2	1.2	1.3
..	1.0	1.0	1.0	.95	1.0	.95	.95	1.0	1.15	1.2	1.25	1.3
..	1.0	.....	1.1	.9	.95	.95	.95	1.0	1.2	1.2	1.25	1.3
..	1.0	.....	1.05	.9	.95	.9	.95	1.0	1.1	1.2	1.25	1.3
..	1.0	.....	1.05	.....	.95	.....	.95	1.0	.....	1.25	.....	1.3

ng table for Willow Creek at Merrillville, Cal., from July 1, 1904, to December 31, 1905.

e t.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0	16	1.10	20	1.20	22	1.30	24
0	18						

e above table is applicable only for open-channel conditions. It is based on four discharge is made during 1904. It is fairly well defined.

Estimated monthly discharge of Willow Creek at Merrillville, Cal., for 1905.

Month.	Discharge in second-feet.			Total i acre-fe
	Maximum.	Minimum.	Mean.	
January	20	18	18.5	1
February	23	17	18.8	1
March	20	17	18.6	1
April	20	16	17.6	1
May	20	16	17.1	1
June	18	16	17.0	1
July	19	16	16.9	
August	18	17	17.7	
September	22	18	18.7	
October	24	20	21.9	
November	24	22	22.2	
December	24	23	24.0	
The year	24	16	19.1	

NOTE.—Ice conditions not known; open-channel rating table applied to winter months wi correction.

WILLOW CREEK NEAR STANDISH, CAL.

This station was originally established June 4, 1900. It was reestablished Janu 1905, and discontinued December 31, 1905. It is located at the bridge on the road Susanville to Hot Springs and is about 1½ miles above the junction of the creek with S River. It is about 4 miles west of north from Standish.

The channel is straight for 300 feet above and 250 feet below the station. The right is rather low and is subject to overflow at extreme high water; the left bank is high an liable to overflow. The stream bed is sandy and liable to shift somewhat.

Discharge measurements are made from the bridge. The initial point for soundings the end of the bridge on the left bank, the bridge being marked at 5-foot intervals acro stream.

The gage, which is read once each day by T. E. Ravenscroft, a farmer who lives ne station, is a 4 by 4-inch vertical timber and is fastened to the left abutment of the brid

Information in regard to this station is contained in the following Water-Supply Pap the United States Geological Survey:

Description: 51, p 407; 66, p 115.
Discharge: 51, p 407.
Gage heights: 51, p 407; 66, p 115.

Discharge measurements of Willow Creek near Standish, Cal., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	ch
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	S
January 24	J. Branham	57	117	0.80	6.15	
January 29	do	57	87	.79	5.35	
February 26	do	57	105	.79	5.75	
April 23	do	32	21	.95	4.00	
November 19	do	57	56	.61	4.80	

Daily gage height, in feet, of Willow Creek near Standish, Cal., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
.....	6.6	6.8	5.0	5.5	4.0	4.0	3.0	4.0	4.2	5.0	5.0	5.0
2.....	6.6	6.7	4.8	5.3	4.0	4.0	3.0	4.0	4.5	4.8	5.1	5.3
3.....	5.0	5.9	4.0	5.0	4.0	4.0	3.0	4.0	4.4	4.6	5.0	5.2
4.....	5.0	.....	4.0	5.0	4.0	4.0	6.0	4.0	4.4	4.3	5.0	5.0
5.....	4.6	5.8	4.0	4.8	4.0	4.0	5.8	4.0	4.4	4.0	5.0	5.1
6.....	4.6	6.0	4.4	4.5	4.0	4.0	4.8	4.0	4.4	4.0	5.1	5.0
7.....	4.6	6.0	4.4	4.0	4.0	4.0	4.0	4.0	4.4	4.0	5.2	5.2
8.....	4.6	5.8	4.4	4.0	4.0	4.2	4.0	4.0	4.4	4.2	5.0	4.1
9.....	4.6	5.6	4.0	4.0	4.0	4.1	4.0	4.0	4.4	4.2	5.0	4.1
0.....	4.6	5.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.1	5.2	4.4
1.....	4.6	5.0	4.4	4.0	4.2	4.0	4.0	4.2	4.0	4.1	5.1	4.4
2.....	4.7	5.0	4.0	3.8	4.2	4.0	6.0	4.0	4.0	4.0	4.6	4.4
3.....	4.7	5.0	4.0	4.0	4.0	4.0	6.0	4.0	4.0	4.0	4.4	4.3
4.....	4.7	5.0	4.0	4.0	4.0	4.0	5.8	4.0	6.0	4.0	4.4	4.5
5.....	5.8	4.6	4.4	4.0	4.0	4.0	5.0	4.0	5.8	4.0	4.4	4.1
6.....	5.8	4.7	4.4	4.0	4.0	4.0	5.8	4.0	5.0	4.1	4.6	4.1
7.....	6.0	4.7	4.4	4.0	4.0	4.0	5.8	4.0	5.0	4.5	4.8	4.3
8.....	6.0	4.7	4.4	4.0	4.0	4.0	5.8	4.2	5.0	4.5	4.8	4.3
9.....	6.4	5.1	5.0	4.0	4.0	4.0	6.0	4.2	5.0	4.5	5.0	4.3
0.....	6.35	6.0	5.0	4.0	4.0	4.0	6.0	4.6	5.0	4.5	5.0	4.3
.....	6.0	7.8	5.2	4.0	4.1	4.0	6.0	4.5	4.8	4.5	4.8	4.0
.....	7.6	7.8	5.2	4.0	4.1	4.0	5.0	4.6	4.8	4.5	4.6	5.0
.....	7.8	7.0	5.0	4.0	4.0	4.0	5.0	4.2	4.8	5.0	4.6	5.0
.....	6.0	6.2	4.8	4.0	4.0	4.0	4.8	4.0	4.6	5.1	4.5	5.2
.....	6.0	6.0	4.6	4.0	4.0	4.0	4.1	4.0	4.5	5.2	4.4	5.0
.....	5.8	6.3	5.3	4.0	4.0	6.2	4.0	4.2	5.0	5.2	4.8	5.2
.....	5.6	5.0	5.0	4.0	4.0	5.0	4.0	4.2	6.0	5.1	4.8	5.3
.....	5.6	5.0	5.0	4.0	3.8	4.0	4.0	4.2	5.8	5.5	5.0	5.3
.....	5.7	.....	5.0	4.0	3.8	4.0	4.0	4.2	5.8	5.2	5.0	5.3
.....	5.0	.....	5.0	4.0	3.8	3.6	4.0	4.3	5.0	5.0	5.0	5.3
.....	5.6	.....	5.5	.....	.....	.....	4.0	4.2	.....	5.0	.....	5.3

ation rating table for Willow Creek near Standish, Cal., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
3.60	10	4.70	34	5.80	86	6.90	165
3.70	11	4.80	37	5.90	92	7.00	173
3.80	13	4.90	41	6.00	98	7.10	181
3.90	15	5.00	45	6.10	105	7.20	189
4.00	17	5.10	49	6.20	112	7.30	197
4.10	19	5.20	54	6.30	119	7.40	205
4.20	21	5.30	59	6.40	126	7.50	213
4.30	23	5.40	64	6.50	133	7.60	221
4.40	25	5.50	69	6.60	141	7.70	229
4.50	28	5.60	74	6.70	149	7.80	238
4.60	31	5.70	80	6.80	157		

NOTE.—The above table is applicable only for open-channel conditions. It is based on five discharge measurements made during 1905 between gage heights 4 feet and 6.15 feet. It is not well defined.

Estimated monthly discharge of Willow Creek near Standish, Cal., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	238	31	80.4	4,944
February	238	31	89.4	4,965
March	69	17	33.5	2,060
April	69	17	22.9	1,363
May	21	13	17.0	1,045
June	112	10	21.1	1,256
July	98	0	46.2	2,841
August	31	17	19.6	1,205
September	98	17	41.0	2,440
October	69	17	31.8	1,955
November	54	25	39.6	2,356
December	59	17	38.7	2,380
The year	238	0	40.1	28,810

NOTE.—Ice conditions not known; open-channel rating table applied to winter months without correction.

OWENS RIVER DRAINAGE BASIN.

Owens River has its source in the Sierra Nevada, in eastern California, and flows southeastward, parallel with this range, finally discharging its waters into Owens Lake. This basin has a length from north to south of approximately 150 miles and a width of from 20 to 25 miles. It lies between the Sierra Nevada on the west and the White Mountains on the east. Practically the entire flow of this river is derived from the Sierra Nevada, as it drains the eastern slope of this range from Mount Lyell, on the north, to a point some distance below Mount Whitney, on the south. The White Mountains furnish no water for this stream except in times of very heavy rain storms, which seldom occur on this range. Numerous tributaries enter Owens River from the west, which have their sources in the high elevations of the Sierra Nevada, extending from the northern to the southern limits of this basin. The topography of that portion of the Sierra Nevada which is drained by this stream is extremely rough and precipitous, the mountains rising abruptly from Owens Valley to elevations of 13,000 to 14,000 feet. The rock formation is of granite, with very little soil covering, and sparse timber growth. Numerous lakes and marshes lie in the upper reaches of this portion of the drainage basin. Owens River, a short distance below its source, enters a flat, swampy country known as Long Valley, where a considerable quantity of its flow is used for the irrigation of meadow lands for stock raising. This water returns to the river channel at the lower end of Long Valley, where the stream enters a deep, narrow gorge with heavy grade. As the river breaks from this canyon it enters Owens Valley, through which it flows for about 80 miles, finally discharging into Owens Lake. The gaging station at Round Valley is located at the lower end of this canyon. Below this point numerous diversions are made for the irrigation of land in Owens Valley, where the soil is extensively cultivated, and large areas are used for raising hay and grain. This country is particularly adapted to stock raising, which is carried on to a large extent throughout the valley. There are numerous opportunities for the construction of storage reservoirs within this basin, both on the main stream and on the upper reaches of its tributaries, though none have been constructed as yet. The precipitation is extremely light within the area of the basin, except on the high elevations of the Sierra Nevada, where there is a heavy fall of snow. The melting of the snow in spring and summer feeds the numerous tributaries of this river, insuring a continued flow throughout the year.

The results of data collected in Owens River Valley are contained in Water-Supply *Paper No. 177*, which presents the results of all the hydrographic data collected in the State *of California* during 1905.

MINOR GREAT BASIN DRAINAGE.

PRINCIPAL STREAMS.

The minor Great Basin drainage includes large areas in Oregon, Nevada, Utah, and California, in which the water supply is very limited, most of the streams being intermittent.

The work of the United States Geological Survey on this drainage in 1905 covered only the collection of data concerning streams in Oregon, which are here classified by the lakes into which they flow, as follows: Silvies River, discharging into Malheur Lake; Silver Creek, into Harney Lake; Silver Creek, Bridge Creek, and Bear Creek, into Silver Lake; Summer Lake and Ana River, into Summer Lake; and Chewaucan River, into Abert Lake.

MALHEUR LAKE BASIN.

MALHEUR LAKE AT THE NARROWS, OREGON.

This station was established May 14, 1903. It is located at the highway bridge across The Narrows. The station is maintained for the purpose of obtaining data in regard to the fluctuations of the lake, which has no outlet.

The gage is a 1 by 4 inch board, 10 feet long, fastened to a telegraph pole. It is read from the bridge once each week by R. J. Haines, the postmaster. The bench mark is a United States Geological Survey standard iron bench-mark post, set at the east end of the bridge, on the south side of the road, near the fence and about 200 feet from the gage; its elevation is 8.20 feet above the zero of the gage and 4,088 feet above sea level.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey:

Description: 100, p 429; 133, pp 344–345.
Gage heights: 100, p 430; 133, p 345.

Gage height, in feet, of Malheur Lake, at The Narrows, Oregon, for 1905.

Day.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
2				4.2			2.7
4						3.0	
5			5.0				
7					3.45		
8		5.65					
9				4.0			2.65
11						2.9	
12			4.8				
14					3.3		
15		5.5					
16	5.7			3.85			2.65
18						2.8	
19			4.6				
21					3.2		
22		5.35					
23				3.6			
25						2.75	
26			4.4				
28					3.1		
29		5.2					
30				3.5			

SILVIES RIVER NEAR SILVIES, OREG.

Silvies River rises at Soda Spring, in southern Grant County, Oreg., flows southwest, then southeast, and discharges into the north end of Malheur Lake.

A temporary station was established near Silvies, Oreg., May 8, 1903, and gage heights were read by John Craddock from May 8 to June 26, 1903. One discharge measurement was made at the temporary station. June 16, 1903, a permanent gage was established at the proposed dam site one-half mile below the temporary gage, 2 miles west of the stage road, and three-fourths of a mile below the mouth of Trout Creek. There is a dam 1½ mile upstream.

The channel is straight for 150 feet above and 200 feet below the station. The right bank is low, and will overflow at high water for a considerable distance; the left bank is high and rocky, and not liable to overflow. The bed of the stream is composed of gravel, is free from vegetation, and shifts somewhat. All the water passes beneath the cable at all stages.

Discharge measurements are made from a five-eighth inch galvanized-iron cable, with a span of 494 feet, located 75 feet downstream from the gage. It is supported in the center. The initial point for soundings is the zero of the tagged wire, 29 feet from the cable support.

The gage is an inclined 2 by 6 inch plank on the left bank. No bench marks have been established.

This station was not maintained regularly during 1905, but a few discharged measurements were made when measurements were made at Burns, a station on the same stream below this point.

Information in regard to this station is contained in the following Water-Supply Papers of the United States Geological Survey.

Description: 100, p 434; 133, pp 345–346.
Discharge: 100, p 434; 133, p 346.
Discharge, monthly: 100, p 436; 133, p 348.
Gage heights: 100, p 435; 133, p 347.
Rating table: 100, p 435; 133, p 347–348.

Discharge measurements of Silvies River, near Silvies, Oreg., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
March 23	M. L. Lewis	47	174	0.96	4.55	166
April 13	do	47	165	.95	4.65	156
April 26	do	48	178	1.08	4.82	193
May 25	do	43	135	.70	3.90	94
October 24	do	18	6.5	.63	2.00	4.1

SILVIES RIVER NEAR BURNS, OREG.

This station was established as a temporary station May 10, 1903, and was made permanent August 14, 1903. A new gage and a cable for discharge measurements were installed January 19, 1904. The station is located about 10 miles above Burns, Oreg.

The channel is straight for 75 feet above and below the cable. The right bank is low, and is liable to overflow for a considerable distance. The left bank is high and rocky, and will not overflow. Both banks have been cleared of brush. At the gage the bed of the stream is composed of clean sand and gravel. There is but one channel at low water; at high stages there are two or more channels. All the waters passes beneath the cable at all stages.

Discharge measurements are made from a five-eighths inch galvanized-iron cable, with a span of 390 feet, located at Lampshir's place, 1 mile above the gage. In addition to the timber supports at the ends, the cable is supported at a point 167 feet from the initial

for soundings by a tree 10 inches in diameter. The initial point for soundings is ero of the tagged wire, 22½ feet from the lower end of the turnbuckle. At low water, the current is sluggish, discharge measurements are made by wading.

gage, which is read once each day by Leonia Parker, is located 10 feet below the near Parker's house. It is in two sections, both consisting of 2 by 6 inch timbers rted by a frame secured to the bank. The lower section is inclined and reads from 2.6 feet; the upper section is vertical and reads from 12.7 to 17 feet. The new gage has me datum as the old one which it replaced. The bench mark is the highest point of a rock on the right bank, directly across the river from the gage, from which it is 135 istant; elevation above zero of gage, 19.76 feet.

ormation in regard to this station is contained in the following Water-Supply Papers United States Geological Survey:

ription: 100, pp 431–432; 133, pp 348-349.
harge: 100, p 432; 133, p 349.
harge, monthly: 100, p 433; 133, p 351.
heights: 100, pp 432–433; 133, p 350.
ng table: 100, p 433; 133, p 351.

Discharge measurements of Silvies River near Burns, Oreg., in 1905.

ate.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Dis-charge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
21	M. L. Lewis	56	476	0.95	7.55	450
11	do	55	466	.87	7.70	405
25	do	55	438	.80	6.65	352
7[a]	do	57	520	.36	4.75	190
3	Ivan Landes	28	22	.89	2.54	20
er 3	M. L. Lewis	25	17	.78	2.40	13.4

[a] Water at cable backed up by dam one-half mile below, but no effect on gage height.

Daily gage height, in feet, of Silvies River near Burns, Oreg., for 1905.

y.	Jan.	Feb.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
	3.5	2.9		6.8	3.8	2.8	2.4	2.3	2.4	2.5	2.5
	3.9	2.9		6.5	3.8	2.8	2.4	2.3	2.4	2.5	2.5
	3.4	2.9		6.3	3.9	2.8	2.4	2.3	2.4	2.5	2.5
	3.3	2.9		6.25	3.9	2.8	2.4	2.3	2.4	2.5	2.5
	3.1	2.9		6.2	3.9	2.8	2.4	2.3	2.4	2.5	2.5
	2.9	2.9		6.0	3.9	2.8	2.4	2.3	2.4	2.5	2.5
	2.8			5.9	3.9	2.8	2.4	2.3	2.4	2.5	2.5
	2.7			5.2	3.8	2.6	2.4	2.3	2.4	2.5	2.5
	2.7		8.3	5.3	3.8	2.6	2.35	2.3	2.4	2.5	2.5
	2.7		8.0	5.4	3.8	2.6	2.35	2.3	2.4	2.5	2.5
	2.7		7.75	5.6	3.[illegible]	2.6	2.35	2.3	2.4	2.5	2.5
	2.7		7.35	5.6	3.5	2.6	2.3	2.3	2.4	2.5	2.5
	2.7		7.15	5.6	3.4	2.6	2.3	2.3	2.4	2.55	2.5
	2.7		7.05	5.5	3.4	2.6	2.3	2.3	2.4	2.55	2.5
			6.65	5.0	3.4	2.6	2.3	2.3	2.4	2.55	2.5
			6.65	4.9	3.3	2.6	2.3	2.3	2.4	2.55	2.5
			6.9	4.8	3.3	2.6	2.3	2.3	2.4	2.55	2.45
			7.0	4.4	3.2	2.6	2.3	2.3	2.4	2.55	2.45
			7.0	4.2	3.2	2.55	2.3	2.3	2.4	2.55	2.4
			7.0	4.2	3.0	2.55	2.3	2.3	2.4	2.5	2.4
			7.2	4.2	3.0	2.5	2.3	2.3	2.4	2.5	2.4
			7.3	4.2	2.9	2.5	2.3	2.3	2.4	2.5	2.4
			7.15	4.2	2.8	2.55	2.3	2.3	2.4	2.5	2.4

Daily gage height, in feet, of Silver Creek near Riley, Oreg., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Oct.	Dec.
1	5.6	5.4	5.8	6.9	6.8	5.2	4.75	3.75	.....
2	.....	5.4	6.0	7.0	6.65	5.25	.....	4.2	.....
3	5.0	5.4	6.0	.....	6.6	5.25	4.7	4.45	.....
4	5.0	5.4	6.0	7.1	6.55	.....	4.7	4.4	.....
5	5.0	5.3	6.1	7.2	6.5	5.25	4.7	4.3	.....
6	5.0	.....	.....	7.7	6.4	5.25	4.7	4.45	.....
7	5.0	5.0	6.8	7.8	.....	5.25	4.65	4.7	.....
8	5.0	5.0	6.6	7.9	6.45	5.2	4.6	.....	.....
9	.....	5.0	7.0	7.9	6.45	5.2	.....	.....	.....
10	5.0	5.0	7.0	.....	6.4	5.2	.....	.....	.....
11	5.0	5.0	7.5	7.5	6.4	.....	.....	.....	.....
12	5.0	5.0	7.9	7.2	6.2	5.2	.....	.....	.....
13	5.0	.....	.....	7.1	6.0	5.1	.....	.....	.....
14	6.7	5.0	8.2	7.0	.....	5.0	.....	.....	.....
15	9.0	5.0	8.1	6.9	5.8	5.0	.....	.....	.....
16	.....	5.0	8.0	6.8	5.8	5.0	.....	.....	.....
17	6.4	5.0	8.8	.....	5.8	5.0	.....	.....	.....
18	6.3	5.0	8.9	6.7	5.8	.....	.....	.....	.....
19	6.0	5.0	8.5	6.7	5.7	4.95	.....	.....	.....
20	6.0	.....	.....	7.0	5.7	4.95	.....	.....	.....
21	5.8	7.8	8.1	6.9	.....	4.95	.....	.....	.....
22	6.8	7.7	8.0	6.95	5.6	4.9	.....	.....	.....
23	.....	7.0	7.9	6.9	5.55	4.9	.....	.....	.....
24	8.6	7.4	7.8	.....	5.5	4.9	.....	.....	.....
25	7.7	6.4	7.5	6.8	5.45	.....	.....	.....	5.
26	6.4	6.0	7.5	7.0	5.45	4.9	.....	.....	5.
27	6.4	.....	.....	7.05	5.45	4.85	.....	.....	5.
28	6.0	6.2	7.4	6.9	.....	4.85	.....	.....	5.
29	5.8	.....	7.4	6.8	5.3	4.85	.....	.....	5.
30	.....	.....	6.8	6.7	5.3	4.85	.....	.....	5.
31	5.5	.....	6.7	.....	5.3	.....	.....	.....	5.

Station rating table for Silver Creek near Riley, Oreg., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
4.20	0.0	5.40	26	6.60	83	7.70	145
4.30	.2	5.50	30	6.70	89	7.80	151
4.40	.6	5.60	34	6.80	94	7.90	157
4.50	1.0	5.70	38	6.90	99	8.00	163
4.60	3	5.80	42	7.00	105	8.10	169
4.70	6	5.90	47	7.10	111	8.20	175
4.80	8	6.00	52	7.20	116	8.30	181
4.90	11	6.10	57	7.30	122	8.40	188
5.00	14	6.20	62	7.40	127	8.50	195
5.10	17	6.30	67	7.50	133	8.60	202
5.20	20	6.40	73	7.60	139	8.70	209
5.30	23	6.50	78				

NOTE.—The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1905. It is well defined.

timated monthly discharge of Silver Creek near Riley, Oreg., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
	230	14	58.8	3,616
	151	14	41.9	2,327
	223	47	128	7,870
	157	89	110	6,545
	94	23	51.0	3,136
	23	10	15.5	922
od				24,020

onditions not known; open-channel rating table applied to winter months without cor-harge interpolated on days when gage was not read. Records fragmentary after July 8, regular observer. Creek was dry in August, September, and the greater part of July.

SILVER LAKE BASIN.

SILVER CREEK NEAR SILVERLAKE, OREG.

k rises in the western part of Lake County, Oregon, flows northward to Pauline rsh, then turns abruptly to the southeast and enters Silver Lake.

station was established December 29, 1904. It is located 0.9 mile above the e, 1.6 miles southwest of Silver Lake, Oreg.

el is straight for 100 feet above and 75 feet below the cable. Both banks are clean, and not subject to overflow. The bed of the stream is composed of rock free from vegetation, and is permanent. There is but one channel at all stages. is swift.

measurements are made by means of a cable, car, tagged wire, and stay wire, e gage. The initial point for soundings is 9.2 feet west from the anchor bolt on of the cable.

which was read during 1905 once each day by Henry Egli, is an inclined staff, ht bank. The bench mark is a copper bolt cemented in the solid rock on the ne stream, 43 feet downstream from the cable, and 12 feet from the edge of low tion above zero of gage, 8.12 feet.

scharge measurements of Silver Creek near Silver Lake, Oreg., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
I. Landes	21	26	0.98	1.00	25
do	22	34	1.50	1.35	51
do	21	41	1.82	1.70	74
do	22	44	2.26	1.90	100
do	24	33	1.45	1.30	48
do	21	28	1.24	1.10	34
do	18	19	1.30	.99	24
do	10	9.2	2.17	.79	20
do	10	8.1	1.83	.74	14.8
do	9	9.8	2.12	.74	21
do	10	9.9	2.22	.93	22
do	9.5	9.2	1.59	.73	14.8
do	9.5	8.3	.95	.60	7.9

nts made about 16 feet above cable; meter on rod.
nts made about 40 feet above cable; meter on rod.
nts made about 50 feet above cable; meter on rod.
nts made about 50 feet above cable; meter on cable.
inches thick.

Daily gage height, in feet, of Silver Creek near Silver Lake, Oreg., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	1.0	1.0	1.5	1.5	1.8	1.05	0.9	0.8	0.8	0.75	0.8	0.8
2	1.0	1.0	1.7	2.45	1.65	1.0	.85	.85	.75	.75	.75	.7
3	1.05	1.0	1.7	2.4	1.4	1.1	.85	.8	.75	.75	.75	.7
4	1.0	.95	1.6	2.4	1.3	1.2	.85	.8	.75	.75	.75	.7
5	.95	.95	1.5	2.8	1.4	1.15	.8	.8	.75	.75	.75	.7
6	.95	.95	1.85	2.5	1.3	1.1	.75	.8	.75	.8	.85	.75
7	1.0	.9	1.8	2.0	1.3	1.15	.7	.8	.75	.9	.95	.7
8	1.0	1.3	1.6	1.95	1.35	1.2	.7	.8	.75	.85	1.2	.75
9	1.0	1.2	1.4	1.7	1.65	1.1	.7	.8	.75	.85	1.2	.75
10	.95	1.1	1.45	1.75	1.35	1.05	.75	.8	.75	.8	1.25	.9
11	.95	1.0	1.6	1.6	1.4	1.05	.75	.75	.75	.75	1.2	1.0
12	1.25	1.05	1.55	1.5	1.7	1.0	.8	.8	.75	.75	1.2	1.0
13	1.25	1.05	1.55	1.75	1.55	1.0	.8	.8	.75	.75	1.15	1.05
14	1.5	1.0	1.5	1.5	1.4	1.0	.8	.8	.75	.75	.95	1.0
15	1.6	1.0	1.4	1.4	1.3	1.0	.8	.8	.75	.75	1.05	1.0
16	1.5	1.0	1.55	1.4	1.25	1.0	.8	.8	.75	.75	.85	1.0
17	1.25	1.1	1.7	1.3	1.25	1.0	.8	.8	.75	.8	.85	1.0
18	1.2	1.3	1.5	1.55	1.25	1.0	.8	.8	.75	.8	.8	1.0
19	1.1	1.05	1.5	1.5	1.2	.95	.8	.8	.75	.75	.8	.85
20	1.0	2.0	1.65	1.4	1.15	.95	.8	.85	.75	.75	.85	.85
21	1.0	2.25	1.55	1.4	1.2	.95	.8	.85	.75	.75	.75	.8
22	1.0	1.4	1.6	1.5	1.15	.95	.8	.8	.8	.75	.75	.8
23	1.05	1.8	1.6	2.0	1.1	.95	.8	.8	.75	.75	.75	.7
24	1.45	1.4	1.75	1.9	1.05	1.0	.8	.8	.75	.75	.75	.95
25	1.6	1.2	1.9	1.85	1.0	.95	.8	.8	.75	.75	.75	1.1
26	1.35	1.4	2.4	2.1	1.1	.95	.8	.8	.75	.75	.7	1.15
27	1.2	1.5	2.2	1.85	1.2	.9	.8	.8	.85	.75	.7	1.0
28	1.2	1.55	1.7	1.4	1.2	.9	.8	.8	.8	.75	.7	.9
29	1.1	.....	1.5	1.65	1.2	.9	.8	.8	.8	.75	.75	.9
30	1.05	.....	1.4	1.5	1.15	.9	.8	.8	.75	.75	.75	.9
31	1.05	.....	1.4	.....	1.1	.....	.8	.8	.....	.75	.....	1.15

Station rating table for Silver Creek near Silver Lake, Oreg., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
0.75	15	1.00	27	1.50	62	2.00	107
0.80	17	1.10	33	1.60	70	2.10	119
0.85	19	1.20	39	1.70	78	2.20	131
0.90	21	1.30	46	1.80	87	2.30	143
0.95	24	1.40	54	1.90	97	2.40	155

NOTE.—The above table is applicable only for open-channel conditions. It is based on 12 discharge measurements made during 1905. It is well defined between gage heights 0.7 foot and 2 feet.

imated monthly discharge of Silver Creek near Silver Lake, Oreg., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
.....	70	24	36.8	2,263
.....	137	21	43.9	2,438
.....	155	54	73.9	4,544
.....	203	46	89.9	5,349
.....	87	27	47.2	2,902
.....	39	21	27.8	1,654
.....	21	13	16.7	1,027
.....	19	15	17.1	1,051
.....	19	15	15.4	916
.....	21	15	15.7	965
.....	42	13	21.4	1,273
.....	36	13	21.6	1,328
ear.....	203	13	35.6	25,710

e is known to form at this station during the winter months, but the observer failed to gth of time that ice conditions existed during 1905. The open-channel rating table was he winter months without correction.

BRIDGE CREEK NEAR SILVER LAKE, OREG.

Creek rises in western Lake County, Oreg., and flows northeastward into Silver the town of Silver Lake.

ng station was established January 21, 1905. It is located at the county bridge t of Silver Lake, Oreg.

nnel is straight for 50 feet above and 80 feet below the station. Both banks ean, and liable to overflow. The bed of the stream is composed of sand, is free ation, and is permanent. There is but one channel at all stages. The current

ge measurements are made from the downstream side of the bridge to which the ached. The initial point for soundings is the west end of the bridge, down-, and is marked by a 10-penny nail and black paint.

al staff gage, which was read once each day during 1905 by M. S. Henderson Robinett, is driven 2 feet into the bed of the stream and spiked to projecting the center of the bridge on the downstream side. The bench mark is a copper ited in a large bowlder on the east side of the stream just above the bridge; 9.73 feet above zero of gage.

Discharge measurements of Bridge Creek near Silver Lake, Oreg., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
... I. Landes.....	7	3.2	1.23	2.05	4.0
..... do.....	7	2.6	1.04	2.05	2.7
..... do.....	7.5	2.8	1.00	2.00	2.8
..... do.....	22	12.4	1.12	2.72	13.9
..... do.....	22	13.2	1.14	2.79	15.0
1..... do.....	3	.7	1.14	2.05	.8

[a] Measurement made 30 feet below bridge.
[b] Measurement made from bridge.

Daily gage height, in feet, of Bridge Creek near Silver Lake, Oreg., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	1.95	1.9	1.95	2.4	2.7	2.2	.....	2.03	2.03	2.03	2.1
2	.....	2.0	1.9	1.95	2.45	2.7	2.2	.....	2.03	2.03	2.02	2.1
3	.....	2.0	1.9	2.0	2.4	2.7	2.2	.....	2.02	2.04	2.03	1.9
4	.....	2.0	1.9	2.0	2.4	2.7	2.15	.....	2.02	2.05	2.03	1.9
5	.....	1.95	1.95	1.8	2.4	2.7	2.1	.....	2.01	2.06	2.02	1.9
6	.....	1.95	1.95	1.8	2.4	2.7	2.0	.....	2.02	2.06	2.03	1.9
7	.....	1.95	1.95	1.85	2.2	2.7	.....	1.94	2.01	2.06	2.03	2.0
8	.....	1.9	1.95	1.85	2.1	2.7	.....	1.93	2.01	2.04	2.03	1.9
9	.....	2.0	1.95	1.85	2.1	2.7	.....	1.94	2.01	2.04	2.03	1.9
10	.....	2.2	1.95	1.9	2.1	2.75	.....	1.92	2.01	2.03	2.03	2.01
11	.....	1.95	1.95	1.9	2.15	2.75	.....	1.9	2.01	2.04	2.03	2.01
12	.....	2.2	1.95	1.95	2.1	2.8	.....	1.9	2.01	2.03	2.03	2.01
13	.....	2.2	1.95	1.95	2.1	2.8	.....	1.92	2.01	2.04	2.03	2.1
14	.....	2.2	2.0	1.95	2.1	2.8	.....	1.92	2.02	2.04	2.03	2.1
15	.....	2.2	2.0	2.0	2.4	2.75	.....	1.9	2.02	2.03	2.02	2.1
16	.....	2.4	2.0	2.0	2.4	2.7	.....	1.92	2.01	2.03	2.03	2.1
17	.....	2.4	2.0	2.0	2.65	2.7	.....	1.95	2.01	2.02	2.03	2.3
18	.....	2.4	2.0	2.0	2.65	2.7	.....	1.98	2.01	2.02	2.03	2.3
19	.....	2.4	2.0	2.0	2.65	2.6	.....	1.96	2.02	2.02	2.1	2.3
20	.....	.....	2.0	1.95	2.65	2.55	.....	1.98	2.02	2.02	2.1	2.3
21	.....	2.3	.....	2.0	1.95	2.65	2.5	.....	1.98	2.02	2.02	2.1	2.4
22	.....	2.3	.....	2.0	1.95	2.65	2.5	.....	2.00	2.01	2.01	2.1	2.4
23	.....	2.15	.....	2.0	1.95	2.6	2.4	.....	1.99	2.01	2.01	2.11	2.4
24	.....	2.2	2.0	2.0	1.95	2.6	2.4	.....	1.98	2.02	2.02	2.11	2.5
25	.....	2.1	1.95	2.0	1.95	2.55	2.35	.....	2.0	2.03	2.02	2.11	2.5
26	.....	2.05	2.0	2.0	2.3	2.6	2.3	.....	2.0	2.03	2.02	2.1	2.5
27	.....	2.0	1.9	2.0	2.4	2.65	2.3	.....	2.04	2.03	2.01	2.1	2.6
28	.....	2.1	1.9	2.0	2.3	2.65	2.25	.....	2.03	2.02	2.01	2.1	2.6
29	.....	2.0	.....	1.9	2.3	2.7	2.2	.....	2.03	2.03	2.02	2.09	2.6
30	.....	1.95	.....	1.95	2.4	2.7	2.2	.....	2.04	2.03	2.03	2.09	2.6
31	.....	1.95	.....	1.95	.....	2.7	.....	.....	2.04	.....	2.03	.....	2.6

NOTE.—Increase in gage heights April 26 to December 31 caused by backwater from a dam. Ice conditions December 17–31.

Station rating table for Bridge Creek near Silver Lake, Oreg., from January 1 to April 25, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.80	0.8	2.00	2.8	2.20	6.3	2.40	10.0
1.90	1.2	2.10	4.5	2.30	8.1		

NOTE.—The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during 1905.

Station rating table for Bridge Creek near Silver Lake, Oreg., from April 26 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
1.90	0.2	2.20	3.0	2.50	8.6	2.80	15.2
2.00	.6	2.30	4.7	2.60	10.7	3.00	20.0
2.10	1.3	2.40	6.6	2.70	12.9		

NOTE.—The above table is applicable only for open-channel conditions. It is based on three discharge measurements made during 1905.

mated monthly discharge of Bridge Creek near Silver Lake, Oreg., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
31	8.1	2.0	4.55	99
19, 24–28	10.0	1.2	4.33	206
	2.8	1.2	2.23	137
	6.6	.8	2.53	151
	12.9	1.3	7.79	479
	15.2	3.0	10.6	631
	3.0	.6	2.18	26
	.8	.2	.46	23
	.7	.6	.66	39
	.9	.6	.73	45
	1.5	.7	.95	57
	1.3	.2	1.00	61
riod				1,954

[a] Ice conditions December 17–31; discharge estimated, 1.3 second-feet.

BEAR CREEK NEAR SILVER LAKE, OREG.

ek rises in western Lake County, Oreg., and flows northeastward into the west-Pauline Lake and Marsh.

ng station was established January 21, 1905. It is located at the county bridge theast of Silver Lake, Oreg.

nel is straight for 60 feet above and 25 feet below the station. Both banks are and liable to overflow. The bed of the stream is composed of sand, is free from and is shifting. There is but one channel, broken at high water by the two bridge. The current is moderate.

e measurements are made from the upstream side of the bridge. The initial undings is a 10-penny nail and paint mark at the west end of the bridge, upstream

, which was read once each day during 1905 by Cliff Smith, is an inclined staff right bank about 6 feet above the bridge. The bench mark is a copper bolt n the solid rock 80 feet upstream from the bridge and 160 feet west of the west bridge; elevation, 27.04 feet above the zero of the gage.

Discharge measurements of Bear Creek near Silver Lake, Oreg., in 1905.

Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
	Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
I. Landes	7	4.6	3.14	4.15	14.4
[a] do	11	7.4	3.19	4.60	23.6
do	8	5.1	2.31	4.0	11.7
do	27	37.0	1.36	5.48	50.0
do	28	25.0	1.88	5.25	46.0
do	11	8.7	.72	3.90	6.3
do	10	7.0	.72	3.85	5.0
do	10	6.1	1.05	3.92	6.4
do	9	6.4	1.06	4.03	6.8

elow bridge. [b] 400 feet below bridge. [c] 100 feet above bridge. [d] 300 feet below bridge.

Daily gage height, in feet, of Bear Creek near Silver Lake, Oreg., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1		4.1	3.95	4.1	5.0	5.45	5.05	3.9	3.8	3.85	3.9	3.9
2		4.1	4.35	4.0	4.95	5.4	5.0	3.9	3.8	3.85	3.9	3.9
3		4.1	4.55	3.95	4.9	5.45	4.95	3.85	3.8	3.85	3.9	3.9
4		4.1	4.0	3.95	4.9	5.45	4.95	3.85	3.8	3.85	3.9	3.9
5		4.1	4.0	3.95	4.9	5.35	4.9	3.8	3.8	3.85	3.6	3.9
6		4.1	3.95	4.0	4.95	5.25	4.9	3.9	3.8	3.85	3.6	3.9
7		4.1	3.95	4.0	4.95	5.2	4.9	3.9	3.8	3.95	3.8	3.9
8		4.1	3.95	4.0	5.05	5.4	4.85	3.9	3.8	3.95	3.95	3.9
9		4.1	3.95	4.0	5.05	5.4	4.8	3.85	3.8	3.95	4.1	3.9
10		4.1	3.95	4.0	5.0	5.4	4.8	3.85	3.8	3.9	4.1	3.7
11		4.1	3.95	4.0	4.95	5.45	4.8	3.8	3.8	3.9	4.1	3.65
12		4.1	3.95	4.0	5.0	5.45	4.75	3.8	3.8	3.9	4.0	3.65
13		4.1	4.0	4.0	4.95	5.4	4.75	3.8	3.8	3.9	4.0	3.7
14		4.1	4.0	4.85	4.95	5.35	4.8	3.8	3.8	3.9	3.9	3.65
15		4.1	3.95	4.85	5.05	5.3	4.8	3.8	3.8	3.9	3.9	3.9
16		4.1	4.0	4.85	5.25	5.2	4.8	3.85	3.8	3.9	3.9	3.95
17		4.55	4.0	4.85	5.05	5.05	4.8	3.85	3.8	3.9	3.9	3.95
18		4.55	4.0	4.8	5.15	5.05	4.8	3.85	3.75	3.9	3.85	3.95
19		4.5	4.0	4.8	5.15	5.0	4.8	3.85	3.75	3.9	3.75	4.0
20		4.85	4.0	4.8	5.1	4.95	3.9	3.8	3.75	3.9	3.7	4.0
21	4.2	5.0	4.0	4.8	5.0	5.35	3.9	3.8	3.75	3.9	3.7	4.1
22	4.2	4.8	4.0	4.8	4.95	5.35	3.9	3.8	3.75	3.9	3.6	4.1
23	4.2	4.6	4.05	4.75	4.9	5.3	3.9	3.8	3.75	3.9	3.65	4.0
24	4.4	4.4	3.95	4.8	5.0	5.3	3.9	3.8	3.75	3.9	3.7	3.6
25	4.4	4.4	3.95	4.95	5.1	5.25	3.9	3.8	3.75	3.9	3.7	4.0
26	4.2	4.0	3.95	4.9	5.2	5.2	3.9	3.8	3.75	3.9	3.85	4.6
27	4.2	4.1	3.95	4.9	5.4	5.2	3.9	3.8	3.75	3.9	3.85	4.6
28	4.1	4.0	3.95	4.95	5.4	5.3	3.9	3.8	3.75	3.9	3.9	4.2
29	4.1	.....	3.95	4.75	5.4	5.25	3.9	3.8	3.75	3.9	3.9	4.2
30	4.1	.....	3.85	5.0	5.5	5.05	3.9	3.8	3.75	3.9	3.9	4.2
31	4.1	.....	3.75	.....	5.5	.....	3.9	3.8	.....	3.9	.....	4.2

NOTE.—Increased gage heights April 14 to July 19 caused by back water from dam. Dam removed July 20. Ice conditions last half of December.

SUMMER LAKE BASIN.

ANA RIVER NEAR SUMMER LAKE, OREG.

Ana River, which discharges into the north end of Summer Lake, has its source in five large springs of almost constant flow and temperature throughout the year. The river is about 5 miles long.

The gaging station was established March 28, 1905. It is located in the NW. ¼ SE. ¼ sec. 6, T. 30 S., R. 17 E., near Summer Lake, Oreg.

The channel is straight for 50 feet above and below the station. Both banks are clean and do not overflow. The bed of the stream is composed of blue clay and is fairly permanent. There is but one channel at all stages. The current is swift. Gage readings may be affected somewhat by backwater from the lake and a temporary irrigation dam.

Discharge measurements are made from a foot log near the gage. The initial point for soundings is the edge of the water on the right bank of the river, and is marked on the foot log.

A vertical staff gage, on which, during 1905, observations were made at irregular intervals by the hydrographer, is set at the right bank of the river. The bench mark is a 60-penny nail in the base of a large yellow pine a short distance above the gage; elevation above zero of gage, 11.84 feet.

Discharge measurements of Ana River near Summer Lake, Oreg., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
March 28	I. Landes	27	54	2.72	3.50	148
April 6	do	27	54	2.73	3.50	149
June 8	do	27	61	2.41	[a] 3.68	148

[a] Gage height affected by irrigation dam.

ALBERT LAKE BASIN.

CHEWAUCAN RIVER AT PAISLEY, OREG.

Chewaucan River rises in south-central Lake County, Oreg., flows northwest, then northeast, and then southeast, and discharges into the south end of Abert Lake. The changes in course are very abrupt.

The gaging station was established January 4, 1905. It is located one-half mile above Paisley, Oreg.

The channel below the station is straight; above the station it is slightly curved for 75 feet and beyond this point there are rapids. The right bank is low, but it overflows only a little, there being no water beyond the cable except in very unusual floods. The left bank is high, is composed of clean gravel, and does not overflow. The bed of the stream is of gravel, is free from vegetation, and is permanent. There is but one channel at all stages. There is a low dam 250 feet below the cable, but it does not back the water up at the gage.

Discharge measurements are made by means of a cable, car, tagged wire, and stay wire, 60 feet below the gage. The initial point for soundings is the zero of the tagged wire, 7.1 feet from the clip to which the wire is attached at the left bank.

The gage, which was read once each day during 1905 by George Reed and Miss Lulu Banister, is a vertical rod attached to a tree on the right bank. The bench mark is a 60-penny spike in a notch in the base of a large cottonwood tree on the right bank, 22.5 feet upstream from the cable; elevation, 7.69 feet above zero of gage.

Discharge measurements of Chewaucan River at Paisley, Oreg., in 1905.

Date.	Hydrographer.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
		Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
January 5[a]	I. Landes	35	64	.80	4.15	51
February 26	do	34	69	1.48	4.20	102
March 22	do	36	75	1.79	4.45	135
April 5	do	37	86	2.14	4.65	183
May 11	do	39	93	2.28	4.72	213
June 4	do	40	111	2.77	5.12	308
July 4	do	32	50	.85	3.80	42
July 26	do	32	37	.61	3.57	23
September 28	do	32	47	.89	3.67	41
November 3	do	32	42	.69	3.57	29
November 22	do	32	54	.78	3.72	42

[a] Slush ice running in river.

Daily gage height, in feet, of Chewaucan River at Paisley, Oreg., for 1905.

Day.	Jan.	Feb.	Mar.	Apr.	May.	June.	July.	Aug.	Sept.	Oct.	Nov.	Dec.
1	.....	4.3	4.2	4.4	5.0	4.8	4.0	3.5	3.4	3.6	3.5	3.6
2	.....	4.1	4.3	4.5	4.95	4.75	3.9	3.5	3.4	3.6	3.5	3.7
3	.....	4.0	4.25	4.5	4.85	4.8	3.82	3.4	3.4	3.6	3.6	3.7
4	4.0	4.0	4.25	4.5	4.8	5.15	3.75	3.4	3.4	3.6	3.5	3.7
5	4.15	4.0	4.3	4.65	4.85	5.0	3.7	3.4	3.5	3.6	3.5	3.5
6	4.2	3.85	4.3	4.8	4.8	4.8	3.7	3.4	3.5	3.6	3.6	3.6
7	4.2	3.6	4.35	4.9	4.8	4.7	3.7	3.4	3.5	3.7	3.6	3.6
8	4.1	3.8	4.3	4.9	4.9	4.8	3.7	3.4	3.5	3.7	3.6	3.8
9	4.1	3.6	4.3	4.9	4.85	4.8	3.6	3.4	3.5	3.6	3.6	4.0
10	5.0	3.6	4.35	4.8	4.7	4.7	3.6	3.4	3.5	3.6	3.6	4.2
11	5.15	3.5	4.4	4.75	4.7	4.6	3.6	3.4	3.5	3.6	3.5	4.1
12	5.2	4.1	4.5	4.8	4.8	4.7	3.6	3.4	3.5	3.6	3.5	4.1
13	4.9	4.2	4.65	4.9	4.75	4.6	3.6	3.4	3.5	3.6	3.6	4.0
14	5.2	4.0	4.6	4.7	4.75	4.6	3.6	3.4	3.5	3.6	3.7	4.0
15	4.5	4.05	4.5	4.8	4.85	4.5	3.6	3.4	3.5	3.6	3.6	4.0
16	4.4	3.9	4.6	4.8	4.95	4.5	3.6	3.4	3.5	3.6	3.7	3.9
17	4.3	3.9	4.65	4.7	5.05	4.4	3.6	3.4	3.5	3.6	3.7	3.8
18	4.1	3.9	4.6	4.75	5.0	4.3	3.6	3.4	3.5	3.6	3.7	3.8
19	4.05	4.05	4.6	4.7	5.0	4.3	3.6	3.4	3.5	3.5	3.7	3.7
20	4.0	4.25	4.5	4.7	4.95	4.3	3.7	3.4	3.5	3.5	3.6	3.8
21	3.95	4.1	4.55	4.75	4.85	4.2	3.7	3.4	3.5	3.5	3.6	4.2
22	3.9	3.95	4.45	4.8	4.85	4.2	3.7	3.4	3.5	3.5	3.6	4.5
23	4.5	4.0	4.45	4.9	4.85	4.2	3.6	3.4	3.5	3.5	3.7	4.6
24	4.4	4.1	4.4	5.0	4.8	4.2	3.6	3.4	3.5	3.6	3.6	4.8
25	4.2	4.1	4.35	5.05	4.7	4.2	3.6	3.4	3.5	3.6	3.6	4.6
26	4.0	4.1	4.8	5.15	4.9	4.2	3.7	3.4	3.5	3.6	3.7	4.0
27	4.2	4.1	4.45	5.1	5.0	4.1	3.6	3.4	3.6	3.6	3.6	4.0
28	3.9	4.15	4.4	5.1	4.9	4.0	3.6	3.5	3.7	3.6	3.7	4.0
29	4.0	.....	4.3	5.1	4.8	4.0	3.6	3.5	3.6	3.6	3.6	4.0
30	4.1	.....	4.0	5.15	4.8	3.9	3.5	3.4	3.6	3.6	3.6	4.0
31	4.5	.....	4.15	.....	4.8	.....	3.5	3.4	.....	3.6	.....	4.1

NOTE.—Ice gorge January 10-13.

Station rating table for Chewaucan River at Paisley, Oreg., from January 1 to December 31, 1905.

Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.	Gage height.	Discharge.
Feet.	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*	*Feet.*	*Second-feet.*
		3.80	43	4.30	111	4.80	223
3.40	19	3.90	53	4.40	131	4.90	249
3.50	23	4.00	64	4.50	152	5.00	276
3.60	29	4.10	77	4.60	174	5.10	304
3.70	36	4.20	93	4.70	198		

NOTE.—The above table is applicable only for open channel conditions. It is based on 10 discharge measurements made during 1905. It is well defined between gage heights 3.55 feet and 5.25 feet.

Estimated monthly discharge of Chewaucan River at Paisley, Oreg., for 1905.

Month.	Discharge in second-feet.			Total in acre-feet.
	Maximum.	Minimum.	Mean.	
January	332	53	94.1	5,786
February	111	23	64.6	3,588
March	223	64	136	8,362
April	318	131	230	13,690
May	290	158	238	14,630
June	318	53	154	9,164
July	64	23	33.2	2,041
August	23	19	19.5	1,199
September	36	19	23.5	1,398
October	36	23	28.5	1,752
November	36	23	29.7	1,767
December	223	23	70.8	4,353
The year	332	19	93.5	67,730

NOTE.—Ice gorge January 10–31; discharge assumed 77 second-feet. Ice conditions for the remainder of the winter months not known; open-channel rating table applied.

MISCELLANEOUS MEASUREMENTS IN GREAT BASIN.

The following miscellaneous measurements were made in the Great Basin in 1905 by W. G. Swendsen, H. S. Kleinschmidt, W. P. Hardesty, A. B. Larson, and I. Landes:

Miscellaneous measurements in Great Basin, 1905.

Date.	Steam.	Locality.	Width.	Area of section.	Mean velocity.	Gage height.	Discharge.
			Feet.	*Square feet.*	*Feet per second.*	*Feet.*	*Second-feet.*
March 21	Logan River	Logan, Hyde Park and Smithfield Canal, near Logan, Utah.	10	5.6	0.83	3.85	4.7
March 8	Jordan River	Near Lehi, Utah	49	20	.83	.50	17
January 28	Hobble Creek	Springville, Utah, near mouth of creek.	23	13.6	1.40	.....	19
February 15	do	do	16	9.8	1.52	.....	15
March 9	do	do	8	8.6	.83	.....	6.5
April 3	Peteetneet Creek.	At mouth of canyon near Payson, Utah.	10	.....	.....	.....	[a]20.6
May 6	do	do	10	.....	.....	.....	[a]11.4
August 31	do	do	3.45	3.86	.92	.....	3.55
May 3	Summit Creek	Near Santaquin, Utah.	11	7.3	2.95	.....	21.5
May 12	do	do	6	3.1	4.81	.55	15
June 10	do	do	6	6.5	3.71	1.08	24
August 31	do	do	6	4.3	1.61	.72	7
July 21	Silver Creek	At Spencer's, Riley, Oreg.	4	1.33	1.13	.....	1.5
January 8	Ana River	County Bridge, Summerlake, Oreg.	32	107	1.40	.....	150
May 11	George Conn's ditch.	Paisley, Oreg	7	3.5	1.93	.....	6.7
July 4	do	do	7	5.2	2.78	.....	14.6

[a] Weir measurement.



INDEX.

Page.

Acknowledgments and cooperation..... 15-16
Acre-foot, definition of..... 8
American Fork, Utah.
  American Fork near:
    description..... 47
    discharge, daily..... 49
    discharge, monthly..... 49
    gage heights..... 48
American Fork near—
  American Fork, Utah:
    description..... 47
    discharge, daily..... 49
    discharge, monthly..... 49
    gage heights..... 48
Ana River near—
  Summer Lake, Oreg.:
    description..... 132
    discharge..... 133,135
Bear Creek near—
  Silver Lake, Oreg.:
    description..... 131
    discharge..... 131
    gage heights..... 132
Bear Lake at—
  Fishhaven, Idaho:
    description..... 19
    gage heights..... 19
Bear River at and near—
  Collinston, Utah:
    description..... 25-26
    discharge..... 26
    discharge, monthly..... 28
    gage heights..... 27
    rating table..... 27
  Dingle, Idaho:
    description..... 20
    discharge..... 20
    discharge, monthly..... 22
    gage heights..... 21
    rating table..... 22
  Preston, Idaho:
    description..... 22-23
    discharge..... 23
    discharge, monthly..... 25
    gage heights..... 24
    rating table..... 24
Bear River Basin, description of..... 18-19
Blacksmith Fork near
  Hyrum, Utah:
    description..... 31-32
    discharge..... 32
    discharge, monthly..... 33
    gage heights..... 32
    rating table..... 33

Page.

Blacksmith Fork power-plant race near—
  Hyrum, Utah:
    description..... 33-34
    discharge..... 34
    discharge, monthly..... 35
    gage heights..... 34
    rating table..... 35
Bridge Creek near—
  Silver Lake, Oreg.:
    description..... 129
    discharge..... 129
    discharge, monthly..... 131
    gage heights..... 130
    rating table..... 130
Burns, Oreg.
  Silvies River near:
    description..... 122-123
    discharge..... 123
    discharge, monthly..... 124
    gage heights..... 123-124
    rating table..... 124
Cable station, figure showing..... 11
California-Nevada State Line. *See* Nevada-California State Line.
Carson River near—
  Empire, Nev.:
    description..... 111
    discharge..... 112
    discharge, monthly..... 113
    gage heights..... 112
    rating table..... 113
Carson River (East Fork) near—
  Gardnerville, Nev.:
    description..... 108-109
    discharge..... 109
    discharge, monthly..... 111
    gage heights..... 110
    rating table..... 110
Carson River (West Fork) near—
  Woodfords, Cal.:
    description..... 106
    discharge..... 106
    discharge, monthly..... 108
    gage heights..... 107
    rating table..... 107
Carson River basin, description of..... 105
Chalk Creek at—
  Coalville, Utah:
    description..... 45
    discharge..... 45
    discharge, monthly..... 47
    gage heights.....
    rating table.....

Chewaucan River at— Page.
Paisley, Oreg.:
description 133
discharge 133
discharge, monthly 135
gage heights 134
rating table 134
Coalville, Utah.
Chalk Creek at:
description 45
discharge 45
discharge, monthly 47
gage heights 46
rating table 46
Coleville, Cal.
Walker River (West Fork) near:
description 99
discharge 100
discharge, monthly 101
gage heights 100
rating table 101
Collinston, Utah.
Bear River near:
description 25–26
discharge 26
discharge, monthly 28
gage heights 27
rating table 27
Computation, methods of 14–15
rules for 8–9
Conn's (George) ditch at
Paisley, Oreg.:
discharge 135
Cooperation and acknowledgments 15–16
Croyden, Utah.
Lost Creek near:
description 43
discharge 44
gage heights 44
Weber River near:
description 38–39
discharge 39
discharge, monthly 41
gage heights 40
rating table 40
Current meters, classes of 12
methods of using 12–13
Dingle, Idaho.
Bear River at:
description 20
discharge 20
discharge, monthly 22
gage heights 21
rating table 22
Donner Creek near—
Truckee, Cal.:
description 97
discharge 97
discharge, monthly 99
gage heights 98
rating table 98
Drainage basins, list of 6–7
East Fork of Carson River. *See* Carson River (East Fork).
East Fork of Walker River. *See* Walker River (East Fork).
Elburz, Nev. Page.
Humboldt River (North Fork) near:
description 70
discharge 70
discharge, monthly 72
gage heights 71
rating table 71
Elko, Nev.
Humboldt River (South Fork) near:
description 72
discharge 73
discharge, monthly 74
gage heights 73
rating table 74
Empire, Nev.
Carson River near:
description 111
discharge 112
discharge, monthly 113
gage heights 112
rating table 113
Equivalents, table of 9–10
Fishaven, Idaho.
Bear Lake at:
description 19
gage heights 19
Floats, use of, in measuring discharge 12
Gaging stations, equipment of 12
Gallons per minute, use of 7
Gardnerville, Nev.
Carson River (East Fork) near:
description 108–109
discharge 109
discharge, monthly 111
gage heights 110
rating table 110
Golconda, Nev.
Humboldt River near:
description 76–77
discharge 77
discharge, monthly 79
gage heights 78
rating table 78
Great Basin:
description of 16–17
miscellaneous measurements in 135
Great Basin drainage (minor), description of 121
Gunnison, Utah.
San Pitch River near:
description 67–68
discharge 68
discharge, monthly 69
gage heights 68–69
rating table 69
Sevier River near:
description 65–66
discharge 66
discharge, monthly 67
gage heights 66
rating table 67
Hobart Mills, Cal.
Prosser Creek near:
description 96–97
discharge 97

Hobble Creek near— Page.
Springville, Utah:
description ... 58
discharge ... 58, 135
discharge, monthly ... 60
gage heights ... 59
rating table ... 59
Humboldt River at and near—
Golconda, Nev.:
description ... 76-77
discharge ... 77
discharge, monthly ... 79
gage heights ... 78
rating table ... 78
Oreana, Nev.:
description ... 79-80
discharge ... 80
discharge, monthly ... 81
gage heights ... 80
rating table ... 81
Palisade, Nev.:
description ... 74-75
discharge ... 75
discharge, monthly ... 76
gage heights ... 75
rating table ... 76
Humboldt River (North Fork) near—
Elburz, Nev.:
description ... 70
discharge ... 70
discharge, monthly ... 72
gage heights ... 71
rating table ... 71
Humboldt River (South Fork) near—
Elko, Nev.:
description ... 72
discharge ... 73
discharge, monthly ... 74
gage heights ... 73
rating table ... 74
Humboldt River basin, description of ... 70
Humboldt Sink drainage, description of ... 70
Hydrographers, list of ... 16
Hydrographic surveys, annual appropriations for ... 5
organization and scope of ... 5-7
Hyrum, Utah.
Blacksmith Fork near:
description ... 31-32
discharge ... 32
discharge, monthly ... 33
gage heights ... 32
rating table ... 33
Blacksmith Fork power plant race near:
description ... 33-34
discharge ... 34
discharge, monthly ... 35
gage heights ... 34
rating table ... 35
ice-covered streams, method of measuring flow of ... 14
Independence Creek below—
Independence Lake, Cal.:
description ... 94-95
discharge ... 95
discharge, monthly ... 96
gage heights ... 95
rating table ... 96
Independence Lake, Cal. Page.
Independence Creek below:
description ... 94-95
discharge ... 95
discharge, monthly ... 96
gage heights ... 95
rating table ... 96
Jordan River near—
Lehi, Utah:
discharge ... 135
Lake Shore, Utah.
Spanish Fork near:
description ... 63
discharge ... 64
discharge, daily ... 64
discharge, monthly ... 65
gage heights ... 64
Lake Winnemucca Inlet near—
Wadsworth, Nev.:
description ... 90
discharge ... 91
discharge, monthly ... 92
gage heights ... 91
rating table ... 91
Lehi, Utah.
Jordan River near:
discharge ... 135
Little Truckee River at—
Pine station, Cal.:
description ... 92
discharge ... 93
discharge, monthly ... 94
gage heights ... 93
rating table ... 94
Logan, Utah.
Logan River near—
description ... 28-29
discharge ... 29, 135
discharge, monthly ... 31
gage heights ... 30
rating table ... 30
Logan River near—
Logan, Utah:
description ... 28-29
discharge ... 29, 135
discharge, monthly ... 31
gage heights ... 30
rating table ... 30
Lost Creek near—
Croyden, Utah:
description ... 43
discharge ... 44
gage heights ... 44
Malheur Lake at—
The Narrows, Oreg.:
description ... 121
gage heights ... 121
Merrillville, Cal.
Willow Creek at:
description ... 116
discharge, monthly ... 118
gage heights ... 117
rating table ... 117
Methods of computing run-off ... 14-15
of measuring stream flow ... 10-14
Miner's inch, definition of ... 7
Multiple-point method of measuring discharge, description of ... 13

Nevada-California State line. Page.
Truckee River at:
description ... 86-87
discharge ... 87
discharge, monthly ... 88
gage heights ... 87
rating table ... 88
North Fork of Humboldt River. *See* Humboldt River (North Fork).
Oakley, Utah:
Weber River near:
description ... 36
discharge ... 37
discharge, monthly ... 38
gage heights ... 37-38
rating table ... 38
Oreana, Nev.
Humboldt River near:
description ... 79-80
discharge ... 80
discharge, monthly ... 81
gage heights ... 80
rating table ... 81
Owens River basin, description of ... 1-0
Paisley, Oreg.
Chewaucan River at:
description ... 133
discharge ... 133
discharge, monthly ... 135
gage heights ... 134
rating table ... 134
Conn's (George) ditch at:
discharge ... 135
Palisade, Nev.
Humboldt River at:
description ... 74-75
discharge ... 75
discharge, monthly ... 76
gage heights ... 75
rating table ... 76
Payson, Utah.
Peteetneet Creek near:
discharge ... 135
Peteetneet Creek near—
Payson, Utah:
discharge ... 135
Pine Station, Cal.
Little Truckee River at:
description ... 92
discharge ... 93
discharge, monthly ... 94
gage heights ... 93
rating table ... 94
Plain City, Utah.
Weber River near:
description ... 41
discharge ... 41
discharge, monthly ... 43
gage heights ... 42
rating table ... 42
Preston, Idaho.
Bear River at:
description ... 22-23
discharge ... 23
discharge, monthly ... 25
gage heights ... 24
rating table ... 24
Prosser Creek near— Page.
Hobart Mills, Cal.:
description ... 96-97
discharge ... 97
Provo, Utah.
Provo River (above Telluride Power Company's dam) near:
description ... 50-51
discharge ... 51
discharge, daily ... 52
discharge, monthly ... 52
gage heights ... 51
Provo River (at mouth of canyon) near:
description ... 53-54
discharge ... 54
discharge, monthly ... 56
gage heights ... 54
rating table ... 55
Provo River (at Rio Grande Western Railway bridge) near:
description ... 56-57
discharge ... 57
gage heights ... 57
Telluride Power Company's flume near:
discharge, daily ... 55
discharge, monthly ... 56
Provo River (above Telluride Power Company's dam) near—
Provo, Utah:
description ... 50-51
discharge ... 51
discharge, daily ... 52
discharge, monthly ... 52
gage heights ... 51
Provo River (at mouth of canyon) near—
Provo, Utah:
description ... 53-54
discharge ... 54
discharge, monthly ... 56
gage heights ... 54
rating table ... 55
Provo River (at Rio Grande Western Railway bridge) near—
Provo, Utah:
description ... 56-57
discharge ... 57
gage heights ... 57
Provo River basin, description of ... 50
Rating curves, methods of construction of ... 14-15
Rating tables, methods of construction of ... 14-15
Riley, Oreg.
Silver Creek near:
description ... 125
discharge ... 125, 135
discharge, monthly ... 127
gage heights ... 126
rating table ... 126
Rules for computation, fundamental and special ... 8-9
Run-off, office methods of computing ... 14-15
Run-off in inches, definition of ... 8
San Pitch River near—
Gunnison, Utah:
description ... 67-68
discharge ... 68
discharge, monthly ... 69
gage heights ... 68-69
rating table ... 69

Santaquin, Utah: Page.
Summit Creek near—
discharge 135
Second-feet pe square mile, definition of 7
Second-foot, definition of 7
Sevier River near—
Gunnison, Utah:
description 65–66
discharge 66
discharge, monthly 67
gage heights 66
rating table 67
Sierra Nevada drainage, description of 81
Silver Creek near—
Riley, Oreg.:
description 125
discharge 125,135
discharge, monthly 127
gage heights 126
rating table 126
Silver Lake, Oreg.:
description 127
discharge 127
discharge, monthly 129
gage heights 128
rating table 128
Silver Lake, Oreg.:
Bear Creek near—
description 131
discharge 131
gage heights 132
Bridge Creek near—
description 129
discharge 129
discharge, monthly 131
gage heights 130
rating table 130
Silver Creek near—
description 127
discharge 127
discharge, monthly 129
gage heights 128
rating table 128
Silvies, Oreg.:
Silvies River near—
description 122
discharge 122
Silvies River near—
Burns, Oreg.:
description 122–123
discharge 123
discharge, monthly 124
gage heights 123–124
rating table 124
Silvies, Oreg.:
description 122
discharge 122
Single-point method of measuring discharge, description of 13
Slope method of measuring discharge, use and value of 10
South Fork of Humboldt River. *See* Humboldt River (South Fork).
Spanish Fork, Utah:
Spanish Fork near—
description 60–61
discharge 61
discharge, daily 62
Spanish Fork, Utah—Continued. Page.
Spanish Fork, near—Continued.
discharge, monthly 63
gage heights 61–62
Spanish Fork near—
Lake Shore, Utah:
description 63
discharge 64
discharge, daily 64
discharge, monthly 65
gage heights 64
Spanish Fork, Utah:
description 60–61
discharge 61
discharge, daily 62
discharge, monthly 63
gage heights 61–62
Springville, Utah:
Hobble Creek near—
description 58
discharge 58,135
discharge, monthly 60
gage heights 59
rating table 59
Standish, Cal.:
Willow Creek near—
description 118
discharge 118
discharge, monthly 120
gage heights 119
rating table 119
Stream flow, field methods of measuring 10–14
Summer Lake, Oreg.:
Ana River near—
description 132
discharge 133,135
Summit Creek near—
Santaquin, Utah:
discharge 135
Susan River near—
Susanville, Cal.:
description 114
discharge 114
discharge, monthly 116
gage heights 115
rating table 115
Susan River basin, description of 113–114
Susanville, Cal.:
Susan River near—
description 114
discharge 114
discharge, monthly 116
gage heights 115
rating table 115
Tables, explanation of 8
Tahoe, Cal.:
Truckee River at—
description 88–89
discharge 89
discharge, monthly 90
gage heights 89
rating table 90
Telluride Power Company's flume near—
Provo, Utah:
discharge, daily 55
discharge, monthly 56
The Narrows, Oreg.:
Malheur Lake at—
description 121
gage heights 121

Truckee, Cal : Page.
Donner Creek near—
description 97
discharge 97
discharge, monthly 99
gage heights 98
rating table 98
Truckee River at and near—
Nevada-California State line:
description 86–87
discharge 87
discharge, monthly 88
gage heights 87
rating table 88
Tahoe, Cal.:
description 88–89
discharge 89
discharge, monthly 90
gage heights 89
rating table 90
Vista, Nev.:
description 84
discharge 85
discharge, monthly 86
gage heights 85
rating table 86
Wadsworth, Nev.:
description 82
discharge 82
discharge, monthly 84
gage heights 83
rating table 83
Truckee River Basin, description of 82
Velocity, method of measuring discharge, description of 11–14
Vertical-integration method of measuring discharge, description of 13
Vertical velocity-curve method of measuring discharge, description of 13
Vista, Nev.
Truckee River at:
description 84
discharge 85
discharge, monthly 86
gage heights 85
rating table 86
Wabuska, Nev.
Walker River near:
description 103
discharge 104
discharge, monthly 105
gage heights 104
rating table 105
Wadsworth, Nev.
Lake Winnemucca Inlet near:
description 90
discharge 91
discharge, monthly 92
gage heights 91
rating table 91
Truckee River near:
description 82
discharge 82
discharge, monthly 84
gage heights 83
rating table 83
Walker River near—
Wabuska, Nev.:
description 103
discharge 104
discharge, monthly 105
gage heights 104
rating table 105
Walker River (East Fork) near— Page.
Yerington, Nev.:
description 101–102
discharge 102
discharge, monthly 103
gage heights 102
discharge, daily 133
Walker River (West Fork) near—
Coleville, Cal.:
description 99
discharge 100
discharge, monthly 101
gage heights 100
rating table 101
Walker River Basin, description of 99
Wasatch Mountains drainage, description of 17
Weber River near—
Croyden, Utah:
description 38–39
discharge 39
discharge, monthly 41
gage heights 40
rating table 40
Oakley, Utah:
description 36
discharge 37
discharge, monthly 38
gage heights 37–38
rating table 38
Plain City, Utah:
description 41
discharge 41
discharge, monthly 42
gage heights 42
rating table 42
Weber River Basin, description of 35–36
Weir method of measuring discharge, requirements of 10–11
West Fork of Carson River. *See* Carson River (West Fork).
West Fork of Walker River. *See* Walker River (West Fork).
Willow Creek at -
Merrillville, Cal.:
description 116
discharge, monthly 118
gage heights 117
rating table 117
Willow Creek near—
Standish, Cal.:
description 118
discharge 118
discharge, monthly 120
gage heights 119
rating table 119
Woodfords, Cal.
Carson River (West Fork) near:
description 106
discharge 106
discharge, monthly 108
gage heights 107
rating table 107
Yerington, Nev.
Walker River (East Fork) near:
description 101–102
discharge 102
discharge, monthly 103
gage heights 102
discharge, daily 103

CLASSIFICATION OF THE PUBLICATIONS OF THE UNITED STATES GEOLOGICAL SURVEY.

[Water-Supply Paper No. 176.]

The publications of the United States Geological Survey consist of (1) Annual Reports; (2) Monographs; (3) Professional Papers; (4) Bulletins; (5) Mineral Resources; (6) Water-Supply and Irrigation Papers; (7) Topographic Atlas of United States, folios and separate sheets thereof; (8) Geologic Atlas of United States, folios thereof. The classes numbered 2, 7, and 8 are sold at cost of publication; the others are distributed free. A circular giving complete lists may be had on application.

Most of the above publications may be obtained or consulted in the following ways:

1. A limited number are delivered to the Director of the Survey, from whom they may be obtained, free of charge (except classes 2, 7, and 8), on application.

2. A certain number are delivered to Senators and Representatives in Congress, for distribution.

3. Other copies are deposited with the Superintendent of Documents, Washington, D. C., from whom they may be had at practically cost.

4. Copies of all Government publications are furnished to the principal public libraries in the large cities throughout the United States, where they may be consulted by those interested.

The Professional Papers, Bulletins, and Water-Supply Papers treat of a variety of subjects, and the total number issued is large They have therefore been classified into the following series: A, Economic geology; B, Descriptive geology; C, Systematic geology and paleontology; D, Petrography and mineralogy; E, Chemistry and physics; F, Geography; G, Miscellaneous; H, Forestry; I, Irrigation; J, Water storage; K, Pumping water; L, Quality of water; M, General hydrographic investigations; N, Water power; O, Underground waters; P, Hydrographic progress reports.

Series P.—The hydrographic progress reports contain the results of stream measurements. A report is issued for every calendar year, containing the results of data collected during that year. These reports were first published as a part of the Director's annual report or as a bulletin; they are now published as water-supply and irrigation papers. The following is a list, by years, of the publications containing the progress reports of stream measurements. A detailed index of these reports (1888–1903) is published as Water-Supply Paper No. 119.

1888. Tenth Annual Report, Part II.
1889. Eleventh Annual Report, Part II.
1890. Twelfth Annual Report, Part II.
1891. Thirteenth Annual Report, Part III.
1892. Fourteenth Annual Report, Part II.
1893. Bulletin No. 131.
1894. Bulletin No. 131; Sixteenth Annual Report, Part II.
1895. Bulletin No. 140.
1896. Water-Supply Paper No. 11; Eighteenth Annual Report, Part IV.
1897. Water-Supply Papers Nos. 15 and 16; Nineteenth Annual Report, Part IV.
1898. Water-Supply Papers Nos. 27 and 28; Twentieth Annual Report, Part IV.
1899. Water-Supply Papers Nos. 35, 36, 37, 38, and 39; Twenty-first Annual Report, Part IV.
1900. Water-Supply Papers Nos. 47, 48, 49, 50, 51, and 52; Twenty-second Annual Report, Part IV.
1901. East of Mississippi River, Water-Supply Papers Nos. 65 and 75.
West of Mississippi River, Water-Supply Papers Nos. 66 and 75.
1902. East of Mississippi River, Water-Supply Papers Nos. 82 and 83.
West of Mississippi River, Water-Supply Papers Nos. 84 and 85.

1903. East of Mississippi River, Water-Supply Papers Nos. 97 and 98.
West of Mississippi River, Water-Supply Papers Nos. 99 and 100.
1904. East of Mississippi River, Water-Supply Papers Nos. 124, 125, 126, 127, 128, and 129.
West of Mississippi River, Water-Supply Papers Nos. 130, 131, 132, 133, 134, and 135.
1905. East of Mississippi River, Water-Supply Papers Nos. 165, 166, 167, 168, 169, 170, and 171.
West of Mississippi River, Water-Supply Papers Nos. 171, 172, 173, 174, 175, 176, 177, and 178.

The Geological Survey and the Reclamation Service have suboffices in different parts of the United States, from which hydrographic and reclamation work in the respective localities is carried on, and where data may be obtained on application. These offices are located as follows:

Boston, Mass., 6 Beacon street; Utica, N. Y., 75 Arcade; Atlanta, Ga., 409 Temple court; Austin, Tex., University of Texas; Chicago, Ill., 876 Federal Building; Belle Fourche, S. Dak.; Cody, Wyo.; Denver, Colo., Chamber of Commerce Building; Salt Lake, Utah; Los Angeles, Cal., 1108 Union Trust Building; Phoenix, Ariz.; Carlsbad, N. Mex.; El Paso, Tex.; Billings, Mont.; Huntley, Mont.; Hazen, Nev.; Boise, Idaho; North Yakima, Wash.; Portland, Oreg., 351 Washington street.

Correspondence should be addressed to

THE DIRECTOR,
UNITED STATES GEOLOGICAL SURVEY,
WASHINGTON, D. C.

JUNE, 1906.

O